



315 S. Chapel St.
Newark, DE 19711

Phone
302.738.7172

Fax
302.738.7175

www.dedc-eng.com

PRE-BID MEETING SUMMARY
DEARNG – ARMY AVIATION SUPPORT FACILITY (AASF)
CLOSED CIRCUIT COOLER INSTALLATION
OMB/DFM CONTRACT #'S MC3601000091
FMO-DEARNG # 17-2016

ADDENDUM #2

Questions

1. Specification section 23 65 33 paragraph 2.03k indicate stand pipe heat tracing by others.
Please clarify.
Response: Disregard “by others”. Contractor shall include heat tracing the water level stand pipe in their bid.
2. Please clarify in Addendum 1 the subcontractor listing paragraph 3.
Response: All contractors (sub contractors and prime) must have a Delaware business license.
3. We need to know which type of antifreeze is in the geothermal system and its concentration.
Response: The geothermal loop contains 25% glycol and 75% water. Contractor is to provide all items in order to remove the antifreeze and to dispose.

Summarized By: DEDC, LLC
Date: February 13, 2017