# SECTION 22 01 40

# FIXTURES – PLUMBING

## PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the Work specified in this Section.

1.2 DESCRIPTION OF WORK

A. This Section includes:

1. Plumbing fixtures and trim work as indicated by drawings and schedules, and by requirements of this section.

2. Types of plumbing fixtures required for the project include the following:

   Water Closets with Sensor Operated Flush Valves
   Lavatories
   Manual-Operated Faucets
   Handicap Lavatory Insulation
   Lavatory Shield Enclosure

3. Refer to Section 220120 for domestic water piping systems used in conjunction with plumbing fixtures; not work of this section.

4. Refer to Section 220110 for soil and waste piping systems used in conjunction with plumbing fixtures; not work of this section.

5. Refer to Division 26 sections for electrical connections to water coolers and other plumbing fixtures; not work of this section.

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

B. Manufacturers: Firms regularly engaged in manufacture of plumbing fixtures of the type, style and configuration required, whose products have been in satisfactory use in similar service for not less than 3 years.

C. Plumbing Fixture Standards: Comply with applicable portions of International Plumbing Code pertaining to materials and installation of plumbing fixtures.

D. ANSI Standards: Comply with applicable ANSI standards pertaining to plumbing fixtures and systems.

E. ANSI & ADA Standards: Comply with ANSI A171.1 Standard and the ADA Standard pertaining to plumbing fixtures and provisions for handicapped.

1. Water closets shall be measured from the floor to the top of the seat. Bowls shall be elongated type. See Architectural details for all heights of fixtures.

2. Flush valve mechanisms shall be on the wide side of the stall. See Architectural details for all heights of fixtures.

3. Lavatories shall be mounted no higher than allowed by Architect's details from the floor and provide knee clearance using an offset drain assembly with "P" trap set parallel to the fixture supporting wall. Trap and wall supplies shall be installed for clearance required for the installation of lavatory shield enclosures.

4. Faucets shall be lever operated. See Fixture Schedule. All faucets shall operate on less than 5 pounds force and shall not require tight grasping, pinching or twisting of the wrist.

F. PDI Compliance: Comply with standards established by Plumbing and Drainage Institute pertaining to plumbing fixture supports.

G. Federal Standards: Comply with applicable FS WW-P-541/- Series sections pertaining to plumbing fixtures.

H. ARI Labels: Provide water coolers which are rated and certified in accordance with applicable Air-Conditioning and Refrigeration Institute Standards.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

B. Submit the following:

1. Product Data: Submit manufacturer's specifications for plumbing fixtures and trim, including catalog cut of each fixture type and trim item furnished, roughing-in dimensioned drawings, templates for cutting substrates, fixture carriers, and installation instructions.

2. Color Selection Data: Submit charts or samples for color selection where applicable.

3. Maintenance Data: Submit maintenance data and parts lists for each fixture type and trim item, including instructions for care of finishes. Include this data in maintenance manual.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

1.7 PRODUCT DELIVERY, STORAGE AND HANDLING

A. Deliver plumbing fixtures individually wrapped in factory-fabricated containers.

B. Handle plumbing fixtures carefully to prevent breakage, chipping and scoring the fixture finish. Do not install damaged plumbing fixtures; replace and return damaged units to equipment manufacturer.

**PART 2 – PRODUCTS**

2.1 PLUMBING FIXTURES

A. Provide factory-fabricated fixtures of type, style and material indicated. For each type fixture, provide fixture manufacturer's standard trim, carrier, seats, and valves as indicated by their published product information; either as designed and constructed, or as recommended by the manufacturer and as required for a complete installation. Where more than one type is indicated, selection is Installer's option; but, all fixtures of same type must be furnished by single manufacturer. Where type is not otherwise indicated, provide fixtures complying with governing regulations.

2.2 MATERIALS

A. Unless otherwise specified, comply with applicable Federal Specification WW-P-541/-Series sections pertaining to plumbing fixtures, fittings, trim, metals and finishes. Comply with the requirements of WW-P-541/-specification relative to quality of ware, glazing, enamel, composition and finish of metals, air gaps, and vacuum breakers, even though some plumbing fixtures specified in this section are not described in WW-P-541/-.

B. Provide materials which have been selected for their surface flatness and smoothness. Exposed surfaces which exhibit pitting, seam marks, roller marks, foundry sand holes, stains, decoloration, or other surface imperfections on finished units are not acceptable.

C. Where fittings, trim and accessories are exposed or semi-exposed, provide bright chrome-plated or polished stainless steel units. Provide copper or brass where not exposed.

D. Stainless Steel Sheets: ANSI/ASTM A-167, Type 302/304, hardest workable temper. Finish: No. 4, bright, directional polish on exposed surfaces.

E. Steel Sheets for Baked Enamel Finish: ANSI/ASTM A-591, coating Class C, galvanized-bonderized.

F. Steel Sheets for Porcelain Enamel Finish: ANSI/ASTM A-424, commercial quality, Type 1.

G. Vitreous China: High quality, free from fire cracks, spots, blisters, pinholes, and specks; glaze exposed surfaces, and test for crazing resistance in accordance with ANSI/ASTM C-554.

2.3 PLUMBING FITTINGS, TRIM AND ACCESSORIES

A. Lavatory Protective Shield Covers:

1. Fully molded enclosure "Lav Shields" as manufactured by Zurn or Truebro, Inc., complete with tamper-resistant stainless steel fasteners.

2. Shield enclosure to meet A.D.A. #4.19.4, ANSI A117.1 and BOCA P- 1203.4.

B. Water Outlets: At locations where water is supplied (by manual, automatic or remote control), provide commercial quality faucets, valves, or dispensing devices, of type and size indicated, and as required to operate as indicated. Include manual shutoff valves and connecting system pipes to permit outlet servicing without shut- down of water supply piping systems.

1. Vacuum Breakers: Provide with flush valves where required by governing regulations, including locations where water outlets are equipped for hose attachment.

C. P-traps: Include removable P-traps where drains are indicated for direct connection to drainage system. All traps shall be minimum 17 gauge.

D. Carriers: Provide cast-iron and/or steel supports for fixtures. Carriers shall be provided for all wall-hung fixtures, and/or the carrier shall be selected to support the fixture independently of the wall. Carriers shall be adjustable type, complete with all fittings and foot supports. Carrier shall be single or double, back-to-back, horizontal offset and vertical stack type. Carrier shall be selected and used as best suited within the pipe chases. Where noted or indicated, stud mount type carriers shall be used and installed within stud wall s 8" and less.

E. Fixture Bolt Caps: Provide manufacturer's standard exposed fixture bolt caps finished to match fixture finish.

F. Escutcheons: Where fixture supplies and drains penetrate walls in exposed locations, provide chrome plated sheet steel escutcheons with friction clips.

G. Aerators: Provide aerators of types approved by Health Departments having jurisdiction.

H. Comply with additional fixture requirements contained in fixture schedule attached to this section.

2.4 FIXTURE LIST

A. Refer to the "Plumbing Fixture & Equipment Schedule" as indicated on the drawings.

2.5 MANUAL-OPERATED LAVATORY SYSTEM FAUCETS

A. This Contractor shall furnish and install complete and operating operational faucets where so indicated and noted.

B. The Contractor shall have a complete understanding of the manual operated equipment and system they are installing during the bid phase of the work.

C. The Contractor shall install the system in strict conformance with the manufacturer's written instructions. The installation shall be executed with good workmanship and to be clear of any interference with the user including the installation of lavatory protective shield enclosures.

2.6 AVAILABLE MANUFACTURERS

A. Subject to compliance with requirements, manufacturers offering fixtures, trim and carriers which may be incorporated in the work include, and are limited to the following:

Water Closets/Floor-Mounted Bottom Outlet (Children Toilet)

Crane
American Standard
Sloan
Zurn
Mansfield

China/Enameled Fixtures

American Standard
Eljer
Crane
ToTo
Sloan
Zurn
Mansfield

Faucets/Trim (Non-Sensor Operated)

American Standard
Delta
Moen
Elkay
Speakman
Chicago
T&S Brass
Zurn

Sensor Operated Flush Valves

Sloan
Coyne & Delany
Delta
Zurn
ToTo

Wall Supplies/Traps

McGuire
Brass-Craft
Kohler
American Standard
Sanitary-Dash
Teledyne
Wolverine
Pro-Flo
Keeny

Fixture Carriers

Zurn
Josam
Wade
Watts
Smith
MIFAB

Fixture Seats

Olsonite
Sperzel
Benke
Bemis
Church
Kohler
American Standard
Centoco
Comfort Seat

B. Cross Reference Identification:

1. If the Contractor selects a manufacturer of drainage equipment products other than as identified on the Schedule but is selected from the available manufacturers listed above, a cover sheet shall be included with the submission of shop drawings indicating the cross referenced manufacturer and model number.

2. Shop drawings shall not be reviewed or accepted if not in compliance with this requirement.

2.8 HANDICAP LAVATORY INSULATION

A. Fully molded "P" trap and angle valve insulation kit Handi-Lav Guard Truebro Model #101, 102 and 105 to suit.

B. Insulation to meet A.D.A. #4.19.4, ANSI A117.1 and BOCA P- 1203.4.

C. Self-extinguishing ASTM D635 burn characteristics, Thermal conductivity ASTM C177-K value 1.17.

**PART 3 – EXECUTION**

3.1 FIXTURE CONNECTIONS

A. Connections to plumbing fixtures shall be of the sizes indicated on the "Plumbing Fixture & Equipment Schedule".

B. The sizes indicated on the Schedule are for drainage and water piping serving an individual fixture; the sizes of the mains and branches shall be as indicated on the drawings.

3.2 FIXTURE SETTING HEIGHTS

A. The plumbing fixtures shall be set in accordance with the heights established by the latest edition of codes and ADA requirements.

Note: Height indicated is established as follows:

| | |
|---|---|
| Water Closets: | From finished floor to top of seat. |
| Urinals: | From finished floor to rim of fixture. |
| Lavatories & EWC: | From finished floor to rim of fixture. |
| Receptor Fitting: | From finished floor to center of fitting. |
| Shower: | From finished floor to center of shower head. |

B. Refer to Architectural drawings and sections for fixture elevations. Fixtures in various areas may be set at lower elevations. Confirm <u>all</u> rough-in elevations prior to any installation.

3.3 LAVATORY PROTECTIVE SHIELD ENCLOSURES

A. Installation shall conform to manufacturer's written instructions.

B. All items involved with wall-hung lavatory installations shall be roughed-in and installed within the enclosure. This includes the offset "P" trap assembly, thermostatic mixing valve, sensor faucet trim and accessories, electrical outlet. Coordinate all work required for complete concealment of all devices.

C. Protective shield enclosures are required on the toilet room's countertop lavatories and are furnished by the Architect. Coordinate all trim and accessories to fit within this enclosure.

3.4 INSPECTION AND PREPARATION

A. Examine roughing-in work of domestic water and waste piping systems to verify actual locations of piping connections prior to installing fixtures. Also examine floors and substrates, and conditions under which fixture work is to be accomplished. Correct any incorrect locations of piping, and other unsatisfactory conditions for installation of plumbing fixtures. Do not proceed with work until satisfactory conditions have been corrected.

B. Install plumbing fixtures of types indicated where shown and at indicated heights; in accordance with fixture manufacturer's written instructions, roughing-in drawings, and with recognized industry practices. Ensure that plumbing fixtures comply with requirements and service intended purposes. Comply with applicable requirements of the International Plumbing Code pertaining to installation of plumbing fixtures.

C. Fasten plumbing fixtures securely to indicated supports or building structure; and ensure that fixtures are level and plumb. Secure plumbing supplies behind or within wall construction so as to be rigid, and not subject to pull or push movement.

3.5 CLEAN AND PROTECT

A. Fixture shall be thoroughly cleaned after completion of installation.

B. Protect installed fixtures from damage during the remainder of the construction period.

3.6 FIELD QUALITY CONTROL

A. Upon completion of installation of plumbing fixtures and after units are water pressurized, test fixtures to demonstrate capability and compliance with requirements. When possible, correct malfunctioning units at site, then retest to demonstrate compliance; otherwise, remove and replace with new units and proceed with retesting.

B. Inspect each installed unit for damage to finish. If feasible, restore and match finish to original at site; otherwise, remove fixture and replace with new unit. Feasibility and match to be judged by Architect/Engineer. Remove cracked or dented units and replace with new units.

**END OF SECTION 22 01 40**