# SECTION 22 00 00

# GENERAL PROVISIONS – PLUMBING/FIRE PROTECTION

## PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and all other applicable Divisions, apply to work of this Section.

B. This specification or drawing and the design features or resulting construction disclosed, are the property of Furlow Associates, Inc., and shall not be reproduced without written permission.

C. All fire protection suppression systems shall be part of and included in all of the following 220000 thru 220191 Sections.

1.2 WORK INCLUDED

A. Provide labor, materials, equipment and supervision necessary to install complete operating Plumbing and Fire Protection Systems as indicated the drawings and specified herein, including all work at the site and within the proposed construction areas to accomplish the required work.

1.3 REGULATIONS, CODES AND STANDARDS

A. Work shall be performed in accordance with latest adopted codes, regulations and ordinances by authorities having jurisdiction. Observe all safety regulations.

B. Latest editions of any referenced standards shall govern.

C. Obtain all municipal and/or the Authorities Having Jurisdiction permits and inspection certificates and pay all charges.

D. Make or arrange for any/or all inspection agency reviews or visits and pay all charges. This includes communication with each respective agency and/or utility to verify the project system work, coordination responsibilities, fees, back charges, etc., required.

E. All fees and back charges shall be verified during the bidding phase of the work. Any discrepancy of this item between any utility, inspection agency and the Contractor shall be brought to the attention of the A/E prior to bid opening.

F. Submission of a bid will be deemed evidence of having complied with these requirements.

1.4 RELATED WORK

A. Refer to equipment shown or specified in all other applicable Divisions that require Plumbing and Fire Protection services.

B. Refer to work related to Plumbing and Fire Protection as shown on the following contract drawings:

Architectural & Structural
HVAC
Electrical

1.5 COORDINATION

A. The Mechanical, Plumbing and Electrical Contractors are responsible to coordinate all manufacturer's recommended circuit breakers, starters, disconnects and fuse sizes for all equipment. Submission of a shop drawing will certify that this has been completed. Any necessary changes required will be included as part of this contract.

B. Plumbing and Sprinkler Contractors shall coordinate scheduling, submittals and work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of independent work elements, with provisions to accommodate items that may be installed at a later time.

C. Plumbing and Sprinkler Contractors shall verify utility requirements and all characteristics of operating equipment are compatible with the building utilities. Coordinate the work of all sections related and required for installing, connection and placing in service of all equipment.

D. Plumbing and Sprinkler Contractors shall coordinate all space requirements, supports and installation of all mechanical, electrical, plumbing and fire protection work, which are indicated diagrammatically on the Drawings. Verify routing of all pipes, ducts, conduits and equipment connections. Maximize accessibility for other work, and service requirements for maintenance and repairs.

E. Obtain written confirmation from all related trade Contractors and the Owner or his representative that requirements, conflicts and coordination issues have been discussed and resolved.

1.6 SUBMITTALS

A. Shop Drawings & Product Data:

1. Shop drawings and product data shall be submitted in accordance with Division 22 specifications except where herein modified.

<u>NOTE: Submittals will only be reviewed once and resubmittals will be reviewed once. Any other submittals will be billed to the Contractor at the Engineer's standard rates.</u>

2. Listed are the required shop drawings and reports required for this project. The Engineer/Owner shall reserve the right to require additional submissions not listed below:

- All fixtures, equipment and associated devices so listed on the Fixture Schedule on Drawing P-501.

- Insulation
- All specified piping systems.
- All specified valves.
- Hanger and supports including Sumner system.
- Piping labels and identification.
- Sprinkler System and all related data, devices, switches and trimmings.
- Testing reports.
- Sterilization report.
- Operating/Maintenance manuals.
- As-Built Drawings.

3. Submittals comprising complete catalog cuts, shop drawings and performance test data for Plumbing materials and equipment as required by other sections of Division 22, shall be submitted for review checking. The Contractor shall review these for conformance to contract documents prior to submission and affix contractor's signature to each submittal certifying that this review has been done. By approving and submitting shop drawings, product data, samples and similar materials, the Contractor represents that the Contractor has determined and verified materials, field measurements and field construction data that relates to the work, and has checked and coordinated this information with all of the requirements contained in the contract documents for the work of all trades.

4. All submittals shall have the following identification data, as applicable, contained therein or permanently adhered thereto.

   a. Project name.

   b. Project number.

   c. Sub-contractor's, vendor's and/or manufacturer's name and address.

   d. Product identification.

   e. Identification of deviation from contract documents.

   f. Applicable contract drawings and specification section number.

   g. Shop drawing title, drawing number, revision number, and date of drawing and revision.

   h. Resubmit revised or additional submittals as requested.

   i. Wherever shop drawings or vendor's standard data sheets indicate work to be done "by others", it shall be the responsibility of the contractor making the submission to identify by name, the contractor who is to do this work. If the contractor named is other than the contractor making the submission, the shop drawing submission must be reviewed by the named contractor and bear his mark of approval, prior to submission to the Architect/Engineer.

j. Where equipment proposed differs from that shown on the drawings or specified, he shall submit for approval drawings showing the manner in which the layout is affected by the substitution.

k. The Contractor shall keep one copy of approved shop drawings at the job site,, filed in a suitable metal container. The shop drawings shall be cataloged and kept in good repair, and shall be available for use by the Owner, Architect and Engineer.

l. No equipment shall be ordered, fabricated, etc., before approval of shop drawings.

B. Contractor is responsible for the shop drawing coordination and interface with the work of other contracts and adjacent work. The relationship of Contractor's work shall be verified as it relates to adjacent and critical features of the work of this and all contracts and materials.

1.7 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in all other applicable Divisions. In addition, refer to specifications for special guarantees.

B. Wherever in the specification sections of this division, reference is made to a specific warranty period, this warranty shall be in addition to and not a limitation of other rights the Owner may have against the Contractor under the contract documents.

C. Contractor to include an 11 month "walk-thru" of the building systems with representatives of the School District, Architect, Engineer and the Construction Manager. The purpose is to establish a list of corrective work that relates to operational issues, material/installation deficiencies.

1.8 SITE INSPECTION

A. The Contractor shall visit the site, inspect, and become aware of all conditions which may affect the work during the estimation phase of his work and prior to bid openings. Investigate utilities, protection requirements for adjacent facilities, storage locations, and access to the construction area.

B. Submission of a bid will be deemed evidence of having complied with this requirement.

1.9 SUBSTITUTIONS

A. Whenever a material, article, piece of equipment or system is identified in the following specification or indicated on the drawings by reference to manufacturers' or vendors' names, trade names, catalog numbers or the like, it is so identified for the purpose of establishing the basis of the Bid.

B. Substitution approval must be obtained and included as an addendum item prior to the submission of the bid. An approved substitution shall not be considered as an approval for the Contractor or an equipment vender to deviate from the written portion of the specifications unless so stated in the addendum.

C. The drawings illustrate the space allocated for equipment and the Contractor shall install the equipment accordingly. If changes are required in the building or arrangement due to substitution of equipment, the Contractor making the substitution must pay for the necessary modifications.

D. The listed equivalent or substituted manufacturers along with the bidding related contractor shall be completely responsible to comply with all requirements as indicated on all contract documents and as described within the specifications. This shall include, but shall not be limited to space requirements, code clearances, the type, horsepower, capacities, number and size of services required from other trades, including all required ancillary items furnished and installed by other trades. If the manufacturer or related bidding contractor does not comply with these requirements, then they shall be responsible for any and all additional costs associated with the changes required by other trades.

1.10 EQUIPMENT START-UP

A. Verify proper installation by manufacturer or his representative.

B. Advise General Contractor 2 days prior to actual start-up.

C. Verify proper operation. Obtain signed statement by manufacturer or his representative that equipment is operating within warranty requirements. Submit statement to General Contractor.

1.11 OPERATION & MAINTENANCE INSTRUCTIONS

A. Properly and fully instruct Owner's personnel in the operation and maintenance of all systems and equipment.

B. Insure that the Owner's personnel are familiar with all operations to carry on required activities.

C. Such instruction shall be for each item of equipment and each system as a whole.

D. Provide report that instruction has taken place. Include in the report the equipment and/or systems instructed, date, contractor, Owner's personnel, vendor, and that a complete operating and maintenance manual has been reviewed.

E. Manual shall include all instructions on operation, maintenance, repair parts list, lubrication requirements, brochures, catalogue cuts, wiring diagrams, piping diagrams, control sequences, service requirements, names and addresses of vendors, suppliers and emergency contacts. Three manuals shall be provided.

F. Submit manuals for review prior to operating instruction period. Manuals shall be 8-1/2 x 11" with hard cover, suitably bound.

G. Provide to the Owner any special tools necessary for operation and routine maintenance of any of the equipment.

H. Furnish three (3) copies of a professionally taped video and three (3) copies of professionally prepared drawings demonstrating the following:

- Location of main shut-off valves
- Procedures for equipment start-up and seasonal shut-downs.
- Procedures for maintenance.
- Provide written version of all procedures included in video.

The above should cover all equipment/systems including, but not limited to the following:

- Sprinkler Systems
- Flush valves
- Manual Faucets

1.12 TOOLS

A. All equipment furnished by the Contractor which requires special tools or devices other than those normally available to the maintenance or operating staff shall be furnished in duplicate to the Owner, sufficiently marked, packed or boxed for staff usage. The tools provided shall be listed by the Contractor identified as to their use or the equipment applicable in a written transmittal to the Owner.

1.13 CLEANING AND FINISHING

A. After equipment start-up and all operating tests have been made and the system pronounced satisfactory, each respective Contractor shall go over the entire project, clean all equipment, etc., installed by him and leave in a clean and working condition. Any surfaces found marred after this final cleaning shall be refinished or replaced by each Contractor at no cost to the Owner.

B. Provide for the safety and good condition of all materials and equipment until final acceptance by the Owner. Protect all materials and equipment from damage. Provide adequate and proper storage facilities during the progress of the work. Special care shall be taken to provide protection for bearings, open connections, pipe coils, pumps, compressors and similar equipment.

C. All NEW fixtures, piping, finished surfaces and equipment installed shall have all grease, adhesive labels and foreign materials removed.

D. All new piping installed shall be drained and flushed to remove grease and foreign matter. Pressure regulating assemblies, traps, flush valves and similar items shall be thoroughly cleaned. Remove and thoroughly clean and reinstall all liquid strainer screens after the system has been in operation ten (10) days.

E. When connections are made to existing systems, the Contractor shall do all cleaning and purging of the existing systems required to restore them to the condition existing prior to the start of work.

F. Clean-up: Remove from the premises, all unused material and debris resulting from the performance of work under this section.

## PART 2 – PRODUCTS

2.1 GENERAL

A. All material and equipment shall be new and of present day manufacture, and shall conform to accepted standards of the trade where such a standard has been established for the particular type of equipment or material.

B. Whenever equipment or material is referred to in the singular, such as "the plumbing fixture", it shall be deemed to apply to as many such items as necessary to complete the work.

2.2 PRODUCT DELIVERY, STORAGE AND HANDLING

A. During loading, transporting and unloading exercise care to prevent damage to material.

B. Store all materials in dry enclosures or under protective coverings out of way of work progress.

C. Material shall not be allowed to be stored directly on ground.

D. Deliver in manufacturer's original cartons or on skids.

E. Handle and protect so as to prevent damage to product or any surrounding material.

2.3 CONCRETE

A. Concrete if used on this project, shall be in accordance with Section 033000.

B. The 28-day minimum compressive strength shall be 3000 psi.

## PART 3 – EXECUTION

3.1 PROTECTION

A. Plug or cap open ends of piping systems.

B. Stored materials shall be covered to prevent damage by inclement weather, sun, dust or moisture.

C. Protect all installed work until accepted in place by the Owner.

D. Plates, polished metal escutcheons and other finished devices shall not be installed until masonry, tile, and painting operations are complete unless otherwise protected.

E. Protect all work from operations which may cause damage such as hauling, welding, soldering, painting, insulating and covering.

F. Do not remove protective material until equipment is placed in service.

3.2 WORKMANSHIP

A. Install all work neat, trim and plumb with building lines.

B. Install work in spaces allocated.

C. Cutting and patching shall be performed by skilled tradesmen normally employed for the work involved.

3.3 EXCAVATION

A. The excavation shall be of the open-trench method and to the depths and widths as may be necessary. The Contractor shall do all excavation required in connection with his work. Bottoms of trenches shall be excavated to a uniform grade. All materials excavated shall be deposited on the side of the trenches and beyond the reach of the slides. Excavated material shall not be piled where it will interfere with traffic. If rock is encountered, it shall be removed by the General Contractor. See provisions in Division 2.

B. No piping shall be bedded directly on rock. They shall be cushioned by a 6-inch layer of crushed stone or gravel of selected grade, of size to pass through 3/4" mesh sieve. Not less than 30% shall be fine which will pass through a 3/8" mesh sieve.

3.4 SHORING AND PUMPING

A. The Contractor shall provide all shoring, bracing or sheet piling necessary to maintain the banks of his excavation and shall take out same as the work progresses and filling in has been accomplished. Shoring shall be in accordance with OSHA Standards.

B. The arrangement of shoring must be such as to prevent any movement of the trench banks and consequent strains on the conduits. Shoring shall be provided to prevent damage to work installed by other trades.

C. The Contractor shall do all pumping required to keep his excavations free of water. The water shall be conveyed in piping or watertight troughs a sufficient distance that it will flow from the site and not affect other work being performed.

3.5 BACKFILLING

A. After work in trenches has been completed, they shall be filled with select fill in 8" layers and shall be pneumatically tamped before the next layer of material has been filled in. The backfill shall be free of excavated rock, cinders, stones, brickbats or other debris.

B. Wherever rock is removed, the Contractor shall secure and fill select clean earth to a minimum depth of 3'-0" above the top of the pipe. Unless otherwise indicated, no rock shall be deposited in the trench fill. This clean earth fill shall be procured other than from the site unless permission for earth borrow from the site is granted by the Architect. If site borrow is permitted, the topsoil removal, relocation and finished grading will be accomplished as directed by the Architect.

C. Under no circumstances shall excavated material be left where it will interfere with the Owner's or other Contractor's operations.

D. All earth and other materials taken from the trenches and not required for backfilling shall be deposited where directed, or removed from the premises as directed by the Architect.

E. Any rock removed from the excavation shall be removed from the project site by the Contractor.

F. Trenches which pass under wall footings or within 18" of column footings shall be backfilled with lean concrete. To secure adequate foundation support, the method and depositing of the concrete fill shall be as directed by the Architect. To prevent the concrete from adhering to the pipes, necessary pipe protection shall be applied.

3.6 EQUIPMENT SETTING

A. Furnish and install as a minimum, a 4 inch concrete pad beneath all floor-mounted equipment. Install anchor bolts in pour.

B. Furnish and install as a minimum, spring vibration isolation under any equipment 10 HP and over and rubber in shear vibration isolation on any equipment up to 10 HP.

C. Concrete shall be 3,000 psi, 28 day compressive strength in accordance with ACI-613. Reinforce with No. 4 rod 12" on centers both ways or as otherwise detailed.

3.7 FASTENERS, HANGERS AND SUPPORTS

A. Furnish and install all hangers and supports required to suspend, mount, or hang the work.

B. Furnish and install all miscellaneous steel angles, channels, beams, clips, brackets and anchors necessary to hang or support the work. Provide submissions for review.

C. Install concrete inserts before concrete is poured.

D. Drilled inserts shall not be loaded more than 1/4 rated capacity or 200 pounds.

E. Power-driven fasteners shall not be allowed for piping larger than 2 inch, or equipment. When used they shall not be loaded more than 1/8 rated capacity or 200 pounds.

F. All hangers, miscellaneous steel, braces and supports shall be galvanized, cadmium plated, or primed steel. Copper tubing shall be supported with copper hangers. No direct contact of dissimilar metals between the piping system and its hanger support shall be permitted.

G. Piping shall be supported from adjustable clevis type hangers with insulation pipe saddles. Where hangers are 18” or longer, provide lateral bracing at every fourth hanger. See IPC Pipe Support Table below:

PIPE SUPPORT SPACING

| Material | Horizontal Max. Feet | Vertical Max. Feet |
|---|---|---|
| ABS Pipe | 4 | 10 |
| Aluminum | 10 | 15 |
| Brass | 10 | 10 |
| Brass Tube up to 1-1/4” | 6 | 10 |
| Brass Tube over 1-1/2” | 10 | 10 |
| Cast Iron | 5 | 15 |
| Copper up to 1-1/4” | 6 | 10 |
| Copper over 1-1/4” | 10 | 10 |
| CPVC Up to 1” | 3 | 10 |
| CPVC Over 1” | 4 | 10 |
| Lead Pipe | Continuous | 4 |
| PB Pipe/Tubing | 2.6 ft. (32”) | 10 |
| PVC Pipe | 4 | 10 |
| PEX | 2.6 ft. (32”) | 10 |
| Steel Tubing | 8 | 10 |
| Steel Pipe | 12 | 15 |

H. Support vertical piping at floor levels using approved riser clamps. Clamp material shall be compatible with pipe material. Maximum vertical spacing shall be10’-0”.

3.8 SLEEVES

A. Provide each pipe passing through a masonry or concrete wall, floor or partition with a sleeve made from standard weight steel pipe for pipe with smooth edges, securely and neatly cemented in place. Provide each pipe passing through a frame or metal partition with a sleeve made from No. 22 gauge galvanized sheet metal, securely fastened in place.

B. Pipe passing through foundation wall or under foundation shall be provided with relieving arch or steel pipe per IPC Section 305.5.

C. Be responsible for the proper location and alignment of all sleeves.

D. Provide hydrostatic seals for sleeves passing through outside walls, below grade, or through hydrostatically sealed slabs or floors on grade. Provide fire-rated seals for all other sleeves.

E. Install both piping and sleeve seals so as to maintain integrity of seals with expansion and contraction of piping.

F. Set floor sleeves flush with floor surface in finished areas, 1" above the finished floor in kitchens, cafeterias, and similar service areas unless such areas are slab-on-grade; 1" above the floor in mechanical rooms, pipe chases, pipe spaces and other unfinished areas, unless otherwise indicated, and flush with the underside of slabs. Extend wall and partition sleeves through and cut flush with each surface unless otherwise indicated or specified.

G. Select sleeves two pipe sizes larger than any pipe that is to remain uncovered, unless otherwise required by the sealing method specified. Where pipes are to be covered, provide sleeves large enough to allow the covering to pass through the sleeves with sufficient clearance for sealing as specified hereinafter. Size sleeves for branch piping from vertical risers large enough to permit vertical expansion at the riser.

H. Place sleeves imbedded in concrete floors or walls in the forms before concrete is poured; sleeves shall have integral waterstop flanges, where they are to receive either watertight or hydrostatic seals.

I. Install sleeves passing through above-grade floors of mechanical rooms, toilet rooms, kitchens or similar service areas where liquid leaks or spillover may occur in a watertight manner. Sleeves shall be such that waterproofing membrane can be flashed around and into the sleeve where necessary.

J. Seal sleeves for pipes passing through ceiling air plenum walls or the floor above air tight in a manner similar to that specified for fire-rated sleeves.

K. Hydrostatic Sealing Method: Provide compressible synthetic rubber seals, equivalent to LINK SEAL, manufactured by the Thunderline Corporation, or THRUWALL manufactured by O.Z. Gedney. Install seals in accordance with the manufacturer's recommendations to provide air tightness aboveground and hydrostatic sealing belowgrade. Caulking or other type mastic is not acceptable.

L. Fire-Rated Sealing Method:

1. Sleeves, openings and sealants shall comply with applicable codes, recommended practices and standards, and manufacturer's instructions. Fire sealants shall have ability to prevent spread of flame, smoke or water throughout the penetration and shall pass 3 hour test, UL test ASTM E814 and UL 1479.

2. Products: Chase Corporation CTC PR-855, O. Z. Gedney CRS/CAFS, 3M Electro-Products Division Putty 303 or Caulk CP25 penetration sealing kits, General Electric Company sealants type RTV-850, 6428 or 7403, Thunderline Corporation "Link-Seal Pyro-Pak". Installation and type of sealant to be used as recommended by the manufacturer.

3. Expansion collars, fire seal/firestop collars – ASTM E814 (UL1479). Spec Seal Corporation, Inc. (plastic pipe).

3.9 PLATES

A. Furnish and install chrome plated plates wherever piping passes into finished area.

B. Plates shall be securely fastened to piping or building construction.

C. Floor plates shall cover 1 inch sleeve extension.

3.10 OFFSETS, TRANSITIONS, MODIFICATIONS

A. Furnish and install all offsets necessary to install the work and to provide clearance for other trades.

B. Maintain adequate headroom and clearance.

C. Incidental modifications necessary to the installation of the systems shall be made as necessary and as approved by the Architect.

3.11 RECESSES

A. Furnish information to the General Contractor as to sizes and locations of recesses required to install panels, boxes, and other equipment or devices which are to be recessed in walls.

B. Make offsets or modifications as required to suit final locations.

3.12 LABELING

A. All Plumbing equipment such as pumps, and devices requiring identification for operating procedures shall be provided with permanent black laminated micarta white core labels with 3/8 inch letters.

B. This shall also apply to all controllers, remote start/stop pushbuttons and equipment cabinets.

3.13 FLASHING AND COUNTERFLASHING

A. Roof drains, vents, roof curbs, etc., shall have counterflashing fittings. General Contractor shall provide flashing.

B. Piping and conduit thru the roof shall be flashed by the General Contractor. Furnish and install counterflashing.

3.14 ACCESS

A. Locate all equipment, valves, devices and controllers which may need service in accessible places.

B. Where access is not available, access panels shall be provided. Furnish access doors to the General Contractor for installation.

C. Access doors shall be Elmdor, Karp Co., MIFAB or Controlled Air Manufacturing Limited, with 16 gauge frames and 14 gauge steel door, prime painted.

D. Maintain required access clearances.

3.15 UTILITIES

A. Do not interrupt any utility or service to the Owner without adequate previous notice and schedule.

B. Arrange and pay for the relocation, disconnection or removal of, or relocate, disconnect or remove existing utilities and services where such work is shown or where such utilities or services interfere with new construction, whether or not shown. Provide all excavation, backfilling and paving required by such work.

C. Perform alteration of utilities and services in accordance with the rules, regulations and requirements of the involved utility companies, regulatory agencies having jurisdiction.

3.16 CUTTING AND PATCHING EXTERIOR SURFACES

A. This Contractor shall be responsible for returning disturbed paved and/or grass areas to original condition where excavation for utilities has been required.

B. Cut and patch paved areas to match original surface.

C. Properly tamp backfill before finishing or repairing disturbed area surfaces.

3.17 OPENINGS - CUTTING, REPAIRING

A. This contractor shall cooperate with the work to be done under other sections in providing information as to openings required in walls, slabs and footings for all piping and equipment, including sleeves where required.

B. Any drilling or cutting required for the performance of work under this Section, shall be the responsibility of this Contractor and the cost thereof shall be borne by him.

C. Holes in Concrete: Sleeves shall be furnished, accurately located and installed in forms before pouring of concrete. This contractor shall pay all additional costs for cutting of holes as the result of the incorrect location of sleeves. All holes through existing concrete shall be either core drill or saw cut. All holes required shall have the approval of the Structural Engineer prior to cutting or drilling.

D. It shall be the responsibility of this Contractor to ascertain that all chases and openings are properly located.

3.18 GUARANTEE

A. All materials and equipment provided and/or installed under this section of the specifications shall be guaranteed for a period of one year from the date of acceptance of the work by the Owner unless otherwise specified in other applicable Divisions. Should any trouble develop during this period due to defective materials or faulty workmanship, the Contractor shall furnish all necessary labor and materials to correct the trouble without any cost to the Owner. Any defective materials or inferior workmanship noticed at time of installation and/or during the guarantee period shall be corrected immediately to the entire satisfaction of the Owner.

In the event of occupancy by the Owner prior to final acceptance of the project, the guarantee date for equipment placed in operation shall be mutually agreed to by the Contractor and the Owner's representative.

B. Contractor to include an 11 month "walk-thru" of the building system with representatives of the School District, Architect, Engineer and the Construction Manager. The purpose is to establish a list of corrective work that relates to operational issues, material/installation deficiencies.

3.19 DRAWINGS

A. The Plumbing and Fire Protection Systems are indicated on the Contract Drawings. Certain pertinent information and details required by the Plumbing and Fire Protection Work appear on the Architectural, Structural and Electrical Drawings; become familiar with all Drawings; and incorporate all pertinent requirements.

B. Drawings are diagrammatic and indicate the general arrangement of systems and requirements of the Work. Do not scale Drawings. Exact locations of fixtures and equipment, not specifically shown shall be obtained before starting work.

C. When indicated on the drawings, plumbing riser diagrams are completely diagrammatic and indicate the intent of the work for both the Contractor, L&I review agencies and/or Authorities Having Jurisdiction. Where valves, shock absorbers, incidental equipment, devices, etc., including execution notes are indicated on the riser diagrams, they shall be so required and installed as part of the system work.

3.20 RECORD DRAWINGS

A. As-Built record drawings, showing dimensions, locations and depth of all buried and concealed piping, plugged outlets and equipment shall be kept up to date. Master copy shall be kept on the job. No backfilling of trenches shall be permitted until as-built drawings are approved as up-to-date by the Owner/Representative. No plumbing progress payments shall be approved unless as-built drawings are up- to-date. Depth of sewers shall be from a permanent bench mark as shown on the contract drawings. Refer to project record drawings under General Conditions.

**END OF SECTION 22 00 00**