

#### ADDENDUM ISSUED BY

ABHA Architects, Inc.  
1621 N. Lincoln Street  
Wilmington, Delaware 19806

NOTICE: Attach this Addendum to the Project Manual for this project. It modifies and becomes a part of the Contract Documents. Work or materials not specifically mentioned herein are to be as described in the main body of the Specifications and as shown on the Drawings.

Acknowledge receipt of the Addendum in the space provided on the Bid Form. This Addendum is being transmitted to all contractors who have received Contract Documents. If there are any problems with legibility or content, please contact ABHA Architects, Inc. (302) 658-6426.

#### ATTACHMENTS

SECTION 004113 – BID FORM, Page 6  
Sketch SKME-1

#### CHANGES TO SPECIFICATIONS

##### SECTION 004113- BID FORM

Replace Page 004113-6 with attached Page 004113-6

##### SECTION 011000 - SUMMARY OF WORK

Clarification: Substantial Completion should be considered after cooling season is over. Therefore, extend project completion date to November 15, 2017.

##### SECTION 230215 - VALVES

- a. Page 230215-3, Paragraph 2.2.F: DELETE 'or grooved end' from the first sentence.
- b. Page 230215-4, Paragraph 2.2.H: DELETE 'or grooved end' from the first sentence.

NOTE: The Owner does not want any mechanical grooved piping and/or accessories in this project.

#### CHANGES TO DRAWINGS

##### DRAWING ME-2 - PARTIAL FIRST FLOOR & SITE PLANS - MECH & ELECT

Detail 2/ME-2 - Provide one (1) chiller pad and extend beyond the footprint per attached sketch SKME-1

Drawings Notes -

Note #2 Clarification: Eleven (11) joists require reinforcing per Structural Detail.

DRAWING ME-3 - SCHEDULES & DETAILS - MECH & ELECT

Chilled Water Pipe Support Detail -

Clarification: This detail is for outside applications only. All interior piping is hung off of building structure.

END OF ADDENDUM NO. 3