

ADDENDUM ISSUED BY

ABHA Architects  
1621 N. Lincoln Street  
Wilmington, Delaware 19806

NOTICE: Attach this Addendum to the Project Manual for this project. It modifies and becomes a part of the Contract Documents. Work or materials not specifically mentioned herein are to be as described in the main body of the Specifications and as shown on the Drawings. Acknowledge receipt of the Addendum in the space provided on the Bid Form.

**This Addendum includes the following:**

**REVISIONS TO PROJECT MANUAL**

**SECTION 10 4400 FIRE PRTECTION SPECIALTIES**

PART 3, ITEM 3.03, PARAGRAPH A – Change to:

- A. Provide (3) type K fire extinguishers and wall brackets. Locations to be determined in field.

**CHANGES TO THE DRAWINGS**

**DRAWING A-113**

Plan A4:

1. Doors at Storage F120 to remain
2. Add Sheet keynote 4 to Door between Storage/Prep F121 and Kitchen F119

**DRAWING A-114**

Plan A4:

1. Doors 227 & 228 – not in contract.

**DRAWING A-301**

Detail A5:

1. Assumed thickness of mud slab per historic drawings is 4".

Detail A4:

1. Provide continuous blocking at coiling door.

DRAWING A-302

Detail A3:

1. Provide continuous blocking at coiling door.

DRAWING I-114

FINISH KEY NOTES: Change note 4 to

4. FRP-1 TO RUN ALONG FACE OF SOFFIT.

DRAWING E-102

Replace Drawing with attached E-102.

DRAWING P-102

Replace Drawing with attached P-102.

DRAWING P-103

Replace Drawing with attached P-103.

**ATTACHMENTS**

E-102

P-102

P-103

END OF ADDENDUM NO. 2