PROJECT MANUAL

FOR

MT PLEASANT HIGH SCHOOL CAFETERIA UPGRADES

BRANDYWINE SCHOOL DISTRICT — **OWNER**
1311 BRANDYWINE BOULEVARD
WILMINGTON, DELAWARE 19809

ABHA ARCHITECTS — **ARCHITECTS**
1621 N. LINCOLN STREET
WILMINGTON, DELAWARE 19806
(302) 658-6426, FAX (302) 658-8431

FURLOW ASSOCIATES — **MECHANICAL/ELECTRICAL AND PLUMBING ENGINEERS**
1206 SOCIETY DRIVE
CLAYMONT, DE 19703
(302) 798-3515, FAX (302) 798-9799

CORSI ASSOCIATES — **FOOD SERVICE**
1489 BALTIMORE PIKE BLDG 9
SPRINGFIELD PA 19064
(610) 541-08225, FAX (610) 541-0824

BSD CONTRACT NO. BSD17012_CAFETERIA_UPGRADES_MPHS

ABHA PROJECT NUMBER: 1403

DATE: MARCH 6 2017

ABHA architects
1621 N. Lincoln Street
Wilmington, DE 19806
(P)302.658.6426
(F)302.658.8431

abhagen@ABHA.com
www.ABHA.com

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

001150 ADVERTISEMENT FOR BIDS
002110 INSTRUCTIONS TO BIDDERS
004113 BID FORM
005000 CONTRACTING FORMS AND SUPPLEMENTS
007310 SUPPLEMENTARY GENERAL CONDITIONS A201-2007
007313 SUPPLEMENTARY CONDITIONS
009000 DE STATE GENERAL REQUIREMENTS
009500 GENERAL AND SPECIAL INSTRUCTIONS

DIVISION 01 - GENERAL REQUIREMENTS

011000 SUMMARY
012000 PRICE AND PAYMENT PROCEDURES
017800 CLOSEOUT SUBMITTALS

DIVISION 02 - EXISTING CONDITIONS

02 4100 DEMOLITION

DIVISION 04 - MASONRY

04 2000 UNIT MASONRY

DIVISION 05 - METALS

05 5213 PIPE AND TUBE RAILINGS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 1000 ROUGH CARPENTRY
06 2000 FINISH CARPENTRY

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 2616 UNDER-SLAB VAPOR BARRIER/RETARDER
07 9200 JOINT SEALANTS

DIVISION 08 - OPENINGS

08 1113 HOLLOW METAL DOORS AND FRAMES
08 1416 FLUSH WOOD DOORS
08 3326 OVERHEAD COILING GRILLES

DIVISION 09 - FINISHES

09 0561 COMMON WORK RESULTS FOR FLOORING PREPARATION
09 2116 GYPSUM BOARD ASSEMBLIES
09 3000 TILING

TABLE OF CONTENTS
MPHS Cafeteria Upgrades

09 5100	SUSPENDED ACOUSTICAL CEILINGS
09 6500	RESILIENT FLOORING
09 7733	GLASS FIBER REINFORCED PLASTIC PANELS
09 9000	PAINTING AND COATING

DIVISION 10 - SPECIALTIES

10 4400	FIRE PROTECTION SPECIALTIES

DIVISION 21: FIRE SUPPRESSION

21 0170	FIRE PROTECTION SYSTEMS

DIVISION 22: PLUMBING

22 0000	GENERAL PROVISIONS – PLUMBING/FIRE PROTECTION
22 0010	BASIC MATERIALS AND METHODS – PLUMBING
22 0030	INSULATION & COVERING – PLUMBING
22 0110	DRAINAGE SYSTEMS – PLUMBING
22 0120	DOMESTIC WATER SYSTEMS – PLUMBING
22 0130	GAS PIPING SYSTEMS – PLUMBING
220140	FIXTURES – PLUMBING
22 0150	EQUIPMENT – PLUMBING
22 0190	TESTING – PLUMBING
22 0191	BALANCING – PLUMBING

DIVISION 23: HVAC

23 0200	GENERAL PROVISIONS – HVAC
23 0230	INSULATION & COVERING – HVAC
23 0600	AIR DISTRIBUTION & ACCESSORIES – HVAC
23 0950	TESTING & BALANCING OF MECHANICAL SYSTEMS

DIVISION 26: ELECTRICAL

26 0000	GENERAL PROVISIONS – ELECTRICAL
26 0055	ELECTRICAL IDENTIFICATION
26 0110	RACEWAYS
26 0120	WIRES AND CABLES
26 0135	ELECTRICAL BOXES & FITTINGS
26 0140	WIRING DEVICES
26 0180	OVERCURRENT PROTECTIVE DEVICES
26 0190	SUPPORTING DEVICES
26 0472	BRANCH CIRCUITS
26 0510	BUILDING LIGHTING

TABLE OF CONTENTS
MPHS Cafeteria Upgrades

DRAWINGS

GENERAL	
G-001	COVER SHEET
G-102	KEY PLAN - FIRST FLOOR
ARCHITECTURAL	
A-011	GENERAL NOTES, SYMBOLS AND ABBREVIATIONS
A-113	FIRST FLOOR CAFETERIA DEMOLITION PLANS - PHASE 1
A-114	FIRST FLOOR CAFETERIA NEW CONSTRUCTION PLANS - PHASE 1
A-221	CAFETERIA INTERIOR SECTIONS AND ELEVATIONS
A-301	CAFETERIA WALL SECTIONS AND DETAILS
A-302	CAFETERIA WALL SECTIONS AND DETAILS
INTERIORS	
I-114	FIRST FLOOR CAFETERIA FINISH PLAN AND FLOOR PATTERN PLAN
PLUMBING	
P-101	FIRST FLOOR CAFETERIA DEMOLITION PLAN PLUMBING - PHASE 1
P-102	FIRST FLOOR CAFETERIA NEW CONSTRUCTION PLAN PLUMBING - PHASE 1
P-103	FIRST FLOOR CAFETERIA NEW CONSTRUCTION PLAN PLUMBING - PHASE 1
MECHANICAL	
M-101	FIRST FLOOR CAFETERIA DEMOLITION PLAN MECHANICAL - PHASE 1
M-102	FIRST FLOOR CAFETERIA NEW CONSTRUCTION PLAN MECHANICAL - PHASE 1
ELECTRICAL	
E-101	FIRST FLOOR CAFETERIA DEMOLITION PLAN ELECTRICAL - PHASE 1
E-102	FIRST FLOOR CAFETERIA NEW CONSTRUCTION PLAN ELECTRICAL - PHASE 1
FOOD SERVICE	FOR REFERENCE ONLY
FS-1.0	PRELIMINARY FOOD SERVICE EQUIPMENT PLAN AND SCHEDULE
FS-1.1	PRELIMINARY FOOD SERVICE ELECTRICAL / PLUMBING PLAN AND SCHEDULE
FS-1.2	PRELIMINARY FOOD SERVICE MECHANICAL PLAN AND SCHEDULE
FS-2.0	PRELIMINARY FOOD SERVICE EXHAUST HOOD DETAILS
FS.KEY	FOODSERVICE EQUIPMENT OVERALL KEY PLAN

SECTION 001150
ADVERTISEMENT FOR BIDS
MOUNT PLEASANT HIGH SCHOOL -CAFETERIA UPGRADE
CONTRACT NO : BSD17012-CAFETERIA_UPGRADES_MPHS

RECEIPT OF BIDS

Sealed bids for Mount Pleasant High School Cafeteria Upgrades, will be received by the Brandywine School District in the Cafeteria at Mount Pleasant High School, 5201 Washington St Extension Wilmington DE 19809 until 11:00AM local time on Thursday, April 20, 2017, at which time they will be publicly opened and read aloud. Bidder bears the risk of late delivery. Any bids received after the stated time will be returned unopened.

Sealed bids shall be addressed to [Carol Riddle] . The outer envelope should clearly indicate: "SEALED BID - DO NOT OPEN."

SCOPE AND SCHEDULE

Project involves upgrades to the Cafeteria Servery area and equipment

Attention is called to construction schedule as detailed in the Bid Documents.

MANDATORY PRE-BID

A MANDATORY Pre-Bid Meeting will be held at 2:00 PM on Thursday March 23, 2017, in Cafeteria at the Mount Pleasant High School for the purpose of establishing the listing of subcontractors and to answer questions. ATTENDANCE OF THIS MEETING IS A PREREQUISITE FOR BIDDING ON THIS CONTRACT. Representatives of each party to any Joint Venture must attend this meeting.

BID DOCUMENTS

Contract documents may viewed and downloaded at ABHA's FTP site on or after March 20 2017. Bidders may request username and password by contacting the office of ABHA Architects at 302-658-6426 and providing company name, contact name, email address, phone number and mailing address. Bid Documents may be examined at the offices of ABHA Architects, 1621 N. Lincoln St Wilmington DE 19806, or at the State of Delaware Online Bid Solicitation Directory at http://bids.delaware.gov. Email questions to David Barisa at dbarisa@abha.com

BID SECURITY

Each bid must be accompanied by a bid security equivalent to ten percent (10%) of the bid amount and all additive alternates. The successful bidder must post a performance bond and payment bond in a sum equal to 100 percent (100%) of the contract price upon execution of the contract.

The Owner reserves the right to reject any or all bids and to waive any informalities therein. The Owner may extend the time and place for the opening of the bids from that described in the advertisement, with not less than two calendar days notice by facsimile machine or other electronic means to those bidders who have requested access to the ABHA FTP site.

Pursuant to the Office of Management and Budget (OMB) "4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects" requires that Contractors and Subcontractors who work on Large Public Works Contracts funded all or in part with public funds implement a Mandatory Drug Testing Program. The regulation can be downloaded from the following website:

http://regulations.delaware.gov/AdminCode/title19/4000/4100/index.shtml#TopOfPage <http://regulations.delaware.gov/AdminCode/title19/4000/4100/index.shtml>

END OF SECTION

SECTION 002110
INSTRUCTIONS TO BIDDERS

TABLE OF ARTICLES

1.01 ARTICLE 1:GENERAL

A. DEFINITIONS

1. Whenever the following terms are used, their intent and meaning shall be interpreted as follows:

STATE: The State of Delaware.

AGENCY: Contracting State Agency as noted on cover sheet.

DESIGNATED OFFICIAL: The agent authorized to act for the Agency.

ARCHITECT:

ABHA Architects
1621 N Lincoln St
Wilmington, DE 19806

BIDDING DOCUMENTS: Bidding Documents include the Bidding Requirements and the proposed Contract Documents. The Bidding Requirements consist of the Advertisement for Bid, Invitation to Bid, Instructions to Bidders, Supplementary Instructions to Bidders (if any), General Conditions, Supplementary General Conditions, General Requirements, Special Provisions (if any), the Bid Form (including the Non-collusion Statement), and other sample bidding and contract forms. The proposed Contract Documents consist of the form of Agreement between the Owner and Contractor, as well as the Drawings, Specifications (Project Manual) and all Addenda issued prior to execution of the Contract.

CONTRACT DOCUMENTS: The Contract Documents consist of the, Instructions to Bidders, Supplementary Instructions to Bidders (if any), General Conditions, Supplementary General Conditions, General Requirements, Special Provisions (if any), the form of agreement between the Owner and the Contractor, Drawings (if any), Specifications (Project Manual), and all addenda.

AGREEMENT: The form of the Agreement shall be AIA Document A101, Standard Form of Agreement between Owner and Contractor where the basis of payment is a STIPULATED SUM. In the case of conflict between the instructions contained therein and the General Requirements herein, these General Requirements shall prevail.

GENERAL REQUIREMENTS (or CONDITIONS): General Requirements (or conditions) are instructions pertaining to the Bidding Documents and to contracts in general. They contain, in summary, requirements of laws of the State; policies of the Agency and instructions to bidders.

SPECIAL PROVISIONS: Special Provisions are specific conditions or requirements peculiar to the bidding documents and to the contract under consideration and are supplemental to the General Requirements. Should the Special Provisions conflict with the General Requirements, the Special Provisions shall prevail.

ADDENDA: Written or graphic instruments issued by the Owner/Architect prior to the execution of the contract which modify or interpret the Bidding Documents by additions, deletions, clarifications or corrections.

BIDDER OR VENDOR: A person or entity who formally submits a Bid for the material or Work contemplated, acting directly or through a duly authorized representative who meets the requirements set forth in the Bidding Documents.
SUB-BIDDER: A person or entity who submits a Bid to a Bidder for materials or labor, or both for a portion of the Work.
BID: A complete and properly executed proposal to do the Work for the sums stipulated therein, submitted in accordance with the Bidding Documents.
BASE BID: The sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents as the base, to which Work may be added or from which Work may be deleted for sums stated in Alternate Bids (if any are required to be stated in the bid).
ALTERNATE BID (or ALTERNATE): An amount stated in the Bid, where applicable, to be added to or deducted from the amount of the Base Bid if the corresponding change in the Work, as described in the Bidding Documents is accepted.
UNIT PRICE: An amount stated in the Bid, where applicable, as a price per unit of measurement for materials, equipment or services or a portion of the Work as described in the Bidding Documents.
SURETY: The corporate body which is bound with and for the Contract, or which is liable, and which engages to be responsible for the Contractor's payments of all debts pertaining to and for his acceptable performance of the Work for which he has contracted.
BIDDER'S DEPOSIT: The security designated in the Bid to be furnished by the Bidder as a guaranty of good faith to enter into a contract with the Agency if the Work to be performed or the material or equipment to be furnished is awarded to him.
CONTRACT: The written agreement covering the furnishing and delivery of material or work to be performed.
CONTRACTOR: Any individual, firm or corporation with whom a contract is made by the Agency.
SUBCONTRACTOR: An individual, partnership or corporation which has a direct contract with a contractor to furnish labor and materials at the job site, or to perform construction labor and furnish material in connection with such labor at the job site.
CONTRACT BOND: The approved form of security furnished by the contractor and his surety as a guaranty of good faith on the part of the contractor to execute the work in accordance with the terms of the contract.

1.02 ARTICLE 2:BIDDER'S REPRESENTATIONS

A. PRE-BID MEETING

1. A pre-bid meeting for this project will be held at the time and place designated. Attendance at this meeting is a pre-requisite for submitting a Bid, unless this requirement is specifically waived elsewhere in the Bid Documents.
2. By submitting a Bid, the Bidder represents that:
3. The Bidder has read and understands the Bidding Documents and that the Bid is made in accordance therewith.
4. The Bidder has visited the site, become familiar with existing conditions under which the Work is to be performed, and has correlated the Bidder’s his personal observations with the requirements of the proposed Contract Documents.

5. The Bid is based upon the materials, equipment, and systems required by the Bidding Documents without exception.

B. JOINT VENTURE REQUIREMENTS
1. For Public Works Contracts, each Joint Venturer shall be qualified and capable to complete the Work with their own forces.
2. Included with the Bid submission, and as a requirement to bid, a copy of the executed Joint Venture Agreement shall be submitted and signed by all Joint Venturers involved.
3. All required Bid Bonds, Performance Bonds, Material and Labor Payment Bonds must be executed by both Joint Venturers and be placed in both of their names.
4. All required insurance certificates shall name both Joint Venturers.
5. Both Joint Venturers shall sign the Bid Form and shall submit a copy of a valid Delaware Business License with their Bid.
6. Both Joint Venturers shall include their Federal E.I. Number with the Bid.
7. In the event of a mandatory Pre-bid Meeting, each Joint Venturer shall have a representative in attendance.
8. Due to exceptional circumstances and for good cause shown, one or more of these provisions may be waived at the discretion of the State.

C. ASSIGNMENT OF ANTITRUST CLAIMS
1. As consideration for the award and execution by the Owner of this contract, the Contractor hereby grants, conveys, sells, assigns and transfers to the State of Delaware all of its right, title and interests in and to all known or unknown causes of action it presently has or may now or hereafter acquire under the antitrust laws of the United States and the State of Delaware, relating to the particular goods or services purchased or acquired by the Owner pursuant to this contract.

1.03 ARTICLE 3:BIDDING DOCUMENTS

A. COPIES OF BID DOCUMENTS
1. Refer to Advertisement (or Invitation) for Bids for information concerning locations where Bidding Documents may be seen or obtained and under what conditions.
2. Bidders shall use complete sets of Bidding Documents for preparation of Bids. The issuing Agency nor the Architect assumes no responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.
3. Any errors, inconsistencies or omissions discovered shall be reported to the Architect immediately.
4. The Agency and Architect may make copies of the Bidding Documents available on the above terms for the purpose of obtaining Bids on the Work. No license or grant of use is conferred by issuance of copies of the Bidding Documents.

B. INTERPRETATION OR CORRECTION OF BIDDING DOCUMENTS
1. The Bidder shall carefully study and compare the Bidding Documents with each other, and with other work being bid concurrently or presently under construction to the extent that it relates to the Work for which the Bid is submitted, shall examine the site and local conditions, and shall report any errors, inconsistencies, or ambiguities discovered to the Architect.
2. Bidders or Sub-bidders requiring clarification or interpretation of the Bidding Documents shall make a written request to the Architect at least seven days prior to the date for receipt of Bids. Interpretations, corrections and changes to the Bidding

Documents will be made by written Addendum. Interpretations, corrections, or changes to the Bidding Documents made in any other manner shall not be binding.

3. The apparent silence of the specifications as to any detail, or the apparent omission from it of detailed description concerning any point, shall be regarded as meaning that only the best commercial practice is to prevail and only material and workmanship of the first quality are to be used. Proof of specification compliance will be the responsibility of the Bidder.
4. Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for all permits, labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for the proper execution and completion of the Work.
5. The Owner will bear the costs for all impact and user fees associated with the project.

C. SUBSTITUTIONS

1. The materials, products and equipment described in the Bidding Documents establish a standard of quality, required function, dimension, and appearance to be met by any proposed substitution. The specification of a particular manufacturer or model number is not intended to be proprietary in any way. Substitutions of products for those named will be considered, providing that the Bidder certifies that the function, quality, and performance characteristics of the material offered is equal or superior to that specified. It shall be the Bidder's responsibility to assure that the proposed substitution will not affect the intent of the design, and to make any installation modifications required to accommodate the substitution.
2. Requests for substitutions shall be made in writing to the Architect at least ten days prior to the date of the Bid Opening. Such requests shall include a complete description of the proposed substitution, drawings, performance and test data, explanation of required installation modifications due the substitution, and any other information necessary for an evaluation. The burden of proof of the merit of the proposed substitution is upon the proposer. The Architect’s decision of approval or disapproval shall be final. The Architect is to notify Owner prior to any approvals.
3. If the Architect approves a substitution prior to the receipt of Bids, such approval shall be set forth in an Addendum. Approvals made in any other manner shall not be binding.
4. The Architect shall have no obligation to consider any substitutions after the Contract award.
5. Bidders shall conform to requirements in Section 01600 MATERIAL AND EQUIPMENT.

D. ADDENDA

1. Addenda will be mailed or delivered to all who are known by the Architect to have received a complete set of the Bidding Documents.
2. Copies of Addenda will be made available for inspection wherever Bidding Documents are on file for that purpose.
3. No Addenda will be issued later than 4 days prior to the date for receipt of Bids except an Addendum withdrawing the request for Bids or one which extends the time or changes the location for the opening of bids.
4. Each bidder shall ascertain prior to submitting his Bid that they have received all Addenda issued, and shall acknowledge their receipt in their Bid in the appropriate

space. Not acknowledging an issued Addenda could be grounds for determining a bid to be non-responsive.

1.04 ARTICLE 4:BIDDING PROCEDURES

A. PREPARATION OF BIDS

1. Submit the bids on the Bid Forms included with the Bidding Documents.
2. Submit the original Bid Form for each bid. Bid Forms may be removed from the project manual for this purpose.
3. Execute all blanks on the Bid Form in a non-erasable medium (typewriter or manually in ink).
4. Where so indicated by the makeup on the Bid Form, express sums in both words and figures, in case of discrepancy between the two, the written amount shall govern.
5. Interlineations, alterations or erasures must be initialed by the signer of the Bid.
6. BID ALL REQUESTED ALTERNATES AND UNIT PRICES, IF ANY. If there is no change in the Base Bid for an Alternate, enter “No Change”. The Contractor is responsible for verifying that they have received all addenda issued during the bidding period. Work required by Addenda shall automatically become part of the Contract.
7. Make no additional stipulations on the Bid Form and do not qualify the Bid in any other manner.
8. Each copy of the Bid shall include the legal name of the Bidder and a statement whether the Bidder is a sole proprietor, a partnership, a corporation, or any legal entity, and each copy shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid by a corporation shall further give the state of incorporation and have the corporate seal affixed. A Bid submitted by an agent shall have a current Power of Attorney attached, certifying agent's authority to bind the Bidder.
9. Bidder shall complete the Non-Collusion Statement form included with the Bid Forms and include it with their Bid.
10. In the construction of all Public Works projects for the State of Delaware or any agency thereof, preference in employment of laborers, workers or mechanics shall be given to bona fide legal citizens of the State who have established citizenship by residence of at least 90 days in the State.
11. Each bidder shall include in their bid a copy of a valid Delaware Business License.
12. Each bidder shall include signed Affidavit(s) for the Bidder and each listed Subcontractor certifying compliance with OMB Regulation 4104- “Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on “Large Public Works Projects.” “Large Public Works” is based upon the current threshold required for bidding Public Works as set by the Purchasing and Contracting Advisory Council.

B. BID SECURITY

1. All bids shall be accompanied by a deposit of either a good and sufficient bond to the agency for the benefit of the agency, with corporate surety authorized to do business in this State, the form of the bond and the surety to be approved by the agency, or a security of the bidder assigned to the agency, for a sum equal to at least 10% of the bid plus all add alternates, or in lieu of the bid bond a security deposit in the form of

a certified check, bank treasurer's check, cashier's check, money order, or other prior approved secured deposit assigned to the State. The bid bond need not be for a specific sum, but may be stated to be for a sum equal to 10% of the bid plus all add alternates to which it relates and not to exceed a certain stated sum, if said sum is equal to at least 10% of the bid. The Bid Bond form used shall be the standard OMB form (attached).

2. The Agency has the right to retain the bid security of Bidders to whom an award is being considered until either a formal contract has been executed and bonds have been furnished or the specified time has elapsed so the Bids may be withdrawn or all Bids have been rejected.
3. In the event of any successful Bidder refusing or neglecting to execute a formal contract and bond within 20 days of the awarding of the contract, the bid bond or security deposited by the successful bidder shall be forfeited.

C. SUBCONTRACTOR LIST

1. As required by Delaware Code, Title 29, section 6962(d)(10)b, each Bidder shall submit with their Bid a completed List of Sub-Contractors included with the Bid Form. NAME ONLY ONE SUBCONTRACTOR FOR EACH TRADE. A Bid will be considered non-responsive unless the completed list is included.
2. Provide the Name and Address for each listed subcontractor. Addresses by City, Town or Locality, plus State, will be acceptable.
3. It is the responsibility of the Contractor to ensure that their Subcontractors are in compliance with the provisions of this law. Also, if a Contractor elects to list themselves as a Subcontractor for any category, they must specifically name themselves on the Bid Form and be able to document their capability to act as Subcontractor in that category in accordance with this law.

D. EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS

1. During the performance of this contract, the contractor agrees as follows:
   a. The Contractor will not discriminate against any employee or applicant for employment because of race, creed, sex, color, sexual orientation, gender identity or national origin. The Contractor will take affirmative action to ensure the applicants are employed, and that employees are treated during employment, without regard to their race, creed, sex, color, sexual orientation, gender identity or national origin. Such action shall include, but not be limited to, the following: Employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.
   b. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, sex, color, sexual orientation, gender identity or national origin.

E. PREVAILING WAGE REQUIREMENT

1. Wage Provisions: For renovation and new construction projects whose costs exceed the thresholds contained in Delaware Code, Title 29, Section 6960, the minimum

wage rates for various classes of laborers and mechanics shall be as determined by the Department of Labor, Division of Industrial Affairs of the State of Delaware

2. The employer shall pay all mechanics and labors employed directly upon the site of work, unconditionally and not less often than once a week and without subsequent deduction or rebate on any account, the full amounts accrued at time of payment, computed at wage rates not less than those stated in the specifications, regardless of any contractual relationship which may be alleged to exist between the employer and such laborers and mechanics.
3. The scale of the wages to be paid shall be posted by the employer in a prominent and easily accessible place at the site of the work.
4. Every contract based upon these specifications shall contain a stipulation that sworn payroll information, as required by the Department of Labor, be furnished weekly. The Department of Labor shall keep and maintain the sworn payroll information for a period of 6 months from the last day of the work week covered by the payroll.
5. Wage Rates applicable to this project are attached after the end of this section.

F. SUBMISSION OF BIDS

1. Enclose the Bid, the Bid Security, and any other documents required to be submitted with the Bid in a sealed opaque envelope. Address the envelope to the party receiving the Bids. Identify with the project name, project number, and the Bidder's name and address. If the Bid is sent by mail, enclose the sealed envelope in a separate mailing envelope with the notation "BID ENCLOSED" on the face thereof. The State is not responsible for the opening of bids prior to bid opening date and time that are not properly marked.
2. Deposit Bids at the designated location prior to the time and date for receipt of bids indicated in the Advertisement for Bids. Bids received after the time and date for receipt of bids will be marked “LATE BID” and returned.
3. Bidder assumes full responsibility for timely delivery at location designated for receipt of bids.
4. Oral, telephonic or telegraphic bids are invalid and will not receive consideration.
5. Withdrawn Bids may be resubmitted up to the date and time designated for the receipt of Bids, provided that they are then fully in compliance with these Instructions to Bidders.

G. MODIFICATION OR WITHDRAW OF BIDS

1. Prior to the closing date for receipt of Bids, a Bidder may withdraw a Bid by personal request and by showing proper identification to the Architect. A request for withdraw by letter or fax, if the Architect is notified in writing prior to receipt of fax, is acceptable. A fax directing a modification in the bid price will render the Bid informal, causing it to be ineligible for consideration of award. Telephone directives for modification of the bid price shall not be permitted and will have no bearing on the submitted proposal in any manner.
2. Bidders submitting Bids that are late shall be notified as soon as practicable and the bid shall be returned.
3. A Bid may not be modified, withdrawn or canceled by the Bidder during a thirty (30) day period following the time and date designated for the receipt and opening of Bids, and Bidder so agrees in submitting their Bid. Bids shall be binding for 30 days after the date of the Bid opening.

1.05 ARTICLE 5:CONSIDERATION OF BIDS

A. OPENING/REJECTION OF BIDS
   1. Unless otherwise stated, Bids received on time will be publicly opened and will be read aloud. An abstract of the Bids will be made available to Bidders.
   2. The Agency shall have the right to reject any and all Bids. A Bid not accompanied by a required Bid Security or by other data required by the Bidding Documents, or a Bid which is in any way incomplete or irregular is subject to rejection.
   3. If the Bids are rejected, it will be done within thirty (30) calendar day of the Bid opening.

B. COMPARISON OF BIDS
   1. After the Bids have been opened and read, the bid prices will be compared and the result of such comparisons will be made available to the public. Comparisons of the Bids may be based on the Base Bid plus desired Alternates. The Agency shall have the right to accept Alternates in any order or combination.
   2. The Agency reserves the right to waive technicalities, to reject any or all Bids, or any portion thereof, to advertise for new Bids, to proceed to do the Work otherwise, or to abandon the Work, if in the judgment of the Agency or its agent(s), it is in the best interest of the State.
   3. An increase or decrease in the quantity for any item is not sufficient grounds for an increase or decrease in the Unit Price.
   4. The prices quoted are to be those for which the material will be furnished F.O.B. Job Site and include all charges that may be imposed during the period of the Contract.
   5. No qualifying letter or statements in or attached to the Bid, or separate discounts will be considered in determining the low Bid except as may be otherwise herein noted. Cash or separate discounts should be computed and incorporated into Unit Bid Price(s).

C. DISQUALIFICATION OF BIDDERS
   1. An agency shall determine that each Bidder on any Public Works Contract is responsible before awarding the Contract. Factors to be considered in determining the responsibility of a Bidder include:
      a. The Bidder's financial, physical, personnel or other resources including Subcontracts;
      b. The Bidder's record of performance on past public or private construction projects, including, but not limited to, defaults and/or final adjudication or admission of violations of the Prevailing Wage Laws in Delaware or any other state;
      c. The Bidder's written safety plan;
      d. Whether the Bidder is qualified legally to contract with the State;
      e. Whether the Bidder supplied all necessary information concerning its responsibility; and,
      f. Any other specific criteria for a particular procurement, which an agency may establish; provided however, that, the criteria be set forth in the Invitation to Bid and is otherwise in conformity with State and/or Federal law.
   2. If an agency determines that a Bidder is nonresponsive and/or nonresponsible, the determination shall be in writing and set forth the basis for the determination. A

copy of the determination shall be sent to the affected Bidder within five (5) working days of said determination.

3. In addition, any one or more of the following causes may be considered as sufficient for the disqualification of a Bidder and the rejection of their Bid or Bids.
   a. More than one Bid for the same Contract from an individual, firm or corporation under the same or different names.
   b. Evidence of collusion among Bidders.
   c. Unsatisfactory performance record as evidenced by past experience.
   d. If the Unit Prices are obviously unbalanced either in excess or below reasonable cost analysis values.
   e. If there are any unauthorized additions, interlineation, conditional or alternate bids or irregularities of any kind which may tend to make the Bid incomplete, indefinite or ambiguous as to its meaning.
   f. If the Bid is not accompanied by the required Bid Security and other data required by the Bidding Documents.
   g. If any exceptions or qualifications of the Bid are noted on the Bid Form.

D. ACCEPTANCE OF BID AND AWARD OF CONTRACT

1. A formal Contract shall be executed with the successful Bidder within twenty (20) calendar days after the award of the Contract.
2. Per Section 6962(d)(13) a., Title 29, Delaware Code, "The contracting agency shall award any public works contract within thirty (30) days of the bid opening to the lowest responsive and responsible Bidder, unless the Agency elects to award on the basis of best value, in which case the election to award on the basis of best value shall be stated in the Invitation To Bid."
3. Each Bid on any Public Works Contract must be deemed responsive by the Agency to be considered for award. A responsive Bid shall conform in all material respects to the requirements and criteria set forth in the Contract Documents and specifications.
4. The Agency shall have the right to accept Alternates in any order or combination, and to determine the low Bidder on the basis of the sum of the Base Bid, plus accepted Alternates.
5. The successful Bidder shall execute a formal contract, submit the required Insurance Certificate, and furnish good and sufficient bonds, unless specifically waived in the General Requirements, in accordance with the General Requirement, within twenty (20) days of official notice of contract award. The successful Bidder shall provide two business days prior to contract execution, copies of the Employee Drug Testing Program for the Bidder and all listed Subcontractors. Bonds shall be for the benefit of the Agency with surety in the amount of 100% of the total contract award. Said Bonds shall be conditioned upon the faithful performance of the contract. Bonds shall remain in affect for period of one year after the date of substantial completion.
6. If the successful Bidder fails to execute the required Contract, Bond, and all required information as aforesaid, within twenty (20) calendar days after the date of official Notice of the Award of the Contract, their Bid guaranty shall immediately be taken and become the property of the State for the benefit of the Agency as liquidated damages, and not as a forfeiture or as a penalty. Award will then be made to the next lowest qualified Bidder of the Work or readvertised, as the Agency may decide.

7. Each bidder shall supply with its bid its taxpayer identification number (i.e., federal employer identification number or social security number) and a copy of its Delaware business license, and should the vendor be awarded a contract, such vendor shall provide to the agency the taxpayer identification license numbers of such subcontractors. Such numbers shall be provided on the later of the date on which such subcontractor is required to be identified or the time the contract is executed. The successful Bidder shall provide to the agency to which it is contracting, within 30 days of entering into such public works contract, copies of all Delaware Business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the Bidder entered the public works contract the Delaware Business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.
8. The Bid Security shall be returned to the successful Bidder upon the execution of the formal contract. The Bid Securities of unsuccessful bidders shall be returned within thirty (30) calendar days after the opening of the Bids.

1.06 ARTICLE 6: POST-BID INFORMATION

A. CONTRACTOR'S QUALIFICATION STATEMENT
1. Bidders to whom award of a Contract is under consideration shall, if requested by the Agency, submit a properly executed AIA Document A305, Contractor's Qualification Statement, unless such a statement has been previously required and submitted.

B. BUSINESS DESIGNATION FORM
1. Successful bidder shall be required to accurately complete an Office of Management and Budget Business Designation Form for Subcontractors.

1.07 ARTICLE 7: PERFORMANCE BOND AND PAYMENT BOND

A. BOND REQUIREMENTS
1. The cost of furnishing the required Bonds, that are stipulated in the Bidding Documents, shall be included in the Bid.
2. If the Bidder is required by the Agency to secure a bond from other than the Bidder's usual sources, changes in cost will be adjusted as provide in the Contract Documents.
3. The Performance and Payment Bond forms used shall be the standard OMB forms (attached).

B. TIME OF DELIVERY AND FORM OF BONDS
1. The bonds shall be dated on or after the date of the Contract.
2. The Bidder shall require the attorney-in-fact who executes the required bonds on behalf of the surety to affix a certified and current copy of the power of attorney.

1.08 ARTICLE 8: FORM OF AGREEMENT BETWEEN AGENCY AND CONTRACTOR

A. Unless otherwise required in the Bidding Documents, the Agreement for the Work will be written on AIA Document A101, Standard Form of Agreement Between Owner and Contractor Where the Basis of Payment is a Stipulated Sum.

END OF INSTRUCTIONS TO BIDDERS

STATE OF DELAWARE PREVAILING WAGE RATES

STATE OF DELAWARE
DEPARTMENT OF LABOR
DIVISION OF INDUSTRIAL AFFAIRS
OFFICE OF LABOR LAW ENFORCEMENT
PHONE: (302) 451-3423

Mailing Address:
225 CORPORATE BOULEVARD
SUITE 104
NEWARK, DE 19702

Located at:
225 CORPORATE BOULEVARD
SUITE 104
NEWARK, DE 19702

PREVAILING WAGES FOR **BUILDING CONSTRUCTION** EFFECTIVE MARCH 15, 2016

CLASSIFICATION	NEW CASTLE	KENT	SUSSEX
ASBESTOS WORKERS	22.58	27.81	40.47
BOILERMAKERS	67.59	34.29	50.41
BRICKLAYERS	50.49	50.49	50.49
CARPENTERS	52.81	52.81	41.97
CEMENT FINISHERS	70.82	30.05	21.89
ELECTRICAL LINE WORKERS	44.90	38.50	29.36
ELECTRICIANS	65.10	65.10	65.10
ELEVATOR CONSTRUCTORS	83.06	63.69	31.54
GLAZIERS	69.30	69.30	55.95
INSULATORS	54.38	54.38	54.38
IRON WORKERS	61.20	61.20	61.20
LABORERS	43.60	43.60	43.60
MILLWRIGHTS	66.83	66.83	53.40
PAINTERS	46.72	46.72	46.72
PILEDRIVERS	72.97	38.86	31.43
PLASTERERS	29.47	29.47	21.84
PLUMBERS/PIPEFITTERS/STEAMFITTERS	65.95	50.85	55.34
POWER EQUIPMENT OPERATORS	61.36	61.36	43.28
ROOFERS-COMPOSITION	23.49	23.40	20.87
ROOFERS-SHINGLE/SLATE/TILE	18.16	18.07	16.98
SHEET METAL WORKERS	65.14	65.14	65.14
SOFT FLOOR LAYERS	49.77	49.77	49.77
SPRINKLER FITTERS	54.57	54.57	54.57
TERRAZZO/MARBLE/TILE FNRS	55.72	55.72	46.92
TERRAZZO/MARBLE/TILE STRS	63.98	63.98	54.33
TRUCK DRIVERS	28.39	27.10	20.68

CERTIFIED: 2/27/17 BY: _____
ADMINISTRATOR, OFFICE OF LABOR LAW ENFORCEMENT

NOTE: THESE RATES ARE PROMULGATED AND ENFORCED PURSUANT TO THE PREVAILING WAGE REGULATIONS ADOPTED BY THE DEPARTMENT OF LABOR ON APRIL 3, 1992.

CLASSIFICATIONS OF WORKERS ARE DETERMINED BY THE DEPARTMENT OF LABOR. FOR ASSISTANCE IN CLASSIFYING WORKERS, OR FOR A COPY OF THE REGULATIONS OR CLASSIFICATIONS, PHONE (302) 451-3423.

NON-REGISTERED APPRENTICES MUST BE PAID THE MECHANIC'S RATE.

PROJECT: Mount Pleasant High School Cafeteria, New Castle County, DE,

SECTION 004113

BID FORM

FOR BIDS DUE: _____

TO: BRANDYWINE SCHOOL DISTRICT
1311 BRANDYWINE BLVD.
WILMINGTON, DE. 19809

FOR: MOUNT PLEASANT HIGH SCHOOL
5201 WASHINGTON ST EXTENSION
WILMINGTON, DE. 19809

FOR CONTRACT: BSD17012-CAFETERIA_UPGRADES_MPHS

NAME OF BIDDER: _____

DELAWARE BUSINESS LICENSE NO.: _____

(A copy of Bidder's Delaware Business License must be attached to this form.)

TAXPAYER ID NO.: _____

(OTHER LICENSE NOS.): _____

PHONE NO.: ( ) _____ FAX NO.: ( )_____

EMAIL ADDRESS: _____

The undersigned, representing that he has read and understands the Bidding Documents, including the complete Project Manual and the Drawings as listed in the Table of Contents, all dated _____, 2017, and that this bid is made in accordance therewith, that he has visited the site and has familiarized himself with the local conditions under which the Work is to be performed, and that his bid is based upon the materials, systems and equipment described in the Bidding Documents without exception, hereby proposes and agrees to provide all labor, materials, plant, equipment, supplies, transport and other facilities required to execute the work described by the aforesaid documents for the lump sum itemized below:

BASE BID:

_____

(expressed in words)

($ _____)

(expressed in figures)

BID FORM

SIGNATURE FORM

I / We acknowledge Addendas Numbered _____ and the price(s) submitted include any cost / schedule impact they may have.

This bid shall remain valid and cannot be withdrawn for 30 days from the date of opening of bids (60 days for School Districts and Department of Education), and the undersigned shall abide by the Bid Security forfeiture provisions. Bid Security is attached to this Bid.

The Owner shall have the right to reject any or all bids, and to waive any informality or irregularity in any bid received.

This bid is based upon work being accomplished by the Sub-Contractors named on the list attached to this bid.

Should I/We be awarded this contract, I/We pledge to achieve substantial completion of all the work within _____ calendar days of the Notice to Proceed.

The undersigned represents and warrants that he has complied and shall comply with all requirements of local, state, and national laws; that no legal requirement has been or shall be violated in making or accepting this bid, in awarding the contract to him or in the prosecution of the work required; that the bid is legal and firm; that he has not, directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken action in restraint of free competitive bidding.

Upon receipt of written notice of the acceptance of this Bid, the Bidder shall, within twenty (20) calendar days, execute the agreement in the required form and deliver the Contract Bonds, and Insurance Certificates, required by the Contract Documents.

I am / We are an Individual / a Partnership / a Corporation

By: _____ Trading as: _____

(Individual's / General Partner's / Corporate Name)

_____

(State of Corporation)

Business Address: _____

_____

Witness: _____ By: _____

(Authorized Signature)

(SEAL) _____

(Title)

Date: _____

Attachments:

Sub-Contractor List.
Non-Collusion Statement.
Affidavit(s) of Employee Drug Testing Program
Bid Security.

BID FORM

SUBCONTRACTOR LIST

In accordance with Title 29, Chapter 6962 (d)(10)b Delaware Code, the following sub-contractor listing must accompany the bid submittal. The name and address of the sub-contractor must be listed for each category where the bidder intends to use a sub-contractor to perform that category of work. In order to provide full disclosure and acceptance of the bid by the Owner, it is required that bidders list themselves as being the sub-contractor for all categories where he/she is qualified and intends to perform such work. This form must be filled out completely with no additions or deletions. Note that all subcontractors listed below must have a signed Affidavit of Employee Drug Testing Program included with this bid.

SUBCONTRACTOR CATEGORY	SUBCONTRACTOR	ADDRESS (City & State)	SUBCONTRACTOR Taxpayer ID # or DE Business License #
Mechanical			
Electrical			
Plumbing			

BID FORM -BID BOND
BID BOND

TO ACCOMPANY PROPOSAL
(Not necessary if security is used)

KNOW ALL MEN BY THESE PRESENTS That: _____ _____of _____ in the County of _____ _____and State of _____as **Principal**, and _____ _____ of _____ in the County of _____ and State of _____ as **Surety**, legally authorized to do business in the State of Delaware ("**State**"), are held and firmly unto the **State** in the sum of _____ _____ Dollars ($_____), or _____ percent not to exceed _____ _____ Dollars ($_____) of amount of bid on Contract No. _____, to be paid to the **State** for the use and benefit of _____ (***insert State agency name***) for which payment well and truly to be made, we do bind ourselves, our and each of our heirs, executors, administrators, and successors, jointly and severally for and in the whole firmly by these presents.

NOW THE CONDITION OF THIS OBLIGATION IS SUCH That if the above bonded **Principal** who has submitted to the _____ (***insert State agency name***) a certain proposal to enter into this contract for the furnishing of certain material and/or services within the **State**, shall be awarded this Contract, and if said **Principal** shall well and truly enter into and execute this Contract as may be required by the terms of this Contract and approved by the _____ _____ (***insert State agency name***) this Contract to be entered into within twenty days after the date of official notice of the award thereof in accordance with the terms of said proposal, then this obligation shall be void or else to be and remain in full force and virtue.

Sealed with _____ seal and dated this _____day of _____ in the year of our Lord two thousand and _____ (20___).

SEALED, AND DELIVERED IN THE
Presence of

_____
Name of Bidder (Organization)

Corporate Seal

By: _____
Authorized Signature

Attest _____

_____
Title

_____
Name of Surety

Witness:_____

By: _____

_____
Title

BID FORM

NON-COLLUSION STATEMENT

This is to certify that the undersigned bidder has neither directly nor indirectly, entered into any agreement, participated in any collusion or otherwise taken any action in restraint of free competitive bidding in connection with this proposal submitted this date.

All the terms and conditions of this Contract have been thoroughly examined and are understood.

NAME OF BIDDER: _____

AUTHORIZED REPRESENTATIVE
(TYPED): _____

AUTHORIZED REPRESENTATIVE
(SIGNATURE): _____

TITLE: _____

ADDRESS OF BIDDER: _____
_____
_____

PHONE NUMBER: _____

Sworn to and Subscribed before me this _____day of _____, 20__

My Commission expires :_____ NOTARY PUBLIC _____

THIS PAGE MUST BE SIGNED AND NOTARIZED FOR YOUR BID TO BE CONSIDERED.

BID FORM

EMPLOYEE DRUG TESTING PROGRAM

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects requires that Contractors and Subcontractors implement a program of mandatory drug testing for Employees who work on Large Public Works Contracts funded all or in part with public funds.

We hereby certify that we have in place or will implement during the entire term of the contract a Mandatory Drug Testing Program for our employees on the jobsite that complies with this regulation:

CONTRACTOR/SUBCONTRACTOR
NAME: _____

CONTRACTOR/SUBCONTRACTOR
ADDRESS: _____
_____
_____

AUTHORIZED REPRESENTATIVE
(TYPED): _____

AUTHORIZED REPRESENTATIVE
(SIGNATURE): _____

Sworn to and Subscribed before me this _____day of _____, 20__

My Commission expires :_____ NOTARY PUBLIC _____

END OF DOCUMENT

END OF SECTION

SECTION 005000
CONTRACTING FORMS AND SUPPLEMENTS

PART 1 GENERAL

1.01 LICENSES

A. Contractor is responsible for obtaining a valid license to use all copyrighted documents specified but not included in the Project Manual.

1.02 AGREEMENT AND CONDITIONS OF THE CONTRACT

A. See Section 007200 - General Conditions for the General Conditions.

B. See Section 007300 - Supplementary Conditions for the Supplementary Conditions.

C. The Agreement form is AIA A101.

D. The General Conditions are based on AIA A201.

1.03 FORMS

A. Use the following forms for the specified purposes unless otherwise indicated elsewhere in the Contract Documents.

B. Bond Forms:
   1. Performance and Payment Bond Form: Conform to those approved by the State of Delaware Office of Management and Budget.

C. Post-Award Certificates and Other Forms:
   1. Application for Payment Forms: AIA G702 with AIA G703 (for Contractors).

D. Clarification and Modification Forms:
   1. Change Order Form: AIA G701.

E. Closeout Forms:
   1. Certificate of Substantial Completion Form: AIA G704.
   2. Affidavit of Payment of Debts and Claims Form: AIA G706.
   3. Affidavit of Release of Liens Form: AIA G706a.
   4. Consent of Surety to Final Payment Form: AIA G707.

1.04 REFERENCE STANDARDS

A. AIA A101 - Standard Form of Agreement Between Owner and Contractor where the basis of Payment is a Stipulated Sum; 2007.

B. AIA A201 - General Conditions of the Contract for Construction; 2007.

C. AIA G701 - Change Order; 2001.

D. AIA G702 - Application and Certificate for Payment; 1992.

E. AIA G703 - Continuation Sheet; 1992.

F. AIA G704 - Certificate of Substantial Completion; 2000.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 007310
SUPPLEMENTARY GENERAL CONDITIONS A201-2007

THE FOLLOWING SUPPLEMENTS MODIFY THE AIA DOCUMENT A201-2007, GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION. WHERE A PORTION OF THE GENERAL CONDITIONS IS MODIFIED OR DELETED BY THE SUPPLEMENTARY CONDITIONS, THE UNALTERED PORTIONS OF THE GENERAL CONDITIONS SHALL REMAIN IN EFFECT.

ARTICLE 1: GENERAL PROVISIONS

1.1 BASIC DEFINITIONS

1.1.1 THE CONTRACT DOCUMENTS

Delete the last sentence in its entirety and replace with the following:

"The Contract Documents also include Advertisement for Bid, Instructions to Bidder, sample forms, the Bid Form, the Contractor's completed Bid and the Award Letter."

Add the following Paragraph:

1.1.2 In the event of conflict or discrepancies among the Contract Documents, the Documents prepared by the State of Delaware, Division of Facilities Management shall take precedence over all other documents.

1.2 CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

Add the following Paragraphs:

1.2.4 In the case of an inconsistency between the Drawings and the Specifications, or within either document not clarified by addendum, the better quality or greater quantity of work shall be provided in accordance with the Architect's interpretation.

1.2.5 The word “PROVIDE” as used in the Contract Documents shall mean “FURNISH AND INSTALL” and shall include, without limitation, all labor, materials, equipment, transportation, services and other items required to complete the Work.

1.2.6 The word “PRODUCT” as used in the Contract Documents means all materials, systems and equipment.

1.5 OWNERSHIP AND USE OF DRAWINGS, SPECIFICATIONS AND OTHER INSTRUMENTS OF SERVICE

Delete Paragraph 1.5.1 in its entirety and replace with the following:

"All pre-design studies, drawings, specifications and other documents, including those in electronic form, prepared by the Architect under this Agreement are, and shall remain, the property of the Owner whether the Project for which they are made is executed or not. Such documents may be used by the Owner to construct one or more like Projects without the approval of, or additional compensation to, the Architect. The Contractor, Subcontractors, Sub-subcontractors and Material or Equipment Suppliers are authorized to use and reproduce applicable portions of the Drawings, Specifications and other documents prepared by the Architect and the Architect's consultants appropriate to and for use in the execution of their Work under the Contract Documents. They are not to be used by the Contractor or any Subcontractor, Sub-subcontractor or Material and Equipment Supplier on other

Projects or for additions to this Project outside the scope of the Work without the specific written consent of the Owner, Architect and Architect's consultants.

The Architect shall not be liable for injury or damage resulting from the re-use of drawings and specifications if the Architect is not involved in the re-use Project. Prior to re-use of construction documents for a Project in which the Architect is not also involved, the Owner will remove from such documents all identification of the original Architect, including name, address and professional seal or stamp."

Delete Paragraph 1.5.2 in its entirety.

ARTICLE 2: OWNER

2.2 INFORMATION AND SERVICES REQUIRED OF THE OWNER

To Subparagraph 2.2.3 - Add the following sentence:

"The Contractor, at their expense shall bear the costs to accurately identify the location of all underground utilities in the area of their excavation and shall bear all cost for any repairs required, out of failure to accurately identify said utilities."

Delete Subparagraph 2.2.5 in its entirety and substitute the following:

2.2.5 The Contractor shall be furnished free of charge up to five (5) sets of the Drawings and Project Manuals. Additional sets will be furnished at the cost of reproduction, postage and handling.

ARTICLE 3: CONTRACTOR

3.2 REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR

Amend Paragraph 3.2.2 to state that any errors, inconsistencies or omissions discovered shall be reported to the Architect and Owner immediately.

Delete the third sentence in Paragraph 3.2.4.

3.3 SUPERVISION AND CONSTRUCTION PROCEDURES

Add the following Paragraphs:

3.3.2.1 The Contractor shall immediately remove from the Work, whenever requested to do so by the Owner, any person who is considered by the Owner or Architect to be incompetent or disposed to be so disorderly, or who for any reason is not satisfactory to the Owner, and that person shall not again be employed on the Work without the consent of the Owner or the Architect.

3.3.4 The Contractor must provide suitable storage facilities at the Site for the proper protection and safe storage of their materials. Consult the Owner and the Architect before storing any materials.

3.3.5 When any room is used as a shop, storeroom, office, etc., by the Contractor or Subcontractor(s) during the construction of the Work, the Contractor making use of these areas will be held responsible for any repairs, patching or cleaning arising from such use.

3.4 LABOR AND MATERIALS

Add the Following Paragraphs:

3.4.4 Before starting the Work, each Contractor shall carefully examine all preparatory Work that has been executed to receive their Work. Check carefully, by whatever means are required, to insure that its Work and adjacent, related Work, will finish to proper contours, planes and levels. Promptly notify the General

Contractor/Construction Manager of any defects or imperfections in preparatory Work which will in any way affect satisfactory completion of its Work. Absence of such notification will be construed as an acceptance of preparatory Work and later claims of defects will not be recognized.

3.4.5 Under no circumstances shall the Contractor's Work proceed prior to preparatory Work proceed prior to preparatory Work having been completely cured, dried and/or otherwise made satisfactory to receive this Work. Responsibility for timely installation of all materials rests solely with the Contractor responsible for that Work, who shall maintain coordination at all times.

3.5 WARRANTY

Add the following Paragraphs:

3.5.1 The Contractor will guarantee all materials and workmanship against original defects, except injury from proper and usual wear when used for the purpose intended, for two years after Acceptance by the Owner, and will maintain all items in perfect condition during the period of guarantee.

3.5.2 Defects appearing during the period of guarantee will be made good by the Contractor at his expense upon demand of the Owner, it being required that all work will be in perfect condition when the period of guarantee will have elapsed.

3.5.3 In addition to the General Guarantee there are other guarantees required for certain items for different periods of time than the two years as above, and are particularly so stated in that part of the specifications referring to same. The said guarantees will commence at the same time as the General Guarantee.

3.5.4 If the Contractor fails to remedy any failure, defect or damage within a reasonable time after receipt of notice, the Owner will have the right to replace, repair, or otherwise remedy the failure, defect or damage at the Contractor's expense.

3.11 DOCUMENTS AND SAMPLES AT THE SITE

Add the following Paragraphs:

3.11.1 During the course of the Work, the Contractor shall maintain a record set of drawings on which the Contractor shall mark the actual physical location of all piping, valves, equipment, conduit, outlets, access panels, controls, actuators, including all appurtenances that will be concealed once construction is complete, etc., including all invert elevations.

3.11.2 At the completion of the project, the Contractor shall obtain a set of reproducible drawings from the Architect, and neatly transfer all information outlined in 3.11.1 to provide a complete record of the as-built conditions.

3.11.3 The Contractor shall provide two (2) prints of the as-built conditions, along with the reproducible drawings themselves, to the Owner and one (1) set to the Architect. In addition, attach one complete set to each of the Operating and Maintenance Instructions/Manuals.

3.17 ROYALTIES, PATENTS AND COPYRIGHTS

In the second sentence of the paragraph, insert "indemnify and" between “shall” and “hold”.

ARTICLE 4: ADMINISTRATION OF THE CONTRACT

4.2 ADMINISTRATION OF THE CONTRACT

Delete the first sentence of Paragraph 4.2.7 and replace with the following:

The Architect will review and approve or take other appropriate action upon the Contractor's submittals such as Shop Drawings, Product Data and Samples for the purpose of checking for conformance with the Contract Documents.

Delete the second sentence of Paragraph 4.2.7 and replace with the following:

The Architect's action will be taken with such reasonable promptness as to cause no delay in the Work in the activities of the Owner, Contractor or separate Contractors, while allowing sufficient time in the Owner's professional judgment to permit adequate review.

Add the following Subparagraph:

4.2.10.1 There will be no full-time project representative provided by the Owner or Architect on this project.

Add the following to the end of Paragraph 4.2.13:

"and in compliance with all local requirements."

ARTICLE 5: SUBCONTRACTORS

5.2 AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK

Delete Paragraph 5.2.3 in its entirety and replace with the following:

5.2.3 If the Owner or Architect has reasonable objection to a person or entity proposed by the Contractor, the Contractor shall propose another to whom the Owner or Architect has no reasonable objection, subject to the statutory requirements of 29 Delaware Code § 6962(d)(10)b.3 and 4.

ARTICLE 6: CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

6.1 OWNER'S RIGHT TO PERFORM CONSTRUCTION AND TO AWARD SEPARATE CONTRACTS

Delete Paragraph 6.1.4 in its entirety.

6.2 MUTUAL RESPONSIBILITY

6.2.3 In the second sentence, strike the word "shall" and insert the word "may".

ARTICLE 7: CHANGES IN THE WORK

(SEE ARTICLE 7: CHANGES IN WORK IN THE GENERAL REQUIREMENTS)

ARTICLE 8: TIME

8.2 PROGRESS AND COMPLETION

Add the following Paragraphs:

8.2.1.1 Refer to Specification Section SUMMARY OF WORK for Contract time requirements.

8.2.4 If the Work falls behind the Progress Schedule as submitted by the Contractor, the Contractor shall employ additional labor and/or equipment necessary to bring the Work into compliance with the Progress Schedule at no additional cost to the Owner.

8.3 DELAYS AND EXTENSION OF TIME

8.3.1Strike "arbitration" and insert "remedies at law or in equity".

Add the following Paragraph:

8.3.2.1 The Contractor shall update the status of the suspension, delay, or interruption of the Work with each Application for Payment. (The Contractor shall

report the termination of such cause immediately upon the termination thereof.) Failure to comply with this procedure shall constitute a waiver for any claim for adjustment of time or price based upon said cause.

Delete Paragraph 8.3.3 in its entirety and replace with the following:

8.3.3 Except in the case of a suspension of the Work directed by the Owner, an extension of time under the provisions of Paragraph 8.3.1 shall be the Contractor's sole remedy in the progress of the Work and there shall be no payment or compensation to the Contractor for any expense or damage resulting from the delay.

Add the following Paragraph:

8.3.4 By permitting the Contractor to work after the expired time for completion of the project, the Owner does not waive their rights under the Contract.

ARTICLE 9: PAYMENTS AND COMPLETION

9.2 SCHEDULE OF VALUES

Add the following Paragraphs:

9.2.1 The Schedule of Values shall be submitted using AIA Document G702, Continuation Sheet to G703.

9.2.2 The Schedule of Values is to include a line item for Project Closeout Document Submittal. The value of this item is to be no less than 1% of the initial contract amount.

9.3 APPLICATIONS FOR PAYMENT

Add the following Paragraph:

9.3.1.3 Application for Payment shall be submitted on AIA Document G702 “Application and Certificate for Payment”, supported by AIA Document G703 “Continuation Sheet”. Said Applications shall be fully executed and notarized.

Add the following Paragraphs:

9.3.4 Until Closeout Documents have been received and outstanding items completed the Owner will pay 95% (ninety-five percent) of the amount due the Contractor on account of progress payments.

9.3.5 The Contractor shall provide a current and updated Progress Schedule to the Architect with each Application for Payment. Failure to provide Schedule will be just cause for rejection of Application for Payment.

9.5 DECISIONS TO WITHHOLD CERTIFICATION

Add the following to 9.5.1:

.8failure to provide a current Progress Schedule;

.9a lien or attachment is filed;

.10failure to comply with mandatory requirements for maintaining Record Documents.

9.6 PROGRESS PAYMENTS

Delete Paragraph 9.6.1 in its entirety and replace with the following:

9.6.1 After the Architect has approved and issued a Certificate for Payment, payment shall be made by the Owner within 30 days after Owner's receipt of the Certificate for Payment.

9.7 FAILURE OF PAYMENT

F.In first sentence, strike “seven” and insert “thirty (30)”.

Also strike “binding dispute resolution” and insert “remedies at law or in equity”.

9.8 SUBSTANTIAL COMPLETION

To Subparagraph 9.8.3- Add the following sentence:

"If the Architect is required to make more than 2 inspections of the same portion of work, the Contractor shall be responsible for all costs associated with subsequent inspections, including but not limited to any Architect's fees."

9.8.5 In the second sentence, strike “shall” and insert “may”.

ARTICLE 10: PROTECTION OF PERSONS AND PROPERTY

10.1 SAFETY PRECAUTIONS AND PROGRAMS

Add the following Paragraphs:

10.1.1 Each Contractor shall develop a safety program in accordance with the Occupational Safety and Health Act of 1970. A copy of said plan shall be furnished to the Owner and Architect prior to the commencement of that Contractor's Work.

10.1.2 Each Contractor shall appoint a Safety Representative. Safety Representatives shall be someone who is on site on a full time basis. If deemed necessary by the Owner or Architect, Contractor Safety meetings will be scheduled. The attendance of all Safety Representatives will be required. Minutes will be recorded of said meetings by the Contractor and will be distributed to all parties as well as posted in all job offices/trailers etc.

10.2 SAFETY OF PERSONS AND PROPERTY

Add the following Paragraph:

10.2.4.1 As required in the Hazardous Chemical Act of June 1984, all vendors supplying any material that may be defined as hazardous must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it has a caution warning on the label relating to a potential physical or health hazard, if it is known to be present in the work place, and if employees may be exposed under normal conditions or in foreseeable emergency situations. Material Safety Data Sheets shall be provided directly to the Owner, along with the shipping slips that include those products.

10.3 HAZARDOUS MATERIALS

Delete Paragraph 10.3.3 in its entirety.

Delete Paragraphs 10.3.6 in its entirety.

ARTICLE 11: INSURANCE AND BONDS

11.1 CONTRACTOR'S LIABILITY INSURANCE

11.1.4 Strike “the Owner” immediately following “(1)”
and strike “and (2) the Owner as an additional insured for claims caused in whole or in part by the Contractor's negligent acts or omissions during the Contractor's completed operations."

11.2 OWNER'S LIABILITY INSURANCE

Delete Paragraph 11.2 in its entirety.

11.3 PROPERTY INSURANCE

Delete Paragraph 11.3 in its entirety and replace with the following:

11.3 The State will not provide Builder's All Risk Insurance for the Project. The Contractor and all Subcontractors shall provide property coverage for their tools and equipment, as necessary. Any mandatory deductible required by the Contractor's Insurance shall be the responsibility of the Contractor.

11.4 PERFORMANCE BOND AND PAYMENT BOND

Add the following sentence: "The bonds will conform to those forms approved by the Office of Management and Budget."

ARTICLE 12: UNCOVERING AND CORRECTION OF WORK

12.2.2 AFTER SUBSTANTIAL COMPLETION

Add the following Paragraph:

12.2.2.1.1 At any time during the progress of the Work, or in any case where the nature of the defects will be such that it is not expedient to have corrected, the Owner, at its option, will have the right to deduct such sum, or sums, of money from the amount of the Contract as it considers justified to adjust the difference in value between the defective work and that required under contract including any damage to the structure.

12.2.2.1 Strike "one" and insert "two".

12.2.2.2 Strike "one" and insert "two".

12.2.2.3 Strike "one" and insert "two".

12.2.5In second sentence, strike "one" and insert "two".

ARTICLE 13: MISCELLANEOUS PROVISIONS

13.1 GOVERNING LAW

Strike "except that, if the parties have selected arbitration as the method of binding dispute resolution, the Federal Arbitration Act shall govern Section 15.4" .

13.6 INTEREST

Strike "the date payment is due at such rate as the parties may agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located." Insert "30 days of presentment of the authorized Certificate of Payment at the annual rate of 12% or 1% per month.

13.7 TIME LIMITS ON CLAIMS

Strike the last sentence.

ADD THE FOLLOWING PARAGRAPH:

13.8 CONFLICTS WITH FEDERAL STATUTES OR REGULATIONS

13.8.1 If any provision, specifications or requirement of the Contract Documents conflict or is inconsistent with any statute, law or regulation of the government of the United State of America, the Contractor shall notify the Architect and Owner immediately upon discovery.

ARTICLE 14: TERMINATION OR SUSPENSION OF THE CONTRACT

14.4 TERMINATION BY THE OWNER FOR CONVENIENCE

Delete Paragraph 14.4.3 in its entirety and replace with the following:

14.4.3 In case of such termination for the Owner's convenience, the Contractor shall be entitled to receive payment for Work executed, and cost incurred by reason of such termination along with reasonable overhead.

ARTICLE 15: CLAIMS AND DISPUTES

15.1.2 THROUGHOUT THE PARAGRAPH STRIKE "21" AND INSERT "45."

15.1.6 CLAIMS FOR CONSEQUENTIAL DAMAGES

Delete Paragraph 15.1.6 in its entirety.

15.2 INITIAL DECISION

Delete Paragraph 15.2.5 in its entirety and replace with the following:

15.2.5 The Architect will approve or reject Claims by written decision, which shall state the reasons therefore and shall notify the parties of any change in the Contract Sum or Contract Time or both. The approval or rejection of a Claim by the Architect shall be subject to mediation and other remedies at law or in equity.

Delete Paragraph 15.2.6 and its subparagraphs in their entirety.

15.3 MEDIATION

15.3.1 Strike "binding dispute resolution" and insert "any or all remedies at law or in equity."

15.3.2 In the first sentence, delete "administered by the American Arbitration Association in accordance with its Construction Industry Mediation Procedure in effect on the date of the Agreement," Strike "binding dispute resolution" and insert "remedies at law and in equity".

15.4 ARBITRATION

Delete Paragraph 15.4 and its sub-sections in its entirety.

END OF SUPPLEMENTARY GENERAL CONDITIONS

SECTION 007313
SUPPLEMENTARY CONDITIONS

PART 1 - GENERAL

1.01 GENERAL CONDITIONS

A. The General Conditions of the Contract for Construction, AIA Document A201, 2007 edition, Articles 1 through 15 inclusive, is a part of this contract and is bound herewith.

B. References to Articles herein are to Articles in A201.

1.02 SUPPLEMENTARY CONDITIONS

A. The following provisions modify, change, delete from or add to AIA Document A201. Where any article of the General Conditions is modified or any paragraph, subparagraph or clause thereof is modified or deleted by these provisions, the unaltered provisions of that article, paragraph, sub-paragraph or clause shall remain in effect.

1.03 REFERENCE TO DIVISION 1 - GENERAL REQUIREMENTS

A. Certain provisions of Division 1 GENERAL REQUIREMENTS supplement the administrative and work-related provisions of the GENERAL CONDITIONS.

B. Articles affected are cross referenced in the various Sections of Division 1.

ARTICLE 1 - GENERAL PROVISIONS

1.1 BASIC DEFINITIONS

Delete last paragraph of 1.1.1. Add to 1.1.1 the following clause:

1.1.1.1 The Invitation to Bid, the bid forms, the contractor's completed bid and all addenda related to bidding requirements are expressly enumerated as contract documents.

Add to 1.1 the following Subparagraphs:

1.1.9 PROVIDE

1.1.9.1 The term “Provide” as used in the Contract Documents shall mean “FURNISH AND INSTALL” and shall include, without limitation, all labor, materials, equipment, transportation, services and other items required to complete the Work.

1.1.10 PRODUCT

1.1.10.1 The term “PRODUCT” as used in the Contract Documents means all materials, systems and equipment.

1.2 CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

Add to 1.2.4. the following Subparagraph:

1.2.4 In the case of an inconsistency between the Drawings and the Specifications, or within either document not clarified by addendum, the better quality or greater quantity of work shall be provided in accordance with the Architect's interpretation.

ARTICLE 2 - OWNER

2.2 INFORMATION AND SERVICES REQUIRED OF THE OWNER

To Subparagraph 2.2.3 - Add the following sentence:

"The Contractor, at their expense shall bear the costs to accurately identify the location of all underground utilities in the area of their excavation and shall bear all cost for any repairs required, out of failure to accurately identify said utilities."

Delete Subparagraph 2.2.5 in its entirety and substitute the following:

2.2.5 The Contractor will obtain Drawings and Project Manuals as described in the Invitation to Bid.

ARTICLE 3 - CONTRACTOR

3.2 REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR

Amend Paragraph 3.2.2 to state that any errors, inconsistencies or omissions discovered shall be reported to the Architect and Owner immediately.

Delete the third sentence in Paragraph 3.2.4.

ARTICLE 4 - ADMINISTRATION OF THE CONTRACT

4.2 ADMINISTRATION OF THE CONTRACT

Add the following clause:

4.2.10.1 There will be no full-time project representative provided by the Owner or Architect on this project.

ARTICLE 6 - CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

6.1 OWNER'S RIGHT TO PERFORM CONSTRUCTION AND TO AWARD SEPARATE CONTRACTS

Delete Paragraph 6.1.4 in its entirety.

6.2 MUTUAL RESPONSIBILITY

6.2.3 In the second sentence, strike the word “shall” and insert the word “may”.

ARTICLE 7 - CHANGES IN THE WORK

Add a new Subparagraph 7.1.4 to read as follows:

7.1.4 The additional cost, or credit to the Owner resulting from a change in the work shall be by mutual agreement of the Owner, Contractor and the Architect. In all cases, this cost or credit shall be based on the 'DPE' wages required and the "invoice price" of the materials/equipment needed.

7.1.4.1 “DPE” shall be defined to mean "direct personnel expense". Direct payroll expense includes direct salary plus customary fringe benefits (prevailing wage rates) and documented statutory costs such as workman's compensation insurance, Social Security/Medicare, and unemployment insurance (a maximum multiplier of 1.27 times DPE).

7.1.4.2 “Invoice price" of materials/equipment shall be defined to mean the actual cost of materials and/or equipment that is paid by the Contractor, (or subcontractor), to a material distributor, direct factory vendor, store, material provider, or equipment leasing entity. Rates for equipment that is leased and/or owned by the Contractor or subcontractor(s) shall not exceed those listed in the latest version of the "Means Building Construction Cost Data" publication.

7.1.4.3 In addition to the above, the General Contractor is allowed a fifteen percent (15%) markup for overhead and profit for additional work performed by the General Contractor's own forces. For additional subcontractor work, the Subcontractor is

allowed a fifteen percent overhead and profit on change order work above and beyond the direct costs stated previously. To this amount, the General Contractor will be allowed a mark-up not exceeding five percent (5%) on the subcontractors work. These mark-ups shall include all costs including, but not limited to: overhead, profit, bonds, insurance, supervision, etc. There will be no other costs associated with the change order."

ARTICLE 8 - TIME

8.2 PROGRESS AND COMPLETION

Add the following subparagraph:

8.2.1.1 Refer to Section 011000 Summary of Work for contract time requirements.

Add the following subparagraph:

8.2.4 If the Work falls behind the Progress Schedule as submitted by the Contractor, the Contractor shall employ additional labor and/or equipment necessary to bring the Work into compliance with the Progress Schedule at no additional cost to the Owner.

ARTICLE 9 - PAYMENTS AND COMPLETION

9.2 SCHEDULE OF VALUES

Add the following Paragraphs:

9.2.1 The Schedule of Values shall be submitted using AIA Document G702, Continuation Sheet to G703.

9.2.2 The Schedule of Values is to include a line item for Project Closeout Document Submittal. The value of this item is to be no less than 1% of the initial contract amount.

9.3 APPLICATIONS FOR PAYMENT

Add the following Paragraph:

9.3.1.3 Application for Payment shall be submitted on AIA Document G702 “Application and Certificate for Payment”, supported by AIA Document G703 “Continuation Sheet”. Said Applications shall be fully executed and notarized.

Add the following Paragraphs:

9.3.4 Until Closeout Documents have been received and outstanding items completed the Owner will pay 95% (ninety-five percent) of the amount due the Contractor on account of progress payments.

9.5 DECISIONS TO WITHHOLD CERTIFICATION

Add the following to 9.5.1:

.8 a lien or attachment is filed;

.9 failure to comply with mandatory requirements for maintaining Record Documents.

Add the following subparagraphs:

9.5.4 The Contractor shall have the obligation to remove any liens filed against the Project or any part thereof, and shall bear all costs connected with said removal prior to the Owner being obligated to make the next monthly progress payment.

9.5.5 No payment of monies nor any partial or entire use of occupancy of the Project by the Owner shall constitute an acceptance of any Work not in accordance with the Contract Documents.

9.6PROGRESS PAYMENTS

Delete Paragraph 9.6.1 in its entirety and replace with the following:

9.6.1 After the Architect has approved and issued a Certificate for Payment, payment shall be made by the Owner within 30 days after Owner's receipt of the Certificate for Payment.

9.8SUBSTANTIAL COMPLETION

To Subparagraph 9.8.3- Add the following sentence:

"If the Architect is required to make more than 2 inspections of the same portion of work, the Contractor shall be responsible for all costs associated with subsequent inspections, including but not limited to any Architect's fees."

9.8.5In the second sentence, strike “shall” and insert “may”.

ARTICLE 10 - PROTECTION OF PERSONS AND PROPERTY

10.1 SAFETY PRECAUTIONS AND PROGRAMS

Add the following Paragraphs:

10.1.1 Each Contractor shall develop a safety program in accordance with the Occupational Safety and Health Act of 1970. A copy of said plan shall be furnished to the Owner and Architect prior to the commencement of that Contractor's Work.

10.1.2 Each Contractor shall appoint a Safety Representative. Safety Representatives shall be someone who is on site on a full time basis. If deemed necessary by the Owner or Architect, Contractor Safety meetings will be scheduled. The attendance of all Safety Representatives will be required. Minutes will be recorded of said meetings by the Contractor and will be distributed to all parties as well as posted in all job offices/trailers etc.

10.2 SAFETY OF PERSONS AND PROPERTY

Add the following Paragraph:

10.2.4.1 As required in the Hazardous Chemical Act of June 1984, all vendors supplying any material that may be defined as hazardous must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it has a caution warning on the label relating to a potential physical or health hazard, if it is known to be present in the work place, and if employees may be exposed under normal conditions or in foreseeable emergency situations. Material Safety Data Sheets shall be provided directly to the Owner, along with the shipping slips that include those products.

Add the following subparagraph:

10.2.8 The Contractor shall certify to the Owner that materials incorporated into the work are free of all asbestos. This certification may be in the form of Material Safety Data Sheets (MSDS) provided by the product manufacturer for the materials used in construction by the Contractor.

10.3 HAZARDOUS MATERIALS

Delete Paragraph 10.3.3 in its entirety.

Delete Paragraphs 10.3.6 in its entirety.

ARTICLE 11 - INSURANCE

11.1 CONTRACTOR'S LIABILITY INSURANCE

Add the following Clause 11.1.2.1 to 11.1.2:

11.1.2.1The insurance required by Subparagraph 11.1.1 shall be written for not less than the following, or greater if required by law:

Workmen's Compensation:

State: Statutory

Applicable Federal (e.g., Longshoremen's): Statutory

Employer's Liability

$ 100,000

Comprehensive General Liability (including Premises Operations; Independent Contractors' Protective; Products and Completed Operations; Broad Form Property Damage):

Bodily Injury

$ 500,000	Each Person
$ 1,000,000	Each Occurrence
$ 1,000,000	Annual Aggregate

Property Damage

$ 500,000	Each Occurrence
$ 500,000	Annual Aggregate

Products and Completed Operations to be maintained for 2 years after final payment.

Property Damage Liability Insurance will provide X, C, or U coverage as applicable.

Contractual Liability:

Bodily Injury

$ 500,000	Each Person
$1,000,000	Each Occurrence
$1,000,000	Annual Aggregate

Property Damage:

$ 500,000	Each Occurrence
$1,000,000	Annual Aggregate

Personal Injury, with Employment Exclusion deleted:

$ 500,000 Each Occurrence

Comprehensive Automobile Liability:

Bodily Injury:

$1,000,000	Each Person
$1,000,000	Each Occurrence

Property Damage:

$ 500,000	Each Occurrence

Subcontractor’s policies shall include contingent and contractual liability coverage in the same minimum amounts as 3, above.

Add the following Clauses 11.1.3.1 and 11.1.3.2 to 11.1.3:

11.1.3.1 The Contractor shall furnish one copy each of Certificates of Insurance herein required for each copy of the Agreement which shall specifically set forth

evidence of all coverage required by Subparagraph 11.1.2. The form of the Certificate shall be AIA Document G705 or insurance carrier's standard form, which presents required information. The Contractor shall furnish to the Owner copies of any endorsements that are subsequently issued amending coverage or limits.

11.1.3.2 Certificates of insurance filed with the Owner shall guarantee fifteen (15) days prior notice of cancellation, non-renewal or any change in coverage and limits of liability shown as included on certificates.

Add the following Subparagraphs 11.1.5 through 11.1.8:

11.1.5 The Contractor shall carry all insurance required by law, such as Unemployment Insurance, etc. He shall carry such insurance coverage as he desires on his own property such as his field office, storage sheds or other structures erected upon the project site that belong to him and for his own use. The Subcontractors involved with this project shall carry whatever insurance protection they consider necessary to cover the loss of any of their personal property, etc.

11.1.6 Bodily Injury Liability and Property Damage Liability Insurance shall, in addition to the coverage included herein, include coverage for injury to or destruction of any property arising out of the collapse of or structural injury to any building or structure due to demolition work and evidence of these coverage shall be filed with and approved by the Owner.

11.1.7 The Contractor’s Property Damage Liability Insurance shall, in addition to the coverage noted herein, include coverage on all real and personal property in their care, custody and control damaged in any way by him or his Subcontractors during the entire construction period on this project.

11.1.8 Builders Risk (including Standard Extended Coverage Insurance) on the existing building during the entire construction period, shall not be provided by the Contractor under this contract. The Owner shall insure the existing building and all of its contents and all this new alteration work under this contract during entire construction period for the full insurable value of the entire work at the site. Note, however, that the Contractor and his Subcontractors shall be responsible for insuring building materials (installed and stored) and their tools and equipment whenever in use on the project, against fire damage, theft, vandalism, etc.

11.2OWNER'S LIABILITY INSURANCE

Delete Paragraph 11.2 and its subparagraphs in their entirety.

Delete Paragraph 11.3 and its subparagraphs in their entirety and replace with the following:

11.3 PROPERTY INSURANCE

11.3.1 The Owner will not provide Builder's All Risk Insurance for the Project. The Contractor and all Subcontractors shall provide property coverage for their tools and equipment, as necessary.

11.4 PERFORMANCE BOND AND PAYMENT BOND

Add the following subparagraphs:

11.4.3Performance and Payment Bond: Simultaneously with delivery of the executed contract, the contractor must deliver to the Owner an executed performance bond in the amount of 100% of the accepted bid as security for the faithful performance of his contract including the required Warranty and Guaranties; and an executed labor

and material payment bond in the amount of 100% of the accepted bid as security for the payment of all persons performing labor or furnishing materials in connection therewith and conditioned that the contractor shall well and faithfully pay all daily labor employed by him for this contract in full once each week. Performance and payment bond may be in a combined form. The bonding company's standard forms are acceptable provided all coverage requirements are included. The bonds shall be maintained in full force for a period of not less than twelve (12) months after the date of the Certificate for Substantial Completion.

11.4.4Bonds are to be in favor of the Owner and shall be paid for by the contractor and furnished by a surety company licensed in the State that the project is located. The Owner has the right to demand proof that the parties signing the bonds are duly authorized to do so.

ARTICLE 13: MISCELLANEOUS PROVISIONS

13.6 INTEREST

Strike "the date payment is due at such rate as the parties may agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located." Insert "30 days of presentment of the authorized Certificate of Payment at the annual rate of 6% or 0.5% per month.

ARTICLE 14 - TERMINATION OR SUSPENSION OF THE CONTRACT

14.4TERMINATION BY THE OWNER FOR CONVENIENCE

Delete Subparagraph 14.4.3 in its entirety and replace with the following:

14.4.3 In case of such termination for Owner's convenience, the Contractor shall be entitled to receive payment for work executed, materials purchased and reasonable overhead.

ADD ARTICLE 16- CONTRACTOR RESPONSIBILITIES

16.1 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Contract. The Contractor shall not permit employment of unfit persons or persons not skilled in tasks assigned to them.

16.2 The Contractor warrants to the Owner that materials and equipment furnished will be new and of good quality, unless otherwise permitted, and that the work will be free from defects and in conformance with the Contract Documents. Work not conforming to these requirements, including substitutions not properly approved, may be considered defective. If required by the Owner, the Contractor shall furnish evidence as to the kind and quality of materials and equipment provided.

16.3 Unless otherwise provided, the Contractor shall pay all sales, consumer, use and other similar taxes, and shall secure and pay for required permits, fees, licenses, and inspections necessary for proper execution of the Work.

16.4 The Contractor shall comply with and give notices required by laws, ordinances, rules, regulations, and lawful orders of public authorities bearing on performance of the work. The Contractor shall promptly notify the Owner if the Drawings and Specifications are observed to be at variance therewith.

16.5 The Contractor shall be responsible to the Owner for the acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons performing portions of the Work under contract with the Contractor.

16.6 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under the Contract.

16.6.1 At completion of the Work the Contractor shall remove from and about the Project all waste materials, rubbish, the Contractor's tools, construction equipment, machinery and surplus materials. The Contractor shall be responsible for returning all damaged areas to their original conditions.

16.7 To the fullest extent permitted by law, the Contractor shall indemnify and otherwise hold harmless the Owner, its agents and employees, and the Architect, his agents and employees, from any and all liability, suits, actions or claims, together with all costs, expenses or attorneys' fees, arising out of their performance of work or supplying materials and services in connection with this contract. This agreement to indemnify and hold harmless shall cover all suits, actions, claims or liabilities asserted against the Owner, its agents and employees, and the Architect, his agents and employees, to the extent caused in whole or part by negligent acts or omissions of the Contractor, a Subcontractor, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss, or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate or abridge other rights or obligations of indemnity which would otherwise exist.

PART 2 - PRODUCTS - NOT USED

PART 3 - EXECUTION - NOT USED

END OF SECTION

SECTION 009000

DE STATE GENERAL REQUIREMENTS

ARTICLE 1: GENERAL

1.01 CONTRACT DOCUMENTS

A. The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary and what is required by one shall be as binding as if required by all. Performance by the Contractor shall be required to an extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the intended results.

B. Work including material purchases shall not begin until the Contractor is in receipt of a bonafide State of Delaware Purchase Order. Any work performed or material purchases prior to the issuance of the Purchase Order is done at the Contractor's own risk and cost.

1.02 EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS

A. For Public Works Projects financed in whole or in part by state appropriation the Contractor agrees that during the performance of this contract:

1. The Contractor will not discriminate against any employee or applicant for employment because of race, creed, sex, color, sexual orientation, gender identity or national origin. The Contractor will take positive steps to ensure that applicants are employed and that employees are treated during employment without regard to their race, creed, sex, color, sexual orientation, gender identity or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.
2. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, sex, color, sexual orientation, gender identity or national origin."

ARTICLE 2: OWNER

(NO ADDITIONAL GENERAL REQUIREMENTS - SEE SUPPLEMENTARY GENERAL CONDITIONS)

ARTICLE 3: CONTRACTOR

3.01 SCHEDULE OF VALUES

A. The successful Bidder shall within twenty (20) days after receiving notice to proceed with the work, furnish to the Owner a complete schedule of values on the various items comprising the work.

3.02 SUBCONTRACTS

A. Upon approval of Subcontractors, the Contractor shall award their Subcontracts as soon as possible after the signing of their own contract and see that all material, their own and

those of their Subcontractors, are promptly ordered so that the work will not be delayed by failure of materials to arrive on time.

B. Before commencing any work or construction, the General Contractor is to consult with the Owner as to matters in connection with access to the site and the allocation of Ground Areas for the various features of hauling, storage, etc.

C. The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for and have control over construction means, methods, techniques, sequences and procedures and for coordinating all portions of the Work under the Contract, unless the Contract Documents give other specific instructions.

D. The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Contract. The Contractor shall not permit employment of unfit persons or persons not skilled in tasks assigned to them.

E. The Contractor warrants to the Owner that materials and equipment furnished will be new and of good quality, unless otherwise permitted, and that the work will be free from defects and in conformance with the Contract Documents. Work not conforming to these requirements, including substitutions not properly approved, may be considered defective. If required by the Owner, the Contractor shall furnish evidence as to the kind and quality of materials and equipment provided.

F. Unless otherwise provided, the Contractor shall pay all sales, consumer, use and other similar taxes, and shall secure and pay for required permits, fees, licenses, and inspections necessary for proper execution of the Work.

G. The Contractor shall comply with and give notices required by laws, ordinances, rules, regulations, and lawful orders of public authorities bearing on performance of the Work. The Contractor shall promptly notify the Owner if the Drawings and Specifications are observed to be at variance therewith.

H. The Contractor shall be responsible to the Owner for the acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons performing portions of the Work under contract with the Contractor.

I. The Contractor shall keep the premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under the Contract. At completion of the Work the Contractor shall remove from and about the Project all waste materials, rubbish, the Contractor's tools, construction equipment, machinery and surplus materials. The Contractor shall be responsible for returning all damaged areas to their original conditions.

3.03 STATE LICENSE AND TAX REQUIREMENTS

A. Each Contractor and Subcontractor shall be licensed to do business in the State of Delaware and shall pay all fees and taxes due under State laws. In conformance with Section 2503, Chapter 25, Title 30, Delaware Code, "the Contractor shall furnish the State Tax Department within ten (10) days after award of the Contract, a statement of the total values of each contract and Subcontract, together with the names and addresses of the contracting parties …. "

3.04 LARGE PUBLIC WORKS CONTRACT PROCEDURES

A. The Contractor shall comply with all requirements set forth in Section 6962, Chapter 69, Title 29 of the Delaware Code.

B. During the contract Work, the Contractor and each listed Subcontractor, shall implement an Employee Drug Testing Program in accordance with OMB Regulation 4104- "Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on "Large Public Works Projects". "Large Public Works" is based upon the current threshold required for bidding Public Works as set by the Purchasing and Contracting Advisory Council.

ARTICLE 4: ADMINISTRATION OF THE CONTRACT

4.01 CONTRACT SURETY

A. Performance Bond And Labor And Material Payment Bond

1. All bonds will be required as follows unless specifically waived elsewhere in the Bidding Documents.
2. Contents of Performance Bonds - The bond shall be conditioned upon the faithful compliance and performance by the successful bidder of each and every term and condition of the contract and the proposal, plans, specifications, and bid documents thereof. Each term and condition shall be met at the time and in the manner prescribed by the Contract, Bid documents and the specifications, including the payment in full to every person furnishing materiel or performing labor in the performance of the Contract, of all sums of money due the person for such labor and materiel. (The bond shall also contain the successful bidder's guarantee to indemnify and save harmless the State and the agency from all costs, damages and expenses growing out of or by reason of the Contract in accordance with the Contract.)
3. Invoking a Performance Bond - The agency may, when it considers that the interest of the State so require, cause judgement to be confessed upon the bond.
4. Within twenty (20) days after the date of notice of award of contract, the Bidder to whom the award is made shall furnish a Performance Bond and Labor and Material Payment Bond, each equal to the full amount of the Contract price to guarantee the faithful performance of all terms, covenants and conditions of the same. The bonds are to be issued by an acceptable Bonding Company licensed to do business in the State of Delaware and shall be issued in duplicate.
5. Performance and Payment Bonds shall be maintained in full force (warranty bond) for a period of two (2) years after the date of the Certificate for Final Payment. The Performance Bond shall guarantee the satisfactory completion of the Project and that the Contractor will make good any faults or defects in his work which may develop during the period of said guarantees as a result of improper or defective workmanship, material or apparatus, whether furnished by themselves or their Sub-Contractors. The Payment Bond shall guarantee that the Contractor shall pay in full all persons, firms or corporations who furnish labor or material or both labor and material for, or on account of, the work included herein. The bonds shall be paid for by this Contractor. The Owner shall have the right to demand that the proof parties signing the bonds are duly authorized to do so.

4.02 FAILURE TO COMPLY WITH CONTRACT

A. If any firm entering into a contract with the State, or Agency that neglects or refuses to perform or fails to comply with the terms thereof, the Agency which signed the Contract may terminate the Contract and proceed to award a new contract in accordance with this Chapter 69, Title 29 of the Delaware Code or may require the Surety on the Performance Bond to complete the Contract in accordance with the terms of the Performance Bond. Nothing herein shall preclude the Agency from pursing additional remedies as otherwise provided by law.

4.03 CONTRACT INSURANCE AND CONTRACT LIABILITY

A. In addition to the bond requirements stated in the Bid Documents, each successful Bidder shall purchase adequate insurance for the performance of the Contract and, by submission of a Bid, agrees to indemnify and save harmless and to defend all legal or equitable actions brought against the State, any Agency, officer and/or employee of the State, for and from all claims of liability which is or may be the result of the successful Bidder's actions during the performance of the Contract.

B. The purchase or nonpurchase of such insurance or the involvement of the successful Bidder in any legal or equitable defense of any action brought against the successful Bidder based upon work performed pursuant to the Contract will not waive any defense which the State, its agencies and their respective officers, employees and agents might otherwise have against such claims, specifically including the defense of sovereign immunity, where applicable, and by the terms of this section, the State and all agencies, officers and employees thereof shall not be financially responsible for the consequences of work performed, pursuant to said contract.

4.04 RIGHT TO AUDIT RECORDS

A. The Owner shall have the right to audit the books and records of a Contractor or any Subcontractor under any Contract or Subcontract to the extent that the books and records relate to the performance of the Contract or Subcontract.

B. Said books and records shall be maintained by the Contractor for a period of seven (7) years from the date of final payment under the Prime Contract and by the Subcontractor for a period of seven (7) years from the date of final payment under the Subcontract.

ARTICLE 5: SUBCONTRACTORS

5.01 SUBCONTRACTING REQUIREMENTS

A. All contracts for the construction, reconstruction, alteration or repair of any public building (not a road, street or highway) shall be subject to the following provisions:

1. A contract shall be awarded only to a Bidder whose Bid is accompanied by a statement containing, for each Subcontractor category, the name and address (city or town and State only - street number and P.O. Box addresses not required) of the subcontractor whose services the Bidder intends to use in performing the Work and providing the material for such Subcontractor category.
2. A Bid will not be accepted nor will an award of any Contract be made to any Bidder which, as the Prime Contractor, has listed itself as the Subcontractor for any Subcontractor unless:

a. It has been established to the satisfaction of the awarding Agency that the Bidder has customarily performed the specialty work of such Subcontractor category by artisans regularly employed by the Bidder's firm;
b. That the Bidder is duly licensed by the State to engage in such specialty work, if the State requires licenses; and
c. That the Bidder is recognized in the industry as a bona fide Subcontractor or Contractor in such specialty work and Subcontractor category.

B. The decision of the awarding Agency as to whether a Bidder who list itself as the Subcontractor for a Subcontractor category shall be final and binding upon all Bidders, and no action of any nature shall lie against any awarding agency or its employees or officers because of its decision in this regard.

C. After such a Contract has been awarded, the successful Bidder shall not substitute another Subcontractor for any Subcontractor whose name was set forth in the statement which accompanied the Bid without the written consent of the awarding Agency.

D. No Agency shall consent to any substitution of Subcontractors unless the Agency is satisfied that the Subcontractor whose name is on the Bidders accompanying statement:
1. Is unqualified to perform the work required;
2. Has failed to execute a timely reasonable Subcontract;
3. Has defaulted in the performance on the portion of the work covered by the Subcontract; or
4. Is no longer engaged in such business.

E. Should a Bidder be awarded a contract, such successful Bidder shall provide to the agency the taxpayer identification license numbers of such subcontractors. Such numbers shall be provided on the later of the date on which such subcontractor is required to be identified or the time the contract is executed. The successful Bidder shall provide to the agency to which it is contracting, within 30 days of entering into such public works contract, copies of all Delaware Business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the Bidder entered the public works contract the Delaware Business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.

5.02 PENALTY FOR SUBSTITUTION OF SUBCONTRACTORS

A. Should the Contractor fail to utilize any or all of the Subcontractors in the Contractor's Bid statement in the performance of the Work on the public bidding, the Contractor shall be penalized in the amount of one (1) percent of Contract amount not to exceed $10,000. The Agency may determine to deduct payments of the penalty from the Contractor or have the amount paid directly to the Agency. Any penalty amount assessed against the Contractor may be remitted or refunded, in whole or in part, by the Agency awarding the Contract, only if it is established to the satisfaction of the Agency that the Subcontractor in question has defaulted or is no longer engaged in such business. No claim for the remission or refund of any penalty shall be granted unless an application is filed within one year after the liability of the successful Bidder accrues. All penalty amounts assessed and not refunded or remitted to the contractor shall be reverted to the State.

5.03 ASBESTOS ABATEMENT

A. The selection of any Contractor to perform asbestos abatement for State-funded projects shall be approved by the Office of Management and Budget/Division of Facilities Management pursuant to Chapter 78 of Title 16.

5.04 STANDARDS OF CONSTRUCTION FOR THE PROTECTION OF THE PHYSICALLY HANDICAPPED

A. All Contracts shall conform with the standard established by the Delaware Architectural Accessibility Board unless otherwise exempted by the Board.

5.05 CONTRACT PERFORMANCE

A. Any firm entering into a Public Works Contract that neglects or refuses to perform or fails to comply with its terms, the Agency may terminate the Contract and proceed to award a new Contract or may require the Surety on the Performance Bond to complete the Contract in accordance with the terms of the performance Bond.

ARTICLE 6: CONSTRUCTION BY OWNER OR SEPARATE CONTRACTORS

6.01 CONSTRUCTION BY OWNER OR SEPARATE CONTRACTORS

A. The Owner reserves the right to simultaneously perform other construction or operations related to the Project with the Owner's own forces, and to award separate contracts in connection with other portions of the Project or other Projects at the same site.

B. The Contractor shall afford the Owner and other Contractors reasonable opportunity for access and storage of materials and equipment, and for the performance of their activities, and shall connect and coordinate their activities with other forces as required by the Contract Documents.

ARTICLE 7: CHANGES IN THE WORK

7.01 CHANGES IN THE WORK

A. The Owner, without invalidating the Contract, may order changes in the Work consisting of Additions, Deletions, Modifications or Substitutions, with the Contract Sum and Contract completion date being adjusted accordingly. Such changes in the Work shall be authorized by written Change Order signed by the Professional, as the duly authorized agent, the Contractor and the Owner.

B. The Contract Sum and Contract Completion Date shall be adjusted only by a fully executed Change Order.

C. The additional cost, or credit to the Owner resulting from a change in the Work shall be by mutual agreement of the Owner, Contractor and the Architect. In all cases, this cost or credit shall be based on the 'DPE' wages required and the “invoice price” of the materials/equipment needed.

1. "DPE" shall be defined to mean “direct personnel expense”. Direct payroll expense includes direct salary plus customary fringe benefits (prevailing wage rates) and documented statutory costs such as workman's compensation insurance, Social Security/Medicare, and unemployment insurance (a maximum multiplier of 1.35 times DPE).
2. "Invoice price" of materials/equipment shall be defined to mean the actual cost of materials and/or equipment that is paid by the Contractor, (or subcontractor), to a material distributor, direct factory vendor, store, material provider, or equipment

leasing entity. Rates for equipment that is leased and/or owned by the Contractor or subcontractor(s) shall not exceed those listed in the latest version of the "Means Building Construction Cost Data" publication.

3. In addition to the above, the General Contractor is allowed a fifteen percent (15%) markup for overhead and profit for additional work performed by the General Contractor's own forces. For additional subcontractor work, the Subcontractor is allowed a fifteen percent overhead and profit on change order work above and beyond the direct costs stated previously. To this amount, the General Contractor will be allowed a mark-up not exceeding seven point five percent (7.5%) on the subcontractors work. These mark-ups shall include all costs including, but not limited to: overhead, profit, bonds, insurance, supervision, etc. No markup is permitted on the work of a Sub-subcontractor. No additional costs shall be allowed for changes related to the Contractor's onsite superintendent/staff, or project manager, unless a change in the work changes the project duration and is identified by the CPM schedule. There will be no other costs associated with the change order.

ARTICLE 8: TIME

8.01 TIME

A. Time limits, if any, are as stated in the Project Manual. By executing the Agreement, the Contractor confirms that the stipulated limits are reasonable, and that the Work will be completed within the anticipated time frame.

B. If progress of the Work is delayed at any time by changes ordered by the Owner, by labor disputes, fire, unusual delay in deliveries, abnormal adverse weather conditions, unavoidable casualties or other causes beyond the Contractor's control, the Contract Time shall be extended for such reasonable time as the Owner may determine.

C. Any extension of time beyond the date fixed for completion of the construction and acceptance of any part of the Work called for by the Contract, or the occupancy of the building by the Owner, in whole or in part, previous to the completion shall not be deemed a waiver by the Owner of his right to annul or terminate the Contract for abandonment or delay in the matter provided for, nor relieve the Contractor of full responsibility.

8.02 SUSPENSION AND DEBARMENT

A. Per Section 6962(d)(14), Title 29, Delaware Code, "Any Contractor who fails to perform a public works contract or complete a public works project within the time schedule established by the Agency in the Invitation To Bid, may be subject to Suspension or Debarment for one or more of the following reasons: 1) failure to supply the adequate labor supply ratio for the project; 2) inadequate financial resources; or, 3) poor performance on the Project."

B. "Upon such failure for any of the above stated reasons, the Agency that contracted for the public works project may petition the Director of the Office of Management and Budget for Suspension or Debarment of the Contractor. The Agency shall send a copy of the petition to the Contractor within three (3) working days of filing with the Director. If the Director concludes that the petition has merit, the Director shall schedule and hold a hearing to determine whether to suspend the Contractor, debar the Contractor or deny the petition. The Agency shall have the burden of proving, by a preponderance of the evidence, that the Contractor failed to perform or complete the public works project

within the time schedule established by the Agency and failed to do so for one or more of the following reasons: 1) failure to supply the adequate labor supply ratio for the project; 2) inadequate financial resources; or, 3) poor performance on the project. Upon a finding in favor of the Agency, the Director may suspend a Contractor from Bidding on any project funded, in whole or in part, with public funds for up to 1 year for a first offense, up to 3 years for a second offense and permanently debar the Contractor for a third offense. The Director shall issue a written decision and shall send a copy to the Contractor and the Agency. Such decision may be appealed to the Superior Court within thirty (30) days for a review on the record."

8.03 RETAINAGE

A. Per Section 6962(d)(5) a., Title 29, Delaware Code: The Agency may at the beginning of each public works project establish a time schedule for the completion of the project. If the project is delayed beyond the completion date due to the Contractor's failure to meet their responsibilities, the Agency may hold permanently, at its discretion, all or part of the Contractor's retainage.

B. This forfeiture of retainage also applies to the timely completion of the punchlist. A punchlist will only be prepared upon the mutual agreement of the Owner, Architect and Contractor. Once the punchlist is prepared, all three parties will by mutual agreement, establish a schedule for its completion. Should completion of the punchlist be delayed beyond the established date due to the Contractor's failure to meet their responsibilities, the Agency may hold permanently, at its discretion, all or part of the Contractor's retainage.

ARTICLE 9: PAYMENTS AND COMPLETION

9.01 APPLICATION FOR PAYMENT

A. Applications for payment shall be made upon AIA Document G702. There will be a five percent (5%) retainage on all Contractor's monthly invoices until completion of the project. This retainage will become payable upon receipt of all required closeout documentation, provided all other requirements of the Contract Documents have been met.

B. A date will be fixed for the taking of the monthly account of work done. Upon receipt of Contractor's itemized application for payment, such application will be audited, modified, if found necessary, and approved for the amount. Statement shall be submitted to the Owner.

C. Article 6516, Chapter 65, Title 29 of the Delaware Code stipulates annualized interest not to exceed 12% per annum beginning thirty (30) days after the “presentment” (as opposed to the date) of the invoice.”

9.02 PARTIAL PAYMENTS

A. Any public works Contract executed by any Agency may provide for partial payments at the option of the Owner with respect to materials placed along or upon the sites or stored at secured locations, which are suitable for use in the performance of the contract.

B. When approved by the agency, partial payment may include the values of tested and acceptable materials of a nonperishable or noncontaminative nature which have been produced or furnished for incorporation as a permanent part of the work yet to be completed, provided acceptable provisions have been made for storage.

1. Any allowance made for materials on hand will not exceed the delivered cost of the materials as verified by invoices furnished by the Contractor, nor will it exceed the contract bid price for the material complete in place.

C. If requested by the Agency, receipted bills from all Contractors, Subcontractors, and material, men, etc., for the previous payment must accompany each application for payment. Following such a request, no payment will be made until these receipted bills have been received by the Owner.

9.03 SUBSTANTIAL COMPLETION

A. When the building has been made suitable for occupancy, but still requires small items of miscellaneous work, the Owner will determine the date when the project has been substantially completed.

B. If, after the Work has been substantially completed, full completion thereof is materially delayed through no fault of the Contractor, and without terminating the Contract, the Owner may make payment of the balance due for the portion of the Work fully completed and accepted. Such payment shall be made under the terms and conditions governing final payment that it shall not constitute a waiver of claims.

C. On projects where commissioning is included, the commissioning work as defined in the specifications must be complete prior to the issuance of substantial completion.

9.04 FINAL PAYMENT

A. Final payment, including the five percent (5%) retainage, shall be made within thirty (30) days after the Work is fully completed and the Contract fully performed and provided that the Contractor has submitted the following closeout documentation (in addition to any other documentation required elsewhere in the Contract Documents):
   1. Evidence satisfactory to the Owner that all payrolls, material bills, and other indebtedness connected with the work have been paid,
   2. An acceptable RELEASE OF LIENS,
   3. Copies of all applicable warranties,
   4. As-built drawings,
   5. Operations and Maintenance Manuals,
   6. Instruction Manuals,
   7. Consent of Surety to final payment.
   8. The Owner reserves the right to retain payments, or parts thereof, for its protection until the foregoing conditions have been complied with, defective work corrected and all unsatisfactory conditions remedied.

ARTICLE 10: PROTECTION OF PERSONS AND PROPERTY

10.01 PROTECTION OF PERSONS AND PROPERTY

A. The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract. The Contractor shall take all reasonable precautions to prevent damage, injury or loss to: workers, persons nearby who may be affected, the Work, materials and equipment to be incorporated, and existing property at the site or adjacent thereto. The Contractor shall give notices and comply with applicable laws ordinances, rules regulations, and lawful orders of public authorities bearing on the safety of persons and property and their protection from injury, damage, or loss. The Contractor shall promptly remedy damage

and loss to property at the site caused in whole or in part by the Contractor, a Subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable.

B. The Contractor shall notify the Owner in the event any existing hazardous material such as lead, PCBs, asbestos, etc. is encountered on the project. The Owner will arrange with a qualified specialist for the identification, testing, removal, handling and protection against exposure or environmental pollution, to comply with applicable regulation laws and ordinances. The Contractor and Architect will not be required to participate in or to perform this operation. Upon completion of this work, the Owner will notify the Contractor and Architect in writing the area has been cleared and approved by the authorities in order for the work to proceed. The Contractor shall attach documentation from the authorities of said approval.

C. As required in the Hazardous Chemical Information Act of June 1984, all vendors supplying any materials that may be defined as hazardous, must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it has a warning caution on the label relating to a potential physical or health hazard, if it is known to be present in the work place, and if employees may be exposed under normal conditions or in any foreseeable emergency situation. Material Safety Data Sheets must be provided directly to the Owner along with the shipping slips that include those products.

D. The Contractor shall certify to the Owner that materials incorporated into the Work are free of all asbestos. This certification may be in the form of Material Safety Data Sheet (MSDS) provided by the product manufacturer for the materials used in construction, as specified or as provided by the Contractor.

ARTICLE 11: INSURANCE AND BONDS

11.01 INSURANCE AND BONDS

A. The Contractor shall carry all insurance required by law, such as Unemployment Insurance, etc. The Contractor shall carry such insurance coverage as they desire on their own property such as a field office, storage sheds or other structures erected upon the project site that belong to them and for their own use. The Subcontractors involved with this project shall carry whatever insurance protection they consider necessary to cover the loss of any of their personal property, etc.

B. Upon being awarded the Contract, the Contractor shall obtain a minimum of two (2) copies of all required insurance certificates called for herein, and submit one (1) copy of each certificate, to the Owner, within 20 days of contract award.

C. Bodily Injury Liability and Property Damage Liability Insurance shall, in addition to the coverage included herein, include coverage for injury to or destruction of any property arising out of the collapse of or structural injury to any building or structure due to demolition work and evidence of these coverages shall be filed with and approved by the Owner.

D. The Contractor's Property Damage Liability Insurance shall, in addition to the coverage noted herein, include coverage on all real and personal property in their care, custody and control damaged in any way by the Contractor or their Subcontractors during the entire construction period on this project.

E. Builders Risk (including Standard Extended Coverage Insurance) on the existing building during the entire construction period, shall not be provided by the Contractor under this contract. The Owner shall insure the existing building and all of its contents and all this new alteration work under this contract during entire construction period for the full insurable value of the entire work at the site. Note, however, that the Contractor and their Subcontractors shall be responsible for insuring building materials (installed and stored) and their tools and equipment whenever in use on the project, against fire damage, theft, vandalism, etc.

F. Certificates of the insurance company or companies stating the amount and type of coverage, terms of policies, etc., shall be furnished to the Owner, within 20 days of contract award.

G. The Contractor shall, at their own expense, (in addition to the above) carry the following forms of insurance:

1. Contractor's Contractual Liability Insurance
   Minimum coverage to be:
   Bodily Injury$ 500,000for each person
   $1,000,000for each occurrence
   $1,000,000aggregate
   Property Damage$ 500,000for each occurrence
   $1,000,000aggregate
2. Contractor's Protective Liability Insurance
   Minimum coverage to be:
   Bodily Injury$ 500,000for each person
   $1,000,000for each occurrence
   $1,000,000aggregate
   Property Damage$ 500,000for each occurrence
   $ 500,000aggregate
3. Automobile Liability Insurance
   Minimum coverage to be:
   Bodily Injury$ 1,000,000for each person
   $ 1,000,000for each occurrence
   Property Damage$ 500,000per accident
4. Prime Contractor's and Subcontractors' policies shall include contingent and contractual liability coverage in the same minimum amounts as 11.7.1 above.
5. Workmen's Compensation (including Employer's Liability):
   a. Minimum Limit on employer's liability to be as required by law.
   b. Minimum Limit for all employees working at one site.
6. Certificates of Insurance must be filed with the Owner guaranteeing fifteen (15) days prior notice of cancellation, non-renewal, or any change in coverages and limits of liability shown as included on certificates.
7. Social Security Liability
   a. With respect to all persons at any time employed by or on the payroll of the Contractor or performing any work for or on their behalf, or in connection with or arising out of the Contractor's business, the Contractor shall accept full and exclusive liability for the payment of any and all contributions or taxes or unemployment insurance, or old age retirement benefits, pensions or annuities

now or hereafter imposed by the Government of the United States and the State or political subdivision thereof, whether the same be measured by wages, salaries or other remuneration paid to such persons or otherwise.

b. Upon request, the Contractor shall furnish Owner such information on payrolls or employment records as may be necessary to enable it to fully comply with the law imposing the aforesaid contributions or taxes.

c. If the Owner is required by law to and does pay any and/or all of the aforesaid contributions or taxes, the Contractor shall forthwith reimburse the Owner for the entire amount so paid by the Owner.

ARTICLE 12: UNCOVERING AND CORRECTION OF WORK

12.01 UNCOVERING AND CORRECTION OF WORK

A. The Contractor shall promptly correct Work rejected by the Owner or failing to conform to the requirements of the Contract Documents, whether observed before or after Substantial Completion and whether or not fabricated, installed or completed, and shall correct any Work found to be not in accordance with the requirements of the Contract Documents within a period of two years from the date of Substantial Completion, or by terms of an applicable special warranty required by the Contract Documents. The provisions of this Article apply to work done by Subcontractors as well as to Work done by direct employees of the Contractor.

B. At any time during the progress of the work, or in any case where the nature of the defects shall be such that it is not expedient to have them corrected, the Owner, at their option, shall have the right to deduct such sum, or sums, of money from the amount of the contract as they consider justified to adjust the difference in value between the defective work and that required under contract including any damage to the structure.

ARTICLE 13: MISCELLANEOUS PROVISIONS

13.01 CUTTING AND PATCHING

A. The Contractor shall be responsible for all cutting and patching. The Contractor shall coordinate the work of the various trades involved.

13.02 DIMENSIONS

A. All dimensions shown shall be verified by the Contractor by actual measurements at the project site. Any discrepancies between the drawings and specifications and the existing conditions shall be referred to the Owner for adjustment before any work affected thereby has been performed.

13.03 LABORATORY TESTS

A. Any specified laboratory tests of material and finished articles to be incorporated in the work shall be made by bureaus, laboratories or agencies approved by the Owner and reports of such tests shall be submitted to the Owner. The cost of the testing shall be paid for by the Contractor.

B. The Contractor shall furnish all sample materials required for these tests and shall deliver same without charge to the testing laboratory or other designated agency when and where directed by the Owner.

13.04 ARCHAEOLOGICAL EVIDENCE

A. Whenever, in the course of construction, any archaeological evidence is encountered on the surface or below the surface of the ground, the Contractor shall notify the authorities of the Delaware Archaeological Board and suspend work in the immediate area for a reasonable time to permit those authorities, or persons designated by them, to examine the area and ensure the proper removal of the archaeological evidence for suitable preservation in the State Museum.

13.05 GLASS REPLACEMENT AND CLEANING

A. The General Contractor shall replace without expense to the Owner all glass broken during the construction of the project. If job conditions warrant, at completion of the job the General Contractor shall have all glass cleaned and polished.

13.06 WARRANTY

A. For a period of two (2) years from the date of Substantial Completion, as evidenced by the date of final acceptance of the work, the contractor warrants that work performed under this contract conforms to the contract requirements and is free of any defect of equipment, material or workmanship performed by the contractor or any of his subcontractors or suppliers. However, manufacturer's warranties and guarantees, if for a period longer than two (2) years, shall take precedence over the above warranties. The contractor shall remedy, at his own expense, any such failure to conform or any such defect. The protection of this warranty shall be included in the Contractor's Performance Bond.

ARTICLE 14: TERMINATION OF CONTRACT

14.01 TERMINATION OF CONTRACT

A. If the Contractor defaults or persistently fails or neglects to carry out the Work in accordance with the Contract Documents or fails to perform a provision of the Contract, the Owner, after seven days written notice to the Contractor, may make good such deficiencies and may deduct the cost thereof from the payment then or thereafter due the Contractor. Alternatively, at the Owner's option, and the Owner may terminate the Contract and take possession of the site and of all materials, equipment, tools, and machinery thereon owned by the Contractor and may finish the Work by whatever method the Owner may deem expedient. If the costs of finishing the Work exceed any unpaid compensation due the Contractor, the Contractor shall pay the difference to the Owner.

B. "If the continuation of this Agreement is contingent upon the appropriation of adequate state, or federal funds, this Agreement may be terminated on the date beginning on the first fiscal year for which funds are not appropriated or at the exhaustion of the appropriation. The Owner may terminate this Agreement by providing written notice to the parties of such non-appropriation. All payment obligations of the Owner will cease upon the date of termination. Notwithstanding the foregoing, the Owner agrees that it will use its best efforts to obtain approval of necessary funds to continue the Agreement by taking appropriate action to request adequate funds to continue the Agreement."

END OF GENERAL REQUIREMENTS

SECTION 009500
GENERAL AND SPECIAL INSTRUCTIONS

PART 1 - GENERAL

1.01 GENERAL INSTRUCTIONS TO BIDDERS

A. The general rules and conditions which follow apply to all purchases and become a part of each contract or purchase order
   1. Before submitting its bid, the bidder must review all instructions and specifications.
   2. A bidder's misinterpretation or ignorance of such instructions or specifications will not excuse the bidder from complying with the instructions and specifications.
   3. The bidder must also review applicable state laws. If these instructions or the bid specifications are inconsistent with state law, state law shall control.

1.02 DEFINITIONS:

A. "District" refers to the Brandywine School District.

1.03 BID PROPOSALS

A. Use the enclosed Proposal Form in submitting a Bid Proposal. The Bid Proposal must be dated and signed by an authorized representative of the bidder.

B. Refer to Section 001000, INSTRUCTIONS TO BIDDERS, for additional information.

1.04 "RFP" - REQUESTS FOR PROPOSALS: N/A

1.05 PRE-BID MEETINGS: REQUIRED

1.06 DELIVERY OF BID PROPOSALS

A. Sealed Bid Proposal must be received at the address listed in the Advertisement for Bid notice, prior to the time set for the Bid Opening. It is the responsibility of the Bidder to make certain that the Bid Proposal is in the location designated above prior to the time set for the Bid Opening. The District accepts no responsibility for any bid entrusted to the United States Postal Service, or any other delivery service or company. Bid Proposals not received in the designated location by the time set for the Bid Opening will not be considered.

1.07 BID OPENING

A. Bids will be publicly opened at the designated location at the time designated on the Proposal Form, and in the Advertisement for Bids. The purpose of the opening is to reveal the names of those bidders submitting proposals. The opening is not to serve as a forum for determining the responsiveness of each bid, or the apparent low bidder. The aggregate amount of each bid shall be disclosed. Additional information shall be disclosed at the discretion of the District.

1.08 POLICY AND PROCEDURE FOR THE EXAMINATION AND COPYING OF PUBLIC RECORDS

A. Title 29 § 10003 Delaware Code Freedom of Information Act
   1. All public records shall be open to inspection and copying by any citizen of the State during regular business hours by the custodian of the records for the appropriate public body. Reasonable access to and reasonable facilities for copying of these records shall not be denied to any citizen. If the record is in active use or in storage and, therefore, not available at the time a citizen requests access, the custodian shall

so inform the citizen and make an appointment for said citizen to examine such records as expediently as they may be made available. Any reasonable expense involved in the copying of such records shall be levied as a charge on the citizen requesting such copy.

2. It shall be the responsibility of the public body to establish rules and regulations regarding access to public records as well as fees charged for copying of such records. (60 Del. Laws, c. 641 § 1.)

B. Examination of Contract File

1. Any citizen of the State or bidder may review the contract file only after making an appointment to do so with the District. Requests to review the records during an unannounced office visit may be denied if department personnel are busy, or if the file is in active use. Trade secrets and commercial or financial information of a privileged or confidential nature shall not be deemed public.

C. Requests for Bid Tabulations

1. Copies of bid tabulation may be obtained from the District either by mail after receipt of a written request and a self-addressed and stamped envelope, or by making an appointment to pick up copies that will be left at the Receptionist's desk. Bid tabulation and/or contract information other than the name of the successful bidder will not be given out over the telephone. Requests for bid tabulations during an unannounced office visit may be denied if work flow of department personnel will be disrupted.

D. Copying Fees

1. The District reserves the right to charge a reasonable fee for the copying of any public record. Such charges must be paid to the District prior to receiving the copies.

1.09 STATUS OF PROPOSALS

A. Unless otherwise stated in the Special Instructions or on the Proposal Form, the Proposal submitted by bidders shall be binding for a period of 60 days from the date the bids are opened. Requests for Proposals shall be binding for a period of 90 days.

B. Bids may be withdrawn up to the time of the bid opening upon request of the bidder. Such a request must be in writing and received by the District prior to the time stated for the bid opening. Timely requests submitted by facsimile or telegram will be honored.

C. Waiver - The District reserves the right to waive any failure to conform to the instructions or specifications if the waiver: (1) does not involve a mandatory statutory requirement; (2) does not provide a competitive advantage to one or more bidders; and (3) is in the best interest of the District.

D. Bidders may take exception to the terms and conditions of the instructions and/or specifications. Exceptions must be submitted prior to the opening of bids. Exceptions that do not conform to State bid law and/or create inequality in the treatment of bidders will be rejected. The bid of a bidder taking exception may be rejected if the District rejects the exception.

1.10 AWARDING OF BIDS

A. The District reserves the right to award the bid to the lowest qualified bidder meeting specifications by item, in total, or any other method, whichever is deemed by the District to be in its best interest.

B. The District reserves the right to award the bid to 2 or more firms if the advertisement for bids notifies bidders of the right of the District to make such an award and the criteria for such an award.

C. The District reserves the right to reject any and all bids, in whole or in part, to make partial awards, to waive any irregularity, to reasonably increase or decrease quantities where estimated quantities are shown or where definite quantities are shown, and may reject any bid which indicates any omission, contains alteration of form or additions not requested or imposes conditions, or where the individual bidder should receive a total award of less than $500.00, or offers alternate items, and make any award which is deemed to be in the best interest of the District.

D. In the event of tie bids, the District will decide which bidder is to be awarded the contract by any criteria of its choice.

E. The contract shall be awarded by the District and its Board(s) within 60 days after the opening of bids. Failure to do so shall be cause for rejection of all bids. Responses to Requests for Proposals shall be awarded within 90 days after the opening of Proposals. Failure to do so shall be cause for rejection of all proposals.

1.11 BID DEPOSIT REQUIRED

1.12 FORMAL CONTRACT AND/OR PURCHASE ORDER

A. The successful bidder shall execute the formal contract, within twenty (20) days after the award of the contract. No bidder or Vendor is to begin any work until it receives a State of Delaware Purchase Order signed by two authorized representatives of the District, properly processed through the State of Delaware Accounting Office. The Purchase Order shall serve as the authorization to proceed with work in accordance with the bid specifications and the special instructions.

B. The formal contract or purchase order shall incorporate by reference these General Instructions, as well as the Special Instructions and Specifications and the bidder's Proposal.

1.13 PERFORMANCE AND PAYMENT BONDS REQUIRED

1.14 FAILURE TO COMPLY WITH CONTRACT: NEW AWARD: SUPERVISION

A. If any person entering into a contract under the authority of this chapter neglects or refuses to perform it or fails to comply with the terms thereof, the District will terminate the contract and proceed to award a new contract in accordance with the provisions of Chapter 69, Title 29 of the Delaware Code, or may require the surety on the performance bond to complete the contract in accordance with the terms of the performance bond.

B. Should a contractor/supplier fail to perform under the conditions of this contract, the District reserves the right to purchase the item or items on the open market and charge to the contractor/supplier or deduct from any monies owed the contractor/supplier, the difference between the bid price and the purchase price. However, no such action will be taken without first notifying the contractor/supplier by certified letter and giving him reasonable time to reply, but in no event longer than 10 days from the mailing of the certified letter. Failure to supply items as bid may be cause for removal of a bidder from our vendor bid list.

1.15 PREFERENCE FOR DELAWARE LABOR: STIPULATION IN CONTRACT

A. In the construction of all public works for the State or any political subdivision thereof, or by persons contracting with the State or any political subdivision thereof, preference in employment of laborers, workmen or mechanics, shall be given to bona fide legal citizens of the State, who have established citizenship by residence of at least ninety days in the State. Any person, company or corporation who violates the provisions of this section shall pay a penalty to the Secretary of Finance equal to the amount of compensation paid to any person in violation of this section. (per Delaware Code, Title 29, Chapter 69, Section 6962, Paragraph (d) Subsection (4)b)

1.16 NON-DISCRIMINATION

A. In performing this work the successful bidder agrees to the following:

B. The successful bidder will not discriminate against any employee or application for employment because of race, creed, color, sex, national origin, age or disability. The vendor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, creed, color, sex, national origin, age or disability. Such action shall include, but not be limited to, the following: Employment, upgrading, demotion, or transfer; recruitment; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship.

C. The successful bidder will, in all solicitations or advertisements for employees place by or on behalf of himself, state that all qualified applicants will receive consideration for employment without regard to race, creed, color, sex, national origin, age or disability.

1.17 EQUAL OPPORTUNITY EMPLOYER

A. The School District is an equal opportunity employer and does not discriminate or deny services on the basis of race, color, creed, national origin, sex, disability, or age.

1.18 INSURANCE - LIABILITY

A. The successful bidder shall maintain, at its expense, the following insurance:
   1. Public Liability and Automobile Liability Insurance
      a. The policy is to be provided for both the owner and the contractor.
      b. Minimum coverage for bodily injury shall be $500,000 for any one individual and $1,000,000 for any one accident.
      c. Minimum coverage for property damage shall be $500,000 for any one accident.
      d. Policies shall include completed operations, owners and contractors Protective Liability and Contractual Liability coverage, including protection against claims arising out of the activities of subcontractors in the same minimum amounts stated above.
      e. If the project involves excavations, deep trenching, or blasting, endorsements to the policy should be obtained to cover these hazards.
      f. Certificates of insurance must be filed with the owner guaranteeing fifteen (15) days' notice prior to cancellation.
   2. Builders Risk Policy
      a. The builders risk policy shall be an all risk coverage policy.
      b. The policy shall be in the name of the owner and prime contractor, jointly, "as their interests may appear."

c. On new construction or complete additions, the policy will be carried on a completed value basis.
d. On renovation projects, the policy will be covered by either an installation floater or a separate policy of sufficient dollar amount to fully cover the cost of the materials stored.
e. If it is your policy to pay for material not stored on the site, either a separate certificate of insurance must be issued or a rider must be added to the existing builders risk policy. The amount of coverage must be sufficient to cover all materials stored off the site.
f. Certificates of insurance must be filed with the owner guaranteeing fifteen (15) days' notice prior to cancellation.

3. Worker's Compensation Including Employee's Liability
   a. Minimum limit on Employee's Liability to be $100,000 minimum limit for all employees working at one site.
   b. Certificates of insurance must be filed with the owner guaranteeing fifteen (15) days' notice prior to cancellation.

1.19 LCENSES, FEES, PERMITS, TAXES, AND STATE LAWS AS APPLICABLE

A. In the performance of this Contract the successful Bidder is required to comply with all applicable Federal, State, and Local laws, ordinances, codes, and regulations. The cost of permits, insurance, taxes, and other relevant costs required in the performance of the Contract shall be borne by the successful Bidder. All Delaware Laws in reference to construction shall be as binding as though quoted in full herein and their application shall be fully adhered to by all parties affected hereby. The vendor shall furnish upon request any or all of the referenced items.

1.20 WAGE SCALE - PREVAILING WAGE RATE

1.21 PATENTS, TRADEMARKS, AND COPYRIGHTS

A. The supplier shall hold free of any liability, the School District and the officers and employees, of any costs or expenses arising from patent, trademark or copyright infringement incurred by use of any item supplied or process used in performance of this Contract.

1.22 COVENANT AGAINST CONTINGENT FEES

A. The bidder warrants that no person or selling agency has been employed or retained to solicit or secure the Contract upon an agreement of understanding for a commission or percentage, brokerage, or contingent fee, excepting bona fide employees or bona fide established commercial or selling agencies maintained by the bidder for the purpose of securing business. For breach or violation of this warrantee the School District shall have the right to annul the Contract without liability or at its discretion to deduct from the contract price or otherwise recover the full amount of such commission, percentage, brokerage or contingent fees.

1.23 TAXES - EXEMPT

A. Since the School District is exempt, prices quoted shall not include Federal taxes or State of Local taxes. Tax Exemption number is (Available from Owner).

1.24 TRADE DISCOUNTS

A. All prices offered must be lowest net price after trade discounts have been considered.

B. Bids offering a percentage off list prices will not be accepted unless;
   1. Specifically requested in that manner;
   2. A copy of the referenced price list accompanies the bid.

1.25 COMMERCIAL WARRANTEE AND GUARANTEE CERTIFICATE

A. The supplier agrees that the supplies or services furnished under the Contract shall be covered by the most favorable commercial warranties the supplier gives to any customer for such supplies or services and that the rights and remedies provided herein are in addition to and do not limit any rights afforded to the District by any other clauses of the Contract. A final payment for performance shall not relieve the successful bidder of responsibility for faulty materials or workmanship.

1.26 INTERPRETATION OF SPECIFICATIONS

A. Should any bidder be in doubt as to the intention and meaning of the specifications, he may make inquiry to the Architect. Questions received less than three working days before the opening of bids may not be considered. All questions in order to be considered must be submitted in writing.

1.27 EXAMINATION OF SITE AND OTHER CONDITIONS BEARING ON THIS WORK

A. Before submitting proposal, bidders shall fully inform themselves of the nature of the work by personal examination of the site and by such means as they consider necessary, as to matters, conditions, or considerations bearing on or in any way affecting the preparation of their proposal.
   1. A bidder shall not at any time after the submission of his proposal claim that there is any misunderstanding in regard to the location, extent, or nature of the work to be performed.
   2. No claims for any extra will be allowed because of alleged impossibilities in the production of the results specified, or because of inadequate or improper plans or specifications, and whenever a result is required, the successful bidder shall furnish any and all extras and make any changes needed to produce, to the satisfaction of the District, the required results at no expense to the District.

B. Failure of the bidder to thoroughly understand all aspects of the solicitation before submitting their bid shall not be sufficient cause to permit withdrawal of its bid nor secure relief on pleas of error, after the contract is awarded.

1.28 BRAND NAMES AND APPROVED EQUAL

A. Where a particular manufacturer or several manufacturers, brands or models are referenced, it is to be interpreted as indicating the type or quality of material, and shall be interpreted to include an "approved equal". Bids may be considered on models or brands or products of manufacturers other than those specified if the items being substituted were approved by the designee of the District.

B. Where a manufacturer, brand, or model is referenced in the bid specifications, the absence of a reference to a different manufacturer, brand, or model in the bidder's proposal shall be interpreted as a bid on the manufacturer, brand, or model specified.

C. Where several manufacturers or models are referenced as being equally acceptable and the bidder does not indicate what particular model or brand they are offering, the Designee of the District shall have the right to select any brand or model referenced.

D. Only one bid per item will be considered. If a vendor submits more than one bid on an item, none of the vendor's bids on that item will be considered.

E. The Board of Education of the District shall be the sole judge as to whether or not items submitted meet specifications or whether or not items being bid are equal. Any attempt to "resell" or disqualify other supplies while the proposals are being analyzed may be reason for your bid to be disqualified.

F. All items furnished under the Contract must be new and unused, latest models (unless otherwise specified) and free from all defects. The foregoing exempts exchange, normal "rebuilt" items, where specified.

1.29 SAMPLES AND DESCRIPTIVE LITERATURE

A. When requesting approval to bid models, brands or products of manufacturers other than those specified, such a request must be accompanied by catalog cuts and/or detailed specifications. The District may also request bidders to submit samples for examination and appraisal.

B. Requested samples shall be submitted at no cost to the District and may be required by the District either prior to, at the time of the bid opening, or within ten calendar days following the request. Time of submission of samples shall be specified in the specifications. Samples shall be specified in the specifications. Samples not provided as requested, will be reason to reject the bid for that item. All such samples shall be identified as to the supplier, model number, bid item number and other information that may be required; these samples will be returned after evaluation. Suppliers shall have the responsibility of picking up their samples within two weeks after notification. Samples not removed after two weeks will automatically become the property of the District at no charge.

1.30 RESPONSIBILITY FOR DAMAGE AND CARE OF SCHOOL PROPERTY

A. The Supplier in the performance of this Contract will be held financially responsible for any damage to the grounds, buildings, or equipment caused by him, his subcontractors or employees, or other persons engaged in the performance of the Contract.

B. Every reasonable effort shall be made by workmen to proceed with the work as described in these specifications in a manner accepted in trade circles as the highest level of workmanship. The successful bidder for this work shall be responsible for all damage to other work caused by his workmen or through the neglect of his workmen on the site.

C. Workmanlike care shall be expected at all times in performing the work. It shall be the responsibility of the successful bidder to repair or replace all damaged property, the damage for which he or anyone working under his direction is responsible.

1.31 SUPPLIER CLEAN-UP

A. All debris resulting from the supplier's delivery and installation shall be disposed of entirely by the supplier in an efficient and expeditious manner as required and directed by the District Designee. The successful bidder shall at all times keep the premises free from accumulation of waste materials or rubbish caused by his employees or work. District-owned trash receptacles are not to be used by the vendor without prior approval.

1.32 STORAGE OF MATERIALS

A. Every effort shall be made by the successful bidder to schedule delivery of materials so that a minimum of storage space is required. The successful bidder shall not encumber

the premises with his materials and shall store all materials in a place designated by the District or its representative. The District will not be responsible for any damage to or theft of tools or materials used in this work.

1.33 UNPACKING AND ASSEMBLING

A. All work described in the specifications regarding unpacking, assembling, and placement of all movable furniture and/or equipment must be completed within five (5) days after furniture and/or equipment is received on the site unless prior approval is received.

B. Any bidder failing to unpack and assemble knockdown equipment and furniture will be charged (deduction will be made from billing) a fee to cover the District's cost of unpacking and assembling.

1.34 SERVICE

A. Each bidder may be required to submit a signed statement to the effect he can furnish service by factory trained personnel Monday to Friday during the hours of 8:00 a.m. - 4:00 p.m.

1.35 SCHEDULE FOR PERFORMANCE OF WORK

A. All work described in these specifications must be completed with reasonable promptness. The District shall be the sole judge of what is "reasonably prompt" under the circumstances. If the successful bidder does not begin the work in a reasonable amount of time, it will be notified that if it fails to initiate the work promptly, the contract may be terminated and the District will forthwith proceed to collect for nonperformance of the work.

1.36 ORDERING

A. All items or services to be furnished under the Contract will be ordered by the issuance of a Purchase Order signed by two authorized representatives of the District. This document must be in the hands of the successful bidder prior to any work commencing on the Contract.

1.37 DELIVERY, INSPECTION, ACCEPTANCE, AND PACKAGING

A. All supplies, materials, equipment, goods, and services are to be delivered postpaid to the location or locations indicated on the Proposal Form, Specifications, or Purchase Order. No labor will be provided to help unload any product under Contract.

B. The delivery of goods or items furnished under the terms of the Contract shall not be considered as acceptance thereof until the goods are inspected. The District shall have a reasonable opportunity to inspect. If, for example, goods are delivered on August 1, the District may not have a reasonable opportunity to inspect such goods until September or October. In all events, shipping invoices or other documents sent with goods shall not be controlling with respect to the timing of inspection. The inspection and test by the District of any supplies or lots thereof does not relieve the supplier from any responsibility regarding defects or other failure to meet the Contract requirements, which may be discovered subsequent to delivery. Except as otherwise provided in the Contract, acceptance shall be conclusive except as regards to patent defects, fraud, or such gross mistakes as amount to fraud.

C. Any item to be supplied as a result of this Contract shall be subject to inspection and test by the Ordering Office, to the extent practicable, at all times and places including the period of manufacture and in any event prior to acceptance.

D. In case any item or lots of items are found to be defective in material or workmanship or otherwise not in conformity with the requirements of the Contract, the Ordering Office shall have the right to either reject them (with or without instructions as to their disposition) or to require their correction. Items or lots of items which have been rejected or required to be corrected shall be removed or, if required by the Ordering Office as they may deem appropriate, corrected in place by and at the expense of the supplier promptly after notice, and shall not thereafter be tendered for acceptance unless the former rejection or requirement of correction is disclosed. If the supplier fails to promptly remove such items or lots of items which are required to be removed, or promptly to replace or correct such items or lots of items, the District either (1) may re-contract or otherwise, replace or correct such items and charge the supplier the cost occasioned the District thereby, or (2) may terminate the Contract for default as provided in the clause of the Contract entitled "Failure to comply with Contract".

E. Acceptance or rejection of any items shall be made as promptly as practicable after delivery, except as otherwise provided in the Contract; but failure to inspect and accept or reject items shall neither relieve the supplier from responsibility for such items as are not in accordance with the Contract requirements nor impose liability on the District therefore.

F. Neither the School District nor other Ordering Office will assume responsibility for damage to any rejected delivery caused by weather, improper warehousing, or mishandling.

G. All outer packs of items delivered under the Contract (except subsistence items delivered to cafeterias) must be marked with the Purchase Order/Contract number and item identification.
   1. Failure to provide adequate identifying markings may result in refusal of the delivery.

H. Unless otherwise stated, all prices include delivery and placement within the ship-to-address in that area specified in the Contract or Purchase Order.

I. Collect shipments will not be accepted.

J. All shipments shall be F.O.B. point of destination as indicated in the Proposal or on the Purchase Order.

1.38 INVOICES

A. Invoices must be completely identifiable, supported by delivery receipts where specified, and contain the following minimum information:
   1. Purchase Order/Contract number.
   2. Delivery destination as it appears on the Purchase Order.
   3. Contract item number, quantity and description of item billed.
   4. Unit price and extended price of each item.
   5. Total amount of invoice.
   6. Any prompt payment discount offered.

1.39 INDEMNIFICATION

A. By submitting a bid, all bidders agree that in the event they are awarded a contract, they will indemnify and otherwise hold harmless the District, its agents and employees from any and all liability, suits, actions or claims, together with all costs, expenses or attorneys'

fees, arising out of their performance of work or supplying materials and services in connection with the contract. This agreement to indemnify and hold harmless shall cover all suits, actions, claims or liabilities asserted against the District, its agents and employees, regardless of whether such suits, actions, claims or liabilities are based upon acts or failures to act attributable to the District or its employees or agents, to the extent that it shall be also determined that the acts, or failure to act are attributable, in whole or in part, to such bidders or its employees or agents.

1.40 ASSIGNMENT OF ANTITRUST CLAIMS

A. As consideration for the award and execution by the Board(s) of this contract, the successful bidder hereby grants, conveys, sells, assigns, and transfers to the State of Delaware all of its right, title and interest in and to all known or unknown causes of action it presently has or may now or hereafter acquire under the antitrust laws of the United States and the State of Delaware, relating to the particular goods or services purchased or acquired by the Board(s) pursuant to this contract.

1.41 HAZARDOUS MATERIALS

A. As required in the Hazardous Chemical Information Act of June, 1984, all vendors supplying any materials that may be defined as hazardous must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it is known to be present in the work place, and if employees may be exposed under normal conditions or in any foreseeable emergency situation.

B. Material Safety Data Sheets must be provided directly to each School along with the shipping slips that includes those products.

1.42 CONTRACT DOCUMENTS

A. These General Instructions and any Special Instructions, Bid Specifications, Requests for Bid, Bid Proposal Form, Purchase Order, and Contract shall be a part of and constitute the contract entered into by the District and any successful bidder. In the event there is any discrepancy between any of the foregoing contract documents, the following order of documents governs so that the former prevails over the latter: Contract, Purchase Order, Bid Specifications, Special Instructions, General Instructions, Requests for Bid and Bid Proposal Form.

1.43 THE CONTRACT

A. This Contract shall be governed by Delaware law, and any dispute concerning the interpretation or application of this Contract, and any documents incorporated by reference into this Contract, or any materials supplied or work performed under this Contract must be heard in Delaware.

1.44 TRANSFER OF BIDS

A. The District named in this bid and the successful bidder may reach an agreement to make available to any agency or school district in the State the bid prices submitted for this contract. Where such an agreement exists, the District named shall have access to purchase under the contract.

1.45 CONTRACT REQUIREMENTS:

A. This contract will be issued to cover the General requirements for multiple locations of the District, as noted in this project manual _____.

1.46 CONTRACT PERIOD:

A. Each vendor's contract shall be valid for a period from Authorization to Proceed through completion.

1.47 PRICES

A. Prices will remain firm for the term of the contract.

1.48 MANDATORY INSURANCE REQUIREMENTS

A. Before any work is done hereunder, the Certificate of Insurance and/or copies of the insurance policies, referencing the contract number stated herein, shall be filed with the State. The certificate holder is as follows:

As required in Section 009000

1.49 BASIS OF AWARD:

A. The Owner shall award this contract to the lowest responsible and responsive bidder(s) who best meets the terms and conditions of the bid. .

B. The Owner reserves the right to reject any or all bids in whole or in part, to make multiple awards, partial awards, award by types, item by item, or lump sum total, whichever may be most advantageous to the District.

1.50 HOLD HARMLESS:

A. The successful bidder agrees that it shall indemnify and hold the District and all its agencies harmless from and against any and all claims for injury, loss of life, or damage to or loss of use of property caused or alleged to be caused by acts or omissions of the successful bidder, its employees, and invitees on or about the premises and which arise out of the successful bidder's performance, or failure to perform as specified in the Agreement.

1.51 NON-PERFORMANCE:

A. In the event the vendor does not fulfill its obligations under the terms and conditions of this contract, the ordering agency may purchase equivalent product on the open market any difference in cost between the contract prices herein and the price of open market product shall be the responsibility of the vendor. Under no circumstances shall monies be due the vendor in the event open market products can be obtained below contract cost. Any monies charged to the vendor may be deducted from an open invoice.

1.52 PAYMENT:

A. The agencies or school districts involved will authorize and process for payment each invoice within thirty (30) days after the date of receipt.

1.53 ALTERNATE BIDS AND SUBSTITUTIONS:

A. All alternate bids/substitutions must be accompanied with the following information for each item in order to be considered for award.
   1. Completed bid forms
   2. Written list, stating deviations from specified product.
   3. Product literature and manufacturers specifications.
   4. Warranty Information.

B. All vendors should also be prepared to provide a sample of the exact item bid for evaluation purposes within 48 hours of a request to provide this information. Failure of a

vendor to meet any of these terms will result in an automatic rejection of the vendor's bid for items that do not comply with these requirements.

C. The District and the Architect reserve sole discretion on the final selections based on any and all criteria and any or all General Conditions, Special Instructions or Supplementary Conditions.

1.54 QUANTITIES:

A. Quantities listed in this Specification are the anticipated needs for this contract. Except where budget constraints would prohibit ordering those quantities, the quantities stated are, to the best of the District's knowledge, the minimum amounts. The right to increase or decrease quantities is reserved and the unit price quoted on the bid form shall remain as quoted for the contract period.

1.55 PUNCH LIST:

A. Vendor(s) shall complete punch list items in a timely manner. Final payment will not be issued until punch list items are complete to Owner's satisfaction

END OF SECTION

SECTION 011000
SUMMARY

PART 1 GENERAL

1.01 PROJECT

A. Project Name: Mount Pleasant High School Servery Upgrades.

B. Owner's Name: Brandywine School District.

C. Architect's Name: ABHA Architects .

D. The Project consists of upgrades to the servery area of the cafeteria. Work includes demolition, new walls, coiling doors, finishes and associated mechanical,electrical, plumbing and fire protection. Owner has purchased and will provide kitchen equipment..

1.02 CONTRACT DESCRIPTION

A. Contract Type: A single prime contract based on a Stipulated Price.

1.03 WORK BY OWNER

A. Owner has awarded a contract for supply and installation of kitchen equipment . Coordinate with Owner's contractor as required. _____ _____

1.04 OWNER OCCUPANCY

A. Owner intends to continue to occupy adjacent portions of the existing building during the entre period of construction for the conduct of normal operations. .

B. Cooperate with Owner to minimize conflict and to facilitate Owner's operations.

C. Construct work to accommodate the Owner's use of the premises during the construction period. Coordinate with the Owner's Representative to minimize inconvenience to faculty, students and parents/guardians.

1.05 TIME OF START AND COMPLETION

A. Site is available for start of work on June 12 2017

B. The Work shall be Substantially Complete within 65 calendar days after issuance of Notice to Proceed (if any) or Date of Contract, whichever is earlier.

1. Provide double shifts and/or overtime if required to meet Substantial Completion date.
2. Work must be completed by August 4 2017
3. Minor work may be permitted after occupancy.

1.06 LIQUIDATED DAMAGES

A. There are no Liquidated Damages applying to this Work.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 012000
PRICE AND PAYMENT PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Procedures for preparation and submittal of applications for progress payments.

B. Documentation of changes in Contract Sum and Contract Time.

C. Change procedures.

D. Correlation of Contractor submittals based on changes.

E. Procedures for preparation and submittal of application for final payment.

1.02 RELATED REQUIREMENTS

A. Section 005000 - Contracting Forms and Supplements: Forms to be used.

B. Document 007300 - Supplementary Conditions: Percentage allowances for Contractor's overhead and profit.

C. Section 012100 - Allowances: Payment procedures relating to allowances.

D. Section 012200 - Unit Prices: Monetary values of unit prices, payment and modification procedures relating to unit prices.

1.03 SCHEDULE OF VALUES

A. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit draft to Engineer for approval.

B. Forms filled out by hand will not be accepted.

C. Submit Schedule of Values in duplicate within 15 days after date of Owner-Contractor Agreement.

D. Include in each line item, the amount of Allowances specified in Section 01210. For unit cost Allowances, identify quantities taken from Contract Documents multiplied by the unit cost to achieve the total for the item.

1.04 APPLICATIONS FOR PROGRESS PAYMENTS

A. Payment Period: Submit at intervals stipulated in the Agreement.

B. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit sample to Engineer for approval.

C. Forms filled out by hand will not be accepted.

D. Execute certification by signature of authorized officer.

E. Use data from approved Schedule of Values. Provide dollar value in each column for each line item for portion of work performed and for stored Products.

F. List each executed Change Order as a separate line item, listing Change Order number and dollar amount as for an original item of Work.

G. Submit three copies of each Application for Payment.

H. Include the following with the application:

1. Insurance certificates for off-site stored products.

1.05 MODIFICATION PROCEDURES

A. Submit name of the individual authorized to receive change documents and who will be responsible for informing others in Contractor's employ or subcontractors of changes to the Contract Documents.

B. For minor changes not involving an adjustment to the Contract Sum or Contract Time, Engineer will issue instructions directly to Contractor.

C. For other required changes, Engineer will issue a document signed by Owner instructing Contractor to proceed with the change, for subsequent inclusion in a Change Order.
   1. The document will describe the required changes and will designate method of determining any change in Contract Sum or Contract Time.
   2. Promptly execute the change.

D. For changes for which advance pricing is desired, Engineer will issue a Contract Modification Request (CMR) that includes a detailed description of a proposed change with supplementary or revised drawings and specifications, a change in Contract Time for executing the change, with a stipulation of any overtime work required and the period of time during which the requested price will be considered valid. Contractor shall prepare and submit a fixed price quotation, including changes in Contract Time, if necessary, .
   1. Such request is for information only, and is not an instruction to execute the changes, nor to stop work in progress.
   2. Format for Contract Modification Requests shall be as issued by the Architect at the Pre-Construction meeting.

E. Contractor may propose a change by submitting a change order request for change to Engineer, describing the proposed change and its full effect on the Work, with a statement describing the reason for the change, and the effect on the Contract Sum and Contract Time with full documentation and a statement describing the effect on Work by separate or other contractors.

F. Computation of Change in Contract Amount: As specified in the Agreement and Conditions of the Contract.

G. Substantiation of Costs: Provide full information required for evaluation.
   1. Provide following data:
      a. Quantities of products, labor, and equipment.
      b. Taxes, insurance, and bonds.
      c. Overhead and profit.
      d. Justification for any change in Contract Time.
      e. Credit for deletions from Contract, similarly documented.
   2. Support each claim for additional costs, including time and material work, with additional information:
      a. Origin and date of claim.
      b. Dates and times work was performed, and by whom.
      c. Time records and wage rates paid.
      d. Invoices and receipts for products, equipment, and subcontracts, similarly documented.
   3. For Time and Material work, submit itemized account and supporting data after completion of change, within time limits indicated in the Conditions of the Contract.

H. When the information in the Contract Modification Request and Change Order Request is complete, it will be submitted to the Architect for review and forwarded to the Owner. If the change is agreed to by the Owner, the Architect will prepare a Change Order and forward it to the Contractor for signature.

I. Execution of Change Orders: Engineer will issue Change Orders for signatures of parties as provided in the Conditions of the Contract.

J. After execution of Change Order by all parties, promptly revise Schedule of Values and Application for Payment forms to record each authorized Change Order as a separate line item and adjust the Contract Sum.

K. Promptly revise progress schedules to reflect any change in Contract Time, revise sub-schedules to adjust times for other items of work affected by the change, and resubmit.

L. Promptly enter changes in Project Record Documents.

1.06 APPLICATION FOR FINAL PAYMENT

A. Prepare Application for Final Payment as specified for progress payments, identifying total adjusted Contract Sum, previous payments, and sum remaining due.

B. Application for Final Payment will not be considered until the following have been accomplished:
   1. All closeout procedures specified in Section 017000.
   2. All Closeout submittals as specified in Section 017800.
   3. Submit Affidavit of Payment of Indebtedness: See General Conditions.
   4. Submit Consent of Surety to Final Payment: See General Conditions.
   5. Submit Releases of Liens: See General Conditions. Release forms shall conform to State law governing mechanics Liens and shall be transmitted with AIA Document G706A. Note that Document G706A is not a release of liens and must be accompanied by actual releases.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 017800
CLOSEOUT SUBMITTALS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Project Record Documents.

B. Operation and Maintenance Data.

C. Warranties and bonds.

1.02 RELATED REQUIREMENTS

A. Section 007200 - General Conditions: Performance bond and labor and material payment bonds, warranty, and correction of work.

B. Section 013000 - Administrative Requirements: Submittals procedures, shop drawings, product data, and samples.

C. Section 017000 - Execution and Closeout Requirements: Contract closeout procedures.

D. Individual Product Sections: Specific requirements for operation and maintenance data.

E. Individual Product Sections: Warranties required for specific products or Work.

1.03 SUBMITTALS

A. Project Record Documents: Submit documents to Engineer with claim for final Application for Payment.

B. Operation and Maintenance Data:

1. Submit two copies of preliminary draft or proposed formats and outlines of contents before start of Work. Engineer will review draft and return one copy with comments.
2. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit completed documents within ten days after acceptance.
3. Submit one copy of completed documents 15 days prior to final inspection. This copy will be reviewed and returned , with Engineer comments. Revise content of all document sets as required prior to final submission.
4. Submit two sets of revised final documents in final form within 10 days after final inspection.

C. Warranties and Bonds:

1. For equipment or component parts of equipment put into service during construction with Owner's permission, submit documents within 10 days after acceptance.
2. Make other submittals within 10 days after Date of Substantial Completion, prior to final Application for Payment.
3. For items of Work for which acceptance is delayed beyond Date of Substantial Completion, submit within 10 days after acceptance, listing the date of acceptance as the beginning of the warranty period.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PROJECT RECORD DOCUMENTS

A. Maintain on site one set of the following record documents; record actual revisions to the Work:
   1. Drawings.
   2. Addenda.
   3. Change Orders and other modifications to the Contract.

B. Ensure entries are complete and accurate, enabling future reference by Owner.

C. Store record documents separate from documents used for construction.

D. Record information concurrent with construction progress.

E. Record Drawings : Legibly mark each item to record actual construction including:
   1. Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
   2. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
   3. Field changes of dimension and detail.
   4. Details not on original Contract drawings.

3.02 OPERATION AND MAINTENANCE DATA

A. Source Data: For each product or system, list names, addresses and telephone numbers of Subcontractors and suppliers, including local source of supplies and replacement parts.

B. Product Data: Mark each sheet to clearly identify specific products and component parts, and data applicable to installation. Delete inapplicable information.

C. Drawings: Supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams. Do not use Project Record Documents as maintenance drawings.

D. Typed Text: As required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions.

3.03 OPERATION AND MAINTENANCE DATA FOR MATERIALS AND FINISHES

A. For Each Product, Applied Material, and Finish:
   1. Product data, with catalog number, size, composition, and color and texture designations.

B. Instructions for Care and Maintenance: Manufacturer's recommendations for cleaning agents and methods, precautions against detrimental cleaning agents and methods, and recommended schedule for cleaning and maintenance.

C. Moisture protection and weather-exposed products: Include product data listing applicable reference standards, chemical composition, and details of installation. Provide recommendations for inspections, maintenance, and repair.

D. Additional information as specified in individual product specification sections.

E. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.

3.04 OPERATION AND MAINTENANCE DATA FOR EQUIPMENT AND SYSTEMS

A. For Each Item of Equipment and Each System:
   1. Description of unit or system, and component parts.
   2. Identify function, normal operating characteristics, and limiting conditions.
   3. Include performance curves, with engineering data and tests.
   4. Complete nomenclature and model number of replaceable parts.

B. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.

C. Panelboard Circuit Directories: Provide electrical service characteristics, controls, and communications; typed.

D. Include color coded wiring diagrams as installed.

E. Operating Procedures: Include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.

F. Maintenance Requirements: Include routine procedures and guide for preventative maintenance and trouble shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.

G. Provide servicing and lubrication schedule, and list of lubricants required.

H. Include manufacturer's printed operation and maintenance instructions.

I. Include sequence of operation by controls manufacturer.

J. Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.

K. Provide control diagrams by controls manufacturer as installed.

L. Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.

M. Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.

N. Additional Requirements: As specified in individual product specification sections.

3.05 ASSEMBLY OF OPERATION AND MAINTENANCE MANUALS

A. Assemble operation and maintenance data into durable manuals for Owner's personnel use, with data arranged in the same sequence as, and identified by, the specification sections.

B. Where systems involve more than one specification section, provide separate tabbed divider for each system.

C. Prepare instructions and data by personnel experienced in maintenance and operation of described products.

D. Prepare data in the form of an instructional manual.

E. Binders: Commercial quality, 8-1/2 by 11 inch (216 by 280 mm) three D side ring binders with durable plastic covers; 3 inch (____ mm) maximum ring size. When multiple binders are used, correlate data into related consistent groupings.

F. Cover: Identify each binder with typed or printed title OPERATION AND MAINTENANCE INSTRUCTIONS; identify title of Project; identify subject matter of contents.

G. Project Directory: Title and address of Project; names, addresses, and telephone numbers of Engineer, Consultants, Contractor and subcontractors, with names of responsible parties.

H. Tables of Contents: List every item separated by a divider, using the same identification as on the divider tab; where multiple volumes are required, include all volumes Tables of Contents in each volume, with the current volume clearly identified.

I. Dividers: Provide tabbed dividers for each separate product and system; identify the contents on the divider tab; immediately following the divider tab include a description of product and major component parts of equipment.

J. Text: Manufacturer's printed data, or typewritten data on 24 pound paper.

K. Drawings: Provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.

L. Arrange content by products and systems under section numbers and sequence of Table of Contents of this Project Manual.
   1. Operating instructions.
   2. Maintenance instructions for equipment and systems.
   3. Maintenance instructions for special finishes, including recommended cleaning methods and materials, and special precautions identifying detrimental agents.

M. Table of Contents: Provide title of Project; names, addresses, and telephone numbers of Engineer, Consultants, and Contractor with name of responsible parties; schedule of products and systems, indexed to content of the volume.

3.06 WARRANTIES AND BONDS

A. Obtain warranties and bonds, executed in duplicate by responsible Subcontractors, suppliers, and manufacturers, within 10 days after completion of the applicable item of work. Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial completion is determined.

B. Verify that documents are in proper form, contain full information, and are notarized.

C. Co-execute submittals when required.

D. Retain warranties and bonds until time specified for submittal.

E. Include originals of each in operation and maintenance manuals, indexed separately on Table of Contents.

END OF SECTION

SECTION 02 4100
DEMOLITION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Selective demolition of building elements for alteration purposes.

1.02 RELATED REQUIREMENTS

A. Section 01 1000 - Summary: Limitations on Contractor's use of site and premises.

B. Section 01 1000 - Summary: Description of items to be removed by Owner.

C. Section 01 1000 - Summary: Description of items to be salvaged or removed for re-use by Contractor.

D. Section 01 5000 - Temporary Facilities and Controls: Site fences, security, protective barriers, and waste removal.

E. Section 01 6000 - Product Requirements: Handling and storage of items removed for salvage and relocation.

F. Section 01 7000 - Execution and Closeout Requirements: Project conditions; protection of bench marks, survey control points, and existing construction to remain; reinstallation of removed products; temporary bracing and shoring.

G. Section 31 2323 - Fill: Fill material for filling holes, pits, and excavations generated as a result of removal operations.

1.03 REFERENCE STANDARDS

A. 29 CFR 1926 - U.S. Occupational Safety and Health Standards; current edition.

B. NFPA 241 - Standard for Safeguarding Construction, Alteration, and Demolition Operations; 2013.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Project Record Documents: Accurately record actual locations of capped and active utilities and subsurface construction.

PART 2 PRODUCTS

2.01 MATERIALS

A. Fill Material: As specified in Section 31 2323 - Fill.

PART 3 EXECUTION

3.01 SCOPE

A. Remove items as indicated on drawings..

B. Fill excavations, open pits, and holes in ground areas generated as result of removals, using specified fill; compact fill as specified in Section 31 2323 - Fill.

3.02 GENERAL PROCEDURES AND PROJECT CONDITIONS

A. Comply with applicable codes and regulations for demolition operations and safety of adjacent structures and the public.

1. Obtain required permits.

2. Take precautions to prevent catastrophic or uncontrolled collapse of structures to be removed; do not allow worker or public access within range of potential collapse of unstable structures.
3. Provide, erect, and maintain temporary barriers and security devices.
4. Conduct operations to minimize effects on and interference with adjacent structures and occupants.
5. Do not close or obstruct roadways or sidewalks without permit.
6. Conduct operations to minimize obstruction of public and private entrances and exits; do not obstruct required exits at any time; protect persons using entrances and exits from removal operations.

B. Do not begin removal until receipt of notification to proceed from Owner.

C. Do not begin removal until built elements to be salvaged or relocated have been removed.

D. Protect existing structures and other elements that are not to be removed.
1. Provide bracing and shoring.
2. Prevent movement or settlement of adjacent structures.
3. Stop work immediately if adjacent structures appear to be in danger.

E. Minimize production of dust due to demolition operations; do not use water if that will result in ice, flooding, sedimentation of public waterways or storm sewers, or other pollution.

F. If hazardous materials are discovered during removal operations, stop work and notify Architect and Owner; hazardous materials include regulated asbestos containing materials, lead, PCB's, and mercury.

3.03 EXISTING UTILITIES

A. Protect existing utilities to remain from damage.

B. Do not close, shut off, or disrupt existing life safety systems that are in use without at least 7 days prior written notification to Owner.

C. Do not close, shut off, or disrupt existing utility branches or take-offs that are in use without at least 3 days prior written notification to Owner.

D. Locate and mark utilities to remain; mark using highly visible tags or flags, with identification of utility type; protect from damage due to subsequent construction, using substantial barricades if necessary.

E. Remove exposed piping, valves, meters, equipment, supports, and foundations of disconnected and abandoned utilities.

F. Prepare building demolition areas by disconnecting and capping utilities outside the demolition zone; identify and mark utilities to be subsequently reconnected, in same manner as other utilities to remain.

3.04 SELECTIVE DEMOLITION FOR ALTERATIONS

A. Drawings showing existing construction and utilities are based on casual field observation and existing record documents only.
1. Verify that construction and utility arrangements are as shown.
2. Report discrepancies to Architect before disturbing existing installation.
3. Beginning of demolition work constitutes acceptance of existing conditions that would be apparent upon examination prior to starting demolition.

B. Separate areas in which demolition is being conducted from other areas that are still occupied.

1. Provide, erect, and maintain temporary dustproof partitions of construction specified in Section 01 5000 in locations indicated on drawings.

C. Remove existing work as indicated and as required to accomplish new work.
   1. Remove items indicated on drawings.

D. Services (Including but not limited to HVAC, Plumbing, Fire Protection, Electrical, and Telecommunications): Remove existing systems and equipment as indicated.
   1. Maintain existing active systems that are to remain in operation; maintain access to equipment and operational components.
   2. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
   3. Verify that abandoned services serve only abandoned facilities before removal.
   4. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings; remove back to source of supply where possible, otherwise cap stub and tag with identification.

E. Protect existing work to remain.
   1. Prevent movement of structure; provide shoring and bracing if necessary.
   2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
   3. Repair adjacent construction and finishes damaged during removal work.
   4. Patch as specified for patching new work.

3.05 DEBRIS AND WASTE REMOVAL

A. Remove debris, junk, and trash from site.

B. Leave site in clean condition, ready for subsequent work.

C. Clean up spillage and wind-blown debris from public and private lands.

END OF SECTION

SECTION 04 2000
UNIT MASONRY

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Concrete Block.

B. Ceramic Glazed Structural Clay Facing Tile.

C. Mortar and Grout.

D. Reinforcement and Anchorage.

E. Lintels.

F. Accessories.

1.02 RELATED REQUIREMENTS

A. Section 05 5000 - Metal Fabrications: Loose steel lintels.

B. Section 07 9200 - Joint Sealants: Sealing control and expansion joints.

1.03 REFERENCE STANDARDS

A. ACI 530/530.1/ERTA - Building Code Requirements and Specification for Masonry Structures and Related Commentaries; 2013.

B. ASTM A615/A615M - Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement; 2016.

C. ASTM A641/A641M - Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire; 2009a (Reapproved 2014).

D. ASTM A1064/A1064M - Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete; 2015.

E. ASTM C90 - Standard Specification for Loadbearing Concrete Masonry Units; 2016.

F. ASTM C126 - Standard Specification for Ceramic Glazed Structural Clay Facing Tile, Facing Brick, and Solid Masonry Units; 2016.

G. ASTM C150/C150M - Standard Specification for Portland Cement; 2016.

H. ASTM C270 - Standard Specification for Mortar for Unit Masonry; 2014a.

I. ASTM C404 - Standard Specification for Aggregates for Masonry Grout; 2011.

J. ASTM C979/C979M - Standard Specification for Pigments for Integrally Colored Concrete; 2016.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data for masonry units, fabricated wire reinforcement, mortar, and masonry accessories.

C. Samples: Submit four samples of decorative block and salvaged structural galzed block units to illustrate color, texture, and extremes of color range.

D. Manufacturer's Certificate: Certify that masonry units meet or exceed specified requirements.

1.05 DELIVERY, STORAGE, AND HANDLING

A. Deliver, handle, and store masonry units by means that will prevent mechanical damage and contamination by other materials.

B. Handle and store ceramic glazed masonry units in protective cartons or trays. Do not remove from protective packaging until ready for installation.

PART 2 PRODUCTS

2.01 CONCRETE MASONRY UNITS

A. Concrete Block: Comply with referenced standards and as follows:
   1. Size: Standard units with nominal face dimensions of 16 by 8 inches and nominal depths as indicated on the drawings for specific locations.
   2. Load-Bearing Units: ASTM C90, normal weight.

2.02 CLAY TILE UNITS

A. Ceramic Glazed Structural Clay Facing Tile: ASTM C126; Grade S (Select); Type I (single-faced units).

B. Color and texture: match existing.

C. Size: 6T Series, thickness as indicated.

D. Special shapes: Molded units as required by conditions indicated, unless standard units can be sawn without chipping to produce equivalent effect.

2.03 **MORTAR** AND GROUT **MATERIALS**

A. Portland Cement: ASTM C150/C150M, Type I; color as required to produce approved color sample.

B. Grout Aggregate: ASTM C404.

C. Pigments for Colored Mortar: Pure, concentrated mineral pigments specifically intended for mixing into mortar and complying with ASTM C979/C979M.

2.04 REINFORCEMENT AND ANCHORAGE

A. Reinforcing Steel: ASTM A615/A615M, Grade 40 (40,000 psi), deformed billet bars; galvanized.

B. Single Wythe Joint Reinforcement: Truss or ladder type; ASTM A1064/A1064M steel wire, mill galvanized to ASTM A641/A641M, Class 3; 0.1483 inch side rods with 0.1483 inch cross rods; width as required to provide not more than 1 inch and not less than 1/2 inch of mortar coverage on each exposure.

2.05 LINTELS

A. Prefabricated Steel Lintels: Refer to Section 05 5000.

2.06 MORTAR AND GROUT **MIXES**

A. Mortar for Unit Masonry: ASTM C270, using the Proportion Specification.
   1. Interior, loadbearing masonry: Type N.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive masonry.

B. Verify that related items provided under other sections are properly sized and located.

C. Verify that built-in items are in proper location, and ready for roughing into masonry work.

3.02 PREPARATION

A. Direct and coordinate placement of metal anchors supplied for installation under other sections.

B. Provide temporary bracing during installation of masonry work. Maintain in place until building structure provides permanent bracing.

3.03 COURSING

A. Establish lines, levels, and coursing indicated. Protect from displacement.

B. Maintain masonry courses to uniform dimension. Form vertical and horizontal joints of uniform thickness.

C. Concrete Masonry Units:
   1. Bond: Running.
   2. Coursing: One unit and one mortar joint to equal 8 inches.
   3. Mortar Joints: Concave.

D. Clay Tile Units:
   1. Bond: Running.
   2. Coursing: One unit and one mortar joint to equal 6" inches or match existing.
   3. Mortar Joints: Concave.

3.04 REINFORCEMENT AND ANCHORAGE - GENERAL

A. Unless otherwise indicated on drawings or specified under specific wall type, install horizontal joint reinforcement 16 inches on center.

B. Place masonry joint reinforcement in first and second horizontal joints above and below openings. Extend minimum 16 inches each side of opening.

C. Lap joint reinforcement ends minimum 6 inches.

3.05 LINTELS

A. Install loose steel lintels over openings.

B. Maintain minimum 8 inch bearing on each side of opening.

3.06 BUILT-IN WORK

A. As work progresses, install built-in metal door frames and other items to be built into the work and furnished under other sections.

B. Install built-in items plumb, level, and true to line.

C. Bed anchors of metal door and glazed frames in adjacent mortar joints. Fill frame voids solid with grout.
   1. Fill adjacent masonry cores with grout minimum 12 inches from framed openings.

D. Do not build into masonry construction organic materials that are subject to deterioration.

3.07 TOLERANCES

A. Maximum Variation from Alignment of Columns: 1/4 inch.

B. Maximum Variation From Unit to Adjacent Unit: 1/16 inch.

C. Maximum Variation from Plane of Wall: 1/4 inch in 10 ft and 1/2 inch in 20 ft or more.

D. Maximum Variation from Plumb: 1/4 inch per story non-cumulative; 1/2 inch in two stories or more.

E. Maximum Variation from Level Coursing: 1/8 inch in 3 ft and 1/4 inch in 10 ft; 1/2 inch in 30 ft.

F. Maximum Variation of Mortar Joint Thickness: Head joint, minus 1/4 inch, plus 3/8 inch.

G. Maximum Variation from Cross Sectional Thickness of Walls: 1/4 inch.

3.08 CUTTING AND FITTING

A. Cut and fit for chases. Coordinate with other sections of work to provide correct size, shape, and location.

B. Obtain approval prior to cutting or fitting masonry work not indicated or where appearance or strength of masonry work may be impaired.

3.09 CLEANING

A. Remove excess mortar and mortar droppings.

B. Replace defective mortar. Match adjacent work.

C. Clean soiled surfaces with cleaning solution.

D. Use non-metallic tools in cleaning operations.

3.10 PROTECTION

A. Without damaging completed work, provide protective boards at exposed external corners that are subject to damage by construction activities.

END OF SECTION

SECTION 05 5213
PIPE AND TUBE RAILINGS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Floor mounted railings

1.02 REFERENCE STANDARDS

A. ASTM E935 - Standard Test Methods for Performance of Permanent Metal Railing Systems and Rails for Buildings; 2013.

B. ASTM E985 - Standard Specification for Permanent Metal Railing Systems and Rails for Buildings; 2000 (Reapproved 2006).

C. ASTM A167 - Standard Specification for stainless and heat resisting chromium nickel steel plate, sheet and strip.

D. ASTM A269 - Standard Specification for seamless and welded austentic stainless steel tubing.

E. AWS D1.6 - Structural Welding Code Stainless Steel; 2007

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Shop Drawings: Indicate profiles, sizes, connection attachments, anchorage, size and type of fasteners, and accessories.

C. Samples: Submit two, 6 inch long samples of handrail with finish.

PART 2 PRODUCTS

2.01 RAILINGS - GENERAL REQUIREMENTS

A. Design, fabricate, and test railing assemblies in accordance with the most stringent requirements of ASTM E985 and applicable local code.

B. Distributed Loads: Design railing assembly, wall rails, and attachments to resist distributed force of 75 pounds per linear foot applied to the top of the assembly and in any direction, without damage or permanent set. Test in accordance with ASTM E935.

C. Concentrated Loads: Design railing assembly, wall rails, and attachments to resist a concentrated force of 200 pounds applied at any point on the top of the assembly and in any direction, without damage or permanent set. Test in accordance with ASTM E935.

D. Dimensions: See drawings for configurations and heights.
   1. Top Rails and Wall Rails: 1-1/2 inches diameter, round.
   2. Posts: 1-1/2 inches diameter, round.

E. Provide anchors and other components as required to attach to structure, made of same materials as railing components unless otherwise indicated; where exposed fasteners are unavoidable provide flush countersunk fasteners.

2.02 STAINLESS STEEL RAILING SYSTEM

A. Provide metal free from pitting, seam marks, roller marks, grinding marks, and stains.

B. Pipe and tubing: ASTM A 269 Type 304

C. Finish: #4 directional

2.03 FABRICATION

A. Accurately form components to suit specific project conditions and for proper connection to building structure.

B. Fit and shop assemble components in largest practical sizes for delivery to site.

C. Fabricate components with joints tightly fitted and secured.

D. Welded Joints:

1. Interior Components: Continuously seal joined pieces by continuous welds.
2. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive work.

3.02 PREPARATION

A. Clean and strip primed steel items to bare metal where site welding is required.

B. Supply items required to be cast into concrete with setting templates, for installation as work of other sections.

3.03 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Install components plumb and level, accurately fitted, free from distortion or defects, with tight joints.

C. Anchor railings securely to structure.

3.04 TOLERANCES

A. Maximum Variation From Plumb: 1/4 inch per floor level, non-cumulative.

B. Maximum Offset From True Alignment: 1/4 inch.

C. Maximum Out-of-Position: 1/4 inch.

END OF SECTION

SECTION 06 1000
ROUGH CARPENTRY

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Concealed wood blocking, nailers, and supports.

1.02 RELATED REQUIREMENTS

1.03 REFERENCE STANDARDS

A. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.

B. AWPA U1 - Use Category System: User Specification for Treated Wood; 2012.

C. PS 20 - American Softwood Lumber Standard; 2010.

1.04 DELIVERY, STORAGE, AND HANDLING

A. General: Cover wood products to protect against moisture. Support stacked products to prevent deformation and to allow air circulation.

B. Fire Retardant Treated Wood: Prevent exposure to precipitation during shipping, storage, or installation.

PART 2 PRODUCTS

2.01 GENERAL REQUIREMENTS

A. Dimension Lumber: Comply with PS 20 and requirements of specified grading agencies.
   1. If no species is specified, provide any species graded by the agency specified; if no grading agency is specified, provide lumber graded by any grading agency meeting the specified requirements.
   2. Grading Agency: Any grading agency whose rules are approved by the Board of Review, American Lumber Standard Committee (www.alsc.org) and who provides grading service for the species and grade specified; provide lumber stamped with grade mark unless otherwise indicated.

B. Lumber fabricated from old growth timber is not permitted.

2.02 DIMENSION LUMBER FOR CONCEALED APPLICATIONS

A. Sizes: Nominal sizes as indicated on drawings, S4S.

B. Moisture Content: S-dry or MC19.

C. Miscellaneous Framing, Blocking, Nailers, Grounds, and Furring:
   1. Lumber: S4S, No. 2 or Standard Grade.
   2. Boards: Standard or No. 3.

2.03 FACTORY WOOD TREATMENT

A. Treated Lumber and Plywood: Comply with requirements of AWPA U1 - Use Category System for wood treatments determined by use categories, expected service conditions, and specific applications.
   1. Fire-Retardant Treated Wood: Mark each piece of wood with producer's stamp indicating compliance with specified requirements.

B. Fire Retardant Treatment:
   1. Interior Type A: AWPA U1, Use Category UCFA, Commodity Specification H, low temperature (low hygroscopic) type, chemically treated and pressure impregnated;

capable of providing a maximum flame spread index of 25 when tested in accordance with ASTM E84, with no evidence of significant combustion when test is extended for an additional 20 minutes.

a. Kiln dry wood after treatment to a maximum moisture content of 19 percent for lumber and 15 percent for plywood.
b. All interior rough carpentry items are to be fire retardant treated.
c. Do not use treated wood in applications exposed to weather or where the wood may become wet.

PART 3 EXECUTION

3.01 PREPARATION

A. Coordinate installation of rough carpentry members specified in other sections.

3.02 INSTALLATION - GENERAL

A. Select material sizes to minimize waste.

B. Reuse scrap to the greatest extent possible; clearly separate scrap for use on site as accessory components, including: shims, bracing, and blocking.

C. Where treated wood is used on interior, provide temporary ventilation during and immediately after installation sufficient to remove indoor air contaminants.

3.03 BLOCKING, NAILERS, AND SUPPORTS

A. Provide framing and blocking members as indicated or as required to support finishes, fixtures, specialty items, and trim.

B. In walls, provide blocking attached to studs as backing and support for wall-mounted items, unless item can be securely fastened to two or more studs or other method of support is explicitly indicated.

C. Where ceiling-mounting is indicated, provide blocking and supplementary supports above ceiling, unless other method of support is explicitly indicated.

3.04 TOLERANCES

A. Framing Members: 1/4 inch from true position, maximum.

B. Variation from Plane (Other than Floors): 1/4 inch in 10 feet maximum, and 1/4 inch in 30 feet maximum.

3.05 CLEANING

A. Waste Disposal: Comply with the requirements of Section 01 7419 - Construction Waste Management and Disposal.
   1. Comply with applicable regulations.
   2. Do not burn scrap on project site.
   3. Do not burn scraps that have been pressure treated.
   4. Do not send materials treated with pentachlorophenol, CCA, or ACA to co-generation facilities or “waste-to-energy” facilities.

B. Do not leave any wood, shavings, sawdust, etc. on the ground or buried in fill.

C. Prevent sawdust and wood shavings from entering the storm drainage system.

END OF SECTION

SECTION 06 2000
FINISH CARPENTRY

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Finish carpentry items.

B. Wood door frames, glazed frames.

C. Hardware and attachment accessories.

1.02 RELATED REQUIREMENTS

A. Section 08 1416 - Flush Wood Doors.

1.03 REFERENCE STANDARDS

A. NEMA LD 3 - High-Pressure Decorative Laminates; 2005.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements for submittal procedures.

B. Shop Drawings: Indicate materials, component profiles, fastening methods, jointing details, and accessories.

1.05 QUALITY ASSURANCE

A. Fabricator Qualifications: Company specializing in fabricating the products specified in this section with minimum five years of documented experience.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Protect work from moisture damage.

PART 2 PRODUCTS

2.01 FINISH CARPENTRY ITEMS

A. Interior Woodwork Items:
   1. Wood Doors and Hardware.
   2. Plastic Laminate:.

2.02 WOOD-BASED COMPONENTS

2.03 PLASTIC LAMINATE MATERIALS

A. Plastic Laminate: NEMA LD 3, HGS; color as selected by Architect; textured, low gloss finish; standard manufactured by Wilsonart.

2.04 SOLID SURFACE

A. Solid Surface: Color as selected by Architect.

B. Manufacturer: DuPont Corian

C. Color: Standard line up to price point C.

2.05 FASTENINGS

A. Adhesive for Purposes Other Than Laminate Installation: Suitable for the purpose; not containing formaldehyde or other volatile organic compounds.

2.06 ACCESSORIES

A. Aluminum Edge Trim: Extruded J shape; brushed surface finish; self locking serrated tongue; of width to match component thickness; clear anodized finish.

2.07 FABRICATION

A. Shop assemble work for delivery to site, permitting passage through building openings.

B. Cap exposed plastic laminate finish edges with aluminum trim.

C. When necessary to cut and fit on site, provide materials with ample allowance for cutting. Provide trim for scribing and site cutting.

D. Apply plastic laminate finish in full uninterrupted sheets consistent with manufactured sizes. Fit corners and joints hairline; secure with concealed fasteners. Slightly bevel arises. Locate counter butt joints minimum 2 feet from sink cut-outs.

END OF SECTION

SECTION 07 2616
UNDER-SLAB VAPOR BARRIER/RETARDER

PART 1 - GENERAL

1.01 SECTION INCLUDES

A. Refer to Scope Information Sheets for this contract bound in the Project Manual under Section 01 1000, Summary of Work. The Scope Information Sheets describe generally the work included in each contract, but the work is not necessarily limited to that described.

B. Vapor Barrier, seam tape, mastic, pipe boots, detail strip for installation under concrete slabs.

1.02 RELATED SECTIONS

A. Section 03300 Cast-in-place Structural Concrete

1.03 REFERENCES

A. American Society for Testing and Materials (ASTM)
   1. ASTM E 1745-97(2004) Standard Specification for Plastic Water Vapor Retarders Used in Contact with Soil or Granular Fill Under Concrete Slabs
   2. ASTM E 154-99(2005) Standard Test Methods for Water Vapor Retarders Used in Contact with Earth Under Concrete Slabs
   3. ASTM E 96-05 Standard Test Methods for Water Vapor Transmission of Materials
   4. ASTM E 1643-98(2005) Standard Practice for Installation of Water Vapor Retarders Used in Contact with Earth or Granular Fill Under Concrete Slabs

1.04 SUBMITTALS

A. Quality Control / Assurance
   1. Independent laboratory test results showing compliance with ASTM & ACI Standards.
   2. Manufacturer's samples, literature
   3. Manufacturer's installation instructions for placement, seaming and pipe boot installation

PART 2 - PRODUCTS

2.01 MATERIALS

A. Vapor Barrier
   1. Vapor Barrier must have the following qualities
      a. Perm rating less than or equal to 0.01 perms (grains/(ft2 *hr * in. Hg)) after conditioning as tested by:
         1) ASTM E 96

B. Vapor Barrier Products
   1. Vaporguard 3-ply laminate, aluminum core with two layers of multi-axially oriented, high density polyethylene by Reef Industries, Inc.

C. ACCESSORIES
   1. Seam Tape
      a. Tape must have the following qualities:
         1) Water Vapor Transmission Rate ASTM E 96: 0.3 perms or lower
   2. Vapor Proofing Mastic
      a. Mastic must have the following qualities:
         1) Water Vapor Transmission Rate ASTM E 96: 0.3 perms or lower
   3. Pipe Boots
      a. Provide manufacturer's supplied pipe boot system or construct pipe boots from vapor barrier material, pressure sensitive tape and/or mastic per manufacturer's instructions.

PART 3 - EXECUTION

3.01 PREPARATION

A. Ensure that subsoil is approved by architect or geotechnical firm
   1. Level and tamp or roll aggregate, sand or tamped earth base.

3.02 INSTALLATION

A. Install Vapor Barrier/Retarder:
   1. Installation shall be in accordance with manufacturer's instructions and ASTM E 1643.
      a. Unroll Vapor Barrier/Retarder with the longest dimension parallel with the direction of the pour.
      b. Lap Vapor Barrier/Retarder over footings and seal to foundation walls.
      c. Overlap joints 6 inches and seal with manufacturer's tape.
      d. Seal all penetrations (including pipes) per manufacturer's instructions.
      e. No penetration of the Vapor Barrier/Retarder is allowed except for reinforcing steel and permanent utilities.
      f. Repair damaged areas by cutting patches of Vapor Barrier/Retarder, overlapping damaged area 6 inches and taping all four sides with tape.

END OF SECTION

SECTION 07 9200
JOINT SEALANTS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Nonsag gunnable joint sealants.

B. Joint backings and accessories.

1.02 RELATED REQUIREMENTS

A. Section 09 3000 - Tiling: Sealant between tile and plumbing fixtures and at junctions with other materials and changes in plane.

1.03 REFERENCE STANDARDS

A. ASTM C834 - Standard Specification for Latex Sealants; 2014.

B. ASTM C920 - Standard Specification for Elastomeric Joint Sealants; 2014.

C. ASTM C1193 - Standard Guide for Use of Joint Sealants; 2013.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data for Sealants: Submit manufacturer's technical data sheets for each product to be used, that includes the following.
   1. Physical characteristics, including movement capability, VOC content, hardness, cure time, and color availability.
   2. List of backing materials approved for use with the specific product.
   3. Substrates that product is known to satisfactorily adhere to and with which it is compatible.
   4. Substrates the product should not be used on.

C. Color Cards for Selection: Where sealant color is not specified, submit manufacturer's color cards showing standard colors available for selection.

D. Samples for Verification: Where custom sealant color is specified, obtain directions from Architect and submit at least two physical samples for verification of color of each required sealant.

1.05 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

B. Installer Qualifications: Company specializing in performing the work of this section and with at least three years of documented experience.

C. Testing Agency Qualifications: Independent firm specializing in performing testing and inspections of the type specified in this section.

1.06 WARRANTY

A. See Section 01 7800 - Closeout Submittals, for additional warranty requirements.

B. Correct defective work within a five year period after Date of Substantial Completion.

C. Warranty: Include coverage for installed sealants and accessories that fail to achieve watertight seal , exhibit loss of adhesion or cohesion, or do not cure.

PART 2 PRODUCTS

2.01 JOINT SEALANT APPLICATIONS

A. Scope:
   1. Interior Joints: Do not seal interior joints unless specifically indicated to be sealed. Interior joints to be sealed include, but are not limited to, the following items.
      a. Joints between door, window, and other frames and adjacent construction.
      b. Joints between hollow metal door frames and resilient flooring.
      c. Joints between dissimilar exposed materials, unless otherwise indicated.
      d. Other joints indicated on drawings.

B. Interior Joints: Use nonsag Acrylic emulsion latex sealant, Type 2, unless otherwise indicated.
   1. Wall and Ceiling Joints in Non-Wet Areas: Acrylic emulsion latex sealant; Type 2.
   2. Joints between Fixtures in Wet Areas and Floors, Walls, and Ceilings: Mildew-resistant silicone sealant; ; Type 6.

C. Definitions:
   1. Interior Wet Areas: Bathrooms, restrooms, kitchens, food service areas, and food processing areas; fixtures in wet areas include plumbing fixtures, food service equipment, countertops, cabinets, and other similar items.

2.02 JOINT SEALANTS - GENERAL

A. Sealants and Primers: Provide products with levels of volatile organic compound (VOC) content as indicated in Section 01 6116.

B. Sealant Types Summary:
   1. Type 1: Non-Staining Silicone.
   2. Type 2: Acrylic Emulsion Latex
   3. Type 3: Non-Curing Butyl Sealant
   4. Type 4: Semi-Rigid Self-Leveling Polyurea Joint Filler
   5. Type 5: Acrylic Emulsion Latex
   6. Type 6: Mildew-Resistant Silicone Sealant

2.03 NONSAG JOINT SEALANTS

A. Type 6 - Mildew-Resistant Silicone Sealant: ASTM C920, Grade NS, Uses M and A; single component, mildew resistant; not expected to withstand continuous water immersion or traffic.
   1. Color: White or Clear.
   2. Manufacturers:
      a. Pecora Corporation; _____: www.pecora.com.
      b. Sika Corporation; Sikasil GP: www.usa-sika.com.
      c. Substitutions: See Section 01 6000 - Product Requirements.

B. Type 2 - Acrylic Emulsion Latex: Water-based; ASTM C834, single component, non-staining, non-bleeding, non-sagging; not intended for exterior use.
   1. Color: Standard colors matching finished surfaces, Type OP (opaque).
   2. Grade: ASTM C834; Grade - Minus 18 Degrees C.
   3. Manufacturers:
      a. Hilti, Inc; CP 506 Smoke and Acoustical Sealant: www.us.hilti.com/#sle.
      b. Pecora Corporation; ____: www.pecora.com.
      c. Sherwin-Williams Company; White Lightning 3006 Siliconized Acrylic Latex Caulk: www.sherwin-williams.com.

d. Tremco Global Sealants; Tremfles 834 Siliconized Acrylic Latex Selant: www.tremcosealants.com..
e. Substitutions: See Section 01 6000 - Product Requirements.

2.04 ACCESSORIES

A. Backer Rod: Cylindrical cellular foam rod with surface that sealant will not adhere to, compatible with specific sealant used, and recommended by backing and sealant manufacturers for specific application.

B. Backing Tape: Self-adhesive polyethylene tape with surface that sealant will not adhere to and recommended by tape and sealant manufacturers for specific application.

C. Masking Tape: Self-adhesive, nonabsorbent, non-staining, removable without adhesive residue, and compatible with surfaces adjacent to joints and sealants.

D. Joint Cleaner: Non-corrosive and non-staining type, type recommended by sealant manufacturer; compatible with joint forming materials.

E. Primers: Type recommended by sealant manufacturer to suit application; non-staining.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that joints are ready to receive work.

B. Verify that backing materials are compatible with sealants.

C. Verify that backer rods are of the correct size.

3.02 PREPARATION

A. Remove loose materials and foreign matter that could impair adhesion of sealant.

B. Clean joints, and prime as necessary, in accordance with manufacturer's instructions.

C. Perform preparation in accordance with manufacturer's instructions and ASTM C1193.

D. Mask elements and surfaces adjacent to joints from damage and disfigurement due to sealant work.

E. Concrete Floor Joints That Will Be Exposed in Completed Work: Test joint filler in inconspicuous area to verify that it does not stain or discolor slab.

3.03 INSTALLATION

A. Perform work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions.

B. Perform installation in accordance with ASTM C1193.

C. Measure joint dimensions and size joint backers to achieve the following, unless otherwise indicated:
1. Width/depth ratio of 2:1.
a. Minumim joint depth: 1/4 inch; Maximum joint depth: 1/2 inch, unless otherwise required by manufacturer.
2. Neck dimension no greater than 1/3 of the joint width.
3. Surface bond area on each side not less than 75 percent of joint width.

D. Install backer rod using blunt or rounded tool to a uniform (+/- 1/8 inch) depth without puncturing the material.

E. Install bond breaker backing tape where backer rod cannot be used.

F. Install sealant free of air pockets, foreign embedded matter, ridges, and sags, and without getting sealant on adjacent surfaces.

G. Do not install sealant when ambient temperature is outside manufacturer's recommended temperature range, or will be outside that range during the entire curing period, unless manufacturer's approval is obtained and instructions are followed.

H. Nonsag Sealants: Tool surface concave, unless otherwise indicated; remove masking tape immediately after tooling sealant surface.

3.04 FIELD QUALITY CONTROL

A. Perform field quality control inspection/testing as specified in PART 1 under QUALITY ASSURANCE article.

B. Destructive Adhesion Testing: If there are any failures in first 1000 linear feet, notify Architect immediately.

C. Remove and replace failed portions of sealants using same materials and procedures as indicated for original installation.

D. Repair destructive test location damage immediately after evaluation and recording of results.

END OF SECTION

SECTION 08 1113
HOLLOW METAL DOORS AND FRAMES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Hollow metal frames for wood doors.

1.02 RELATED REQUIREMENTS

A. Section 09 9123 - Interior Painting: Field painting.

1.03 REFERENCE STANDARDS

A. ADA Standards - Americans with Disabilities Act (ADA) Standards for Accessible Design; 2010.

B. ANSI/SDI A250.8 - Specifications for Standard Steel Doors and Frames (SDI-100); 2014.

C. ANSI/SDI A250.10 - Test Procedure and Acceptance Criteria for Prime Painted Steel Surfaces for Steel Doors and Frames; 2011.

D. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2015.

E. ASTM A1008/A1008M - Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable; 2016.

F. ASTM A1011/A1011M - Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength; 2015.

G. ICC A117.1 - Accessible and Usable Buildings and Facilities; 2009.

H. NAAMM HMMA 840 - Guide Specifications for Installation and Storage of Hollow Metal Doors and Frames; 2007.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Materials and details of design and construction, hardware locations, reinforcement type and locations, anchorage and fastening methods, and finishes.

C. Shop Drawings: Details of each opening, showing elevations, glazing, frame profiles, and any indicated finish requirements.

1.05 QUALITY ASSURANCE

A. Copies of Documents at Project Site: Maintain at the project site a copy of each referenced document that prescribes installation requirements.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Comply with NAAMM HMMA 840 or ANSI/SDI A250.8 (SDI-100) in accordance with specified requirements.

B. Protect with resilient packaging; avoid humidity build-up under coverings; prevent corrosion and adverse effects on factory applied painted finish.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Hollow Metal Doors and Frames:

1. Ceco Door, an Assa Abloy Group company: www.assaabloydss.com.
2. Republic Doors: www.republicdoor.com.
3. Steelcraft, an Allegion brand: www.allegion.com/sle.
4. Substitutions: See Section 01 6000 - Product Requirements.

2.02 DESIGN CRITERIA

A. Requirements for Hollow Metal Doors and Frames:
   1. Steel used for fabrication of doors and frames shall comply with one or more of the following requirements; Galvannealed steel conforming to ASTM A653/A653M, cold-rolled steel conforming to ASTM A1008/A1008M, or hot-rolled pickled and oiled (HRPO) steel conforming to ASTM A1011/A1011M, Commercial Steel (CS) Type B for each.
   2. Accessibility: Comply with ICC A117.1 and ADA Standards.

B. Combined Requirements: If a particular door and frame unit is indicated to comply with more than one type of requirement, comply with the specified requirements for each type; for instance, an exterior door that is also indicated as being sound-rated must comply with the requirements specified for exterior doors and for sound-rated doors; where two requirements conflict, comply with the most stringent.

2.03 HOLLOW METAL FRAMES

A. Comply with standards and/or custom guidelines as indicated for corresponding door in accordance with applicable door frame requirements.

B. Frame Finish: Factory primed and field finished.

C. Interior Door Frames, Non-Fire Rated: Full profile/continuously welded type.
   1. Frame Metal Thickness: 18 gage, 0.042 inch, minimum.
   2. Kerfed stops for gasketing.

D. Frames for Wood Doors: Comply with frame requirements in accordance with corresponding door.

E. Provide mortar guard boxes for hardware cut-outs in frames to be installed in masonry or to be grouted.

F. Frames in Masonry Walls: Size to suit masonry coursing with head member to fill opening without cutting masonry units.

2.04 ACCESSORIES

A. Grout for Frames: Portland cement grout with maximum 4 inch slump for hand troweling; thinner pumpable grout is prohibited.

B. Kerf Gasket: Cellular modified foam core clad in an embossed, non-vinyl, UV stablized, paint resistant liner.

C. Temporary Frame Spreaders: Provide for factory- or shop-assembled frames.

2.05 FINISHES

A. Primer: Rust-inhibiting, complying with ANSI/SDI A250.10, door manufacturer's standard.

B. Bituminous Coating: Asphalt emulsion or other high-build, water-resistant, resilient coating.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify existing conditions before starting work.

B. Verify that opening sizes and tolerances are acceptable.

C. Verify that finished walls are in plane to ensure proper door alignment.

3.02 PREPARATION

A. Coat inside of frames to be installed in masonry or to be grouted, with bituminous coating, prior to installation.

3.03 INSTALLATION

A. Install doors and frames in accordance with manufacturer's instructions and related requirements of specified door and frame standards or custom guidelines indicated.

B. Coordinate frame anchor placement with wall construction.

C. Grout frames in masonry construction, using hand trowel methods; brace frames so that pressure of grout before setting will not deform frames.

D. Coordinate installation of hardware.

3.04 TOLERANCES

A. Maximum Diagonal Distortion: 1/16 in measured with straight edge, corner to corner.

3.05 ADJUSTING

A. Adjust for smooth and balanced door movement.

3.06 SCHEDULE

A. Refer to Door and Frame Schedule on the drawings.

END OF SECTION

SECTION 08 1416
FLUSH WOOD DOORS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Flush wood doors; flush and flush glazed configuration; non-rated.

1.02 RELATED REQUIREMENTS

A. Section 06 2000 - Finish Carpentry: Wood door frames.

B. Section 08 1113 - Hollow Metal Doors and Frames.

C. Section 09 9123 - Interior Painting: Field finishing of doors.

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Indicate door core materials and construction; veneer species, type and characteristics.

C. Shop Drawings: Show doors and frames, elevations, sizes, types, swings, undercuts, beveling, blocking for hardware, factory machining, factory finishing, cutouts for glazing and other details.

D. Specimen warranty.

E. Samples: Submit two samples of door veneer, 12 by 12 inch in size illustrating wood grain, stain color, and sheen.

F. Warranty, executed in Owner's name.

1.04 QUALITY ASSURANCE

A. Maintain one copy of the specified door quality standard on site for review during installation and finishing.

B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section, with not less than three years of documented experience.

1.05 DELIVERY, STORAGE, AND HANDLING

A. Package, deliver and store doors in accordance with specified quality standard.

B. Accept doors on site in manufacturer's packaging. Inspect for damage.

C. Protect doors with resilient packaging sealed with heat shrunk plastic. Do not store in damp or wet areas; or in areas where sunlight might bleach veneer. Seal top and bottom edges with tinted sealer if stored more than one week. Break seal on site to permit ventilation.

1.06 WARRANTY

A. See Section 01 7800 - Closeout Submittals, for additional warranty requirements.

B. Interior Doors: Provide manufacturer's warranty for the life of the installation.

C. Include coverage for delamination of veneer, warping beyond specified installation tolerances, defective materials, and telegraphing core construction.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Wood Veneer Faced Doors:

1. Eggers Industries: www.eggersindustries.com.

2. Graham Wood Doors: www.grahamdoors.com.
3. Marshfield DoorSystems, Inc: www.marshfielddoors.com.
4. Substitutions: See Section 01 6000 - Product Requirements.

2.02 DOORS

A. Doors: Refer to drawings for locations and additional requirements.
   1. Wood Veneer Faced Doors: 5-ply unless otherwise indicated.

B. Interior Doors: 1-3/4 inches thick unless otherwise indicated; flush construction.
   1. Provide solid core doors at each location.
   2. Wood veneer facing for field transparent finish.

2.03 DOOR AND PANEL CORES

A. Non-Rated Solid Core and 20 Minute Rated Doors: Type particleboard core (PC), plies and faces as indicated.

2.04 DOOR FACINGS

A. Veneer Facing for Transparent Finish: White oak, veneer grade in accordance with quality standard indicated, plain sliced (flat cut), with book match between leaves of veneer, center balance match of spliced veneer leaves assembled on door or panel face.

2.05 DOOR CONSTRUCTION

A. Fabricate doors in accordance with door quality standard specified.

B. Cores Constructed with stiles and rails:
   1. Provide solid blocks at lock edge and top of door for closer for hardware reinforcement.

C. Glazed Openings: Non-removable stops on non-secure side; sizes and configurations as indicated on drawings.

D. Factory machine doors for hardware other than surface-mounted hardware, in accordance with hardware requirements and dimensions.

E. Factory fit doors for frame opening dimensions identified on shop drawings, with edge clearances in accordance with specified quality standard.

F. Provide edge clearances in accordance with the quality standard specified.

2.06 ACCESSORIES

A. Hollow Metal Door Frames: As specified in Section 08 1113.

B. Door Hardware: As shown on drawings.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify existing conditions before starting work.

B. Verify that opening sizes and tolerances are acceptable.

C. Do not install doors in frame openings that are not plumb or are out-of-tolerance for size or alignment.

3.02 INSTALLATION

A. Install doors in accordance with manufacturer's instructions and specified quality standard.

B. Field-Finished Doors: Trimming to fit is acceptable.
   1. Adjust width of non-rated doors by cutting equally on both jamb edges.
   2. Trim maximum of 3/4 inch off bottom edges.

C. Use machine tools to cut or drill for hardware.

D. Coordinate installation of doors with installation of frames and hardware.

3.03 TOLERANCES

A. Conform to specified quality standard for fit and clearance tolerances.

B. Conform to specified quality standard for telegraphing, warp, and squareness.

3.04 ADJUSTING

A. Adjust doors for smooth and balanced door movement.

B. Adjust closers for full closure.

3.05 SCHEDULE

A. Refer to Door and Frame Schedule on drawings.

END OF SECTION

SECTION 08 3326
OVERHEAD COILING GRILLES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Overhead coiling metal grilles, counter doors, and operating hardware, electric operation.

B. Wiring from electric circuit disconnect to operator to control station.

1.02 RELATED REQUIREMENTS

A. Section 26 0534 - Conduit: Conduit from electric circuit to operator and from operator to control station.

B. Section 26 2717 - Equipment Wiring: Power to disconnect.

1.03 REFERENCE STANDARDS

A. ASTM A666 - Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2015.

B. ITS (DIR) - Directory of Listed Products; current edition.

C. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.

D. NEMA ICS 2 - Industrial Control and Systems Controllers, Contactors and Overload Relays Rated 600 Volts; 2000 (R2005), with errata, 2008.

E. NEMA MG 1 - Motors and Generators; 2014.

F. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

G. UL 325 - Standard for Door, Drapery, Gate, Louver, and Window Operators and Systems; Current Edition, Including All Revisions.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide general construction, component connections and details, and electrical equipment.

C. Shop Drawings: Indicate pertinent dimensioning, anchorage methods, hardware locations, and installation details.

D. Manufacturer's Installation Instructions: Indicate installation sequence and procedures, adjustment and alignment procedures.

E. Maintenance Data: Indicate lubrication requirements and frequency and periodic adjustments required.

1.05 QUALITY ASSURANCE

A. Products Requiring Electrical Connection: Listed and classified by UL (DIR) as suitable for the purpose specified and indicated.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Overhead Coiling Grilles:
   1. Cornell Iron Works, Inc; 5015 Grille: www.cornelliron.com.
   2. Substitutions: See Section 01 6000 - Product Requirements.

2.02 GRILLE AND COMPONENTS

A. Grille: Stainless steel; horizontal bar curtain, coiling on overhead counterbalanced shaft.
   1. Finish: No. 4 - Brushed.
   2. Electric operation.
   3. Mounting: Surface mounted.

B. Curtain: Round horizontal bars connected with vertical links.
   1. Horizontal bars: 5/16 inch diameter.
   2. Bar spacing: 1-1/2 inch on center.
   3. Tube spacers: 1/2 inch diameter.
   4. Spacer spacing: 2 1/4" inch on center.
   5. Vertical links: 5/8 x 1/8 inch flat bar.
   6. Link spacing: 6 inch on center.
   7. Bar Ends: Provide with nylon runners for quiet operation.
   8. Bottom Bar: Back-to-back angles with tubular resilient cushion.

C. Guides: Stainless steel angles, of profile to retain grille in place with snap-on trim, mounting brackets of same metal.

D. Hood Enclosure: Sheet metal; completely covering operating mechanisms; internally reinforced to maintain rigidity and shape.
   1. Material: Stainless steel.
   2. Finish: No. 4 - Brushed.

E. Lock Hardware:
   1. Latchset Lock Cylinders: Standard mortise cylinder.
      a. Keying: Master keyed.

F. Roller Shaft Counterbalance: Steel pipe and helical steel spring system, capable of producing torque sufficient to ensure smooth operation of curtain from any position and capable of holding position at mid-travel; with adjustable spring tension; requiring 25 lb nominal force to operate.

2.03 MATERIALS

A. Stainless Steel: ASTM A666, Type 304, with rollable temper.

2.04 ELECTRIC OPERATION

A. Operator, Controls, Actuators, and Safeties: Comply with UL 325; provide products listed by ITS (DIR), UL (DIR), or testing agency acceptable to authorities having jurisdiction.
   1. Provide interlock switches on motor operated units.

B. Electric Operators:
   1. Mounting: Side mounted.
   2. Motor Enclosure:
      a. Interior grilles: NEMA MG 1, Type 1; open drip proof.
   3. Motor Rating: 1/3 hp; continuous duty.
   4. Motor Voltage: ____ volt, single phase, 60 Hz.
   5. Motor Controller: NEMA ICS 2, full voltage, reversing magnetic motor starter.
   6. Controller Enclosure: NEMA 250 Type 1.
   7. Opening Speed: 12 inches per second.
   8. Brake: Adjustable friction clutch type, activated by motor controller.
   9. Manual override in case of power failure.

C. Control Station: Standard three button (OPEN-STOP-CLOSE) momentary control for each operator.
   1. 24 volt circuit.
   2. Recessed.

D. Safety Edge: Located at bottom of curtain, full width, electro-mechanical sensitized type, wired to stop operator upon striking object, hollow neoprene covered.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that opening sizes, tolerances and conditions are acceptable.

3.02 INSTALLATION

A. Install grille unit assembly in accordance with manufacturer's instructions.

B. Use anchorage devices to securely fasten assembly to wall construction and building framing without distortion or stress.

C. Securely and rigidly brace components suspended from structure.

D. Fit and align assembly including hardware; level and plumb, to provide smooth operation.

E. Coordinate installation of electrical service with Section 26 2717.

F. Complete wiring from disconnect to unit components.

G. Install perimeter trim and closures.

3.03 TOLERANCES

A. Maintain dimensional tolerances and alignment with adjacent work.

B. Maximum Variation From Plumb: 1/16 inch.

C. Maximum Variation From Level: 1/16 inch.

D. Longitudinal or Diagonal Warp: Plus or minus 1/8 inch per 10 ft straight edge.

3.04 ADJUSTING

A. Adjust grille, hardware and operating assemblies for smooth and noiseless operation.

3.05 CLEANING

A. Clean grille and components.

B. Remove labels and visible markings.

END OF SECTION

SECTION 09 0561

COMMON WORK RESULTS FOR FLOORING PREPARATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. This section applies to all floors identified in the contract documents as to receive the following types of floor coverings:
   1. Resilient tile and sheet.

B. Removal of existing floor coverings.

C. Preparation of new and existing concrete floor slabs for installation of floor coverings.

D. Testing of concrete floor slabs for moisture and alkalinity (pH).

E. Remediation of concrete floor slabs due to unsatisfactory moisture or alkalinity (pH) conditions.
   1. Contractor shall perform all specified remediation of concrete floor slabs. If such remediation is indicated by testing agency's report and is due to a condition not under Contractor's control or could not have been predicted by examination prior to entering into the contract, a contract modification will be issued.

1.02 REFERENCES

A. ASTM C109/C109M - Standard Test Method for Compressive Strength of Hydraulic Cement Mortars (Using 2-in. or (50-mm) Cube Specimens); 2016a.

B. ASTM C472 - Standard Test Methods for Physical Testing of Gypsum, Gypsum Plasters and Gypsum Concrete; 1999 (Reapproved 2014).

C. ASTM F710 - Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring; 2011.

D. ASTM F1869 - Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride; 2011.

E. RFCI (RWP) - Recommended Work Practices for Removal of Resilient Floor Coverings; Resilient Floor Covering Institute; October 2011.

1.03 ADMINISTRATIVE REQUIREMENTS

A. Coordinate scheduling of cleaning and testing, so that preliminary cleaning has been completed for at least 24 hours prior to testing.

1.04 SUBMITTALS

A. Visual Observation Report: For existing floor coverings to be removed.

B. Floor Covering and Adhesive Manufacturers' Product Literature: For each specific combination of substrate, floor covering, and adhesive to be used; showing:
   1. Moisture and alkalinity (pH) limits and test methods.
   2. Manufacturer's required bond/compatibility test procedure.

C. Testing Agency's Report:
   1. Description of areas tested; include floor plans and photographs if helpful.
   2. Summary of conditions encountered.
   3. Moisture and alkalinity (pH) test reports.
   4. Copies of specified test methods.
   5. Recommendations for remediation of unsatisfactory surfaces.
   6. Submit report to Architect.

7. Submit report not more than two business days after conclusion of testing.

D. Adhesive Bond and Compatibility Test Report.

E. Copy of RFCI (RWP).

F. Remedial Materials Product Data: Manufacturer's published data on each product to be used for remediation.

1.05 QUALITY ASSURANCE

A. Moisture and alkalinity (pH) testing shall be performed by an independent testing agency employed and paid by Contractor.

B. Testing Agency Qualifications: Independent testing agency experienced in the types of testing specified.
   1. Submit evidence of experience consisting of at least 3 test reports of the type required, with project Owner's project contact information.

C. Contractor's Responsibility Relating to Independent Agency Testing:
   1. Provide access for and cooperate with testing agency.
   2. Confirm date of start of testing at least 10 days prior to actual start.
   3. Allow at least 4 business days on site for testing agency activities.
   4. Achieve and maintain specified ambient conditions.
   5. Notify Architect when specified ambient conditions have been achieved and when testing will start.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, handle, and protect products in accordance with manufacturer’s instructions and recommendations.

B. Deliver materials in manufacturer’s packaging; include installation instructions.

C. Keep materials from freezing.

1.07 FIELD CONDITIONS

A. Maintain ambient temperature in spaces where concrete testing is being performed, and for at least 48 hours prior to testing, at not less than 65 degrees F or more than 85 degrees F.

B. Maintain relative humidity in spaces where concrete testing is being performed, and for at least 48 hours prior to testing, at not less than 40 percent and not more than 60 percent.

PART 2 PRODUCTS

2.01 MATERIALS

A. Patching Compound: Floor covering manufacturer's recommended product, suitable for conditions, and compatible with adhesive and floor covering. In the absence of any recommendation from flooring manufacturer, provide a product with the following characteristics:
   1. Cementitious moisture-, mildew-, and alkali-resistant compound, compatible with floor, floor covering, and floor covering adhesive, and capable of being feathered to nothing at edges.
   2. Compressive Strength: 3000 psi, minimum, after 28 days, when tested in accordance with ASTM C109/C109M or ASTM C472, whichever is appropriate.

B. Alternate Flooring Adhesive: Floor covering manufacturer's recommended product, suitable for the moisture and pH conditions present; low-VOC. In the absence of any recommendation

from flooring manufacturer, provide a product recommended by adhesive manufacturer as suitable for substrate and floor covering and for conditions present.

C. Remedial Floor Coating: Single- or multi-layer coating or coating/overlay combination intended by its manufacturer to resist water vapor transmission to degree sufficient to meet flooring manufacturer's emission limits, resistant to the level of alkalinity (pH) found, and suitable for adhesion of flooring without further treatment.
   1. If testing agency recommends any particular products, use one of those.
   2. Products:
      a. ARDEX Engineered Cements; ARDEX MC ULTRA with ARDEX FEATHERFINISH: www.ardexamericas.com.
      b. Substitutions: See Section 01 6000 - Product Requirements.

PART 3 EXECUTION

3.01 CONCRETE SLAB PREPARATION

A. Perform following operations in the order indicated:
   1. Existing concrete slabs (on-grade and elevated) with existing floor coverings:
      a. Visual observation of existing floor covering, for adhesion, water damage, alkaline deposits, and other defects.
      b. Removal of existing floor covering.
   2. Preliminary cleaning.
   3. Moisture vapor emission tests; 3 tests in the first 1000 square feet and one test in each additional 1000 square feet, unless otherwise indicated or required by flooring manufacturer.
   4. Internal relative humidity tests; in same locations as moisture vapor emission tests, unless otherwise indicated.
   5. Alkalinity (pH) tests; in same locations as moisture vapor emission tests, unless otherwise indicated.
   6. Specified remediation, if required.
   7. Patching, smoothing, and leveling, as required.
   8. Other preparation specified.
   9. Adhesive bond and compatibility test.
   10. Protection.

B. Remediations:
   1. Active Water Leaks or Continuing Moisture Migration to Surface of Slab: Correct this condition before doing any other remediation; re-test after correction.
   2. Excessive Moisture Emission or Relative Humidity: If an adhesive that is resistant to the level of moisture present is available and acceptable to flooring manufacturer, use that adhesive for installation of the flooring; if not, apply remedial floor coating over entire suspect floor area.
   3. Excessive Alkalinity (pH): If remedial floor coating is necessary to address excessive moisture, no additional remediation is required; if not, if an adhesive that is resistant to the level present is available and acceptable to the flooring manufacturer, use that adhesive for installation of the flooring; otherwise, apply a skim coat of specified patching compound over entire suspect floor area.

3.02 REMOVAL OF EXISTING FLOOR COVERINGS

A. Comply with local, State, and federal regulations and recommendations of RFCI Recommended Work Practices for Removal of Resilient Floor Coverings, as applicable to floor covering being removed.

B. Dispose of removed materials in accordance with local, State, and federal regulations and as specified.

3.03 PRELIMINARY CLEANING

A. Clean floors of dust, solvents, paint, wax, oil, grease, asphalt, residual adhesive, adhesive removers, film-forming curing compounds, sealing compounds, alkaline salts, excessive laitance, mold, mildew, and other materials that might prevent adhesive bond.

B. Do not use solvents or other chemicals for cleaning.

3.04 MOISTURE VAPOR EMISSION TESTING

A. Where the floor covering manufacturer's requirements conflict with either the referenced test method or this specification, comply with the manufacturer's requirements.

B. Where this specification conflicts with the referenced test method, comply with the requirements of this section.

C. Test in accordance with ASTM F1869 and as follows.

D. Plastic sheet test and mat bond test may not be substituted for the specified ASTM test method, as those methods do not quantify the moisture content sufficiently.

E. In the event that test values exceed floor covering manufacturer's limits, perform remediation as indicated. In the absence of manufacturer limits, perform remediation if test values exceed 3 pounds per 1000 square feet per 24 hours.

F. Report: Report the information required by the test method.

3.05 ALKALINITY TESTING

A. Where the floor covering manufacturer's requirements conflict with either the referenced test method or this specification, comply with the manufacturer's requirements.

B. The following procedure is the equivalent of that described in ASTM F710, repeated here for the Contractor's convenience.

C. Use a wide range alkalinity (pH) test paper, its associated chart, and distilled or deionized water.

D. Place several drops of water on a clean surface of concrete, forming a puddle approximately 1 inch in diameter. Allow the puddle to set for approximately 60 seconds, then dip the alkalinity (pH) test paper into the water, remove it, and compare immediately to chart to determine alkalinity (pH) reading.

E. In the event that test values exceed floor covering manufacturer's limits, perform remediation as indicated. In the absence of manufacturer limits, perform remediation if alkalinity (pH) test value is over 10.

3.06 PREPARATION

A. See individual floor covering section(s) for additional requirements.

B. Comply with requirements and recommendations of floor covering manufacturer.

C. Fill and smooth surface cracks, grooves, depressions, control joints and other non-moving joints, and other irregularities with patching compound.

D. Do not fill expansion joints, isolation joints, or other moving joints.

3.07 ADHESIVE BOND AND COMPATIBILITY TESTING

A. Comply with requirements and recommendations of floor covering manufacturer.

3.08 APPLICATION OF REMEDIAL FLOOR COATING

A. Comply with requirements and recommendations of coating manufacturer.

3.09 PROTECTION

A. Cover prepared floors with building paper or other durable covering.

END OF SECTION

SECTION 09 2116
GYPSUM BOARD ASSEMBLIES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Performance criteria for gypsum board assemblies.

B. Metal stud wall framing.

C. Metal channel ceiling framing.

D. Cementitious backing board.

E. Gypsum wallboard.

F. Joint treatment and accessories.

1.02 RELATED REQUIREMENTS

A. Section 06 1000 - Rough Carpentry: Wood blocking product and execution requirements.

B. Section 07 9200 - Joint Sealants: Sealing acoustical gaps in construction other than gypsum board or plaster work.

C. Section 09 3000 - Tiling: Tile backing board.

1.03 REFERENCE STANDARDS

A. AISI S100-12 - North American Specification for the Design of Cold-Formed Steel Structural Members; American Iron and Steel Institute; 2012.

B. ANSI A108.11 - American National Standard for Interior Installation of Cementitious Backer Units; 2010 (Revised).

C. ANSI A118.9 - American National Standard Specifications for Test Methods and Specifications for Cementitious Backer Units; 1999 (Reaffirmed 2010).

D. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2015.

E. ASTM C475/C475M - Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board; 2015.

F. ASTM C557 - Standard Specification for Adhesives for Fastening Gypsum Wallboard to Wood Framing; 2003 (Reapproved 2009).

G. ASTM C645 - Standard Specification for Nonstructural Steel Framing Members; 2014.

H. ASTM C754 - Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products; 2015.

I. ASTM C840 - Standard Specification for Application and Finishing of Gypsum Board; 2013.

J. ASTM C954 - Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs From 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness; 2015.

K. ASTM C1002 - Standard Specification for Steel Self-Piercing Tapping Screws for Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs; 2014.

L. ASTM C1047 - Standard Specification for Accessories For Gypsum Wallboard and Gypsum Veneer Base; 2014a.

M. ASTM C1325 - Specification for Non-Asbestos Fiber-Mat Reinforced Cementitious Backer Units; 2014.

N. ASTM C1396/C1396M - Standard Specification for Gypsum Board; 2014a.

O. ASTM D3273 - Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber; 2016.

P. ASTM E90 - Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2009.

Q. ASTM E413 - Classification for Rating Sound Insulation; 2016.

R. GA-216 - Application and Finishing of Gypsum Board; 2013.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data on metal framing, gypsum board, accessories, and joint finishing system.

C. Product Data: Provide manufacturer's data on partition head to structure connectors, showing compliance with requirements.

1.05 QUALITY ASSURANCE

A. Copies of Documents at Site: Maintain at the project site a copy of each referenced document that prescribes execution requirements.

PART 2 PRODUCTS

2.01 GYPSUM BOARD ASSEMBLIES

A. Provide completed assemblies complying with ASTM C840 and GA-216.

B. Interior Partitions: Provide completed assemblies with the following characteristics:

2.02 METAL FRAMING MATERIALS

A. Manufacturers - Metal Framing, Connectors, and Accessories:
   1. Clarkwestern Dietrich Building Systems LLC: www.clarkdietrich.com.
   2. Marino: www.marinoware.com.
   3. Phillips Manufacturing Company: www.phillipsmfg.com.
   4. Substitutions: See Section 01 6000 - Product Requirements.

B. Non-Loadbearing Framing System Components: ASTM C645; galvanized sheet steel, of size and properties necessary to comply with ASTM C754 for the spacing indicated, with maximum deflection of wall framing of L/120 at 5 psf.
   1. Studs: "C" shaped with flat or formed webs with knurled faces.
   2. Runners: U shaped, sized to match studs.
   3. Ceiling Channels: C-shaped.

C. Ceiling Hangers: Type and size as specified in ASTM C754 for spacing required.

D. Partition Head to Structure Connections: Provide mechanical anchorage devices that accommodate deflection using slotted holes, screws and anti-friction bushings, preventing rotation of studs while maintaining structural performance of partition.
   1. Structural Performance: Maintain lateral load resistance and vertical movement capacity required by applicable code, when evaluated in accordance with AISI S100-12.
   2. Material: ASTM A653/A653M steel sheet, SS Grade 50/340, with G60/Z180 hot dipped galvanized coating.
   3. Provide top track preassembled with connection devices spaced to fit stud spacing indicated on drawings; minimum track length of 12 feet.

2.03 BOARD MATERIALS

A. Manufacturers - Gypsum-Based Board:
   1. American Gypsum Company: www.americangypsum.com.
   2. Georgia-Pacific Gypsum: www.gpgypsum.com.
   3. National Gypsum Company: www.nationalgypsum.com.
   4. Substitutions: See Section 01 6000 - Product Requirements.

B. Gypsum Wallboard: Paper-faced gypsum panels as defined in ASTM C1396/C1396M; sizes to minimize joints in place; ends square cut.
   1. Application: Use for vertical surfaces and ceilings, unless otherwise indicated.
   2. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
   3. Use Type X board, UL or WH listed.
   4. Thickness:
      a. Vertical Surfaces: 5/8 inch.
   5. Mold Resistant Paper Faced Products:
      a. American Gypsum Company; M-Bloc Type X.
      b. Georgia-Pacific Gypsum; ToughRock Fireguard X Mold-Guard.
      c. National Gypsum Company; Gold Bond XP Gypsum Board .

C. Backing Board For Wet Areas:
   1. Application: Surfaces behind tile in wet areas including kitchen and servery walls.
   2. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
   3. ANSI Cement-Based Board: Non-gypsum-based; aggregated Portland cement panels with glass fiber mesh embedded in front and back surfaces complying with ANSI A118.9 or ASTM C1325.
      a. Thickness: 1/2 inch.
      b. Products:
         1) National Gypsum Company; PermaBase Cement Board: www.nationalgypsum.com.
         2) USG Corporation: www.usg.com.
         3) Substitutions: See Section 01 6000 - Product Requirements.

2.04 ACCESSORIES

A. Finishing Accessories: ASTM C1047, rolled zinc, unless noted otherwise.
   1. Types: As detailed or required for finished appearance.
   2. Products:
      a. Same manufacturer as framing materials.
      b. Substitutions: See Section 01 6000 - Product Requirements.

B. Joint Materials: ASTM C475/C475M and as recommended by gypsum board manufacturer for project conditions.
   1. Tape: 2 inch wide, coated glass fiber tape for joints and corners, except as otherwise indicated.
   2. Ready-mixed vinyl-based joint compound.

C. High Build Drywall Surfacer: Vinyl acrylic latex-based coating for spray application, designed to take the place of skim coating and separate paint primer in achieving Level 5 finish.

D. Screws for Fastening of Gypsum Panel Products to Cold-Formed Steel Studs Less than 0.033 inch in Thickness and Wood Members: ASTM C1002; self-piercing tapping screws, corrosion resistant.

E. Screws for Fastening of Gypsum Panel Products to Steel Members from 0.033 to 0.112 inch in Thickness: ASTM C954; steel drill screws, corrosion resistant.

F. Anchorage to Substrate: Tie wire, nails, screws, and other metal supports, of type and size to suit application; to rigidly secure materials in place.

G. Adhesive for Attachment to Metal:

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that project conditions are appropriate for work of this section to commence.

3.02 FRAMING INSTALLATION

A. Metal Framing: Install in accordance with ASTM C754 and manufacturer's instructions.

B. Suspended Ceilings and Soffits: Space framing and furring members as indicated.
   1. Level ceiling system to a tolerance of 1/1200.
   2. Laterally brace entire suspension system.

C. Studs: Space studs at 16 inches on center.
   1. Extend partition framing to structure in all locations.
   2. Partitions Terminating at Structure: Attach top runner to structure, maintain clearance between top of studs and structure, and connect studs to track using specified mechanical devices in accordance with manufacturer's instructions; verify free movement of top of stud connections; do not leave studs unattached to track.

3.03 BOARD INSTALLATION

A. Comply with ASTM C840, GA-216, and manufacturer's instructions. Install to minimize butt end joints, especially in highly visible locations.

B. Cementitious Backing Board: Install over steel framing members where indicated, in accordance with ANSI A108.11 and manufacturer's instructions.

3.04 INSTALLATION OF TRIM AND ACCESSORIES

A. Control Joints: Place control joints consistent with lines of building spaces and as indicated.

B. Corner Beads: Install at external corners, using longest practical lengths.

3.05 JOINT TREATMENT

A. Finish gypsum board in accordance with levels defined in ASTM C840, as follows:
   1. Level 1: Wall areas above finished ceilings, whether or not accessible in the completed construction.

B. Tape, fill, and sand exposed joints, edges, and corners to produce smooth surface ready to receive finishes.
   1. Feather coats of joint compound so that camber is maximum 1/32 inch.

C. Where Level 5 finish is indicated, spray apply high build drywall surfacer over entire surface after joints have been properly treated; achieve a flat and tool mark-free finish.

END OF SECTION

SECTION 09 3000
TILING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Refer to Scope Information Sheets for this contract bound in the Project Manual under Section 01 1000, Summary of Work. The Scope Information Sheets describe generally the work included in each contract, but the work is not necessarily limited to that described.

B. Cleavage membrane for floor and wall tile.

C. Tile for floor applications.

D. Tile for wall applications.

E. Ceramic accessories.

F. Ceramic trim.

G. Non-ceramic trim.

1.02 RELATED REQUIREMENTS

A. Section 07 9200 - Joint Sealants: Sealing joints between tile work and adjacent construction and fixtures.

B. Section 09 2116 - Gypsum Board Assemblies: Tile backer board.

1.03 REFERENCE STANDARDS

A. ANSI A108/A118/A136.1 - American National Standard Specifications for the Installation of Ceramic Tile (Compendium); 2013.1.

1. ANSI A108.1a - American National Standard Specifications for Installation of Ceramic Tile in the Wet-Set Method, with Portland Cement Mortar; 2014.
2. ANSI A108.1b - American National Standard Specifications for Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set or Latex-Portland Cement Mortar; 1999 (Reaffirmed 2010).
3. ANSI A108.1c - Specifications for Contractors Option: Installation of Ceramic Tile in the Wet-Set Method with Portland Cement Mortar or Installation of Ceramic Tile on a Cured Portland Cement Mortar Bed with Dry-Set or Latex-Portland Cement; 1999 (Reaffirmed 2010).
4. ANSI A108.4 - American National Standard Specifications for Installation of Ceramic Tile with Organic Adhesives or Water Cleanable Tile-Setting Epoxy Adhesive; 2009 (Revised).
5. ANSI A108.5 - American National Standard Specifications for Installation of Ceramic Tile with Dry-Set Portland Cement Mortar or Latex-Portland Cement Mortar; 1999 (Reaffirmed 2010).
6. ANSI A108.6 - American National Standard Specifications for Installation of Ceramic Tile with Chemical Resistant, Water Cleanable Tile-Setting and -Grouting Epoxy; 1999 (Reaffirmed 2010).
7. ANSI A108.8 - American National Standard Specifications for Installation of Ceramic Tile with Chemical Resistant Furan Resin Mortar and Grout; 1999 (Reaffirmed 2010).
8. ANSI A108.9 - American National Standard Specifications for Installation of Ceramic Tile with Modified Epoxy Emulsion Mortar/Grout; 1999 (Reaffirmed 2010).
9. ANSI A108.10 - American National Standard Specifications for Installation of Grout in Tilework; 1999 (Reaffirmed 2010).

10. ANSI A108.11 - American National Standard for Interior Installation of Cementitious Backer Units; 2010 (Revised).
11. ANSI A108.12 - American National Standard for Installation of Ceramic Tile with EGP (Exterior Glue Plywood) Latex-Portland Cement Mortar; 1999 (Reaffirmed 2010).
12. ANSI A108.13 - American National Standard for Installation of Load Bearing, Bonded, Waterproof Membranes for Thin-Set Ceramic Tile and Dimension Stone; 2005 (Reaffirmed 2010).
13. ANSI A118.1 - American National Standard Specifications for Dry-Set Cement Mortar; 2012 (Revised).
14. ANSI A118.3 - American National Standard Specifications for Chemical Resistant, Water Cleanable Tile-Setting and -Grouting Epoxy and Water Cleanable Tile-Setting Epoxy Adhesive; 2013 (Revised).
15. ANSI A118.4 - American National Standard Specifications for Modified Dry-Set Cement Mortar; 2012 (Revised).
16. ANSI A118.5 - American National Standard Specifications for Chemical Resistant Furan Mortars and Grouts for Tile Installation; 1999 (Reaffirmed 2010).
17. ANSI A118.6 - American National Standard Specifications for Standard Cement Grouts for Tile Installation; 2010 (Revised).
18. ANSI A118.7 - American National Standard Specifications for High Performance Cement Grouts for Tile Installation; 2010 (Revised).
19. ANSI A118.8 - American National Standard Specifications for Modified Epoxy Emulsion Mortar/Grout; 2012.1.
20. ANSI A118.9 - American National Standard Specifications for Test Methods and Specifications for Cementitious Backer Units; 1999 (Reaffirmed 2010).
21. ANSI A118.11 - American National Standard Specifications for EGP (Exterior Glue Plywood) Latex-Portland Cement Mortar; 1999 (Reaffirmed 2010).

B. ANSI A118.12 - American National Standard Specifications for Crack Isolation Membranes for Thin-Set Ceramic Tile and Dimension Stone Installation; 2014.

C. ANSI A118.13 - American National Standard Specifications for Bonded Sound Reduction Membranes for Thin-Set Ceramic Tile Installation; 2014.

D. ANSI A118.15 - American National Standard Specifications for Improved Modified Dry-Set Cement Mortar; 2012.

E. ANSI A118.15 - American National Standard Specifications for Improved Modified Dry-Set Cement Mortar; 2012.
   1. ANSI A136.1 - American National Standard for Organic Adhesives for Installation of Ceramic Tile; 2008 (Reaffirmed 2013).
   2. ANSI A137.1 - American National Standard Specifications for Ceramic Tile; 2013.1.
   3. ASTM C373 - Standard Test Method for Water Absorption, Bulk Density, Apparent Porosity, and Apparent Specific Gravity of Fired Whiteware Products, Ceramic Tiles, and Glass Tiles; 2014a.

F. ASTM C847 - Standard Specification for Metal Lath; 2014a.

G. TCNA (HB) - Handbook for Ceramic, Glass, and Stone Tile Installation; 2016.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturers' data sheets on tile, mortar, grout, and accessories. Include instructions for using grouts and adhesives.

C. Shop Drawings: Indicate tile layout, patterns, color arrangement, perimeter conditions, junctions with dissimilar materials, control and expansion joints, ceramic accessories, and setting details.

D. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.

E. Maintenance Data: Include recommended cleaning methods, cleaning materials, and stain removal methods.

F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
   1. See Section 01 6000 - Product Requirements, for additional provisions.
   2. Extra Tile: 10 square feet of each size, color, and surface finish combination.

1.05 QUALITY ASSURANCE

A. Maintain one copy of and ANSI A108/A118/A136.1 and TCNA (HB) on site.

B. Manufacturer Qualifications: Company specializing in manufacturing the types of products specified in this section, with minimum five years of documented experience.

C. Installer Qualifications: Company specializing in performing tile installation, with minimum of five years of documented experience.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Protect adhesives from freezing or overheating in accordance with manufacturer's instructions.

1.07 FIELD CONDITIONS

A. Do not install solvent-based products in an unventilated environment.

B. Maintain ambient and substrate temperature of 50 degrees F during installation of mortar materials.

PART 2 PRODUCTS

2.01 TILE

A. Quarry Tile: ANSI A137.1, standard grade.
   1. Moisture Absorption: 0.5 to 3.0 percent as tested in accordance with ASTM C373.
   2. Size: 6 by 6 inch, nominal.
   3. Thickness: 1/2 inch, nominal.
   4. Edges: Cushioned.
   5. Surface Finish: Unglazed.
   6. Color(s): To be selected by Architect from manufacturer's standard range.
   7. Trim Units: Matching cove base shapes in sizes coordinated with field tile.
   8. Products:
      a. Daltile: Quarry Tile..

B. Porcelain Tile: ANSI A137.1, standard grade.
   1. Moisture Absorption: 0 to 0.5 percent as tested in accordance with ASTM C373.
   2. Size: As shown on drawings
   3. Thickness: 3/8 inch.
   4. Edges: Cushioned.
   5. Surface Finish: Unglazed.
   6. Color(s): To be selected by Architect from manufacturer's standard range.
   7. Pattern: as shown on drawings.
   8. Trim Units: Matching bullnose, double bullnose, cove base, and cove shapes in sizes coordinated with field tile.

9. Products:
    a. Garden State Tile: Overall.

2.02 TRIM AND ACCESSORIES

A. Non-Ceramic Trim: Brushed stainless steel, style and dimensions as indicated on drawings, for setting using tile mortar or adhesive.
    1. Manufacturers:
        a. Schluter-Systems: www.schluter.com.
        b. Substitutions: See Section 01 6000 - Product Requirements.

2.03 SETTING MATERIALS

A. Provide setting materials made by the same manufacturer as grout.

B. Latex-Portland Cement Mortar Bond Coat: ANSI A118.4 or ANSI A118.15.
    1. Applications: Use this type of bond coat where indicated and where no other type of bond coat is indicated.
    2. Products:
        a. ARDEX Engineered Cements; ARDEX X 77 MICROTEC: www.ardexamericas.com.
        b. AVM Industries, Inc; Thin-Set 780: www.avmindustries.com.
        c. LATICRETE International, Inc; LATICRETE 254 Platinum: www.laticrete.com.
        d. Merkrete, by Parex USA, Inc; Merkrete 735 Premium Flex: www.merkrete.com/sle.
        e. ProSpec, an Oldcastle brand; Permalastic System: www.prospec.com.
        f. Substitutions: See Section 01 6000 - Product Requirements.

C. Organic Adhesive: ANSI A136.1, thinset mastic type.
    1. Applications: wall and soffit tile.
    2. Use Type I in areas subject to prolonged moisture exposure.
    3. Products:
        a. ARDEX Engineered Cements; ARDEX D14: www.ardexamericas.com.
        b. Bostik Inc: www.bostik-us.com.
        c. LATICRETE International, Inc; LATICRETE 15 Premium Mastic: www.laticrete.com.
        d. Merkrete, by Parex USA, Inc; Merkrete Merstik: www.merkrete.com/sle.
        e. ProSpec, an Oldcastle brand; B-4050 Multi-Purpose Adhesive: www.prospec.com.
        f. Substitutions: See Section 01 6000 - Product Requirements.

2.04 ADHESIVE MATERIALS

A. Manufacturers:
    1. Bonsal American, Inc: www.prospec.com
    2. Bostik Inc: www.bostik-us.com.
    3. Mapei Corporation: www.mapei.com.
    4. Substitutions: See Section 01 6000 - Product Requirements.

B. Organic Adhesive: ANSI A136.1, thinset bond type; use Type I in areas subject to prolonged moisture exposure.

C. Mortar Bed Materials: Portland cement, sand, latex additive, and water.

D. Mortar Bond Coat Materials:
    1. Dry-Set Portland Cement type: ANSI A118.1.
    2. Latex-Portland Cement type: ANSI A118.4.

2.05 GROUTS

A. Manufacturers:
   1. ARDEX Engineered Cements: www.ardexamericas.com.
   2. ProSpec, an Oldcastle brand: www.prospec.com.
   3. Bonsal American, Inc: www.prospec.com
   4. Bostik Inc: www.bostik-us.com.
   5. LATICRETE International, Inc: www.laticrete.com.
   6. Merkrete, by Parex USA, Inc: www.merkrete.com/sle.
   7. Custom Building Products: www.custombuildingproducts.com.
   8. Substitutions: See Section 01 6000 - Product Requirements.

B. Standard Grout: ANSI A118.6 standard cement grout.
   1. Applications: Use this type of grout where indicated and where no other type of grout is indicated.
   2. Use sanded grout for joints 1/8 inch wide and larger; use unsanded grout for joints less than 1/8 inch wide.
   3. Color(s): As selected by Architect from manufacturer's full line.
   4. Products:
      a. Bostik Inc: www.bostik-us.com.
      b. LATICRETE International, Inc: www.laticrete.com.
      c. Merkrete, by Parex USA, Inc: www.merkrete.com/sle.
      d. ProSpec, an Oldcastle brand: www.prospec.com.
      e. Substitutions: See Section 01 6000 - Product Requirements.

2.06 THICK-BED MATERIALS

A. Mortar Bed Materials: Portland cement, sand, latex additive, and water.
   1. Products:
      a. LATICRETE International, Inc; LATICRETE 3701 Fortified Mortar Bed: www.laticrete.com.
      b. Merkrete, by Parex USA, Inc.; Merkrete Underlay C: www.merkrete.com.
      c. Substitutions: See Section 01 6000 - Product Requirements.

B. Cleavage Membrane: No. 15 asphalt saturated felt.

2.07 ACCESSORY MATERIALS

A. Backer Board: Cementitious type complying with ANSI A118.9; high density, glass fiber reinforced, 1/2 inch thick; 2 inch wide coated glass fiber tape for joints and corners.
   1. Products:
      a. Refer to section 09 2116 Gypsum Board Assemblies.

B. Grout Sealant: Manufacturer's standard product for sealing grout joints that does not change color or appearance of grout.
   1. Bonsal American, Inc.: Grout Sealer.
   2. Bostik: CeramaSeal Grout Sealer.
   3. C-Cure: Penetrating Sealer 978.
   4. MAPEI Corporation: KER 003, Silicone Spray Sealer for Cementitious Tile Grout.
   5. Summitville Tiles, Inc.: SL-15, Invisible Seal Penetrating Grout and TIle Sealer.
   6. TEC Specialty Products, Inc.; TA-256 Penetrating Silicone Grout Sealer.

C. Heavy-duty, non-staining construction paper with compatible adhesive tape.

D. Neutral Cleaner:

1. Hillyard Super Shine-All.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that sub-floor surfaces are smooth and flat within the tolerances specified for that type of work and are ready to receive tile.

B. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive tile.

C. Verify that sub-floor surfaces are dust-free and free of substances that could impair bonding of setting materials to sub-floor surfaces.

D. Verify that concrete sub-floor surfaces are ready for tile installation by testing for moisture emission rate and alkalinity; obtain instructions if test results are not within limits recommended by tile manufacturer and setting materials manufacturer.

E. Verify that required floor-mounted utilities are in correct location.

3.02 PREPARATION

A. Protect surrounding work from damage.

B. Vacuum clean surfaces and damp clean.

C. Seal substrate surface cracks with filler. Level existing substrate surfaces to acceptable flatness tolerances.

D. Install cementitious backer board in accordance with ANSI A108.11 and board manufacturer's instructions. Tape joints and corners, cover with skim coat of specified mortar to a feather edge.

E. Prepare substrate surfaces for adhesive installation in accordance with adhesive manufacturer's instructions.

3.03 INSTALLATION - GENERAL

A. Install tile and grout in accordance with applicable requirements of ANSI A108.1a through ANSI A108.13, manufacturer's instructions, and TCNA (HB) recommendations.

B. Lay tile in pattern as shown on drawings. Do not interrupt tile pattern through openings.

C. Cut and fit tile to penetrations through tile, leaving sealant joint space. Form corners and bases neatly.

D. Place tile joints uniform in width, subject to variance in tolerance allowed in tile size. Make grout joints without voids, cracks, excess mortar or excess grout, or too little grout.

E. Form internal angles square and external angles square.

F. Install non-ceramic trim in accordance with manufacturer's instructions.

G. Sound tile after setting. Replace hollow sounding units.

H. Prior to grouting, allow installation to completely cure; minimum of 48 hours.

I. Grout tile joints unless otherwise indicated. Use standard grout unless otherwise indicated.

J. At changes in plane and tile-to-tile control joints, use tile sealant instead of grout, with either bond breaker tape or backer rod as appropriate to prevent three-sided bonding.

K. Apply sealant to junction of tile and dissimilar materials and junction of dissimilar planes.

3.04 INSTALLATION - FLOORS - MORTAR BED METHODS

A. Over interior concrete substrates, install in accordance with TCNA (HB) Method F111, with cleavage membrane, unless otherwise indicated.
   1. Where waterproofing membrane is indicated, with standard grout or no mention of grout type, install in accordance with TCNA (HB) Method F121.
   2. Where epoxy bond coat and grout are indicated, install in accordance with TCNA (HB) Method F132, bonded.
   3. Where epoxy or furan grout is indicated, but not epoxy or furan bond coat, install in accordance with TCNA (HB) Method F114, with cleavage membrane.

B. Cleavage Membrane: Lap edges and ends.

C. Mortar Bed Thickness: match existing inch, unless otherwise indicated.

3.05 INSTALLATION - WALL TILE

A. Over cementitious backer units install in accordance with TCNA (HB) Method W223, organic adhesive.

B. Over interior concrete and masonry install in accordance with TCNA (HB) Method W202, thin-set with dry-set or latex-Portland cement bond coat.

3.06 GROUTING

A. Follow grout manufacturer's recommendations as to grouting procedures and precautions.

B. Remove all grout haze, observing both tile and group manufacturer's recommendations as to use of acid and chemical cleaners.

C. Rinse tile work thoroughly with clean water before and after chemical cleaners.

D. Polish surface of tile work with soft cloth.

E. Seal finished grout lines with sealer, applied following directions by the manufacturer.

3.07 CLEANING

A. Clean tile and grout surfaces.

3.08 PROTECTION

A. Apply a protective coat of neutral cleaner solution, 1 part cleaner to 1 part water, or as specified by manufacturer's instructions, to completed tile floors.

B. Cover all tile floors with heavy-duty, non-staining construction paper, taped in place.

C. Prior to final acceptance of tile work, remove paper and rinse protective coat of neutral cleaner from all tile surfaces.

D. Do not permit traffic over finished floor surface for 7 days after installation.

END OF SECTION

SECTION 09 5100
SUSPENDED ACOUSTICAL CEILINGS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Suspended metal grid ceiling system.

B. Acoustical units.

1.02 REFERENCE STANDARDS

A. ASTM C635/C635M - Standard Specification for the Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings; 2013a.

B. ASTM C636/C636M - Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels; 2013.

C. ASTM E580/E580M - Standard Practice for Installation of Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels in Areas Subject to Earthquake Ground Motions; 2014.

D. ASTM E1264 - Standard Classification for Acoustical Ceiling Products; 2014.

PART 2 PRODUCTS

2.01 ACOUSTICAL UNITS

A. Acoustical Panels Type 1: Painted mineral fiber, ASTM E1264 Type III, with the following characteristics:
   1. Size: 24 by 24 inches.
   2. Thickness: 3/4 inches.
   3. Edge: Square.
   4. Surface Color: White.
   5. Suspension System: Exposed grid Type 1.
   6. Products:
      a. Armstrong: Ultima Health Zone High NRC.
      b. Substitutions: See Section 01 6000 - Product Requirements.

2.02 SUSPENSION SYSTEM(S)

A. Suspension Systems - General: Complying with ASTM C635/C635M; die cut and interlocking components, with stabilizer bars, clips, splices, perimeter moldings, and hold down clips as required.

B. Exposed Aluminum Suspension System Type 1: Extruded aluminum; heavy-duty.
   1. Profile: Tee; 15/16 inch wide face.
   2. Finish: Painted white.

2.03 ACCESSORIES

A. Support Channels and Hangers: Galvanized steel; size and type to suit application, seismic requirements, and ceiling system flatness requirement specified.

B. Perimeter Moldings: Same material and finish as grid.
   1. At Exposed Grid: Provide L-shaped molding for mounting at same elevation as face of grid.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that layout of hangers will not interfere with other work.

3.02 INSTALLATION - SUSPENSION SYSTEM

A. Install suspension system in accordance with ASTM C636/C636M, ASTM E580/E580M, and manufacturer's instructions and as supplemented in this section.

B. Rigidly secure system, including integral mechanical and electrical components, for maximum deflection of 1:360.

C. Locate system on room axis according to reflected plan.

D. Install after major above-ceiling work is complete. Coordinate the location of hangers with other work.

E. Hang suspension system independent of walls, columns, ducts, pipes and conduit. Where carrying members are spliced, avoid visible displacement of face plane of adjacent members.

F. Where ducts or other equipment prevent the regular spacing of hangers, reinforce the nearest affected hangers and related carrying channels to span the extra distance.

G. Do not support components on main runners or cross runners if weight causes total dead load to exceed deflection capability.

H. Support fixture loads using supplementary hangers located within 6 inches of each corner, or support components independently.

I. Do not eccentrically load system or induce rotation of runners.

J. Perimeter Molding: Install at intersection of ceiling and vertical surfaces and at junctions with other interruptions.
   1. Use longest practical lengths.
   2. Overlap and rivet corners.

3.03 TOLERANCES

A. Maximum Variation from Flat and Level Surface: 1/8 inch in 10 feet.

B. Maximum Variation from Plumb of Grid Members Caused by Eccentric Loads: 2 degrees.

END OF SECTION

SECTION 09 6500
RESILIENT FLOORING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Resilient tile flooring.

B. Resilient base.

1.02 RELATED REQUIREMENTS

A. Section 03 3000 - Cast-in-Place Concrete: Restrictions on curing compounds for concrete slabs and floors.

B. Section 09 0561 - Common Work Results for Flooring Preparation: Independent agency testing of concrete slabs, removal of existing floor coverings, cleaning, and preparation.

1.03 REFERENCE STANDARDS

A. ASTM F1066 - Standard Specification for Vinyl Composition Floor Tile; 2004 (Reapproved 2014).

B. ASTM F1344 - Standard Specification for Rubber Floor Tile; 2015.

C. ASTM F1861 - Standard Specification for Resilient Wall Base; 2008 (Reapproved 2012).

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data on specified products, describing physical and performance characteristics; including sizes, patterns and colors available; and installation instructions.

C. Selection Samples: Submit manufacturer's complete set of color samples for Architect's initial selection.

D. Concrete Testing Standard: Submit a copy of ASTM F710.

E. Certification: Prior to installation of flooring, submit written certification by flooring manufacturer and adhesive manufacturer that condition of sub-floor is acceptable.

F. Maintenance Data: Include maintenance procedures, recommended maintenance materials, and suggested schedule for cleaning, stripping, and re-waxing.

G. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
   1. See Section 01 6000 - Product Requirements, for additional provisions.

1.05 DELIVERY, STORAGE, AND HANDLING

A. Upon receipt, immediately remove any shrink-wrap and check materials for damage and the correct style, color, quantity and run numbers.

B. Store all materials off of the floor in an acclimatized, weather-tight space.

C. Maintain temperature in storage area between 55 degrees F and 90 degrees F.

D. Protect roll materials from damage by storing on end.

E. Do not double stack pallets.

1.06 FIELD CONDITIONS

A. Store materials for not less than 48 hours prior to installation in area of installation at a temperature of 70 degrees F to achieve temperature stability. Thereafter, maintain conditions above 55 degrees F.

PART 2 PRODUCTS

2.01 TILE FLOORING

A. Vinyl Composition Tile: Homogeneous, with color extending throughout thickness.
   1. Minimum Requirements: Comply with ASTM F1066, of Class corresponding to type specified.
   2. Size: 12 by 12 inch.
   3. Thickness: 0.125 inch.
   4. Color: Match exisitng.

B. Rubber Tile: Type I- Homogeneous, color and pattern throughout thickness; Type II- Heterogeneous, laminated.
   1. Minimum Requirements: Comply with ASTM F1344, of Class corresponding to type specified.
   2. Size: 24 by 24 inch.
   3. Total Thickness: 0.125 inch.

2.02 RESILIENT BASE

A. Resilient Base: ASTM F1861, Type TS rubber, vulcanized thermoset; top set Style B, Cove.
   1. Height: 4 inch.
   2. Thickness: 0.125 inch thick.
   3. Finish: Satin.

END OF SECTION

SECTION 09 7733
GLASS FIBER REINFORCED PLASTIC PANELS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Glass fiber reinforced plastic panels.

B. Trim.

1.02 REFERENCE STANDARDS

A. ASTM D5319 - Standard Specification for Glass-Fiber Reinforced Polyester Wall and Ceiling Panels; 2012.

B. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2016.

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data on specified products, describing physical and performance characteristics; including sizes, patterns and colors available; and installation instructions.

C. Samples: Submit two samples 6 by 6 inch in size illustrating material and surface design of panels.

1.04 DELIVERY, STORAGE, AND HANDLING

A. Store panels flat, indoors, on a clean, dry surface. Remove packaging and allow panels to acclimate to room temperature for 48 hours prior to installation.

PART 2 PRODUCTS

2.01 PANEL SYSTEMS

A. Wall Panels:
   1. Panel Size: 4 by 8 feet.
   2. Panel Thickness: 0.10 inch.
   3. Surface Design: Embossed.
   4. Color: White.
   5. Attachment Method: Adhesive only, with trim and sealant in joints.

2.02 MATERIALS

A. Panels: Glass fiber reinforced plastic (FRP), complying with ASTM D5319.
   1. Surface Burning Characteristics: Maximum flame spread index of 25 and smoke developed index of 450; when system tested in accordance with ASTM E84.

B. Trim: Vinyl; color coordinating with panel.

C. Adhesive: Type recommended by panel manufacturer.

D. Sealant: Type recommended by panel manufacturer; white.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify existing conditions and substrate flatness before starting work.

B. Verify that substrate conditions are ready to receive the work of this section.

3.02 INSTALLATION - WALLS

A. Install panels in accordance with manufacturer's instructions.

B. Cut and drill panels with carbide tipped saw blades, drill bits, or snips.

C. Apply adhesive to the back side of the panel using trowel as recommended by adhesive manufacturer.

D. Apply panels to wall with seams plumb and pattern aligned with adjoining panels.

E. Install panels with manufacturer's recommended gap for panel field and corner joints.

F. Place trim on panel before fastening edges, as required.

G. Fill channels in trim with sealant before attaching to panel.

H. Install trim with adhesive and screws or nails, as required.

I. Seal gaps at floor, ceiling, and between panels with applicable sealant to prevent moisture intrusion.

J. Remove excess sealant after paneling is installed and prior to curing.

END OF SECTION

SECTION 09 9000
PAINTING AND COATING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Surface preparation.

B. Field application of paints and stains.

C. Surfaces to be finished are indicated in this section and on the Drawings.

1.02 RELATED REQUIREMENTS

1.03 REFERENCE STANDARDS

A. 40 CFR 59, Subpart D - National Volatile Organic Compound Emission Standards for Architectural Coatings; U.S. Environmental Protection Agency; current edition.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide complete list of all products to be used, with the following information for each:
   1. Manufacturer's name, product name and/or catalog number, and general product category (e.g. "alkyd enamel").
   2. Submit products and systems by substrate as listed in Part 2.

C. Certification: By manufacturer that all paints and coatings comply with VOC limits specified.

D. Samples: Submit one paper "drop" samples, 8-1/2 by 11 inches in size, illustrating colors selected for each finishing product specified.
   1. Where sheen is specified, submit samples in only that sheen.

1.05 MAINTENANCE MATERIALS SUBMITTALS

A. Coating Maintenance Manual: Upon conclusion of the project, the Contractor or paint manufacturer/supplier shall furnish a coating maintenance manual.

B. Manual shall include:
   1. Area Summary with finish schedule,
   2. Area Detail designating where each product/color/finish was used,
   3. product data pages, Material Safety Data Sheets, care and cleaning instructions, touch-up procedures,
   4. color samples of each color and finish used.

1.06 QUALITY ASSURANCE

A. Applicator Qualifications: Company specializing in performing the work of this section with minimum 5 years experience.

B. Material Safety Data Sheets: At project site maintain file of MSDS sheets for each product used; become familiar with and follow manufacturer's stated application and safety requirements.

1.07 DELIVERY, STORAGE, AND HANDLING

A. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.

B. Container Label: Include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation, and instructions for mixing and reducing.

C. Paint Materials: Store at minimum ambient temperature of 45 degrees F and a maximum of 90 degrees F, in ventilated area, and as required by manufacturer's instructions.

1.08 FIELD CONDITIONS

A. Do not apply materials when surface and ambient temperatures are outside the temperature ranges required by the paint product manufacturer.

B. Follow manufacturer's recommended procedures for producing best results, including testing of substrates, moisture in substrates, and humidity and temperature limitations.

C. Minimum Application Temperatures for Latex Paints: 45 degrees F for interiors; 50 degrees F for exterior; unless required otherwise by manufacturer's instructions.

D. Provide lighting level of 80 ft candles measured mid-height at substrate surface.

1.09 EXTRA MATERIALS

A. See Section 01 6000 - Product Requirements, for additional provisions.

B. Supply 1 gallon of each color; store where directed.

C. Label each container with color in addition to the manufacturer's label.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Provide all paint and coating products used in any individual system from the same manufacturer.

B. Provide all paint and coating products from the same manufacturer to the greatest extent possible.

C. In the event that a single manufacturer cannot provide all specified products, minor exceptions will be permitted provided approval by Architect is obtained using the specified procedures for substitutions.

D. Paints: Acceptable manufacturers are limited to the following:
   1. Benjamin Moore & Co: www.benjaminmoore.com.
   2. Sherwin-Williams: www.sherwin-williams.com.
   3. Glidden Professional: www.gliddenprofessional.com.

E. Stains: Acceptable manufacturers are limited to the following:
   1. Benjamin Moore & Co: www.benjaminmoore.com.
   2. Sherwin-Williams: www.sherwin-williams.com.
   3. Glidden Professional: www.gliddenprofessional.com.

F. Substitutions: See Section 01 6000 - Product Requirements.

2.02 MATERIALS - GENERAL

A. Volatile Organic Compound (VOC) Content:
   1. Provide coatings that comply with the most stringent requirements specified in the following:
      a. 40 CFR 59, Subpart D--National Volatile Organic Compound Emission Standards for Architectural Coatings.
      b. Ozone Transport Commission (OTC) Model Rule, Architectural, Industrial, and Maintenance Coatings; www.otcair.org; specifically:
         1) Opaque, Flat: 50 g/L, maximum.
         2) Opaque, Nonflat: 150 g/L, maximum.
         3) Opaque, High Gloss: 250 g/L, maximum.

4) Varnishes: 350 g/L, maximum.
c. Architectural coatings VOC limits of State in which the project is located.
2. Determination of VOC Content: Testing and calculation in accordance with 40 CFR 59, Subpart D (EPA Method 24), exclusive of colorants added to a tint base and water added at project site; or other method acceptable to authorities having jurisdiction.
3. Provide tints and colorants that will not add VOCs to specified products.

B. Paints and Coatings:
1. Provide ready mixed paints and coatings .
2. Provide materials that are compatible with one another and the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.

2.03 PAINT SYSTEMS

A. Provide colors as directed by Architect.
1. Allow for minimum of five colors for each system, unless otherwise indicated, without additional cost to Owner.
2. Extend colors to surface edges; colors may change at any edge as directed by Architect.

2.04 INTERIOR PAINT SYSTEMS

A. SYSTEM I-1:
1. Substrate: Concrete Masonry Units
2. Manufacturers and Products:
a. Sherwin Williams:
1) 1st Coat: S-W PrepRite® Block Filler, B25W25
2) 2nd Coat: S-W Pro Industrial PreCatalyzed WB Epoxy, semi-gloss
3) 3rd Coat: S-W Pro Industrial PreCatalyzed WB Epoxy, semi-gloss
b. Benjamin Moore:
1) 1st Coat:Moore 160 Super Spec Latex Block Filler
2) 2nd Coat:333 Regal AquaGlo Acrylic Semi-Gloss Enamel
3) 3rd Coat:333 Regal AquaGlo Acrylic Semi-Gloss Enamel
c. Glidden Professional:
1) 1st Coat:Glidden Professional Block Filler 3010 primer
2) 2nd Coat:Glidden Professional Diamond 450 7400 topcoat
3) 3rd Coat:Glidden Professional Diamond 450 7400 topcoat

B. SYSTEM I-4
1. Substrate: Hollow metal door frames:
2. Finish: Semi-Gloss.
3. Manufacturers and Products:
a. Sherwin Williams:
1) 1st Coat: S-W Pro Industrial Pro-Cryl® Primer, B66-310 Series
2) 2nd Coat: S-W ProIndustrial WB Alkyd Urethane Enamel,semi-gloss B53-1150
3) 3rd Coat: S-W ProIndustrial WB Alkyd Urethane Enamel,semi-gloss B53-1150
b. Benjamin Moore:
1) 1st Coat: Moorcraft Super Spec DTM Alkyd Satin, Z163
2) 2nd Coat:Moorcraft Super Spec Urethane Gloss Enamel, Z22
3) 3rd Coat: Moorcraft Super Spec Urethane Gloss Enamel, Z22
c. Glidden Professional:
1) 1st Coat: DEVGUARD 4360 Low VOC Universal Primer

2) 2nd Coat:DEVGUARD 4309 Rust Preventative Gloss Enamel
3) 3rd Coat: DEVGUARD 4309 Rust Preventative Gloss Enamel

C. SYSTEM I-5
1. Substrate: Metal door frames - PREVIOUSLY PAINTED
a. Sherwin Williams:
1) 1st Coat: S-W Extrem Bond Primer
2) 2nd Coat: S-W ProIndustrial WB Alkyd Urethane Enamel,semi-gloss B53-1150
3) 3rd Coat: S-W ProIndustrial WB Alkyd Urethane Enamel,semi-gloss B53-1150
b. Benjamin Moore:
1) 1st Coat: Moorcraft Super Spec DTM Alkyd Satin, Z163
2) 2nd Coat:Moorcraft Super Spec Urethane Semi-Gloss Enamel
3) 3rd Coat: Moorcraft Super Spec Urethane Semi-Gloss Enamel
c. Glidden Professional:
1) 1st Coat: DEVGUARD 4360 Low VOC Universal Primer
2) 2nd Coat:DEVGUARD 4309 Rust Preventative Gloss Enamel
3) 3rd Coat: DEVGUARD 4309 Rust Preventative Gloss Enamel
d.

D. SYSTEM I-8
1. Substrate: Woodwork (Transparent, Not Floors or Stairs):
2. Applications include but are not limited to wood doors:
3. Manufacturers and Products:
a. Sherwin Williams:
1) Stain: S-W Minwax 250 VOC Oil Stain
2) Sealer: Sher-Wood Natural Wood Filler
3) 2nd Coat: S-W Wood Classics® Waterborne Polyurethane Varnish, Satin
4) 3rd Coat: S-W Wood Classics® Waterborne Polyurethane Varnish, Satin
b. Benjamin Moore:
1) Stain: Moore 234 Benwood Alkyd Wood Stain
2) Sealer: Moore 413 Benwood Quick-Dry Alkyd Sanding Sealer
3) 2nd Coat: 423 Benwood Stays Clear Acrylic Low Lustre Polyurethane
4) 3rd Coat: 423 Benwood Stays Clear Acrylic Low Lustre Polyurethane
c. Glidden Professional:
1) Stain: 1700V Wood Pride Water-Based Wood Stain
2) Sealer: 1808 Wood Pride Water-based Gloss Varnish
3) 2nd Coat: 1802 Wood Pride Water-based Satin Varnish
4) 3rd Coat: 1802 Wood Pride Water-based Satin Varnish

E. SYSTEM I-13
1. Substrate: Gypsum Board (Microbicidal Eggshell Finish):
2. Manufacturers and Products:
a. Sherwin Williams:
1) 1st Coat: S-W Harmony Primer
2) 2nd Coat: S-W Paint Shield Microbicidal Latex Eggshell, (no substitutions)
3) 3rd Coat: S-W Paint Shield Microbicidal Latex Eggshell, (no substitutions)

PART 3 EXECUTION

3.01 SCOPE -- SURFACES TO BE FINISHED

A. Paint all exposed surfaces except where indicated not to be painted or to remain natural; the term "exposed" includes areas visible through permanent and built-in fixtures when they are in place.

B. Paint the surfaces described in PART 2, indicated on the Drawings, and as follows:
   1. If a surface, material, or item is not specifically mentioned, paint in the same manner as similar surfaces, materials, or items, regardless of whether colors are indicated or not.
   2. Paint surfaces behind movable equipment and furnishings the same as similar exposed surfaces.
   3. Paint surfaces to be concealed behind permanently installed fixtures, equipment, and furnishings, using primer only, prior to installation of the permanent item.
   4. Finish top, bottom, and side edges of exterior doors the same as exposed faces.

C. Do Not Paint or Finish the Following Items:
   1. Items fully factory-finished unless specifically noted; factory-primed items are not considered factory-finished.
   2. Items indicated to receive other finish.
   3. Items indicated to remain naturally finished.
   4. Fire rating labels, equipment serial number and capacity labels, and operating parts of equipment.
   5. Anodized aluminum.
   6. Polished and brushed stainless steel items.
   7. Brick, precast concrete, integrally colored plaster.
   8. Polished and brushed stainless steel, anodized aluminum, bronze, terne, and lead.
   9. Acoustical materials.
   10. Concealed piping, ductwork, and conduit.

3.02 EXAMINATION

A. Verify that surfaces are ready to receive Work as instructed by the product manufacturer.

B. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially affect proper application.

C. Test shop-applied primer for compatibility with subsequent cover materials; report incompatible primer conditions and submit recommended changes for Architect's approval.

D. Measure moisture content of surfaces using an electronic moisture meter. Do not apply finishes unless moisture content of surfaces are below the following maximums:
   1. Masonry, Concrete, and Concrete Unit Masonry: 12 percent.
   2. Interior Wood: 15 percent, measured in accordance with ASTM D4442.
   3. Exterior Wood: 15 percent, measured in accordance with ASTM D4442.

E. Measure the ph factor of concrete, masonry, and mortar before starting any finishing process, using the method specified in MPI Architectural Painting Manual.
   1. Report results in writing to Architect before starting work.
   2. If results of test indicates need for remedial action, provide written description of remedial action. If a different primer or paint systems is required, state the total cost of the change. Do not proceed with remedial action or change without receiving written authorization from Architect.

3.03 PREPARATION

A. Prepare surfaces as specified in MPI Architectural Painting Specification Manual and as follows for the applicable surface and coating; if multiple preparation treatments are specified, use as many as necessary for best results; where the Manual references external standards for preparation (e.g. SSPC standards), prepare as specified in those standards; comply with coating manufacturer's specific preparation methods or treatments, if any.

B. Coordinate painting work with cleaning and preparation work so that dust and other contaminants do not fall on newly painted, wet surfaces.

C. Surface Appurtenances: Prior to preparing surfaces or finishing, remove electrical plates, hardware, light fixtures, light fixture trim, escutcheons, machined surfaces, fittings, and similar items already installed that are not to be painted.
   1. If removal is impractical or impossible because of the size or weight of the item, provide surface-applied protection before preparation and finishing.
   2. After completing painting in each space or area, reinstall items removed using workers skilled in the trades involved.

D. Surfaces: Correct defects and clean surfaces which affect work of this section.

E. Marks: Seal with shellac those which may bleed through surface finishes.

F. Impervious Surfaces: Remove mildew by scrubbing with solution of tetra-sodium phosphate and bleach. Rinse with clean water and allow surface to dry.

G. Concrete, Cement Plaster and Unit Masonry Surfaces to be Painted: Remove dirt, loose mortar, scale, salt or alkali powder, and other foreign matter. Remove oil and grease with a solution of tri-sodium phosphate; rinse well and allow to dry. Remove stains caused by weathering of corroding metals with a solution of sodium metasilicate after thoroughly wetting with water. Allow to dry.

H. Interior Wood Items to Receive Transparent Finish: Sand wood to obtain a uniform appearance before immediately starting work. Wipe off dust and grit prior to sealing, seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes and cracks after sealer has dried; sand lightly between coats. Prime concealed surfaces with gloss varnish reduced 25 percent with thinner.

3.04 APPLICATION

A. Apply products in accordance with manufacturer's instructions and as specified or recommended by MPI Manual, using the preparation, products, sheens, textures, and colors as indicated.
   1. Remove, refinish, or repaint work not complying with requirements.

B. Do not apply finishes over dirt, rust, scale, grease, moisture, scuffed surfaces, or other conditions detrimental to formation of a durable coating film; do not apply finishes to surfaces that are not dry.

C. Use applicators and methods best suited for substrate and type of material being applied and according to manufacturer's instructions.

D. Minimum Coating Thickness: Apply paint materials no thinner than manufacturer's recommended spreading rate; provide total dry film thickness of entire system as recommended by manufacturer.
   1. Number of coats and film thickness required are the same regardless of application method.

2. If undercoats, stains, or other conditions show through final coat of paint, apply additional coats until paint film is of uniform finish, color, and appearance.
3. Give special attention to ensure edges, corners, crevices, welds, and exposed fasteners receive dry film thickness equivalent to that of flat surfaces.

E. Apply finish to completely cover surfaces with uniform appearance without brush marks, runs, sags, laps, ropiness, holidays, spotting, cloudiness, or other surface imperfections.
1. Before applying finish coats, apply a prime coat of material recommended by manufacturer, unless the surface has been prime coated by others; where evidence of suction spots or unsealed areas in first coat appear, recoat primed and sealed surfaces to ensure finish coat with no burn through or other defects due to insufficient sealing.
2. Apply first coat to surface that has been cleaned, pretreated, or otherwise prepared as soon as practical after preparation and before subsequent surface deterioration.
3. Do not apply succeeding coats until the previous coat has cured as recommended by manufacturer.
4. Do not recoat until paint has dried to where it feels firm, does not deform or feel sticky under moderate thumb pressure, and application of another coat will not cause the undercoat to lift or lose adhesion.
5. If manufacturer's instructions recommend sanding to produce a smooth, even surface, sand between coats.
6. Before applying next coat vacuum clean surfaces of loose particles. Use tack cloth to remove dust and particles just prior to applying next coat.
7. Pigmented (Opaque) Finishes: Provide smooth, opaque surface of uniform finish, color, appearance, and coverage.

3.05 FIELD QUALITY CONTROL

A. See Section 01 4000 - Quality Requirements, for general requirements for field inspection.

B. Owner will provide field inspection.

3.06 CLEANING AND PROTECTION

A. Collect waste material which may constitute a fire hazard, place in closed metal containers, and remove daily from site.

B. At the end of each workday, remove empty cans, rags, rubbish, and other discarded paint materials from site.

C. Protect other work, whether being painted or not, against damage by painting. Correct damage by cleaning, repairing or replacing, and repainting as approved by Architect.

D. Provide "Wet Paint" signs to protect newly painted finishes. Remove temporary protective wrappings provided by others to protect their work after completing painting operations.

E. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces. Comply with procedures specified in MPI Manual.

END OF SECTION

SECTION 10 4400
FIRE PROTECTION SPECIALTIES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Fire extinguishers.

B. Accessories.

1.02 REFERENCE STANDARDS

A. NFPA 10 - Standard for Portable Fire Extinguishers; 2013.

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide extinguisher ratings and classifications, color and finish, and installation instructions.

C. Shop Drawings: Indicate cabinet physical dimensions, rough-in measurements for recessed cabinets, installation procedures, and accessories required for complete installation.

D. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.

E. Maintenance Data: Include test, refill or recharge schedules and re-certification requirements.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Fire Extinguishers:
1. Amerex Corporation: www.amerex-fire.com.
2. Substitutions: See Section 01 6000 - Product Requirements.

2.02 FIRE EXTINGUISHERS

A. Fire Extinguishers - General: Comply with product requirements of NFPA 10 and applicable codes, whichever is more stringent.

B. Dry Chemical Type Fire Extinguishers: Stainless steel tank, with pressure gage.
1. Class: K type.
2. Size: 1.6 gallons.
3. Finish: Polished stainless steel.
4. Temperature range: Minus 20 degrees F to 120 degrees F.

2.03 ACCESSORIES

A. Extinguisher Brackets: Formed steel, chrome-plated.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify existing conditions before starting work.

B. Verify rough openings for cabinet are correctly sized and located.

3.02 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Secure rigidly in place.

C. Place extinguishers on wall brackets.

D. Position cabinet signage at _____.

3.03 SCHEDULES

A. Loactins as shown on drawings.

END OF SECTION

SECTION 210170

FIRE PROTECTION SYSTEMS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The drawings and general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the work specified in this Section.

B. Codes and Standards listed below, apply to work indicated on the drawings and in the specifications.

1. National Fire Protection Association (NFPA)
2. Delaware State Fire Prevention Regulations (DSFPR)
3. American National Standards Institute (ANSI)
4. American Society for Testing Materials (ASTM)
5. National Electrical Manufacturer's Association (NEMA)
6. Underwriters' Laboratories (UL)

1.2 DESCRIPTION OF WORK

A. This Section shall include all work necessary and/or required and furnish all materials and equipment for construction of a complete automatic sprinkler system (and fire standpipe system) for the building areas indicated. Such work includes but is not limited to the following:

1. UL/FM labeled equipment.
2. Connection to water supply provided by Plumbing Contractor.
3. Installation of fire department connection.
4. All piping and equipment required for a complete wet sprinkler system on occupied floor levels.
5. All piping and equipment required for a complete dry sprinkler system where shown.
6. Installation of zoned test assemblies.
7. Installation of tamper and flow switches.
8. Installation of riser check valve assembly.
9. Installation of backflow preventer.
10. All piping and equipment for a complete wet fire standpipe system.
11. A complete fire pump installation including fire pump, jockey pump, pump controller and test header. (See Section 210171)
12. To coordinate with the Mechanical, Plumbing and Electrical Contractors, the installation of the mains and sprinkler piping and supports to allow installation of their work with maximized accessibility for these trades and service requirements for maintenance and repair. Prior to installing any piping or other devices, obtain written conformation from these contractors that requirements, conflicts and coordination issues have been discussed and resolved. Provide system drawings with elevation of any piping or other systems to the Mechanical Contractor so he can prepare the necessary coordination drawings that may be required. No work may be installed until the coordination issues are resolved. Any and all expense relating to coordination issues shall be born by the Contractor who did not install his work according to the coordination drawings.

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

B. Sprinkler System Contractor shall provide new separate and complete sprinkler systems (wet and dry) in satisfactory operating condition which shall conform to requirements of the following:

1. NFPA Pamphlet 13
2. _____ Fire Marshal's Office
3. Owner's Insurance Agency
4. Owner’s Standards

C. Submit working drawings to the _____ Fire Marshal's Office and obtain approval before beginning work.

D. Sprinkler systems shall be "_____ Hazard Occupancy" and shall cover all rooms, closets, attic spaces, etc., in the entire building.

1. Design and layout shall be based on Calculated System (Hydraulic).
2. Exact routing of piping shall be governed by structural conditions and obstructions.
3. The Sprinkler Contractor shall coordinate his work with the other trades so as to clear all construction items, lights, ducts, piping, etc.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

Submit shop drawings with Fire Marshal's approval and descriptive data, complete with product designation for the following:

1. OS&Y Valves
2. Sprinkler Heads
3. Check Valves
4. Siamese Connection
5. Dry Pipe Valve w/Compressor
6. Riser Check Valve Assembly
7. Fire Department Hose Valves
8. Backflow Preventer

B. Submit complete sprinkler layout indicating location of heads by dimensions from walls, pipe size, and locations of valves, fittings and accessories, with Fire Marshal's approval.

C. Submit manufacturer's product data on sprinkler heads, valves, fire department connections, air compressor, hangers, pipe, and fittings, etc.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

1.7 TESTS AND INSPECTIONS

A. Contractor shall arrange and pay for all inspections, examinations and tests required by authorities specified herein and deliver certificates of such inspections to Owner.

B. Complete sprinkler system shall be tested in accordance with the latest requirements of NFPA Pamphlet 13 and the _____ Fire Marshal's Office.

C. Fire Marshal's acceptance test shall be performed before system is placed in service and not less than five working days after Fire Marshal is notified.

1.8 QUALIFICATIONS OF CONTRACTOR

A. Contractor for sprinkler installation shall be licensed by the State of _____and be regularly engaged in installation of automatic sprinkler systems and other fire protection equipment.

B. Consult General Provisions for additional requirement.

PART 2 – PRODUCTS

2.1 FIRE PROTECTION PIPING MATERIALS & PRODUCTS

A. Provide piping materials and factory-fabricated piping products of sizes, types, pressure ratings, temperature ratings, and capacities as indicated. Where not indicated, provide proper selection as determined by installer to comply with installation requirements. Provide sizes and types matching piping and equipment connections; provide fittings of materials which match pipe materials used in fire protection piping systems. Where more than 1 type of materials or products are indicated, selection is installer's option.

2.2 BASIC IDENTIFICATION

A. Provide identification complying with applicable Division 22 sections in accordance with the following listings:

1. Fire Protection Piping: Plastic pipe markers.

2. Fire Protection Valves: Metallic valve tags.

2.3 BASIC PIPE AND FITTINGS

A. Comply with the weight, size and type of pipe and fittings by the latest issued schedule of NFPA Pamphlet 13, adopted by Authorities having jurisdiction.

B. All fire protection piping within the Mechanical Room shall be minimum Schedule 40 black iron pipe.

C. Plastic piping shall not be permitted.

D. Uni-Flange type connections shall not be permitted on this project.

2.4 BASIC PIPING SPECIALTIES

A. Provide piping specialties complying with Section 220010 Basic Materials & Methods in accordance with the following listing:

Pipe escutcheons

Dielectric unions

Drip pans

Sleeves

Sleeve seals

2.5 BASIC VALVES

A. Comply with the latest issue of NFPA 13 adopted by the Authorities having jurisdiction for the following:

Control Valve - OS&Y Valve

Check - Swing Valve

2.6 SPECIAL VALVE & ASSEMBLIES

A. Provide valves, UL listed, in accordance with the following listing. Provide sizes and types which mate and match piping and equipment connections.

B. Fire Department Connection: 4" x 2-1/2" x 2-1/2" back outlet, cast brass two-way inlet body with drop clappers, polished bronze plate with letters "AUTO SPKR" double female snoots with rigid end threaded to match local fire department, plugs and chain.

2.7 FIRE PROTECTION SPECIALTIES

A. Provide fire protection specialties, UL listed, in accordance with the following listing. Provide sizes and types which mate and match piping and equipment connections.

B. Automatic Sprinklers: Sprinkler heads shall be UL approved for intended use and have temperature ratings as indicated or required for location.

Provide the following type sprinkler heads as indicated:

Upright: Viking “Micromatic Model "M" bronze finish, 1/2" orifice.

Pendent: Viking “Micromatic Model "M" chrome plated, 1/2" orifice and escutcheon plate.

Pendent: Viking “Microfast Model “M” quick response with all white finish including escutcheon plate, ½” orifice.

Sidewall: Viking “Micromatic Model “M”, chrome plate, ½” orifice.

Sidewall: Viking “Microfast Model “M” – quick response, all white finish including escutcheon plate, ½” orifice.

Sidewall: (Extended Coverage) Viking “Microfast Model “M”, quick response, all white finish, extra large orifice.

Semi-Recessed: Viking “Silhouette Model A-1 quick response, chrome plated, ½” orifice.

Full Concealed: Viking “Horizon-Mirage” large orifice quick response, white cover plate.

Dry Sprinklers:

Upright: Viking “Model “M” plain barrel, ½” orifice bronze finish.

Pendent: Viking “Model “M”, adjustable standard, all white finish, ½” orifice.

Pendent: Viking “Model “M” adjustable semi-recessed, all white finish, ½” orifice.

Sidewall: Viking “Model “M” adjustable standard, all white finish, ½” orifice.

Sidewall: Viking “Model “M” adjustable semi-recessed, all white finish, ½” orifice.

C. Dry System - Dry Pipe Valve: Viking Model E furnished complete with all trimmings, all necessary fittings, appurtenances, accelerator, etc., including a suitable circuit closer for flow indication for the fire alarm system.

D. Dry System - Air Compressor: Provide an FM/UL approved listed Viking Model D-1 riser-mounted single stage, air-cooled, oilless air compressor, wired for 208 volt, 3 phase, 60 cycle. C.F.M. capacity and pressure requirements shall be based on system size and calculations. A dedicated electrical circuit shall be provided by the Electrical Contractor up to 2 HP rating at 208 volt, 3 phase.

E. Sprinkler Cabinet and Wrench: Furnish steel, baked red enameled, sprinkler box with capacity to store 10 sprinklers and wrench sized to sprinklers.

2.8 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the work include, but are not limited to, the following:

B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Specialty Valves and Devices:

   Vicatulic Company

   Tyco Fire Suppression & Building Products

   Reliable Automatic Sprinkler Co., Inc.

   Viking Corp.

2. Water-Flow Indicators and Supervisory Switches/and Electrical Bells:

   Tyco Fire Suppression & Building Products

   Potter Electric Signal Co.

   Reliable Automatic Sprinkler Co., Inc.

   Viking Corp.

3. Sprinkler, Drain and Alarm Test Fittings:

   Tyco Fire Suppression & Building Products

   Fire-End and Croker Corp.

   Victaulic Company

   AFG Manufacturing

4. Sprinkler, Branch-Line Test Fittings:

   Elkhart Brass Mfg. Co., Inc.

   Fire-End and Croker Corp.

   Smith Industries, Inc.; Potter-Roemer Div.

   AFG Manufacturing

5. Sprinkler, Inspector's Test Fittings:

   Fire-End and Croker Corp.

   G/J Innovations, Inc.

   Triple R Specialty of Ajax, Inc.

   AFG Manufacturing

6. Fire Department Connections:

   Potter-Roemer

   Elkhart Brass Mfg. Co., Inc.

   Fire-End and Croker Corp.

   Tyco Fire Suppression & Building Products

   Guardian Fire Equipment, Inc.

   Reliable Automatic Sprinkler Co., Inc.

7. Sprinklers:

   Tyco Fire Suppression & Building Products

   Reliable Automatic Sprinkler Co., Inc.

   Viking Corp.

   Victaulic Company

8. Fire Dept. Hose Valves:

   Potter-Roemer

   Elkhart

   Fire-End and Croker Corp.

   Guardian Fire Equipment, Inc.

   Fire Hose Valve Cabinets:

   Potter-Roemer

   Larsen

   Guardian Fire Equipment, Inc.

   Fire-End and Croker Corp.

9. Fire-Protection-Service Valves:

   Tyco Fire Suppression & Building Products

   Central Sprinkler Corp.

   Nibco, Inc.

   Stockham Valves & Fittings, Inc.

   Victaulic Company

10. Keyed Couplings for Steel Piping: (Grooved Fittings)

    Tyco Fire Suppression & Building Products

    Victaulic Company

    Viking Corp.

    Anvil International Grulok

11. Fire Protection Backflow Prevention Valve Assemblies (including RPZ Type).

    Ames Fire & Waterworks

Watts Regulator Company

Apollo Valves (Conbraco)

PART 3 – EXECUTION

3.1 INSTALLATION OF BASIC IDENTIFICATION

A. Install fire protection signs on piping in accordance with ANSI/NFPA 13.

3.2 FIRE SPRINKLER PIPING SYSTEMS

A. Comply with requirements of ANSI/NFPA 13 for installation of fire sprinkler piping materials. Install fire sprinkler piping products where indicated, in accordance with manufacturer's written instructions, and in accordance with recognized industry practices to ensure that fire sprinkler piping complies with requirements and serves intended purposes.

B. Coordinate with ceiling space available, other trades, including plumbing piping, as necessary to interface components of fire sprinkler piping properly with all other items of construction.

C. Install drain piping at low points of fire sprinkler piping.

D. Provide auxiliary drains as required.

E. Install system valve assemblies where indicated.

F. Install electric weatherproof bell where indicated.

G. Install siamese connection where indicated.

H. Install the following type sprinkler head in the following locations:

I. Exterior Sprinklers: Exterior sprinkler coverage and protection shall be provided for any canopy or soffit overhang construction.

J. Install sprinkler in acoustical tile suspended ceilings, in the center of the tile with heads installed in such a way that the requirements for both coverage and symmetry are fulfilled.

K. Install dry pipe valve complete with circuit closure and all trimmings required.

L. Install wall-mounted air compressor and piping to dry pipe valve.

M. No portion of the wet sprinkler system shall be installed within the attic and/or potential freezing areas of the building without being provided with freeze protection.

N. Provide tamper and flow switches where indicated or noted. All switches shall be wired by the Fire Alarm System Contractor. Provide all coordination and communication with the Fire Alarm Contractor for number and relocation of all switches.

3.3 INSTALLATION OF SUPPORTS, ANCHORS AND SEALS

A. Comply with the latest issue of NFPA adopted by the Authorities having jurisdiction.

3.4 INSTALLATION OF FIRE PROTECTION SPECIALTIES

A. Comply with the latest issue of NFPA adopted by the Authorities having jurisdiction.

3.5 ADJUST & CLEAN

A. Sprinkler Piping Flushing: Prior to connecting sprinkler risers for flushing, flush water feed mains, lead-in connections and control portions of sprinkler piping. After fire sprinkler piping installation has been completed and before piping is placed in service, flush entire sprinkler system, as required to remove foreign substances, under pressure as specified in ANSI/NFPA 13. Continue flushing until water is clear, and check to ensure that debris has not clogged sprinklers.

3.6 FIELD QUALITY CONTROL

A. Notify the Authority Having Jurisdiction, the Owner's Representative, and Architect & Engineer of time and date of scheduled testing. Provide minimum of 5 day prior notice of testing to allow for witnessing.

B. Perform all required system testing and acceptance requirements on the new (and modified) system installations in accordance with NFPA 13, 14, & 25, the Delaware State Fire Prevention Regulations, the Authorities Having Jurisdictions (AHJ) requirements and all other local codes and ordinances. At a minimum, provide hydrostatic pressure testing on new (and modified) above ground systems piping in accordance with NFPA 13. New system shall be tested to 50 psi over normal system working pressure (minimum 200 psi) for 2 hours without leaks.

C. Provide all required reports, records, and documentation, to the Owner, Engineer, and Authority Having Jurisdiction prior to or at the completion of the project. At a minimum, provide completed and signed "Contractor's Material and Test Certificate for Aboveground Piping" for each system.

D. As part of the sprinkler system renovations, the fire protection contractor shall perform an internal visual inspection of the sprinkler piping that is opened up as part of the renovation work (the five year internal pipe inspection in accordance with NFPA 25). This shall also include a visual inspection of the sprinklers that are removed as part of the renovation work. Any material found within the sprinkler piping and sprinklers that could potentially obstruct piping or plug sprinklers shall be reported to Owner (CCHS Fire Protection Services) for their review. Preferably and if possible, the obstruction material shall be left in situ for the Owner (CCHS Fire Protection Services) review before being removed.

3.7 EXTRA STOCK

A. For each style and temperature range required, furnish additional sprinkler heads, amounting to 1 unit for every 100 installed units.

END OF SECTION 210170

SECTION 220000

GENERAL PROVISIONS - PLUMBING/FIRE PROTECTION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and all other applicable Divisions, apply to work of this Section.

B. This specification or drawing and the design features or resulting construction disclosed, are the property of Furlow Associates, Inc., and shall not be reproduced without written permission.

C. All fire protection suppression systems shall be part of and included in all of the following 220000 thru 220191 Sections.

D. Refer to Section 07841 for Through-Penetration Firestop Systems. (DN: For BSA+A Specs)

E. Refer to Section 08311 for Access Doors and Frames (DN: For BSA+A Specs)

1.2 WORK INCLUDED

A. Refer to Section 220005: SCOPE OF WORK - PLUMBING/FIRE PROTECTION.

B. Provide labor, materials, equipment and supervision necessary to install complete operating Plumbing and Fire Protection Systems as indicated the drawings and specified herein, including all work at the site and within the proposed construction areas to accomplish the required work.

1.3 REGULATIONS, CODES AND STANDARDS

A. Work shall be performed in accordance with latest adopted codes, regulations and ordinances by authorities having jurisdiction. Observe all safety regulations.

B. Latest editions of any referenced standards shall govern.

C. Obtain all municipal and/or the Authorities Having Jurisdiction permits and inspection certificates and pay all charges.

D. Make or arrange for any/or all inspection agency reviews or visits and pay all charges. This includes communication with each respective agency and/or utility to verify the project system work, coordination responsibilities, fees, back charges, etc., required.

E. All fees and back charges shall be verified during the bidding phase of the work. Any discrepancy of this item between any utility, inspection agency and the Contractor shall be brought to the attention of the A/E prior to bid opening.

F. Submission of a bid will be deemed evidence of having complied with these requirements.

1.4 RELATED WORK

A. Refer to equipment shown or specified in all other applicable Divisions that require Plumbing and Fire Protection services.

B. Refer to work related to Plumbing and Fire Protection as shown on the following contract drawings:

Architectural & Structural

HVAC

Electrical

1.5 COORDINATION

A. The Mechanical, Plumbing and Electrical Contractors are responsible to coordinate all manufacturer's recommended circuit breakers, starters, disconnects and fuse sizes for all equipment. Submission of a shop drawing will certify that this has been completed. Any necessary changes required will be included as part of this contract.

B. Plumbing and Sprinkler Contractors shall coordinate scheduling, submittals and work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of independent work elements, with provisions to accommodate items that may be installed at a later time.

C. Plumbing and Sprinkler Contractors shall verify utility requirements and all characteristics of operating equipment are compatible with the building utilities. Coordinate the work of all sections related and required for installing, connection and placing in service of all equipment.

D. Plumbing and Sprinkler Contractors shall coordinate all space requirements, supports and installation of all mechanical, electrical, plumbing and fire protection work, which are indicated diagrammatically on the Drawings. Verify routing of all pipes, ducts, conduits and equipment connections. Maximize accessibility for other work, and service requirements for maintenance and repairs. Develop overall coordination drawing (all trades) and submit for review prior to fabrication/installation.

E. Obtain written confirmation from all related trade Contractors and the Owner or his representative that requirements, conflicts and coordination issues have been discussed and resolved.

F. Coordination of Trades in the Field: The Sheet Metal Contractor shall take precedence and, therefore, shall develop his shop drawings first. These then will be used to overlay the other trades. Next shall be the mechanical piping, plumbing, fire sprinkler and electrical in the order stated. Drawings shall be 3/8" in scale. Initial meeting of contractors shall be convened prior to start of drawings to work out layout, breakdown of building and other details. All drawings shall be completed in CAD with a format compatible and convertible to DWG files. At the end of the effort, each contractor shall provide a full set of shop drawings to each of the other contractors and three sets to the construction manager. Devices requiring access for maintenance shall not be infringed upon by adjacent trades. Coil pull allowances shall be shown on drawings.

1.6 SUBMITTALS

A. Shop Drawings & Product Data:

1. Shop drawings and product data shall be submitted in accordance with Division 22 specifications except where herein modified.

   NOTE: Submittals will only be reviewed once and resubmittals will be reviewed once. Any other submittals will be billed to the Contractor at the Engineer's standard rates.

2. Listed are the required shop drawings and reports required for this project. The Engineer/Owner shall reserve the right to require additional submissions not listed below:

   - All fixtures, equipment and associated devices so listed on the Fixture Schedule on Drawing _____.
   - Sewage Pumps.
   - Insulation
   - All specified piping systems.
   - All specified valves.
   - Medical Gas Systems, certifier and report.

- Gauges and thermometers
- Recirculating pump.
- Hanger and supports including Sumner system.
- Piping labels and identification.
- Sprinkler System and all related data, devices, switches and trimmings.
- Sump pumps.
- Testing reports.
- Sterilization report.
- Operating/Maintenance manuals.
- As-Built Drawings.

3. Submittals comprising complete catalog cuts, shop drawings and performance test data for Plumbing materials and equipment as required by other sections of Division 22, shall be submitted for review checking. The Contractor shall review these for conformance to contract documents prior to submission and affix contractor's signature to each submittal certifying that this review has been done. By approving and submitting shop drawings, product data, samples and similar materials, the Contractor represents that the Contractor has determined and verified materials, field measurements and field construction data that relates to the work, and has checked and coordinated this information with all of the requirements contained in the contract documents for the work of all trades.

4. All submittals shall have the following identification data, as applicable, contained therein or permanently adhered thereto.

   a. Project name.

   b. Project number.

   c. Sub-contractor's, vendor's and/or manufacturer's name and address.

   d. Product identification.

   e. Identification of deviation from contract documents.

   f. Applicable contract drawings and specification section number.

   g. Shop drawing title, drawing number, revision number, and date of drawing and revision.

   h. Resubmit revised or additional submittals as requested.

   i. Wherever shop drawings or vendor's standard data sheets indicate work to be done "by others", it shall be the responsibility of the contractor making the submission to identify by name, the contractor who is to do this work. If the contractor named is other than the contractor making the submission, the shop drawing submission must be reviewed by the named contractor and bear his mark of approval, prior to submission to the Architect/Engineer.

   j. Where equipment proposed differs from that shown on the drawings or specified, he shall submit for approval drawings showing the manner in which the layout is affected by the substitution.

   k. The Contractor shall keep one copy of approved shop drawings at the job site,, filed in a suitable metal container. The shop drawings shall be cataloged and kept in good repair, and

shall be available for use by the Owner, Architect and Engineer.

l. No equipment shall be ordered, fabricated, etc., before approval of shop drawings.

B. Contractor is responsible for the shop drawing coordination and interface with the work of other contracts and adjacent work. The relationship of Contractor's work shall be verified as it relates to adjacent and critical features of the work of this and all contracts and materials.

1.7 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in all other applicable Divisions. In addition, refer to specifications for special guarantees.

B. Wherever in the specification sections of this division, reference is made to a specific warranty period, this warranty shall be in addition to and not a limitation of other rights the Owner may have against the Contractor under the contract documents.

C. Contractor to include an 11 month "walk-thru" of the building systems with representatives of the School District, Architect, Engineer and the Construction Manager. The purpose is to establish a list of corrective work that relates to operational issues, material/installation deficiencies.

1.8 SITE INSPECTION

A. The Contractor shall visit the site, inspect, and become aware of all conditions which may affect the work during the estimation phase of his work and prior to bid openings. Investigate utilities, protection requirements for adjacent facilities, storage locations, and access to the construction area.

B. Submission of a bid will be deemed evidence of having complied with this requirement.

1.9 SUBSTITUTIONS

A. Whenever a material, article, piece of equipment or system is identified in the following specification or indicated on the drawings by reference to manufacturers' or vendors' names, trade names, catalog numbers or the like, it is so identified for the purpose of establishing the basis of the Bid.

B. Substitution approval must be obtained and included as an addendum item prior to the submission of the bid. An approved substitution shall not be considered as an approval for the Contractor or an equipment vender to deviate from the written portion of the specifications unless so stated in the addendum.

C. The drawings illustrate the space allocated for equipment and the Contractor shall install the equipment accordingly. If changes are required in the building or arrangement due to substitution of equipment, the Contractor making the substitution must pay for the necessary modifications.

D. The listed equivalent or substituted manufacturers along with the bidding related contractor shall be completely responsible to comply with all requirements as indicated on all contract documents and as described within the specifications. This shall include, but shall not be limited to space requirements, code clearances, the type, horsepower, capacities, number and size of services required from other trades, including all required ancillary items furnished and installed by other trades. If the manufacturer or related bidding contractor does not comply with these requirements, then they shall be responsible for any and all additional costs associated with the changes required by other trades.

1.10 LUBRICATION

A. Furnish, install and maintain all required lubrication of any equipment operated prior to acceptance by the Owner. Lubrication shall be as recommended by the equipment manufacturer.

B. Provide one year's supply of lubricants to Owner at date of acceptance.

C. Verify that required lubrication has taken place prior to any equipment start-up.

1.11 EQUIPMENT START-UP

A. Verify proper installation by manufacturer or his representative.

B. Advise General Contractor 2 days prior to actual start-up.

C. Verify proper operation. Obtain signed statement by manufacturer or his representative that equipment is operating within warranty requirements. Submit statement to General Contractor.

1.12 OPERATION & MAINTENANCE INSTRUCTIONS

A. Properly and fully instruct Owner's personnel in the operation and maintenance of all systems and equipment.

B. Insure that the Owner's personnel are familiar with all operations to carry on required activities.

C. Such instruction shall be for each item of equipment and each system as a whole.

D. Provide report that instruction has taken place. Include in the report the equipment and/or systems instructed, date, contractor, Owner's personnel, vendor, and that a complete operating and maintenance manual has been reviewed.

E. Manual shall include all instructions on operation, maintenance, repair parts list, lubrication requirements, brochures, catalogue cuts, wiring diagrams, piping diagrams, control sequences, service requirements, names and addresses of vendors, suppliers and emergency contacts. Three manuals shall be provided.

F. Submit manuals for review prior to operating instruction period. Manuals shall be 8-1/2 x 11" with hard cover, suitably bound.

G. Provide to the Owner any special tools necessary for operation and routine maintenance of any of the equipment.

H. Furnish three (3) copies of a professionally taped video and three (3) copies of professionally prepared drawings demonstrating the following:

- Location of main shut-off valves
- Procedures for equipment start-up and seasonal shut-downs.
- Procedures for maintenance.
- Provide written version of all procedures included in video.

The above should cover all equipment/systems including, but not limited to the following:

- Sprinkler Systems
- Hot water heater and pumps
- Grease trap
- Flush valves
- Water coolers
- Sump pumps
- Mixing valve
- Solids interceptor

1.13 TOOLS

A. All equipment furnished by the Contractor which requires special tools or devices other than those normally available to the maintenance or operating staff shall be furnished in duplicate to the Owner, sufficiently marked, packed or boxed for staff usage. The tools provided shall be listed by the Contractor identified as to their use or the equipment applicable in a written transmittal to the Owner.

1.14 CLEANING AND FINISHING

A. After equipment start-up and all operating tests have been made and the system pronounced satisfactory, each respective Contractor shall go over the entire project, clean all equipment, etc., installed by him and leave in a clean and working condition. Any surfaces found marred after this final cleaning shall be refinished or replaced by each Contractor at no cost to the Owner.

B. Provide for the safety and good condition of all materials and equipment until final acceptance by the Owner. Protect all materials and equipment from damage. Provide adequate and proper storage facilities during the progress of the work. Special care shall be taken to provide protection for bearings, open connections, pipe coils, pumps, compressors and similar equipment.

C. All NEW fixtures, piping, finished surfaces and equipment installed shall have all grease, adhesive labels and foreign materials removed.

D. All new piping installed shall be drained and flushed to remove grease and foreign matter. Pressure regulating assemblies, traps, flush valves and similar items shall be thoroughly cleaned. Remove and thoroughly clean and reinstall all liquid strainer screens after the system has been in operation ten (10) days.

E. Gas piping shall be blown out with clean compressed air or inert gas.

F. When connections are made to existing systems, the Contractor shall do all cleaning and purging of the existing systems required to restore them to the condition existing prior to the start of work.

G. Clean-up: Remove from the premises, all unused material and debris resulting from the performance of work under this section.

PART 2 – PRODUCTS

2.1 GENERAL

A. All material and equipment shall be new and of present day manufacture, and shall conform to accepted standards of the trade where such a standard has been established for the particular type of equipment or material.

B. Whenever equipment or material is referred to in the singular, such as "the plumbing fixture", it shall be deemed to apply to as many such items as necessary to complete the work.

2.2 PRODUCT DELIVERY, STORAGE AND HANDLING

A. During loading, transporting and unloading exercise care to prevent damage to material.

B. Store all materials in dry enclosures or under protective coverings out of way of work progress.

C. Material shall not be allowed to be stored directly on ground.

D. Deliver in manufacturer's original cartons or on skids.

E. Handle and protect so as to prevent damage to product or any surrounding material.

2.3 CONCRETE

A. Concrete if used on this project, shall be in accordance with Section 033000.

B. The 28-day minimum compressive strength shall be 3000 psi.

PART 3 – EXECUTION

3.1 PROTECTION

A. Plug or cap open ends of piping systems.

B. Stored materials shall be covered to prevent damage by inclement weather, sun, dust or moisture.

C. Protect all installed work until accepted in place by the Owner.

D. Plates, polished metal escutcheons and other finished devices shall not be installed until masonry, tile, and painting operations are complete unless otherwise protected.

E. Protect all work from operations which may cause damage such as hauling, welding, soldering, painting, insulating and covering.

F. Do not remove protective material until equipment is placed in service.

3.2 WORKMANSHIP

A. Install all work neat, trim and plumb with building lines.

B. Install work in spaces allocated.

C. Cutting and patching shall be performed by skilled tradesmen normally employed for the work involved.

3.3 EXCAVATION

A. The excavation shall be of the open-trench method and to the depths and widths as may be necessary. The Contractor shall do all excavation required in connection with his work. Bottoms of trenches shall be excavated to a uniform grade. All materials excavated shall be deposited on the side of the trenches and beyond the reach of the slides. Excavated material shall not be piled where it will interfere with traffic. If rock is encountered, it shall be removed by the General Contractor. See provisions in Division 2.

B. No piping shall be bedded directly on rock. They shall be cushioned by a 6-inch layer of crushed stone or gravel of selected grade, of size to pass through 3/4" mesh sieve. Not less than 30% shall be fine which will pass through a 3/8" mesh sieve.

3.4 SHORING AND PUMPING

A. The Contractor shall provide all shoring, bracing or sheet piling necessary to maintain the banks of his excavation and shall take out same as the work progresses and filling in has been accomplished. Shoring shall be in accordance with OSHA Standards.

B. The arrangement of shoring must be such as to prevent any movement of the trench banks and consequent strains on the conduits. Shoring shall be provided to prevent damage to work installed by other trades.

C. The Contractor shall do all pumping required to keep his excavations free of water. The water shall be conveyed in piping or watertight troughs a sufficient distance that it will flow from the site and not affect other work being performed.

3.5 BACKFILLING

A. After work in trenches has been completed, they shall be filled with select fill in 8" layers and shall be pneumatically tamped before the next layer of material has been filled in. The backfill shall be free of excavated rock, cinders, stones, brickbats or other debris.

B. Wherever rock is removed, the Contractor shall secure and fill select clean earth to a minimum depth of 3'-0" above the top of the pipe. Unless otherwise indicated, no rock shall be deposited in the trench fill. This clean earth fill shall be procured other than from the site unless permission for earth borrow from the site is granted by the Architect. If site borrow is permitted, the topsoil removal, relocation and finished grading will be accomplished as directed by the Architect.

C. Under no circumstances shall excavated material be left where it will interfere with the Owner's or other Contractor's operations.

D. All earth and other materials taken from the trenches and not required for backfilling shall be deposited where directed, or removed from the premises as directed by the Architect.

E. Any rock removed from the excavation shall be removed from the project site by the Contractor.

F. Trenches which pass under wall footings or within 18" of column footings shall be backfilled with lean concrete. To secure adequate foundation support, the method and depositing of the concrete fill shall be as directed by the Architect. To prevent the concrete from adhering to the pipes, necessary pipe protection shall be applied.

3.6 EQUIPMENT SETTING

A. Furnish and install as a minimum, a 4 inch concrete pad beneath all floor-mounted equipment. Install anchor bolts in pour.

B. Furnish and install as a minimum, spring vibration isolation under any equipment 10 HP and over and rubber in shear vibration isolation on any equipment up to 10 HP.

C. Concrete shall be 3,000 psi, 28 day compressive strength in accordance with ACI-613. Reinforce with No. 4 rod 12" on centers both ways or as otherwise detailed.

3.7 FASTENERS, HANGERS AND SUPPORTS

A. Furnish and install all hangers and supports required to suspend, mount, or hang the work.

B. Furnish and install all miscellaneous steel angles, channels, beams, clips, brackets and anchors necessary to hang or support the work. Provide submissions for review.

C. Install concrete inserts before concrete is poured.

D. Drilled inserts shall not be loaded more than 1/4 rated capacity or 200 pounds.

E. Power-driven fasteners shall not be allowed for piping larger than 2 inch, or equipment. When used they shall not be loaded more than 1/8 rated capacity or 200 pounds.

F. All hangers, miscellaneous steel, braces and supports shall be galvanized, cadmium plated, or primed steel. Copper tubing shall be supported with copper hangers. No direct contact of dissimilar metals between the piping system and its hanger support shall be permitted.

G. Piping shall be supported from adjustable clevis type hangers with insulation pipe saddles. Where hangers are 18” or longer, provide lateral bracing at every fourth hanger. See IPC Pipe Support Table below:

PIPE SUPPORT SPACING

Material	Horizontal Max. Feet	Vertical Max. Feet
ABS Pipe	4	10
Aluminum	10	15

Material	Horizontal Max. Feet	Vertical Max. Feet
Brass	10	10
Brass Tube up to 1-1/4”	6	10
Brass Tube over 1-1/2”	10	10
Cast Iron	5	15
Copper up to 1-1/4”	6	10
Copper over 1-1/4”	10	10
CPVC Up to 1”	3	10
CPVC Over 1”	4	10
Lead Pipe	Continuous	4
PB Pipe/Tubing	2.6 ft. (32”)	10
PVC Pipe	4	10
PEX	2.6 ft. (32”)	10
Steel Tubing	8	10
Steel Pipe	12	15

H. Support vertical piping at floor levels using approved riser clamps. Clamp material shall be compatible with pipe material. Maximum vertical spacing shall be10’-0”.

3.8 SLEEVES

A. Provide each pipe passing through a masonry or concrete wall, floor or partition with a sleeve made from standard weight steel pipe for pipe with smooth edges, securely and neatly cemented in place. Provide each pipe passing through a frame or metal partition with a sleeve made from No. 22 gauge galvanized sheet metal, securely fastened in place.

B. Pipe passing through foundation wall or under foundation shall be provided with relieving arch or steel pipe per IPC Section 305.5.

C. Be responsible for the proper location and alignment of all sleeves.

D. Provide hydrostatic seals for sleeves passing through outside walls, below grade, or through hydrostatically sealed slabs or floors on grade. Provide fire-rated seals for all other sleeves.

E. Install both piping and sleeve seals so as to maintain integrity of seals with expansion and contraction of piping.

F. Set floor sleeves flush with floor surface in finished areas, 1" above the finished floor in kitchens, cafeterias, and similar service areas unless such areas are slab-on-grade; 1" above the floor in mechanical rooms, pipe chases, pipe spaces and other unfinished areas, unless otherwise indicated, and flush with the underside of slabs. Extend wall and partition sleeves through and cut flush with each surface unless otherwise indicated or specified.

G. Select sleeves two pipe sizes larger than any pipe that is to remain uncovered, unless otherwise required by the sealing method specified. Where pipes are to be covered, provide sleeves large

enough to allow the covering to pass through the sleeves with sufficient clearance for sealing as specified hereinafter. Size sleeves for branch piping from vertical risers large enough to permit vertical expansion at the riser.

H. Place sleeves imbedded in concrete floors or walls in the forms before concrete is poured; sleeves shall have integral waterstop flanges, where they are to receive either watertight or hydrostatic seals.

I. Install sleeves passing through above-grade floors of mechanical rooms, toilet rooms, kitchens or similar service areas where liquid leaks or spillover may occur in a watertight manner. Sleeves shall be such that waterproofing membrane can be flashed around and into the sleeve where necessary.

J. Seal sleeves for pipes passing through ceiling air plenum walls or the floor above air tight in a manner similar to that specified for fire-rated sleeves.

K. Hydrostatic Sealing Method: Provide compressible synthetic rubber seals, equivalent to LINK SEAL, manufactured by the Thunderline Corporation, or THRUWALL manufactured by O.Z. Gedney. Install seals in accordance with the manufacturer's recommendations to provide air tightness aboveground and hydrostatic sealing belowgrade. Caulking or other type mastic is not acceptable.

L. Fire-Rated Sealing Method:

1. Sleeves, openings and sealants shall comply with applicable codes, recommended practices and standards, and manufacturer's instructions. Fire sealants shall have ability to prevent spread of flame, smoke or water throughout the penetration and shall pass 3 hour test, UL test ASTM E814 and UL 1479.

2. Products: Chase Corporation CTC PR-855, O. Z. Gedney CRS/CAFS, 3M Electro-Products Division Putty 303 or Caulk CP25 penetration sealing kits, General Electric Company sealants type RTV-850, 6428 or 7403, Thunderline Corporation "Link-Seal Pyro-Pak". Installation and type of sealant to be used as recommended by the manufacturer.

3. Expansion collars, fire seal/firestop collars – ASTM E814 (UL1479). Spec Seal Corporation, Inc. (plastic pipe).

3.9 PLATES

A. Furnish and install chrome plated plates wherever piping passes into finished area.

B. Plates shall be securely fastened to piping or building construction.

C. Floor plates shall cover 1 inch sleeve extension.

3.10 OFFSETS, TRANSITIONS, MODIFICATIONS

A. Furnish and install all offsets necessary to install the work and to provide clearance for other trades.

B. Maintain adequate headroom and clearance.

C. Incidental modifications necessary to the installation of the systems shall be made as necessary and as approved by the Architect.

3.11 RECESSES

A. Furnish information to the General Contractor as to sizes and locations of recesses required to install panels, boxes, and other equipment or devices which are to be recessed in walls.

B. Make offsets or modifications as required to suit final locations.

3.12 LABELING

A. All Plumbing equipment such as pumps, and devices requiring identification for operating procedures shall be provided with permanent black laminated micarta white core labels with 3/8 inch letters.

B. This shall also apply to all controllers, remote start/stop pushbuttons and equipment cabinets.

3.13 FLASHING AND COUNTERFLASHING

A. Roof drains, vents, roof curbs, etc., shall have counterflashing fittings. General Contractor shall provide flashing.

B. Piping and conduit thru the roof shall be flashed by the General Contractor. Furnish and install counterflashing.

3.14 ACCESS

A. Locate all equipment, valves, devices and controllers which may need service in accessible places.

B. Where access is not available, access panels shall be provided. Furnish access doors to the General Contractor for installation.

C. Access doors shall be Elmdor, Karp Co., MIFAB or Controlled Air Manufacturing Limited, with 16 gauge frames and 14 gauge steel door, prime painted.

D. Maintain required access clearances.

3.15 WIRING

A. Packaged plumbing system equipment shall be furnished with disconnect switches, and magnetic starters, factory furnished and wired by the unit manufacturer.

B. All control wiring shall be furnished and installed under this Division of the work.

C. All wiring shall be in accordance with the National Electrical Code and as recommended by the equipment manufacturer.

3.16 UTILITIES

A. Do not interrupt any utility or service to the Owner without adequate previous notice and schedule.

B. Arrange and pay for the relocation, disconnection or removal of, or relocate, disconnect or remove existing utilities and services where such work is shown or where such utilities or services interfere with new construction, whether or not shown. Provide all excavation, backfilling and paving required by such work.

C. Perform alteration of utilities and services in accordance with the rules, regulations and requirements of the involved utility companies, regulatory agencies having jurisdiction.

3.17 CUTTING AND PATCHING EXTERIOR SURFACES

A. This Contractor shall be responsible for returning disturbed paved and/or grass areas to original condition where excavation for utilities has been required.

B. Cut and patch paved areas to match original surface.

C. Properly tamp backfill before finishing or repairing disturbed area surfaces.

3.18 OPENINGS - CUTTING, REPAIRING

A. This contractor shall cooperate with the work to be done under other sections in providing information as to openings required in walls, slabs and footings for all piping and equipment, including sleeves where required.

B. Any drilling or cutting required for the performance of work under this Section, shall be the responsibility of this Contractor and the cost thereof shall be borne by him.

C. Holes in Concrete: Sleeves shall be furnished, accurately located and installed in forms before

pouring of concrete. This contractor shall pay all additional costs for cutting of holes as the result of the incorrect location of sleeves. All holes through existing concrete shall be either core drill or saw cut. All holes required shall have the approval of the Structural Engineer prior to cutting or drilling.

D. It shall be the responsibility of this Contractor to ascertain that all chases and openings are properly located.

3.19 GUARANTEE

A. All materials and equipment provided and/or installed under this section of the specifications shall be guaranteed for a period of one year from the date of acceptance of the work by the Owner unless otherwise specified in other applicable Divisions. Should any trouble develop during this period due to defective materials or faulty workmanship, the Contractor shall furnish all necessary labor and materials to correct the trouble without any cost to the Owner. Any defective materials or inferior workmanship noticed at time of installation and/or during the guarantee period shall be corrected immediately to the entire satisfaction of the Owner.

In the event of occupancy by the Owner prior to final acceptance of the project, the guarantee date for equipment placed in operation shall be mutually agreed to by the Contractor and the Owner's representative.

B. Contractor to include an 11 month “walk-thru” of the building system with representatives of the School District, Architect, Engineer and the Construction Manager. The purpose is to establish a list of corrective work that relates to operational issues, material/installation deficiencies.

3.20 DRAWINGS

A. The Plumbing and Fire Protection Systems are indicated on the Contract Drawings. Certain pertinent information and details required by the Plumbing and Fire Protection Work appear on the Architectural, Structural and Electrical Drawings; become familiar with all Drawings; and incorporate all pertinent requirements.

B. Drawings are diagrammatic and indicate the general arrangement of systems and requirements of the Work. Do not scale Drawings. Exact locations of fixtures and equipment, not specifically shown shall be obtained before starting work.

C. When indicated on the drawings, plumbing riser diagrams are completely diagrammatic and indicate the intent of the work for both the Contractor, L&I review agencies and/or Authorities Having Jurisdiction. Where valves, shock absorbers, incidental equipment, devices, etc., including execution notes are indicated on the riser diagrams, they shall be so required and installed as part of the system work.

3.21 RECORD DRAWINGS

A. As-Built record drawings, showing dimensions, locations and depth of all buried and concealed piping, plugged outlets and equipment shall be kept up to date. Master copy shall be kept on the job. No backfilling of trenches shall be permitted until as-built drawings are approved as up-to-date by the Owner/Representative. No plumbing progress payments shall be approved unless as-built drawings are up- to-date. Depth of sewers shall be from a permanent bench mark as shown on the contract drawings. Refer to project record drawings under General Conditions.

END OF SECTION 220000

SECTION 220010

BASIC MATERIALS AND METHODS – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the work specified in this Section.

1.2 REFERENCE

A. Install all piping, fixtures, equipment, etc., to meet the requirements of the following:

_____Department of License and Inspection

_____Department of Sewers

_____Plumbing Code

_____Fire Marshal's Office

NATIONAL Plumbing Code

International Plumbing Code (All applicable sections)

International Mechanical Code (All applicable sections)

International Fuel Gas Code (All applicable sections)

Gas Utility Company

Water Company

NFPA

OSHA

All requirements of the above governing agencies shall be in compliance with the latest issues, rules or regulations in effect.

B. Appliances and materials governed by UL requirements shall meet such requirements and bear the label.

1.3 QUALITY ASSURANCE

A. Provide adequate supervision of labor force to assure all aspects of specifications are being fulfilled.

B. Insure that all work and equipment is installed in accordance with manufacturer's warranty requirements.

C. Replace all pipes and fittings shown to be defective as a result of testing.

1.4 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

B. Submit the following:

1. Manufacturer's Product Data on all pipe and fittings to be used in project.
2. Manufacturer's Product Data on all valves to be used in project.

1.5 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

PART 2 – PRODUCTS

2.1 STEEL PIPE & FITTINGS

A. Pipe: ASTM A-53, seamless, Schedule 40.

B. Fittings:

1. Cast iron, threaded, 175 psi, ANSI B-16.4.
2. Malleable iron, threaded, ASA B 16.3.
3. Steel, socket weld, ASTM A-53.
4. Wrought iron, socket weld, ASTM A-72.

C. Thread tape shall be teflon tape, 3 mils minimum thickness. Teflon tape shall not be permitted for use on gas piping systems.

D. See Section 220130 for Gas Piping Systems.

2.2 CAST IRON PIPE AND FITTINGS

(Note: Any cast iron piping made or marked “CHINA” will NOT be acceptable on this project)

A. Aboveground:

1. Pipe & Fittings: Hubless cast iron, CISPI 301, ASTM A-74 and ASTM A-888 shall be marked with the collective trademark of the Cast Iron Institute (soil pipe).
2. Joints: Neoprene sleeve and stainless steel shield and clamp assembly, CISPI 310, ASTM-1277.

B. Below grade and/or slab: (Contractor's Option)

1. Bell and Spigot: Service weight bell and spigot pattern ASTM-74 with compression type neoprene gaskets ASTM C-564.
2. Hubless: Hubless cast iron pipe CISPI 301, with heavy duty 3.04.016 stainless steel bands for below-grade installation. Elastomeric seal component ASTM C-564 and CSA B-602.
3. Hubless Joints: Cast iron CISPI 310 and as TM C-1277.
4. PVC DWV pipe and fittings, Schedule 40, ASTM D-2665, D2949, F891 and CSA B181.2.
5. Corrosion protection shall be in accordance with IPC 305.1. Provide appropriate wrapping or sheathing when pipe is exposed to lime and acid of concrete, cinder or other corrosive materials.
6. Protection of all below-grade storm and sanitary shall be in accordance with IPC Section 305.
7. All Kitchen and Boiler Room below slab piping shall be extra heavy schedule cast iron only. PVC not allowed.

C. Corrosion protection shall be in accordance with IPC 305.1. Provide appropriate wrapping or sheathing when piping is exposed to lime and acid of concrete, cinder or other corrosive materials.

2.3 COPPER TUBING

A. Domestic hot, cold and recirculated water:

1. Aboveground:

a. Tubing: Hard-drawn, seamless ASTM B-88, Type "L".

b. Fittings: Solder joint wrought copper ANSI B-16.22.

c. Joints: Lead-free solder 410°, ASTM B-32 alloy designation “TC”, ASTM B-828.

d. Flux: Non-toxic and non-corrosive, ASTM B-813.

2. Underground:

a. Tubing: Soft-drawn, seamless ASTM B-88, Type "K".

b. Fittings: Solder joint wrought copper ANSI B-16.22.

c. Joints: Lead-free solder 410°, ASTM B-32, ASTM B-828.

d. Flux: Non-toxic and non-corrosive, ASTM B-813.

B. Drainage and vent piping:

1. Aboveground:

a. Tubing: Hard-drawn seamless ASTM B-88, ASTM B-75, Type "M" and DWV as pipe size permits.

b. Fittings: Solder joint cast copper drainage type ANSI B-16.29.

c. Joints: Soldered, 95/5 tin-antimony ASTM B-828, ASTM B-32.

d. Flux: Non-toxic and non-corrosive, ASTM B-813.

C. Solder/Flux: See Paragraph 3.4 of this section for Soldering/Brazing.

2.4 DUCTILE IRON PIPE

A. Pipe: Ductile iron, ANSI A-21.51, ANSI/AWWA C151.

B. Joints: Rubber gasket, ANSI A-21.11, ANSI/AWWA C111.

C. Fittings: Mechanical joint, ANSI/AWWA C110, C153 bolt tolerances – AWWA C-111, ASTM A-563.

D. Lining: Cement mortar, ANSI A-21.4, ANSI/AWWA C104.

2.5 PVC GRAVITY SEWER PIPE

A. Pipe: Unplasticized polyvinyl chloride (PVC) with integral wall bell and spigot joints.

B. Material: ASTM D-3034 for SDR 35, colored green for inground identification as sewer pipe.

C. Joints: Two sections of pipe shall be assembled in accordance with manufacturer's recommendations and tested as per ASTM D 3212 for use with flexible elastomeric seals.

D. Sizes: For site drainage systems 4" to 15".

E. Additional compliances:

1. Drop Impact Test - ASTM D-2444

2. Pipe Stiffness - ASTM D-2412

3. Temperature for Testing - Designed to pass all tests at 73 degrees F (+/- 3 degrees F).

2.6 POLYVINYL CHLORIDE (PVC) PIPE AND FITTINGS

A. Aboveground – Drainage & Vent (Sanitary) IPC Table 202.1

1. ASTM D 2665

2. ASTM D 2949
3. CSA CAN/CSA B 181.2
4. ASTM F 1488
5. ASTM F-81

B. Underground – Drainage & Vent (Sanitary) IPC Table 702.2

1. ASTM D 2665
2. ASTM D 2949
3. ASTM F 891
4. CSA CAN/CSA-B 181.2

C. Building Sewer Pipe (Near Water Service) IPC Table 702.3 (DWV)

1. ASTM D 2665
2. ASTM D 2949
3. ASTM D 3034
4. ASTM F 891
5. CSA B182.2
6. CSA B 182.4 (Ribbed Sewer Pipe & Fittings)

D. Fittings:

1. ASTM D 3311
2. ASTM D-2665
3. ASTM F-1866

E. Solvent Cement: (All Purpose on ABS, PVC and CPVC)

Potable Water, Sewer, Drain Waste and Vent

1. ASTM D-2564, D-2235 and F-493
2. CSA B137.3
3. CSA B181.2 or B182.1 (Sanitary Pipe only)
4. ASTM D2855
5. CSA B181.1

F. Primers: (PVC and CPVC)

1. ASTM F 656, purple color, SCAQMD Rule 1168 and OTC Regulations for VOC emission levels. NSF Standard 61 PW, DWV, Sewer.

G. Uniformity: To insure installation uniformity, all piping components shall be of one manufacturer.

2.7 POROUS CONCRETE PIPE

A. Pipe & Fittings: Porous concrete drain pipe, A.A.H.O. designation M176.

B. Joints: Interlocking tongue and groove.

2.8 REINFORCED CONCRETE PIPE AND FITTINGS

A. Pipe & Fittings: Reinforced concrete, ANSI/ASTM C-75, Class 2.

B. Joints: Modified tongue and groove, with compression gasket, ANSI/ASTM C-443.

2.9 POLYPROPYLENE PIPE & FITTINGS

A. Pipe & Fittings: Polypropylene flame retardant ASTM D-2146 Schedule (40) (80).

B. Joints: (Aboveground)

1. Mechanical

2. Fusion welded socket ends.

C. Joints: (Below ground) Fusion welded - socket ends

2.10 PLENUM RATED PVDF PIPE & FITTINGS/CORROSIVE WASTE DRAINAGE SYSTEM

A. Pipe & Fittings: Polyvinyllidene fluoride (PVDF), ASTM F-1673, pipe shall be marked with "UL" to indicate compliance with UL723 (ASTM E84).

B. Joints (Aboveground)

1. No hub, plain end, outerban, nuts and bolts per ASTM B117.

2. Socket Fusion: ASTM 2657, ASTM D3222.

2.11 FLOWGUARD GOLD CPVC PIPE

A. Scope: This specification covers the manufacturing requirements for CPVC SDR 11 Copper Tube Size (CTS) pipe and fittings. Both the pipe and fittings are manufactured in North America and meet or exceed the requirements set forth by the American Society for Testing Materials (ASTM) and ANSI/NSF Standards 14 and 61.

B. CPVC Materials: FlowGuard Gold® CPVC pipe and fittings are extruded/molded from CPVC compounds manufactured by Lubrizol. The pipe compound meets cell class 24448 and the fitting compound meets cell class 23447 as defined by ASTM D1784. Both the pipe and the fitting compounds are certified by NSF International for use with potable water.

C. Dimensions And Properties:

Dimensions, tolerances and physical properties meet or exceed the requirements of ASTM D2846.

D. Solvent Cement: All socket type joints shall be assembled employing solvent cements that meet or exceed the requirements of ASTM F493. The standard practice for safe handling of solvent cements shall be in accordance with ASTM F402. Solvent cement shall be listed by NSF International for use with potable water, and approved by the FlowGuard Gold® pipe and fittings manufacturers.

E. Flame And Smoke Requirements: Water filled FlowGuard Gold® pipe and fittings (1/2" through 2") tested in general accordance with UL 723/ASTM E 84 (NFPA 255 and UBC 8-1) meet the 25/50 flame and smoke requirement and shall be permitted to be installed in return air plenums. Test reports from a third party testing laboratory shall be obtained and made available upon request.

F. Marking: The marking on the CPVC pipe and fittings meet the requirements of ASTM D2846 and state the pipe/fitting manufacture's name or trademark, the material designation, the size, the NSF mark for potable water and the ASTM designation (ASTM D2846).

2.12 CORZAN CPVC PIPE

A. Scope: This specification covers the manufacturing requirements for CPVC Schedule 80 Iron Pipe Size (IPS) pipe and fittings. Both the pipe and fittings are manufactured in North America and meet or

exceed the requirements set forth by the American Society for Testing Materials (ASTM) and ANSI/NSF Standards 14 and 61.

B. CPVC Materials: Corzan® CPVC pipe and fittings are extruded/molded from CPVC compounds manufactured by Lubrizol. The pipe compound meets cell class 24448 and the fitting compound meets cell class 23447 as defined by ASTM D1784. Both the pipe and the fitting compounds are certified by NSF International for use with potable water.

C. Dimensions and Properties: Dimensions, tolerances and physical properties meet or exceed the requirements of ASTM Standards F441 for pipe, F439 for socket fittings and ASTM F437 or F439 for threaded fittings. Threaded fittings have taper pipe threads in accordance with ASTM F1498. Unions and flanges meet or exceed the requirements of ASTM F1970.

D. Solvent Cement: All socket type joints shall be assembled employing solvent cements that meet or exceed the requirements of ASTM F493. The standard practice for safe handling of solvent cements shall be in accordance with ASTM F402. Solvent cement shall be listed by NSF International for use with potable water, and approved by the Corzan® pipe and fittings manufacturers.

E. Flame And Smoke Requirements: Water filled Corzan® pipe and fittings (1/2" through 6") tested in general accordance with UL 723/ASTM E 84 (NFPA 255 and UBC 8-1) meets the 25/50 flame and smoke requirement and shall be permitted to be installed in return air plenums. Test reports from a third party testing laboratory shall be obtained and made available upon request.

F. Marking: The marking on the CPVC pipe meet the requirements of ASTM F441 and the marking on the fittings meets the requirements of ASTM Standards F437, F438 or F1970. The pipe and fittings markings state the pipe/fitting manufacture's name or trademark, the material designation, the size, the NSF mark for potable water and the ASTM designation.

G. To ensure compliance with Green Building Design and Construction under IEQ Credit 4.1 for Low-Emitting Materials (adhesives and sealants), all interior use adhesives, sealants and sealant primers shall comply with the South Coast Air Quality Management District (SCAQMD) Rule #1168. All primers and cements used for joining CPV and CPVC piping shall comply with the following Volatile Organic Compound (VOC) limits when calculated according to 40 CFR 59, subpart D (EPA Method 24):

PVC welding	-510 g/L less water
CPVC welding	-490 g/L less water
Adhesive Primer of Plastic	-550 g/L less water

H. Valves - Plastic PVC & CPVC: Valves listed below shall be for domestic water systems and comply with ASTM Standard D 1784, Rigid PVC and CPVC compounds. Classes 12454 (Type 1, Grade 1) PVC and 23447 (Type 4, Grade 1) CPVC.

All PVC and CPVC Valves are listed by the NSF International to NSF/ANSI Standard 14: Plastic Piping System Components and Related materials. This independent third-party agency certifies that products and materials bearing the 'NSF-pw' marking are regularly tested to comply with ASTM F 1970 Standard Specification for Special Engineered Fittings, Appurtenances or Valves for use in Poly (Vinyl Chloride) (PVC) or Chlorinated Poly (Vinyl Chloride) (CPVC) Systems, as well as, certifying these products conform to the requirements of NSF/ANSI Standard 61: Drinking Water System Components-Health Effects.

Ball and Ball-Check Valves are 100% pressure tested for shell and seat leaks in accordance with quality standards established by NIBCO Engineering. The rejection point is a leak greater than 60 cc per minute.

All True Union-Tru-Bloc Ball Valves, True Union Check Valves, Model-B Butterfly Valves, Chemcock Valve, Needle Valve, Angle and Y-Pattern Valves are manufactured and assembled silicone free. Lubricants are occasionally used to assemble these valves, but these lubricants contain no silicone.

Butterfly Valves shall be assembled using a lubricant containing silicone.

The above listed valves shall be manufactured in an ISO 9001:2000 certified facility.

Valves-Plastic Manufacturers - Subject to compliance with requirements, provide valves of one of the following:

Chemtrol

Haywood

Ipex

2.13 GLASS PIPE AND FITTINGS

A. Pipe & Fittings: Borosilicate glass, ANSI/ASTM C-599.

B. Joints: Stainless steel couplings.

2.14 VITRIFIED CLAY PIPE

A. Pipe & Fittings: Extra strength, hub and spigot pattern ASTM C-200.

B. Joints: Double ball polyvinyl chloride plastic type similar to "Wedge-Lock" Type 1. Joints shall be factory bonded to pipe.

2.15 CORRUGATED METAL PIPE

A. Pipe:

1. 24" diameter and smaller shall be 16 U.S. gauge steel.
2. 30" diameter and larger shall be 14 U.S. gauge steel.
3. All piping shall be completely bituminous coated on the interior and exterior and shall have a paved invert for 25% of its periphery.

B. Joints: Standard coupling bands and bolts as furnished by the pipe manufacturer.

2.16 VALVES (Copper Systems) – Solder ends of Threaded

A. Valves listed below shall be for domestic water systems and comply with the latest requirements of NSF 61-8. Refer to individual sections for gas valves.

B. Ball Valves: NIBCO two piece, full port, 600 psi WOG rated, cold non-shock valve with reinforced TFE seals, 316 stainless steel ball, Eco-brass body, ASTM 584, Alloy C87850, solder ends, or threaded non-blowout stem design. Acceptable NIBCO figure numbers: T/S 685-80-66-LF; T/S 595-Y-66-LF (3 piece).

C. Check Valves: NIBCO Class 125, Eco-brass body, ASTM 584, Alloy C87850, swing type, Y Pattern, threaded cap access. Acceptable NIBCO figure number: T/S 413-LF.

D. Gate Valves: NIBCO Class 125, Eco-Brass body, ASTM 584, Alloy C87850, Rising Stem. Acceptable NIBCO figure number: T/S 113-LF.

E. Balance Valves: All balance valves shall be provided with a memory stop feature with calibrated name plate to assure specific valve setting. Bronze body/brass ball, carbon filled TFE seat rings. NIBCO, Bell & Gosset, Accu-Flow, Taco or Flow Design "Accusetter". Acceptable NIBCO figure

numbers: T/S 1710, F/G 737.

F. Strainers:

1. Class 125 Bronze Y-Strainer, body to be ASTM B584 or B62 bronze with threaded, solder or female press end connections and .033 inch perforated type 304 stainless steel screen or 20 mesh type 304 stainless steel screen accessible without removing the strainer from the line. Acceptable Figure numbers: NIBCO Fig. S/T-221, S/T-222, PF-221/222-A,B.

2. Class 125 Flanged Cast Iron Y-Strainer, body to be ASTM A-126 Class B cast iron. End connections to be Class 125 flanged, tapped bolted bonnet with plug. Screen shall be .033 inch perforated type 304 stainless steel screen or 20 mesh type 304 stainless steel screen accessible without removing the strainer from the line. Acceptable Figure numbers: NIBCO Fig. F 721-A.

3. Class 250 Threaded Cast Iron Y-Strainer: Strainer body to be ASTM A-126 Class B cast iron. End connections to be Class 250 threaded, tapped screw-in bonnet with plug. Screen shall be .033 inch perforated type 304 stainless steel screen or 20 mesh type 304 stainless steel screen accessible without removing the strainer from the line. Acceptable Figure numbers: NIBCO Fig. T-751-A

G. VALVES (Copper Systems) – Press Fit

1. Valves listed below shall be for domestic water systems and comply with the latest requirements of NSF-61-8.

a. 2 Inch and Smaller Ball Valves (On/Off):

Ball Valves with male or female press to connect shall be rated at 200 PSI CWP to +225°F maximum. Valves shall be manufactured in accordance with MSS SP-110 and constructed of dezincification resistant cast bronze bodies. Brass with more than 15% zinc shall not be approved. Valve shall have reinforced PTFE Seats, Blow-out Proof Stem, Full Port Ball, Chrome/Nickel Plated or Stainless Steel Ball for aggressive water.

b. 2 Inch and Smaller Check Valves (Swing Type):

Check valves shall be swing type Y pattern with male or female press to connect ends and shall be rated 200 PSI CWP to + 250°F maximum. Valves shall be manufactured in accordance with MSS SP-80. Body & cap shall be manufactured of dezincification resistant cast bronze ASTM B62 or ASTM B584 Alloy C8440. Valves shall have PTFE seat disc.

c. 2 Inch and Smaller Check Valves (Lift or Spring Type):

Incline resilient disc, spring actuated, 250psi rating, non-shock cold working pressure, 2500F maximum working temperature, bronze ASTM B584 alloy C84400. Stainless steel stem and disc holder and spring, EDPM O-ring.

H. Insofar as possible, all valves of the same type shall be of the same manufacturer.

I. Valve Manufacturers: Subject to compliance with requirements, provide valves of one of the following:

Apollo/Conbraco

Stockham

Nibco

Milwaukee

Watts

Hammond

Webstone

J. System Application:

1. Domestic Water:

a. Check Valves - 2" & Smaller - threaded or soldered.

b. Ball Valves - 3" & Smaller - threaded or soldered.

c. Balance Valves - All sizes - threaded.

d. Butterfly Valves - 4" and larger - flanged.

e. Butterfly Valves – 3” and smaller – wafer type.

2.17 THERMOMETERS

A. Separable socket, inserted into fluid flow, adjustable, hermetically sealed, red mercury, die-cast, baked enamel finish, double strength glass lens, white scale and black graduations.

B. Scale: Select range of thermometer to indicate normal operating temperature at mid-point of scale for domestic water systems.

C. Manufacturer: U.S. Gauge, H.O. Trerice, Moeller, Duro.

2.18 GAUGES

A. Phosphor bronze bourdon tube, polypropylene case, gasketed glass crystal, aluminum dial, black graduations 4-1/2 inch diameter.

B. Range: 0 to 150 psi, 5 pound intervals, 1/2 pound graduations.

C. Manufacturers: Danton, U.S. Gauge, H.O. Trerice, Moeller.

D. Install with bronze gauge cock.

2.19 ISOLATING FITTINGS

A. Furnish isolating fittings between all sections of dissimilar piping materials or piping, general supports, equipment and supports, including piping hanger and rack supports where one material is ferrous and the other is non-ferrous.

B. Install copper or brass piping or tubing in such a way as not to touch or come in contact with ferrous metals.

C. Where ferrous piping or equipment is connected to copper or brass piping, make connection with insulating or dielectric unions to prevent electrolytic action between the ferrous and non-ferrous metals.

D. Where copper or brass piping, tubing or fittings are anchored to, supported by or may come in contact with ferrous metal construction, provide an insulating nonconductor spacer of rubber, fiber or equivalent material to assure prevention of electrolysis.

E. Manufacturer: Epco Sales, Inc., or insulated unions by Central Plastic Co.

2.20 ANCHORS AND GUIDES

A. Anchors and guides shall be provided to support and maintain pipes in position and properly distribute expansion. The anchors and guides must be securely fastened to the building structure, and must be completely installed before the system is tested.

B. Guides shall be as manufactured by J.J. McNally, Inc., Flexonics, Inc., Tube-Turns, American District Steam Co.

2.21 UNIONS

A. Up to and including 2 inch pipe size: Screwed pattern, bronze-to- bronze seat.

B. Above 2 inch pipe size: 125 Class Flanged pattern, A.S.A. sweat copper fitting, with gaskets, bolts and nuts.

C. Copper tubing unions shall have sweated type ends. Flanged unions on copper tubing may be soldered connections.

D. Materials and pressure ratings shall be the same as specified for the respective pipe and fitting system unless otherwise specified.

2.22 MOTORS

A. All single phase and polyphase motors shall be manufactured to incorporate the latest NEMA standards.

B. All single phase and polyphase motors shall have steel frames with ball bearings and copper windings. All motors to have a Class "F" insulation system with a service factor of 1.15.

C. All motors shall be 1725 RPM, 4 pole design, unless otherwise noted on the drawings, or in the equipment specifications.

D. Motors installed indoors and not exposed to moisture shall be open, dripproof, Class B temperature rise based on 40 deg. C maximum ambient temperature.

E. Motors installed outdoors and exposed to moisture shall be totally enclosed, fan cooled, Class B temperature rise based on 40 deg. C maximum ambient temperature.

F. Based on NEMA Standards motors shall comply with the following minimum nominal efficiencies at full load.

Nominal Efficiencies for "NEMA Premium ™" Induction Motors Rated 600 Volts or Less (Random Wound)						
	Open Drip-Proof			**Totally Enclosed Fan-Cooled**		
HP	**6-Pole**	**4-Pole**	**2-Pole**	**6-Pole**	**4-Pole**	**2-Pole**
1	**82.5**	**85.5**	**77.0**	**82.5**	**85.5**	**77.0**
1.5	**86.5**	**86.5**	**84.0**	**87.5**	**86.5**	**84.0**
2	**87.5**	**86.5**	**85.5**	**88.5**	**86.5**	**85.5**
3	**88.5**	**89.5**	**85.5**	**89.5**	**89.5**	**86.5**
5	**89.5**	**89.5**	**86.5**	**89.5**	**89.5**	**88.5**
7.5	**90.2**	**91.0**	**88.5**	**91.0**	**91.7**	**89.5**
10	**91.7**	**91.7**	**89.5**	**91.0**	**91.7**	**90.2**
15	**91.7**	**93.0**	**90.2**	**91.7**	**92.4**	**91.0**
20	**92.4**	**93.0**	**91.0**	**91.7**	**93.0**	**91.0**

Nominal Efficiencies for "NEMA Premium ™" Induction Motors Rated 600 Volts or Less (Random Wound)						
	Open Drip-Proof			Totally Enclosed Fan-Cooled		
HP	6-Pole	4-Pole	2-Pole	6-Pole	4-Pole	2-Pole
25	93.0	93.6	91.7	93.0	93.6	91.7
30	93.6	94.1	91.7	93.0	93.6	91.7
40	94.1	94.1	92.4	94.1	94.1	92.4
50	94.1	94.5	93.0	94.1	94.5	93.0
60	94.5	95.0	93.6	94.5	95.0	93.6
75	94.5	95.0	93.6	94.5	95.4	93.6
100	95.0	95.4	93.6	95.0	95.4	93.6
125	95.4	95.4	94.1	95.0	95.4	94.1
150	95.4	95.8	94.1	95.8	95.8	95.0
200	95.4	95.8	94.1	95.8	96.2	95.0

G. Motor Characteristics: Refer to Equipment Schedules for specific data.

120/208 Volt System: Motors 1/2HP & Larger - 208V, 3 Phase, 3 Wire
Motors Less than 1/2HP- 120V, 1 Phase, 2 Wire

277/480 Volt System: Motors 1/2HP & Larger - 480V, 3 Phase, 3 Wire
Motors Less than 1/2HP-120/277V, 1 Phase, 2 Wire.

Pick One

H. All motors rated less than 1/2HP shall have thermal protection of the auto-reset type as an integral part of the motor.

I. All motors rated 1/2HP and larger shall have thermal protection provided by an external device.

2.23 POWER FACTOR CORRECTION AT MOTORS

A. All motors 3 HP and above shall be provided with capacitors sized as recommended by the motor manufacturer to correct the full load running current of the motor to 95 PF, or to the maximum PF value as determined by the total capacitance which the particular motor design and duty can safely accommodate. Capacitors shall be wired to the load side of the starting contacts ahead of the overload protective devices so that motor and capacitor are switches simultaneously.

B. Capacitors for motors with starters located in a motor control center shall be furnished and mounted on the rear of the motor control center by the Electrical Contractor.

C. Where the motor, starter, and wiring area integral part of a packaged type equipment assembly, the capacitors shall be furnished, wired and mounted on the equipment by the manufacturer.

D. Multi-speed motors with two or more windings shall have capacitors on each speed (or winding) arranged with auxiliary contactors so that when that winding is not energized the capacitor is disconnected.

E. For motors connected to high inertia loads, a time delay device shall be provided to prevent restart of that motor until its speed has been reduced and the charge remaining in the capacitor has reached a safe level for restart.

F. Power capacitors shall be 3 phase, industrial grade, mounted in a dust tight enclosure with removable shroud. Sprague Power Capacitors, Square D, General Electric or approved substitute.

PART 3 – EXECUTION

3.1 PIPING SYSTEM INSTALLATION REQUIREMENTS

A. Drawings are generally diagrammatic and due to small scale, it is impossible to indicate all fittings, valves, gauges and specialties required. Provide complete operating systems and all necessary fittings, valves gauges and specialties whether or not indicated.

B. Install all piping in accordance with the best practices of the trade and latest code requirements. Use uniform system materials throughout the building. All branch take-offs shall be off the top of the pipe.

C. Pipe and fittings shall be clean from cutting burrs, foreign materials and defects in structure and threading. Make all cuts square. Ream after cutting. Clean off scale and dirt inside and outside, before assembly. Remove welding slag or other foreign material.

D. Keep all piping as high as possible, consistent with proper pitch, to maintain maximum headroom. Cut piping accurately to measurements established at the building, work into place without springing, forcing or cutting of the building structure, and install as directly as possible between connecting points parallel with or at right angles to building construction, except as required to obtain pitch.

E. Unless otherwise shown, run piping within the building, concealed in the walls, furred spaces, pipe spaces or above suspended ceilings. Unless otherwise noted, do not build in or bury horizontal piping in partitions. Install all exposed piping as closely as possible to walls, ceilings and columns, consistent with access and applicable insulation requirements.

F. This project includes a return air plenum ceiling. Regardless of materials specified, all system piping and/or materials shall be non-combustible and shall be in full compliance with the requirements set forth in the IPC.

G. All piping to drain to low points. Low points will be provided with drain valves with hose thread. All piping shall have high points vented with ball valve, nipple and threaded cap.

H. Do not install trapped lines where water cannot be drained or air can accumulate without being vented.

I. Piping shall run square with building lines.

J. Piping shall not be insulated or covered until tested and until building is closed in.

K. Necessary drains, off-sets, vents and drips shall be provided for coordination of the work as part of the contract.

L. Piping shall not be installed over electrical transformers, panels, switchgear, substations, and control panels as per the National Electric Code. No piping shall be installed in elevator machine rooms unless it is directly related to the room's system equipment.

M. Allow clearance for expansion and contraction.

N. Install isolating fittings between sections of ferrous and non- ferrous pipe or connected equipment.

O. Valves shall be installed with stems above horizontal.

P. Valves shall be installed on all sides of equipment and control valves to allow isolation for repair.

Q. Do not support piping from other piping, conduits or equipment. Provide additional bracing to prevent movement of trapeze piping, or any singular run of pipe to fixtures. Provide additional bracing on all piping through walls to flush valves to prevent movement during normal operation or performing maintenance on valves.

R. Thermometers and gauges shall be installed where indicated on the drawings, required by equipment specifications and where indicated elsewhere in the specifications. Gauges shall be located at an elevation that can be readable.

S. Unions shall be provided adjacent to all valves, at equipment connections, and where necessary to facilitate dismantling of the piping system.

T. Ball valves to be installed with the proper clearance for operating the valve handle. A minimum clearance of 10" from center of valve to wall must be maintained for ease of operation.

U. Thermometers are to be located so they can easily be seen from the floor in front of unit. Make final adjustment by tilting thermometer. Locate bulb in waterway with an oversized tee or elbow fitting.

V. Install pressure gauges on incoming services both domestic water and fire services. Locate pressure gauge after main shut-off valve and ahead of water meter if one is provided within building.

W. All pipe unions installed shall be accessible. Unions shall not be concealed or located in places where they cannot be maintained.

X. Support and bracing of 4” and above pipe shall be in accordance with the CISPI Standards and IPC Chapter 3.

3.2 TAGS, CHARTS, AND IDENTIFICATION

A. All piping shall be labeled in accordance with IPC 303.1 and 303.4.

B. Identify each valve in all systems with black, numbered and stamped 1-1/2" brass or aluminum tags fastened to valve by brass chain and S-hook.

C. Piping Identification: Provide identification and safety products, semi-rigid plastic, wraparound pipe markers with flow arrows and conforming to ANSI A13.1. Locate marker at each valve, changes in direction, where pipes pass thru barriers and every 25' of horizontal runs. Lettering on background shall be in accordance with the following colors:

Legend	Background	Lettering
1. Gas	- Yellow	- Black
2. Fire Protection	- Red	- White
3. Domestic Cold Water	- Green	- White
4. Domestic Hot Water (110° ^ 140°)	- Yellow	- Black
5. Domestic Hot Water Return (110° ^ 140°)	- Yellow	- Black
6. Sanitary Drainage	- Green	- White
7. Condensate Drainage	- Yellow	- Black
8. Vent	- Yellow	- Black
9. Storm Drainage	- Green	- White
10. Medical Gas	Conform to NFPA-99 Regulations	

11. Plant Compressed Air	- Yellow	- Black

D. Provide 1/8" scale diagrams showing location, number and service or function of each tagged item.

1. Frame diagrams in approved metal frames with clear acrylic front, hinges, and locks.
2. Secure to wall in Mechanical Room.
3. Provide two additional separate copies permanently covered and bound.

E. Furnish and install color coded 1" diameter markers on ceiling tile grids to indicate system and valve locations.

1. Domestic cold water: - Green
2. Domestic hot water: - Yellow
3. Domestic hot water return: - Yellow
4. Gas - Yellow

F. Available Manufacturers: Subject to compliance with requirements, manufacturer's offering identification markers which may be incorporated in the work are limited to the following:

Seton

Brimar

B-Line

Marking Services, Inc.

3.3 WELDING

A. All concealed and inaccessible black steel piping shall be welded.

B. All black steel piping larger than 2 inch shall be fusion welded.

C. All elbows, tees and branch connections shall be made with welding fittings ANSI B16.9.

D. Welding shall be in accordance with the ASME Boiler and Pressure Vessel Code Section IX.

E. Furnish welder test certificate for review. Certificates of successful qualification by the following organizations shall be acceptable.

1. ASME Boiler and Pressure Vessel Code
2. ANSI Code for Pressure Piping
3. National Certified Pipe Welding Bureau
4. Military Specification MIL-STD-248

3.4 SOLDERING/BRAZING

A. Connections between copper tubing and copper sweat fittings shall be made by soldering using Taramet Sterling or approved substitute. Flux shall be non-corrosive type "Nokorode" or approved substitute or as recommended by the manufacturer of the solder.

B. All solder shall be "lead nickel and antimony free" in accordance with the Federal Safe Drinking Water Act Amendments of 1986 and 1996 as is ASTM B-32 Grade TC.

Composition:

Tin	95%
Copper	4.0 – 5.0%
Selenium	.04 - .2%
Tensile Strength	7,130 psi
Shear Strength	5,970 psi
Melting temperature	410°F

C. Tubing shall be cut square and then reamed and deburred. End of tubing and inside of fitting cup shall be cleaned with steel wool and the flux shall be applied to the clean surface before soldering. After soldering, the excess solder shall be wiped off while still plastic.

D. Silver brazing alloy shall be equal to and shall be used for joints in:

1. Medical Gas Piping (All Systems)
2. Medical Vacuum Piping

E. Brazed Joints:

1. All brazed joints shall be cleaned. An approved flux shall be applied; joint filler metal shall conform to AWS A5.8.
2. Flux shall meet AWS Standard A5.31, Type F83-A or F83-C.

F. 410 solder shall be used for all joints in:

1. Domestic cold water
2. Domestic hot water
3. Domestic hot water return
4. Copper drainage piping
5. Plant compressed air

G. Lead-Tin (50-50) solder or any solder containing lead shall NOT be used or permitted for joint connections on this project.

H. Where the silver brazing is performed in a confined non-ventilated space, a non-toxic, cadmium-free brazing alloy such as Stay-Brite shall be used instead of Easy-Flo. Bring joint to solder temperature or brazing temperature in as short a time as possible.

I. Form continuous solder bead or brazing filler bead around entire circumference of joint.

J. Wipe excess solder from joint area while solder is still plastic.

K. Solder joints shall be in accordance with IPC Section 605.2, 605.14.3 and ASTM B838. Flux shall conform to ASTM B-813.

3.5 PRESS-FIT SYSTEM

A. All new domestic water piping installed on this project shall be a solderless, press-fit, domestic water system. The system shall be Viega/Rigid copper press fitting system. Fittings shall be rated 0□ to 250□ at 200 psi and tested to 600 psi.

B. Fittings shall meet ANSI/NSF 61, – ASME B-16.22 and ASTM B88. Elastomeric seals shall meet ASTM D-2000.

C. Mechanical joining shall be recognized by:

IPC International Plumbing Code

SBCCI Standard Plumbing Code

IAPMO Uniform Plumbing Code

PHCC National Standard Plumbing Code

D. Copper and copper alloy press fittings shall conform to material requirements of ASME B16.18 or ASME B16.22 and performance criteria of IAPMO PS 117. Sealing elements for press fittings shall be EPDM. Sealing elements shall be factory installed or an alternative supplied by fitting manufacturer. Press end shall have SC (Smart Connect) feature design (leakage path). Smart Connect™ (SC Feature). In ProPress ½" to 4" dimensions, the Smart Connect Feature assures leakage of liquids and/or gases from inside the system past the sealing element of an unpressed connection. This feature shall provide the installer quick and easy identification of connections which have not been pressed prior to putting the system into operation.

E. Press Connections: Copper press fitting joints shall be made in accordance with the manufacturer's installation instructions. The tubing shall be fully inserted into the fitting and the tubing marked at the shoulder of the fitting. The fitting alignment shall be checked against the mark on the tubing to assure the tubing is fully engaged (inserted) in the fitting. The joints shall be pressed using the tool approved by the manufacturer.

F. Installer shall be a qualified installer, licensed within the jurisdiction, and familiar with the installation of ProPress copper press joint systems. ProPress copper press fittings shall be installed using the proper tool, actuator, jaws and rings as instructed by the press fitting manufacturer. The installation of copper tubing for hot and cold water distribution systems shall conform to the requirements of the ICC International Plumbing Code or IAPMO Uniform Plumbing Code.

G. Note: Viega Press-fit installation shall only be permitted on this project. Push-on shark-teeth, or any type connection fittings that are not Press-Fit, shall NOT be approved.

H. T-drill mechanically formed tee fittings shall be used in conjunction with the ProPress Copper System in accordance with the IPC Chapter 6 Section 605.5.1, 605.5.1.2 and 605.14.1. Use caution around combustible material and follow all safety guidelines for open flame during silver brazing.

END OF SECTION 220010

SECTION 220030

INSULATION & COVERING – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the Work specified in this Section.

1.2 DESCRIPTION OF WORK

A. Refer to Section 220005 for a general description of the scope of work in this contract.

B. This section includes insulation and covering furnished and installed on the following piping systems and equipment:

1. Domestic cold water.
2. Domestic hot water supply and return
3. "Primary" Horizontal rainwater conductors including underside of roof drains. "Secondary" rainwater systems insulation is not required.
4. Condensate waste piping from air conditioning units.
5. Hot water storage tanks.
6. Cold water storage tanks.
7. Exposed waste, trap and wall supplies at all handicap lavatories.
8. Branch waste lines from all chilled water fountains.

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

B. Materials shall conform to the requirements of the NFPA Code.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

B. Submit the following:

1. Product data on all insulation and covering.
2. Provide at project site, a sample of each type of insulation hereinafter specified. Display insulation in an "installed" condition, showing typical completed pipe, fitting, , and equipment insulation. No insulation shall be applied until these samples have been accepted by the Engineer. Any insulation work which does not conform to the accepted samples will not be acceptable, and shall be removed and reinstalled in a manner acceptable to the Engineer. **(Note to Specifier: Use this option only if you feel it is absolutely necessary. If it used, <u>YOU</u> must remember to call for the simplest at Shop Drawing time.**

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of

the Contract and in Division 1, GENERAL REQUIREMENTS.

PART 2 – PRODUCTS

2.1 PIPE INSULATION MATERIAL

A. Fiberglass:

1. Material: Preformed fiberglass bonded with resins to form circular pipe sleeves with factory applied, white all-service jacket bonded to reinforced foil vapor barrier jacketing. The jacket shall have factory-applied double pressure-sensitive adhesive closure and vapor sealing of longitudinal joints. Thermal Conductivity: .25 per inch at 100 degrees F. Flame spread of 25 and developed smoke of 50 or less.

2. All Valves and Fittings:

   a. Class fiber insert and premolded PVC cover, Manville "Zeston" and "Hi-Lo Temp Inserts" for valves and fittings.

   b. Factory molded fibrous glass fitting covering for fittings.

   c. Mitered sections of pipe covering for valves.

3. Manufacturers: Johns-Manville, Certain-Teed, Owens-Corning.

B. Closed Cell:

1. Material: Flexible elastomeric foamed plastic closed cell structure insulation 25/50 rated with a flame spread rating of 25 or less and a smoke developed rating of 50 or less.

2. Flexible pipe insulation shall be a foamed plastic closed cell structure material, with a thermal conductivity of not more than 0.27 Btu/Hr./Sq. Ft./Inch at a mean temperature of 75 degrees F. The insulation shall have an average density of at least 2 pounds per cubic foot, shall be self-extinguishing, and shall have a water vapor transmission rating of not more than 0.1 perms. Between temperature limits of -40 degrees F and plus 220 degrees F, the insulation shall not indicate any deviation from its original state.

3. Manufacturers: Armacel, Insul-Tube, Nomaco Insulation.

4. Specification Compliance: (Latest accepted Standards and Codes)

IECC 804.5:	Insulation thickness for domestic hot and recirculation mains.
ASTM-E-84	Flame spread and smoke developed.
NFPA 255:	Standard method of test of surface burning of building materials.
ASTM C177:	Thermal conductivity.
NFPA 90A, 90B:	Flame & smoke rating
ASTM-C-534 Type 1	Tubular Grade, Self-Sealing
UL 181	Factory made air ducts and air connectors. (Armacell UL181 has to do with mold growth)
UL723	Test for surface burning characteristics of building materials.
ASTM G21/C1338:	Fungi resistance
ASTM G2:	Bacterial Resistance
ASTM D1056, 2B1:	Standard spec for flexible cellular materials.

MIL-P-15280J, FORMT

MIL-C-3133B (MIL STD 670B) Grade SBE-3

MEA 96-85M

C. Covering of Pipe Insulation Outdoors:

1. Wrapping: Wrap insulation with embossed .016" aluminum jacket.
2. Fastenings: Cover shall be held in place with soft aluminum bands on 12" centers.
3. Valves and Fittings: Weatherproof all valves and fittings.
4. Manufacturers: Johns-Manville, Certain-Teed, Owens-Corning, Knauf.

D. Protective cover for foam insulation in wet areas indoors:

1. PVC heavy duty fitting covers and jacketing for kitchen wet areas.
2. Fitting covers shall be glossy white, high impact, UV resistant PVC.
3. Operating Temperature Limit: Up to 150ºF.
4. Flame Spread: 25 or less.
5. Smoke Developed: 50 or less.
6. Grade: Weatherable.
7. Color: White
8. Finish: Gloss
9. Fitting covers and jacketing shall be “Zeston” 300 Series PVC, heavy duty covers and “Zeston” PVC jacketing.

PART 3 – EXECUTION

3.1 INSTALLATION

A. Do not install until systems have been tested and meet requirements.

B. Do not install until building is closed in.

C. Heavy work which may damage insulation shall have been completed in the vicinity of the insulation work.

D. All installations shall be made by skilled craftsmen regularly engaged in this type of work.

E. Insulation shall be continuous thru-wall, ceiling and floors.

F. Pipe and equipment to be clean and dry prior to insulating.

G. Install all insulation in strict conformance with manufacturer's instructions.

H. Where "Barrier-free" lavatory supplies and waste are covered with a protective covering or insulation, the insulation must be installed back to wall, flush with wall escutcheon. Escutcheon to be finished flush with wall and wall opening to be smaller than escutcheon plate through entire building.

I. All electrical heat tracing installations shall be coordinated with the electrical contractor. No insulation shall be installed until the heat trace wiring is completely installed, tested and approved. All insulation materials and installation work shall be the responsibility of the Insulation Contractor.

J. Install pipe insulation by slitting tubular sections and applying onto piping or tubing. Alternately, whenever possible, slide unslit sections over the open ends of piping or tubing. All seams and butt

joints shall be adhered and sealed using Armaflex 520 or 520 BLV Adhesive. If when using AP Armaflex SS, only the butt joints shall be adhered using Armaflex 520 or 520 BLV Adhesive, Armaflex HT 625 Adhesive shall be used with HT Armaflex.

K. Insulation shall be pushed onto the pipe, never pulled. Stretching of insulation may result in open seams and joints.

L. Tape the ends of the copper tubing before slipping the Armaflex insulation over the new pipes to prevent dust from entering the pipe.

M. All edges shall be clean cut. Rough or jagged edges of the insulation shall not be permitted. Proper tools such as sharp, non-serrated knives must be used.

N. On cold piping, insulation shall be adhered directly to the piping at the high end of the run using a two-inch strip of Armaflex 520 or 520 BLV Adhesive on the ID of the insulation and on the pipe. All exposed end cuts of the insulation shall be coated with Armaflex 520 or 520 BLV Adhesive. All penetrations through the insulation and termination points must be adhered to the substrate to prevent condensation migration.

O. Sheet insulation shall be used on all pipes larger than 6” IPS. Insulation shall not be stretched around the pipe. On pipes larger than 12” IPS, adhere insulation directly to the pipe on the lower 1/3 of the pipe.

P. Seams shall be staggered when applying multiple layers of insulation.

3.2 VALVES, FLANGES AND FITTINGS:

A. All fittings shall be insulated with the same insulation thickness as the adjacent piping. All seams and mitered joints shall be adhered with Armaflex 520 or 520 BLV Adhesive. Screwed fittings shall be sleeved and adhered with a minimum 1” overlap onto the adjacent insulation. Armaflex HT 625 Adhesive shall be used with HT Armaflex.

B. Valves, flanges, strainers and Victaulic couplings shall be insulated using Armaflex donuts that shall then be covered with sheet or oversized tubular insulation.

3.3 HANGERS

A. Support piping system using high density inserts with sufficient compressive strength. The pipe support insulation shall be elastomeric foam with the same or greater thickness than the pipe insulation. All joints shall be sealed with Armaflex 520 or 520 BLV adhesive.

B. Standard and split hangers: Piping supported by ring hangers shall have hangers insulated with the same insulation thickness as the adjacent pipe. All seams and butt joints shall be sealed with Armaflex 520 or 520 BLV Adhesive. Armaflex HT 625 Adhesive shall be used with HT Armaflex. Ring hangers may be sleeved using oversized tubular insulation. On cold piping, insulation shall extend up the hanger rod a distance equal to four times the insulation thickness. Insulation tape may be used to a thickness equal to the adjacent insulation thickness.

C. Clevis Hangers or other pipe support systems: Saddles shall be installed under all insulated lines at unistrut clamps, clevis hangers or locations where the insulation may be compressed due to the weight of the pipe. All piping shall have wooden dowels or blocks of a thickness equal to the insulation inserted and adhered to the insulation between the pipe and the saddle.

It is highly recommended for continuous insulation protection to use hanger sizes equal to the outer diameter of the pipe plus insulation thickness

D. Armafix IPH o Armafix NPH can be used to prevent compression of insulation at standard split, clevis hangers or other pipe support systems. To minimize the movement of Armafix, it is recommended that a pair of non-skid pads be adhered to the clamps. In addition, to prevent loosening of the clamps,

use of an antivibratory fastener, such as a nylon-locking nut, is also recommended.

3.4 OUTDOORS EXPOSED PIPING

A. All outdoor exposed piping shall be painted with two coats of WB Armaflex Finish. Prior to applying the Finish, the insulation shall be wiped clean with denatured alcohol. The Finish shall not be tinted.

B. All outdoor exposed piping shall have the seams located on the lower half of the pipe.

3.5 EXTERIOR PIPE COVERING

A. Wrapping: Wrap insulation with embossed .016" aluminum jacket.

B. Fastenings: Cover shall be held in place with soft aluminum bands on 12" centers.

C. Valves and Fittings: Weatherproof all valves and fittings.

D. Finish: Apply two coats of vapor resistant mastic reinforced with glass fabric over wrapping.

3.6 PIPE COVERING (FOAMED PLASTIC TYPE)

A. All joints and seams shall be sealed with a compatible adhesive. Approved adhesives are as follows:

Armacel No. 520 (Low VOC use 520 BLV

Benjamin Foster Company No. 85-75 up to 200 degrees F.

Contractor may use self-sealing insulation in lieu of above.

B. Fitting covers shall be fabricated from the foamed plastic pipe insulation or from sheet insulation of the identical material. The fabrication shall be in accordance with manufacturer's instructions, and all seams mitered joints shall be joined using the adhesives described.

3.7 PIPE INSULATION – TYPES & THICKNESSES

A. Flexible Closed Cell:

Piping System	Up to 3"	Over 3" to 6"	Over 6"
Cold Water	½"	½"	¾"
Hot Water (120º)	1"	1"	1-1/2"
Hot Water Return (120º)	1"	1"	1-1/2"
Hot Water (140º)	1"	1"	1-1/2"
Hot Water Return (140º)	1"	1"	1-1/2"
Condensate Waste	½"	½"	-
Horizontal Storm (Primary)	½"	½"	¾"
Horizontal Storm (Secondary) -----Not Required-----			
Underside of Roof Drains	½"	½"	¾"
Branch Waste From EWC's	½"	---	---
Handicap Lav Waste & Water	½"	---	---
Soil/Waste Piping Above Ceiling	½"	½"	¾"

B. Fiberglass:

Piping System	Up to 3”	Over 3” to 6”	Over 6”
Cold Water	½”	½”	¾”
Hot Water	1”	1”	1-1/2”
Hot Water Return	1”	1”	1-1/2”
Hot Water	1”	1”	1-1/2”
Hot Water Return	1”	1”	1-1/2”
Condensate Waste	½”	½”	---
Horizontal Storm (Primary)	½”	½”	¾”
Horizontal Storm (Secondary)	½”	½”	¾”
Underside of Roof Drains	½”	½”	---
Soil/Waste Piping Above Ceiling	½”	½”	¾”

END OF SECTION 220030

SECTION 220110

DRAINAGE SYSTEMS – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the work specified in this Section.

1.2 DESCRIPTION OF WORK

A. Refer to Section 220005 for a general description of the scope of work in this contract.

B. This section includes:

1. Soil and waste piping system work as indicated on drawings and schedules, and by requirements of this section.
2. Applications for soil and waste piping systems include the following:
   a. Above ground soil, waste and vent piping within buildings including soil stacks, vent stacks, horizontal branches, traps and connections to fixtures and drains.
   b. Underground building drain piping including mains, branches, traps, connections to fixtures and drains, and connections to stacks, extension from the building, terminating at connection to site sewer.
3. Storm water drainage piping as indicated on drawings and by requirements of this section.
4. Applications for storm water drainage piping include the following:
   a. Roof drains and connections to gutters, with rain water conductors and connections to underground building storm drains.
   b. Underground building storm drains, extending and connecting to site drainage system.
5. Insulation for soil and waste and storm water drainage as specified in Section 220030 is included as work of this section.
6. Trenching and backfilling required in conjunction with underground building drainage and site drainage piping as specified in Section 220000 is included as work of this section. Refer to Division I.
7. Installation of detectable metallic underground tape for <u>all</u> exterior buried PVC drainage piping.

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section, and a listing of all applicable codes.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

B. Submit the following:

1. Product data on all systems equipment.

C. See requirements for submission of cross referencing information.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

PART 2 – PRODUCTS

2.1 PIPING UNDERGROUND

A. Interior:

1. Sanitary, storm water and condensate waste drainage piping within the building and extending beyond the building wall, unless otherwise noted on the plans shall be an option selection of a, b, or c below:

   a. Service weight hub and spigot pattern cast iron soil pipe and fittings with neoprene gaskets.

   b. Hubless cast iron soil pipe and fittings with cast iron coupling clamps and gaskets or heavy duty 3.04-.016" thick stainless steel bands.

   c. PVC Schedule 40 pipe and fittings with solvent cement joints.

2. Kitchen Sanitary Drainage and/or Mechanical Room Sanitary Drainage: All Kitchen and/or Mechanical Room sanitary below slab piping and fittings shall be service weight cast iron hub and spigot fitting with butyl rubber gaskets or hubless fittings with heavy duty couplings (no PVC shall be acceptable).

B. Exterior:

1. Stormwater drainage piping 10 inches and smaller, and all sanitary drainage piping unless otherwise noted on the plans, shall be:

   a. Service weight hub and spigot pattern cast iron soil pipe and fittings, with neoprene gaskets.

   b. Hubless cast iron soil pipe and fittings with cast iron coupling clamps and gaskets.

   c. Unplasticized PVC sewer pipe and fittings SDR-35.

2. Stormwater drainage piping 12 inches and larger, shall be:

   a. Reinforced concrete pipe and fittings.

   b. Corrugated metal pipe.

   c. As identified on the drawings.

3. Foundation drainage piping shall be:

   a. Porous concrete pipe and fittings.

   b. Perforated PVC pipe and fittings Schedule 40.

2.2 PIPING ABOVE GROUND

A. All above ground storm water, condensate, soil, waste and vent piping shall be:

1. Hubless cast iron soil pipe with cast iron drainage fittings, couplings and stainless steel clamp bands for piping 2" and larger.

2. Copper tubing, type DWV with wrought copper solder type drainage fitting for piping smaller than 2" in size.

3. PVC pipe and fittings type DWV with solvent cement joint connections. (Not permitted in areas

of plenum rated ceilings.)

2.3 CONDENSATE WASTE PIPING SYSTEM

A. All aboveground condensate waste piping including connection to equipment shall be:

1. PVC pipe and fittings type DWV with solvent cement joint connections. (Not permitted in areas of plenum rated ceilings.)

2. Copper tubing, type DWV with wrought copper solder type drainage fittings.

2.4 ACID WASTE PIPING

A. Pipe & Fittings: Polyvinyllidene fluoride (PVDF), ASTM F-1673, pipe shall be marked with "UL" to indicate compliance with UL723 (ASTM E84).

B. Joints (Aboveground)

1. No hub, plain end, outerban, nuts and bolts per ASTM B117.

2. Socket Fusion: ASTM 2657, ASTM D3222.

C. All above ground acid waste piping including connections to lab sink or equipment shall be:

1. Flame retardant polypropylene Type II Schedule (40) (80), with mechanical or fusion-welded joints.

2. Schedule 40 Borosilicate glass pipe and fittings with stainless steel couplings.

D. All below ground acid waste piping including stub-ups 6" above the floor slab shall be:

1. Flame retardant polypropylene pipe and fittings Type II Schedule (40) (80) fusion welded.

2.5 FLASHING

A. All vents extending through the roof shall be flashed by the General Contractor. However, the Plumbing Contractor shall furnish and install the necessary counterflashing consisting of a Jay R. Smith Figure 1748 counterflashing fitting, or approved substitute as manufactured by Josam or Zurn. Vents shall terminate 18" above the roof.

2.6 SPECIAL EXPANSION COMPENSATION

A. Special expansion compensation products required for storm, condensate, soil and waste piping systems include the following types:

B. Cast Iron Drainage System Expansion Joints: Cast-iron body, adjustable bronze sleeve, bronze bolts with wing nuts; for vertical installation only.

C. PVC Drainage System Expansion Joints: Factory prelubricated "O" ring expansion joint fitting. Installation must be in strict conformance with manufacturer's recommendations.

D. Available Manufacturers: Subject to compliance with requirements. Manufacturers offering expansion joints which may be incorporated in the work include:

1. Cast Iron Piping Systems - J.R. Smith or approved substitute.

2. PVC Piping Systems – George Fisher or approved substitute.

2.7 BACKWATER VALVES / FLOODGATE

A. Backwater valves (BWV) installed in the interior or exterior building sewer extension, shall be all PVC construction materials.

B. The backwater valve shall be in compliance with the latest edition of IPC and UPC Plumbing Codes.

C. Description:

1. The BWV shall be as manufactured in accordance with "ICC-ES" criteria.

2. The BWV shall be 3- and 4-inch diameter backwater valves, shall meet the performance requirements of CSA B181.1 and CSA B181.2. The factory kit consists of a valve body, disc, disc seat, and upper collar. The factory supplied plastic materials conform to NSF 14-99 and ASME A 112.14.1.

3. Removal of the integral lifting device from a buried valve allows above-grade replacement of the disc assembly and reinstallation into the valve body. The integral lifting device is self-aligning, self-seating, and provided with an alignment indicator located within 12 inches (305 mm) of the upper access opening.

4. Floodgate / Backwater Valve Basin

   Valve basin must be installed in a ventilated and dry access pit in the horizontal drain line between the building and the sewer main.

   Provide access pit of a size that will provide suitable room to inspect and or replace the valve.

   Floodgate / backwater valves are approved for storm and sanitary drain systems. Consult with the local plumbing and sewer authority for any additional requirements.

2.8 SYSTEMS EQUIPMENT

A. Refer to Plumbing Fixture and Equipment Schedule for type, number, size and manufacturer of all drainage equipment and accessories.

B. Available Manufacturers: Subject to compliance with requirements, manufacturers offering drainage equipment which may be incorporated in the work are limited to the following:

Floor Drains (all types)

Zurn

Josam

Wade

Watts

Smith

MIFAB

Roof Drains

Zurn

Josam

Wade

Watts

Smith

MIFAB

Cleanouts

Zurn

Josam

Wade

Watts

Smith

MIFAB

Downspout Shoes

Neenah

Zurn

Josam

Wade

Smith

Watts

MIFAB

Interceptors

Zurn

Josam

Wade

Watts

Smith

Woodford

MIFAB

Backwater Valves & Traps (Cast Iron)

Zurn

Josam

Wade

Watts

Smith

Red Valve Co.

MIFAB

Backwater Valve (PVC)

Clean Check, Inc.

Wall Spout Nozzles

Zurn

Josam

Wade

Watts

Smith

MIFAB

C. Cross Reference Identification:

1. If the Contractor selects a manufacturer of drainage equipment products other than as identified on the Schedule but is selected from the available manufacturers listed above, a cover sheet shall be included with the submission of shop drawings indicating the cross-referenced manufacturer and model number.

2. Shop drawings shall not be reviewed or accepted if not in compliance with this requirement.

PART 3 – EXECUTION

3.1 INSTALLATION OF SOIL AND WASTE PIPING

A. The Plumbing Contractor shall install a complete system of sanitary drainage piping as shown on the drawings. All drainage lines shall be properly run, trapped and vented in accordance with the local Plumbing Code and all dry vents, back vents, loop vents, revents or special vents required by the Code shall be furnished and installed by the Plumbing Contractor.

B. Drainage lines of the sizes shown on the drawings shall be extended within the building with branches connecting to the base of all soil, waste and vent stack, etc., leaving outlets for connection to all fixtures, floor drains, as required.

C. All changes in direction of drainage piping shall be installed with "Y" branches and 1/8 bends. All stacks shall be supported with concealed pipe clamps or hangers as required and the openings in the roof for the vent pipes will be provided by this Contractor.

D. All drainage piping which will be located above suspended ceilings shall be checked for slope to assure positive drainage, prior to installation of the ceilings. Pressure tests for leaks, as hereinafter specified, shall also be performed prior to ceiling installation.

E. Install soil and vent piping pitched to drain at minimum slope of 1/4" per foot (2%) for piping 3" and smaller, and 1/8" per foot (1%) for piping 4" and larger.

F. Vertical to horizontal change in direction to be made with long radius fittings.

G. Support all soil and waste piping per IPC Section 308.5, 308.6 and 308.7.

3.2 INSTALLATION OF STORM WATER DRAINAGE PIPING

A. Connect piping to roof drains and outlets provided in gutters, install rainwater conductors and extend to underground storm building drains as indicated.

B. Underground storm building drains shall be extended from the building, terminating beyond the building wall.

C. Provide exterior clean-out on both sanitary and storm drain mains. Minimum size shall be 4” installed within 5 ft. of the building. (Also see Paragraph 3.5).

D. Connect to exterior downspouts, install cast iron downspout shoes, and extend piping from the building wall.

E. All changes in direction of drainage piping shall be installed with "Y" branches and 1/8 bends. All stacks shall be supported with concealed pipe clamps or hangers as required, and the openings in the roof for the vent pipes will be provided by this Contractor.

F. All drainage piping which will be located above suspended ceilings shall be checked for slope to assure positive drainage, prior to installation of the ceilings. Pressure tests for leaks, as hereinafter specified, shall also be performed prior to ceiling installation.

G. Install storm water drainage piping pitched to drain at minimum slope of 1/8" per foot (1%) for piping 4" and larger.

H. Vertical to horizontal change in direction to be made with long radius fittings.

3.3 INSTALLATION OF ACID WASTE & VENT PIPING

A. Connect to all laboratory equipment requiring acid waste piping, furnish and install traps and extend piping to sanitary drainage piping as indicated.

B. Acid vents shall be extended through the roof, independently of the sanitary system vents.

C. All acid resistant pipe shall be installed in strict accordance with the manufacturers recommendations. The use of solvent cement to dissimilar PVC pipe materials shall not be permitted.

D. All changes in direction of acid drainage piping shall be installed with "Y" branches and 1/8 bends. All stacks shall be supported with concealed pipe clamps or hangers as required, and the openings in the roof for the vent pipes will be provided by this Contractor.

E. All drainage piping which will be located above suspended ceilings shall be checked for slope to assure positive drainage, prior to installation of the ceilings. Pressure tests for leaks, as hereinafter specified, shall also be performed prior to ceiling installation.

F. Install acid waste and vent piping pitched to drain at minimum slope of 1/4" per foot (2%) for piping 3" and smaller, and 1/8" per foot (1%) for piping 4" and larger.

3.4 INSTALLATION OF SPECIAL EXPANSION COMPENSATION PRODUCTS

A. Expansion Joints: Install expansion joints on vertical risers as indicated, and/or as required by _____ Plumbing Code.

B. PVC piping systems in multi-story (four stories or more) shall require "O" ring expansion joints to compensate for length changes in soil, waste and vent stacks. Expansion joints shall be required at every floor level for soil and waste stack and at alternate floors for vent stacks and rainwater conductors.

3.5 INSTALLATION OF CLEANOUTS

A. Cleanouts: Install in sanitary piping and storm conductor and building drain piping as indicated, and/or as required by _____ Plumbing Code; at each change in direction of piping greater than 45 degrees; at minimum intervals of 100' for all size straight run piping; and at base of each conductor. Install floor and wall cleanout covers for concealed piping, select type to match adjacent building finish.

B. Exterior cleanouts shall be installed with access covers flush to grade. The cleanout shall be installed within a concrete pad, 18”x18”x6” thick.

3.6 INSTALLATION OF FLOOR DRAINS (ALL TYPES)

A. Install floor drains in accordance with manufacturer's written instructions and in locations indicated.

B. Install floor drains at low points of surface areas to be drained, or as indicated. Set tops of drains flush with finished floor.

C. Install drain flashing collar or flange so that no leakage occurs between drain and adjoining flooring. Maintain integrity of waterproof membranes, where penetrated.

D. Position drains so that they are accessible and easy to maintain.

E. All floor drains shall be provided with trap primer connections. All floor drains shall have a trap primer discharge line connected to the outlet.

F. All exposed drainage piping shall be DWV copper pipe and fittings. All piping shall be rigidly supported off the wall with split ring clamps or uni-strut.

3.7 INSTALLATION OF ROOF DRAINS

A. Install drains in accordance with manufacturer's written instruction and in location indicated.

B. Coordinate with roofing as necessary to interface roof drains with roofing work.

C. Install drains at low points of surface areas to be drained, or as indicated.

D. Install drain flashing collar or flange so that no leakage occurs between drain and adjoining roofing. Maintain integrity of waterproof membranes, where penetrated.

E. Position drains so that they are accessible and easy to maintain.

F. The roof drain specified is a combination “Primary and Secondary” arrangement. Verify the correct outlet connections to their respective systems.

3.8 INSTALLATION OF DOWNSPOUT SHOES

A. Install downspout shoes in accordance with manufacturer's written instructions and in locations indicated.

B. Downspout shoes shall be installed with top of shoe located 18 inches above finished grade.

3.9 INSTALLATION OF BACKWATER VALVES

A. A threaded plug, female adaptor and 6-inch diameter (152.4 mm) pipe shall be supplied by others for use as the access sleeve and cover. The access sleeve shall be cut to length in the field and attached to the socket on the top of the valve body. This forms the housing for the removable integral lifting device. The integral lifting device consists, in part, of a 4-inch diameter (101.6 mm) pipe which is supplied by others. The 4-inch diameter (101.6 mm) pipe is cut to length in the field, then joined to the disc assembly on the bottom and the collar on the top.

B. The manufacturer’s published installation instructions shall be strictly adhered to and, if requested by the code official, a copy shall be maintained on the job site during installation. A copy of the maintenance instructions shall be left with the Owner.

3.10 INSTALLATION OF INTERCEPTORS

A. Install interceptors in accordance with manufacturer's written instruction and in location indicated.

B. Install flow control fitting where indicated on the drawing and/or diagrams including vent relief piping.

C. Interceptors shall be vented in accordance with the local plumbing code and as indicated on the drawings.

3.11 INSTALLATION OF FOUNDATION DRAINAGE

A. Each section of foundation drainage piping shall be extended up, to a cleanout at grade. Piping shall pitch toward the connection to the stormwater drainage system.

B. Piping shall be laid on minimum of 6 inches No. 8 aggregate crushed stone, and backfill shall be done as detailed on the drawings. Crushed stone shall be washed. Aggregate shall be of the sizes indicated and in accordance with ASTM standards. Stone fill layer shall be carefully placed to the indicated depth without disturbing the pipe alignment and a layer of untreated building paper or 2 inches of salt

hay placed on top of the stone, the full width of the trench. Remaining earth fill shall be mounded at top to allow for settlement.

3.12 UNDERGROUND METALLIC TAPE

A. All exterior underground PVC drainage piping (sanitary, storm, condensate waste) shall be provided with detectable metallic underground tape.

B. Tape shall be similar to Lineguard Maintenance Systems as provided by Utility Supply of America 800-548-1234 or approved substitute as manufactured by Seton.

C. Installation shall comply with manufacturer's recommendations and shall be installed in the backfill after refilling the trench opening completely, and allowed to settle to the desired 4" to 6" depth. The Contractor shall install the tape after final lifts in compaction backfilling or unroll it before final restoration or installation of sod, black dirt, seeding, etc.

D. The tape system shall be installed under the supervision of the Owner's Representative. When the tape system is complete, the Contractor shall provide a test using the tape manufacturer's recommended detection device, to prove the integrity of the installation with the Owner's Representative.

3.13 INVERTS AND ELEVATIONS

A. Indicated inverts and elevations of existing utilities are approximate and based on the best information available. Upon award of Contract, Contractor shall verify in the field all such information and report any discrepancies to the Engineer before proceeding with work.

3.14 PIPING INSTALLED IN FILLED GROUND

A. Piping located below floor slab in filled areas shall be supported either from the floor slab, or with masonry piers to undisturbed earth. Drainage piping shall be supported at each joint. Exterior piping located in filled areas shall be supported with piers.

B. Details of supports and method of installation shall meet with the approval of the Engineer.

3.15 INSPECTION

A. The Plumbing Contractor shall, upon completion of the drainage systems, secure from the Inspector and/or the Municipality under which the installation was made and inspected, certificates or letters of approval indicating the system has been installed satisfactorily. The Plumbing Contractor shall certify that all inspection fees, permits and charges have been duly paid.

3.16 BUILDING DRAINAGE SYSTEM CLEANING AND CAMERA VIDEO TAPE/TRANSMITTER

A. The Plumbing Contractor shall hire the services of Tri-State Grouting (302) 286-0701, Contact: Bert Andrus.

B. The Camera-Video tape/transmitter work shall be executed for the benefit of the Plumbing Contractor to locate all existing below-floor slab sanitary and storm water drainage systems. This work shall be done to verify exact locations where new piping systems shall connect to existing piping systems.

C. When all plumbing work is complete and before final test of the drainage systems, the entire building active below-slab storm and sanitary waste systems, including all short run and small pipe laterals, shall be power flushed and cleaned to clear all or any obstructions in the line. The work shall include all stack systems through each (VTR) vent thru roof and roof drain to the exterior laterals that exit the building.

END OF SECTION 220110

SECTION 220120

DOMESTIC WATER SYSTEMS – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the work specified in this Section.

1.2 DESCRIPTION OF WORK

A. Refer to Section 220005 for a general description of the scope of work in this contract.

B. This Section includes:

1. Domestic water piping systems work is indicated on drawings and schedules and by requirements of this section.

C. Applications for water piping systems include the following:

1. Exterior water service piping from main at curb to building domestic water piping.
2. Exterior water service piping from connection 5'-0" beyond building foundation to building domestic water piping.
3. Exterior fire/sprinkler service from connection 5'-0" beyond building foundation to flanged connection 12" above finished floor slab in Mechanical/Boiler Room.
4. Exterior fire/sprinkler service from street main connection to flanged connection 12" above finished floor slab in Mechanical/Boiler Room.
5. Exterior domestic water meter and pit installation.
6. Domestic cold-water piping.
7. Domestic hot-water piping.
8. Domestic recirculating-water piping.

D. Complete flow balancing of the entire domestic hot water return system.

E. Insulation for domestic water piping as specified in Section 220030 is included as work of this section.

F. Trenching and backfill required in conjunction with exterior water piping as specified in Section 220000 is included as work of this section. Refer to Division 1.

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

B. Submit the following:

1. Product data on all specialties and systems equipment.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

PART 2 – PRODUCTS

2.1 DOMESTIC WATER PIPING MATERIALS AND PRODUCTS

A. Provide piping materials and factory fabricated piping products of sizes, types, pressure ratings, temperature ratings, and capacities as indicated. Where not indicated, provide proper selection as determined by Installer to comply with installation requirements. Provide sizes and types matching piping and equipment connections; provide fittings of materials which match pipe materials used in domestic water piping systems. Where more than 1 type of materials or products are indicated, selection is Installer's option.

2.2 BASIC PIPE, TUBE AND FITTINGS

A. Provide pipe, tube, and fittings complying with Division 22 Basic Materials and Methods section "Pipe, Tube, and Fittings", in accordance with the following listing:

B. Interior Domestic Water Piping:

Tube Size 4" and Smaller:	Copper tube.
Wall Thickness:	Type "L" hard-drawn temper.
Fittings:	Wrought-copper, solder-joints.

C. Exterior Water Service Piping:

Pipe Size 3" and Smaller:	Copper tube.
Wall Thickness:	Type "K" Soft Temper
Fittings:	Wrought copper solder joint.
Pipe Size 4" and Over:	Ductile-iron pipe with cement-mortar lining, and gasketed joints.
Pipe Weight:	Schedule 150.
Fittings:	Ductile-iron, with cement-mortar lining, mechanical joint.
Pipe Size 3" and Smaller:	Polyvinyl Chloride (PVC) ASTM 1785
Wall Thickness:	Schedule 80.
Fittings:	PVC with Schedule 80, socket-type solvent joints or elastomeric gasketed joints.
Pipe Size 4" to 12":	Polyvinyl Chloride (PVC) AWWA C900
Pipe Class:	Class 150
Fittings:	Molded pressure Class 150 with AWWA C907, gaskets conforming to ASTM F-477.

2.3 BASIC PIPING SPECIALTIES

A. Provide piping specialties complying with Section 220010 Basic Materials and Methods in accordance with the following listing:

Pipe escutcheons

Dielectric unions

Drip pans

Pipe sleeves

Sleeve seals

2.4 SPECIAL PIPING SPECIALTIES

A. Water Hammer Arresters: Provide bellows or piston type water hammer arresters, pressure rated for 250 psi, tested and certified in accordance with PDI Standard WH-201.

2.5 BASIC VALVES

A. Provide valves complying with applicable Division 22 sections "Valves", in accordance with the following listing:

B. Sectional Valves:

2-1/2" and Smaller:	Ball Valves.
	Gate Valves.
3” and Larger:	Ball Valves.
	Butterfly Valves.

C. Shutoff Valves:

2-1/2" and Smaller:	Ball Valves.
	Gate Valves
3" and Larger:	Ball Valves.
	Butterfly Valves.

D. Drain Valves:

All	Hose End Threaded Gate or Ball Valves.

E. Balancing Valves:

2" and Smaller:	Ball Valves (Circuit Setter Type).
	(w/ Memory Stop)

F. Check Valves:

All Sizes:	Swing Check Valves. Horizontal Installations
	Spring Check Valves. Vertical Installations

2.6 WATER METER

A. Provide water meter and related piping conforming to applicable local Utility Company regulations and AWWA Standards.

B. Water Meter: Provided by Local Utility Company. Provide roughing- in and bypass for meter in accordance with Utility Company requirements.

2.7 SPECIAL VALVES

A. Special valves required for domestic water piping systems include the following types:

B. Hose Bibbs: Threaded end, renewable composition disc, tee handle, 3/4" NPT inlet, 3/4" hose outlet with vacuum breaker.

1. Finished Areas: Chrome plated.

2. Unfinished Areas: Bronze finish.

C. Wall Hydrants: Non-freeze, cast-bronze body, tee handle key, bronze casing, length to suit wall thickness, vacuum breaker, hinged locking cover, 3/4" inlet, hose outlet.

D. Lawn Boxes: Non-freeze, bronze ground hydrant with locking cover, rough bronze box, vacuum breaker, 1 inch connection, and suitable for 4'-0" depth of bury.

2.8 BASIC THERMOMETERS AND GAUGES

A. Provide thermometers and gauges complying with Division 22 Basic Materials and Methods Section "Meters and Gauges", in accordance with the following listing:

Pressure gauges

Glass thermometers

Pressure and temperature connections

2.9 BASIC PUMPS

A. Provide pumps as specified in applicable Section 220150 Equipment - Plumbing. Use inline pumps for hot water recirculating.

2.10 BACKFLOW PREVENTERS

A. Provide, of the type indicated on the drawing schedule, reduced pressure principal type, blackflow preventers shall consist of an assembly including shutoff valves on inlet and outlet, and strainer on inlet. Backflow preventers shall include test cocks, and pressure-differential relief valve located between two positive seating check valves. Construct in accordance with ASSE Standard.

B. On dead-end services (HVAC make-up) provide a spring-loaded check valve ahead of the backflow preventer assembly.

2.11 SYSTEMS EQUIPMENT MANUFACTURERS

A. Refer to Plumbing Fixture and Equipment Schedule for type, number, size and manufacturer of all equipment and accessories.

B. Available Manufacturers: Subject to compliance with requirements, manufacturers offering equipment which may be incorporated in the work are limited to the following:

<u>Shock Absorbers:</u>

Zurn

Josam

Wade

Watts

Smith

PPP Inc.

MIFAB

Automatic Trap Primers

PPP Inc.

Sloan

Sioux Chief

MIFAB

Hose Bibbs

Nibco

Tanner

Central Brass

Wolverine

Wall Hydrants

Nibco

Tanner

Central Brass

Wolverine

Wall Hydrants

Zurn

Josam

Wade

Watts

Smith

Woodford

MIFAB

Lawn Boxes

Zurn

Josam

Wade

Watts

Smith

Woodford

MIFAB

Backflow Preventers

Conbraco

Febco

Cla-Val

Wilkins

ITT Grinnell

Neptune

Watts

Relief Valves

Rockwell

Fisher

DeZurik

Pressure Reducing Valves

Conbraco

Jamesbury

DeZurik

Fisher

ITT Bell & Gossett

PART 3 – EXECUTION

3.1 INSTALLATION OF BASIC IDENTIFICATION

A. Install mechanical identification in accordance with Section 220010 Basic Materials and Methods.

B. Support vertical piping at floor levels using approved riser clamps. Clamp material shall be compatible with pipe material. Maximum vertical spacing shall be 10'-0". Domestic water piping shall be supported in accordance with the International Mechanical Code, Section 305 and Table 305.4 Spacing Intervals, or in accordance with MSS-SP-69. International Plumbing Code's latest edition, Section 308.5, accept as follows:

1. Copper tubing ½" to 1-1/4" nominal size, not to exceed 6 ft. horizontal intervals.
2. Copper tubing 1-1/2" and larger nominal size, not to exceed 10 ft. horizontal intervals.
3. Copper tubing ½" to 1-1/4" nominal size, not to exceed 10 ft. vertical intervals.
4. Copper tubing 1-1/2" and larger nominal size not to exceed 10 ft. vertical intervals.
5. CPVC pipe or tubing ¼" to 1" nominal size, not to exceed 3 ft. horizontal spacing.
6. CPVC pipe or tubing 1-1/4" and larger nominal size not to exceed 4 ft. horizontal spacing.
7. CPVC pipe or tubing ¼" to 1" nominal size not to exceed 10 ft. vertical.
8. CPVC pipe or tubing 1-1/4" and larger nominal size not to exceed 10 ft. vertical."

*Mid-Story Guide.

3.2 INSTALLATION OF DOMESTIC WATER SERVICE SYSTEM - BUILDING

A. Install water distribution system in accordance with Section 220010 Basic Materials and Methods, and the International Mechanical Codes Section 305, and Support Intervals under Tables 305.4 and 308.5 or in accordance with MSS-SP-69.

3.3 INSTALLATION OF DOMESTIC WATER SERVICE SYSTEM - SITE

A. Install site water service system in compliance with local governing regulations.

B. Street Main Connection: Arrange and pay for tap in water main, of size and in location indicated, by Local Water Utility Company.

C. Water Service Piping: Extend water service piping from service stop of size and in location indicated to the meter pit and from the meter pit to the water service entrance at building. Provide sleeve in foundation wall for water service entry; make entry watertight. Provide gate valve at water service entry inside building; strainer, pressure gauge, test tee with valve.

D. Ductile-Iron Pipe: Install in accordance with ANSI/AWWA C-60.

E. Sterilization: At completion of water service line installation, flush and sterilize in conformance with AWWA C-601, to satisfaction of local Authorities having jurisdiction.

3.4 INSTALLATION OF PIPING SPECIALTIES

A. Install piping specialties in accordance with Section 220010 Basic Materials and Methods.

B. Water Hammer Arresters: Install in upright position, in locations and of sizes in accordance with PDI Standard WH-201, and elsewhere as indicated.

3.5 INSTALLATION OF LAWN BOXES

A. Lawn boxes shall be provided with 18" x 18" x 6" concrete pad at grade, unless located in paving. Installation shall include 1 cu. ft. of crushed stone at the base of the hydrant, to accept drainage from weep holes.

3.6 REACTION BACKING

A. All plugs, tees and elbows in the underground piping shall be provided with reaction backing consisting of concrete placed between solid undisturbed earth and the fitting to be anchored. Concrete shall be of such bearing area as to assure adequate resistance to the thrust to be encountered. In general, backing shall be so placed that the joint will be accessible for inspection and repair.

3.7 INSTALLATION OF VALVES

A. Install valves in accordance with Division 22 Basic Materials and Methods section, "Valves".

B. Sectional Valves: Install on each branch and riser, close to main, where branch or riser serves 2 or more fixtures, equipment connections, and elsewhere as indicated.

C. Shutoff Valves: Install on inlet of each plumbing equipment item, and on inlet of each plumbing fixture, and elsewhere as indicated.

D. Drain Valves: Install on each plumbing equipment item located to completely drain equipment for service or repair. Install at base of each riser, at base of each rise or drop in piping system, and elsewhere where indicated or required to completely drain domestic water piping system.

E. Check Valves: Install on discharge side of each pump, and elsewhere as indicated.

F. Balance Cocks: Install in main recirculating loop and in each branch hot water recirculating loop. Install a ball valve and check valve at each balance valve installation.

G. Hose Bibbs: Install on exposed piping where indicated, with vacuum breaker.

3.8 INSTALLATION OF BACKFLOW PREVENTERS

A. Install backflow preventers where indicated, and where required by International Plumbing Code. Locate in same room or area as equipment being protected.

B. RPZ type backflow preventers to be piped from the relief outlet to nearest floor drain.

C. A check valve is required on the upstream side of all RPZ installations.

3.9 INSTALLATION OF PRESSURE REGULATING VALVES

A. Install pressure regulating valves where indicated. Provide inlet and outlet shutoff valves, and ball valve bypass. Provide pressure gauge on valve outlet.

3.10 INSTALLATION OF EXPANSION COMPENSATION PRODUCTS

A. This project shall require the installation of expansion compensators.

B. Furnish and install expansion compensation products in accordance with Section 220210 Basic Materials and Methods – HVAC

3.11 INSTALLATION OF THERMOMETERS AND GAUGES

A. Install thermometers and gauges in accordance with Section 220010 Basic Materials and Methods.

3.12 INSTALLATION OF WATER METER

A. Install water meter in accordance with Section 220010 Basic Materials and Methods.

B. Meter shall be supported in accordance with the requirements of the Water Department.

3.13 EQUIPMENT CONNECTIONS

A. Piping Runouts to Fixtures: Provide hot and cold water piping runouts to fixtures of sizes indicated, but in no case smaller than required by International Plumbing Code.

B. Equipment furnished by the Owner or Contractors other than this Contractor: After equipment has been set in place, this Contractor shall furnish all labor and material required to make final connections, between roughing-in and the equipment. Install valves, fittings, trim and appurtenances furnished with the equipment. All exposed piping in the kitchen areas shall be chrome plated. Piping in other areas shall be of the same material as the system to which it connects.

3.14 AUTOMATIC TRAP PRIMERS

A. Install units in accordance with manufacturer's written instructions.

B. Cap-off all unused tube connections not to be used for discharge procedures.

C. Units installed in Mechanical Room shall be surface mounted. All others shall be arranged for recessed installation and shall include a 14"x16" access door #D-1416SS.

D. All discharge tubing from the tube connectors to the floor drain connection shall be minimum Type "M" copper for above floor slab installations. Where discharge piping runs below the floor slab, the piping may be PVC grade water piping. Ensure that all connections are properly made and leak-free.

E. Verify all electrical connections prior to the start-up of the units.

F. Shield copper from direct contact with concrete, stone and sharp edges below slab.

3.15 SPARE PARTS

A. Furnish to Owner, with receipt, one valve key for each key operated hydrant, bibb, or faucet installed.

3.16 INSTALLATION OF EXTERIOR WATER PIPING (5'-0" EXTENSIONS)

A. Install exterior water service piping system in compliance with local governing regulations.

B. Main Connections: Coordinate all work with the Site Contractor. The Plumbing Contractor shall make final connections of the domestic and fire protection water services.

C. Water Service Piping: From the final connection points, extend water service piping of size and in locations indicated to the water service entrance in building. Provide ball valve at the domestic water service and a flanged connection with a ¾" blow-off valve for the fire protection water service (12" A.F.F.).

D. Ductile-Iron Pipe: Install in accordance with ANSI/AWWA C-60.

E. Test:

1. Domestic Water Service: Minimum 125 psi.
2. Fire Protection Water Service: Minimum 200 psi.
3. Combination Domestic & Fire Protection Water Service: Minimum 200 psi.

F. Sterilization: At completion of water service line installation, flush and sterilize in conformance with AWWA C-601, to satisfaction of local Authorities Having Jurisdiction.

3.17 KITCHEN DOMESTIC WATER

A. All kitchen domestic water system piping shall be roughed-in and strictly coordinated with the kitchen equipment drawings.

B. Provide all rough-in piping and final connections to equipment furnished by the Kitchen Equipment Contractor (KEC). This also includes any equipment items furnished by the KEC and are to be completely installed by the Plumbing Contractor.

C. Verify all responsibilities during the bid phase of the work.

D. All piping shall be supported off the wall with split ring clamps or uni-strut.

E. All piping shall be insulated and identified.

F. Provide shut-off valves and stainless steel flex hose connections to all individual equipment connections.

G. All exposed piping shall be chrome plated brass.

3.18 DOMESTIC HOT WATER RETURN

A. This Contractor shall install complete and operating hot water return system. The system shall be balanced and include a report as required in HVAC Specification Section 230950.

B. Balancing Valves are required in the system as hereinbefore specified. The system shall also include the installation of "air bleed" or "burp" valves to remove any trapped air in the system.

C. Where emergency showers are installed with thermostatic mixing valve, they shall require the installation of a hot water return line as detailed on the drawings.

END OF SECTION 220120

SECTION 220130

GAS PIPING SYSTEMS – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the work specified in this Section.

1.2 DESCRIPTION OF WORK

A. Refer to Section 220005 for a general description of the scope of work in this contract.

B. This Section includes:

1. Natural gas piping system as indicated on drawings and schedules, and by requirements of this section.
2. Applications for natural gas piping systems include the following:
   a. Gas service from street main to building meter by _____ Gas Division.
   b. Elevated pressure (psi) gas from meter location to rooftop gas-fired equipment.
   c. Low pressure (WC) from the meter location to all other equipment and outlets, requiring gas service.
3. Applications for propane gas piping systems include the following:
   a. All gas piping from the exterior secondary regulator assembly location to all equipment and outlets, requiring gas service.
4. Trenching and backfill required in conjunction with exterior gas distribution as specified in Section 220000 is included as work of this section. Refer to Division 1.

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this Section.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

B. Submit the following:

1. Product data on gas valves.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

PART 2 – PRODUCTS

2.1 NATURAL GAS PIPING MATERIALS AND PRODUCTS

A. Provide piping materials and factory-fabricated piping products of sizes, types, pressure ratings, and capacities as indicated. Where not indicated, provide proper selection as determined by Installer to

comply with installation requirements. Provide materials and products complying with ANSI B31.2 where applicable, base pressure rating on natural gas piping system maximum design pressures. Provide sizes and types matching piping and equipment connections; provide fittings of materials which match piping materials used in natural gas piping systems. Where more than 1 type of material or product is indicated, selection is Installer's option.

2.2 BASIC IDENTIFICATION

A. Provide identification complying with Division 22 Sections and in accordance with the following listing:

Building Distribution Piping: Plastic pipe markers.

Gas Service: Underground type plastic line markers with detectable wire.

Gas Valves: Plastic valve tags.

2.3 BASIC PIPE, TUBE AND FITTINGS

A. Provide pipe, tube and fittings complying with Section 220010 Basic Materials and Methods - Plumbing and in accordance with the following listing:

1. Interior Piping: Schedule 40 black steel ASTM A-53, A-106

   Fittings: Malleable black iron, threaded (NCC)

   Fittings: Malleable galvanized iron, threaded (WILM)

2. Exterior Below Grade Piping:_____ASTM-A-53. (Medium-density polyethylene pipe.)

   Fittings:_____.

   By reference meet the Department of Transportation Title 49 Part 192.

3. Exterior Exposed or Roof Top Piping: Schedule 40 black steel with weather coating.

   Fittings: Wrought steel, butt welded.

2.4 BASIC PIPING SPECIALTIES

A. Provide piping specialties complying with applicable Division 22 Sections and in accordance with the following listing:

Pipe escutcheons

Pipe sleeves

Sleeve seals

2.5 SPECIAL VALVES

A. Valves required for gas piping systems on this project shall be the following types:

Gas Valves: (Up to 3”)

1. Apollo 80-100 Series bronze gas ball valve. Threaded, 600 PSIG WOG, cold non-shock. 250 PSIG LP-Gas. 150 PSIG saturated steam. Vacuum service to 29 inches Hg. Federal Specification: WW-V-35C, Type: II, Composition: BZ, Style: 3.

2. Features:

   - UL Listed for LP-Gas and natural gas.

   - Large ports to reduce pressure drop

- Reinforced TFE seats and seals
- Blow-out-proof stem design
- Optional tee handle available
- Quarter turn on-off
- Adjustable packing gland
- One piece bronze body
- Chromium plated ball

3. UL Listings:

   - Guide YSDT: LP-Gas shut-off valve.
   - Guide YRPV: Gas shut-off valve for use with natural and manufactured gases.

4. This valve shall be used for all pipe sizes up to 3" in the system.

Gas Valves (4" and Larger)

1. Apollo 88A-100 Series carbon steel, ANSI Class 150 flanged standard port ball valves.

   Standards of Compliance:

   IFGC: Section 409 (Valves)

   ASME B16.5 – Pipe Fittings and Flanges

   ASME B16.33 – Manual Operated Metal Gas Valves up to 125 psig

   ASME B16.38 – Large Metal Valve Gas Distribution

   ASME B31.8 – Gas Transmission and Distribution Piping Systems

   UL 125

B. Manufacturers: Subject to compliance with requirements, provide gas valves of one of the following:

Apollo/Conbraco

Stockham

Milwaukee

NIBCO, Inc.

Watts

2.6 GAS METER

A. Provided by _____ Gas Division.

2.7 GAS PRESSURE REGULATORS

A. ANSI Z21.18, single-stage, steel-jacketed, corrosion-resistant pressure regulators. Include atmospheric vent, elevation compensator, with threaded ends conforming to ASME B1.20.1 for 2 inch NPS and smaller and flanged ends for 2-1/2" NPS and larger. Regulator pressure ratings, inlet and outlet pressures, and flow volume in cubic feet per hour of natural gas at specific gravity are as indicated.

1. Service Pressure Regulators: Inlet pressure rating not less than natural gas distribution system service pressure.

2. Line Gas Pressure Regulators: Inlet pressure rating not less than system pressure.
3. Appliance Gas Pressure Regulators: Inlet pressure rating not less than system pressure.
4. Gas Pressure Regulator Vents: Factory or field installed corrosion-resistant screen in opening when not connected to vent piping.
5. Regulators shall be as manufactured by Fisher (no equal substitute permitted).

PART 3 – EXECUTION

3.1 INSTALLATION OF BASIC IDENTIFICATION

A. Install mechanical identification in accordance with applicable Division 22 Sections.

3.2 INSTALLATION OF NATURAL GAS PIPING (INTERIOR)

A. Install natural gas distribution piping in accordance with Section 220010 Basic Materials and Methods - Plumbing and in accordance with applicable codes IFGC latest edition, and local Utility Company requirements.

B. Use sealants on metal gas piping threads which are chemically resistant to natural gas. Use sealants sparingly, and apply to only male threads of metal joints.

C. Remove cutting and threading burrs before assembling piping.

D. Do not install defective piping or fittings. Do not use pipe with threads which are chipped, stripped or damaged.

E. Plug each gas outlet, including valves, with threaded plug or cap immediately after installation and retain until continuing piping or equipment connections are completed.

F. Install drip-legs in gas piping where indicated, and where required by code or regulation.

G. Install "Tee" fitting with bottom outlet plugged or capped at bottom of pipe risers.

H. Use dielectric unions where dissimilar metals are joined together.

I. Install piping with 1" drop in 60' pipe run (0.14%) in direction of flow.

J. Install piping parallel to other piping, but maintain minimum of 12" clearance between gas piping and steam or hot water piping above 200 degrees F (93 degrees C).

K. For piping buried in building substrate, or below floor slabs, install in welded conduit, ventilated to outdoors on both ends, and tested to same requirements as gas piping.

L. Gas valves shall not be installed above ceilings without access and signage.

M. Supports:

1. All pipe, fittings, valves, installation and testing shall be in accordance with the IFGC, Chapter 4.
2. Gas piping shall be supported in accordance with the International Fuel Gas Code's latest accepted 2003 Edition, Section 407, as follows:
3. Support intervals shall be in accordance with the IFGC listed above and in Section 415, Table 415.1 as follows:
   a. Steel pipe ½" nominal size – not to exceed 6 ft.
   b. Steel pipe ¾" to 1" nominal size – not to exceed 8 ft.
   c. Steel pipe 1-1/4" and larger nominal size horizontal – not to exceed 10 ft.
   d. Steel pipe 1-1/4" and larger nominal size, vertical not to exceed every floor.

4. Support and spacing of CSST Systems shall be in accordance with CSST manufacturer's instructions.

3.3 GAS SERVICE

A. Arrange and coordinate with Utility Company to provide gas service and meter at indicated location with shutoff at terminus. Consult with Utility as to extent of its work, costs, fees and permits involved. Pay such costs and fees; obtain permits.

B. Extend service pipe from Utility's terminus to distribution piping, in compliance with Utility's requirements.

3.4 INSTALLATION OF VALVES

A. Gas valves: Provide at connection to gas train for each gas-fired equipment item; and on risers and branches where indicated.

B. Locate gas valves where easily accessible, and where protected from possible damage.

3.5 EQUIPMENT CONNECTIONS

A. Connect gas piping to each gas-fired equipment item, with drip leg, union and shutoff gas valve. Comply with equipment manufacturer's instructions. Drip legs shall not be installed on any exterior gas piping.

B. Equipment furnished by the Owner, or Contractors other than this Contractor: After equipment has been set in place, this Contractor shall furnish all labor and material required to make final connections between roughing-in and the equipment. Install valves, fittings, trim and appurtenances furnished with the equipment. Piping shall be of the same material as the system to which it connects.

C. All rooftop, gas-fired equipment shall be provided with gas pressure regulating valve to reduce gas pressure from _____ psi to _____" WC. All regulators shall be provided with relief vent discharge piping of lengths as required for minimum distance of equipment air intake grilles.

3.6 INSTALLATION OF GAS PRESSURE REGULATORS

A. This Contractor shall furnish and install gas pressure regulating valves for all shown on the drawings. Installation shall be in strict accordance with the requirements of the Utility Company and the Canadian Gas Association.

B. All regulators installed shall be tagged with data noting the inlet and outlet pressure for each individual regulator installed.

C. Medium or High Pressure (MP) (HP) Regulators shall comply with the following:

1. The MP regulator shall be approved and shall be suitable for the inlet and outlet gas pressures for the application.

2. The MP regulator shall maintain a reduced outlet pressure under lockup (no flow) conditions.

3. The capacity of the MP regulator, determined by published ratings of its manufacturer, shall be adequate to supply the appliances served.

4. The MP pressure regulator shall be provided with access. Where located indoors, the regulator shall be vented to the outdoors or shall be equipped with a leak-limiting device, in either case complying with Section 410 of the IFGC.

5. A tee fitting with one opening capped or plugged shall be installed between the MP regulator and its upstream shutoff valve. Such tee fitting shall be positioned to allow connection of a pressure-measuring instrument and to serve as a sediment trap.

6. A tee fitting with one opening capped or plugged shall be installed not less than 10 pipe diameters downstream of the MP regulator outlet. Such tee fitting shall be positioned to allow connection of a pressure-measuring instrument.

3.7 EXTERIOR GAS PIPING

A. All rooftop or exterior gas piping shall be weatherproof with and epoxy resin approved by the Gas Company.

B. Uncoated, threaded or socket welded joints shall not be used in piping in contact with soil or where internal or external service corrosion is known to occur.

C. Protective Coatings and Wrapping: Pipe protective coatings and wrappings shall be approved for the application and shall be factory applied.

OR

C. In lieu of coated steel pipe, the Contractor may use high grade material, physical and mechanical properties as classified in accordance to ASTM D 3350 and cell classification of 234373E plastic pipe and fittings for underground use only, and shall conform with ASTM D-2513. Pipe shall be marked "GAS" and "ASTM D-2513". Only Contractors registered and/or certified for installation of underground or below-grade plastic piping shall be permitted to install this material on this project.

D. Detectable underground warning tape shall read ("CAUTION – BURIED GAS LINE BELOW"). Printed on APWA approved colors, minimum 2" wide, 5 mil tape with aluminum backing for using non-ferrous locator.

OR

A. All exterior gas pipe and fittings installed, including all welded joints, shall be provided with weatherproof coatings. The coatings shall be a two-layer PE "Pritec" coating as manufactured by Liberty Coating. The coatings shall be Butyl rubber adhesive with a polyethylene topcoat.

B. Component Properties:

Adhesive

Polyethylene

ADHESIVE		
Softening Point	ASTM E28	190°F
Water Absorption	ASTM D570	<0.1%
Adhesive		Compounded Butyl Rubber

POLYETHYLENE		
Color		Black
Density	ASTM D1505	>0.950
Elongation	ASTM D638	>600%
Tensile Strength	ASTM D638	>2,800 psi
Outdoor Exposure		>2 years
Hardness, Shore D	ASTM D2240	>60

PRITEC®		
Operating Temperature		-40°F to +180°F
*Peel Strength	ASTM D1000	>20 lbs lineal
Field Bending	Arctic Service Equipment	1.9 deg. per pipe dia.
Water Absorption	ASTM D570	0.06%
Impact Resistance	ASTM G14	33.65 in/lbs (10/40 sys.)
Volume Resistivity	ASTM D257	$10x10^{16}$ Ohm cm
Dielectric Strength	ASTM D149 @73°F	700 Volts/Mil
Cathodic Disbondment	1.5v/3%/70°F/24 Hrs.	6 mm radiius

END OF SECTION 220130

SECTION 220140

FIXTURES – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the Work specified in this Section.

1.2 DESCRIPTION OF WORK

A. Refer to Section 220005 for a general description of the scope of work in this contract.

B. This Section includes:

1. Plumbing fixtures and trim work as indicated by drawings and schedules, and by requirements of this section.
2. Types of plumbing fixtures required for the project include the following:

   Water Closets

   Urinals

   Lavatories

   Countertop Sinks

   Service Sinks

   Mop Receptors

   Showers

   Electric Water Coolers

   Drinking Fountain/Cuspidor

   Sensor-Operated Flush Valves and Faucets

   Manually Operated Flush Valves

   Handicap Lavatory Insulation

   Lavatory Shield Enclosure
3. Refer to Section 220120 for domestic water piping systems used in conjunction with plumbing fixtures; not work of this section.
4. Refer to Section 220110 for soil and waste piping systems used in conjunction with plumbing fixtures; not work of this section.
5. Refer to Division 26 sections for electrical connections to water coolers and other plumbing fixtures; not work of this section.

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

B. Manufacturers: Firms regularly engaged in manufacture of plumbing fixtures of the type, style and configuration required, whose products have been in satisfactory use in similar service for not less than 3 years.

C. Plumbing Fixture Standards: Comply with applicable portions of _____Plumbing Code pertaining to materials and installation of plumbing fixtures.

D. ANSI Standards: Comply with applicable ANSI standards pertaining to plumbing fixtures and systems.

E. ANSI & ADA Standards: Comply with ANSI A171.1 Standard and the ADA Standard pertaining to plumbing fixtures and provisions for handicapped.

1. Water closets shall measure 17" to 19" from the floor to the top of the seat. Bowls shall be elongated type.

2. Flush valve mechanisms shall be on the wide side of the stall, no higher than 44" above the floor.

3. Urinals shall be elongated (14" rim from the wall) mounted no higher than 17" from the floor.

4. Lavatories shall be mounted no higher than 34" from the floor and provide knee clearance using an offset drain assembly with "P" trap set parallel to the fixture supporting wall. Trap and wall supplies shall be installed for clearance required for the installation of lavatory shield enclosures.

5. Faucets shall be lever operated, push type, touch type, electronically operated. See Fixture Schedule. All faucets shall operate on less than 5 pounds force and shall not require tight grasping, pinching or twisting of the wrist.

F. PDI Compliance: Comply with standards established by Plumbing and Drainage Institute pertaining to plumbing fixture supports.

G. Federal Standards: Comply with applicable FS WW-P-541/- Series sections pertaining to plumbing fixtures.

H. UL Labels: Provide water coolers which have been listed and labeled by Underwriters' Laboratories.

I. ARI Labels: Provide water coolers which are rated and certified in accordance with applicable Air-Conditioning and Refrigeration Institute Standards.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

B. Submit the following:

1. Product Data: Submit manufacturer's specifications for plumbing fixtures and trim, including catalog cut of each fixture type and trim item furnished, roughing-in dimensioned drawings, templates for cutting substrates, fixture carriers, and installation instructions.

2. Color Selection Data: Submit charts or samples for color selection where applicable.

3. Maintenance Data: Submit maintenance data and parts lists for each fixture type and trim item, including instructions for care of finishes. Include this data in maintenance manual.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

1.7 PRODUCT DELIVERY, STORAGE AND HANDLING

A. Deliver plumbing fixtures individually wrapped in factory-fabricated containers.

B. Handle plumbing fixtures carefully to prevent breakage, chipping and scoring the fixture finish. Do not install damaged plumbing fixtures; replace and return damaged units to equipment manufacturer.

PART 2 – PRODUCTS

2.1 PLUMBING FIXTURES

A. Provide factory-fabricated fixtures of type, style and material indicated. For each type fixture, provide fixture manufacturer's standard trim, carrier, seats, and valves as indicated by their published product information; either as designed and constructed, or as recommended by the manufacturer and as required for a complete installation. Where more than one type is indicated, selection is Installer's option; but, all fixtures of same type must be furnished by single manufacturer. Where type is not otherwise indicated, provide fixtures complying with governing regulations.

2.2 MATERIALS

A. Unless otherwise specified, comply with applicable Federal Specification WW-P-541/-Series sections pertaining to plumbing fixtures, fittings, trim, metals and finishes. Comply with the requirements of WW-P-541/-specification relative to quality of ware, glazing, enamel, composition and finish of metals, air gaps, and vacuum breakers, even though some plumbing fixtures specified in this section are not described in WW-P-541/-.

B. Provide materials which have been selected for their surface flatness and smoothness. Exposed surfaces which exhibit pitting, seam marks, roller marks, foundry sand holes, stains, decoloration, or other surface imperfections on finished units are not acceptable.

C. Where fittings, trim and accessories are exposed or semi-exposed, provide bright chrome-plated or polished stainless steel units. Provide copper or brass where not exposed.

D. Stainless Steel Sheets: ANSI/ASTM A-167, Type 302/304, hardest workable temper. Finish: No. 4, bright, directional polish on exposed surfaces.

E. Steel Sheets for Baked Enamel Finish: ANSI/ASTM A-591, coating Class C, galvanized-bonderized.

F. Steel Sheets for Porcelain Enamel Finish: ANSI/ASTM A-424, commercial quality, Type 1.

G. Vitreous China: High quality, free from fire cracks, spots, blisters, pinholes, and specks; glaze exposed surfaces, and test for crazing resistance in accordance with ANSI/ASTM C-554.

H. Fiberglass: ANSI Z124 smooth surfaced, with color selected by Architect/Engineer.

I. Aluminum: ANSI/ASTM B-209/B-221 sheet, plate and extrusions, as indicated; alloy, temper and finish as determined by manufacturer, except 0.40 mil natural anodized finish on exposed work unless another finish is indicated.

J. Synthetic Stone: High quality free from defects, glaze on exposed surfaces, stain resistant.

2.3 PLUMBING FITTINGS, TRIM AND ACCESSORIES

A. Lavatory Protective Shield Covers:

1. Fully molded enclosure “Lav Shields” as manufactured by Zurn or Truebro, Inc., complete with tamper-resistant stainless steel fasteners.

2. Shield enclosure to meet A.D.A. #4.19.4, ANSI A117.1 and BOCA P- 1203.4.

B. Water Outlets: At locations where water is supplied (by manual, automatic or remote control), provide commercial quality faucets, valves, or dispensing devices, of type and size indicated, and as required to operate as indicated. Include manual shutoff valves and connecting system pipes to permit outlet servicing without shut- down of water supply piping systems.

1. Vacuum Breakers: Provide with flush valves where required by governing regulations, including locations where water outlets are equipped for hose attachment.

C. P-traps: Include removable P-traps where drains are indicated for direct connection to drainage system. All traps shall be minimum 17 gauge.

D. Carriers: Provide cast-iron and/or steel supports for fixtures. Carriers shall be provided for all wall-hung fixtures, and/or the carrier shall be selected to support the fixture independently of the wall. Carriers shall be adjustable type, complete with all fittings and foot supports. Carrier shall be single or double, back-to-back, horizontal offset and vertical stack type. Carrier shall be selected and used as best suited within the pipe chases. Where noted or indicated, stud mount type carriers shall be used and installed within stud wall s 8” and less.

E. Fixture Bolt Caps: Provide manufacturer's standard exposed fixture bolt caps finished to match fixture finish.

F. Escutcheons: Where fixture supplies and drains penetrate walls in exposed locations, provide chrome plated sheet steel escutcheons with friction clips.

G. Aerators: Provide aerators of types approved by Health Departments having jurisdiction.

H. Comply with additional fixture requirements contained in fixture schedule attached to this section.

2.4 FIXTURE LIST

A. Refer to the "Plumbing Fixture & Equipment Schedule" as indicated on the drawings.

2.5 SHOWER – HANDICAP

A. The shower modules shall be manufactured by Crane Plumbing/Fiat Products #MSCI-307, RH/LH (36" x 35") and shall be thermoformed from continuous cast acrylic sheet into one piece, seamless units. The units shall be reinforced in the back with fiberglass reinforced polyester resin and have a backside fire rating of "A" and flame spread of 25.

B. Shower modules shall be pre-drilled and equipped with a model 180AA pressure balanced, single dial lever mixing valve with stops, hand held shower head with swivel fitting, 69" flexible stainless steel hose and in-line vacuum breaker, 10 oz. GSA approved shower curtain with curtain hoods, 2" cast brass chrome plated shower drain, and 1" diameter stainless steel curtain rod.

C. All units shall have anti-skid floor treatment to meet performance requirements of ASTM F-462-78. All units are listed under SBCCI Report No. 8556 and BOCA Report No. 86-40.

D. Additional back reinforcements shall be suitably located to provide code complying structural integrity for factory attaching of grab bars, curtain rod, and slide guide for hand held flexible hose shower head.

E. Standard Equipment:

1. Factory Installed:

a. Grab Bars: see table for individual models.

b. Curtain rod: 1" diameter, stainless steel.

c. Shower curtain, 10 oz. with curtain hooks, GSA approved.

d. 2” shower drain, chrome plated, cast brass.

e. Retractable, compact shower seat with stainless steel frame and teakwood seat.

2. Optional Equipment:

a. Model 180AA pressure balanced, single dial lever mixing valve with integral check stops.

b. Hand held shower H-11with swivel fitting, 69" flexible stainless steel hose, and in-line vacuum breaker.

c. Slide guide H-12, 24”

d. Dome light, ATP-1, 60 watt, recessed.

F. Color: Color option is required. Final selection by Architect.

2.6 SENSOR-OPERATED FLUSH VALVES & FAUCETS

A. This Contractor shall furnish and install complete and operating sensor operational faucets and flush valves where so indicated and noted. This shall include, but not be limited to, transformers and low voltage wiring.

B. Electrical power wiring shall be provided at the pipe chases and lavatory wash stations as required by the Electrical Contractor. See Electrical Plans. All wiring beyond that point shall be considered control wiring and shall be the complete responsibility of the Plumbing Contractor.

C. The Contractor shall have a complete understanding of the sensor operated equipment and system they are installing during the bid phase of the work. This includes all control wiring for the operation and function of the flush valves and faucets.

D. The Contractor shall install the system in strict conformance with the manufacturer’s written instructions. The installation shall be executed with good workmanship and to be clear of any interference with the user including the installation of lavatory protective shield enclosures.

E. All faucet installations shall require a mixing valve for single water supply to faucet.

F. All sensor wall-mounted boxes and/or panels, including setting heights, shall be strictly coordinated with the masonry contractor for both drywall and block wall installations.

G. Flush valve electrical box positioning and support kits shall be provided wherever drywall partitions are installed. The kit shall be specifically designed to accurately position and ease the installation of the electrical box and the plumbing rough-in piping and valve. The kit shall be supplied by the flush valve manufacturer and installed by the Plumbing Contractor.

H. The manufacturer’s representative shall have at least two (2) site visits to verify that equipment and wiring are properly installed.

I. The Contractor shall coordinate the location of the electrical power junction box with Electrical Contractor including the installation of the transformer unit. The Plumbing Contractor shall provide an adequate sized access panel for maintenance and servicing of the transformer and junction box. The Contractor shall locate the junction box and transformer where best suited either above the ceiling or pipe chase wall.

2.7 AVAILABLE MANUFACTURERS

A. Subject to compliance with requirements, manufacturers offering fixtures, trim and carriers which may be incorporated in the work include, and are limited to the following:

Designer Choice

Water Closets (Floor-Mounted Bottom Outlet – China)

Water Closets (Wall-Mounted Back Outlet – China)

Water Closets (Tank Type-Floor Outlet - China)

All water closets on this project shall be maximum 1.6 gallons per flush and shall be of the pressure tank (pneumatic assisted) type with the Water Control International "WCI" System ANSI A112-19-2M and ASSE Standard 1037. Manufacturers shall be limited to the following:

All water closets on this project shall be maximum 1.6 gallons per flush, and shall be of the direct-fed siphon jet action with water control international "WCI" System, ASME A112.19.2M (and 19.6M) for vitreous china fixtures.

Crane

American Standard

Kohler

China/Enameled Fixtures

Kohler

American Standard

Eljer

Crane

ToTo

Faucets/Trim (Non-Sensor Operated)

Kohler

American Standard

Delta

Moen

Elkay

Speakman

Chicago

Faucets/Trim (Sensor-Operated)

Sloan

Speakman

ToTo

Chicago

Flush Valves

Sloan "Royal" (optima Series (Sensor-Operated)

Coyne & Delany

Zurn

ToTo

Wall Supplies/Traps

McGuire

Brass-Craft

Kohler

American Standard

Sanitary-Dash

Teledyne

Wolverine

Pro-Flo

Keeny

Fixture Carriers

Zurn

Josam

Wade

Watts

Smith

MIFAB

Fixture Seats

Olsonite

Sperzel

Benke

Bemis

Church

Kohler

American Standard

Centoco

Comfort Seat

Mop Receptors

Fiat

Stern-Williams

Mustee

Florestone

Water Coolers

Elkay

Haws

Halsey-Taylor

Oasis

Acorn

Stainless Steel Sinks

Elkay

Note: All mop receptor installations must include the combination eyewash and service sink faucet arrangement.

Just

Dayton

Advanced-Tabco

Shower Assemblies & Systems

Acorn

Symmons

Leonard

Powers

Bradley

Emergency/Safety Equipment

Bradley

Haws

Western

Speakman

Guardian

Shower Units

Fiat

Fibersheen

Kohler

American Standard

Acryline

Aqua-Glass

Aquarius

Aqua-Bath

Washer Utility Boxes

Symmons

Guy-Gray

Oatey

Instantaneous Electric Water Heaters

Chronomite

Eemax

B. Cross Reference Identification:

1. If the Contractor selects a manufacturer of drainage equipment products other than as identified on the Schedule but is selected from the available manufacturers listed above, a cover sheet shall be included with the submission of shop drawings indicating the cross referenced manufacturer and model number.

2. Shop drawings shall not be reviewed or accepted if not in compliance with this requirement.

2.8 HANDICAP LAVATORY INSULATION

A. Fully molded "P" trap and angle valve insulation kit Handi-Lav Guard Truebro Model #101, 102 and 105 to suit.

B. Insulation to meet A.D.A. #4.19.4, ANSI A117.1 and BOCA P- 1203.4.

C. Self-extinguishing ASTM D635 burn characteristics, Thermal conductivity ASTM C177-K value 1.17.

PART 3 – EXECUTION

3.1 FIXTURE CONNECTIONS

A. Connections to plumbing fixtures shall be of the sizes indicated on the "Plumbing Fixture & Equipment Schedule".

B. The sizes indicated on the Schedule are for drainage and water piping serving an individual fixture; the sizes of the mains and branches shall be as indicated on the drawings.

3.2 FIXTURE SETTING HEIGHTS

A. The plumbing fixtures shall be set in accordance with the heights established by the latest edition of codes and ADA requirements.

Note: Height indicated is established as follows:

Water Closets:	From finished floor to top of seat.
Urinals:	From finished floor to rim of fixture.
Lavatories & EWC:	From finished floor to rim of fixture.
Receptor Fitting:	From finished floor to center of fitting.
Shower:	From finished floor to center of shower head.

B. Refer to Architectural drawings and sections for fixture elevations. Fixtures in various areas may be set at lower elevations. Confirm all rough-in elevations prior to any installation.

3.3 LAVATORY PROTECTIVE SHIELD ENCLOSURES

A. Installation shall conform to manufacturer’s written instructions.

B. All items involved with wall-hung lavatory installations shall be roughed-in and installed within the enclosure. This includes the offset “P” trap assembly, thermostatic mixing valve, sensor faucet trim and accessories, electrical outlet. Coordinate all work required for complete concealment of all devices.

C. Protective shield enclosures are required on the toilet room’s countertop lavatories and are furnished by the Architect. Coordinate all trim and accessories to fit within this enclosure.

3.4 INSPECTION AND PREPARATION

A. Examine roughing-in work of domestic water and waste piping systems to verify actual locations of piping connections prior to installing fixtures. Also examine floors and substrates, and conditions under which fixture work is to be accomplished. Correct any incorrect locations of piping, and other unsatisfactory conditions for installation of plumbing fixtures. Do not proceed with work until satisfactory conditions have been corrected.

B. Install plumbing fixtures of types indicated where shown and at indicated heights; in accordance with fixture manufacturer's written instructions, roughing-in drawings, and with recognized industry

practices. Ensure that plumbing fixtures comply with requirements and service intended purposes. Comply with applicable requirements of the _____ Plumbing Code pertaining to installation of plumbing fixtures.

C. Fasten plumbing fixtures securely to indicated supports or building structure; and ensure that fixtures are level and plumb. Secure plumbing supplies behind or within wall construction so as to be rigid, and not subject to pull or push movement.

3.5 CLEAN AND PROTECT

A. Fixture shall be thoroughly cleaned after completion of installation.

B. Protect installed fixtures from damage during the remainder of the construction period.

3.6 FIELD QUALITY CONTROL

A. Upon completion of installation of plumbing fixtures and after units are water pressurized, test fixtures to demonstrate capability and compliance with requirements. When possible, correct malfunctioning units at site, then retest to demonstrate compliance; otherwise, remove and replace with new units and proceed with retesting.

B. Inspect each installed unit for damage to finish. If feasible, restore and match finish to original at site; otherwise, remove fixture and replace with new unit. Feasibility and match to be judged by Architect/Engineer. Remove cracked or dented units and replace with new units.

END OF SECTION 220140

SECTION 220150

EQUIPMENT – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the Work specified in this Section.

1.2 DESCRIPTION OF WORK

A. Refer to Section 220005 for a general description of the scope of work in this contract.

B. This section includes:

1. Plumbing equipment as indicated on drawings and provisions of this section, including schedules and equipment lists associated with either drawings or this section.
2. Types of plumbing equipment required for project include the following:

   Recirculating Pumps-Domestic Water Return (110 degrees & 140 degrees)

   Instantaneous Water Heater (Gas-Fired)

   Instantaneous Water Heater (Electric)

   Packaged Domestic Water Heater

   Exterior Grease Interceptor Vault

   Solids Interceptor

   Domestic Water Heater

   Thermostatic Mixing Valve

   Covers, Grates and Frames

   Catch Basin Traps

   Duplex Sewage Pump System

   Foundation Drain System Sump Pump

   Elevator Sump Pump System

   Boiler Relief Quench Tank

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

B. UL and NEMA Compliance: Provide electric motors and electrical components required as part of plumbing equipment, which have been listed and labeled by Underwriters' Laboratories and comply with NEMA Standards.

C. NEC Compliance: Comply with National Electrical Code (ANSI/NFPA 70) as applicable to installation and electrical connections of ancillary electrical components of plumbing equipment.

D. ASME Relief Valve Stamps: Provide water heaters with safety relief valves bearing ASME valve markings.

E. AWWA Compliance: Comply with applicable American Water Works Association Standards pertaining to steel water tanks.

F. CSA and NSF Labels: Provide water tanks which have been listed and labeled by CSA International and National Sanitation Foundation.

G. ASME Code Symbol Stamps: For the following equipment, comply with ASME Boiler & Pressure Vessel Code for construction and stamp with ASME Code Symbol:

Packaged Domestic Water Heater

H. All packaged equipment shall be independently third party, labeled as a system for its intended use by a nationally recognized testing laboratory (NRTL) in accordance with OSHA Federal Regulations 29CFR 1910.303 and .349 as well as NFPA Pamphlet #70 and NEC Article 90.7.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 220000.

B. Submit the following:

1. Product data on all equipment including roughing-in data.
2. Connection diagrams for related piping and specialties.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS

PART 2 – PRODUCTS

2.1 EQUIPMENT

A. Refer to "Plumbing Fixture & Equipment Schedule" for type, numbers, size and manufacturer of all equipment accessories.

2.2 HOT WATER CIRCULATING PUMPS

A. Provide and install where indicated on the drawings, domestic hot water circulating pumps complete with controls and piping as shown on the drawings. Each pump shall have a capacity of 5 gallons per minute against a total discharge head of 17 feet.

B. Pumps shall be close coupled, centrifugal type, all low lead or lead free bronze with flexible connection to a 1/6 HP, 1750 RPM, 60 cycle, 120 volt, single phase motor.

C. Pump shall be controlled by a manual starter, furnished and installed by the Electrical Contractor. Pumps shall run continuously and be wired into night setback operations.

2.3 MASTER MIXING VALVE

A. Mixing valve shall be constructed entirely of lead free bronze and copper and hydrostatically tested to a pressure of 300 lb. Unit shall be provided with the following features.

1. A long mixing chamber with vanes at an angle to the longitudinal axis of the valve which shall cause a thorough mixing of the hot and cold water.
2. The length of the hydraulic thermostatic element shall assure effective contact with the water.

3. The thermostatic element shall be placed in the body of the valve where the hot and cold water mix. Unit shall be sensitive to any change in water temperature and make the proper correction by opening or closing the hot and cold water inlets in the valve.

4. The sensitive parts of the thermostatic element shall be inside a heavy non-ferrous tube which shall protect them from any corrosive or scaling action caused by the continuous flow of water past them.

B. Unit shall be as sized on the drawings.

C. Temperature adjusting range shall be between 80 and 160 degrees F.

2.4 DUPLEX SEWAGE PUMP SYSTEM

A. The Contractor shall provide one (1) Sewage Pump System Model DSP-75-22-8775-3660 by Penn Pump and Equipment Co., Inc., 215-997-6100, www.pennpump.com or prior approval equal.

B. The sewage pumps shall be Goulds WS-BF Series Model 3887 BF submersible type, non-clog type cast iron construction each with a capacity of 75 gpm at 22 ft., ¾ HP, 1750 rpm, 230/60/1 7.3 amp each with 3” discharge and 2” solids handing capacity. Each pump shall include quick removal system with stainless steel lifting cable.

C. The fiberglass wet well shall be 36” diameter by 60” deep. The pumping system manufacturer shall provide the fiberglass basin and anti-flotation ring (3” below the top of basin rim), vapor-tight coated steel coverplate access hatch with openings as required.

D. Pump Controls: Furnish a NEMA 1 duplex alternating control panel for remote mounting to contain:

- ATL Magnetic starters
- Circuit breakers
- Control transformer
- HOA selector switches
- Pump pilot lights
- Electronic alternator
- High level alarm light and horn
- Alarm silence and test button
- Remote alarm contacts
- Float switches with stainless steel mounting clamp.
- Remote Weatherproof alarm

E. Complete system equipment shall be furnished by Penn Pump Equipment Co., Inc., 215-997-6100 or dave@pennpump.com.

2.5 WATER HEATER

A. The water heater shall be Bradford White Model _____ with a storage capacity of not less than _____ gallons, a minimum input of _____ BtuH, and a minimum recovery of _____ GPH at 100 deg. F. It shall be design certified by the CSA International Z21.10.3 for 180 deg. F application. The tank shall be lined with Vitraglas vitreous enamel. The tank shall have one extruded magnesium anode rod. The insulation shall be foam material of 1" nominal thickness. The entire installation shall be made in accordance with state and local codes and ordinances.

B. Vacuum Relief Valve: All bottom fed water heaters and bottom fed hot water storage tanks connected to water heaters shall be installed with a vacuum relief valve. The valve shall be installed on the (cold water) fed piping above the top of the water heater and/or storage tank and per the manufacturer's requirements. Vacuum relief valves shall comply with ANSI Z21.22.

2.6 GAS-FIRED WATER HEATER

A. The domestic water heater shall be provided by a _____Model No._____. The System shall consist of an Efficiency+ EW Series Water Heater, a jacketed and insulated Lock-Temp Storage Tank and a bronze fitted circulating pump. The components shall be factory assembled as a unit with the water heater mounted on top of the tank, pre-piped, pressure tested and ready for installation. Components shall be as follows:

1. The Water Heater shall be a _____Model No. _____having an input rating of 300,000 Btu/Hr., a recovery capacity of 305 gallons per hour at a 100° rise and shall be operated on Natural Gas.

2. The water containing section shall be of a "Fin Tube" design, with straight copper tubes having extruded integral fins spaced seven (7) fins per inch. The tubes shall terminate into a one piece, lined, cast iron header. There shall be no bolts, gaskets or "O" rings in the header configuration. There shall be access to the front header of the heat exchanger for the purposes of inspection, cleaning or repair. The heat exchanger shall be mounted in a stress free jacket assembly in order to provide a "free floating design" able to withstand the effects of thermal shock. The assembled heat exchanger shall be hydrostatically tested to 240 psi water pressure. The water heater shall bear the ASME "H" stamp for 160 psi working pressure and shall be National Board listed. The complete heat exchanger assembly shall carry a five (5) year limited warranty. The heat exchanger shall be equipped with an outlet thermometer to monitor discharge water temperature.

3. The combustion chamber shall be sealed and completely enclosed with _____ ceramic fiberboard insulation. A burner/flame observation port shall be provided. The burners shall be a premix design, constructed of high temperature stainless steel and fire on a horizontal plane. The water heater shall have an integral combustion air blower to precisely control the fuel/air mixture for maximum efficiency.

4. The water heater shall be constructed with a heavy gauge galvanized steel jacket assembly. All steel jacket components must be galvanized on both sides. The exterior of the jacket assembly shall be finished in a 3-coat acrylic enamel finish. The jacket design shall allow single unit venting connection without the use of external draft hood devices.

5. The water heater shall be certified and listed by the CSA International under the latest edition of the applicable Z21.10.3 test standard. The water heater shall comply with the energy efficiency requirements of the latest edition of the ASHRAE 90.1 Standard. The water heater shall be certified and listed in Canada by The Canadian Gas Association under the latest edition of applicable CGA Standards. The water heater shall operate at a minimum of 85% thermal efficiency.

6. Standard operating controls shall include an immersion type operating aquastat and high limit control. The control panel shall have a master power switch. The ignition control shall have four LED lights to indicate sequential operation and diagnostics on control sensed malfunctions. The control panel shall have a terminal strip for easy field connection of remote temperature controls and field installed safety controls.

7. The standard control system shall include a hot surface ignition system with full flame monitoring capability. The main combination gas valve shall have redundant valve seats and a built-in low gas pressure regulator as standard. The gas pressure regulator portion of the main gas valve shall

be referenced to the combustion air fan. Additional standard controls shall include a combination low air and blocked flue pressure switch to monitor fan operation, low voltage transformer for the control circuit and an ASME temperature and pressure relief valve. The manufacturer shall verify proper operation of the burners, all controls and the heat exchanger by connection to water and venting for a factory fire test prior to shipping. A quality test report shall be shipped with each unit.

8. A 24 Vac control circuit and components shall be used. All components shall be easily accessed and serviceable from the front of the jacket. Access to the controls shall be provided by a quick access, quarter turn knob on the control panel cover.

9. The water heater shall be installed and vented with a direct vent system with a vertical roof air intake and exhaust vent. The flue shall be an AL29-4C sealed vent material and accessories terminating at the rooftop with the manufacturer'' specified vent cap. A separate pipe shall supply combustion air directly to the heater from the outside. The air inlet pipe may be PVC, CPVC, ABS or sealed type "B" or galvanized vent pipe. The air inlet shall terminate on the rooftop with the manufacturer's specified air inlet cap assembly.

10. The water heater shall be certified for low emissions of Oxides of Nitrogen (NOX).

11. The water heater shall be mounted on top of the storage tank, pre-piped to the tank with copper pipe and equipped with a factory installed 1/6 HP circulating pump to ensure scale-free heater performance. The pump shall be bronze-fitted and provided for operation on 120 volt, 60 cycle, 1 phase power supply. The assembled heater shall have a 2" copper cold water inlet connection and a 1 ½" copper outlet connection. The water heater will have a 150 psi pressure only relief valve and the storage tank will have a 150 psi temperature and pressure relief valve. All relief valves are sized per ASME requirements and factory installed.

12. The storage tank shall be a vertical _____tank having a storage capacity of 100 gallons. The tank shall be constructed with a baffled inlet, designed to receive all circulation from the water heater and eliminate turbulence in the tank. The baffled tank shall supply 80% of tank capacity without a drop in outlet temperature, regardless of rate of draw.

13. The storage tank shall be constructed in accordance with standard construction requirements. The tank shall be designed to withstand a hydrostatic test pressure of two times the working pressure without leakage. The storage tank shall be independently tested and certified by a nationally recognized test agency and shall have a working pressure of 150 psi. The tank shall be furnished with the following connections, two circulating connections pre-piped to the water heater, one (1) ½" copper hot water outlet, one (1) relief valve connection, one (1) ¾" NPT aquastat opening and one (1) ¾" NPT drain connection. The tank shall be furnished with a handhole for ease of inspection, clean out and service. The interior of the storage tank shall be glass lined and fired to 1600°F to ensure a molecular fusing of glass and steel, furnished with a magnesium anode and carry a five (5) year limited warranty.

14. The Lock-Temp storage tank shall be furnished with a factory installed, heavy gauge steel jacket finished with three coats of acrylic enamel. The storage tank shall be completely encased in a minimum of 2" thick, high density polyurethane R-16 foam insulation to meet the energy efficiency requirements of the latest edition of the ASHRAE 90.1 Standard.

15. The firing control system shall be F-9 electronic control with hot surface ignition. Prefix "F" denotes water heater standard on-off firing.

B. Field Services: Contractor shall provide the services of the local factory authorized representative to supervise all phases of equipment startup. A letter of compliance with all factory recommendations and installation instructions shall be submitted to the Engineer with operation and maintenance

instructions.

2.7 INSTANTANEOUS GAS-FIRED WATER HEATER

A. The water heaters shall be a Rannai or Bradford White Mode IGI-180-5X with a gas input of 15,000 – 180,000 BtuH and a flow rate of 3.87 GPM at 77°F temperature rise. It shall be design certified by CSA International (formerly AGA/CGA). The heater shall have a flame rod sensor to indicate flame failure, boiler protection, 203°F lockout thermistor and combustion fan rpm check. The entire installation shall be in compliance with State and local codes and ordinances.

B. Features:

- Continuous flow operation.
- Heat exchanger.
- Direct electronic ignition.
- Low noise level – 49 dB.
- Fully automatic controls.
- Diagnostic controls.
- Lime accumulation sensor
- Venting (interior model – vented horizontally)
- Five Year (5 yr.) limited warranty on heat exchanger.
- Five Year (5 yr.) limited warranty on parts.

C. Expansion Tank: Expansion tank shall be included as part of the water heater package by the unit equipment supplier.

D. Air Intake/Exhaust Vents: Air intake/exhaust venting, including terminus grilles, shall be included as part of the water heater packaging by the equipment supplier.

2.8 FOUNDATION DRAIN PUMP SYSTEM

A. The Contractor shall provide one (1) Effluent Pump System Model EPS-50-20-8550-2448 by Penn Pump and Equipment Co., Inc., 215-997-6100, www-pennpump.com or prior approved equal.

B. The Effluent pump shall be Series 3885 cast iron construction with a capacity of 50 gpm at 20 ft., ½ HP, 115-230/60/1 with a ¾” solids handling capacity with pump plug and plug-in type on-off float switch float switch and high level alarm panel with remote alarm contacts.

C. The sump pump shall be fiberglass size 24” diameter by 48” deep with a ¼” steel epoxy coated simplex steel cover. The cover to be modified with 3/8” spacers to elevate the cover from the basin rim for area drainage if required.

D. Pump Alarm:

- UL listed and CSA Certified.
- Voltage: 120 VAC, 50/60 Hz, 8.5 watts maximum (alarm condition).
- Enclosure meets Type 3R watertight standards, listed for indoor or outdoor use under UL Standard 864. Dimensions are 6.5”x4.5”x3.0”.
- Premounted terminal block so enclosure can also be used as a junction box for splicing pump, pump switch and pump power. Meets NEC Standard for junction boxes.
- N.O. float switch has a 15’ long, 18 gauge, 2 conductor SJOW (UL) cord.

- Mechanical SignalMaster® Float on TAN3M, switches are rated for a maximum fluid temperature of 140ºF (60ºC).
- Automatic alarm reset, alarm test switch and horn silence switch.
- Alarm Horn: 85 decibels at 10 feet (3 meters)
- Shall not control or interface with pump.
- Operates if pump circuit fails when wired on separate circuit.
- Provide weatherproof remote alarm.

E. The complete system equipment shall be furnished by Penn Pump Equipment Co., Inc., 215-997-6100 or dave@pennpump.com.

2.9 BOILER RELIEF HOT WATER PUMP WITH TANK

A. Hot water tank shall be polypropylene roto-molded cylindrical open-top with rigid flange, suitable for 180°F water with a maximum temperature limit of 200°F as manufactured by Plastico or equivalent.

B. Hot water pump shall be of cast iron construction, heavy duty application. Stainless steel shaft, screen and float. Motor shall be fitted with automatic switch and 8 ft. cord, SSPMA certified and UL listed. Motor shall be 115V, single phase, TEFC. Pump shall be capable of 20 GPM @ 15 ft. TDH.

C. Manufacturers: OTS Model 523A-98 Curb B: See Manufacturers listed at end of this section.

2.10 COVERS, GRATES AND FRAMES

A. Each manhole and catch basin shall be fitted with a cast iron cover or grate and frame of the dimensions and weight shown on the drawings. The material used in the manufacture of the casings shall conform to ASTM Designation A-48, as last amended, class 30 iron. The castings shall be free from imperfection and thoroughly cleaned with covers or grates and frames straight and true to pattern. The cover or grate must have a continuous and even bearing on the frame and shall be properly set to avoid rocking. All inequalities, projections, or roughness on abutting surfaces of the castings must be removed and the cover or grate fitted into the frame as neatly as possible without jamming.

B. Prior to setting the frames, grates and covers on manholes or catch basins, this Contractor shall verify final finish grade adjacent to each structure and make the necessary adjustments to locate the cover or grate level and flush with finished grade.

2.11 INSTALLATION OF CATCH BASIN TRAPS

A. Install catch basin traps, hooks and plates in each catch basin, at locations indicated.

B. Traps and plates shall be located in the basin at the elevation required to satisfy the City of _____ standards.

2.12 EXTERIOR GREASE INTERCEPTOR

A. Interceptor shall be constructed of precast, reinforced concrete in accordance with the Local Plumbing Code requirements. Interceptor shall include inlet, outlet and vent piping, baffles and manhole frames and covers. All piping shall be PVC soil pipe and fittings, and manhole frames and covers shall be rated for _____ duty.

2.13 SOLIDS INTERCEPTOR

A. Solids interceptor shall be cast iron, porcelain enameled inside and outside with lumaloy sediment bucket and removable bronze screens and lumaloy gasketed cover with locking device.

2.14 MANUFACTURERS

A. Subject to compliance with requirements, manufacturers offering plumbing equipment shall be limited to the following:

1. Domestic Water Heaters

   PVI

   Weben-Jarco

   Ace-Buehler

2. Domestic Water Heaters

   Ruud

   Bradford-White

   State

3. Hot Water Circulating Pumps

   Armstrong

   Bell and Gossett

   Taco

   Aurora

   Grundfos

   Amtrol

4. Solids Interceptors

   Zurn

   Josam

   Wade

   Ancon

   Smith

5. Exterior Interceptor Vaults (Precast)

   Tyson F. Sartin

   A.C. Miller

   Penn Cast

6. Instantaneous Water Heater (Electric)

   Chronomite

7. Instantaneous Water Heater (Gas-Fired)

   Rannai

   Bradford-White

   Navrin

8. Master Mixing Valve (Domestic Hot Water System)

   Holby Valve Co.

9. Self-Powered Water Conditioner

   Ecotec (no equal)

10. Electronic Monitored Grease Trap

    J. R. Smith

11. Automatic Trap Primer

    PPP, Inc.

12. Boiler Relief Hot Water Pump

    Oats

    Hydromatic

    Zoeller

13. Foundation Drain Sump Pump

    Penn Pump Equipment Co., Inc.

14. Hot Water Circulating Pumps

    Taco

2.15 ELEVATOR SUMP PUMP SYSTEM

A. The sump pump system shall be furnished with all components for a complete and operating system. The system shall be an "Oil Smart Water Pump System" and shall pump water only and shall shut down on detection of hydrocarbons.

B. The pump switch shall be rated for an industrial 120 VAC, 6 amp switch. The switch shall be SEE WATER, Inc. Oil Smart Water Pump Switch. The sensor shall be an integral part of the pump assembly. The sensor shall be a totally solid state device in a watertight enclosure. The sensor shall be capable of differentiating between oil and water. The switch shall comply with State and Federal Regulations.

C. System Equipment:

1. The complete system shall include a 1/3 HP automatic submersible sump pump, 120 volt, 1-1/4" discharge.

2. Oil Smart Pump Switch, 120 volt, 6 AMP with ignition protection, UL Marine Listed, watertight, 24" long UL listed flexible cord with recognized adhesive filled heat shrink wire connectors.

3. Pump gate valve and check valve.

4. High water alarm panel "Weil" #8341k1013 complete with 8233 float switch, audible and visual alarm, test switch, silence switch, terminal strip, flashing red dome light.

E. Complete system shall be furnished by Basse Co., P.O. Box 2518, Warminster, Pennsylvania 18974-0052, (215) 364-8855.

F. Operation: Sensing shall be accomplished by measuring the dielectric constant of the medium at the sensor. To prevent cycling the pump <u>off</u> and <u>on</u>, the sensor shall have two sensing points: one to control the water level for pump turn <u>on</u> and the other to control the point to turn the pump <u>off</u>. Separation of the two (2) points shall be controlled by two independent sensors that shall connect to a

logic circuit which shall work as follows:

1. When the water level reaches the top sensor, the "Oil Smart Water Pump Switch" will turn on pump until the lower sensor is uncovered.
2. The "Oil Smart Water Pump Switch" will turn off and stay off until the top sensor is again covered with water.

OR

2.15 ELEVATOR SUMP PUMP (COMPLIES W/DE STATE ELEVATOR CODE)

A. Provide pump and control systems capable of pumping water while containing oil. The system shall function automatically and shall provide for an alarm and separate LED lights in the event of (a) the presence of oil in the sump, (b) high liquid in the sump, or (c) high amps or a locked rotor condition. In addition, LED lights shall be provided for (1) power and (2) pump run function. An alarm that sounds only in the event of a high liquid condition or does not separately identify the above five functions shall not be acceptable.

B. The pump shall be a submersible type, capable of pumping up to 37' TDH and 74 GPM. The pump shall be approved to UL 778 standards and shall include thermal and overload protection. The motor shall be rated 1/2 H.P., 1 phase, 115V and capable of operating continuously or intermittently. The motor housing shall be constructed of #304 stainless steel and mechanical seats shall be housed in a separate oil-filled compartment.

C. The main control shall be approved to UL 508 standards and housed in a gasketed NEMA 4X enclosure with a see-through window for observation of operating functions. The control unit, junction box, pump, floats and sensor shall be factory assembled as a complete, ready-to-use system and shall be tested and approved as a complete system by a nationally recognized testing laboratory such as ENTELA. The control panel shall be equipped with dual solid state Oil-Minder relays with variable sensitivity settings, an over current relay, self-cleaning stainless steel sensor probe, high decibel warning horn with alarm silencing switch, dual floats, clearly marked cable terminal board and remote monitoring contact. A NEMA 4X (sump pit) junction box with rigid conduit shall be provided. (Note: The control panel and the NEMA 4X (sump pit) junction box shall not be provided with 8-pin twist lock receptacles. All pump power and control cables between the control panel and NEMA 4x junction box shall be by the E.C. and shall have their length determined in the field. The cables between the control panel and junction box shall be connected directly to the equipment terminal boards and shall be run in ridge, galvanized conduit.) See installation detail on Plumbing Drawings. All cables between the pump and junction box shall be 16 ft. long and the power cable and plug from the control panel shall be 6 ft. long. The system shall allow for the main control to be located outside of the elevator hoistway and monitoring of all functions without having to enter the elevator shaft.

(Note To Engineer: This spec section has been developed around the Stancor OM-50 submersible pump and Oil-Minder Multi-Option Control Panel. The pump shall be listed a Stancor Model OM50-DEL/ELV/115 in the fixture schedule)

PART 3 – EXECUTION

3.1 INSTALLATION OF WATER HEATERS

A. Install water heaters where indicated in accordance with manufacturer's installation instructions and in compliance with applicable codes.

B. Set units where indicated, orient so controls and devices needing service and maintenance have adequate access. Level and plumb units. Each unit shall be set on a concrete housekeeping pad.

C. Existing Mechanical Room: Reconnect existing gas hot and cold piping to new unit. Alter piping to suit new connections. Connect recirculating line to unit with check valve and shutoff valve. Extend

relief valve discharge to nearest floor drain. Extend and connect new flue exhaust to existing breeching.

D. New Mechanical Room: Connect gas, hot and cold and recirculating piping system and all associated equipment and devices as detailed on the drawing. Flue extension, roof penetration and weatherproof hood shall be by this Contractor.

E. Start-up, test and adjust hot water heaters in accordance with manufacturer's start-up instructions. Check and calibrate controls.

3.2 INSTALLATION OF GAS-FIRED AND INSTANTANEOUS GAS-FIRED WATER HEATER

A. Furnish and install a complete and operating system. Install water heaters where indicated in accordance with manufacturer’s installation instructions and in compliance with applicable codes. Provide all control wiring for proper operation of the unit.

B. Set unit where indicated, orient so controls and devices needing service and maintenance have adequate access. Level and plumb unit.

C. The unit shall be set on a concrete pad or wall hung for instantaneous type.

D. Start-up, test and adjust hot water heaters in accordance with manufacturer’s start-up instructions. Check and calibrate controls. Start-up shall include the services of the manufacturer’s representative.

E. Combination exhaust vent and air intake shall be included as part of the heater package and extended through the exterior wall and terminate with a grille furnished by the unit manufacturer.

F. Install piping and valving as indicated on piping diagram.

3.3 INSTALLATION OF THERMOSTATIC MIXING VALVE

A. Install mixing valve in accordance with manufacturer's installation instructions and in compliance with applicable codes.

B. At startup of domestic hot water system, mixing valve outlet temperature shall be checked to insure proper setting and operation. Following adjustments, if required, the mixing valve, if not performing. check if factory required differential temperature in/out with a minimum of 20º Delta “T” is maintained.

C. Provide minimum 27" (end of pipe to end of pipe) heat trap in accordance with manufacturer's recommendations and as detailed on the drawing.

D. The temperature of the water delivered by the mixing valve shall be changed by turning the adjusting screw to the right or clockwise for lower temperature; and to the left or counter clockwise for higher temperatures. Maintain a uniform temperature regardless of temperature of incoming water. To facilitate adjustment, a thermometer shall be placed in the line beyond the Holby Tempering Valve as shown in the diagram and water shall be flowing through the Holby Tempering Valve while adjustment is being made.

E. Check valves shall be installed on both inlet (hot and cold) to the unit. Include a full-size bypass valve arrangement.

F. The hot water return line shall always be piped through the cold-water make-up side of the mixing valve.

3.4 INSTALLATION OF DUPLEX SEWAGE PUMP SYSTEM

A. The duplex pump system supplier shall provide all of the system equipment and components to ensure proper sewage pump performance.

B. The contractor shall furnish and install all system equipment for a complete and operating installation. The equipment shall be installed in accordance with manufacturer's/supplier's written instructions.

C. The duplex shall be installed Mechanical/Electrical Room #008.

D. The pump supplier shall include one (1) day of field start-up service, and one (1) day of Owner instruction with copies of all start-up and tests.

E. Provide a shut-off valve and check valve in each pump discharge line.

F. Install weatherproof remote alarm where indicate on the drawings.

G. Install the sewage pump system as detailed on the drawings.

H. Electrical Contractor shall provide all power wiring to the control panel and to each pump. All wiring beyond that point shall be condensed power wiring and shall be the complete responsibility of the pump installation contractor. All wiring shall be in conduit and comply with the NEC.

3.5 INSTALLATION OF FOUNDATION DRAIN SYSTEM PUMP

A. The pump system supplier shall provide all the system equipment and components to ensure proper sump pump performance.

B. The Contractor shall furnish and install all system equipment for a complete and operating installation. The equipment shall be installed in accordance with the manufacturer's/supplier's written instructions.

C. The pump shall be installed within the Mechanical/Electrical Room #002 pump basin. The pump basin shall be a fiberglass basin, 24"x48" deep with a ¼" steel epoxy coated cover. The cover shall be modified with 3/8" spacers to elevate the cover from the basin rim for room/area drainage.

D. Provide a shut-off valve and check valve in the pump discharge.

E. Provide a 12" thick concrete block at the base of the pit for setting of the pump. The block is to be provided to keep the pump off the bottom so that silt and other infiltration collection debris will not clog or interfere with the pump's operation.

F. Electrical plug-in power wiring shall be provided at the pump by the Electrical Contractor. All wiring beyond that point shall be considered control wiring and shall be the responsibility of the pump installation contractor, including the remote alarm. All wiring shall be in conduit and comply with the NEC.

G. Installation of weatherproof remote alarm shall be the responsibility of this Contractor including the signal wiring for the alarm operation.

3.6 INSTALLATION OF HOT WATER CIRCULATING PUMPS

A. Install pumps where indicated, in accordance with manufacturer's published installation instructions, with recommended clearances provided for service and maintenance.

B. Install in-line pumps, supported from piping system, located for access to oil cups, service, and maintenance.

C. Lubricate pumps before start-up. Start-up shall be in accordance with manufacturer's instructions.

D. Install pump unit as detailed on the drawing. Include a check valve and thermometer at the pump unit. The pump shall run on continuous operation. The pump shall be wired into night setback by the ATC system installer.

3.7 INSTALLATION OF EXTERIOR GREASE INTERCEPTOR

A. Install precast interceptor in accordance with manufacturer's installation instructions and in compliance with applicable codes.

B. Interceptor shall be set level on a base bed of crushed stone. Inlet, outlet and piping shall be adjusted, as required, to insure proper elevations with respect to inlet and outlet.

C. Provide all excavation and backfill as required to install the unit.

D. Install increment rings or extensions for access to finished grade. Install and set manhole frames and covers true and level flush with finished grade.

E. Install vent piping and extend up through building to 18" above roof level. The vents shall be a minimum of 4" in size and shall be connected to the vault chamber and also in the drain line prior to the inlet connection. No other system vents shall connect to the grease interceptor vent system.

3.8 SELF-POWERED WATER CONDITIONER

A. The unit shall be installed in the cold water make-up as indicated on the drawing diagram to serve the kitchen equipment steamer.

B. The unit shall include an "Autoflo Type HC" valve on the inlet side and an "Autoflow Type AC" on the outlet side. These valve assemblies shall be included with the Ecotec unit as furnished by the equipment supplier

C. The unit shall be installed in strict conformance with the manufacturer's written instructions and shall be accessible for maintenance.

D. The unit is available through Ecotec – Larry Mitchell – Vineland, NJ 08361 (856-205-9283).

E. One (1) unit is required for installation.

3.9 AUTOMATIC TRAP PRIMER

A. The automatic trap primer units specified shall be recessed mounted and in the location indicated.

B. Installation shall conform to manufacturer's written instructions. The Electrical Contractor shall provide 120 volt electrical power and final connection.

C. The unit installation shall include a discharge line to each floor drain (F-8, F-9 and F-10) indicated and/or noted on the drawings. Any unused discharge line off the unit's discharge manifold shall be capped off within the panel.

D. All discharge lines shall be minimum "M" copper tube or flexible polyethylene tubing. All tubing shall be protected during below floor slab construction.

E. The unit shall be factory tested, assembled and prepiped and shall include a ¾" ball valve, shock absorber, vacuum breaker, copper distribution manifold, solenoid valve.

3.10 INSTALLATION OF ELEVATOR SUMP PUMP SYSTEM

A. Furnish and install all system equipment for a complete and operating installation. The equipment shall be installed as detailed on the drawing and in accordance with manufacturer's and equipment supplier's written instructions.

B. The pump and switch shall be installed within the elevator pit sump cavity. Install gate valve and check valve in pump discharge. Provide a cover grate atop the sump pit opening.

C. The installation shall include a high water alarm system and panel. Install floats within the sump pit. The alarm panel shall be a remote installation in the Elevator Machine Room where indicated on the drawing.

D. Electrical power wiring shall be provided to the panel by the Electrical Contractor, including control wiring and conduit to junction box in the sump pit. All wiring beyond that point shall be considered control wiring and shall be the responsibility of the pump installation contractor. Coordinate with the

Electrical Contractor for all electrical connections required. All work responsibilities shall be verified and executed for a complete operating and functional installation. Refer to drawing detail/diagram.

E. The Electrical Contractor shall provide a dedicated receptacle at the pump unit for system operation.

F. All pump equipment, piping, etc., shall be kept clear of all elevator cab operations and shall meet the approval of the elevator inspector.

3.11 INSTALLATION OF BOILER RELIEF HOT WATER TANK WITH PUMP (QUENCH TANK)

A. Provide installation of unit tank with separate pump as shown on drawings.

B. Unit installation shall include all piping, fittings, adapters, supports and all necessary material for complete installation from the boiler relief valves to the hot water storage tank, and from pump to drain.

C. Electrical power for pump shall be provided by the Electrical Contractor to a receptacle mounted on the column at the pump/tank location.

D. Float level shall be field set.

E. Pump shall be installed inside the tank. Provide brace for pump as needed.

F. Pipe pump discharge to the nearest drain as shown on the drawings. Provide funnel for attaching to drain grating.

END OF SECTION 220150

SECTION 220190

TESTING – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other conditions, if any) and Division 1 as appropriate, apply to the work specified in this Section.

1.2 DESCRIPTION OF WORK

A. Refer to Section 220005 for a general description of the scope of work in this contract.

B. Extent of plumbing systems to be tested is indicated on the drawings and by requirements of this section.

C. Applications of tests include the following:

1. Interior Piping
   a. Domestic cold, hot & hot water return piping
   b. Gas piping
   c. Sanitary and condensate waste drainage piping
   d. Storm water drainage piping
   e. Compressed air piping
2. Exterior Piping
   a. Sanitary drainage piping
   b. Domestic water service
   c. Gas service
   d. Storm drainage piping

D. See Fire Protection Specifications for testing of Fire Protection Systems.

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

1.5 SUBMITTALS

A. Submit test reports in accordance with Section 220000.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

PART 2 – PRODUCTS

2.1 PIPE & FITTING REPLACEMENTS

A. Refer to Section 220010 for replacement of any defective pipe or fittings. Replacement shall include

all required uncovering, excavating, recovering and backfilling.

PART 3 – EXECUTION

3.1 GENERAL

A. All exterior or interior piping shall be tested and approved before backfilling or concealing. Failure to secure the approval of the Municipal Inspector, Utility Company's Inspector or the Inspector of the Architect/Engineer makes it mandatory for the Contractor to completely expose the piping for testing. All expense involved in the uncovering of the piping for the test and recovering shall be borne by the respective Contractor with no change in Contract.

B. All equipment, material and labor required for testing a plumbing system or part thereof shall be furnished by the Plumbing Contractor responsible for installing the work.

3.2 INTERIOR PIPING

A. Drainage Piping:

Rough Plumbing: The piping of all plumbing storm, condensate waste, sanitary drainage and venting systems shall be tested upon completion of the rough piping installation by water or air and proved watertight. Where required by the code official, the cleanout plugs shall be removed to ascertain if the pressure has reached all parts of the system. Either of the following methods shall be used:

1. Water Test: The water test shall be applied to the drainage system either in its entirety or in sections after rough piping has been installed. If applied to the entire system, all openings in the piping shall be closed, except the highest opening, and the system filled with water to the point of overflow. If the system is tested in sections, each opening shall be plugged except the highest opening of the section under test, and each section shall be filled with water, but a section shall not be tested with less than a 10-foot head of water.

   In testing successive sections, at least the upper 10 feet of the next preceding section shall be tested, so that a joint or pipe in the building (except the uppermost 10 feet of the system) shall not have been subjected to a test of less than a 10-foot head of water. The water shall be kept in the system or in the portion under test for a minimum of 15 minutes before inspection starts. The system shall then be tight at all points.

2. Air Test: The air test shall be made by attaching an air compressor testing apparatus to an opening, and, after closing all other inlets and outlets to the system, forcing air into the system until there is a gauge pressure of 5 pounds per square inch (5 psi) or a minimum of 10-inch column of mercury. This pressure shall be held without introduction of additional air for a minimum period of 15 minutes.

   Precautionary Note: The compressibility of air and/or other gases result in tremendous amounts of stored energy, even at lower pressures. Over-pressurizing creates a substantial hazard to personnel and property near the area should a failure occur. Consult with the Plastic Pipe Institute (PPI) for statements and alerts, along with State and local safety offices.

Finished Plumbing: Where required by the code official, after the plumbing fixtures have been set and their traps filled with water, their connections shall be tested and proved gas and water-tight by one of the following test methods.

1. The final test for gas and water-tightness of the completed drainage and vent systems shall be made by a smoke test or other approved method. The test shall be made by filling all traps with water, and then introducing into the system smoke produced by one or more smoke machines. When the smoke appears at stack openings on the roof, the stack openings shall be closed and a pressure equivalent to a 1" water column shall be built and maintained for the period of the inspection.

2. After the plumbing fixtures have been set and their traps filled with water, their connections shall be tested and proven gas and water-tight by plugging the stack openings on the roof and building drain where the drain leaves the building and with air introduced into the system equal to the pressure of a 1-inch water column. This shall be accomplished by the use of a "U" tube or manometer inserted in the trap of a water closet. Such pressure shall remain constant for the period of inspection without the introduction of additional air.

Building sewer test: The building sewer shall be tested by insertion of a test plug at the point of connection with the public sewer or individual sewage disposal system. The building sewer shall then be filled with water under a head of not less than 10 feet. The water level at the top of the test head of water shall not drop for at least 15 minutes.

B. Domestic Water Piping: All new, altered, extended or replaced interior water piping installed shall be tested at 100 psig maintaining the pressure for four hours with not more than 1% drop in pressure. The system shall be filled with water which shall remain in the system until the water and the piping are the same temperature. If water pipe testing is under the jurisdiction of the local inspector, his requirements shall be used; however, they shall be not less than specified herein. The tests shall be performed in the presence of the representative of the Architect/Engineer and to his satisfaction.

C. Natural Gas Piping:

1. All new, altered, extended or replaced interior natural gas piping installed shall be tested in accordance with the requirements of the National Fire Protection Association, latest edition of the IFGC, Section 107, and the requirements of the local Utility Company as applicable. In the absence of a specific test required by the Authorities, or if such requirements are less stringent than the test hereinafter specified, then the interior gas piping shall be tested as follows in the presence of the representative of the Architect.

2. Before appliances are connected, piping shall be filled with air or nitrogen, to a pressure of 10 psi and proved tight with no drop in pressure for the length of time required to inspect the joints, but in no case less than 30 minutes. The source of pressure shall be isolated before the pressure tests are performed. Pressure shall be measured with a mercury manometer, or slope gauge or equivalent device so calibrated as to be read in increments of not greater than one-tenth pound. All piping which will be concealed shall be tested, prior to being closed in by construction.

D. Compressed Air Piping: Compressed air piping shall be tested at 125 psi. The pressure shall be maintained on the system a minimum of 30 minutes without any loss in pressure. If a loss in pressure occurs, leakage shall be corrected and piping retested.

3.3 EXTERIOR PIPING

A. Sanitary & Storm Water Drainage Piping:

1. All new exterior sanitary and storm water drainage installed shall be tested in a manner and in a sequence best suited to project. The test shall be performed in the presence of the Inspector of the Municipality under whose jurisdiction the installation is made and shall conform to his requirements.

2. In the absence of a specific code test, the Contractor shall perform the following testing in the presence of the representatives of the Architect.

3. Before any section of sanitary and storm water drainage has been backfilled more than 6 inches above the top of the pipes, exclusive of the joint area, the system shall be tested. Wherever possible, the section of the system shall be tested from manhole to manhole. The lower end of each section to be tested shall be plugged with a suitable device manufactured for this purpose. The section being tested shall be filled with water and the leakage observed and gauged.

4. For the gravity sanitary drainage piping to be acceptable, the water leakage after filling shall not exceed 2 gallons per 24 hours per lineal foot of pipe joints with all joints under a constant pressure of not less than 0.1 pound.

5. For the storm water to be acceptable, the water leakage after filling shall not exceed 3 gallons per 24 hours per lineal foot of pipe joints with all joints under a constant pressure of not less than 0.1 pound.

B. Domestic Water Service: All new exterior water service piping installed shall be tested and proved tight. In the absence of specific requirements or requirements less stringent than those specified herein, this contractor shall test the piping at a minimum pressure of 125 psig maintaining the pressure for two hours without more than 2% drop in pressure. The system shall be filled with water which shall remain in the system until the water and piping are the same temperature.

OR

B. Water Service: All new exterior water service piping installed shall be tested and proved tight. In the absence of specific requirements or requirements less stringent than those specified herein, this contractor shall test the domestic water service piping at a minimum pressure of 125 psig maintaining the pressure for two hours without more than 2% drop in pressure. The 6" water service from the wet tap to the 6" sprinkler service entry location shall be tested in accordance with the NFPA requirements of at least 200 psi. The systems shall be filled with water which shall remain in the system until the water and piping are the same temperature.

C. Gas Service:

1. All new exterior distribution piping, installed by this Contractor, for natural gas systems shall be tested in accordance with the requirements of the National Fire Protection Association, latest edition of the IFGC, Section 107, and the requirements of the local Utility Company. In the absence of a specific test required by the Authorities, or if such requirements are less stringent than the test hereinafter specified, then the exterior piping shall be tested as follows, before pressure regulating valves are installed, or connection made to interior piping.

2. Piping shall be filled with air or nitrogen, to a pressure of 100 psi, and proved tight with no drop in pressure for the length of time required to inspect the joints, but in no case less than one hour. The source of pressure shall be isolated before the pressure tests are performed. Pressure shall be measured with a gauge so calibrated as to be read in increments of not greater than one pound.

3.4 STERILIZATION

A. After final testing for leaks, all new potable water piping installed including water service piping, shall be flushed to remove foreign material.

B. Before placing domestic water systems in service, a qualified service organization shall be engaged, to sterilize the entire building including the exterior water service piping in accordance with the following procedure:

1. Contractor shall provide a 3/4" hose connection somewhere in the main entering the building, or in the Mechanical Room and/or in the meter pit, pump in sufficient sodium hypochlorite to produce a free available chlorine residual of not less than 100 PPM.

2. Proceed upstream from the point of chlorine application opening all faucets and taps until chlorine is detected. Close faucets and taps when chlorine is evident. Consult with the local code department for additional concentrations and durations.

3. When chlorinated water has been brought to every faucet and tap with a minimum concentration of 200 PPM chlorine, retain this water in the system for at least three hours.

4. At the end of the retention period, no less than 100 PPM of chlorine shall be present at the extreme end of the system.
5. Proceed to open all faucets and taps and thoroughly flush all new lines until the chlorine residual in the water is less than 1.0 PPM.
6. Obtain representative water samples from the system for analysis by a recognized Bacteriological Laboratory.
7. If all samples tested for impurities and organisms are negative, a letter and laboratory reports shall be submitted by the service organization to the contractor, certifying successful completion of the sterilization.
8. If any samples tested indicate the presence of harmful impurities and organisms, the entire sterilization procedure shall be repeated.
9. Plumbing Contractor shall provide plumbing connections and power for pumping chlorine solution into the system.

Warning: PVC and CPVC Pipe: Do not use a dry granular calcium hypochlorite as a disinfecting material for water purification in potable water piping systems. The introduction of granules or pellets of calcium hypochlorite with solvent cements and primers (including their vapors), may result in violent chemical reactions.

C. Available Service Organizations: Subject to compliance with requirements, provide the sterilization service of one of the following:

Water Chem

Arc Company, Inc.

Nova Consultants

Artesian Water Co.

END OF SECTION 220190

SECTION 220191

BALANCING – PLUMBING

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other conditions, if any) and Division 1 as appropriate, apply to the work specified in this Section.

1.2 DESCRIPTION OF WORK

A. Refer to Section 220005 for a general description of the scope of work in this contract.

B. Extent of plumbing systems to be balanced is indicated on the drawings and by requirements of this section.

C. Applications of tests include the following:

1. Interior Piping

a. Domestic hot water and hot water return

1.3 REFERENCE STANDARDS

A. Refer to Section 220000 for a general description of requirements applying to this section.

1.4 QUALITY ASSURANCE

A. Refer to Section 220010 for a general description of requirements applying to this section.

1.5 SUBMITTALS

A. Submit balancing report in accordance with Section 220000.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

PART 2 – PRODUCTS

2.1 PIPE & FITTING REPLACEMENTS

A. Refer to Section 220010 for replacement of any defective pipe or fittings. Replacement shall include all required draining of system, removal and replacement and uncovering, recovering.

PART 3 – EXECUTION

3.1 GENERAL

A. All new hot water return piping installed or wherever system valves are being replaced, the system shall be tested, balanced and approved before concealing. Failure to secure the approval of the Municipal Inspector, A/E Inspector or the Inspector of the Owner makes it mandatory for the Contractor to completely expose the piping for balancing. All expense involved in the uncovering of the piping for the balancing and recovering shall be borne by the respective Contractor with no change in Contract.

B. All equipment, material and labor required for balancing a plumbing system or part thereof shall be furnished by the Plumbing Contractor responsible for installing the work.

3.2 INTERIOR PIPING

A. Domestic Hot Water Return System: Upon completion of the testing of the domestic hot water supply and recirculation systems, a final procedure is to be performed to obtain uniform circulation within each hot water loop of the domestic hot water system. At the ends of the hot water mains, or wherever a branch return line connects to the main return line, there shall be three (3) valves: ball valve, check valve and balancing valve. These valves are to be installed in an accessible space at/or above the ceiling or where indicated on the drawings.

B. Based on an Accu-Flo balancing valve, the use of a differential pressure gauge Model No. 779 shall be used to achieve the greatest accuracy.

END OF SECTION 220191

SECTION 230200

GENERAL PROVISIONS – HVAC

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to work of this Section.

B. This specification or drawing and the design features or resulting construction disclosed, are the property of Furlow Associates, Inc., and shall not be reproduced without written permission.

C. All Mechanical Systems shall be part of and included in all of the following: 230200 thru 230950 (230960). (Designer Note: Check for Alternates)

1.2 WORK INCLUDED

A. Provide labor, materials, equipment and supervision necessary to install complete operating HVAC Systems, including all work at the site and within the proposed construction areas to accomplish the required work.

B. Wherever the term "provide" is used, it shall be understood to mean both "furnish" and "install".

1.3 REGULATIONS, CODES AND STANDARDS

A. Work shall be performed in accordance with latest adopted codes, regulations and ordinances by authorities having jurisdiction. Observe all safety regulations.

B. Obtain all permits and inspection certificates and pay all charges.

C. Make or arrange for utility connections and pay all charges. (Designer Choice)

D. Latest editions of any referenced standards shall govern.

1.4 RELATED WORK

A. Refer to equipment shown or specified in sections of Division 1 thru 14 and 26 that will require Mechanical services and provide such service.

B. Refer to work related to HVAC as shown on the following contract drawings:

Architectural & Structural

Plumbing

Electrical

C. This Contractor shall coordinate with the work of Division 26 and the Fire Alarm System vendor for locations and mounting of all duct smoke detectors. These devices are shown on the Mechanical Drawings for reference only to show the intent of the work. All locations shall be determined based on approved shop drawings from the Fire Alarm System vendor and the Contractor for the work of Division 26, Electrical.

1.5 COORDINATION

A. The Mechanical, Plumbing and Electrical Contractors are responsible to coordinate all manufacturer's recommended circuit breakers, starters, disconnects and fuse sizes for all equipment. Submission of a shop drawing will certify that this has been completed. Any necessary changes required will be included as part of this contract.

B. Mechanical Contractor shall coordinate scheduling, submittals and work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of independent work elements, with provisions to accommodate items that may be installed at a later time.

C. Mechanical Contractor shall verify utility requirements and all characteristics of operating equipment are compatible with the building utilities. Coordinate the work of all sections related and required for installing, connection and placing in service of all equipment.

D. Mechanical Contractor shall coordinate all space requirements, supports and installation of all mechanical, electrical, plumbing and fire protection work, which are indicated diagrammatically on the Drawings. Verify routing of all pipes, ducts, conduits and equipment connections. Maximize accessibility for other work, and service requirements for maintenance and repairs. Develop overall coordination drawing (all trades) and submit for review prior to fabrication/installation.

E. Obtain written confirmation from all related trade Contractors and the Owner or his representative that requirements, conflicts and coordination issues have been discussed and resolved.

F. Submit coordination drawings to verify access and clearances.

1.6 DEFINITIONS

A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawl spaces, and tunnels.

B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.

C. Exposed, Exterior Installations: Exposed to view outdoors, or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.

D. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in duct shafts.

E. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants, but subject to outdoor ambient temperatures. Examples include installation within unheated shelters.

1.7 SUBMITTALS

A. Shop Drawings:

1. Shop drawings shall be submitted in accordance with Division 1 of these specifications except where herein modified.

2. Shop drawings comprising complete catalog cuts, performance test data for HVAC equipment as required by other sections of Division 23, shall be submitted for review checking. The Contractor shall review these shop drawings for conformance to contract documents prior to submission and affix contractor's signature to each submittal certifying that this review has been done. By approving and submitting shop drawings, product data, samples and similar materials, the Contractor represents that the Contractor has determined and verified materials, field measurements and field construction data that relates to the work, and has checked and coordinated this information with all of the requirements contained in the contract documents for the work of all trades.

a. The Contractor and equipment manufacturer shall clearly indentify in all submittals and shop drawings any and all applications standards which require additional work to accommodate this equipment and provide a complete and operational system as described in the contract documents.

b. The Contractor shall be completely responsible for any and all additional costs associated with the changes required by this and all other trades.

3. Submit a 1/4" scale layout of all mechanical equipment rooms. All equipment and pads shall be to scale of equipment being furnished. Obtain size information of any and all equipment from other trades and indicate on drawings. The drawings shall be fully coordinated with all trades prior to submission. Indicate coil pull areas, filter pull areas, maintenance clearances, and access as applicable.

4. All shop drawing submittals shall have the following identification data, as applicable, contained therein or permanently adhered thereto.

   a. Project name.

   b. Project number.

   c. Sub-contractor's, vendor's and/or manufacturer's name and address.

   d. Product identification.

   e. Identification of deviation from contract documents.

   f. Applicable contract drawings and specification section number.

   g. Shop drawing title, drawing number, revision number, and date of drawing and revision.

5. Resubmit revised or additional shop drawings as requested.

6. Wherever shop drawings or vendor's standard data sheets indicate work to be done "by others", it shall be the responsibility of the contractor making the submission to identify by name, the contractor who is to do this work. If the contractor named is other than the contractor making the submission, the shop drawing submission must be reviewed by the named contractor and bear his mark of approval, prior to submission to the Architect/Engineer.

7. Where equipment proposed differs from that shown on the drawings or specified, he shall submit for approval drawings showing the manner in which the layout is affected by the substitution.

8. The Contractor shall keep one copy of approved shop drawings at the job site,, filed in a suitable metal container. The shop drawings shall be cataloged and kept in good repair, and shall be available for use by the Owner, Architect and Engineer.

9. No equipment shall be ordered, fabricated, etc., before approval of shop drawings.

B. Contractor is responsible for the shop drawing coordination and interface with the work of other contracts and adjacent work. The relationship of Contractor’s work shall be verified as it relates to adjacent and critical features of the work of this and all contracts and materials.

C. The Contractor shall submit a complete schedule of all shop drawings required for the scope of work covering all materials and equipment listed in all sections of Division 23, Mechanical, including all documents required for contract closeout, Owner instructions and training, and all turnover items at the completion of the work. This schedule shall be submitted for review and approval within thirty days of contract award and before any subsequent materials are provided for review.

D. The shop drawings provided by the Contractor will be reviewed only once and resubmittals will be reviewed only once. Any other submittals will be billed to the Contractor at the Engineer’s standard rates.

1.8 SITE INSPECTION

A. The Contractor shall visit site, inspect, and become aware of all conditions which may effect the work during the estimation phase of his work prior to bid openings. Investigate utilities, protection requirements for adjacent facilities, storage locations, and access to the construction area.

B. Submission of a bid will be deemed evidence of having complied with this requirement.

1.9 SUBSTITUTIONS

A. Whenever a material, article, piece of equipment or system is identified in the following specification or indicated on the drawings by reference to manufacturers' or vendors' names, trade names, catalog numbers or the like, it is so identified for the purpose of establishing the basis of the Bid.

B. Substitution approval must be obtained and included as an addendum item prior to the submission of the bid. An approved substitution shall not be considered as an approval for the Contractor or an equipment vendor to deviate from the written portion of the specifications unless so stated in the addendum.

C. The drawings illustrate the space allocated for equipment and the Contractor shall install the equipment accordingly. If changes are required in the building or arrangement due to substitution of equipment, the Contractor making the substitution must pay for the necessary modifications.

D. The listed equivalent or substituted manufacturers along with the bidding related contractor shall be completely responsible to comply with all requirements on all contract documents. This shall include, but not be limited to all: space requirements, code clearances, type-horsepower-capacities-number and size of services required from other trades including all auxiliary items provided by this Contractor and all other trades, and all manufacturer’s specific equipment applications standards and requirements, for approved equipment including that which is basis of design or a substitution. The bidding related contractor and equipment manufacturers shall clearly identify in all submittals and shop drawings any and all applications standards which require additional work to accommodate this equipment and provide a complete and operational system as described in the contract documents. If the bidding contractor or manufacturer does not comply with these requirements then they shall be completely responsible for any and all additional costs associated with the changes required by this and all other trades.

E. Where only one brand name or manufacturer is identified, no substitutions are permitted (Design Choice)

F. Substitutions:

1. Until a date no later than seven (7) days before the date Bids are due, Architect will consider written requests from bidders for substitution of Products. Architect will review requests and will notify Bidders in an Addendum if the requested substitution is acceptable.

2. Submit a separate request for each Product, supported with complete data, with drawings and samples as appropriate, including:

   a. Comparison of the qualities of the proposed substitution with that specified.

   b. Changes required in other elements of the work because of the substitution.

   c. Effect on the construction schedule.

   d. Cost data comparing the proposed substitution with the Product specified.

   e. Any required license fees or royalties.

   f. Availability of maintenance service, and source of replacement materials.

3. Architect shall be the judge of the acceptability of the proposed substitution.
4. A request for a substitution constitutes a representation that Bidder:
   a. Has investigated the proposed Product and determined that it is equal to or superior in all respects to that specified.
   b. Will provide the same warranties or bonds for the substitution as for the Product specified.
   c. Will coordinate the installation of an accepted substitution into the work, and make such other changes as may be required to make the work complete in all respects.
   d. Waives all claims for additional costs, under his responsibility, which may subsequently become apparent.

D.N.: Verify if Architect or CM has this covered in Division 1 or Instructions to Bidders.

Include whenever FAI is prime professional.

1.10 LUBRICATION

A. Provide and maintain all required lubrication of any equipment operated prior to acceptance by the Owner. Lubrication shall be as recommended by the equipment manufacturer.

B. Provide one year's supply of lubricants to Owner at date of acceptance.

C. Verify that required lubrication has taken place prior to any equipment start-up.

1.11 EQUIPMENT START-UP

A. Verify proper installation by manufacturer or his representative.

B. Advise General Contractor/Construction Manager/Owner's Representative (Choose one) 2 days prior to actual start-up.

C. Verify proper operation. Obtain signed statement by manufacturer or his representative that equipment is operating within warranty requirements. Submit statement to General Contractor/Construction Manager/Owner's Representative (Choose one).

D. Perform field mechanical balancing in accordance with Section 230950: TESTING AND BALANCING OF MECHANICAL SYSTEMS.

E. The Mechanical Contractor shall own as part of his work, the following:

Provide one (1) additional drive set, if necessary, to obtain final design balancing requirements. The Mechanical Contractor shall coordinate with Balancing Firm and equipment manufacturer for drive selection, including belts and pulleys.

1.12 OPERATION & MAINTENANCE INSTRUCTIONS

A. Properly and fully instruct Owner's personnel in the operation and maintenance of all systems and equipment.

1. Contractor to demonstrate all systems to Engineer for verification of operation prior to Owner's instruction period.
2. Provide two (2) 4-hour sessions of training to School District/Owner's Maintenance Staff.

B. Insure that the Owner's personnel are familiar with all operations to carry on required activities.

C. Such instruction shall be for each item of equipment and each system as a whole.

D. Provide report that instruction has taken place. Include in the report the equipment and/or systems instructed, date, contractor, Owner's personnel, vendor, and that a complete operating and maintenance manual has been reviewed.

E. Manual shall include all instructions on operation, maintenance, repair parts list, lubrication requirements, brochures, catalogue cuts, complete schedule of air filters for each unit type in Excel spreadsheet format, wiring diagrams, piping diagrams, control sequences, service requirements, names and addresses of vendors, suppliers and emergency contacts. Three manuals shall be provided.

F. Submit manuals for review prior to operating instruction period. Manuals shall be 8-1/2 x 11" with hard cover, suitably bound.

G. Provide to the Owner any special tools necessary for operation and routine maintenance of any of the equipment.

H. Upon completion of the project, the Mechanical Contractor shall provide a complete set of legible as-built drawings for the Owner.

I. Furnish three (3) copies of a professionally taped video and three (3) copies of professionally prepared drawings demonstrating the following:

- Locations of main shut-off valves.
- Procedures for equipment start-up and seasonal shut-downs.
- Procedures for maintenance.
- Provide written version of all procedures included in video.

The above should cover all equipment/systems including, but not limited to, the following:

- Hot water distribution system.
- Chilled water distribution system.
- Air handlers
- Energy recovery unit
- Fans
- Pumps
- D/X cooling units
- Boilers
- VAV box
- Unit ventilators/fan coil units
- Chillers
- Cooling tower
- ATC System

D.N. – Include Paragraph I on all BSD projects as directed by the Project Manager.

1.13 TOOLS

A. All equipment furnished by the Mechanical Contractor which requires special tools or devices other than those normally available to the maintenance or operating staff shall be furnished in duplicate to the Owner, sufficiently marked, packed or boxed for staff usage. The tools provided shall be listed by

the Mechanical Contractor identified as to their use or the equipment applicable in a written transmittal to the Owner.

1.14 CLEANING AND FINISHING

A. After equipment start-up and all operating tests have been made and the system pronounced satisfactory, each respective Contractor shall go over the entire project, clean all equipment, etc., installed by him and leave in a clean and working condition. Any surfaces found marred after this final cleaning shall be refinished or replaced by each Contractor at no cost to the Owner.

B. Provide for the safety and good condition of all materials and equipment until final acceptance by the Owner. Protect all materials and equipment from damage. Provide adequate and proper storage facilities during the progress of the work. Special care shall be taken to provide protection for bearings, open connections, pipe coils, pumps, compressors and similar equipment.

C. All fixtures, piping, finished surfaces and equipment shall have all grease, adhesive labels and foreign materials removed.

D. All piping shall be drained and flushed to remove grease and foreign matter. Pressure regulating assemblies, traps, and similar items shall be thoroughly cleaned. Remove and thoroughly clean and reinstall all liquid strainer screens after the system has been in operation ten (10) days.

E. When connections are made to existing systems, the Mechanical Contractor shall do all cleaning and purging of the existing systems required to restore them to the condition existing prior to the start of work.

F. Clean-up: Remove from the premises, all unused material and debris resulting from the performance of work under this section.

D.N. – DELETE 1.15 ON ALL PROJECTS WITHIN NEW CASTLE COUNTY.

1.15 TEMPORARY USE OF EQUIPMENT

A. The use of permanent equipment and terminal units during the construction period shall be done at the specific direction of the Construction Manager or the Owner's Representative, and as permitted by Local Code.

B. Whenever equipment has been used as directed, the Mechanical Contractor shall change unit filters as required in other sections of Division 23, as well as vacuum clean the interior of all unit enclosures to a like-new condition, including cleaning of coils. Under no circumstances will energy recovery equipment be used for temporary purposes.

C. Mechanical Contractor shall also vacuum clean the interior of all connecting ductwork, fittings, dampers, air outlets and inlets.

D. Mechanical Contractor shall also provide the Owner with a full and complete warranty required in other sections of Division 23 and the General Conditions of the contract.

PART 2 – PRODUCTS

2.1 GENERAL

A. All material and equipment shall be new and of present day manufacture, and shall conform to accepted standards of the trade where such a standard has been established for the particular type of equipment or material.

B. Whenever equipment or material is referred to in the singular, such as "the fan", it shall be deemed to apply to as many such items as necessary to complete the work.

2.2 PRODUCT DELIVERY, STORAGE AND HANDLING

A. During loading, transporting and unloading exercise care to prevent damage to material.

B. Store all materials in dry enclosures or under protective coverings out of way of work progress.

C. Material shall not be allowed to be stored directly on ground.

D. Deliver in manufacturer's original cartons or on skids.

E. Handle and protect so as to prevent damage to product or any surrounding material.

2.3 CONCRETE

A. Concrete shall be in accordance with Section 03300, or ACI-613. Designer choice if 03300 is not used.

2.4 WARRANTY

A. Wherever in the specification sections of this division, reference is made to a specific warranty period, this warranty shall be in addition to and not a limitation of other rights the Owner may have against the Mechanical Contractor under the contract documents.

PART 3 – EXECUTION

3.1 PROTECTION

A. Plug or cap open ends of piping systems, conduit and ductwork.

B. Stored materials shall be covered to prevent damage by inclement weather, sun, dust or moisture.

C. Protect all installed work until accepted in place by the Owner.

D. Plates, polished metal escutcheons, thermostats and other finished devices shall not be installed until masonry, tile, and painting operations are complete unless otherwise protected.

E. Protect all work from operations which may cause damage such as hauling, welding, soldering, painting, insulating and covering.

3.2 WORKMANSHIP

A. Install all work neat, trim and plumb with building lines.

B. Install work in spaces allocated.

C. Cutting and patching shall be performed by skilled tradesmen normally employed for the work involved.

D. This Contractor shall provide a complete weathertight seal to all new systems in the building including the necessary caulking, weather-stripping and insulation.

(DESIGN NOTE: INCLUDE 3.3, 3.4 AND 3.5 ONLY DIVISION 23 HAS SITE WORK FOR UNDERGROUND PIPING OR DUCTWORK.)

3.3 EXCAVATION

A. The excavation shall be of the open-trench method and to the depths and widths as may be necessary. The Mechanical Contractor shall do all excavation required in connection with his work. Bottoms of trenches shall be excavated to a uniform grade. All materials excavated shall be deposited on the side of the trenches and beyond the reach of the slides. Excavated material shall not be piled where it will interfere with traffic. If rock is encountered, it shall be removed by the General Contractor. See provisions in Division 2.

B. No conduits shall be bedded directly on rock. They shall be cushioned by a 6-inch layer of crushed stone or gravel of selected grade, of size to pass through 3/4" mesh sieve. Not less than 30% shall be fine which will pass through a 3/8" mesh sieve.

3.4 SHORING AND PUMPING

A. The Mechanical Contractor shall provide all shoring, bracing or sheet piling necessary to maintain the banks of his excavation and shall take out same as the work progresses and filling in has been accomplished. Shoring shall be in accordance with OSHA Standards.

B. The arrangement of shoring must be such as to prevent any movement of the trench banks and consequent strains on the conduits. Shoring shall be provided to prevent damage to work installed by other trades.

C. The Mechanical Contractor shall do all pumping required to keep his excavations free of water. The water shall be conveyed in piping or watertight troughs a sufficient distance that it will flow from the site and not affect other work being performed.

3.5 BACKFILLING

A. After work in trenches has been completed, they shall be filled with select fill in 8" layers and shall be pneumatically tamped before the next layer of material has been filled in. The backfill shall be free of excavated rock, cinders, stones, brickbats or other debris.

B. Wherever rock is removed, the Mechanical Contractor shall secure and fill select clean earth to a minimum depth of 3'-0" above the top of the pipe. Unless otherwise indicated, no rock shall be deposited in the trench fill. This clean earth fill shall be procured other than from the site unless permission for earth borrow from the site is granted by the Architect. If site borrow is permitted, the topsoil removal, relocation and finished grading will be accomplished as directed by the Architect.

C. Under no circumstances shall excavated material be left where it will interfere with the Owner's or other Mechanical Contractor's operations.

D. All earth and other materials taken from the trenches and not required for backfilling shall be deposited where directed, or removed from the premises as directed by the Architect.

E. Any rock removed from the excavation shall be removed from the project site by the Mechanical Contractor.

F. Trenches which pass under wall footings or within 18" of column footings shall be backfilled with clean concrete. To secure adequate foundation support, the method and depositing of the concrete fill shall be as directed by the Architect. To prevent the concrete from adhering to the pipe, necessary pipe protection shall be applied.

3.6 EQUIPMENT SETTING

A. Provide as a minimum, a 4 inch concrete pad beneath all floor-mounted equipment. Install anchor bolts in pour.

B. Provide as a minimum, spring vibration isolation under any equipment 10 HP and over and rubber in shear vibration isolation on any equipment up to 10 HP. For further specifications and additional requirements, refer to other sections.

C. Concrete shall be 3,000 psi, 28 day compressive strength in accordance with ACI-613. Reinforce with No. 4 rod 12" on centers both ways or as otherwise detailed.

3.7 FASTENERS, HANGERS AND SUPPORTS

A. Provide all hangers and supports required to suspend, mount, or hang the work.

B. Provide all miscellaneous steel angles, channels, beams, clips, brackets and anchors necessary to hang or support the work. Provide submissions for review.

C. Install concrete inserts before concrete is poured.

D. Drilled inserts shall not be loaded more than 1/4 rated capacity.

E. Power-driven fasteners shall not be allowed for piping larger than 2 inch, or equipment. When used they shall not be loaded more than 1/8 rated capacity or 200 pounds.

F. All hangers, miscellaneous steel, braces and supports shall be galvanized, cadmium plated, or primed steel. Copper tubing shall be supported with copper hangers.

G. Piping shall be supported from adjustable clevis type hangers with insulation pipe saddles or pipe shields in accordance with piping support spacing table on the drawings. Where hangers are 18" or longer provide lateral bracing at every fourth hanger.

H. Support vertical piping at floor levels. Piping shall have split rings.

I. Any lintels required for openings for this work if not indicated on Architectural or Structural drawings shall be provided under this Section.

J. Piping on the roof shall be supported by an engineered, prefabricated hanger system specifically designed for installation on the roof without roof penetrations, flashing or damage to the roofing material. The system shall consist of bases made of high density polypropylene plastic with additives for UV protection, hot dipped galvanized structural steel frames, hangers, fasteners, rods, etc. The system shall be complete and designed to fit the piping installed under actual conditions of service. The system shall be furnished as manufactured by PHP Systems & Design or Anvil International Haydon H-Block. (Designer Choice)

3.8 SLEEVES

A. Provide each pipe, duct or conduit passing through a masonry or concrete wall, floor or partition with a sleeve made from standard weight steel pipe for pipe or conduit and No. 12 gauge galvanized steel for ducts, with smooth edges, securely and neatly cemented in place. Provide each pipe, duct or conduit passing through a frame or metal partition with a sleeve made from No. 22 gauge galvanized sheet metal, securely fastened in place.

B. Be responsible for the proper location and alignment of all sleeves.

C. Provide hydrostatic seals for sleeves passing through outside walls, either above or below grade, or through hydrostatically sealed slabs or floors on grade. Provide fire-rated seals for all sleeves which penetrate fire-rated walls.

D. Install both piping and sleeve seals so as to maintain integrity of seals with expansion and contraction of piping.

E. Set floor sleeves flush with floor surface in finished areas, 1" above the finished floor in kitchens, cafeterias, and similar service areas unless such areas are slab-on-grade; 1" above the floor in mechanical rooms, pipe chases, pipe spaces and other unfinished areas, unless otherwise indicated, and flush with the underside of slabs. Extend wall and partition sleeves through and cut flush with each surface unless otherwise indicated or specified.

F. Select sleeves two pipe sizes larger than any pipe or conduit that is to remain uncovered, unless otherwise required by the sealing method specified. Where pipes are to be covered, provide sleeves large enough to allow the covering to pass through the sleeves with sufficient clearance for sealing as specified hereinafter. Size sleeves for branch piping from vertical risers large enough to permit vertical expansion at the riser.

G. Select duct sleeve sizes to suit requirements of fire and/or smoke dampers (Choice) and sealing methods as specified.

H. Place sleeves imbedded in concrete floors or walls in the forms before concrete is poured; sleeves shall have integral waterstop flanges, where they are to receive either watertight or hydrostatic seals.

I. Install sleeves passing through above-grade floors of mechanical rooms, toilet rooms, kitchens or similar service areas where liquid leaks or spillover may occur in a watertight manner. Sleeves shall be such that waterproofing membrane can be flashed around and into the sleeve where necessary.

J. Seal sleeves for pipes or conduit passing through ceiling air plenum walls or the floor above air tight in a manner similar to that specified for fire-rated sleeves. (Choice)

K. Hydrostatic Sealing Method: Provide compressible synthetic rubber seals, equivalent to LINK SEAL, manufactured by the Thunderline Corporation, or THRUWALL manufactured by O.Z. Gedney. Install seals in accordance with the manufacturer's recommendations to provide air tightness aboveground and hydrostatic sealing belowgrade. Caulking or other type mastic is not acceptable.

L. Fire-Rated Sealing Method:

1. Sleeves, openings and sealants shall comply with applicable codes, recommended practices and standards, and manufacturer's instructions. Fire sealants shall have ability to prevent spread of flame, smoke or water throughout the penetration and shall pass 3 hour test, UL test ASTM E814 and UL 1479.

2. Products: Chase Corporation CTC PR-855, O. Z. Gedney CRS/CAFS, 3M Electro-Products Division Putty 303 or Caulk CP25 penetration sealing kits, General Electric Company sealants type RTV-850, 6428 or 7403, Thunderline Corporation "Link-Seal Pyro-Pak". Installation and type of sealant to be used as recommended by the manufacturer.

3.9 PLATES

A. Provide chrome plated plates wherever piping passes into finished area.

B. Plates shall be securely fastened to piping or building construction.

C. Floor plates shall cover 1 inch sleeve extension.

3.10 OFFSETS, TRANSITIONS, MODIFICATIONS

A. Provide all offsets necessary to install the work and to provide clearance for other trades.

B. Maintain adequate headroom and clearance.

C. Incidental modifications necessary to the installation of the systems shall be made as necessary and as approved by the Architect.

3.11 RECESSES

A. Furnish information to the Construction Manager or General Contractor as to sizes and locations of recesses required to install panels, boxes, and other equipment or devices which are to be recessed in walls.

B. Make offsets or modifications as required to suit final locations.

3.12 LABELING

A. All HVAC equipment such as pumps, fans, air handling units, and devices requiring identification for operating procedures shall be provided with permanent black laminated micarta white core labels with 3/8 inch letters.

B. This shall also apply to all controllers, remote start/stop pushbuttons and equipment cabinets.

C. This shall not apply to individual room thermostats.

D. All Mechanical Rooms shall be identified with a permanent placard of red-white-red laminated, commercial grade, plastic construction. Letters shall be minimum one inch high and read in capital letters: WARNING – MECHANICAL EQUIPMENT ROOM – LIMITED ACCESS. Placard shall be

centered on each door leading into the mechanical room at five feet above the floor and attached at each corner with brass screws.

E. Refrigeration Machinery Rooms shall be identified with a permanent placard of red-white-red laminated, commercial grade, plastic construction. Letters shall be minimum one inch high for the header to read in capital letters: WARNING – REFRIGERATION EQUIPMENT ROOM – LIMITED ACCESS. The following information shall be posted in a similar fashion, minimum half-inch high capital letters, indicating:

1. The name and address of the installer.
2. The refrigerant number and amount of refrigerant in pounds.
3. The lubricant identity and amount in pounds or ounces as appropriate.
4. The field test pressure applied to the equipment in psig.

Placard shall be centered on each door leading into the refrigeration equipment room at five feet above the floor and attached at each corner with brass screws.

F. At all fire damper, smoke damper and combination fire/smoke damper locations, access doors in ductwork shall be identified with a permanent placard of red-white-red laminated commercial grade plastic construction, minimum one-half inch high capital letters, reading, “FIRE DAMPER”, “SMOKE DAMPER”, “FIRE/SMOKE DAMPER” as appropriate for the installation. Attach securely to face of access door with brass screws at each corner, sealed airtight.

3.13 FLASHING AND COUNTERFLASHING

A. Roof curbs, etc., shall have counterflashing fittings. General Contractor shall provide flashing.

B. Piping and conduit thru the roof shall be flashed by the General Contractor. Provide counterflashing.

C. Provide curbs with base features required to match roof materials, finishes and configuration; e.g., flat, sloped, raised seam, etc.

3.14 ACCESS

A. Locate all equipment, valves, devices and controllers which may need service in accessible places.

B. Where access is not available, access panels shall be provided. Furnish access panels to the Construction Manager or General Contractor for installation.

C. Access panels shall be Nailor-Hart Industries, Karp Co., or Controlled Air Manufacturing Limited, with 16 gauge frames and 14 gauge steel door, prime painted.

D. Maintain access clearances for tube or fan removal, coil pulls, and filter removal.

3.15 WIRING AND MOTOR CONTROLS

A. Packaged equipment shall be furnished with disconnect switches, starters, overloads, factory furnished and wired by the unit manufacturer.

B. Roof-mounted exhaust fans, except utility sets, rated less than 1/2 HP at 115 volts, single phase, shall be furnished with disconnect switches, factory furnished and wired by unit manufacturer.

C. Rooftop equipment shall be furnished with starters, disconnect switches, overloads, factory furnished and wired by unit manufacturer.

D. This Contractor shall furnish all information and assistance required for the Electrical Contractor to purchase all motor starters that are not specified to be part of the mechanical equipment.

E. Control wiring shall be provided under this Division of the work.

F. All wiring shall be in accordance with the National Electrical Code and as recommended by the equipment manufacturer.

3.16 UTILITIES (DESIGNER NOTE: INCLUDE B AND C IF NEEDED)

A. Do not interrupt any utility or service to the Owner without adequate previous notice and schedule.

B. Arrange and pay for the relocation, disconnection or removal of, or relocate, disconnect or remove existing utilities and services where such work is shown or where such utilities or services interfere with new construction, whether or not shown. Provide all excavation, backfilling and paving required by such work. (Choice)

C. Perform alteration of utilities and services in accordance with the rules, regulations and requirements of the involved utility companies, regulatory agencies having jurisdiction. (Choice)

3.17 CUTTING AND PATCHING EXTERIOR SURFACES (DESIGNER NOTE: INCLUDE ONLY FOR UNDERGROUND SITE WORK)

A. This Contractor shall be responsible for returning disturbed paved and/or grass areas to original condition where excavation for utilities has been required.

B. Cut and patch paved areas to match original surface.

C. Properly tamp backfill before finishing or repairing disturbed area surfaces.

3.18 OPENINGS - CUTTING, REPAIRING

A. This Contractor shall cooperate with the work to be done under other sections in providing information as to openings required in walls, slabs and footings for all piping, ductwork and equipment, including sleeves where required.

B. Any drilling or cutting required for the performance of work under this Section, shall be the responsibility of this Contractor and the cost thereof shall be borne by him.

C. Holes in Concrete: Sleeves shall be furnished, accurately located and installed in forms before pouring of concrete. This Contractor shall pay all additional costs for cutting of holes as the result of the incorrect location of sleeves. All holes through existing concrete shall be either core drilled or saw cut. All holes required shall have the approval of the Structural Engineer prior to cutting or drilling.

D. It shall be the responsibility of this Contractor to ascertain that all chases and openings are properly located.

3.19 PAINTING (DESIGNER NOTE: COORDINATE WITH ARCHITECT)

A. The General Contractor shall be responsible for painting.

OR

D. N.: Pick One

A. Refer to the Construction Manager's Scope of Work.

OR

A. This Contractor shall be responsible for painting required in conjunction with cutting and patching of existing building construction, in areas which are not scheduled for painting under the General Contract. This Contractor shall also be responsible for painting existing equipment, and/or piping, where finish is damaged by new work, in these same areas.

B. Refer to Division 1 for types of paint, color and finish.

C. Surfaces subjected to temperatures below 180 degrees F, shall be painted with one coat of rust-resisting paint and one coat of high gloss enamel or sufficient finish coats for complete and uniform cover and high glossy finish.

D. Surfaces subjected to temperatures above 180 deg. F, shall be painted with one coat of heat-resistant paint and one coat of heat resistant enamel, or sufficient finish coats for complete and uniform cover and high glossy finish.

E. All painting shall be done in a careful, neat and workmanlike manner, with particular care being exercised to protect adjacent building and equipment finishes. All surfaces shall be thoroughly cleaned of dirt, rust, scale, dust, grease, oil, debris and sanded, sand blasted or power brushed to properly prepare to provide bond for the paint. Contractor shall be entirely responsible for cleaning and preparing all surfaces. Should evidence appear that the surface was not properly prepared, the Contractor shall remove paint, prepare surface and repaint, as required, at no additional cost.

F. All name plates, data plates that indicate manufacturer, model, size, capacity codes or identifying data on equipment painted, shall not be painted, but shall be carefully cut in.

G. All exposed canvas, insulation jackets and other porous surfaces shall be cleaned and sized with at least two coats of sizing primer before finish coats are applied. Sizing shall completely cover canvas so that canvas will not be noticeable through the final finish coat.

H. Equipment factory painted and not damaged shall not be painted, except equipment herein specified to be painted a particular color. Damaged surfaces on factory painted equipment will necessitate the painting by this Contractor.

I. Grilles, access panels, fan screen, convector, and unit heater enclosures and other prime-coated equipment in finished areas, will be painted by the General Contractor.

J. Piping, fans, floor-mounted pipe supports, containers, hangers, pump and other equipment surfaces that are insulated or uninsulated shall be finished in accordance with the Owner's color code.

K. The Mechanical Contractor shall furnish and lay drop clothes in all areas where painters finish work is being done, to protect floors and roofs and all other work from defacement. All temporary protections or coverings removed too early from any part of the work shall be promptly replaced, and any damage from neglect to do so shall be made good at the Mechanical Contractor's expense.

L. At the end of each day, the Mechanical Contractor shall place in covered metal containers, or destroy, all cloths, waste and refuse, which have been used in the application of inflammable paint materials. At the completion of work, all staging, scaffolding, containers and debris shall be removed from premises, leaving all painting in perfect and clean condition. Upon completion, leave the work clean and free from blemishes. Hardware, tile, marble, and similar material shall be thoroughly cleaned of all paint.

3.20 GUARANTEE

A. All work shall be guaranteed to be free from defects for a period of one year of operation from date of acceptance by the Owner.

B. Guarantee shall be extended on an equal time basis for all non-operational periods due to failure within the guarantee period.

C. All materials and equipment provided and/or installed under this section of the specifications shall be guaranteed for a period of one year from date of acceptance of the work by the Owner unless otherwise specified in Division 1. Should any trouble develop during this period due to defective materials or faulty workmanship, the Mechanical Contractor shall furnish necessary labor and materials to correct the trouble without any cost to the Owner. Any defective materials or inferior

workmanship noticed at time of installation and/or during the guarantee period shall be corrected immediately to the entire satisfaction of the Owner.

D. In the event of occupancy by the Owner prior to final acceptance of the project, the guarantee date for equipment placed in operation shall be mutually agreed to by the Mechanical Contractor and the Owner's representative.

E. Contractor to include an 11 month “walk-thru” of the building systems with representatives of the School District, Architect, Engineer and the Construction Manager. The purpose is to establish a list of corrective work that relates to operational issues, material/installation deficiencies, etc. prior to the expiration of the guarantee period.

3.21 DRAWINGS

A. The Mechanical Systems are indicated on the Contract Drawings. Certain pertinent information and details required by the Mechanical Work appear on the Architectural, Structural and Electrical Drawings; become familiar with all drawings, and incorporate all pertinent requirements.

B. Drawings are diagrammatic and indicate the general arrangement of systems and requirements of the work. Do not scale drawings. Exact locations of fixtures and equipment, not specifically shown, shall be obtained before starting work.

3.22 TESTING AND BALANCING OF MECHANICAL EQUIPMENT

A. Perform field mechanical balancing in accordance with Section 230950: TESTING AND BALANCING OF MECHANICAL SYSTEMS.

B. The Mechanical Contractor shall own as part of his work, the following:

Provide one (1) additional drive set, if necessary, to obtain final design balancing requirements. The Mechanical Contractor shall coordinate with Balancing Firm and equipment manufacturer for drive selection, including belts and pulleys.

END OF SECTION 230200

SECTION 230230

INSULATION & COVERING – HVAC

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the contract, including the conditions of the contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the work specified in this section.

B. Refer to Section 230200 for HVAC General Provisions

C. Refer to Section 230210 for HVAC Basic Materials & Methods.

1.2 DESCRIPTION OF WORK

A. This Section includes insulation and covering provided on the following piping and equipment:

1. Steam and Condensate Piping
2. Cold Water Make-Up Piping
3. Hot Water Heating Piping
4. Chilled Water Piping
5. Condensate Drain Lines
6. Dual temperature water piping.
7. Refrigerant Piping.
8. Cold Equipment Surface
9. Hot equipment surfaces.
10. Exterior Piping
11. Heating Water Recovery
12. Acoustic Duct Liner
13. Reusable Valve Covers
14. Insulated Pipe Saddles

B. Insulation shall be installed on the following duct systems:

1. All supply ductwork.
2. All return ductwork.
3. All outside air intake and relief ductwork.
4. All ductwork connected to energy recovery units.

1.3 REFERENCE STANDARDS

A. Refer to Section 230200 for a general description of requirements applying to this section.

1.4 QUALITY ASSURANCE

A. Refer to Section 230210 for a general description of requirements applying to this section.

B. Install insulation in accordance with manufacturer's recommendations.

C. Provide adequate supervision of labor force to assure that all aspects of the specifications are being fulfilled.

1.5 SUBMITTALS

A. Submit shop drawings, installation instructions, and manufacturer's literature of all materials specified in accordance with Section 230200.

B. Submit fabrication instructions for pipe fitting and valve insulation.

C. Submit manufacturer's joining recommendations for butt joints and longitudinal seams.

1.6 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, General Requirements.

PART 2 – PRODUCTS

2.1 PIPE INSULATION MATERIAL

A. Fiberglass:

1. Material: Preformed fiberglass bonded with resin to form circular pipe sleeves with factory applied, white all service jacket bonded to reinforced foil vapor barrier jacketing. The jacket shall have factory applied double pressure-sensitive, self-sealing, adhesive closure and vapor sealing of longitudinal joints. Thermal conductivity: 0.24 Btu/Hr./SF/inch at 100 degrees F. Flame spread of 25 and developed smoke of 50 or less.

2. All Valves and Fittings:

a. Glass fiber insert and pre-molded PVC cover, Johns Manville Corp. "Zeston" and "Hi-Lo Temp Inserts" for fittings. Glass fiber or prefabricated elastomeric foam fittings must fill the entire space within the cover completely.

b. Factory molded fibrous glass fitting covering for fittings. Coat ends with Fosters 30-36 lagfast adhesive

c. Mitered sections of pipe covering for valves.

3. Manufacturers: Johns Manville Corp., Certain-Teed, Owens- Corning, Knauf, Armacell.

B. Closed Cell:

1. Material: Black flexible elastomeric foamed closed cell structure insulation 25/50 rated with a flame spread rating of 25 or less and a smoke developed rating of 50 or less with both a moisture seal and a reinforced elastic foam lap seal closure system.

2. Flexible pipe insulation shall be a foamed elastomeric closed cell structure material, with a thermal conductivity of not more than 0.27 Btu/Hr./Sq. Ft./Inch at a mean temperature of 75 degrees F. The insulation shall have an average density of at least 2 pounds per cubic foot, shall be self-extinguishing, and shall have a water vapor transmission rating of not more than 0.1 perms. Between temperature limits of -40 degrees F and plus 220 degrees F, the insulation shall not indicate any deviation from its original state.

3. Specification Compliance:

ASTM-E-84

ASTM-C-534 Type I – Tubular, Type II – Sheet.

ASTM-D-1056, 2B1 – Tubular, Sheet.

MIL-C-3133B (MIL STD 670B) Grade SBE-3

MIL-P-15S280J, Form T, Form S.

4. Manufacturers: Armacell, Nomaco, K-Flex.

C. Covering of Pipe Insulation Outdoors:

1. Wrapping: Wrap insulation with embossed 0.016" aluminum jacket.
2. Fastenings: Cover shall be held in place with soft aluminum bands on 12" centers.
3. Valves and Fittings: Weatherproof all valves and fittings.

D. Manufacturers: Johns Manville Corp.., Certain-Teed, Owens- Corning, Knauf.

2.2 DUCT INSULATION

D.N. – MIN. R-VALUE MUST BE 8.0 FOR WORK INSTALLED IN UNCONDITIONED SPACES.

A. Concealed Supply, Return, Relief, and Outside Air Ductwork, and all ductwork connected to energy recovery units: Fiberglass duct wrap bonded with resins, 3/4 pound density, aluminum foil facing reinforced with fiberglass scrim, laminated to Kraft, 2" thick.

1. Thermal Conductivity: 0.27 Btu/Hr./SF/Inch at 75 degrees F. Min. installed "R" value w/25% compression shall be 5.6.
2. Duct wrap shall be cut to stretch-out dimensions as provided in manufacturer's instructions. Remove a 2" piece of insulation from the facing at the end of the piece of insulation to form an overlapping staple and tape flap. Install with facing outside so tape flap overlaps insulation and facing at other end. Insulation shall be tightly butted and not compressed excessively at duct corners. Seams shall be stapled 6" on center with outward clinching staples. All seams, tears, punctures and other penetrations of the insulation facing shall be sealed with foil tape or vapor proof mastic. Where rectangular ducts are 24" in width or greater, duct wrap shall be secured to the bottom of the duct with mechanical fasteners; i.e., stick pins spaced 18" on center.

B. Exposed supply, return, relief, and outside air ductwork, and all ductwork connected to energy recovery units, shall be insulated in finished conditioned spaces, penthouse, mechanical rooms, mezzanine areas, equipment closets, and non-conditioned spaces with 2" thick rigid fiberglass board. Insulation shall be 6 P.C.F. density with a "K" value of 0.25 Btu/Hr./SF/Inch at 75 degrees F. mean temperature and shall be U.L. listed at 25 maximum for flame spread, and 50 maximum for smoke developed. Insulation shall be applied using Graham Pins or Stik-Clips and all seams, edges and breaks shall be sealed with 4" matching tape and sealed with Vicryl CP-10 to match ASJ jacket. Insulation shall be provided with all-service jacket facing.

C. Manufacturers: Johns Manville Corp., Certain-Teed or Owens- Corning, Knauf.

D. Outdoor Installation:

1. Two Inch (2") thick Arma Tuff supplied in sheet and roll forms laminated with a white, 0.012" thick thermoplastic rubber membrane.
2. Material shall be resistant to ozone and ultraviolet radiation with a of 10 year limited warranty against breakdown of the membrane.
3. Thermal conductivity shall be 0.25 at 75°F mean temperature with a vapor permeability of 0.05 perm-inch for the foam and 0.00 for the laminate.
4. Insulation shall be applied using Armaflex 520 adhesive; seams shall be covered with minimum 6 inch wide self-sealing tape and minimum 6 inch wide self-sealing tape along all exposed edges.

Install per manufacturer's instructions.

5. Minimum insulation value shall be R-8.
6. Coordinate with the work of Section 230600 to ensure that the top of all single wall, square or rectangular horizontal ductwork is crowned to minimize accumulation of weather on top of the finished insulation jacket.

OR

D.N.: USE ARMATUFF ABOVE ON ALL PROJECTS UNLESS OTHERWISE DIRECTED BY PROJECT MANAGER.

D. Outdoor Installation:

1. Pre-manufactured panel system consisting of four (4) piece interlocking panels.
2. The interlocking panels shall be constructed of Dow Thermax Polyisocyanurate insulation, ASTM D-1622, nominal 2 pcf; water vapor transmission as permeance less than 0.03, per ASTM E-96; water absorption less than 0.3% (24 hours), per ASTM C-209; flexure strength more than 40 psi, per ASTM C-203.
3. Operating temperature range of -100°F to +250°F.
4. Insulation shall be laminated in two (2) layers to provide R-14 at 2" thickness, per ASTM C-236/C-518.
5. The insulation shall be jacketed with 0.032" thick embossed aluminum and sealed with vapor barrier compound. All joints shall interlock to ensure a thermal seal.
6. Panels shall be secured with #10 self-tapping stainless screws with weather seal washers.
7. Manufacturers: Techna-Duc Insulation System as made by P.T.M. Manufacturing, L.L.C., Newark, Delaware.

OR

D. Outdoor Installation (Sheet metal ductwork not required):

1. The ductwork shall be a panel system manufactured of CFC-free Kingspan Kooltherm closed cell rigid thermoset resin thermally bonded on both sides to a factory applied 0.001" (25 micron) aluminum foil facing reinforced with a fiberglass scrim. Joints shall be sealed with Kingspan foam gaskets and aluminum grip flange connections.
2. The density of the Kooltherm foam shall not be less than 3.43-3.75 PCF with minimum compressive strength at 10% compression 29 PSI/200kPa.
3. Insulation shall be laminated in two (2) layers to provide R-14 at 2-1/4" thickness, 0.146 Btu-in/ft2-hr-f per ASTM C-518.
4. The duct shall be jacketed with 0.032" thick embossed aluminum (color white). Joints shall be insulated and sealed. Panels shall be secured with #10 self tapping stainless steel screws with weather seal washers.
5. Manufacturer: Dual-Tech as made by PTM Manufacturing, LLC or Thermaduct.

OR

D. Outdoor Installation:

1. On all outdoor square and rectangular ductwork, provide a minimum 0.032 inch thick plain stucco embossed aluminum jacket over 2 inch thick rigid fiberglass board insulation as described in part B of this article.

a. 32-mill aluminum roll jacketing, ASTM B2089, with 2.5 mil poly/surlyn backing, plain or white acrylic coated, as made by Childers, RPR, or Pabco.

2. Provide duct roof pitch-supports at all flanges, stiffeners, insulation joints along the top of the horizontal ducts with 24 inch maximum spacing, with 12 degree pitch and anti-sweat coating.

3. Provide rolled metal jacketing with all seams overlapping 2 inches in a watershed fashion.

4. Apply the roll metal jacketing from 48 inch wide roll stock lengthwise with the duct to minimize the number of seams for ducts that measure 44 inches and less on any side including insulation.

5. Machine break the metal jacketing for sharp corners; on large ducts, cross break the jacket to eliminate wrinkles.

6. Secure seams with stainless steel sheet metal screws 4 inches on center. On horizontal ducts, seal seams on duct horizontal surfaces and on vertical ducts seal the vertical seams with continuous bead of caulking sealant.

a. sealer made by Fosters Foamseal 30-45, Childers CP-70, Epolux Cadaseal 745.

7. Flash metal jacket with same material applied to the duct where insulation terminates at bolted flanges. Allow for bolt removal where access or disassembly is required.

8. Manufacturer: Fabrite as made by County Insulation Company, New Castle, Delaware.

2.3 CALCIUM SILICATE INSULATION

A. Material: Insulation for hot equipment shall be heavy density fiberglass insulation retained by .016” aluminum held in place by 1”x25 gauge stainless steel bands spaced on a maximum center distance of 12". All joints and voids shall be filled with insulating cement, well trowelled into the openings. Cleanouts, manholes and nameplates shall not be insulated, and the insulation shall be neatly beveled off at such openings.

B. Thickness: 3-1/2" thick.

K Factor @ 200 deg. F = 0.38 – Surface Temperature 87°F

K Factor @ 600 deg. F = 0.90 – Surface Temperature 112°F

C. Equipment Included:

1. Steam or Hot Water Convertor or Heat Exchanger
2. Field Fabricated Boiler Breaching
3. High Temperature Water (up to 250°F) Storage Tanks.
4. Steam Condensate Receivers.
5. Steam Flash Tanks.

D. Manufacturers: Industrial Insulation Group.

2.4 KITCHEN HOOD DUCT INSULATION & FIRE RATED AIR DUCTWORK (Select one)

A. Materials: Non-mineral wool, passive, low biopersistant fiber, ceramic blanket insulation totally encapsulated on all sides with aluminum foil scrim on kitchen hood exhaust duct.

B. Installation shall be 1 layer, 2” thick to provide 2-hour protection on grease duct. Apply directly to the duct with zero clearance to combustibles at the overlap.

C. Secure with metal bands per manufacturer's recommendations on type and spacing. For ducts spacing 24" or greater, secure with insulation pins on the bottom of horizontal runs and on vertical runs to prevent sagging.

D. Manufacturers: Thermal Ceramics - Firemaster Fast Wrap Plus, ETS Schaefer or Pyroscat.

OR

A. Materials: Non-mineral wool, passive, low biopersistant fiber, ceramic blanket insulation totally encapsulated on all sides with aluminum foil scrim on kitchen hood exhaust duct.

B. Installation shall be 2 layer, 1-1/2" thick to provide 2-hour protection on grease duct. Apply directly to the duct with zero clearance to combustibles through the length of the assembly

C. Secure with metal bands per manufacturer's recommendations on type and spacing. For ducts spacing 24" or greater, secure with insulation pins on the bottom of horizontal runs and on vertical runs to prevent sagging.

D. Manufacturers: Thermal Ceramics - Firemaster Duct Wrap Plus, Pyroscat, or Unifrax FyreWrap®.

1. Contractor may provide an agency approved, single layer system of 6 PCF density, 1.5 inch thick, passive fire protection blanket installed as a two-hour rated enclosure system, Type FSB Ultra, as made by ETS Schaefer, or Unifrax FyreWrap® Elite 1.5.

2. Contractor may provide an agency approved, single layer system of insulation which consists of glass fiber blanket completely encapsulated in a UL Classified fiberglass reinforced foil facing, 2 inches thick, as a two-hour rated enclosure system. Type FlameChek Plus2, as made by CertainTeed Insulation Group.

2.5 ACOUSTIC DUCT LINER

A. Duct liner shall be designed for use as an acoustical insulation to absorb air conditioning noise in sheet metal ducts and plenums operating at velocities up to 6000 fpm and temperatures up to 250 deg. F.

B. Duct liner shall be a bonded mat of glass fibers coated with an EPA registered biocide and a black pigmented fire-resistant coating on the air stream side or flexible elastomeric closed cell foam made with an EPA approved anti-microbial.

C. Duct liner shall comply with the requirements of NFPA 90A and 90B. Surface burning characteristics shall comply with UL Standard 723 for 25/50 flame and smoke development.

D. Duct liner shall comply with the property requirements of ASTM Specification C1071 Type 1, or ASTM C1534. Material shall resist fungal and bacterial growth when subjected to ASTM G21 and G22 test methods.

E. Material thickness, name of manufacturer and type shall be printed on the air stream side of the liner for ease of identification.

F. Duct liner shall be 2" thick, unless otherwise noted on the drawings.

G. Manufacturers: Owens Corning QuietR® AcousticR™ Duct Liner, Certainteed, Evonik Industries Solcoustic, Johns Manville Linacoustic® RC, Armacell.

OR

Designer Note: Check with Project Manager on choice of liner. If you select this product, you must specify a minimum of one inch thick duct wrap to maintain R-value to meet the Energy Code.

2.5 ACOUSTIC DUCT LINER

A. Duct liner shall be designed for use as an acoustical insulation to absorb air conditioning noise in sheet metal ducts and plenums operating at velocities up to 6000 fpm and temperatures up to 250 deg. F.

B. Duct liner shall be open-cell melamine-based foam, 0.5 to 0.7 pounds per cubic ft. or, AP Coilflex flexible elastomeric foam meeting ASTM C1534, or, AP Armaflex Duct Liner / Wrap.

C. Duct liner shall comply with the requirements of NFPA 90A and 90B. Surface burning characteristics shall comply with UL Standard 723 for 25/50 flame and smoke development.

D. Duct liner shall comply with the property requirements of ASTM Specification C1071 Type 1, or ASTM C1534. Material shall resist fungal and bacterial growth when subjected to ASTM G21 and G22 test methods.

E. Material thickness, name of manufacturer and type shall be printed on the air stream side of the liner for ease of identification.

F. Manufacturers: Pinta-Acoustic "Willduct" acoustical duct liner, natural white or gray, 1" thick; Armacell.

2.6 REUSABLE VALVE COVERS

A. All valves, strainers, combination valves, etc. in chilled water and heating hot water systems shall be insulated with a factory fabricated removable and reusable cover. (This product shall not be used for pipe and fittings.)

B. Insulation shall be either fiberglass blanket or flexible elastomeric thermal insulation as listed in Paragraph 3.2 of this specification, or prefabricated fitting from the supplier. Flame and smoke spread shall be 25/50 per ASTM 84.

C. Outer jacket shall be made of material equal to Tychem QC, overlap and completely cover the insulation, with seams joined by tabs made from Velcro or fabric straps per manufacturer's standards.

D. Outer jacket shall overlap adjoining sections of pipe insulation, and shall be non-combustible, impermeable to water, and prevent mold, mildew and condensation.

E. Installation shall not require the use of any special hand tools.

F. Manufacturers: Corick Valve Covers, NoSweat Valve Wraps.

2.7 INSULATED PIPE SADDLES

A. Insulation and facing shall each meet 25/50 flame and smoke ratings per ASTM E-84 on a component basis.

B. A section of rigid insulation shall be used at all cold pipe hangers or support locations and shall consist of:

1. A rigid 3.75 PCF phenolic foam pipe insulation designed to support pipe sizes up to and including 6" iron pipe size.

2. A rigid 5 PCF phenolic foam pipe insulation designed to support pipe sizes from 8" to 30" iron pipe size.

3. For all hot pipe hanger or support locations, the insert material shall be either rigid calcium silicate per ASTM C303 or perlite silicate per ASTM C303 with all service jacket and laminated to a steel support saddle.

C. The insulation jacket shall contain a vapor retarding material to provide low moisture vapor permeability and resistance to mold, mildew and fungus growth.

D. The insulation shall be free of any CFC or HCFC materials.

E. The insulation shall have a minimum K-factor of 0.13 at 75 deg. F mean temperature, and self-sealing lap joint with high performance acrylic pressure sensitive adhesive tape.

F. Integral insulation saddle shall be made of G-90 carbon steel, with full 180 deg. Coverage, flared edges to protect the vapor barrier jacket and insulation, and short rib surface to center the saddle inside the hanger and prevent movement.

G. Preformed insulation shall extend beyond the saddle by a minimum of 1-1/2" to accommodate a tape joint seal at the butt edges of adjoining insulation sections.

H. Minimum product dimensions shall be as follows:

Nominal pipe size (inches)	Insulation density (PCF)	Insulation length (inches)	Saddle length (inches)	Saddle gauge
½ - 3-1/2	3.75	9	6	20
4 – 6	3.75	12	9	18
8 – 18	5.0	18	12	16
20 – 30	5.0	24	18	14

I. Manufacturer: Tru-Balance insulated saddles as made by Buckaroos, Inc.

PART 3 – EXECUTION

3.1 INSTALLATION – GENERAL

A. Do not install until systems have been tested and meet requirements.

B. Do not install until building is enclosed. (New construction only)

C. Heavy work which may damage insulation shall have been completed in the vicinity of the insulation work.

D. Provide non-compressible insulation saddles at all piping hanger locations, and at all piping hanger locations where piping is insulated with flexible closed cell insulation.

Option: Provide insulation coupling system as made by Klo-Shure Co.

E. All installations shall be made by skilled craftsmen regularly engaged in this type of work.

F. Insulation shall be continuous thru-wall, ceiling and floors.

G. Metal shields, 16 gauge galvanized, shall be installed between hangers and pipe insulation.

H. Pipe, ductwork and equipment shall be clean and dry prior to insulating.

I. Install all insulation per manufacturer's instructions.

J. To avoid undue compression of insulation, provide solid core inserts at all supports as recommended by the insulation manufacturer. Provide insulation shields between the insulation jacket and the hanger.

K. Ductwork treated with internal acoustic duct liner does not require external insulation.

OR

Designer Note: Article "K" is true if you specify O/C or CT type liner 1-1/2" thick. When you specify the optional 1 inch liner by Illbruck, use the following article:

K. Ductwork treated with one inch thick internal acoustic duct liner requires one inch thick fiberglass external insulation.

L. Apply vapor proof mastic as recommended by the insulation manufacturer on all longitudinal and butt joints of sectional pipe insulation. Apply similar mastic to the end of every third length of sectional pipe insulation on all chilled water and dual temperature pipe insulation to prevent the migration of condensation that might occur.

M. For pre-manufactured expansion loops, provide a second layer of insulation with air gap to maintain loop flexibility. Install in accordance with the loop manufacturer's written instructions. (Designer Choice)

N. Provide insulation on all piping, equipment, and fixtures that are part of a factory assembly package not otherwise insulated by the manufacture of such packaged equipment. Insulation type and thickenss shall comply with all of the requirements of this section.

3.2 PIPE INSULATION – TYPES & THICKNESSES

A. Provide fiberglass insulation of thickness specified on:

1. Steam Supply (Including steam vent lines from all vessels)

   2-1/2" for pipes 3" and below.

   3" for pipes 4" and over.

2. Steam Condensate (including pump condensate and boiler feed lines)

   1-1/2" for pipes 1-1/4" and below.

   2" for pipes 1-1/2" and over.

3. Cold Water Make-Up:

   1/2" for piping 1-1/4" and below.

   1" for piping 1-1/2" and over

4. Heating Hot Water: (Up to 140°F)

   1" for piping 1-1/4" and below

   1-1/2" for pipes 1-1/2" and over.

5. Heating Hot Water: (141°F to 200°F)

   1-1/2" for piping 1-1/4" and below

   2" for pipes 1-1/2" and over.

6. Chilled Water:

   1/2" for piping 1-1/4" and below. Option: Flexible closed cell insulation

   1" for piping 1-1/2" and over

7. Dual Temperature Water:

   1-1/2" for piping 1-1/4" and below. Option: Flexible closed cell insulation

   2" for piping 1-1/2" and larger

8. Refrigerant Piping: Interior locations, exposed and concealed for suction lines and hot gas bypass lines, if applicable. (NOTE: Insulate liquid line if metering device is mounted at the condensing unit.) Option: Flexible closed cell insulation

   Suction Line:

   1/2" for piping 1-1/4" and below

   1" for piping 1-1/2" and larger

   Hot Gas Bypass: (Liquid Line)

   1" for piping 1-1/4" and below

   1-1/2" for piping 1-1/2" and larger

9. Freeze protection of outdoor piping (over heat tracing tape): 3” thick insulation, with metal jacket.

   a. HVAC: Chilled water and condenser water piping designated on the drawings.

   b. Plumbing: Cold water make-up to cooling tower.

   c. Equipment drain piping.

10. Heat Recovery:

    1" for piping 1-1/4" and below.

    1-1/2" for piping 1-1/2" and larger.

B. Provide flexible closed cell insulation of thickness specified on:

1. Refrigerant Piping: Exterior Locations for suction lines and hot gas bypass lines, if applicable. (NOTE: Insulate liquid line if metering device is mounted at the condensing unit.)

   Suction Line:

   1/2" for piping 1-1/4" and below

   1" for piping 1-1/2" and larger

   Hot Gas Bypass: (Liquid Line)

   1" for piping 1-1/4" and below

   1-1/2" for piping 1-1/2" and larger

2. Cold surfaces of refrigeration equipment, air separators for chilled and heating hot water, and chilled water pumps. 3/4" thickness

3. Hot and chilled water expansion tanks. 3/4" thickness

4. 1” thickness for all water piping within terminal unit cabinets.

5. ½” thickness for condensate drain lines.

3.3 PIPE COVERING (FOAMED PLASTIC TYPE)

A. All joints and seams shall be sealed with a compatible adhesive. Approved adhesives are as follows:

Armstrong World Industries	No. 520
Benjamin Foster Company	No. 85-75 up to 200 degrees F.

Contractor may use Armstrong Self-Seal Armaflex 2000 insulation in lieu of the above wherever 1/2" is specified.

B. Fitting covers shall be fabricated from the foamed plastic pipe insulation or from sheet insulation of the identical material. The fabrication shall be in accordance with manufacturer's instructions, and all seams mitered joints shall be joined using the adhesives described hereinbefore.

C. Pipe insulation in concealed spaces shall require no finish coatings.

D. Pipe insulation in all other areas shall receive two coats of finish of color selected by Architect. Approved finishes are as follows:

Armstrong World Industries WB Armaflex Finish

3.4 EXTERIOR PIPE COVERING

A. Wrapping: Wrap insulation with embossed 0.016" aluminum jacket, orient seam down.

B. Fastenings: Cover shall be held in place with soft aluminum bands on 12" centers.

C. Valves and Fittings:

1. Weatherproof all valves and fittings.

2. Finish: Apply two coats of vapor resistant mastic reinforced with glass fabric over wrapping.

3.5 INTERIOR PIPE COVERING

A. Provide premolded PVC cover on all interior insulated piping exposed in finished spaces. Orient seams up in overhead piping and toward the wall in vertical runs.

B. Provide factory molded fitting covering for fittings and accessories, sealed and held in place by manufacturer’s recommended sealing system.

C. Provide mitered sections of covering for valves.

3.6 ACOUSTIC DUCT LINER

A. All portions of duct designated on the drawings to receive duct liner shall be completely covered with duct liner, adhered to the sheet metal with a 100% coverage of adhesive complying with ASTM C916.

B. Transverse joints shall be neatly butted and there shall be no interruptions or gaps. All transverse joints and all exposed leading edges shall be coated. The black coated surface of the duct liner shall face the airstream.

C. Duct liner shall be secured with mechanical fasteners which shall compress the duct liner sufficiently to hold it firmly in place.

D. Duct liner shall be cut to assure overlapped and compressed longitudinal joints.

E. After installation is complete, blow out the duct system prior to operation to remove any cutting scraps and foreign material remaining in the duct.

3.7 INSULATED PIPE SADDLES

A. Insulated pipe saddles shall be installed at all hangers, rollers or supports in accordance with manufacturer’s written instructions.

B. All piping shall be clean and free of oil, rust and moisture prior to and during support installation.

C. All insulated saddles and accessories shall be stored in a dry area protected from weather before and during installation

D. Seal adjoining butt edges of pipe insulation with approved mastic and tape to insure continuity of the insulation jacket and vapor barrier, especially on cold piping system installations.

END OF SECTION 230230

SECTION 230600

AIR DISTRIBUTION & ACCESSORIES – HVAC

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the contract, including the conditions of the contract (General, Supplementary and other Conditions, if any) and Division 1 as appropriate, apply to the work specified in this section.

B. Refer to Section 230200 for HVAC General Provisions

C. Refer to Section 230210 for HVAC Basic Materials & Methods.

D. This Contractor shall coordinate with the work of Division 26 and the Fire Alarm System vendor for locations and mounting of all duct smoke detectors. These devices are shown on the Mechanical Drawings for reference only to show the intent of the work. All locations shall be determined based on approved shop drawings from the Fire Alarm System vendor and the Contractor for the work of Division 26, Electrical. Mount smoke detectors in the supply and return air stream at each unit in accordance with NFPA 72.

1.2 DESCRIPTION OF WORK

A. This Section includes labor, material, equipment and supervision to provide a complete air distribution system as specified herein and as shown on drawings.

1. Ductwork – Single Wall, Square and Rectangular
2. Ductwork - Single Wall, Spiral Round
3. Flexible Air Duct
4. Air Diffusers, Registers and Grilles

1.3 REFERENCE STANDARDS

A. Refer to Section 230200 for a general description of requirements applying to this section.

B. Requirements established within the portions of the Project Manual titled Division 1, General Requirements, are collectively applicable to the work of this section.

C. IMC (International Mechanical Code).

D. SMACNA (Sheet Metal and Air Conditioning Contractors National Association, Inc.)

E. American Society of Heating, Refrigerating and Air Conditioning Engineers' recommendations in ASHRAE Guide shall apply to this work.

F. ARI Standard 885 - Standard for Estimating Occupied Sound Levels in the Applications of Air Terminals and Air Outlets.

G. UL (Underwriter's Laboratories, Inc.)

H. NFPA 90A and 96 (Designer choice) shall apply to this work.

I. State Fire Prevention Regulations.

1.4 QUALITY ASSURANCE

A. Refer to Section 230210 for a general description of requirements applying to this Section.

1.5 SUBMITTALS

A. Submit shop drawings and product data in accordance with Section 230200.

B. Submit the following:

1. Shop drawings of all sheet metal. Indicate all steel, piping, conduit, and Architectural/Structural features to demonstrate complete coordination. Scale shall not be less than ¼”.

   a. Shop drawings shall indicate the sizes and lengths of each section of ductwork as well as all system components such as coils, VAV boxes, access doors, dampers, diffusers and register locations. Also indicate the type of joints used and where internal acoustic lining or insulation, if required, will be utilized.

   b. The location of the duct runs and the air outlets shall be closely coordinated with all other trades by the sheet metal contractor to avoid interference. The shop drawings shall show the contact surfaces adjacent to the ducts or air outlets and the space assigned for concealment. The drawings shall indicate principal items of equipment, adjacent piping and conduit, etc., the location of which shall be secured from the contractors of other trades.

   c. Sheet Metal Contractor to include resubmissions of the shop drawings to the Engineer. The resubmissions are to include all corrections to previous submissions.

2. Manufacturer's literature and performance data of all equipment and devices.

3. Samples: Furnish color samples, etc., at request of the Architect.

1.6 SUBSTITUTIONS

A. The listed equivalent or substituted manufacturers along with the bidding related contractor shall be completely responsible to comply with all requirements on all contract documents. This shall include, but shall not be limited to space requirements, code clearances, the type, horsepower, capacities, number and size of services required from other trades, including all required ancillary items furnished and installed by other trades. If the manufacturer or related bidding contractor does not comply with these requirements, they shall be responsible for any and all additional costs associated with the changes required by other trades.

1.7 WARRANTY GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, General Requirements.

PART 2 – PRODUCTS

2.1 DUCTWORK (SINGLE WALL, SQUARE AND RECTANGULAR)

A. All ductwork shall be fabricated in accordance with SMACNA "HVAC Duct Construction Standards - Metal and Flexible" latest Edition except as described below. The minimum thickness of metal ductwork is 26 gauge. Fabrication requirements shall be based on ductwork subjected to positive or negative pressures of 4”, 3”, 2” W.G. Ductwork systems shall be sealed to SMACNA "Seal Class “A”, “B”, “C” Standards. Alternatively, "Ductmate" System 45 can be used in accordance with manufacturer's specifications. Drive slip joints are not permitted.

   Exception: For ductwork smaller than 12” x 8”, Contractor may provide slip and drive joints with all joints sealed with Hardcast tape and mastic system.

B. Rectangular ducts for 4”, 3”, 2” W.G. or less, positive or negative pressure shall be per SMACNA Table 1-7, 1-6, 1-5. Longitudinal seams shall be Pittsburgh Lock Type L-l per SMACNA Figure 1-5. Transverse joints shall be standing seam type T -15 per Figure 1-4.

   1. In the event that material size is not compatible with duct size and segmenting must be utilized to fabricate duct, use SMACNA Figure 1-5, seam L-4 (Standing Seam).

C. Joints:

1. Per SMACNA Transverse Joint Reinforcement Table 1-12, only joints T -22, T -25a, T -25b and Proprietary slip on flanges will be acceptable.

2. Joints T -25a and T -25b that have stress fractures from bending will not be accepted.

3. All joints will have butyl gasket 3/16" thick by 5/8" wide installed per manufacturers installation instructions.

D. Ductwork systems for this standard shall be galvanized sheet steel, commercial quality of lock - forming grade, conforming to ASTM coating standards A-525 or A-527 with coating of designation G-60. For corrosive or moist conditions, use coating designation G-90.

1. Where the outer surface of the duct is exposed in finished spaces and is not scheduled for insulation, duct material shall be galvannealed, suitable for field painting by the Mechanical/General Contractor. (Designer Choice/Coordinate with Architect)

E. The size and configuration of each duct shall be indicated on design drawings. Where thicker sheets or different types of materials are required, they shall be specified on the design drawings or in the project specifications.

F. Aluminum Rectangular Ductwork:

1. Aluminum ductwork shall be two B.& S. gauges heavier than specified for the equivalent width steel ductwork. Bracing, supports and joints shall be as specified for steel ductwork.

2. Aluminum ducts shall be used where the ducts are concealed when exhausting saturated air from dishwashing, showers, outside air intakes and similar designated spaces.

3. Dishwashing exhaust ducts shall be made watertight by means of silicone or 3M duct sealant properly installed and compressed at each joint and seam.

G. Kitchen exhaust duct shall have all joints, seams, penetrations and duct-to-hood collar connections with continuous, external, liquid-tight welds.

1. Carbon Steel: Fabricate from 16 gauge, ASTM-A569 hot rolled or ASTM-A366.

2. Stainless Steel: Fabricate from 18 gauge, Type 304, 2D finish.

3. Option: Factory fabricated grease duct system, U .L. listed, which meets all the requirements of NFPA 96.

2.2 DUCTWORK (SINGLE WALL, SPIRAL ROUND)

A. Design Pressure: 2”, 3”, 4"(Designer Choice)

B. Leakage: All ductwork shall meet SMACNA Class "A" leak standards.

C. Fabrication:

1. Gauges, reinforcing angles, seams, joints, fabrication methods, installation methods and practices, duct reinforcement, fabricated dampers and devices installed in duct system, fittings, etc., shall conform to the latest editions of SMACNA standards for construction in accordance with requirements indicated in these specifications.

2. Minimum metal gauges shall be 26 gauge (.019). Follow SMACNA Table 3-2A for Positive pressure and Table 3-2B for Negative pressure.

3. Where the outer surface of the duct is exposed in finished spaces and is not scheduled for insulation, duct material shall be galvannealed, suitable for field painting by the Mechanical/General Contractor.

D. Joints:

1. Duct up to 36" diameter - Male/Female beaded slip joint similar to SMACNA Figure 3-2, joint RT-1 or RT-5, as long as it meets the criteria for the system design pressure. Fittings shall be undersized to fit into spiral duct. All joints shall be secured with a minimum of 4 screws on each duct section (equally spaced). Seal joint with an approved sealant compound, continuously applied prior to assembly of joint and after fastening, making certain that the majority of the sealant resides on the interior of the joint.

2. Duct 37" - 60" diameter: Companion angle Vanstone with full face gaskets having bolt holes punched through prior to insertion of bolts. Gasketing shall be 1/8" thick. Joint is per SMACNA Figure 3-2, joint RT -2 and RT -2A.

3. For all dust collection and particulate carrying duct, SMACNA Figure 3-2, joint RT -3 up to 16" diameter and RT -2 or RT -2A are the only acceptable joints. RT -3 joints do not require any additional sealant as long as the band has gasketing installed by manufacturer. Joints RT -2 and RT -2A require full face gaskets having bolt holes punched through prior to insertion of bolts. Gasketing shall be 1/8" thick. There shall be no fasteners penetrating the duct for collection systems.

4. In lieu of beaded slip connections or Vanstone angle ring connections (the above-mentioned joints), there are proprietary connections that may be used, as long as they meet the pressure criteria set forth in this specification.

2.3 FLEXIBLE AIR DUCT

A. Insulated flexible air duct shall be non-metallic. Air duct shall comply with the latest NFPA Bulletin No. 90A and be labeled as Class 1 Air Duct, U.L. Standard No. 181.

B. Air ducts shall be suitable for working pressure of not less than plus 10.0 and minus 0.5 inches of W.G.

C. Non-metallic air duct shall be two element spiral construction composed of a corrosion resisting metal supporting spiral and a vinyl coated fiberglass base fabric and shall be mechanically interlocked together.

D. Insulation shall be 1-1/2” thick fiberglass flexible blanket with vapor barrier outer jacket of polyethylene or reinforced mylar. Maximum thermal conductance of 0.23 Btu/Hr./SF/Inch at 75 deg. F temperature.

E. Approved manufacturers shall include the Wiremold Company, Flexmaster USA, Owens-Corning, Thermaflex Flex Vent.

OR

A. Core material shall be an acoustical spun bond nylon fabric supported by helically wound galvanized steel. The fabric shall be mechanically fastened to the steel helix without the use of adhesive. The core shall maintain its free area and a center line radius of 1.0 or better.

B. The internal working pressure rating shall be at least as follows with a bursting pressure of at least 2½ times the working pressure.

1. Positive: 6 inches W. G.

2. Negative: 5 inches W. G.

C. The duct shall be rated for a velocity of at least 5,500 feet per minute.

D. Suitable for operating temperatures of at least 250°F.

E. Minimum Acoustic Performance:

1. The insertion loss (dB) of a 9 foot length of duct when tested in accordance with ASTM E 477 at a velocity of 2,500 feet per minute shall be at least:

	125 Hz	250 Hz	500 Hz	1,000 Hz	2,000 Hz	4,000 Hz
1) 8 inch dia.	27	27	32	33	37	33
2) 12 inch dia.	24	23	30	31	37	25

F. Insulation shall be fiberglass flexible blanket with metalized vapor barrier, rated for R6.

G. Manufacturer: Flexmaster USA

2.4 AIR DIFFUSERS, REGISTERS AND GRILLES

A. Air diffusing terminals shall be provided in duct runs on drawings. The diffusers shall properly and uniformly distribute the design air quantity with no objectionable drafts, while maintaining not more than 50 F. P. M. velocity in the occupied portion of the space.

Designers Note: Use Price, Titus, Tuttle & Bailey on all CCHS Projects: All Aluminum.

B. Ceiling Diffusers:

1. Perforated face air diffusers shall be nominal 24 X 24 size, with borders suitable for lay-in ceiling tile application. Diffusers shall provide one, two, three or four-way blow on the drawings. Provide diffusers with perforated face, 3/16" diameter holes on 1/4" staggered centers. Discharge pattern shall be easily adjusted by unlatching and dropping the perforated face, then rotating the pattern controllers. Diffusers shall be heavy gauge steel back pan and face. **Provide adjustable control grid with volume damper. Damper adjustment shall be through the diffuser face. (Designer's Note: NOT Used on CCHS Projects)** Finish shall be factory primed and painted with a baked-on white enamel finish.

   a. Manufacturer: Titus Model PAS. Price Model PDMC

OR

1. Perforated face radial air diffusers shall be nominal 24x24 or 24x48 module size with borders suitable for lay-in ceiling tile application. Diffusers shall provide two-way blow. Provide diffusers with 51 % free area perforated face, 3/16" diameter holes on 1/4" staggered centers. Diffusers shall be heavy gauge steel back pan, maximum 6" deep and face maximum 5/8" deep reveal on face plate. Finish shall be factory primed and painted white.

   a. Face and air chamber shall be provided with two retainer cables.

   b. Manufacturer: Titus Model TriTec. Price HCF

D.N.: Used for high air volume; such as labs, paint bays, kitchens, etc.

2. Square Louvered Diffuser Face:

   a. Square housing, welded steel construction core of square concentric louvers, removable at face of diffuser, round duct connection, with borders suitable for lay-in ceiling tile application.

   b. Diffuser Patterns: Fixed louver face for 1, 2, 3, or 4 direction air flow, direction indicated on drawings. Each diffuser shall be provided with adjustable control grids. **(Designer's Note: NOT Used on CCHS Projects)**

   c. Finish: Matte white finish.

   d. Manufacturers: Titus Model TDC. Price Model SMD

D.N.: Edit to Suit Project

3. Linear Diffusers:

   a. Linear diffusers shall be horizontal continuous slot type with multiple slots per the schedule and drawings. Construction shall be extruded aluminum with 1/2", 3/4" or 1 "

slots. The diffusers shall have integral devices to equalize air flow over the entire length of the diffuser.

b. Multiple sections of diffusers shall be installed in a continuous arrangement, the butt ends shall be provided without flanges to provide a continuous effect. Multiple sections shall be aligned and fastened with alignment pins and slots or a similar method.

c. Linear diffusers shall be provided with adjustable vanes to provide horizontal, vertical or midway patterns of air diffusion. Finish as selected by Architect.

4. Drum Diffusers:

a. Drum diffusers shall be vertical rotating louvered type. Diffusers shall be extruded aluminum with a felt seal around rotating drum. Drum shall rotate up to 30 degrees off center, each direction.

b. Drum diffusers shall have vertical adjustable vanes for horizontal control.

5. VA V Ceiling Diffusers:

a. Diffusers shall be square face, round inlet neck design, complete with integral, thermally, powered thermostats and variable volume type airflow control.

b. Diffusers shall be nominal 24"x24" face size suitable for lay-in, tee bar ceiling grid.

c. Temperature setpoints shall be separately adjustable for heating and cooling, easily accessible near or behind the faceplate.

d. Diffuser faceplate shall swing down or slide back and be retained by hinges, clips or brackets.

e. Control mechanism shall automatically change over between heating and cooling by sensing duct supply air temperature.

f. Diffuser finish shall be white enamel.

g. Manufacturers: Acutherm Therma-Fuser, Thermal Products Corp., Vari-Flow Diffuser, Titus-Rickard, Performance Air Products, Inc.

6. Square Ceiling Supply Diffuser:

a. Square panel ceiling diffusers shall have a 22-gauge steel face panel that captures a secondary 22-gauge panel. The OMNI-AA Price ASPD shall have a heavy gauge aluminum face panel that captures a secondary heavy gauge aluminum panel. The exposed surface of the face panel shall be smooth, flat, and free of visible fasteners. The back of the face panel shall have an aerodynamically shaped, rolled edge to ensure a tight horizontal discharge pattern.

b. The back pan shall be one piece precision die-stamped and shall include an integrally drawn inlet. The diffuser back pan shall be constructed of 22-gauge steel. The finish shall be #26 white. The finish shall be a baked on anodic acrylic paint, with a pencil hardness of HB to H.

c. Back shall have molded insulation blanket. The insulation shall be R-6, foil-backed, and provide an additional 1-inch gap around the neck to install insulated flex duct.

d. Titus model: OMNI Price Model SPD

7. Round Ceiling Supply Diffuser:

a. Round plaque ceiling diffusers shall be constructed of 18-gauge steel and heavy gauge aluminum plaque face. The exposed surface of the plaque shall be smooth and flat. The

airflow discharge pattern shall be field adjusted from horizontal to vertical by repositioning the plaque assembly using the adjusting screws. The plaque assembly shall be constructed as a single inner assembly and must be easily removable.

b. The finish shall be #26 white. The finish shall be a baked on anodic acrylic paint, with a pencil hardness of HB to H.

c. Titus model: R-OMNI Price Model RPD

8. Round Cone Diffusers:

a. Adjustable round cone diffuser, welded steel construction with round neck and removable inner assembly of cones.

b. Air pattern shall be field adjustable from horizontal to vertical.

c. Finish: Matte white finish

d. Titus Model TMRA Price Model RCD

C. Registers & Grilles:

1. Registers and grilles shall be steel construction, fixed single deflection type, with clips and/or flange holes and screws (as required by Architectural finishes) to secure registers to ceiling construction. Face bars shall be inclined 30 degrees. Registers and grilles shall be factory primed and painted with a baked-on white enamel finish.

2. Wall Supply Registers:

a. Provide manufacturer's standard wall registers where shown; of size, shape, capacity, type of materials and components indicated.

b. Register Materials: Steel construction: Manufacturer's standard stamped sheet steel frame and adjustable blades.

c. Register Faces: **Vertical/Horizontal** Straight Blades: **Vertical/Horizontal** blades, individually adjustable, at manufacturer's standard spacing.

d. Register Patterns: Double Deflection: 2 sets of blades in face, rear set at 90 degrees to face set.

e. Register Finishes: Aluminum Enamel: Air-dried aluminum enamel prime finish.

3. Wall Registers: (Security Grade)

a. Provide manufacturer's standard, heavy duty wall registers where shown; of size, shape, capacity, type of materials and components indicated.

b. Register Border: 16-gauge steel construction with mitered comers.

c. Register Louvers: 14-gauge steel louvers on 3/8" centers through the sleeve and wire welded at both ends, supports at 6" centers.

d. Sleeve: 14-gauge steel sleeve welded to grille frame.

e. Steel Mesh Screen: 10-gauge, 3/8" woven steel screen.

f. Register Finishes: Aluminum Enamel: Air-dried aluminum enamel prime finish.

4. Direct Spiral Duct-Mounted Supply Grilles:

a. Aluminum supply grilles shall be direct spiral duct-mounted supply grilles, double deflection of the sizes and mounting types as shown on the plans. The deflection blades shall be available parallel to the long or short dimension of the grille or register. All

supply grilles shall be constructed with radius end caps and foam gaskets for a tight seal to the duct diameter. All supply grilles shall be constructed with a border.

b. Blades shall be constructed of heavy duty extruded aluminum and shall be spaced ¾" apart. Blades shall extend completely through the side frame on each side to ensure stability. Blades shall be individually adjustable without loosening or rattling and shall be securely held in place with tension wire.

c. Air scoop damper/extractor shall be constructed of heavy duty aluminum. The ASD must be operable from the face with a screwdriver.

d. The grille finish shall be as selected by the Architect.

5. Supply Grilles (SG):

a. Aluminum supply grilles shall be available parallel to the long dimension of the grille. All supply grilles shall be constructed with a 11/4-inch wide heavy aluminum border having a minimum thickness of 0.040-0.050 inch. Outer borders shall be assembled and interlocked at the four corners and mechanically staked to form a rigid frame. Screw holes shall be countersunk for a neat appearance.

b. Blades shall be constructed of heavy duty aluminum and shall be contoured to a specifically designed airfoil cross-section to meet published performance data. Where indicated in drawing schedule or plans opposed-blade volume damper shall be constructed of heavy gauge steel or aluminum.

c. The finish shall be #26 white. The finish shall be a baked on anodic acrylic paint, with a pencil hardness of HB to H.

d. Titus model: 272FL Price Model 22

6. Ceiling Return Register (CR):

a. Ceiling registers shall have a perforated face with 3/16-inch diameter holes on 1/4-inch staggered centers and no less than 51 percent free area. Perforated face shall be aluminum according to the model selected. The back pan shall be one piece stamped heavy gauge steel of the sizes and mounting types shown on the plans and outlet schedule.

b. The finish shall be #26 white. The finish shall be a baked on anodic acrylic paint, with a pencil hardness of HB to H. Inside of back pan shall be painted flat black.

c. Titus Model: PAR Price Model PDDR

7. Return Grille (RG):

a. Return grilles shall provide a free area of at least 90%. Outer borders shall be constructed of heavy extruded aluminum with a thickness of 0.040-0.050 inch and shall have countersunk screw holes for a neat appearance. Aluminum grid shall be 1/2 x 1/2 x 1/2 inch.

b. The finish shall be #26 white. The finish shall be a baked on anodic acrylic paint, with a pencil hardness of HB to H.

c. Titus model: 50F Price Model 80

8. Supply, Return, Exhaust and Transfer Grilles (SG, RG, EG & TG):

a. Grilles shall be available parallel to the long dimension of the grille. Construction shall be of steel with a 11/4-inch wide border on all sides. Screw holes shall be countersunk for a neat appearance. Corners shall be welded with full penetration resistance welds.

b. Deflection blades shall be firmly held in place by mullions from behind the grille and fixed to the grille by welding in place. Blade deflection angle shall be available at 35°.

c. The finish shall be #26 white. The finish shall be a baked on anodic acrylic paint, with a pencil hardness of HB to H.

d. Titus model: 300 RL (SG), 355RL (RG, EG, & TG)

Price Model 520FL(SG), 535 FL(RG,EG & TG)

D.N.: Use on all ASD and BSD Schools

9. Ceiling Return Filter Grille (CR):

a. Return filter grilles shall be of size and mounting type as shown on the drawings and schedules.

b. Return grilles shall provide minimum free area of 90%.

c. Borders shall be constructed of heavy extruded aluminum with countersink holes or frame suitable for ceiling finish in each room.

d. The four corners shall be interlocked and mechanically staked to form a rigid frame.

e. Aluminum grid core shall have ½ x ½ x ½ inch openings

f. Return grilles shall be provided with a filter frame that will accommodate a standard 1-inch thick disposable filter to fit the specified duct size. Filter shall be grille module size minus 4 inches. Filter capacity shall be as scheduled on the drawings.

g. Return grille finish shall be white powder coat.

h. Titus Model: 355RLF1. Price Model 535FF

10. Ceiling Louvered Return Filter Grille (CR): **D.N.: Use on all ASD and BSD Schools**

a. Return filter grilles shall be of size and mounting type as shown on the drawings and schedules.

b. Borders shall be constructed of steel with countersink holes or frame suitable for ceiling finish in each room.

c. The four corners shall be interlocked and mechanically staked to form a rigid frame.

d. Deflection blades shall be ½ inch spacing, 45° deflection.

e. Return grilles shall be provided with a filter frame that will accommodate a standard 1-inch thick disposable filter to fit the specified duct size. Filter shall be grille module size minus 4 inches. Filter capacity shall be as scheduled on the drawings.

f. Return grille finish shall be white powder coat.

g. Titus Model: 355RLF1. Price Model 535FF

D. Manufacturers: Provide diffusers, registers and grilles of one of the following:

Anemostat	Price
Carnes Co.	Titus
Krueger	Tuttle & Bailey
Metalaire	Nailor Industries

PART 3 – EXECUTION

3.1 DUCTWORK

A. Dimensions on drawings are inside dimensions. Sheet metal dimensions shall be increased to suit thickness of acoustic duct lining, if applicable. Ductwork that is lined with acoustic lining is or is not insulated.

Designer Note: Coordinate choice in 3.1.A with your choice of liner in Section 230230.

B. Ducts shall be concealed unless otherwise indicated.

C. Changes in direction shall be made with radius bends or turning vanes.

D. Supports shall be galvanized steel for steel ductwork and aluminum for aluminum ductwork.

E. Locate ceiling air diffusers, registers, and grilles on "Reflected Ceiling Plans". Unless otherwise indicated, locate units in center of acoustical ceiling modules.

F. Do not install ductwork directly above any electrical equipment.

G. Ductwork shall be supported per SMACNA Standards except as follows:

1. Rivet or screw to side of duct when using flat strap hangers. Rivet or screw to bottom of duct when using trapeze hangers.
2. Extend hangers down the side of the duct at least 9"; pass hangers under ducts less than 9" deep.
3. Space hangers not more than 8' on centers for ducts up to 18" wide and 4' on centers for ducts over 18" wide.
4. Wire hangers are not acceptable.
5. Support ductwork from building structure with expansion bolts, rods, steel angles or channels installed to meet existing or new building conditions.
6. Drilling into the roof deck is not permitted.
7. Driving nails into anchors is not permitted.

H. Air Flow Control:

1. Major take-offs: Install volume control dampers.
2. Branches: Install volume control dampers in all branches and at tap in branch take-off connections.
3. Elbows: Use unvaned elbows with throat radius equal to width of duct and full heel radius; provide turning vanes where full throat and heel radius are not possible.
4. Transitions: Make transitions in ducts as required by structural or architectural interferences.
   a. Proportion airways to compensate for any obstructions within duct.
   b. Avoid dead ends and abrupt angles.
   c. Do not exceed 15 degrees slope on sides of transitions.

I. Ductwork from humidifiers to 20'-0" downstream shall have watertight joints. **(D.N.: OMIT IF NOT USED)**

J. For all exterior single wall, square or rectangular ductwork, ensure that the top of all horizontal ductwork is crowned to minimize accumulation of weather on top of the finished insulation system jacket specified in Section 230230.

K. Ductwork on the roof shall be supported by an engineered, prefabricated hanger system specifically designed for installation on the roof without roof penetrations, flashing or damage to the roofing material. The system shall consist of bases made of high density polypropylene plastic with additives for UV protection, hot dipped galvanized structural steel frames, hangers, fasteners, rods, etc. The system shall be completed and designed to fit the ductwork installed under actual conditions of service. The system shall be furnished as manufactured by PHP Systems & Design or Anvil International Haydon H-Block. (Designer Choice)

3.2 LOUVERS

A. When open louvers are provided on a job, and the louver is open on the back, the contractor shall provide a 2" deep drip pan. Pan shall extend the full length of the louver. Drip pan shall be fabricated from a minimum of 24 gauge galvanized sheet steel. Cross break pan for rigidity. All seams to be welded.

B. Drip pans shall be securely fastened to building structure. Do not hang pans from ductwork, piping systems or equipment. Contractor shall submit shop drawings, showing pan detail and methods of support.

OR

3.2 LOUVERS

A. Locate and place louver units level, plumb and at indicated alignment with adjacent work.

B. Use concealed anchorages where possible.

C. Provide perimeter reveals and openings of uniform width for sealants and joint fillers.

D. Repair damaged finishes so no evidence remains of corrective work. Return items that cannot be refinished in the field to the factory, make required alternations and refinish entire unit or provide new units.

E. Protect galvanized and non-ferrous metal surfaces from corrosion or galvanic action by applying a heavy coating of bituminous paint on surfaces that will be in contact with concrete, masonry or dissimilar metals.

3.3 FLEXIBLE AIR DUCT

A. When flexible duct is used for final connection between duct mains on branches and diffusers on registers. The maximum length of flexible ductwork shall be 5'-0" in length.

B. Flexible ductwork shall be properly hung at the tap collar in order to prevent eventual wear and damage to the flexible duct.

C. The ceiling tile system should not be considered a support on which to lay flexible duct. Refer to SMACNA Standards for proper installation.

3.4 DUCT SYSTEM LEAK SEALING

A. Joints in duct systems at duct heaters, air monitors, fire dampers, sound traps, supply air terminals including air handling light fixtures, shall be sealed to prevent air leakage.

B. All duct joints and seams in medium pressure and high pressure duct systems shall be sealed to SMACNA Seal Class" A" Standards to prevent air leakage.

C. In the event there is in excess of 5% air leakage indicated in low pressure duct systems, it shall be the Contractors responsibility to seal the duct system. The amount of sealing necessary shall be that required to obtain the design air quantity at each terminal.

D. Duct sealing shall be by means of high velocity duct sealants such as Hardcast and/or Neoprene gaskets. Type of sealant and method of application shall conform to recommendations in SMACNA high velocity duct construction standards.

3.5 DUCTWORK TESTING

A. The following ductwork shall be pressure leak tested:

1. Supply ductwork
2. Return ductwork
3. Exhaust ductwork
4. Outside air intake ductwork

B. All tests shall be conducted in accordance with AABC National Standards.

C. Ducts to be tested at 100% maximum of static pressure before any duct is insulated externally and concealed in accordance with SMACNA Standards.

D. Calculate the allowable leakage using leakage factor of 5% of Design Air Flow.

E. Select a limited section of duct for which the estimated leakage will not exceed capacity of the test apparatus.

F. Connect the blower and flow meter to the duct section and provide temporary seals at all openings of the ductwork.

G. Start the blower motor with the inlet damper closed. Increase pressure until the required level is reached.

H. Read the flow meter and compare the leakage in cfm. Reading should be 5% or less of design flow for the duct segment being tested.

I. If reading is more than 5% of design flow, depressurize duct, repair all leaks and retest until 5% or less of design flow is obtained.

J. Complete test reports and obtain Owner's witness signature.

K. Remove all temporary blanks and seals.

L. Warning: Do not overpressure duct.

3.6 EQUIPMENT

A. Test apparatus shall consist of an airflow measuring device, flow producing unit, pressure indicating devices and accessories necessary to connect the metering system to the test specimen.

B. The Contractor conducting tests shall arrange for or provide all temporary services, all test apparatus, all temporary seals and all qualified personnel necessary to conduct the specified testing.

C. Test apparatus shall be accurate within plus or minus 7.5% at the indicated flow rate and test pressure and shall have calibration data or a certificate signifying manufacture of the meter in conformance with the ASME Requirements for Fluid Meters. Verification of above, to be supplied to Owner upon request.

D. Pressure differential sensing instruments shall be readable to 0.05" scale division for flow rates below 10 cfm or below 0.5" w.g. differential. For flows greater than 10 cfm scale divisions of 0.1" are appropriate. U-tube manometers should not be used for reading less than 1" of water.

E. Liquid for manometers shall have a specific gravity of 1 (as water) unless the scale is calibrated to read in inches of water contingent on use of a liquid of another specific gravity, in which case

the associated gauge fluid must be used.

F. Instruments must be adjusted to zero reading before pressure is applied.

3.7 TEST REPORT

A. Log the project and system identification data.

B. Enter the fan CFM, the test pressure, and the leakage class specified by the designer.

C. Enter an identification for each duct segment to be tested.

D. Calculate the allowable leakage factor. Enter this number on the report for each test segment.

E. Conduct and record the field tests. If the sum of the CFM measured is less than or equal to the sum of the allowable leakage, the test is passed. Record the date(s), presence of witnesses and flow meter characteristics.

F. Maintain a mechanical duct plan of all tested duct segments. Plan to include duct segment identification and dates tested.

G. Test reports shall be submitted as required by the project documents.

3.8 LABELING

A. At all fire damper, smoke damper and combination fire/smoke damper locations, access doors in ductwork shall be identified with a permanent placard of red-white-red laminated commercial grade plastic construction, minimum one-half inch high capital letters, reading, “FIRE DAMPER”, “SMOKE DAMPER”, “FIRE/SMOKE DAMPER” as appropriate for the installation. Attach securely to face of access door with brass screws at each corner, sealed airtight.

3.9 DOUBLE-WALL PHENOLIC DUCT SYSTEM

A. Air Leakage: Ductwork system air leakage shall be in accordance with the requirements of the relevant jurisdiction. (Consult the DOE (US Department of Energy) ComCheck/ResCheck or the relevant authority for applicable codes/standards).

B. Support:

1. It shall be the responsibility of the installer to ensure that the ductwork system is properly and adequately supported. A number of support systems are approved for use by AQC Industries. It shall be the responsibility of the installer to ensure that the chosen method of support is compatible with ductwork fabricated from the Pal Phenolic Duct System and AQC Industries.

2. Supports on straight runs of the Q Duct Ductwork System shall be positioned at center’s not exceeding 10 ft. for ductwork sections fabricated in 10 ft. lengths, and 13 ft. for ductwork sections fabricated in 13 ft. lengths.

3. Additionally, ductwork shall be supported at changes of direction, at branch duct connections, tee fittings, etc.

4. All ductwork accessories such as dampers shall be independently supported.

C. Hangers and Supports:

1. Hanger Materials: SMACNA approved duct supports shall be utilized in accordance with SMACNA Standards for Phenolic Duct.

2. Penetration into the Q Duct System duct is not permitted.

3. Trapeze and Riser Supports: Steel shapes complying with ASTM A 36/A 36M.

4. Exterior Duct Supports:

a. To meet all SMACNA and ASHRAE requirements.

b. Supports to be installed on the outside finished Q Duct System.

c. Supports to be manufactured by PHP System/Design, Miro or approved equal.

D. Storage and Handling:

1. Care shall be exercised in the handling and transportation of Q Duct ductwork sections in order to prevent physical damage.

2. All Q Duct ductwork sections shall be stored under cover, clear of the ground or roof and protected from the weather and sunlight by an opaque and light colored waterproof material. In cases where the ductwork sections are to be stored for prolonged periods, the open ends of the ductwork sections shall be sealed with a polythene sheet or other suitable material to prevent the ingress of foreign matter.

END OF SECTION 230600

SECTION 230950

TESTING & BALANCING OF MECHANICAL SYSTEMS

PART 1 – GENERAL

1.1 JOB CONDITIONS

A. Systems shall be completely installed and in continuous operation as required to accomplish the tests.

B. Heating, ventilating and air conditioning equipment shall be completely installed and in continuous operation as required to accomplish the balance work specified.

C. Adjust and balance shall be performed when outside conditions approximate design conditions indicated for heating and cooling functions.

D. Make at least two inspections of the mechanical systems during construction to verify that balancing procedures may be accomplished. Report findings to the Architect/Engineer/Construction Manager.

E. Balancing firm shall balance Mechanical System two (2) times. The first time shall be considered a rough balance. Any discrepancy in air flow shall be addressed to the Architect/Engineer/Construction Manager. The final balancing will be accomplished after review of rough balance reports.

F. The final balancing reports shall be submitted and approved prior to project's being considered complete; i.e., commencement of warranties.

1.2 ENGINEER QUALIFICATIONS

A. The firm shall be an independent organization having no affiliation with construction contractors, equipment sales or design engineering.

B. The firm shall specialize in balancing heating, ventilating and air conditioning systems.

C. The firm shall show proof of having balanced and tested at least five projects of similar size and scope.

D. All field work shall be under the direct supervision of a registered Professional Engineer who is a full-time employee of the balancing firm.

E. The firm shall be certified by and a member of the AABC (Associated Air Balance Council), or NEBB (National Environmental Balancing Bureau).

1.3 REPORT

A. Data Sheets:

1. Submit data sheets on each item of testing equipment required.
2. Include name of device, manufacturer’s name, model number, latest date of calibration and correction factors.

B. Report Forms:

1. Submit specimen copies of report forms.
2. Forms shall be 8-1/2 x 11 inch paper for loose-leaf binding, with blanks for listing of the required test ratings and for certification of report.
3. Reports shall be on standard forms published by AABC or NEBB.

PART 2 – PRODUCTS

2.1 AIR BALANCE INSTRUMENTS

A. Alnor Velometer with probes and alnor pitot tube.

B. Rotating Vane Anemometer: 4 inch size.

C. ASHRAE Standard Pitot Tubes, stainless steel 5/16 inch outside diameter, lengths 18 inches and 36 inches.

D. Magnehelic Differential Air Pressure Gauges, 0 to 0.5 inches, 0 to 1.0 inch and 0 to 5.0 inches water pressure ranges, each arranged as a portable unit for use with a standard Pitot tube.

E. Combination Inclined-Vertical Portable Manometer, range 0 to 5.0 inches water.

2.2 WATER BALANCING INSTRUMENTS

A. 30 Inch Mercury U-Tube Manometer, 200 psig, with 3 valve bypass assembly and return wells or mercury check valves.

B. Inspector's gauge testing set.

C. Water Differential Pressure Gauge, 4-1/2 inch dial, 0 to 100 psi range.

D. Pressure gauge measurement points, quick connect couplings, 1/4 inch psi.

2.3 SYSTEM PERFORMANCE MEASURING INSTRUMENTS

A. Insertion Thermometers, with graduation at 0.5 degrees F for air and 0.1 degrees F for water.

B. Sling Psychrometer.

PART 3 – EXECUTION

3.1 GENERAL REQUIREMENTS

A. Arrange and pay for all tests.

B. Notify Architect/Engineer/Construction Manager at least three working days in advance of test and conduct in presence of Architect/Engineer/Construction Manager.

C. Tests to be performed prior to insulation, covering or concealment.

D. Provide signed report of completion of test with signature of witnesses. Report shall indicate:

1. System Tested
2. Date
3. Specified test requirements and actual testing results

E. The balancing firm shall report to and review the work required with the Architect/Engineer before beginning field balance work. The balancing firm shall make at least two inspections of the air systems during construction and shall report his findings in writing to the Architect/Engineer.

F. The balancing firm shall cooperate with the Architect/Engineer/Construction Manager and the Mechanical Contractor to effect smooth coordination of the balancing work with the job schedule.

G. The balancing firm shall be responsible for getting the various systems into proper operation. They shall enlist the aid of the equipment suppliers and Mechanical Contractor as may be required to effect proper operation consistent with the contract plans and specifications.

H. When the balancing firm cannot balance a belt-driven piece of equipment with the supplied belts and sheaves, inform the Mechanical Contractor that the Mechanical Contractor shall provide additional sheaves as spelled out in other Division 23 Sections.

3.2 CIRCULATING WATER SYSTEM TEST

A. All piping tests shall be applied not only to piping, but also to all devices and equipment connected

thereto with the exception of control valves, boilers or any other equipment which may be damaged by the test pressure. All valves shall be full open.

B. Test at 100 psi hydrostatic pressure for 6 hours:

1. Record pressures each hour
2. Repair all leaks
3. Retest until 6 hours can be completed with no leaks or loss of pressure.

C. After completion of successful test, strainers shall be cleaned, then system shall be backflushed and strainers cleaned again.

(DESIGNER NOTE: OMIT 3.3 IF COVERED BY PLUMBING SPECS – VERIFY)

3.3 DRAINAGE AND CONDENSATE SYSTEMS TESTING (INCLUDING EXTERIOR PIPING)

A. Disconnect all equipment and devices which may be damaged by test pressures.

B. Plug or cap lines.

C. Test each piping system for leaks in accordance with local inspection test code.

D. Repair all leaks noted.

E. Minimum test shall be to fill system to top vent stack and roof drain, and not show a drop of more than 3 inches for 1 hour. Test shall be performed before piping is concealed.

F. Secure certificate from Municipal Inspector of acceptable test.

(DESIGNER NOTE: OMIT 3.4 IF COVERED BY PLUMBING SPECS – VERIFY)

3.4 DOMESTIC WATER & MAKE-UP WATER PIPING TESTING (INCLUDING EXTERIOR PIPING)

A. Test domestic water piping at 10 psig hydrostatic pressure for 4 hours. Drop in pressure shall not be greater than 1 psig. Use gauge calibrated in one pound increments. If test is under the jurisdiction of local inspector, his requirements may be used provided they are not less than above. Furnish signed report of test and witness.

3.5 DUCTWORK TESTING

A. Witness testing conducted by the Mechanical Contractor per Section 230600, PART 3: EXECUTION.

3.6 STEAM SYSTEM TEST

A. All piping tests shall be applied, only to piping. Piping test shall be made after piping is hung, supported, anchored and guided, and before insulation is applied. When leaks occur in the system, the leaks shall be repaired and retested until no leaks are present. Do not apply test pressures to control valves, coils or traps.

B. Low pressure steam and condensate piping shall be hydrostatically tested at 100 psig and with steam at 15 psig.

C. After the steam test is completed, all safety valves, strainers, traps, etc., shall be cleaned of foreign matter and the system shall be operated to prove a positive and quiet steam system circulation.

3.7 FUEL OIL SYSTEM TEST

A. All piping tests shall be applied only to piping. Piping test shall be made after all piping is hung, supported, anchored, and guided. When leaks occur in the system, the leaks shall be repaired and retested until no leaks occur.

B. All piping shall be tested under pressure or vacuum in accordance with the appropriate articles in NFPA Standards 30 and 31 that govern the installation.

C. All piping tests shall be witnesses by the **Construction Manager/General Contractor (Choose One)** and the Owner's Representative. A written record of the test results and witnesses shall be submitted to the **Architect/Engineer (Choose One).**

3.8 BALANCING PROCEDURE

A. Air System Balance:

1. With the fan supply system set to handle normal minimum outdoor air, the balancing firm shall perform the following tests and compile the following information:

   Air Handling Equipment

   a. Design Conditions:

      (1) CFM Supply Air

      (2) Static Pressure

      (3) CFM Fresh Air

      (4) Fan RPM

   b. Installed Equipment:

      (1) Manufacturer

      (2) Size/Model Number

      (3) Motor HP, Voltage, Phase, Full Load Amperes

   c. Field Test:

      (1) Fan Speed

      (2) No Load Operating Amperes

      (3) Fan Motor Operating Amperes

      (4) Calculated BHP

   d. Test for Total Air:

      (1) Size of discharge, return air and outside air ducts.

      (2) Number and locations of Velocity Readings taken.

      (3) Duct Average Velocity

      (4) Total CFM

      (5) Outside Air CFM

      (6) Return Air CFM

   e. Individual Outlets (Diffusers, Registers and/or Grilles):

      (1) Identify each outlet or inlet as to location and area and fan system

      (2) Outlet, manufacture and type

      (3) Outlet size

(4) Outlet free area, core area, or neck area

(5) Required FPM and test velocity found for each outlet.

(6) Required CFM and test results for each outlet

f. Test for room/space pressurization

(1) As noted on the drawings or as required, final balancing shall include room/space pressure adjustments

(2) As confirmed in writing by the Engineer, the supply, return, and/or exhaust air shall be adjusted to required pressure relationship (positive, neutral, negative) while maintaining required total air changes.

Designer Note: required by CCHS, verify for any other sensitive project design.

2. After completion of tests, adjustment and balancing under minimum fresh air conditions, set the system for 100% fresh air. Repeat the total CFM tests to check field versus design conditions. The results under 100% fresh air cycle shall agree with conditions found under "minimum fresh air operation" before the system is considered to be in balance. Adjustments of the proper dampers shall be made to achieve balance.

3. Testing and adjusting of individual outlets shall be performed under procedures recommended by the manufacturers of the outlets. All outlets shall be set for air pattern required and all main supply air and return air dampers to be adjusted and set for design CFM indicated. Any required changes in air patterns, settings, etc., necessary for achieving correct air balance, shall be provided by this Contractor. Total CFM of all outlets shall agree with total CFM of all branches and the grand total shall agree with the air volume for the fan(s).

B. Water Balance:

1. Water balance shall include heating water, chilled water and condenser water systems. The balancing agency shall perform the following tests, compile data and submit reports.

2. Pumps:

a. Design Data

(1) GPM, head

(2) RPM, BHP

b. Installed Equipment

(1) Manufacturer, Size

(2) Type Drive

(3) Motor HP, Volts, Cycles and Phase

(4) Full Load Amperes

c. Field Test

(1) Discharge Pressures: Full flow & no flow

(2) Suction Pressures: Full flow & no flow

(3) Operating Head and GPM

(4) No Load Amperes (where possible)

(5) Full Flow Amperes, No Flow Amperes

(6) Calculated BHP

3. Heating and/or Cooling Elements Including Loop Water to all terminal Units:

a. Design Data:

(1) MBH Specified, GPM Specified

(2) Entering Water Temperature (EWT)

(3) Entering Air Temperature (EAT)

(4) Water Temperature Drop (DTW)

(5) Element Type Specified

b. Field Test:

(1) Identify each element as to location

(2) Required water temperature drop corrected for item (3) above

(3) Actual entering air and water conditions (temperature and GPM)

(4) Adjust element until required temperature drop is obtained

DESIGNER NOTE: keep the following paragraph whenever you have critical building operations that are sensitive to vibration. Most measures in Section 230300 take care of equipment isolation issues. TAB agencies usually ignore this test report, unless there is a problem during start-up.

C. Take vibration measurements on all motors 1 HP and above; submit written report.

1. Furnish instruments and perform vibration measurements as specified in Section 230300: Vibration Isolation – HVAC. Provide measurements for all rotating HVAC equipment including centrifugal compressors, pumps, fans and motors.

2. Record initial and final measurements for each unit of equipment on test forms. Where vibration readings exceed the allowable tolerance and efforts to make corrections have proved unsuccessful, forward a separate report to the Engineer.

D. In addition to the above work, the Balancing Firm shall check the operation of all automatic temperature control equipment; verify all thermostat, aquastat, etc., set-points and operations; and enlist the aid of the Mechanical Contractor and the Control Subcontractor to make necessary adjustments where required.

END OF SECTION 230950

SECTION 260000

GENERAL PROVISIONS – ELECTRICAL

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other conditions, if any) and Division 1 as appropriate, apply to the work of this Section.

B. The specification or drawing and the design features or resulting construction disclosed, are the property of Furlow Associates, Inc., and shall not be reproduced without written permission.

C. **Refer to Section 078413 for Through-Penetration Firestop Systems. (DN: For BSA+A Specs)**

D. **Refer to Section 083113 for Access Doors and Frames (DN: For BSA+A Specs)**

1.2 DESCRIPTION OF WORK (Add or Delete Systems)

A. Provide all materials, equipment, labor, services and all appurtenances required to completely install and satisfactorily operate the various systems. The items listed below are for general guidance only and do not necessarily include the entire requirements for the project.

1. Coordination with other trades
2. Electrical service
3. Interior feeders
4. Lighting and power panels
5. Lighting branch wiring
6. Power wiring
7. Lighting fixtures and lamps
8. Wiring devices
9. Connections for electrically operated equipment
10. Fire alarm and detection system
11. Telephone raceway system
12. Motor control centers
13. Lightning protection system
14. Related work as herein described or otherwise defined under the heading "Related Work".

B. Wherever the term "provide" is used, it shall be understood to mean both "furnish" and "install".

1.3 RELATED WORK

A. Equipment specified in sections of Divisions 1 thru 23 that require electric power supply.

B. Work related to this trade as defined on the following contract drawings:

Architectural/Structural

HVAC

Plumbing

1.4 SITE CONDITIONS

A. Attention of all bidders is called to the necessity for a careful inspection of the site, its present condition and encumbrances, the extent of the work, the protection to be afforded to adjacent properties or structure, availability of utilities, the extent and nature of the material required to be excavated and the amount of fill and removal. He shall also determine local or site limitations which will affect construction.

1.5 PERMITS, INSPECTIONS AND ORDINANCES

A. All work shall be executed and inspected in accordance with local and state ordinances, rules and regulations and the requirements of public utilities having jurisdiction. The contractor shall secure and pay for all permits, inspections and connections required.

B. The Electrical Contractor shall furnish a certificate of inspection to the Owner at the time of completion.

C. Requirements of the following organization shall be considered minimum:

1. National Electrical Code
2. National Electrical Safety Code
3. OSHA
4. Local City and County Codes

D. Reference to technical societies, trade organizations and governmental agencies are in accordance with the following:

1. ANSI - American National Standards Institute
2. ASTM - American Society for Testing Materials
3. IEEE - Institute of Electrical and Electronics Engineers, Inc.
4. NEC - National Electrical Code
5. NEMA - National Electrical Manufacturer's Association
6. NFPA - National Fire Protection Association
7. MSS - Manufacturer's Standardization Society
8. IES - Illuminating Engineers Society
9. ETL - Engineering Testing Laboratories
10. EIA - Electronic Industries Association
11. OSHA - Occupational Safety and Health Administration
12. Federal Specifications
13. UL - Underwriters Laboratories, Inc.

1.6 QUALITY ASSURANCE

A. Provide adequate supervision of labor force to assure that all aspects of the contract documents are fulfilled.

B. Contractor to provide manufacturer’s written certification that the following equipment has been installed and will operate correctly and in accordance with the manufacturer’s warranty requirements.

Fire Alarm and Detection System

(ADD OTHER SPECIAL SYSTEMS)

C. Testing:

1. After completion of the work, the entire wiring system shall test entirely free from grounds, short circuits, opens, overloads and improper voltage.

2. The grounding system shall be tested for a resistance of 25 ohms or less.

3. Perform testing as follows: Arrange and pay for all tests, provide all equipment, materials and labor to perform test. Notify Engineer and Owner three (3) working days before tests are to be made. Conduct tests in the presence of the Engineer or authorized representative. Repeat tests after defects are corrected.

D. Special Engineering Services: In the instance of complex specialized electrical power and signaling systems, and other similar systems, the installation and final connections of these systems shall be made by and/or under the supervision of a competent installation and service engineer who shall be a representative of the respective equipment manufacturer. Any and all expenses of these installation and service engineers shall be borne by this Contractor.

1.7 COORDINATION

A. As a requirement of this project, the Electrical Contractor shall furnish coordination for his equipment and layouts with other subcontractors furnishing equipment and services for Divisions 1 thru 23. Any and all contractors who install their equipment or furnish services prior to coordination, any contractor who changes their equipment or services after coordination has occurred, without notifying associated subcontractors, shall be held responsible for making all required changes with no additional cost to the Owner. Or delay in construction time. This coordination will include conduit layout to allow access to equipment for maintenance.

B. The Mechanical, Plumbing and Electrical Contractors are responsible to coordinate all manufacturer's recommended circuit breakers, starters, disconnects and fuse sizes for all equipment. Submission of a shop drawing will certify that this has been completed.

C. The drawings and specifications reflect the type, number and size of services required for the equipment the design is based upon. Should the supplying subcontractor elect to furnish an alternate piece of equipment requiring difference services and/or space conditions, he shall inform the subcontractor furnishing those services and be held responsible to pay for all required changes as part of this contract.

1.8 SUBMITTALS

A. Shop Drawings:

1. Shop drawings shall be submitted in accordance with Division 1 of these specifications except where herein modified.

NOTE: Submittals will only be reviewed once and resubmittals will be reviewed once. Any other submittals will be billed to the Contractor at the Engineer's standard rates.

2. Shop drawings comprising complete catalog cuts, performance test data for electrical equipment as required by other sections of Division 26 shall be submitted for review checking. The Contractor shall review these shop drawings for conformance to contract documents prior to submission and affix contractor's signature to each submittal certifying that this review has been done. By approving and submitting shop drawings, product data, wiring diagrams and similar materials, the Electrical Contractor represents that he and/or his subcontractor has determined and verified materials, field measurements and field construction data that relates to the work, and has checked and coordinated this information with all of the Divisions 1 thru 23 subcontractors.

3. All shop drawing submittals shall have the following identification data, as applicable, contained therein or permanently adhered thereto:

   a. Project name

   b. Project number

   c. Sub-Contractor's, Vendor's and/or manufacturer's name and address.

   d. Product identification.

   e. Identification of deviation from the contract documents.

   f. Applicable contract drawings and specification section number.

   g. Shop drawing title, drawing number, revision number, and date of drawing and revision.

   h. Resubmit revised or additional shop drawings as requested.

   i. Wherever shop drawings or vendor's standard data sheets indicate work to be done "by others", it shall be the responsibility of the Contractor making the submission to identify by name, the Contractor who is to do this work. If the Contractor named is other than the Contractor making the submission, the shop drawing submission must be reviewed by the named Contractor and bear his mark of approval, prior to submission to the Architect/Engineer.

   j. Where equipment proposed differs from that shown on the drawings or specified, he shall submit for approval drawings showing the manner in which the layout is affected by the substitution.

   k. The Contractor shall keep one copy of approved shop drawings at the job site, filed in a suitable metal container. The shop drawings shall be cataloged and kept in good repair, and shall be available for use by the Owner, Architect and Engineer.

   l. No equipment shall be ordered, fabricated, etc., before approval of shop drawings.

1.9 SUBSTITUTIONS

A. Whenever a material, article, piece of equipment or system is identified in the following specification or indicated on the drawings by reference to manufacturers' or vendors' names, trade names, catalog numbers or the like, it is so identified for the purpose of establishing the basis of the Bid.

B. Substitution approval must be obtained and included as an addendum item prior to the submission of the bid. An approved substitution shall not be considered as an approval for the contractor or an equipment vendor to deviate from the written portion of the specifications unless so stated in the addendum.

C. The drawings illustrate the space allocated for equipment and the Contractor shall install the equipment accordingly. If changes are required in the building or arrangement due to substitution of equipment, the Contractor making the substitution must pay for the necessary modifications.

D. The listed equivalent or substituted manufacturers along with the bidding related contractor shall be completely responsible to comply with all requirements on all contract documents. This shall include, but shall not be limited to space requirements, code clearances, the type, horsepower, capacities, number and size of services required from other trades, including all required ancillary items furnished and installed by other trades. If the manufacturer or related bidding contractor does not comply with these requirements, then they shall be responsible for any and all additional costs associated with the changes required by other trades.

1.10 LUBRICATION

A. Furnish, install and maintain all required lubrication of any equipment operated prior to acceptance by the Owner. Lubrication shall be as recommended by the equipment manufacturer.

B. Provide one year's supply of lubricants to Owner at date of acceptance.

C. Verify that required lubrication has taken place prior to any equipment start-up.

1.11 ADJUSTMENT & CLEANING

A. Adjust and clean equipment to be placed in proper operation condition.

1.12 EQUIPMENT START-UP

A. Verify proper installation by manufacturer or his representative.

B. Advise General Contractor 2 days prior to actual start-up.

C. Verify proper operation. Obtain signed statement by manufacturer or his representative that equipment is operating within warranty requirements. Submit statement to General Contractor.

1.13 OPERATION AND MAINTENANCE INSTRUCTIONS

A. Properly and fully instruct Owner's personnel in the operation and maintenance of all systems and equipment.

B. Insure that the Owner's personnel are familiar with all operations to carry on required activities.

C. Such instruction shall be for each item of equipment and each system as a whole.

D. Provide report that instruction has taken place. Include in the report the equipment and/or systems instructed, date, contractor, Owner's personnel, vendor, and that a complete operating and maintenance manual has been reviewed.

E. Manual shall include all instructions on operation, maintenance, repair parts list, lubrication requirements, brochures, catalogue cuts, wiring diagrams, piping diagrams, control sequences, service requirements, names and addresses of vendors, suppliers and emergency contacts. Three manuals shall be provided.

F. Submit manuals for review prior to operating instruction period. Manuals shall be 8-1/2 x 11" with hard cover, suitably bound.

G. Training

1. Electrical Contractor shall be responsible for coordination of Owner training. Factory employed technician(s) shall provide training, including demonstration and education on the system capabilities, operation and maintenance. Training sessions shall be minimum 4 hours (maximum 8 hours), and shall be provided for each shift of workers. Scheduled training shall be coordinated at least two 92) weeks in advance with the Owner and the Commissioning Agent.

2. Video Documentation: Furnish three (3) copies of a professionally taped video and three (3) copies of professionally prepared drawings demonstrating the following:

- Emergency Generator System
- Security System
- Fire Alarm System
- Integrated Access Control
- Clock and Speaker System

- VFD's
- MDF/IDF
- Stage Sound System
- Stage Dimming Rack

1.14 TOOLS

A. All equipment furnished by the Contractor which requires special tools or devices other than those normally available to the maintenance or operating staff shall be furnished in duplicate to the Owner, sufficiently marked, packed or boxed for staff usage. The tools provided shall be listed by the Contractor identified as to their use or the equipment applicable in a written transmittal to the Owner.

1.15 CLEANING AND FINISHING

A. After equipment start-up and all operating tests have been made and the system pronounced satisfactory, each respective Contractor shall go over the entire project, clean all equipment, etc., installed by him and leave in a clean and working condition. Any surfaces found marred after this final cleaning shall be refinished or replaced by each Contractor at no cost to the Owner.

1.16 OPERATING AND MAINTENANCE MANUALS

A. Three complete sets of instructions containing the manufacturer's operating and maintenance instructions for each piece of equipment shall be furnished to the Architect. Each set shall be furnished before the contract is completed. The following identification shall be inscribed on the covers: the words "OPERATING AND MAINTENANCE INSTRUCTIONS", the name and location of the building, the name of the Contractor and the name of the Architect and Engineer. Flysheet shall be placed before instructions covering each subject. The instruction sheets shall be approximately 8-1/2 by 11 inches, with large sheets of drawings folded in. The instructions shall include, but shall not be limited to, the following:

Approved wiring and control diagrams, with data to explain the detailed operation and control of each component.

A control sequence describing start-up, operation and shutdown.

Operating and maintenance instructions for each piece of equipment, including lubrication instructions.

Manufacturer's bulletins, cuts and descriptive data.

Parts lists and recommended spare parts.

1.17 SERVICE INTERRUPTION

A. All service interruptions to the electric or related systems, whether during regular working hours or at any other time, must be coordinated with the Owner. All such interruptions shall be so scheduled and planned as to require a minimum of time and shall occur only during a mutually satisfactory period.

1.18 INTERPRETATION OF SYSTEMS

A. The interpretation of the Architect will be final in the event there is a lack of understanding of the full scope or requirements of the systems under this contract.

1.19 LAYOUTS

A. On small scale drawings, i.e., 1/8" - 1'-0", the approximate location of the electrical branch circuit items such as receptacle, telephone, grounding and equipment outlets are shown to indicate their existence. The exact location of these items and their related raceways are governed by structural

conditions, coordination with the work of other trades and the Architect's final decision. By accepting a contract, the Contractor agrees to install the work in accordance with the above statement and within the contract price.

PART 2 – PRODUCTS

2.1 MATERIAL

A. All material shall be new and of good quality. Material shall conform to all accepted trade standards, codes, ordinances, regulations, or requirements governing same, and shall be approved before being installed.

B. The Architect reserves the right to require the Contractors to submit samples of any or all articles or materials to be used on the project.

C. Where any device or equipment is herein referred to in the singular number, such as "the panel", this reference shall be deemed to apply to as many such devices or equipment as are required to complete the installation as shown on the drawings or specified.

D. All materials and equipment used in the work shall comply with the standards of recognized authorities such as UL, NEMA, IEEE, ETL, IES and EIA in every instance where such standards have been established for the particular type of materials to be installed.

E. All similar pieces of equipment or materials of the same type or classification used for the same purpose shall be of the same manufacturer.

F. All manufactured equipment shall have factory applied finishes.

2.2 CONCRETE

A. Concrete shall be in accordance with Section 03300, or ACI-613. Designer choice if 03300 is not used.

B. The 28-day minimum compressive strength shall be 3000 psi.

2.3 WARRANTY

A. Wherever in the specification sections of this division, reference is made to a specific warranty period, this warranty shall be in addition to and not a limitation of other rights the Owner may have against the Contractor under the contract documents.

PART 3 – EXECUTION

3.1 INSPECTION

A. Prior to performing the work, examine areas and conditions; check and verify all dimensions, under which the work is to be installed and notify the Architect in writing of conditions and dimensions detrimental to the proper and timely completion of the work. Do not proceed until authorization is given by the Architect.

3.2 LAYING OUT WORK

A. The Contractor is responsible for the accuracy of all lines, elevations, and measurements, grading and utilities and must exercise proper precaution to verify figures shown on drawings before laying out work and will be held responsible for any error resulting from his failure to exercise such precaution.

3.3 WORKMANSHIP

A. Install all work neat, trim, parallel and plumb with building lines in accordance with standard trade practice acceptable to the Architect.

3.4 PRODUCT DELIVERY, STORAGE AND HANDLING

A. Protect all equipment and materials from damage during transportation, storage and installation.

3.5 PROTECTION

A. Protect all work, equipment and materials during construction up to the time of acceptance by the Owner.

Arrange and design the protection to prevent damage from infiltration or dust, debris, moisture, chemicals and water. Cap or plug electrical raceways.

B. Protect all surfaces against damage from welding, cutting, burning, or similar construction functions. This protection shall be accomplished by care in operations, covering and shielding. Special care is directed to exposed finished masonry, metal or wood surfaces and painted surfaces. Corrective measures required shall be accomplished by the trade which made the original installation when and as directed by the Architect at the expense of the Contractor.

C. Cover and protect all lighting fixtures as may be necessary until completion of the work. Replace damaged fixtures or damaged fixture parts as directed by the Architect at no cost to the Owner.

D. Do not install devices, polished metal fittings or parts until adjoining tile or masonry work is completed.

E. Maintain and replace protective covering when so directed by the Architect until the work is ready for acceptance.

3.6 CUTTING & PATCHING

A. Furnish information to the General Contractor as to sizes and locations of recesses required to install panel boxes and other equipment or devices. If the information is late or incorrect, this Contractor shall, at his own expense, have the trade which originally installed the work do the required cutting and patching.

B. Perform all cutting of concrete or other material for passage of raceways as required to install the work.

C. Close all such openings around raceways with material as specified under the heading "SEALING".

D. Install concealed work in place for the mason to wall-in as he carries up the walls; otherwise, this Contractor will be responsible as stated in the first paragraph.

3.7 SEALING

A. Where raceways pass through fire-rated walls and floors, seal opening with RTV foam.

B. Seal raceways entering the building to conform to the requirements of the NEC.

3.8 OFFSETS AND MODIFICATIONS

A. Furnish and install all offsets necessary to install the work and to provide clearance for the work of other trades.

B. Maintain adequate clearance as directed by the Architect/Engineer.

C. Incidental modifications necessary to the installation shall be made as necessary and at the direction and/or approval of the Architect.

3.9 SLEEVES

A. Furnish and install sleeves for all raceways passing through floors and walls. Sleeves shall be Schedule 40 galvanized steel pipe and shall extend 1" above finished floor surface. Where sleeves are set in interior walls, they shall finish flush with the wall.

B. Furnish and install watertight sleeves for all raceways extending through foundation walls into crawl spaces, mechanical rooms or basement areas from building exterior or from unexcavated areas to building interior. Sleeve shall consist of extra heavy pipe sleeve with anchor flange. Space between raceway and the sleeve shall be sealed with modular wall and casing seal similar to Thunderline Corporation "Link-Seal",, Metraseal or approved substitute. Install seal in strict accordance with the manufacturer's recommendations.

3.10 EXCAVATION

A. The excavation shall be of the open-trench method and to the depths and widths as may be necessary. The Contractor shall do all excavation required in connection with his work. Bottoms of trenches shall be excavated to a uniform grade. All materials excavated shall be deposited on the side of the trenches and beyond the reach of slides. Excavated material shall not be piled where it will interfere with traffic.

B. No conduits shall be bedded directly on rock. They shall be cushioned by a 6-inch layer of crushed stone or gravel of selected grade, of size to pass through a 3/4" mesh sieve. Not less than 30% shall be fine which will pass through a 3/8" mesh sieve.

C. Where excavation is required through tree root areas, roots shall be saw cut, treated with pruning paint and covered with burlap. Burlap shall be wet and shall be protected and maintained in a moist condition during entire period of exposure. Backfill shall be carefully placed and hand-tamped to a minimum of 6" above roots.

D. Bidder shall base his estimate upon the presumption that all excavation required in the performance of this Contract will be earth. If rock is encountered, Contractor will be reimbursed for the additional work required to remove same based upon the unit cost established in the proposal.

E. All detached boulders or loose stone not exceeding 1 cubic yard, all topsoil, sand, gravel, clay, rubbish, walls or other subgrade construction, and all other materials of every name and nature which can be removed without breaking up with pneumatic breakers or explosives shall be considered earth excavation.

F. All rocks, attached boulders, boulders exceeding 1 cubic yard, walls or other subgrade construction and materials which cannot be removed without breaking up with pneumatic equipment or explosives shall be considered rock excavation.

G. Before commencing any rock excavation for which extra compensation is to be paid, a rock contour drawing shall be prepared by the Contractor and checked by the Architect. The width shall be based on 2'-0". This rock contour drawing and width allowance will be used to compute the quantity of rock for which the Contractor will be reimbursed at the unit price established.

3.11 SHORING AND PUMPING

A. The Contractor shall provide all shoring, bracing or sheet piling necessary to maintain the banks of his excavation and shall take out same as the work progresses and filling in has been accomplished. Shoring shall be in accordance with OSHA Standards.

B. The arrangement of shoring must be such as to prevent any movement of the trench banks and consequent strains on the conduits. Shoring shall be provided to prevent damage to work installed by other trades.

C. The Contractor shall do all pumping required to keep his excavations free of water. The water shall be conveyed in piping or watertight troughs a sufficient distance that it will flow from the site and not affect other work being performed.

3.12 BACKFILLING

A. After work in trenches has been completed, they shall be filled with good, clean, fine earth in 8" layers and shall be pneumatically tamped before the next layer of material has been filled in. The backfill shall be free of excavated rock, cinders, stones, brickbats or other debris.

B. Wherever rock is removed, the Contractor shall secure and fill select clean earth to a minimum depth of 3'-0" above the top of the conduit. Unless otherwise indicated, no rock shall be deposited in the trench fill. This clean earth fill shall be procured other than from the site unless permission for earth borrow from the site is granted by the Architect. If site borrow is permitted, the topsoil removal, relocation and finished grading will be accomplished as directed by the Architect.

C. Under no circumstances shall excavated material be left where it will interfere with the Owner's or other Contractor's operations.

D. All earth and other materials taken from the trenches and not required for backfilling shall be deposited where directed, or removed from the premises as directed by the Architect.

E. Any rock removed from the excavation shall be removed from the project site by the Contractor.

F. Trenches which pass under wall footings or within 18" of column footings shall be backfilled with clean concrete. To secure adequate foundation support, the method and depositing of the concrete fill shall be as directed by the Architect. To prevent the concrete from adhering to the conduits, necessary conduit protection shall be applied.

3.13 FOUNDATIONS FOR EQUIPMENT/HOUSEKEEPING PADS

A. Provide all foundations for equipment installed under this specification Division and/or as indicated on plans.

B. Construct concrete foundations on structural floor slabs or on grade in the manner or as required by the approved shop drawing details of the manufacturer or the utility company.

C. Provide and install concrete.

D. Metal reinforcement shall be deformed steel bars or cold drawn steel wire, or fabricated forms of these materials as required.

E. Furnish anchors of size and number noted, with bottom plates and sleeves.

F. Forms shall conform to the shape, lines, grades, and dimensions of the concrete, required by the approved shop drawing details of the equipment manufacturers, or approved on the Contractor's Equipment room layouts. They shall be sufficiently tight to prevent leakage of mortar and shall be braced or tied together to maintain position and shape. Forms shall be moved in such manner as to insure the complete safety of the structure.

G. All exposed corners or edges shall be chamfered. All burrs, fins, irregularities of forming or spillage shall be removed and the surface float or trowel finished to a smooth, straight surface.

H. Housekeeping Pads: Provide 4” thick, and size as required by approved shop drawings, concrete pad for all equipment installed on floor. Pad shall be steel reinforced with all edges and surfaces finished as described above. When installing over existing concrete, surface of existing pad shall be prepped using a bushing tool to rough in entire surface. Whether pouring over new or existing concrete, provide U-shaped rebar anchors set in epoxy to secure pad to pad.

3.14 ITEMS RECESSED IN MASONRY CONSTRUCTION

A. Wherever boxes, electric panels, equipment, devices, access panels, and similar items of electrical construction are installed in exposed masonry construction, the Contractor shall utilize and submit for approval items of such size, height, and arrangement to conform to the corresponding masonry unit.

The Contractor shall include as part of this contract, the necessary offsets, adjustments and relocations necessary to conform with the instructions of the Architect as to the final location of the equipment item in the exposed masonry.

B. As part of his contract and before the purchase of the items hereinbefore mentioned, the Contractor shall notify the Architect of such modifications in the building arrangement that will be necessary to accommodate the proposed equipment.

3.15 ROOF FLASHINGS

A. All conduit extending through roofs shall be provided with watertight flashing and counterflashing as hereinafter described.

B. Furnish and install standard counterflashing fittings on the conduit or properly designed clamped counterflashing with caulking as directed by the Architect/Engineer.

3.16 PAINTING

A. Refinish all factory applied finishes that have been damaged to match the original finish as directed by the Architect.

B. Prime coat all steel furnished under this Division with material and methods as described in another Section under the heading "PAINTING".

3.17 EQUIPMENT CONNECTIONS

A. Provide required wiring, raceways and final connections for all equipment provided by this Division and Divisions 1 thru 23.

B. Make final connections in accordance with wiring diagrams obtained from equipment manufacturer.

C. Rough-in in accordance with approved shop drawings from the manufacturer or supplier of the equipment. Rough-in prior to shop drawing approval will be subject to change without adjustment to contract cost.

3.18 BALANCING

A. The system of feeder and branch circuits for power and lighting shall be connected to panel busses in such a manner as to electrically balance the connected load as close as is practicable. Should the Owner disclose any unfavorable conditions reacting on the service, this Contractor shall make such changes as may be suggested to balance the load.

3.19 GUARANTEE

A. All work shall be guaranteed to be free from defects for a period of one year of operation from date of acceptance by the Owner unless otherwise specified in Division 1.

B. Guarantee shall be extended on an equal time basis for all non- operational periods due to failure within the guarantee period.

C. Contractor to include an 11 month “walk-thru” of the building system with representatives of the School District, Architect, Engineer and the Construction Manager. The purpose is to establish a list of corrective work that relates to operational issues, material/installation deficiencies.

END OF SECTION 260000

SECTION 260055

ELECTRICAL IDENTIFICATION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. This section is a Division 26 Basic Materials and Methods Section, and is part of each Division 26 Section making reference to electrical identification specified herein.

1.2 DESCRIPTION OF WORK

A. Types of electrical identification specified in this section include the following:

Cable conductor identification.

Operational instructions and warnings.

Danger signs.

Equipment/system identification signs.

PART 2 – PRODUCTS

2.1 MANUFACTURERS

A. Subject to compliance with requirements, provide products of one of the following (for each type of marker):

W. H. Brady Co.

Ideal Industries, Inc.

Seton Name Plate Co.

3M Electrical Products

2.2 ELECTRICAL IDENTIFICATION MATERIALS

A. Provide manufacturer's standard products of categories and types required for each application. Where more than single type is specified for an application, selection is Installer's option, but provide single selection for each application.

2.3 COLOR-CODED PLASTIC TAPE

A. Provide manufacturer's standard vinyl tape not less than 7 mils thick by 3/4" wide.

B. Colors: Unless otherwise indicated or required by governing regulations, provide tape color as indicated in Paragraph 3.2.B.

C. Tape shall be of Type 3M Scotch 35 for color coding, Scotch Super 33+ for splices and Tem Flex 1700 for general use.

2.4 CABLE/CONDUCTOR IDENTIFICATION BANDS

A. Provide manufacturer's standard vinyl cloth, self-adhesive cable/conductor markers of wrap-around type; either pre-numbered, plastic-coated type, or write-on type with clear plastic, self-adhesive cover flap; numbered to show circuit identification.

2.5 BAKED ENAMEL DANGER SIGNS

A. Provide manufacturer's standard "DANGER" signs of baked enamel finish on 20-gage steel; of standard red, black and white graphics; 14" x 10" size except where 10"x 7"is the largest size which can be applied where needed, and except where larger size is needed for adequate vision; with

recognized standard explanation wording (as examples: HIGH VOLTAGE, KEEP AWAY, BURIED CABLE, DO NOT TOUCH SWITCH).

2.6 ENGRAVED PLASTIC-LAMINATE SIGNS

A. Provide engraved stock melamine plastic laminate, in sizes and thicknesses indicated, engraved with engraver's standard letter style of sizes and wording indicated, punched for mechanical fastening except where adhesive mounting is necessary because of substrate.

B. Thickness: 1/16" for units up to 20 sq. in. or 8" length; 1/8" for larger units.

C. Fasteners: Self-tapping stainless steel screws, except contact-type permanent adhesive where screws cannot or should not penetrate substrate.

2.7 LETTERING AND GRAPHICS

A. Coordinate names, abbreviations and other designations used in electrical identification work, with corresponding designations shown, specified or scheduled. Provide numbers, lettering and wording as indicated or, if not otherwise indicated, as recommended by manufacturers or as required for proper identification and operation/maintenance of electrical systems and equipment.

PART 3 – EXECUTION

3.1 APPLICATION AND INSTALLATION

A. Coordination: Where identification is to be applied to surfaces which require finish, install identification after completion of painting.

B. Regulations: Comply with governing regulations and requests of governing authorities for identification of electrical work.

3.2 CABLE/CONDUCTOR IDENTIFICATION

A. Apply cable/conductor identification on each cable and conductor in each box/enclosure/cabinet where wires of more than one circuit or communication/signal system are present. Match identification with marking system used in panelboards, shop drawings, contract documents, and similar previously established identification for project electrical work.

B. Conductor Color Coding:

1. All conductors used in all systems shall have insulation that is inherently colored. All conductors of a system performing the same function shall be colored alike throughout the project.

2. Equipment Grounding Conductors:

a. Standard and/or general feeders or circuits shall be green.

b. Isolated feeders or circuits shall be green with yellow stripe.

3. On larger conductors, where colored insulation is not available, colored tape adhesive vinyl bands 3/4" width may be installed 6" maximum from the end of the conductors. Where passing through pull boxes without splice, each conductor shall be banded.

4. Power system conductor colors shall be as follows:

a. 120/208 Volt System

Phase A - Black

Phase B - Red

Phase C - Blue

Neutral - White or Gray

b. 277/480 Volt System

Phase A - Brown

Phase B - Orange

Phase C - Yellow

Neutral - White or Gray

3.3 DANGER SIGNS

A. In addition to installation of danger signs required by governing regulations and authorities, install appropriate danger signs at locations indicated and at locations subsequently identified by Installer of electrical work as constituting similar dangers for persons in or about project.

B. High Voltage: Install danger signs wherever it is possible, under any circumstances, for persons to come into contact with electrical power voltages higher than 110-120 volts.

3.4 EQUIPMENT/SYSTEM IDENTIFICATION

A. Install engraved, plastic laminate sign on each major unit of electrical equipment in building, including central or master unit of each electrical system including communication/signal systems, unless unit is specified with its own self-explanatory identification or signal system. Except as otherwise indicated, provide single line of text, 1/2" high lettering on 1-1/2" high sign (2" high where 2 lines are required), white lettering in black field. Provide text matching terminology and numbering of the contract documents and shop drawing. Provide signs for each unit of the following categories of electrical work:

1. Panelboards, electrical cabinets and enclosures.
2. Access panel/doors to electrical facilities.
3. Major electrical switchgear, main and feeder circuit breakers and/or disconnects..
4. Power transfer equipment.
5. Fire Alarm Master Station and Annunciator.
6. Paging and Intercommunication Systems
7. Security Control Panels and Annunciator.

B. Install signs at locations for best convenience of viewing without interference with operation and maintenance of equipment. Secure to substrate with fasteners, except use adhesive where fasteners should not or cannot penetrate the substrate.

3.5 JUNCTION AND PULL BOX IDENTIFICATION

A. Emergency Systems: Each junction and pull box cover shall be painted orange. Use black indelible liquid marker to label "EMERG." in 3/8" letters minimum.

B. Fire Alarm System: Each junction and pull box cover shall be painted red. Use black indelible liquid marker to label "F.A." in 3/8" letters minimum.

C. Feeders Shown on Single Line Diagram: Each junction and pull box shall be marked with black indelible liquid marker with the assigned feeder number "FDR #38" in 3/8" letters minimum.

END OF SECTION 260055

SECTION 260110

RACEWAYS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other conditions, if any) and Division 1 as appropriate, apply to the Work specified in this Section.

B. Refer to Section 260000 for General Provisions - Electrical.

1.2 DESCRIPTION OF WORK

A. Types of raceways in this section include the following:

Rigid metal conduit

Intermediate metal conduit

Electrical metallic tubing.

Polyvinyl chloride conduit (Exterior Underground Only)

Flexible metal conduit.

Liquid-tight flexible metal conduit.

Surface raceway.

Multi-Cell Raceway

Wireways.

1.3 REFERENCE STANDARDS

A. Refer to Section 260000 for a general description of requirements applying to this Section.

1.4 QUALITY ASSURANCE

A. Refer to Section 260000 for a general description of requirements applying to this Section.

1.5 WARRANTY/GUARANTEE

A. All work and materials are subject to the general warranty as described in the General Conditions of the Contract and in Division 1, GENERAL REQUIREMENTS.

1.6 COORDINATION

A. The drawings and details there upon are scheme and/or diagrammatic in nature, and indicate the need and intent of the design. These are to be used for general guidance only. It shall be the responsibility of the Electrical Contractor to coordinate, with other Division Subcontractors, the installation of all raceways, raceway supports, junction boxes and required fittings. This coordination will include conduit layout to allow access to equipment for maintenance.

B. This coordination shall be carried out prior to actual installation; this shall be done to eliminate the possibility of conflicts between trades on items such as access, clearances and maintenance issues that may arise after completion of construction.

C. Should the coordination not be carried out prior to installation, and a conflict exists, the installing contractor shall remove and reinstall the equipment as required to clear the conflict at no additional cost to the Owner and no delay in project completion.

PART 2 – PRODUCTS

2.1 MATERIALS AND EQUIPMENT

A. Rigid Metal Conduit:

1. Raceway: Full weight, heavy wall rigid steel with zinc coating conforming to ANSI-C80.1.
2. Fittings: Cast malleable iron fittings with threaded hubs, insulated throat and zinc protective coating.
3. Subject to compliance with requirements, provide products of one of the following:

   Allied Tube and Conduit Corporation

   LTV Steel Tubular Products Co.

   Wheatland Tube

B. Intermediate Metal Conduit:

1. Raceway: Light weight, rigid steel, hot dipped galvanized manufactured in accordance with UL1242.
2. Fittings: Cast malleable iron fittings with threaded hubs, insulated throat and zinc protective coating.
3. Subject to compliance with requirements, provide products of one of the following:

   Allied Tube and Conduit Corporation

   LTV Steel Tubular Products Co.

   Wheatland Tube

C. Electrical Metallic Tubing:

1. Raceway: Light weight, thin wall, rigid steel, hot dipped galvanized manufactured in accordance with ANSI C80.3.
2. Fittings: Raintight, insulated throat, compression type with zinc protective coating.
3. Subject to compliance with requirements, provide products of one of the following:

   Allied Tube and Conduit Corp.

   LTV Steel Tubular Products Co.

   Wheatland Tube Co.

D. Polyvinyl Chloride Conduit:

1. Raceway: Heavy wall, rigid non-metallic, schedule 40 with bell type end, designed for above ground exposed applications, direct earth burial, and concrete encasement.
2. Fittings: Polyvinyl chloride, heavy duty, glue type, designed for Schedule 40 application.
3. Subject to compliance with requirements, provide products of one of the following:

   Allied Tube & Conduit

   Carlon

   Queen City Plastics, Inc.

   Scepter Electric Systems

E. Flexible Metal Conduit:

1. Raceway: Construct of single strip, flexible, continuous, interlocked, and double-wrapped steel, galvanized inside and outside.
2. Fittings: Steel, insulated throat, with zinc protective coating.
3. Subject to compliance with requirements, provide products of one of the following:

   AFC

   Alflex Corp.

   Electri-Flex Company

F. Liquid-Tight Flexible Metal Conduit:

1. Raceway: Construct of single strip, flexible, continuous, interlocked, and double-wrapped, galvanized inside and outside, coat with liquid-tight jacket of flexible polyvinyl chloride.
2. Fittings: Steel, water and oiltight, insulated throat, with zinc protective coating.
3. Subject to compliance with requirements, provide products of one of the following:

   AFC

   Alflex Corp.

   Electri-Flex Company

G. Multi-Cell Raceway

1. Raceways: Shall be a multi-cell raceway system for concrete encasement applications, 20 ft. lay length sections of 4” PVC outer shell type C with four (4) 1-1/4” nominal pre-lubed PVC innerducts pre-installed. The innerducts shall be color coded (white/grey/orange/green). Raceway shall be similar to Carlon Telecom System Part No. MXSS4S-020.
2. Fittings: Raceway shall be provided with a complete line of, but shall not necessarily be limited to, couplings, offsets, 90 deg., 36” radius bends, adapters, hold-down clips, end-caps and other accessories as needed for a complete system.
3. Interior Use Only:

   a. Raceways: Shall be multi-cell raceway system for use inside building applications. 10 ft. length sections of 4” electrical metallic tubing with four (4) 1-1/4” nominal pre-lubed PVC innerducts pre-installed. The innerducts shall be color-coded (white/grey/orange/green). Raceway shall be similar to Carlon Telecom System Part No. MESS4S-010.

   b. Fittings: Raceway shall be provided with a complete line of, but shall not necessarily be limited to, couplings, offsets, 90 deg., 36” radius bends, adapters, hold-down clips, end-caps and other accessories as needed for a complete system.
4. Subject to compliance with requirements, provide products of the following:

   Carlon Electrical Products.

H. Surface Raceway:

1. Dual Service Raceway: Two-piece wireway, base to be .054" galvanized steel, cover to be .040" galvanized steel. Complete unit shall have a cross sectional area of 7.2 square inches. Finish shall be color as selected by Architect. Wireway to be similar to Wiremold Series 4000, Cat #V4000B and V4000C.

2. Fittings: Wireway shall be provided with a complete line of, but shall not necessarily be limited to, couplings, offsets, elbows, adapters, hold-down clips, end-caps and other components and accessories as needed for a completed system.

3. Subject to compliance with requirements, provide products of one of the following:

   Wiremold Co.

   Walker, Butler Manufacturing Co.

   Hubbell

I. Wireways:

1. Furnish electrical wireways of the type, size, and style for each service indicated. Wireway shall be a complete assembly including but not necessarily limited to, couplings, offsets, elbows, adapters, hold-down clips, end-caps and other components and accessories as needed for a complete system.

2. System shall fulfill wiring requirements as indicated in contract documents, and shall comply with applicable portions of Article 362 of the National Electrical Code.

3. Subject to compliance with requirements, provide products of one of the following:

   Circle AW Products Co.

   The EMF Company, Inc.

   Hoffman Engineering Company

   Square "D" Company

J. The above items shall include the statement "Approved Equal" and/or "Approved Substitute". This statement requires that the product or item be in compliance with the written intent of this specification and the submission meets the requirements of Section 260000.

PART 3 – EXECUTION

3.1 INSTALLATION OF ELECTRICAL RACEWAYS

A. Install electrical raceways in accordance with manufacturer's written instructions, applicable requirements of NEC and NECA "Standard of Installation", and complying with recognized industry practices.

B. Coordinate with other work as necessary to interface installation of electrical raceways, wireways and required components.

C. Raceways used for distribution, feeders, or branch circuits shall be a minimum size of 3/4" or equal equivalent cross-sectional area. Raceways used for control and signal shall be a minimum size of 1/2" or equal equivalent cross-sectional area.

D. All raceways shall be concealed within the building construction, where indicated on the floor plans surface raceway shall be installed. Should it be impossible or impracticable to install a raceway concealed and surface raceway is not indicated, the Contractor shall consult with the Architect or Engineer for approval prior to installation.

E. All raceways installed in ceiling cavities and exposed within mechanical spaces shall be run parallel with building lines and installed level and square at the proper elevation/height.

F. Complete the installation of electrical raceways before starting the installation of cables/wires within the raceway.

G. Furnish and install one (1) nylon or fiberglass pull cord in each empty raceway. Each empty raceway shall be cleaned, capped, and tagged as to its termination location.

H. Install liquid-tight flexible metal conduit for connections to motors and for other electrical equipment when subject to movement and vibration, and also where subjected to one or more of the following conditions:

1. Exterior locations.
2. Moist or humid atmosphere when condensation can be expected to accumulate.
3. Corrosive atmosphere.
4. Subjected to water spray.
5. Subjected to dripping oil, grease or water.

I. Install Electrical Metallic Tubing for building interior electrical work except:

1. Underground
2. In gravel, cinder, concrete or other sub-base floor construction.
3. Horizontal runs in concrete floor slabs.
4. Where exposed to the elements.
5. In masonry construction below finished grade.
6. Vertically in poured concrete walls.

J. Refer to Section 260000 for excavation, shoring and pumping, concrete and backfilling requirements.

K. Where and whenever possible, install horizontal electrical raceways as tight to building construction as possible and above water, drain and steam piping. A separation of at least six (6) inches shall be maintained between electrical conduits and hot water and steam piping.

L. In accordance with NEC requirements, install Rigid or Intermediate Metal Conduit where Electrical Metallic Tubing is not permitted.

M. In all instances where recessed type panelboards are installed, furnish and install one (1) one inch raceway for each two (2) future circuits for which "space" or "spare" provisions have been made in the panelboard. These raceways shall extend between the panelboard cabinet and a convenient location above an access panel or a removable tile ceiling construction and capped.

3.2 CLEANING

A. Upon completion of installation of raceways, inspect interiors of raceways; remove burrs, dirt and construction debris.

END OF SECTION 260110

SECTION 260120

WIRES AND CABLES

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. This section is a Division 26 Basic Materials and Methods section and is part of each Division 26 Section making reference to wires and cables specified herein.

1.2 DESCRIPTION OF WORK

A. Electrical wire and electrical cable work is indicated by drawings and specifications.

B. Arrange for and coordinate with the Utility Company and pay any and all costs in conjunction with the 25KV primary service from the point of connection to 25KV pad-mounted transformer.

C. Types of wire, cable and connectors in this section include, but not limited to the following:

Copper conductors.

Tap type connectors.

Split-bolt connectors.

D. Refer to other sections of Division 26 for, but not limited to, raceways, connections used in conjunction with wire and cable work.

E. Applications for wire, cable and connectors required for project are as follows unless otherwise indicated:

1. Primary Service Circuitry.
2. Power Distribution Circuitry.
3. Appliance and Equipment Circuitry.
4. Motor Branch Circuitry.
5. Control Circuitry.
6. Signal/Communication Circuitry.

PART 2 – PRODUCTS

2.1 MANUFACTURERS

A. <u>Wire and Cable</u>

Anaconda Wire and Cable Co.

Advance Wire and Cable, Inc.

American

Cerro Wire and Cable Co.

Electrical Conductors, Inc.

General Cable Corp.

Hitemp Wires, Inc.

Rome Cable Corp.

Southwire Company

Triangle PWC,, Inc.

The Okonite Co.

General Electric Co.

Rockbestos Surprenant Cable Corp.

Connectors

Burndy Corp.

Eagle Electric Mfg. Co., Inc.

Gould, Inc.

Ideal Industries, Inc

Joslyn Mfg. and Supply Co.

O-Z/Gedney Co.

Pyle National Co.

Thomas and Betts Co.

2.2 WIRE, CABLE AND CONNECTIONS

A. Except as otherwise indicated, provide wire, cable and connectors of manufacturer's standard materials, as indicated by published product information; designed and constructed as recommended by manufacturer, and as required for the installation. Minimum wire and cable size is #12 AWG for power and branch circuits and #14 AWG for control and signal/communication circuits unless otherwise indicated.

B. Wire: Provide factory fabricated wire of sizes, ratings, materials and types indicated for each service. Where not indicated, provide proper selection as determined by Installer to comply with project's installation requirements and NEC standards. Select from the following types, materials, conductor configurations, insulation and coverings:

UL Type: THHN

UL Type: TW

UL Type: THW

UL Type: THWN

UL Type: TF

UL Type: XHHW

UL Type: AC (Armor Clad)

UL Type: MC (Metal Clad)

UL Type: ACTHH (Health Care Facility Cable)

UL Type: NM (Non-Metallic)

UL Type: MI (Mineral Insulated) Fire Pump Feed

UL Type: MC (2-Hour Metal Clad) Fire Pump Feed

Material: Aluminum (Service Entrance Only)

Copper

Conductors: Solid (AWG 14 to AWG 10 only).

Conductors: Concentric-lay-stranded (standard flexibility)

Outer Covering: Nylon

Outer Covering: Thermoplastic

C. Connectors: Provide factory fabricated metal connectors of sizes, ratings, materials, types and classes as required for each service. Where not indicated, provide proper selection as determined by Installer to comply with installation requirements and NEC standards. Select from the following types, classes, kinds and styles.

Type: Pressure

Type: Crimp

Type: Threaded

Class: Insulated

Class: Non-insulated

Kind: Copper (for CU to Cu connection).

Style: Butt connection

Style: Elbow connection

Style: Combined "T" and straight connection

Style: "T" connection.

Style: Split-bolt parallel connection

Style: Tap connection

Style: Pigtail connection

D. 25KV Cable: Provide factory fabricated and tested primary service cable; underground residential distribution (URD) type cable, size #1/0 AWG solid aluminum conductor with 25KV cross-linked polyethylene insulation (XLP) with tinned or coated copper wire full size concentric neutral as approved by the Utility Company.

E. 25KV Terminations: Provide 25KV terminations for 25KV #1/0 AWG solid aluminum cable as approved by the Utility Company in quantities required by the Utility Company.

PART 3 – EXECUTION

3.1 INSTALLATION

A. Install electrical cables, wires and connectors, in compliance with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation", and in accordance with recognized industry practices.

B. Coordinate cable and wire installation work with electrical raceway and equipment installation work, as necessary for proper interface. Pull conductors together where more than one is being installed in a raceway. Use pulling compound or lubricate, where necessary; compound must not deteriorate conductor or insulation. Use pulling means including fish tape, cable or rope which cannot damage raceway. Rope must be used as pulling means when pulling wires or cables into plastic conduit and duct. Keep conductor splices to a minimum and install in junction boxes only. No splices shall be permitted within conduit. Install splices and tapes which have mechanical strength and insulation rating equivalent or better than conductor. Use splice and tape connectors which are compatible with

conductor material.

C. Installation of 25KV primary service cable with the Utility Company.

D. Deliver 25KV cable terminations to the Utility Company for installation and connection.

3.2 FIELD QUALITY CONTROL

A. Prior to energization, test cable and wire for continuity of circuitry and also for short circuits. Correct malfunctions when detected.

B. Subsequent to wire and cable hook-ups, energize circuitry and demonstrate functioning in accordance with requirements.

C. Test 25KV cable after installation using D.C. high potential (Hi-Pot) testing. All testing shall be performed in accordance with cable manufacturer's recommended specifications. Keep a complete record of all tests and submit to the Engineer upon completion. Testing shall be performed by an independent cable testing company or service.

END OF SECTION 260120

SECTION 260135

ELECTRICAL BOXES & FITTINGS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. This section is a Division 26 Basic Materials and Methods section, and is a part of each Division 26 section making reference to electrical wiring boxes and fittings specified herein.

1.2 DESCRIPTION OF WORK

A. Types of electrical boxes and fittings in this section include the following:

Outlet boxes.

Junction boxes.

Pull boxes.

Conduit bodies.

Bushings.

Locknuts.

Knockout closures.

Sealing Fittings.

Explosion-Proof junction box.

PART 2 – PRODUCTS

2.1 INTERIOR METALLIC OUTLET BOXES

A. Provide galvanized flat rolled sheet steel interior outlet non-gangable wiring boxes, of types, shapes and sizes, including box depths, to suit each respective location and installation; construct with stamped knockouts in back and sides and with threaded screw holes with corrosion-resistant screws for securing box covers and wiring devices.

B. Provide outlet box accessories as required for each installation, including mounting brackets, wallboard hangers, extension rings, fixture studs, cable clamps and metal straps for supporting outlet boxes, which are compatible with outlet boxes being used and fulfilling requirements of individual wiring situations. Choice of accessories is Installer's option.

C. Manufacturer: Subject to compliance with requirements, provide interior outlet boxes of one of the following:

Appleton Electric Co.

Bell Electric/Square D Co.

Pass and Seymour, Inc.

RACO, Inc.

Steel City/Midland-Ross Corp.

2.2 INTERIOR NON-METALLIC OUTLET BOXES

A. Provide non-metallic electrical interior outlet non-gangable wiring boxes,of types, shapes and sizes, including box depths, to suit each respective location and installation; construct with non-metallic, high impact strength polyvinyl chloride material with knockouts in sides and integral cable clamps.

B. Provide non-metallic outlet box accessories as required for each installation, including mounting brackets, wallboard hangers, extension rings, fixture studs, and metal straps for supporting outlet boxes, which are compatible with outlet boxes being used and fulfilling requirements of individual wiring situations.

C. Manufacturers: Subject to compliance with requirements, provide interior outlet boxes of one of the following:

Carlon

Sedco

Certainteed

Hoffman

2.3 WEATHERPROOF OUTLET BOXES

A. Provide corrosion resistant cast-metal weatherproof outlet wiring boxes, of types, shapes and sizes, including depth of boxes, with threaded conduit ends, cast-metal face plates with spring-hinged waterproof caps suitably configured for each application, including face plate gaskets and corrosion-resistant fasteners.

B. Manufacturer: Subject to compliance with requirements, provide weatherproof outlet boxes of one of the following:

Arrow-Hart Div., Crouse-Hinds Co.

Bell Electric/Square D Co.

Harvey Hubbell, Inc.

O-Z/Gedney Co.

Slater Electric Co.

C. Refer to Section 260140 – WIRING DEVICES for exterior receptacle outlet boxes.

2.4 JUNCTION PULL BOXES

A. Provide galvanized code-gauge sheet steel junction and pull boxes, with screw-on covers; of types, shapes and sizes, to suit each respective location and installation; with welded seams and equipped with stainless steel nuts, bolts, screws and washers.

B. Manufacturers: Subject to compliance with requirements, provide junction and pull boxes of one of the following:

Adalet-PLM Div., Scott and Fetzer Co.

Appleton Electric Co.

Arrow-Hart Div., Crouse-Hinds Co.

Bell Electric/Square D Co.

GTE Corporation

Keystone Columbia, Inc.

O-Z/Gedney Co.

Slater Electric Co.

Spring City Elect. Mfg. Co.

2.5 CONDUIT BODIES

A. Provide galvanized cast-metal conduit bodies, of types, shapes, and sizes, to suit respective locations and installation, construct with threaded-conduit-entrance ends, removable covers, and corrosion-resistant screws.

B. Manufacturers: Subject to compliance with requirements, provide conduit bodies of one of the following:

Appleton Electric Co.

Crouse-Hinds Co.

Gould, Inc.

Killark Electric Mfg. Co.

O-Z/Gedney Co.

Spring City Electrical Mfg. Co.

2.6 BUSHINGS, KNOCKOUT CLOSURES AND LOCKNUTS

A. Provide corrosion-resistant punched-steel box knockout closures, conduit locknuts and insulated malleable iron conduit bushings, offset connectors, of types and sizes to suit respective uses and installation.

B. Manufacturers: Subject to compliance with requirements, provide bushings, knockout closures, locknuts and connectors of one of the following:

Appleton Electric Co.

Burndy Corp.

Crouse-Hinds Co.

Gould, Inc.

O-Z/Gedney Co.

RACO, Inc.

Steel City/Midland-Ross Corp.

Thomas and Betts Co., Inc.

2.7 SEALING FITTINGS

A. Provide corrosion-resistant, hi-pressure die-cast aluminum sealing fittings, of the types and sizes to suit respective uses and installation.

B. Manufacturers: Subject to compliance with requirements, provide sealing fittings of one of the following:

Appleton Electric Co.

Crouse-Hinds Co.

O.Z./Gedney Co.

L.E. Mason Co. (Red Dot)

2.8 EXPLOSION-PROOF JUNCTION BOXES

A. Box body shall be constructed of malleable iron with a finish of zinc electroplate and aluminum

lacquer. Size shall be 4-1/8" x 4-1/8" x 3- 7/16" with a threaded cover opening of 3-5/8" and 3/4" threaded hubs to match conduit installation requirements.

B. Cover shall be constructed of copper-free aluminum with a natural finish. Cover to be externally threaded to fit a 3-5/8" opening.

C. Box shall be designed for Class I, Division I, Group B areas, and be as manufactured by Crouse-Hinds, Appleton or approved substitute.

PART 3 – EXECUTION

3.1 INSTALLATION OF ELECTRICAL BOXES AND FITTINGS

A. Install electrical boxes and fittings, complying with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

B. Coordinate installation of electrical boxes and fittings with wire/cable and raceway installation work.

C. Provide weatherproof outlets for interior and exterior locations exposed to weather or moisture.

D. Provide knockout closures to cap unused knockout holes where blanks have been removed.

E. Install boxes and conduit bodies in those locations to ensure ready accessibility of electrical wiring.

F. Avoid using round boxes where conduit must enter box through side of box, which would result in difficult and insecure connections when fastened with locknut or bushing on rounded surface.

G. Fasten boxes rigidly to substrates or structural surfaces to which attached, or solidly embed electrical boxes in concrete or masonry.

H. Provide electrical connections for installed boxes.

I. Install sealing fittings in all hazardous locations as required by the NEC. Installation shall be carried out in accordance with manufacturer's written instructions.

J. Pull boxes and junction boxes shall be furnished and installed in all conduit runs at intervals not exceeding 100 feet maximum.

K. Identify each circuit in all pull boxes and junction boxes whether the box contains one or more circuits.

END OF SECTION 260135

SECTION 260140

WIRING DEVICES

PART 1 – GENERAL

1.1 DESCRIPTION OF WORK

A. The extent of wiring device work is indicated by drawings, schedules and specifications. Wiring devices are defined as single discrete units of the electrical distribution system which are intended to carry but not utilize electric energy.

B. Types of electrical wiring devices in this section include the following:

Receptacles.

Switches.

Device plates.

Surface Receptacle Strip

Lamp dimmers

Time Clocks

Contactors

Fire-Rated Poke-Thru Floor Outlet

Energy Control Devices

1.2 SUBMITTALS

A. Product Data: Submit manufacturer's data on electrical wiring devices.

PART 2 – PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products of one of the following (for each type of wiring device):

Legrand Co.

Hubbell, Inc.

Leviton Mfg. Co.

Lutron Electronics Co., Inc.

Cooper Wiring Devices

Square D Co.

Eaton Corp.

Siemens

Tork

Grasslin

Paragon

Wattstopper

2.2 FABRICATED WIRING DEVICES

A. Provide factory fabricated wiring devices, in types, styles, colors, and electrical ratings for applications indicated and complying with NEMA Standards Pub. No. WD 1. Where types and grades are not indicated, provide proper selection as determined by Installer to fulfill wiring requirements, and complying with NEC and NEMA Standards for wiring devices. Color selection to be verified by Contractor with Architect/Engineer.

2.3 RECEPTACLES

A. All simplex receptacles shall be extra heavy duty, hospital grade, 20 amperes, 125 volts, 2 pole, 3 wire grounding, with green hexagonal equipment ground screw, with metal plaster ears, side wiring, NEMA configuration 5-20R unless otherwise indicated. Hubbell Cat. #HBL5361, #HBL8310 or approved substitute.

B. All duplex receptacles shall be extra heavy duty, hospital grade, 20 amperes, 125 volts, 2 pole, 3 wire grounding type with green hexagonal equipment ground screw, with metal plaster ears, side wiring, NEMA configuration 5-20R unless otherwise indicated. Hubbell Cat. #HBL5362, #HBL8300, or approved substitute, HBL5362TR, HBL8300SG where tamperproof is indicated.

C. Special Purpose Receptacles: Provide polarized grounding type special purpose receptacles of the required amperage and voltage ratings, extra heavy duty. Device shall include a green hexagonal equipment ground screw.

D. All ground fault receptacles shall be extra heavy duty duplex, tamper resistant, hospital grade, 20 amperes, 125 volts, 2 pole, 3 wire grounding type with green hexagonal equipment ground screw,integral ground fault circuit interrupter, UL rated Class A, Group 1, with metal plaster ears, side wiring, NEMA Configuration 5-20R, self-testing with red and green LED indicator lights. Device shall include solid state ground-fault sensing and signalling, with a 5 milliampere ground fault trip level, plus or minus 1 milliampere. Hubbell Cat. #GFR5362SG, #GFR8300SG, or approved substitute.

1. Whether indicated or not on the floor plans, the Electrical Contractor shall furnish and install GFI protected devices in kitchen areas on countertops near sinks, water coolers, refrigerators, on rooftop equipment, on exterior walls; and as indicated by the N.E.C., it shall be the discretion of the Electrical Contractor to provide GFI receptacles or GFI circuit breaker. Receptacles protected by GFI circuit breakers shall be permanently labeled on the faceplate as GFCI.

E. All Isolated Ground Duplex Receptacles shall be extra heavy duty, hospital grade, 20 amperes, 125 volts, 2 pole, 3 wire isolated ground with metal plaster ears, isolated from ground circuit, side wiring, NEMA configuration 5-20R unless otherwise indicated. Devices shall be color coded with an orange face and black triangle to identify all isolated ground devices. Hubbell Cat. #IG5362, #IG8300R, or approved substitute.

F. All surge protection receptacles shall be extra heavy duty duplex, hospital grade, 20 amperes, 125 volts, 2 pole, 3 wire with built-in surge protection, metal plaster ears. Devices shall include efficient 3-level MOV protection for phase to neutral, phase to ground and neutral to ground. Devices shall also include diagnostic LED indicator light to be on continuously when protection is active, and shall flash on and off when protection circuit is deactivated due to excessive transients. Hubbell Cat. #HBL5362SA, #HBL8362SA (if hospital grade), or approved substitute. Devices to be red when fed from emergency power.

G. All isolated ground, surge protection receptacles shall be extra heavy duty duplex, hospital grade, 20 amperes, 125 volts, 2 pole, 3 wire isolated ground with built-in surge protection with metal plaster ears isolated from ground circuit. Device shall include efficient 3-level MOV protection for phase to neutral, phase to ground and neutral to ground. Device shall also include diagnostic LED indicator

light to be on continuously when protection is active, and shall flash on and off when protection circuit is deactivated due to excessive transients. Devices shall be blue with green dot and orange triangle, Hubbell Cat. #IG5362SA, #IG8362SA, or approved substitute.

1. Whether indicated or not on the floor plans, the Electrical Contractor shall furnish and install one (1) isolated ground, surge protective receptacle next to each data outlet and connect to isolated ground panelboard, unless directed otherwise.

2.4 USB CHARGING DEVICES

A. All USB charging devices shall be heavy duty, 5VDC, 4.2A charging capacity, 3-wire grounding, with green hexagonal equipment ground screw, with metal plaster ears, quadruple charging outlet ports, Hubbell Cat. #USB4, Pass and Seymour Cat. #TM8USB4XCC6 or approved substitute.

B. All USB charging devices with receptacles shall be extra heavy duty, hospital grade, 20 amperes, 125 volts, 2 pole, 3 wire grounding, with green hexagonal equipment ground screw, with metal plaster ears, side wiring, NEMA configuration 5-20R, with teo charging outlet ports, 5VDC, 3.8 amp charging capacity, Hubbell Cat. #B20X2, Pass & Seymour #TM8USB4XCC6, #USB8300 if hospital grade, or approved substitute.

2.5 SWITCHES

A. Toggle Switch: Provide extra heavy duty, industrial series flush toggle, 1 pole, 2 pole, 3-way, 4-way AC quiet switch rated 20 amperes @ 120/277 volts with green hexagonal equipment ground screw, metal plaster earls, and side wired screw terminals. Similar to Hubbell Series HBL Series or approved substitute.

B. Toggle Switch with Pilot Light: Provide extra heavy duty industrial series, flush toggle, single pole, AC quiet switch rated 20 amperes @ 120 volts with green hexagonal equipment ground screw, metal plaster ears, side-wired screw terminals and 1/25 watts, 125 volt neon pilot light, designed to mount within a single gang outlet box. Similar to Hubbell HBL or approved substitute.

C. Framed Rocker Decorator Switch: Provide heavy-duty flush, framed rocker, 1 pole, AC quiet switch rated 20 amperes @ 120 volts with green hexagonal equipment ground screw, metal plaster ears, and side-wired screw terminals. Similar to Hubbell Cat. No. 212 series, or approved substitute.

D. Three Position Switch: Provide extra heavy duty industrial series, flush toggle, single pole, three position, momentary contact, center position OFF, AC quiet switch rated 20 amperes @ 120/277 volts, with green hexagonal equipment ground screw, metal plaster ears, and side-wired screw terminals. Similar to Hubbell Series HBL or approved substitute.

E. Key Switch: Provide extra heavy duty, industrial, 1 pole, 2 pole, 3-way, 4-way barrel key locking switch rated at 20 AMPs @ 120/277 volts with green grounding screw, metal plaster ears and side wired screw terminals. The tumbler shall be a six-point cylinder type. All project keyed switches to be keyed alike. Similar to Hubbell 122*RKL series.

2.6 DEVICE PLATES

A. Provide switch and receptacle outlet wall plates for wiring devices, of types, sizes, and with ganging and cut outs required by the devices being installed. Construct with metal screws for securing plates to devices; screw heads colored to match finish of plates; plates colored to match wiring devices to which attached. **All emergency receptacles to have red coverplates.** Provide device plates possessing the following additional construction features: **Receptacle outlet plates to be permanently marked with panel designation and circuit number on back side of plate.**

1. Metal Plates to be stainless steel of non-corrosive and non-magnetic 302 alloy, .032" nominal thickness. Plates shall have brushed satin finish.

2. Non-Metallic Plates to be a thermoplastic, virtually indestructible, molded polycarbonate material offering resistance to impact, scratches, discoloration and be self-extinguishing. Plates shall have no-line smooth finish.

B. Weatherproof device plates shall have spring-hinged waterproof cap suitably configured for each application, including face plate gaskets and corrosion-resistant fasteners. Boxes and devices shall be recessed, weatherproof with smoke gray opaque in-use covers. Intermatic Cat. #WP1000(H)GRC.

C. Existing mechanical spaces where concealed work is impractical, such as masonry pr block walls, Provide 4" square boxes, surface mounted, with ½" deep surface mounted device plates consisting of same material for devices indicated on plans, whether single or double gang. Use of plaster flange and standard cover plate will not be acceptable.

2.7 SURFACE RECEPTACLE STRIP (4000 Wiremold only)

A. Refer to Specifications Section 260110 – RACEWAYS for surface raceway specifications.

B. Power, telephone and data outlets with device plates shall match devices used elsewhere in the project. Where power and telephone, power and data, or power, telephone and data are indicated on the Floor Plan, the strip shall be divided into two (2) sections "Power" and "Communications". Communications and power wiring shall be as indicated in contract documents on the floor plans.

C. Length of receptacle strip and the centers on which the device outlets are mounted shall be as indicated in contract documents. The strip shall be complete with all required hardware needed to provide the layout indicated on the floor plan.

D. Drops shall be installed in order to minimize vertical runs and obstructions, unless noted otherwise on drawings.

2.8 LAMP DIMMERS

A. Incandescent: Provide a solid-state A.C. wall dimmer with integrated linear slide control and separate rocker for ON/OFF switching at present lighting level. Device shall have a built-in RF interference filter and be rated 600 watts @ 120 volts, 60 Hertz. Dimmer control shall be similar to Leviton or approved equal.

B. Low Voltage: Provide a solid-state A.C. wall dimmer with integrated linear slide control and separate rocker for ON/OFF switching at present lighting level. Device shall have a built-in RF interference filter and be rated 600 VA @ 120 volts, 60 Hertz. Dimmer control shall be similar to Leviton or approved equal.

C. Fluorescent: Provide solid state AC wall dimmer with integrated linear slide control and separate rocker for ON/OFF switching at present lighting level. Device shall have a built-in RF interference filter and be rated to control from 2 to 12 40 watt rapid-start lamps up to 4800 watts maximum @ 120/277 volts, 60 hertz. Dimmer control and fixture ballast shall be compatible in accordance with equipment manufacturer's requirements. Dimmer control shall be similar to Leviton or approved equal.

D. LED: Provide solid state AC wall dimmer with integrated linear slide control and separate rocker for ON/OFF switching at present lighting level. Device shall have built-in RF interference filter and be rated to control load as required at 120/277V, 60 Hertz. Dimmer control and fixture driver shall be compatible in accordance with equipment manufacturer's requirements. Provide all necessary wiring to provide complete operating system.

2.9 TIME CLOCKS (High End System, Not for Typical Project)

A. Digital Lighting Controller: Shall be a time clock/photocell operation for two (2) circuits:

- Circuit No. 1: Photocell ON/TIME OFF/TIME ON/PHOTOCELL OFF (Selected Days).
- Circuit No. 2: Photocell ON/PHOTOCELL OFF (Every day).

B. Controller shall provide the following features:

1. Seven (7) day scheduling
2. Special day scheduling
3. 32 setpoints
4. Battery back-up
5. Manual override
6. Automatic daylight saving
7. Automatic leap year compensation
8. AM/PM or 24 Hour Format

Clock input shall be 120 or 277 volt AC, 60 Hertz, .4 VA maximum. Output to be two (2) SPDT dry contacts rated 10 AMPs @ 120/240 volts A.C. Clock to be similar to Tork Model No. DGLC - 120 VAC, DGLC-3 - 277 VAC or approved substitute.

C. Digital Time Clock: Shall be a multi-purpose, 24-hour clock with seven (7) setpoints and DPST. Time switch shall provide the following features:

1. Repeat the same schedule each day.
2. AM/PM format
3. LCD display
4. Battery backup
5. Manual override

Clock input shall be 120 or 277 volt A.C., 60 Hertz, .4 VA. Maximum output to be DPST dry contacts rated 20 AMPs @ 120/240 volts A.C. Clock to be similar to Tork Model No. E103, 120 VAC, E103-3, 277 VAC or approved substitute.

2.10 CONTACTORS

A. Electrically Held Power Lighting Contactor: Shall be rated 30 to 200 AMPs for 2 thru 5-pole versions and 300 to 800 AMPs for 2 and 3 pole versions, as indicated on the Floor Plan. Contactor shall have factory wired control and clearly marked termination points, designed for mixed load ratings with a UL listed short-circuit rating up to 100,000 amperes. Contactor shall be housed in a NEMA Type I, general purpose enclosure and be similar to Square D Company, Type "S", Class 8903 or approved substitute.

B. Mechanically Held Power Lighting Contactor: Shall be rated 30 to 200 AMPs for 2 thru 5 pole versions and 300 to 800 AMPs for 2 and 3 pole versions, as indicated on the Floor Plan. Contactor shall have factory wired control with coil clearing contacts and clearly marked termination points, designed for mixed load ratings with a UL listed short-circuit rating up to 100,000 amperes. Contactor shall be housed in a NEMA Type I, general purpose enclosure and be similar to Square D Company, Type "S", Class 8903 or approved substitute.

C. Multiple Lighting Contactor: Shall be an electrically or Mechanically held device with 2 thru 12 poles rated 30 AMPs ballast and 20 AMPs tungsten, as indicated. Mechanically held contactor shall have factory wired control with coil clearing contacts and clearly marked termination points. Contactor

shall be housed in a NEMA Type I, general purpose enclosure and be similar to Square D Company Types "L" and "LX", Class 8903 or approved substitute.

D. General: All contactor control setups shall include all required interface relays needed to function with maintained or momentary contact switches, time clocks and photocell controls. Control circuits and coil voltages shall be 120 volts A.C. single phase. Where system voltage is 277/480 volts, a control power transformer shall be furnished and installed within the contactor enclosure. Transformer shall be sized to handle the contactor's coil load as well as all associated control devices.

2.11 FIRE-RATED POKE-THRU FLOOR OUTLET

A. Provide complete fire-rated assembly poke-thru device of type Wiremold Model RCH with four (4) 20A receptacles capable of being wired for isolated ground, four (4) Ortronics Cat 5e jacks for data and brass cover flange or approved equal.

OR

2.11 FIRE-RATED POKE-THRU FLOOR OUTLET

A. Floor outlet shall be designed for a fire rating of a minimum of three (3) hours in floors employing steel units with concrete topping.

B. Floor thickness range shall be from 2-1/4" to 7" with a UL spacing of a minimum of two (2) feet on center and not more than one (1) unit per each 65 square feet of floor area.

C. Floor outlet shall be designed to fit a 4" diameter cored hole.

D. Floor outlet shall be equipped with four (4) NEMA 5 – 20R, 20 AMP, 125 volt receptacles and four (4) data/telephone outlets as indicated in contract documents.

E. Floor outlet shall be similar to Hubbell Cat. No. PT4X4BRS or approved substitute.

2.12 ENERGY CONTROL DEVICES (Occupancy Sensors)

A. Line Voltage:

1. Combination wall switch and sensor shall be Dual Technology Passive Infrared and Ultrasonic, designed for single gang outlet box installation, with a coverage of 180° for a maximum of 400 square feet. Device shall be suitable for 120/277 dual voltage operation, and have vandal resistant, hard sensor lens. Device shall be similar to Sensor Switch Cat. No. WSD-PDT or Wattstopper DW-100 Series, DW-103 Series for multi-way, DW-200 for dual relay, DW-203 for multi-way dual relay, or approved substitute.

2. Ceiling sensor shall be Dual Technology Passive Infrared and Ultrasonic 360° coverage, 1200 square feet maximum. Self Contained Relay Device shall be suitable for 120/277 Dual Voltage operation. Device shall be similar to Sensor Switch Cat. No. CMR-PDT, Wattstopper DT-355 or approved substitute.

B. Low Voltage:

1. Ceiling mounted sensor shall be Dual Technology Passive Infrared and Ultrasonic with 360° coverage up to 2o feet. Device accepts 12 to 24 volt AC or DC. Device shall be similar to Sensor Switch Cat. No. CM-PDT or approved substitute.

2. Sensor power pack shall be a low voltage power supply with an input of either 120 volts or 277 volts AC and an output of 24 volts DC @ 150 mA. Device shall contain a 20 AMP isolated load control relay. When relay is used, power supply output shall be reduced to 24 volts DC @ 114 mA. Device shall be similar to Sensor Switch PP-20 or approved substitute.

C. Photocontrol

1. Provide epoxy conformal coated cadmium sulphide photocell with Lexan impact and vandal resistant enclosure. Dome and base to be ultrasonically welded. Photocell shall respond to the light spectrum near to that of a human eye. Housing shall mount to ½" conduit and have 180° swivel.
2. Photocell shall have on/off time delay, on at 1 to 5 FC, off at 3 to 15 FC. Tool free adjustment. Unit shall fail in the ON position.
3. Unit shall operate from -40°F to 140°F, with a minimum 5-year warranty.
4. Provide Tork 2001 series or approved equivalent.

PART 3 – EXECUTION

3.1 INSTALLATION OF WIRING AND CONTROL DEVICES

A. Install wiring devices as indicated, in compliance with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation", and in accordance with recognized industry practices to fulfill project requirements.

B. Coordinate with other work, including painting, electrical box and wiring work, as necessary to interface installation of wiring devices with other work.

C. Install wiring devices only in electrical boxes which are clean, free from building materials, dirt and debris.

D. Provide electrical connections for wiring and control devices.

E. Delay installation of all wiring and control devices until wiring work is completed.

F. Isolated Ground Receptacle Devices shall be connected to the system ground by way of an insulated ground conductor color coded green with a yellow stripe.

3.2 PROTECTION OF WALL PLATES AND RECEPTACLES

A. At time of Substantial Completion, replace those items which have been damaged, including those burned and scorched by faulty plugs.

3.3 GROUNDING

A. Provide electrically continuous, tight grounding connections for wiring and control devices.

3.4 TESTING AND COMMISSIONING

A. Prior to energizing circuitry, test wiring devices for electrical continuity and proper polarity connections. After energizing circuitry, test wiring devices to demonstrate compliance with requirements.

B. After energizing circuitry, the Electrical Contractor shall test and adjust all control devices to provide optimum operation and performance.

C. All areas where energy control devices are specified shall be verified for full coverage and accurate operation. If any area is determined by the Owner, Architect, or Engineer to have inadequate coverage or operation, Contractor shall provide additional energy control devices to remedy the coverage or operation issue. For bidding purposed, own 5 extra devices fully installed. After successful commissioning, uninstalled devices shall be handed over to the Owner for spare devices. Device types shall be as required for commissioning, or as selected by Owner for space devices as applicable.

END OF SECTION 260140

SECTION 260180

OVERCURRENT PROTECTIVE DEVICES

PART 1 – GENERAL

1.1 DESCRIPTION OF WORK

A. Extent of overcurrent protective device work is indicated by drawing schedules and specifications.

B. Types of overcurrent protective devices in this section include the following:

1. Service entrance rated disconnect.
2. Molded case circuit breaker.

1.2 SUBMITTALS

A. Product Data: Submit manufacturer's data on overcurrent protective devices, including: voltages and current ratings, interrupting ratings, current limitations, internal inductive and non-inductive loads, time-current trip characteristic curves, and mounting requirements.

B. Shop Drawings: Submit layout drawings of overcurrent protective devices, showing spatial relationships of units to associated electrical equipment, and connections to electrical power supplies.

PART 2 – PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, manufacturers offering products which may be incorporated in the work include the following:

1. Circuit-Breakers

   Cutler-Hammer, Inc. (Eaton)

   Square D Co.

   Siemens

2.2 CIRCUIT BREAKERS

A. Except as otherwise indicated, provide circuit breakers and ancillary components, of types, sizes, ratings and electrical characteristics indicated, which comply with manufacturer's standard design, materials, components, and construction in accordance with published product information, as required for a complete installation.

B. Service Entrance Rated Disconnect: The service disconnect device shall be a molded-case circuit breaker totally front accessible and front connectable. The circuit breaker shall be a three pole device suitable for operation on a 480 volt, 60 Hertz system. Circuit breaker shall have 22,000 RMS symmetrical amperes interrupting rating, and shall be UL approved for Service Entrance equipment.

C. Molded-Case Circuit Breakers: Provide factory assembled, molded-cased circuit breakers of frame size indicated; 120/208 volts, and 277/480 volts 60 Hertz, one, two, or three poles with a short circuit symmetrical ampere interrupting rating as indicated by the panel schedule and/or as shown by the single line riser diagram. Provide circuit breakers with permanent thermal instantaneous magnetic trips in each pole with ampere ratings as indicated. Construct with overcenter, trip-free, toggle type operating mechanisms with quick-make, quick- break action and

positive handle trip indication. Construct devices for mounting and operating in any physical position and operating in an ambient temperature of 40 degrees C. Provide circuit breakers with mechanical screw type connector lugs, AL/CU rated.

PART 3 – EXECUTION

3.1 INSTALLATION OF OVERCURRENT PROTECTIVE DEVICES

A. Install overcurrent protective devices as indicated in contract documents, in accordance with the manufacturer's written instructions and with recognized industry practices to ensure that protective devices comply with requirements. Comply with NEC Standards for Installation of overcurrent protective devices.

B. Coordinate with other work, including electrical wiring work, as necessary to interface installation of overcurrent protective devices with other work.

C. Fasten circuit breakers without causing mechanical stresses, twisting or misalignment being exerted by clamps, supports, or cabling.

3.2 ADJUST AND CLEAN

A. Inspect circuit-breaker operating mechanisms for malfunctioning and, where necessary, adjust units for free mechanical movement.

3.3 FIELD QUALITY CONTROL

A. Prior to energization of overcurrent protective devices, test devices for continuity of circuitry and for short-circuits. Correct malfunctioning units, and then demonstrate compliance with requirements.

END OF SECTION 260180

SECTION 260190

SUPPORTING DEVICES

PART 1 – GENERAL

1.1 DESCRIPTION OF WORK

A. Types of supports, anchors, sleeves and seals specified in this section include the following:

Hangers.

Riser Clamps.

C-clamps

I-beam clamps.

One-hole conduit straps.

Two-hole conduit straps.

Round steel rods.

Lead expansion anchors.

Toggle bolts.

U-Channel Strut Systems.

PART 2 – PRODUCTS

2.1 MANUFACTURED SUPPORTING DEVICES

A. Provide supporting devices, complying with manufacturer's standard materials, design and construct in accordance with published product information, and as required for a complete installation, and as herein specified.

B. Supports: Provide supporting devices of types, sizes and materials having the following construction features:

Hangers: For supporting EMT conduit, electro-galvanized steel, with 1/4" minimum diameter hole for round steel rod; approximately MSS types 5, 7, 9 or spring steel conduit clips.

Reducing Couplings: Steel rod reducing coupling, 1/4" minimum black steel.

C-Clamps: Black malleable iron, 1/4" minimum rod size.

I-Beam Clamps: Black steel, 1-1/4" x 3/16" stock; 3/8" cross bolt; flange width 2"; approx. 52 pounds per 100 units.

One-Hole Conduit Straps: For supporting EMT conduit, electro- galvanized steel.

Two-Hole Conduit Straps: For supporting EMT conduit, electro-galvanized steel; 3/4" strap width; and 2-1/8" between center of screw holes.

Hexagon Nuts: For 1/4" rod size; galvanized steel.

Round Steel Rod: Black steel; 1/4" min. dia.

Offset Conduit Clamps: For supporting rigid metal conduit; black steel.

C. Anchors: Provide anchors of types, sizes and materials indicated; and having the following construction features:

Lead Expansion Anchors: 1/4" - 20 Minimum.

Toggle Bolts: Springhead; 3/16 x 4".

D. Manufacturer: Subject to compliance with requirements, provide anchors of the following:

Ackerman Johnson Fastening Systems, Inc.

Elcen Metal Products Co.

Ideal Industries, Inc.

Rawlplug Co., Inc.

Star Expansion Co.

U.S. Expansion Bolt Co.

Erico Products, Inc. (Caddy)

Hilti, Inc.

E. U-Channel Strut Systems: Provide U-channel strut system for supporting electrical equipment, 16-gauge hot dip galvanized steel, construct with 9/16" dia. holes, 8" o.c. on top surface, with standard hot dip galvanized finish, and with the following fittings which mate and match with U-channel.

Beam clamps.

Thinwall conduit clamps.

Conduit hangers.

U-bolts.

F. Manufacturers: Subject to compliance with requirements, provide channel systems of one of the following:

B-Line Systems, Inc.

Elcen Metal Products Co.

Power-Strut Div.; Van Huffel Tube Corp.

Unistrut Div.; GTE Products Corp.

Hilti, Inc.

PART 3 – EXECUTION

3.1 INSTALLATION OF SUPPORTING DEVICES

A. Install hangers and anchors in accordance with manufacturer's written instructions and with recognized industry practices to insure supporting devices comply with requirements. Comply with requirements of NECA, NEC and ANSI/NEMA for installation of supporting devices.

B. Install hangers, supports, clamps and attachments to support piping properly from building structure. Arrange for grouping of parallel runs of horizontal conduits to be supported together on trapeze type hangers where possible. Install supports with maximum spacings.

END OF SECTION 260190

SECTION 260472

BRANCH CIRCUITS

PART 1 – GENERAL

1.1 DESCRIPTION OF WORK

A. Branch circuit work is indicated by drawings.

B. The branch circuits shall include furnishing and installing a complete wire and conduit or cable system between panelboards and lighting fixtures, receptacles, fractional horsepower motors, and small single phase loads.

C. Types of equipment to be furnished and installed in this section include the following:

Rigid Raceways – See Section 260110

Electrical Metallic Tubing (EMT)

MC (Metal Clad) (Concealed Work only)

ACTHH (Health Care Facility Cable)

NM (Non-Metallic)

MC (2-Hour Metal Clad) – Fire Pump

MI (Mineral Insulated) – Fire Pump

Wires and Cables

Junction Boxes

Pull Boxes

Conduit Bodies

Bushings

Locknuts

Supporting Devices

PART 2 – PRODUCTS

2.1 BRANCH CIRCUITS

A. Furnish each branch circuit with an assembly of materials, including but not necessarily limited to, conduit, wire, cable, pull boxes, junction boxes and other items and accessories needed for a complete installation. Where materials or components are not otherwise indicated, comply with NEC, NEMA and established industry standards for applications indicated.

2.2 CONVENIENCE BRANCH CIRCUITS

A. Intent:

1. The intent of this portion of the specifications is to describe the requirements of a convenience circuit as it applies to 120-volt receptacles.

2. All convenience branch circuits may consist of more than one 120 volt receptacle.

B. Convenience Circuit - General: A circuit consisting of a phase and neutral conductor, which may share its neutral with other phase conductors provided that the neutral conductor does not become overloaded due to circuit phase relationship. This type of circuit shall also include an equipment

grounding conductor as described under the grounding section of the specifications.

C. Convenience Circuit - Dedicated: A circuit consisting of a phase and neutral conductor which DOES NOT share conductors with any other circuits. This type of circuit shall also include an equipment grounding conductor as described under the grounding section of the specifications.

D. Convenience Circuit Dedicated with Isolated Ground: A circuit consisting of a phase, neutral and ground conductor which DOES NOT share conductors with any other circuits. This type of circuit shall also include an equipment grounding conductor as described under the grounding section of the specifications.

1. The isolated ground conductor shall be connected to an isolated ground type receptacle as described under the Wiring Devices Section of the specifications.
2. The isolated ground conductor shall be identified by green insulation with a yellow stripe.
3. The isolated ground conductor shall be connected to an isolated ground bar in the branch circuit panelboard. This isolated ground bar shall then be connected to an applicable derived system ground or service entrance ground.

PART 3 – EXECUTION

3.1 INSTALLATION OF BRANCH CIRCUITS

A. Install branch circuits, complying with equipment manufacturer's written instructions, applicable requirements of NEC, NEMA, and NECA's "Standard of Installation", and in accordance with recognized industry practices.

B. Multiple circuits within a single raceway or cable shall be permitted under this section. It shall be the responsibility of the Electrical Contractor to assure that the neutral conductors do not become overloaded due to circuit phase relationship, and isolated grounds not become voided or compromised due to miswiring or wrong connections.

C. The Electrical Contractor may elect to use metal clad cable in lieu of electrical metallic tubing (EMT) in wall cavities, and/or above tile or dry wall ceilings. In all areas of exposed construction, electrical metallic tubing (EMT) shall be installed.

END OF SECTION 260472

SECTION 260510

BUILDING LIGHTING

PART 1 – GENERAL

1.1 DESCRIPTION OF WORK

A. Lighting fixture work is indicated by specifications, drawings and schedules.

B. Types of lighting fixtures in this section include the following:

1. Fluorescent.
2. Incandescent.
3. High Intensity Discharge.
4. LED

C. Applications of lighting fixtures required for the project include the following:

1. General Lighting.
2. Supplementary Lighting.
3. Emergency Lighting.

1.2 SUBMITTALS

A. Product Data: Submit manufacturer's data on building lighting fixtures.

B. Shop Drawings: Submit dimensioned drawings of lighting fixture installations, including but not necessarily limited to, layout, relation to associated panelboards, and connections to panelboards. Submit fixture shop drawings in booklet form with separate sheet for each fixture, assembled in luminaire "type" alphabetical order, with proposed fixture and accessories clearly indicated on each sheet.

PART 2 – PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

A. Each lighting fixture type specified represents a specific style and quality of fixture acceptable for this project.

B. The Engineer reserves the right to reject any shop drawing and to request a resubmission should the contractor submit a shop drawing of an equivalent manufacturer which is viewed as being of an incompatible style or inferior quality.

C. No fixture shop drawing shall be submitted, nor will any be accepted, for any manufacturer which is not specifically listed for that fixture type. When a fixture manufacturer is listed for a specific fixture type, this does not provide him with the right to submit for fixtures he is not listed under. A bidding Contractor may elect to bid using non listed fixtures for the listed Lighting Representatives. The Engineer and the Architect shall make the final decision on whether the submitted fixture meets the project's requirements during shop drawing review.

D. Should the Contractor be unable to obtain approval of the resubmitted manufacturer, then he should submit the basis of design specified manufacturer/fixture.

2.2 LIGHTING FIXTURES

A. Provide lighting fixtures of the size, type and rating indicated complete with, but not necessarily limited to, housings, lamp holders, reflectors, ballast, lamps, mounting frames, pendants and wiring; wired and connected in place, complete, tested and left in satisfactory operating condition.

B. Fluorescent Lamp Ballasts:

Section 1 - Physical Characteristics

1. The ballast shall be physically interchangeable with a standard core & coil electromagnetic ballast.
2. The electronic ballast shall be provided with integral leads, color coded to ANSI standard C82.11 (latest version).

Section 2 - Performance Requirement

1. The "High Frequency" electronic ballast shall operate lamps at a frequency of 20 KHz or higher without visible flicker.
2. The electronic ballast's input current shall have Total Harmonic Distortion (THD) of less than 20% when used with primary lamp.
3. The electronic ballast shall have a Power Factor greater than 98% when used with primary lamp.
4. The electronic ballast shall have Lamp Current Crest Factor of less than 1.7, in accordance with lamp manufacturers' recommendations and ANSI C82.11.
5. The electronic ballast shall support a sustained short to ground or open circuit of any output lead without damage to the ballast.
6. The electronic ballast shall have an audible noise rating of Class A or better.

Section 3 - Regulatory Requirements

1. Ballast shall meet the requirements of the Federal Communications Commission Rules and Regulations, Part 18, for non-consumer equipment.
2. The electronic ballast shall meet ANSI C82.11 standards regarding harmonic distortion.
3. Ballast shall meet ANSI C62.41 Cat. A for transient protection.
4. The electronic ballast shall comply with all applicable state and federal efficiency standards.
5. The electronic ballast shall be Underwriters' Laboratories (UL) listed (Class P) and CSA Certified where applicable.

Section 4 - Other

1. The electronic ballast shall not contain Polychlorinated Biphenyls (PCB's).
2. The electronic ballast shall carry a five year (5) warranty.

C. High Intensity Discharge Ballasts

Section 1 - Physical Characteristics

1. The ballast shall be either a open core and coil mounted within the fixture or an encapsulated core and core.
2. With both types the capacitor and the igniter are mounted separately within the fixture.

Section 2 - Performance Requirement

1. Where quiet performance is required the standard open core and coil shall be potted in a cube-shaped steel can utilizing Class H (180 Deg. C.) polyester compound.
2. Encapsulated ballasts shall carry a Class A noise rating up through 175 watts and Class B for 250 and 400 watts.

3. The ballast shall be designed with multiple input voltage taps on the primary coil. The four (4) tap design shall operate on 120 volt, 208 volt, 240 volt and 277 volt.

Section 3 - Regulatory Requirements

1. Ballast shall be Underwriters' Laboratories (UL) listed in accordance with UL 1029.
2. Ballast shall be designed and manufactured in accordance with ANSI C82.4.

D. LED Drivers

1. All LED fixtures shall be provided with integral drivers (unless noted otherwise) and must operate at line voltage as indicated on drawings (unless noted otherwise).
2. LED drivers shall have operating temperature of 50°F - 140°F unless noted otherwise.
3. LED drivers shall carry a 5-year warranty.

E. Fixture Lamps: For the type, number and color of the fixture lamps, refer to the Lighting Fixture Schedule on the drawings.

PART 3 – EXECUTION

3.1 INSTALLATION OF LIGHTING FIXTURES

A. Install lighting fixtures at locations and heights as indicated, in accordance with fixture manufacturer's written instructions, applicable requirements of NEC, NECA's "Standard of Installation", NEMA Standards and with recognized industry practices to ensure that lighting fixtures fulfill requirements of the project.

B. Install lighting fixtures in removable tile ceilings using 3/8" flexible metal conduit with 3 # 12 awg. conductor. Maximum length of flexible lead shall not exceed 60". Flexible lead shall extend from the fixture to the junction box. The junction box shall be securely fastened to the building structure above the removable tile ceiling and shall not serve more than two (2) lighting fixtures, nor shall the junction box support any of the lighting fixtures.

3.2 LIGHTING FIXTURE MOUNTING

A. 1' x 4', 2' x 2' and 2' x 4' fixtures installed in a removable tile ceiling shall be installed using T-Bar grid safety clips as provided by the fixture manufacturer and as required by the NEC.

B. 2'x 2' and 2' x 4' fixtures installed in a removable tile ceiling shall be installed using support wires at all four corners of the fixture. The support wires shall be carried up to the building structure and securely anchored using screwed or bolted hardware. Pressure type clips will not be acceptable. The Electrical Contractor shall be responsible for installing or having installed these four (4) support wires.

C. 1' x 4' fixtures installed in a removable tile ceiling shall be installed using support wires at two (2) corners of the fixture. The support wires shall be carried up to the building structure and securely anchored using screwed or bolted hardware. Pressure type clips will not be acceptable. The Electrical Contractor shall be responsible for installing or having installed these Two (2) support wires.

D. Downlights installed in a removable tile ceiling shall be installed using 24" spreader bars attached to the T-Bar grid system. Two (2) support wires shall be installed, one (1) on each side of the fixture and centered between the spreader bars, these support wires shall be carried up to building structure and securely anchored using screwed or bolted hardware. Pressure type clips will not be acceptable. The Electrical Contractor shall be responsible for installing or having installed these two (2) support wires.

E. Pendant lighting fixtures, either chain, cable or stem hung below a removable tile ceiling shall be installed in accordance with fixture manufacturer's written instructions and recommendations. The Electrical Contractor shall furnish and install support wire or threaded rod from the fixture mounting hardware up to building structure and securely anchor using screwed or bolted hardware. Pressure type clips will not be acceptable. These support devices shall be independent from the ceiling T-Bar grid system, the system may be used as a guide, but in no way shall the T-Bar grid system carry any of the weight produced by the fixture or it's support devices.

F. Surface mounted fixtures installed on removable tile ceilings or dry wall ceilings shall be installed in accordance with fixture manufacturer's written instructions and recommendations.

1. Fixtures installed on removable tile ceilings shall be anchored to the T-Bar grid system using snap-on clips with threaded studs and wing nuts. The Electrical Contractor shall furnish and install a support wire from each snap-on clip carried up to building construction and securely anchor using screwed or bolted hardware.

2. Fixtures installed on dry wall ceilings shall be mounted using spring-loaded toggle bolts. The number and location of the anchors shall depend on the fixture manufacture's written instructions and recommendations. It shall be the responsibility of the Electrical Contractor to follow these instructions and recommendations.

3.3 ADJUST and CLEAN

A. Clean lens, reflectors and interiors of all lighting fixtures of dirt and construction debris upon completion of installation.

B. Protect installed lighting fixtures from damage during the remainder of the construction period.

3.4 FIELD QUALITY CONTROL

A. Upon completion of the installation of the lighting fixtures, and after the building circuitry has been energized, apply electrical energy to demonstrate capability and compliance with project requirements. Where possible, correct malfunctioning units at the site, then retest to demonstrate compliance; otherwise, remove and replace with new units, and proceed with retesting.

B. At the time of Substantial Completion, replace lamps in lighting fixtures which are observed to be noticeably dimmed after Contractor's use and testing, as judged by the Architect/Engineer. Furnish stock or replacement lamps amounting to 15% (but not less than one (1) lamp in each case) of each type and size used in each type of fixture. Deliver the replacement stock as directed to the Owner's storage area.

1. Refer to Division 1 sections for the replacement/restoration of lamps in lighting fixtures, where used for temporary lighting prior to the time of Substantial Completion.

C. Replace defective and burned out lamps for a period of one (1) year following the time of Substantial Completion.

3.5 GROUNDING

A. Provide tight equipment grounding connections for each lighting fixture installation, in accordance with fixture manufacturer's recommendations and the NEC's requirements.

END OF SECTION 260510