

Brandywine School District  
Brandywine High School Renovations Phase 2  
Roof Package  
ABHA Project 1629

ADDENDUM NO. 3  
May 15, 2019  
PAGE 1 of 3

ADDENDUM NO. 3 ISSUED BY

ABHA Architects, Inc.  
1621 N. Lincoln Street  
Wilmington, Delaware 19806

NOTICE: Attach this Addendum to the Project Manual for this project. It modifies and becomes a part of the Contract documents. Work or materials not specifically mentioned herein are to be as described in the main body of the Specifications and as shown on the Drawings.

Acknowledge receipt of the Addendum in the space provided on the Bid Form. This Addendum is being transmitted to contractors who have received Contract Documents. If there are any problems with legibility or content, please contact ABHA Architects, Inc. (302) 658-6426.

ATTACHMENTS

Drawings: Architectural: A-105.1 Mark-up  
Photo's: 6 pages A through G

RFI CLARIFICATIONS:

1. Existing Roof Assembly Thickness:
  - a. See Attached A-105.1 Mark-up
2. Roof Slope of Assembly 2B:
  - a. Roof slope to match adjoining roof type 2 over auditorium.
3. Smoke Hatch Steel:
  - a. Additional Steel to be provided by General Construction Contractor.
  - b. Roofing Contractor to coordinate with General Construction Contractor.
    - i. Size of Hatches
    - ii. Location of Hatches

CHANGES TO PROJECT MANUAL:

1. Section 07 7100, PART 2, ARTICLE 2.01, PARAGRAPH A:
  - a. DELETE Subparagraph 1.
  - b. ADD Subparagraphs:
    1. Metal-Era, Inc: [www.metalera.com](http://www.metalera.com), private label systems for roofing manufactures (basis of specifications).
      - a. Fascia and Roof Edge: Anchor-Tite Fascia System; Adhered Single Ply Version.
    2. Substitutions: see Section 01 6000 – Product Requirements

END OF ADDENDUM NO. 3