

SECTION 090000 – FINISH SCHEDULE

Carpet Tile

Basis of Design: Shaw Contract Group

CPT-1: Manufacturer: Tandus Centiva
Style: Freelance 11024
Color: Jet Fuel #23804
Size: Modular 24" x 24" / ER3 construction.
Installation Method: Verical Ashlar
Primary Backing: Non-woven synthetic fiber
Construction: Statatec Patterned Loop
Face Weight: 18 oz. / sq. yd.
Gauge: 5/64"
Pile height average: .187"
Fiber System: Dynex SD Nylon (Permanent Stain Resistance)
Dye Method: 100% solution dyed
Fluorine-free soil protection: Eco-Ensure
ER3 Construction
Surface Flammability: Passes CPSC FF 1-70
Flooring Radiant Panel: Class 1
Soil Protection: application rate: 2% of face weight.
Antimicrobial Chemicals: No antimicrobials added to product

Ceramic Tile

Basis of Design: Daltile

CT-1: Manufacturer: Daltile
Style: Unity
Color: Tobacco P403 **Addendum 3**
Size: 12" x 24"
Pattern: Horizontal Brick
(Bathroom Floor Tile)
Grout Color: Mapei, Sahara Beige **Addendum 3**

CT-2: Manufacturer: Daltile
Style: Elevare
Color: Crater EL41 **Addendum 3**
Size: 4" x 16"
Pattern: Horizontal Brick
(Bathroom Wall Tile)
Grout Color: Mapei, Straw **Addendum 3**

Vinyl Composite Tile

Basis of Design: Johnsonite / Azrock Collection

VCT-1: Manufacturer: Azrock Collection

Style: Spirited II

Color: V-216 Part Putty

Size: 12" x 12"

Pattern: Monolithic

(Suite Vestibule/Waiting Area border) **Addendum 3**

VCT-2: Manufacturer: Azrock Collection

Style: Spirited II

Color: V-2609 Iceberg

Size: 12" x 12"

Pattern: Monolithic

(Exam Room & Lab/Storage, Tile 1)

VCT-3: Manufacturer: Azrock Collection

Style: Spirited II

Color: V-238 Cool Down

Size: 12" x 12"

Pattern: Monolithic

(Waiting Area field) **Addendum 3**

VCT-4: Manufacturer: Azrock Collection

Style: Spirited II

Color: V-205 Beige

Size: 12" x 12"

Pattern: Monolithic

(Exam Room & Lab/Storage Tile 2) **Addendum 3**

4" Resilient Rubber Cove Wall Base

Basis of Design: Roppe / Pinnacle

RB-1: Manufacturer: Roppe

Style: Pinnacle

Color: 178 Pewter **Addendum 3**

Paint

Basis of Design:

Manufacturer: Sherwin Williams.

PT-1: Color: SW 6385. Dover White

PT-2: Color: SW 6218. Tradewind

PT-3: Color: SW 6640. Tangerine

PT-4: Color: SW 6512. Notable Hue

Plastic Laminate

Basis of Design: Wilsonart

PL-1: Manufacturer: Wilsonart
Color: Blueberry Taffy Y0355-60
(Base cabinets)

PL-2: Manufacturer: Wilsonart
Color: Asian Sand 7952K-18
(Upper Cabinets)

PL-3: Manufacturer: Wilsonart
Color: White Sand D403-60
(Countertops)

END OF SECTION 090000



TETRA TECH

240 Continental Drive, Suite 200
Newark, Delaware 19713
Tel. (302) 738-7551
Fax (302) 454-5989/5988

Addendum 3

Colonial School District
Wilmington, DE

Bid No.: 4-17-38

Colonial School District – Eisenberg Elementary School Nurse’s/ Counseling Suite

Tt Project No. 16101-17001

Addendum No. 3
to
Drawings and Project Manual

June 28, 2017

To: ALL BIDDERS

This ADDENDUM forms a part of the BIDDING AND CONTRACT DOCUMENTS and modifies the following documents:
Original DRAWINGS dated June 19, 2017
PROJECT MANUAL dated June 19, 2017.

Acknowledge receipt of the ADDENDUM in the space provided on the FORM OF PROPOSAL

This ADDENDUM consists of two (2) pages not including the attachments:

1.0 PROJECT MANUAL – MODIFICATIONS

1.1 Spec Section 09 00 00; FINISH SCHEDULE

1.1.1 **REPLACE** existing Spec Section with the Revised Spec Section attached to this addendum.

2.0 DRAWINGS - MODIFICATIONS

1.1 SHEET A-101, See bubbled revisions on attached full sheet. Revisions include but are not limited to; Partition realignment to increase size of Counseling Room 105, existing classroom door (Door 12) is now remaining instead of being removed, finishes information moved to Finishes plan on Sheet A-601.

1.2 SHEET A-601, See bubbled revisions on attached full sheet. Revisions include but are not limited to; Finishes floor plan added to sheet, Window shade schedule added to sheet (window shade tags included in Finishes floor plan), revisions made to Room Finish and Door Schedules.

ATTACHMENT LIST

1. Spec Section 09 00 00; FINISH SCHEDULE

2. Revised Sheet A-101 DEMOLITION, NEW WORK AND REFLECTED CEILING PLANS
3. Revised Sheet A-601 SCHEDULES AND DETAILS

END OF ADDENDUM No. 3