



For Your Health & Safety<sup>SM</sup>

# COMPLIANCE ENVIRONMENTAL, INC.

150 South Bradford Street, Dover, Delaware 19904

Phone: 302-674-4427 Fax: 302-674-4429

[www.compliancecanhelp.com](http://www.compliancecanhelp.com)

## ADDENDUM No. 1

**April 20, 2015**

**Project:** Specification for 2015 Asbestos Abatement for the Locker Replacement Project at the William Henry Middle School.

**Bid Due:** Tuesday, May 5, 2015, at 2:00 PM (Local Time) (Unchanged)  
Bids are due at the Capital School District, District Office,  
198 Commerce Way, Dover, Delaware 19904.  
Bids will be publicly opened at that time.

### Address

**Bids To:** Mr. Elliot Hardin, Supervisor of Building and Grounds  
Capital School District  
198 Commerce Way  
Dover, Delaware 19904  
(302) 857-4210

**The Contractor shall submit two (2) complete copies of the bid with original signatures. Submit bids in a sealed envelope addressed and labeled as follows:**

**“BID FOR 2015 ASBESTOS ABATEMENT FOR THE LOCKER REPLACEMENT PROJECT AT THE WILLIAM HENRY MIDDLE SCHOOL - DO NOT OPEN”**

**The Contractor shall provide a bid on the form provided in the specification with all required attachments. Bids can be mailed using the U.S. Postal Service, hand-delivered or sent via an overnight delivery service. NO FACSIMILE BIDS WILL BE ACCEPTED. The Contractor is responsible for verifying that their bid has been received prior to the bid due date and time.**

**Bids mailed using the U.S. Postal Service, overnight delivery services (e.g. FEDEX, UPS) can be received at the street address:**

**Capital School District  
District Office  
198 Commerce Way  
Dover, Delaware 19904**

All entries must be typed or made in ink. Bids must be completed by the Contractor in accordance with all instructions to the bidder as included in this Specification. It is the intention of the Capital School District to award this work to one (1) Contractor to include only the Base Bid, the Base Bid with some of the alternates, or the Base Bid with all of the alternates as listed on the Bid Form.

**The Contractors providing bids shall incorporate this Addendum into the Project Specifications and acknowledge receipt on the bid form. The Capital School District reserves the right to waive irregularities and reject any and all bids.**

## **ADDENDUM No. 1**

April 20, 2015

Capital School District

William Henry Middle School

Page 2 of 9

A Pre-Bid Meeting was held on April 20, 2015 from 10:12 a.m. to 10:55 a.m. The Pre-Bid Meeting sign-in sheet is attached. The following are the minutes of the meeting. Subsequent to the Pre-Bid Meeting, the Project Specification is hereby affirmed or changed as follows:

1. **Work Period:** The work will begin on or about June 10, 2015 depending upon potentially added snow days to the current school calendar. All work must be completed within thirty (30) calendar days of the starting date. Final completion must be achieved within thirty (30) calendar days of the starting date. No Contractor representative present at the Pre-Bid Meeting objected to this required work period.
2. **Liquidated Damages:** The Contractor shall pay liquidated damages at the rate of \$ 2,000.00 per calendar day if substantial completion is not achieved within thirty (30) calendar days of the starting date.
3. **Bid Due Date:** Completed bids are due on or before 2:00 p.m. (local time) on Tuesday, May 5, 2015, at Capital School District at which time they will be publicly opened, read, and recorded. No Contractor representative present at the Pre-Bid Meeting objected to this required bid due date.
4. **Bid Award:** The Owner reserves the right to award the project to the Contractor with the best bid amount which the Owner feels is in the best interest of the Owner.
5. **Bid Forms:** The Subcontractor list was reviewed and list of Subcontractors established at the meeting. Bidding Contractors shall provide a completed Bid Form including the Subcontractor list included in the bid documents. Contractors were reminded to include a copy of the current State of Delaware business license with the Bid Form. Contractors shall state on the bid form the number of days required to complete the project and the number of workers scheduled to be on site daily. In addition, the Subcontractor List and all other requested information must be provided completely by the bidding contractor.
6. **Bonds:** A Bid bond is required with the bid to include 10-percent of the amount of the Base Bid plus any alternates (if applicable). The awarded contractor shall also provide a Payment bond and Performance Bond for 100-percent of the amount included as the Base Bid plus any alternates on the Bid Form prior to beginning the work if the total bid is greater-than \$50,000.00. **Payment and Performance Bonds must be provided by the awarded contractor prior to execution of a contract and notice to proceed.**
7. **Questions During Bid Preparation: ALL QUESTIONS REGARDING THE PROJECT REQUIREMENTS MUST BE SUBMITTED TO COMPLIANCE ENVIRONMENTAL IN WRITING NO LATER THAN FRIDAY, MAY 1, 2015. ANY CHANGES TO THE SPECIFICATION WILL BE PROVIDED BY ADDENDUM PRIOR TO THE BID DUE DATE.**
8. **Building Occupant Notice:** The Owner will distribute and post an asbestos abatement building occupant notice once the Contractor is awarded the work.

**ADDENDUM No. 1**

April 20, 2015

Capital School District

William Henry Middle School

Page 3 of 9

9. **Work to be Performed Under This Contract:** The work consists of the removal of interior asbestos-containing joint compounds (and drywall spackling), acoustical composite transite panels, floor tiles and associated mastic from the William Henry Middle School building in the work areas shown on the drawings for work described in the specification. See Table 1. for more information. The work also includes the removal of presumed asbestos-containing floor tiles and associated mastic at locations shown on the drawings. See Table 2. for more information. Additionally, the removal of non-asbestos-containing metal lockers, locker bases and associated debris is required at locations shown on the drawings. This work is being performed in preparation of renovations to the building including the installation of new lockers. **Since part of the school building may be occupied during the work, the Contractor must perform all work in a manner to prevent asbestos exposure, contamination, and/or uncontrolled releases of asbestos outside of work areas. Wooden containment barriers (barricade with signs) shall be constructed prior to asbestos removal activities at locations shown on the drawings in a manner to prevent intentional and/or accidental entry into Work Areas. Barriers shall remain after the project is completed.**

The estimated (approximate) quantities of exposed asbestos-containing materials to be removed and disposed for this project is as follows. See Table 1 for more information:

- A. Joint Compound (and Drywall Spackling) . . . . . 1,500 square-feet
- B. Acoustical Composite Transite Panels . . . . . 1,400 square-feet

The estimated (approximate) quantities of presumed asbestos-containing materials to be removed and disposed for this project is as follows. See Table 2 for more information:

- C. Floor Tile (double floor and associated mastic) . . . . . 250 square-feet

The estimated (approximate) quantities of non-asbestos-containing materials to be removed and disposed for this project is as follows:

- D. Metal Lockers (and associated bases) . . . . . 576 each

10. **Temporary Wooden Barriers: Wooden containment barriers (barricade with signs) shall be constructed prior to asbestos removal activities at locations shown on the drawings in a manner to prevent intentional and/or accidental entry into Work Areas.** Barriers will remain in place after the project is completed. The barrier shall be constructed in a manner to prevent accidental entry into work areas. The Contractor shall place “Danger–Construction Area” signs at each barrier location mounted outside of protected areas in clear view. The barrier shall consist of, at a minimum, 5/8-inch thick OSB with wooden support studs at 16-inches on center. The barrier shall completely cover all openings and be installed in a manner to prevent damage to the building components, including but not limited to, paint, ceilings, floor coverings and building components.

11. **Removal Procedures:** The Contractor shall follow the procedures for removal of asbestos-containing materials removal provided in the specification. (See Section 01013).

**ADDENDUM No. 1**

April 20, 2015

Capital School District

William Henry Middle School

Page 4 of 9

12. **Desired Work Schedule:** The Owner desires that all work be completed as soon as possible without the addition of overtime hours. **The Contractor shall start the project by installing all temporary wooden barriers at locations shown on the drawings. The Contractor shall then start work areas 1 and 3 together, completing work area 3 first, then work area 2 second, and then work area 1 last all within the work period.** After completion, new locker installation will begin in work area 3 and follow to work area 1.
13. **Cutting of Acoustical Composite Transite Panels:** The Contractor shall safely cut to remove, handle, transport and dispose of transite panels. Transite shall be cut both sides with even horizontal and vertical lines. Fiberboard insulation shall be trimmed to match transite cut. All cuts shall be straight with no jagged edges. **Cutting activities will produce high levels of asbestos fibers in air. Proper air controls are crucial for this project.**
14. **Asbestos Bridging Encapsulant:** An asbestos bridging encapsulant such as Fosters 32-32 or equal, shall be applied in at least (2) coats to all final transite edges.
15. **Floor Tile Machines:** The use of floor tile machines are allowed on this project at the discretion of the Contractor during bidding and if the Contractor can demonstrate after bidding and prior to the start of the work, that proper usage and effective decontamination procedures will be used by the Contractor. If the Contractor elects to use a floor tile machine for any portion of the work herein, prior to its usage, the Contractor shall submit a written Work Plan for review and have the Work Plan approved. The Work Plan shall contain, at a minimum, the following elements:
  - A. The floor tile machine(s) will be visual inspection by the Owner's Representative prior to use on this Project to verify that the machine is clean and containing no viable debris or contamination. If not acceptable, the floor tile machine(s) cannot be used on this Project.
  - B. The Contractor shall be responsible for any damage caused by the machine(s).
  - C. Detailed description of the method(s) which will be used by the Contractor to decontaminate the equipment and verify using AHERA visual and air testing clearance protocols, that the equipment was effectively decontaminated. All visual and air testing required will be at no additional cost to the Owner. The Contractor shall provide documentation to the Owner's Representative that it has passed all AHERA visual and air testing clearance protocols prior removal of any floor tile machines from its decontamination area.
  - D. Decontamination shall be performed prior to moving of the machine(s) out of any Work Area to effectively remove any asbestos residue. Decontamination shall be performed in a dedicated containment (the equipment decontamination/bag-out area can be used provided it can accommodate all of the required activities). After decontamination, the Contractor shall provide documentation to the Owner's Representative that the machine was properly decontaminated prior to removal of the machine out of any Work Area including all air testing results.

## **ADDENDUM No. 1**

April 20, 2015

Capital School District

William Henry Middle School

Page 5 of 9

**The Contractor acknowledges by submission of it's bid, that there are no guarantees made by the Owner that approval of floor tiles machines will be granted and the Contractor reaffirms that if floor tile machines are not approved for use on this project, that manual scrapping methods will be used to complete the project in accordance with the Specifications at no additional cost to the Owner.**

16. **Ten-Day Notification:** The Contractor shall submit a ten-day notification of asbestos abatement activities to the EPA and DNREC for this project. The Contractor shall provide a copy of this notification to the Owner's Representative prior to the start of work.
17. **Prevailing Wage Rates:** Current State of Delaware Prevailing Wage Rates are in effect. Wage rates are provided in the specification. The project is in Kent County. (Part II., General Specifications)
18. **Certificate of Liability Insurance:** Prior to the start of work, the Contractor shall provide a Certificate of Liability Insurance in accordance with the General Specifications. The Capital School District and Compliance Environmental, Inc. shall be named as additionally insured. A waiver of subrogation in favor of the Capital School District and Compliance Environmental, Inc. (See General Conditions)
19. **Base Bid:** The Base Bid is a lump sum dollar amount which includes the complete removal and proper disposal of asbestos-containing materials, asbestos-contaminated materials and debris associated with all of the work listed in Section 01013. Estimated quantities are provided for the Contractor's use while preparing its bid. However, the Contractor shall determine that actual quantities required to complete this work and consider these actual quantities in its bid (See Bid Form).
20. **Alternate Bid Items:** No alternate bid items are included on the Bid Form. The Contractor shall provide the lump sum cost on the Bid Form for all asbestos abatement activities required by the Specification.
21. **Unit Prices:** The unit prices listed on the bid form could be used to adjust the Contractor's base bid, add or deduct, for changes in quantities on the project. However, the Owner reserves the right to accept or reject these listed unit prices and to ask the Contractor to provide other pricing based upon project conditions. (See the Bid Form)
22. **Use of Drawings:** All drawings provided in the Specification are diagrammatic and are not to scale or proportion. Drawings are provided to the Contractor for reference purposes. The Contractor shall develop and verify all dimensions and measurements.
23. **Owner's Representative Oversight:** Compliance Environmental (CEI) will act as the Owner's Representative on the project. CEI will be performing routine inspections during the Contractor's work and will act as a liaison between the Contractor and Owner. The Contractor shall provide adequate notice to CEI to provide site meetings and inspections. Adequate notice is the period of time agreed to by the Contractor and Professional Service Firm. (See Section 01013)

## **ADDENDUM No. 1**

April 20, 2015

Capital School District

William Henry Middle School

Page 6 of 9

24. **Contractor Project Staffing:** A minimum of three (3) asbestos personnel are required to be present at the project site at all times. The Contractor's on-site supervisor must be able to make timely decisions for this company. **Prior to any site activity, the Contractor shall submit the name and address of each supervisor, worker and any other person he intends to use at the project site for informational screening (e.g. registered sex offenders list and other lists) by the Owner. The Contractor shall be notified by the Owner if their personnel will be allowed to work at the project site based upon the results of the screening. The Owner reserves the right to reject any proposed Contractor personnel for this project.** (Section 01043)
25. **Project Supervisor:** During all asbestos abatement work, a State of Delaware licensed Supervisor, employed by the Contractor, shall be on site at all times. The licensed Supervisor shall maintain all daily records as required.
26. **Project Monitor Must Be On-Site:** The Contractor shall not begin or continue work for any asbestos abatement related activities until a certified Project Monitor is resident on site. The Project Monitor must be on site at all times during asbestos abatement related activities. The Contractor shall provide adequate notice to the Professional Service Firm providing the Project Monitor. Adequate notice is the period of time agreed to by the Contractor and Professional Service Firm.
27. **Equality of Employment Opportunity:** During the performance of this contract, the Contractor agrees as follows:
- The Contractor will not discriminate against any employee or applicant for employment because of race, creed, color, sex, or national origin. The Contractor will take positive steps to ensure that applicants are employed and that employees are treated during employment without regard to their race, creed, color, sex, or national origin. Such action will include, but not limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applications for employment notices to be provided by the contracting agency setting fourth this nondiscrimination clause.
- The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, color, sex, or national origin.
28. **Penalty for Substitution of Subcontractors:** Should the Contractor fail to utilize any or all of the listed subcontractors in the performance of the work, the Contractor shall be subject to a penalty in the amount of one-percent (1%) of the total contract amount (not to exceed \$10,000.00). The agency may determine to deduct payments of the penalty from the Contractor or have the amount paid directly to the agency. Any penalty amount assessed against the Contractor may be remitted or refunded, in whole or in part, by the agency awarding the contract, only if it is established to the satisfaction of the agency that the subcontractor in question has defaulted or is no longer engaged in such business. No claim for the remission or refund of any penalty will be granted unless an application is filed within one (1) year after the liability of the successful bidder accrues. All penalty amounts assessed and not refunded or remitted to the Contractor will be reverted to the State of Delaware.
29. **Waste Handling and Disposal:** All asbestos-containing materials and contaminated

## **ADDENDUM No. 1**

April 20, 2015

Capital School District

William Henry Middle School

Page 7 of 9

- asbestos-containing materials shall be properly handled, stored and disposed by the Contractor at a licensed and permitted landfill. **The Contractor shall utilize the landfill disposal facility written on the bid form for this project.** All non-asbestos-containing or non-asbestos-contaminated wastes shall be properly and safely stored by the Contractor inside of the building. Waste shall be stored in a manner which does not block ingress or egress of the building, rooms, closets, doors or windows and does not pose a fire or safety concern as determined by the Owner or the Owner's Representative. The Contractor shall provide all waste disposal documentation to the Owner's Representative. (See Section 01013 and 02084 for more information).
30. **Access to Work Areas:** The Contractor shall, at all times, take every measure to secure all work areas from entry by non-authorized people. It is the Contractor's responsibility to adequately barricade, sign and control access to work areas in such a way to prevent accidental access to work areas. (See Section 01013)
31. **Work Area Security & Protection:** In performing the work, the Contractor is responsible for the security of the work area and protection of any and all equipment, materials, and surfaces not scheduled for work activities. The Contractor shall not be provided with a key to building(s) where work is to be performed. **Since the school campus will be in operation during the project work period, the Contractor shall, at all times, take every measure to secure all work areas from intentional or accidental entry by non-authorized people.** It is the Contractor's responsibility to adequately barricade, sign and control access to work areas in such a way to prevent accidental access to Work Areas. Drop cloths shall be installed and used from all exterior access points to work areas. Plastic sheeting shall be installed by the Contractor to cover all articles and equipment remaining in Work Areas and access areas prior asbestos removal activities. All drop cloths and plastic sheeting shall be properly disposed by Contractor after use.
32. **Exhaust from Negative Air Machines:** Windows, doors and any other building openings used to exhaust negative air shall be protected by the Contractor by installing plywood and bracing if the opening is located on the first floor or below. The plywood and bracing shall be installed in a manner by the Contractor that prevents damage to the building components and prevents unauthorized access into the building.
33. **Electronic Equipment and Building Sensors:** The bidding contractors were advised that parts of the building may contain electronics including, but limited to, smoke and fire sensors which cannot be relocated prior to work activities. Further, the Contractor must provide all necessary means to protect all building electronics within work areas which cannot be relocated.
34. **Smoking or Open Flames:** Smoking or open flames are not permitted in the building. The Contractor shall follow OSHA requirements for all cutting using open flames including, but not limited to, cutting permits and fire watch provisions.
35. **Contractor Provided Personal Protective Equipment:** The Contractor shall provide, at no additional cost to the Owner or Owner's Representative, all necessary personal protective equipment required by the Owner's Representative to perform all required inspections.

## **ADDENDUM No. 1**

April 20, 2015

Capital School District

William Henry Middle School

Page 8 of 9

36. **Respirator Protection:** The minimum respiratory protection on this project will be Powered Air Purifying Respirators (PAPR). The Contractor shall perform the required OSHA worker and supervisor personal monitoring and personal air sampling. The Owner's Representative will not be performing personal monitoring and personal air sampling for this project.
37. **Final Clearance Sampling:** Final air clearance samples will be by Transmission Electron Microscopy (TEM). See Section 02081 and this specification for more information.
38. **Electric Power and Service:** All electric power shall be shut down in each work area where possible. The Owner shall provide low voltage temporary electric service (single phase, 120-volt, 100 amp circuit source). The Contractor shall provide the Owner with their specifications within five (5) calendar days prior to scheduling the start of work. The Owner shall provide a plug type outlet within 300 feet of work locations. Adequate extension cords shall be provided by the Contractor. Temporary lighting adequate to provide sufficient illumination for safe work and traffic conditions in each work area shall be provided by the Contractor. If required by the Contractor, a licensed electrician shall be provided, at no additional cost, for making electrical connections and disconnections.
39. **Water Service:** The Owner shall provide limited cold water service for small connections (3/4-inch hose maximum). The Contractor shall provide, at no additional cost to the Owner, all necessary connections and ensure proper back-flow protection. Hot water heaters shall be supplied and operated by the Contractor at no additional cost to the Owner. The Contractor shall be responsible for turning on and off valves at their point of connection.
40. **Confined and Enclosed Spaces:** The Contractor shall follow OSHA requirements for work in confined and enclosed spaces.
41. **Lock-Out and Tag-Out Procedures:** The Contractor shall follow OSHA requirements for all equipment and locations requiring lock-out and tag-out. The Contractor shall verify, prior to the start of work in any work area, that all utilities (e.g., water, fuel oil, gas, electric) are isolated (dead) and purged.
42. **Emergency Needs:** For duration of the contract, the Contractor agrees to respond to the needs of the Owner by providing abatement personnel at the project site within 24-hours after notification for abatement of additional asbestos materials which may be discovered and require abatement after the Contractor has completed all of their planned work. A change order will be provided for these services.
43. **Building Access:** No contractor personnel, subcontractors, vendors or visitors are allowed inside or outside the school building and property except in designated work areas and work area access points without written permission from the Owner.
44. **Zero Tolerance:** Capital School District has a Zero Tolerance for drugs, alcohol, tobacco products and weapons. The use or possession of drugs, tobacco products, weapons, firearms, dangerous devices, or destructive devices are prohibited and will not be tolerated at buildings or properties. Additionally, the use of vulgar language will not be tolerated on school grounds.

**ADDENDUM No. 1**

April 20, 2015

Capital School District

William Henry Middle School

Page 9 of 9

45. **Personnel Clothing Requirement:** At no time will the Contractor's employees expose bare skin or remove any articles of clothing in clear sight of building occupants or users inside or outside of the building and on the property except at work area designated hygiene shower out locations.
46. **Scaffolding, Lifts and Ladders:** Safety is a prime importance on this project. If scaffolding is used, the Contractor must erect, use, and disassemble the scaffolding in accordance with OSHA Standards. Additionally, all lifts and ladders shall meet and be used in accordance with OSHA Standards. The Contractor shall insure that all building components are protected during the use of scaffolding, lifts and ladders. The Contractor shall use only trained personnel experienced with roof elevation work and when using scaffolding, lifts, ladders, and working in elevated conditions.
47. **Work Area Movable Objects:** The Owner will be responsible for moving of all large non-fixed (i.e., movable) objects from the work area (s) that are not contaminated. It is the Contractor's responsibility to move any smaller non-contaminated materials out of the work area prior to starting the abatement.
48. **Decontamination Stations:** As required by the regulations, the Contractor shall provide three (3) stage decontamination stations at all work areas.
49. **Walking Tour:** During the meeting, a walking tour of all work areas included in the Base Bid was provided to the bidding contractors.
50. **Additional Site Visits:** Please contact Compliance Environmental, Inc. if you would like to schedule an additional site visit.

This depicts to the best of our knowledge the items that transpired during the Pre-Bid Meeting held on April 20, 2015. If you have any further comments, please contact Compliance Environmental (302-674-4427) in writing within five (5) days. Therefore, these minutes shall become part of Addendum No. 1 and therefore binding on the Contractor for this project.

**COMPLIANCE ENVIRONMENTAL, INC.**



Valentino P. De Rocili, Ph.D., CHMM

Senior Principal Consultant

[vderocili@compliancecanhelp.com](mailto:vderocili@compliancecanhelp.com)

Attachment: (2-Pages): Pre-Bid Meeting Sign-In Sheet.

[ END OF ADDENDUM No.1 ]



For Your Health & Safety™

# COMPLIANCE ENVIRONMENTAL, INC.

150 South Bradford Street, Dover, Delaware 19904

Phone: 302-674-4427 Fax: 302-674-4429

[www.compliancecanhelp.com](http://www.compliancecanhelp.com)

## CAPITAL SCHOOL DISTRICT 2015 ASBESTOS ABATEMENT FOR THE LOCKER REPLACEMENT PROJECT AT THE WILLIAM HENRY MIDDLE SCHOOL

### PRE-BID MEETING - SIGN-IN SHEET Monday, April 20, 2015 at 10:00 a.m. (Local Time)

Company: Compliance Environmental, Inc.	Company: <i>Fishers Environmental</i>
Address: 150 South Bradford Street, Dover, DE 19904	Address: <i>809 Maryland Ave Delaware</i>
Representative Name: Val P. De Rocili	Representative Name: <i>Lance Fish</i>
Telephone: 302-674-4427	Telephone: <i>410 251 3274</i>
FAX: 302-674-4429	FAX:
Email: <a href="mailto:vderocili@compliancecanhelp.com">vderocili@compliancecanhelp.com</a>	Email: <i>lance@fishersenvironmental.com</i>
Company: Compliance Environmental, Inc.	Company: <i>BEI</i>
Address: 150 South Bradford Street, Dover, DE 19904	Address: <i>9100 Yellow Brick Road</i>
Representative Name: Jamie S. Dill	Representative Name: <i>Stephen Dinner</i>
Telephone: 302-674-4427	Telephone: <i>410-692-3701</i>
FAX: 302-674-4429	FAX: <i>410-692-3705</i>
Email: <a href="mailto:jdill@compliancecanhelp.com">jdill@compliancecanhelp.com</a>	Email: <i>sdinner@msd.com</i>
Company: <i>DFM</i>	Company: <i>Capital School District</i>
Address:	Address: <i>198 Commerce Way Dover, DE 19904</i>
Representative Name: <i>Ted Drew</i>	Representative Name: <i>Elliot Hardin</i>
Telephone:	Telephone: <i>302.672.1500</i>
FAX:	FAX: <i>302.672.1714</i>
Email: <i>ted.drew@state.de.us</i>	Email: <i>elliot.hardin@capital.k12.de.us</i>
Company: <i>Astec Inc</i>	Company: <i><del>BEI</del> Plymouth Env.</i>
Address: <i>1554 Locwood General Middletown DE</i>	Address: <i>923 Haws Ave., Norristown, PA</i>
Representative Name: <i>Matt Nichols</i>	Representative Name: <i>Russell King</i>
Telephone: <i>302 378 2717</i>	Telephone: <i>610-239-9920</i>
FAX:	FAX: <i>610-239-9921</i>
Email: <i>astec@mac.com</i>	Email: <i>RKing@plyenv.com</i>

**CAPITAL SCHOOL DISTRICT**  
**2015 ASBESTOS ABATEMENT FOR THE LOCKER REPLACEMENT**  
**PROJECT AT THE WILLIAM HENRY MIDDLE SCHOOL**

**PRE-BID MEETING - SIGN-IN SHEET**  
**Monday, April 20, 2015 at 10:00 a.m. (Local Time)**

Company: <i>CEC</i>	Company:
Address: <i>461 New Churchmans Rd.</i>	Address:
Representative Name: <i>Virgel Cassel</i>	Representative Name:
Telephone: <i>302 322 8946</i>	Telephone:
FAX: <i>302.324 8482</i>	FAX:
Email: <i>vcassel@countygrp.com</i>	Email:
Company:	Company:
Address:	Address:
Representative Name:	Representative Name:
Telephone:	Telephone:
FAX:	FAX:
Email:	Email:
Company:	Company:
Address:	Address:
Representative Name:	Representative Name:
Telephone:	Telephone:
FAX:	FAX:
Email:	Email:
Company:	Company:
Address:	Address:
Representative Name:	Representative Name:
Telephone:	Telephone:
FAX:	FAX:
Email:	Email: