

ADDENDUM NO. 2 ELECTRICAL IMPROVEMENTS AT THE DELAWARE ARMY NATIONAL GUARD DUNCAN READINESS CENTER 41 CORPORATE CIRCLE, NEW CASTLE, DELAWARE 19720 DEARNG CONTRACT NO. 03-2014 FE&ES Comm.: 13-1117 Date of Issue: September 5, 2014

- 1.0 This Addendum, Addendum No. 2, shall be made part of the Project Manual and Drawings dated August 11, 2014 for the Electrical Improvements at the Delaware Army National Guard Duncan Readiness Center.
- 2.0 Any provision in any of the Contract Documents which may be in conflict or be inconsistent with the contents of this Addendum shall be void to the extent of such conflicts or inconsistency.
- 3.0 Bid Date has not changed. Sealed bids for **DEARNG Contract No. 03-2014** Duncan Readiness Center Electrical Upgrades, will be received by the Delaware Army National Guard at the Security Officers desk in the Main Lobby of the Armed Forces Reserve Center, 250 Airport Road, New Castle, Delaware, 19720 until **2:00 PM local time on September 12, 2014**, at which time they will be publicly opened and read aloud in the Multi-Purpose Room. Allow ample time to enter the facility since the site is secure and each vehicle entering the facility will need to pass through security.
- 4.0 Changes to prior Addenda4.1. There are no Changes to prior Addenda.
- 5.0 Changes to Specifications5.1 There are no changes to Specifications
- 6.0 Changes to Drawings:6.1 There are no Changes to Drawings.
- 7.0 Questions/Clarifications
 - Q1 On drawing E2 single line there are three comb. Starters shown. Where will these starters to be mounted? Will there be a housekeeping pad for the switchboards, 75 KVA transformer and the MCC? Need location of generator annunciation. Do not see a EM stop button for generator is there one?
 - A1: Starters shall be Across the Line, Size 1 with HOA selector switch, Red and Green Pilot light and electronic overloads. They do not need to be combination starters if located in the Electric Room.



Addendum No. 2 Electrical improvements at the Delaware Army National Guard Duncan Readiness Center

Page 2 of 10

- A2: Starters shall be installed in a convenient location within the Electric Room. Expect location is up to 30ft from Panel MPS.
- A3: A housekeeping pad is not required since most of this gear is wall mounted.
- A4: Refer to First Floor Plan-New Work on Drawing E-2 for location of Annunciator. Annunciator shall be mounted recessed in wall and services to annunciator shall be run concealed.
- A5: Generator Emergency Stop Station shall be located in the electric room near the emergency side of the transfer switch.

END OF ADDENDUM #2

EF/ef 13-1117 Add No 2

cc: All Registered Plan Holders P File