

Advertisement

Sealed proposals for the following contract will be received by the Department of Transportation, State of Delaware, in the Bidders Room (Room B1.11.01) in the DeIDOT Transportation Administration Center, US Route 113 South, Dover, DE until 2:00 P.M. Local Time, Tuesday, August 10, 2010, and thereafter be publicly opened:

Contract No. T200707103

BR 1-652 ON N331 KIAMENSI ROAD OVER HERSHEY RUN

COMPLETION DATE: 110 Calendar Days

Cost of Contract Documents: \$32.50

New Castle County

ELECTRONIC BIDDING

Bidders wishing to use the Windows-compatible electronic bidding software should request a bid file disk and installation disk if needed, from the Competitively Bid Contracts Coordinator at the email address or phone number listed at the bottom of this Advertisement. Alternately, the installation software may be downloaded by clicking [here](#).

Prospective Bidder's Note: The Department has adopted an External Equal Opportunity Complaint Procedure. The procedure can be viewed on our website by clicking [here](#) or you may request a copy by calling (302)760-2555.

THIS PROJECT WILL REPLACE EXISTING CORRUGATED METAL PIPES WITH A CAST-IN-PLACE CONCRETE BOX CULVERT, RECONSTRUCT THE ROADWAY APPROACHES, CONSTRUCT SIDEWALK, INSTALL IMPROVED ROADWAY DRAINAGE FEATURES, AND PLACE RIPRAP IN THE STREAM FOR SCOUR PROTECTION.

Item Quantity	Item UOM No	Item Description
1	LS	CLEARING AND GRUBBING
485	CY	EXCAVATION AND EMBANKMENT
128	CY	EXCAVATION AND BACKFILL FOR STRUCTURES
190	CY	EXCAVATION AND BACKFILLING FOR PIPE TRENCHES
1	CY	FLOWABLE FILL
130	CY	BORROW, TYPE A
125	CY	BORROW, TYPE B
40	CY	BORROW, TYPE F
364	CY	FURNISHING BORROW TYPE "C" FOR PIPE, UTILITY TRENCH, AND
1	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS
150	CY	UNDERCUT EXCAVATION

10	CY	SEDIMENT REMOVAL
480	LF	REINFORCED SILT FENCE
10	EACH	INLET SEDIMENT CONTROL, DRAINAGE INLET
10	EACH	INLET SEDIMENT CONTROL, AT GRADE INLET
2	EACH	SUMP PIT, TYPE 1
100	CY	SANDBAG DIKES
120	TON	STABILIZED CONSTRUCTION ENTRANCE
2	EACH	PORTABLE SEDIMENT TANK
185	CY	GRADED AGGREGATE BASE COURSE, TYPE B
54	TON	DELAWARE NO. 3 STONE
30	TON	DELAWARE NO. 57 STONE
78	TON	SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22
83	TON	SUPERPAVE, TYPE B HOT-MIX, 160 GYRATIONS, PG 64-22
168	TON	SUPERPAVE, BITUMINOUS CONCRETE BASECOURSE, 160 GYRATIONS, PG
9	TON	SUPERPAVE, TYPE C HOT-MIX, 160 GYRATIONS, PG 64-22, PATCHING
44	TON	SUPERPAVE, BITUMINOUS CONCRETE BASECOURSE, 160 GYRATIONS, PG
106	CY	PORTLAND CEMENT CONCRETE MASONRY, CLASS A
650	SF	SILICONE ACRYLIC CONCRETE SEALER
22700	LB	BAR REINFORCEMENT, EPOXY COATED
41	LF	REINFORCED CONCRETE PIPE, 15", CLASS IV
81	LF	REINFORCED CONCRETE PIPE, 24", CLASS IV
55	LF	REINFORCED CONCRETE ELLIPTICAL PIPE, 34"X53", CLASS IV
177	LF	PIPE VIDEO INSPECTION
47	LF	STEEL CASING PIPE, 24"
592	LF	INTEGRAL PORTLAND CEMENT CONCRETE CURB AND GUTTER, TYPE 2
2431	SF	P.C.C. SIDEWALK, 4"
524	SF	P.C.C. SIDEWALK, 6"
56	SF	SIDEWALK SURFACE DETECTABLE WARNING SYSTEM
229	SF	CURB RAMP, TYPE 2, 3, AND/OR 4

1	EACH	DRAINAGE INLET, 34" X 18"
1	EACH	DRAINAGE INLET, 48" X 30"
2	EACH	DRAINAGE INLET, 48" X 48"
1	EACH	DRAINAGE INLET, 66" X 48"
2	EACH	DRAINAGE INLET, 72" X 72"
1	EACH	MANHOLE, 66" X 66"
1	EACH	ADJUSTING AND REPAIRING EXISTING MANHOLE
1	EACH	ADJUST AND REPAIR EXISTING SANITARY MANHOLE
160	SY	RIPRAP, R-5
11	CY	CHANNEL BED FILL
225	SY	GEOTEXTILES, SEPARATION
205	SY	GEOTEXTILES, RIPRAP
55	LF	TEMPORARY DRAINAGE PIPE, 30"
115	LF	TEMPORARY DRAINAGE PIPE, 48"
30	LF	TEMPORARY DRAINAGE PIPE, 24"
2000	EADY	PLASTIC DRUMS
7	EACH	MONUMENTS
200	LF	CONSTRUCTION SAFETY FENCE
450	SY	TOPSOIL, 6" DEPTH
505	SY	PERMANENT GRASS SEEDING, DRY GROUND
25	SY	PERMANENT GRASS SEEDING, WET GROUND
230	SY	MULCHING, STRAW
90	SY	SOIL RETENTION BLANKET MULCH, TYPE 3
230	SY	SOIL RETENTION BLANKET MULCH, TYPE 4
320	HOUR	FLAGGER, NEW CASTLE COUNTY, STATE
80	HOUR	FLAGGER, NEW CASTLE COUNTY, STATE, OVERTIME
50	EADY	FURNISH AND MAINTAIN PORTABLE CHANGEABLE
2225	EADY	WARNING LIGHTS , TYPE B
85	EACH	WARNING SIGNS
18000	LFDY	TEMPORARY BARRICADE, TYPE III
180	EADY	TEMPORARY WARNING SIGNS
580	SF	PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST
450	SF	TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND
715	LF	PERMANENT PAVEMENT STRIPING, EPOXY RESIN

		PAINT, 4"
165	SF	RETROREFLECTIVE PREFORMED PATTERNED MARKINGS, SYMBOL/LEGEND
590	SF	REMOVAL OF PAVEMENT STRIPING
29	EACH	INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE
30	LF	INSTALLING SANITARY SEWER, PVC, 8"
56	LF	INSTALLING SANITARY SEWER, PVC, 12"
23	LF	INSTALLING SANITARY SEWER, PVC, 15"
178	SY	REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT, CURB,
6	EAMO	FIELD OFFICE, SPECIAL I
503	LF	SAW CUTTING, HOT MIX
58	LF	SAW CUTTING, CONCRETE, FULL DEPTH
1	LS	INITIAL EXPENSE
1	LS	MAINTENANCE OF TRAFFIC
1	LS	CONSTRUCTION ENGINEERING
1	LS	PROJECT CONTROL SYSTEM DEVELOPMENT PLAN
4	EAMO	CPM SCHEDULE UPDATES AND/OR REVISED UPDATES

Plans, Specifications, and Bidding Proposals may be obtained from:
 Scott S. Gottfried, Competitively Bid Contracts Coordinator
 Delaware Department of Transportation
 P.O. Box 778
 Dover, DE 19903
 (302) 760-2030
 FAX (302) 739-2254
scott.gottfried@state.de.us

Checks should be made payable to Department of Transportation. When it is in the best interest of the State, DelDOT may extend the time and place for the opening of bids from that described above, on not less than two calendar days' notice by certified delivery, facsimile transmission, or by other verifiable electronic means to those bidders who obtained copies of the Plans, Specifications, Proposals or contract descriptions. Cost of the Contract Documents is not refundable.

DEPARTMENT OF TRANSPORTATION
 STATE OF DELAWARE
 BY: Carolann Wicks, Secretary
 DOVER, DE
 July 26, 2010