



DELAWARE STATE UNIVERSITY

OFFICE OF PLANNING & CONSTRUCTION

1200 N. DuPont Highway
Dover, Delaware 19901-2277

Addendum # 2

Date: April 27, 2016

Project: Wilmington Campus Paving and Draining Project

Contract: FD-15-069

The work herein shall be considered part of the bid documents for the referenced project and carried out in accordance with the following supplemental instructions issued in accordance with the Contract Documents without change in Contract Sum or Contract Time. Acknowledge receipt of addendum on the bid form as indicated.

Clarifications:

1. A minimum overlay depth of 2" of Type C Hot Mix is required.
2. Epoxy resin paint shall be required for long line striping. Thermo plastic (extruded or preformed material) will be required on Asphalt surfaces, for short line striping, i.e. symbols/legends.

Changes to Specifications:

1. Revisions were made to section 00 41 13 - Bid Form - Bid Bond, which indicate a list of subcontractors. See attached

Changes to Drawings:

1. Revised limits of mill and overlay.

General Information:

1. Pre-Bid Sign-in Sheet: Please see attached sheet for a list of the attendees at the mandatory pre-bid. **See attached.**
2. Pre-Bid Meeting Minutes: These minutes are now integral to the bidding documents. **See attached.**

Questions and Answers:

1. **Question:** There is a small grass area located on the northeast side of the one-story building that is called out to be milled and overlaid. Is this grass area to remain or to be paved?
Answer: The grass area and concrete pad are to remain. The drawings have been revised to reflect the correct mill and overlay limits.
2. **Question:** Are there any pavement markings required on any concrete?
Answer: There are no proposed markings on the concrete. The DeIDOT specification was used in the clarification section which referenced concrete, but was not applicable. It has been removed for clarification.
3. **Question:** Please confirm that there are no alternates or unit prices needed on the bid form.
Answer: There are no alternates or unit prices needed on the bid form.
4. **Question:** I received addendum # 1 but could you please clarify the pavement markings again? We're going to have the blue handicap parking stall lines and symbols, the regular parking stall lines and hash markings denoting no parking, the new crosswalk and replacing another existing crosswalk and then there are the yellow letters FIRE LANE in several places along with the long yellow lines that box out this no parking fire lane area. I'm not exactly sure what gets the epoxy, the thermo plastic and the permanent pavement marking tape.
Answer: All pavement lines/markings (including FIRE LANE text) are proposed to be epoxy resin, with the exception of the handicap symbols and the crosswalk symbols, which will be thermoplastic. All pavement markings shall be replaced in kind with the exception of the handicap spaces which were relocated on the plan.
5. **Question:** Does the sign near the proposed handicap ramp need to be moved by the contractor as part of this project?
Answer: The sign will need to be relocated by the contractor as part of this project. The sign was installed after the survey was done and is not shown on the plans. The sign shall be relocated approximately 3 feet to the southeast of proposed handicap ramp. Contractor shall coordinate with owner for the desired location of the sign in the field.
6. There are no Long Lines on this project
7. There is no striping on concrete surfaces on this project.

END