

## **Specifications - Two Center Office/Workrooms**

NETWORK	
COMPONENT	DESCRIPTION
General	
	See attached list of (15) approved manufacturers by "Geographic Regions"
Locations) Floor Plan/Drawing	Didder to provide proposed floor plan with hid Identify on #504.5
Description	Bidder to provide proposed floor plan with bid. Identify as #S64-5  (2) Offices with integral corridor. Center unit.
Exterior Dimensions	(2) Crinces with integral control. Center unit. 14'x 64' (896 sq.ft nominal).
Office Dimensions	14' x 28' 6" (399 sq-ft nominal).
Shipping Height	14' 6" or less. 14'2" or less in Northeast Region only.
State Approvals	As Required.
Regional Availability	All except State of California
Construction Type	V-B
Occupancy Classification Floors	E - Education.
Frame Type	Outrigger with main rails at 72" on center or as required by code.
Floor Framing	Journal of the state of the sta
	mate line walls.
Underlayment	Factory-installed, 1/4" or 1/2" hardibacker throughout.
Insulation	Kraft-faced R-22 or as required by code.
Bottom Board	Plastic, roll type.
Floor Live Load	50 PSF in offices and 100 PSF in corridor or as required by code.
Floor Covering - Offices and	12" x 12" x 1/8" standard "Excelon Imperial" vinyl composition tile as manufactured by Armstrong, or equal.
Corridor	
Cove Base	4" x .0125" Type TV thermoplastic vinyl as manufactured by Roppe , or equal.
Walls	
Interior Wall Covering	Factory standard 1/2" or 5/8" vinyl covered gypsum. Battenless at vertical panel seams.
Interior Wall Finish	ractory standard 12 of 30 winy covered gypsum. Batterness at ventical paner seams.  Group II, vind covered gypsum.
Inside and Outside Corners	Group II, vinyi covered gypsum. Vinyi covered wood battens.
Outside Corners - Corridor Only	Model 169V 2" x 2" x 8" 6" vinyl with Model 168A metal track as manufactured by InPro, or equal.
Interior Wall Framing	2" x 4" (SPF#2) at 16" on center to 8'6" minimum nominal wall height. Double top plate and single bottom plate.
Sound Insulation	Soundbatk® R-11 as manufactured by Owens Coming, or equal.
Exterior Wall Finish	5/16" Hardipanel® with T-molding. Vapor barrier. 1/8" thermoply sheathing or as required by code.
Exterior Wall Framing	2" x 6" (SPF#2) at 16" on center or as required by code. Double top plate and single bottom plate. 8'6" minimum nominal wall height.
Exterior Insulation	R-22 or as required by code.
Exterior Trim	Rough sawn cedar. 1" x 4" at corners, vertical mate lines, windows and doors. 1" x 6" at top and bottom of mansard and top of skirting.
Foundation Enclosure	5/16" Hardipanel® to 36" height above finish grade.
Foundation Vents	SolarTek Model "RA" automatic foundation vents. Quantity as required by code.
Mansard	5/16" Hardipanel® with T-molding. Vapor barrier. 1/8" thermoply sheathing or as required by code.
Corridor	1-hour rated walls and ceilings or as required by code.
Roof	The first state while comings of the required by beau.
Roof Membrane	.045 mil black EPDM Rubber with 10-year warranty as manufactured by Mule Hide Products. 1/4":12" slope or as required by code.
Roof Framing	Factory standard (SPF#2). Snow load as required by code.
Roof Insulation	R-38 Kraft-faced or as required by code.
Roof Mansard	1 1/2" x 30" projection around full perimeter.
Roof Ventilation	As required by code. No rooftop vents.
Roof Drainage	Terminate EPDM per Mule Hide detail MDE-109 dated 9/22/08. Manufacturer to furnish and install flashing as shown.
Ceiling	Textured gypsum with no visible fasteners as manufactured by Sea Spray Drywall Textures, or equal. 8'6" nominal ceiling height.
Doors and Door Hardware	
Interior Doors	See attached door schedule.
Electrical - Line Voltage	
Electrical Panel	120/208 VAC, single phase, 60 Hz panels sized as required by code. Location as shown.
Electrical Raceway Lighting	90°C Romex. EMT or MC cable above suspended ceiling or as required by code.  Electronic ballast with energy efficient lamps and infrared occupancy sensors.
Lighting - Corridor	Electronic ballast with energy efficient lamps and infrared occupancy sensors. Battery backup.
Lighting - Exit and Emergency	As required by code.
Office - Voice, Data, CATV, Fire	(1) 4" x 4" and (6) 2" x 4" junction boxes with cover plate and 3/4" EMT with pull wire to below finished floor per office. Locations to be determined.
Alarm, PA and Security	
Switches and Receptacles	Ivory with unbreakable plastic cover plates.
Electrical - Other Electrical - Low Voltage	As required by code.
Fire Alarm System	Factory to install rough in junction boxes as required. System labor and material by Others.
Security System	Factory to install rough in junction boxes as required. System labor and material by Others.  Factory to install rough in junction boxes as required. System labor and material by Others.
PA System	System labor and material by Others.
Voice	System labor and material by Others.
Data	System labor and material by Others.
CATV	System labor and material by Others.
HVAC	(4) Dard Model Witte At A. Ht. D. D. V. V. V. electric heat/local unit or Magnetic access. (***) = Oit (***) = Iit (***) = Iit (***)
Air Conditioning Unit	(1) Bard Model W***-A1-A-**-P-P-X-X-X electric heat/cool unit, or Marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and heat strips sized as required by code.
HVAC System Warranty	Strips sized as required by code.  5-year parts and 1-year labor.
Thermostat	(1) Bard Model 8403-060 electronic thermostat with auto changeover and Model 8405-033 lockable, plastic cover or Marvair equal.
Diffuser	Factory standard directional diffusers.
Smoke/Fire Dampers	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code
Supply and Return Air Duct	Fiberglass. Galvanized as may be required by code in one-hour rated areas.
Return Air Plenum	Plenum wall. (1) Model 900 FG, interior 20" x 30" return air filter grille as manufactured by Shoemaker or Bard equal. Located at 12" AFF.
Furnishings	
Storage Closet	(1) 3' x 5' with wire shelving at 72" AFF per office.
Building Options/Upgrades	
Frame Type and Floor Framing	Perimeter with cross members at 48" on center or as required by code. Provide 3/4" tongue and groove plywood over 2" x 6" (SPF#2) framing at 16" on center
FI 0 : 255	or as required by code.
Floor Covering - Offices	Field installed "Associate" 24 oz., 100% solution dyed nylon, broadloom carpet with Teklok backing as manufactured by Shaw. Delete hardibacker
Floor Covering - Offices	underlayment. Field installed "Captivate", 100% solution dyed nylon, 24" x 24" carpet tile with Ecoworx backing as manufactured by Shaw. Delete hardibacker underlayment.
Floor Covering - Offices	There installed Capitivate , 100 % Solution used hybor, 24 × 24 called the with Ecoworx backing as manufactured by Snaw, Delete naroibacker underlayment.
Roof Mansard	Around full perimeter. 1 1/2" x 30" projection on 64' walls and 24" x 30" projection on 14' walls. Hardisoffit® vented panels.
Ceiling	2' x 4' "Baroque" accoustical ceiling tile as manufactured by Certanteed, or equal. Includes Model "Snap Grid™ 200" 15/16" exposed ceiling grid as
-	manufactured by Chicago Metallic, or equal. 8'6" nominal ceiling height. Provide Model FPD 24" x 24", 4-way directional diffusers as manufactured by Hart
	and Cooley. All junction boxes (quantity as specified above) with cover plate and 3/4" EMT with pull wire to above finished ceiling in lieu of below finished
Poof Drainege	floor.  E' companyed complete aluminum authors with 2" v 4" daymopouts to grade. Eigld installed
Roof Drainage	5" commercial, seamless aluminum gutters with 3" x 4" downspouts to grade. Field installed.
Air Conditioning Unit	
Air Conditioning Unit	(1) Bard Model W**-H1-A-*-V-P-X-X-R electric heat pump unit, or Marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and heat strips sized as required by code
Air Conditioning Unit Storage Closet	(1) Bard Model W**-H1-A-*V-P-X-X-R electric neat pump unit, or marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and neat strips sized as required by code.  [2) 3' x 5' with wire shelving at 72" AFF.

The information contained herein is proprietary to the Keystone Purchasing Network (KPN) and it may not be reproduced or shared with any third party without the express writter KPN other then for the purposes of responding to this IPB.	consent of



## Specifications - Restrooms, Office/Workroom and Janitor Closet

THETWORK	
COMPONENT	DESCRIPTION
General	
	See attached list of (15) approved manufacturers by "Geographic Regions"
Locations)	
Floor Plan/Drawing Description	Bidder to provide proposed floor plan with bid. Identify as #S64-4 (2) Restrooms (Boy's and Girl's), Staff restroom, Janitor Closet and (1) Office/Workroom. Center unit.
Exterior Dimensions	(2) restricting topy a find chiral, other restricting samples dissert and (1) clinical violations. Center units.
Office/Workroom Dimensions	14' x 13' 6" (190 sq-ft nominal).
Shipping Height	14' 6" or less. 14'2" or less in Northeast Region only.
State Approvals	As Required.  All except State of California
Regional Availability Construction Type	An except state of California
Occupancy Classification	V=0 E - Education.
Floors	
Frame Type	Outrigger with main rails at 72" on center or as required by code.
Floor Framing	3/4" tongue and groove plywood over 2" x 6" (SPF#2) or 2" x 8" (SPF#2) at 16" on center or as required by code. Double side rails below all exterior and
	mate line walls.
Underlayment	Factory-installed, 1/4" or 1/2" hardibacker throughout.
Insulation	Kraft-faced R-22 or as required by code.
Bottom Board Floor Live Load	Plastic, roll type.  50 PSF or as required by code in Office, Boy's, Girl's and Staff restrooms and Janitor Closet. 100 PSF in corridor.
Floor Covering - Office and	12" x 12" x 1/8" standard "Excelon Imperial" vinyl composition tile as manufactured by Armstrong, or equal.
Corridor	, , , , , , , , , , , , , , , , , , , ,
Floor Covering - Restrooms	Factory installed, 80 mil, commercial grade "Connection Corlon" heat welded vinyl roll goods as manufactured by Armstrong.
Floor Covering - Janitor Closet	Factory installed, 75 mil, commercial grade "Coin Pattern" vinyl roll goods as manufactured by Better Life Technologies, or equal.
Cove Base - Office and Corridor	4" x .0125" Type TV thermoplastic vinyl as manufactured by Roppe , or equal.
	6" x .0125" Type TV thermoplastic vinyl as manufactured by Roppe , or equal.
Closet	
Walls	
Interior Wall Covering	Factory standard 1/2" or 5/8" vinyl covered gypsum. Battenless at vertical panel seams.
Interior Wall Finish	Group II, vinyl covered gypsum.
Inside and Outside Corners Outside Corners - Corridor Only	Vinyl covered wood battens.  Model 169V 2" x 2" x 8' 6" vinyl with Model 168A metal track as manufactured by InPro, or equal.
-	0.30" FRP over APA-rated substrate. Full wall height.
Janitor Closet	1000 TTA OFFICE AND ATRICE SUBSTITUTE TO THE MET HEIGHT.
Interior Wall Framing	2" x 4" (SPF#2) at 16" on center to 8'6" minimum nominal wall height. Double top plate and single bottom plate.
Sound Insulation	Soundbatts® R-11 as manufactured by Owens Corning, or equal.
Exterior Wall Finish	5/16" Hardipanel® with T-molding. Vapor barrier. 1/8" thermoply sheathing or as required by code.
Exterior Wall Framing	2" x 6" (SPF#2) at 16" on center or as required by code. Double top plate and single bottom plate. 8'6" minimum nominal wall height.
Exterior Insulation	R-22 or as required by code.
Exterior Trim	Rough sawn cedar. 1" x 4" at corners, vertical mate lines, windows and doors. 1" x 6" at top and bottom of mansard and top of skirting.
Foundation Enclosure	5/16" Hardipanel® to 36" height above finish grade.
Foundation Vents	SolarTek Model "RA" automatic foundation vents. Quantity as required by code.
Mansard	5/16" Hardipanel® with T-molding. Vapor barrier. 1/8" thermoply sheathing or as required by code.
Corridor	1-hour rated walls and ceilings or as required by code.
Roof	
Roof Membrane	.045 mil black EPDM Rubber with 10-year warranty as manufactured by Mule Hide Products. 1/4":12" slope or as required by code.
Roof Framing Roof Insulation	Factory standard (SPF#2). Snow load as required by code.  R-38 Kraft-faced or as required by code.
Roof Mansard	11/2" x 30" projection around full perimeter.
Roof Ventilation	As required by code. No rooftop vents.
Roof Drainage	Terminate EPDM per Mule Hide detail MDE-109 dated 9/22/08. Manufacturer to furnish and install flashing as shown.
Ceiling	Textured gypsum with no visible fasteners as manufactured by Sea Spray Drywall Textures, or equal. 8'6" nominal ceiling height.
Windows	
Windows	(1) 48" x 48" vinyl frame, horizontal sliding windows with insect screens and low-E, double insulated glass per classroom.
Window Accessories	(1) 1" Ascot, horizontal louver mini-blinds.
Doors and Door Hardware	
Interior Doors	See attached door schedule.
Electrical - Line Voltage Electrical Panel	120/208 VAC single phase 60 Hz nanels sized as required by code. Location as shown
Electrical Panel Electrical Raceway	120/208 VAC, single phase, 60 Hz panels sized as required by code. Location as shown.  90°C Romex. EMT or MC cable above suspended ceiling or as required by code.
Lighting	See dividing: I will divide above above assignment of the appearance by code.  Electronic ballast with energy efficient lamps and infrared occupancy sensors.
Lighting - Corridor	Electronic ballast with energy efficient lamps and infrared occupancy sensors. Battery backup.
Lighting - Exit and Emergency	As required by code.
Office - Voice, Data, CATV, Fire Alarm, PA and Security	(6) 4" x 4" and (6) 2" x 4" junction boxes with cover plate and 3/4" EMT with pull wire to below finished floor. Locations to be determined.
Switches and Receptacles	Ivory with unbreakable plastic cover plates.
Electrical - Other	As required by code.
Electrical - Low Voltage	
Fire Alarm System	Factory to install rough in junction boxes as required. System labor and material by Others.
Security System PA System	Factory to install rough in junction boxes as required. System labor and material by Others.  System labor and material by Others.
Voice PA System	System labor and material by Others.  System labor and material by Others.
Data	System labor and material by Others. System labor and material by Others.
CATV	System labor and material by Others.
HVAC	
Air Conditioning Unit	(1) Bard Model W***-A1-A-**-P-P-X-X-X electric heat/cool unit, or Marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and heat strips sized as required by code.
HVAC System Warranty	sinps sized as required by code.  5-year parts and 1-year labor.
Thermostat	(1) Bard Model 8403-060 electronic thermostat with auto changeover and Model 8405-033 lockable, plastic cover or Marvair equal.
Diffuser	Factory standard directional diffusers.
Smoke/Fire Dampers	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.
Exhaust Fan	(3) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.
Supply and Return Air Duct	Fiberglass. Galvanized as may be required by code in one-hour rated areas.
Return Air Plenum	Plenum wall. (1) Model 900 FG, interior 20" x 30" return air filter grille as manufactured by Shoemaker or Bard equal. Located at 12" AFF.
Plumbing	
Piping	Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.
Water Cooler	(1) Model VRCTL8SC stainless steel as manufactured by Elkay.
Service Sink	(1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet.
Office/Work Room Sink	(1) Model PSRQ1918-2, 19" x 18" x 7 1/8" stainless steel sink and Model LKE4121 faucet as manufactured by Elkay.


Water Closet	(1) Madera Model 2234.015 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite.
Water Closet	(3) Madera Model 3043.102 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite. ADA compliant. Stainless steel grab bars.
Urinal	(1) Trimbrook Model vitreous china as manufactured by American Standard with Royal 186-1 Model flush valuve as manufactured by Sloan.
Modesty Partitions	Floor-mounted, 1" thick HDPE, overhead braced toilet compartments as manufactured by Santana Products, Comtec Industries or Capitol Partitions. 15-year warranty.
Lavatory	(5) Comrade Model 18" x 20", vitreous china wall-hung as manufactured by American Standard. Factory standard. ADA compliant.
Lavatory Faucet	(1) Model 802-V665CP as manufactured by Chicago Faucet per lavatory.
Water Heater	(1) Electric water heater. Size as required by code.
Recirculating Pump	(1) Model UP15-42SF as manufactured by Grundfos.
Mirror	(1) 18" x 36" with stainless steel frame per lavatory.
Restroom Accessories	Soap, toilet paper, sanitary napkin and paper towel dispensers by Others.
Furnishings	
Cabinet - Office	(1) Model "Essentials Rutland II" 24" x 72" base cabinet with 12" x 72" upper cabinet. Includes 25 1/2" x 72" x 1/16" HPLAM countertop.
Building Options/Upgrades	
Frame Type and Floor Framing	Perimeter with cross members at 48" on center or as required by code. Provide 3/4" tongue and groove plywood over 2" x 6" (SPF#2) framing at 16" on center or as required by code.
Floor Covering - Office	Field installed "Associate" 24 oz., 100% solution dyed nylon, broadloom carpet with Teklok backing as manufactured by Shaw. Delete hardibacker underlayment.
Floor Covering - Office	Field installed "Captivate", 100% solution dyed nylon, 24" x 24" carpet tile with Ecoworx backing as manufactured by Shaw. Delete hardibacker underlayment.
Roof Mansard	Around full perimeter. 1 1/2" x 30" projection on 64' walls and 24" x 30" projection on 14' walls. Hardisoffit® vented panels.
Ceiling	2' x 4' "Baroque" accoustical ceiling tile as manufactured by Certanteed, or equal. Includes Model "Snap Grid™ 200" 15/16" exposed ceiling grid as manufactured by Chicago Metallic, or equal. 8'6" nominal ceiling height. Provide Model FPD 24" x 24", 4-way directional diffusers as manufactured by Hart and Cooley. All junction boxes (quantity as specified above) with cover plate and 3/4" EMT with pull wire to above finished ceiling in lieu of below finished floor.
Roof Drainage	5" commercial, seamless aluminum gutters with 3" x 4" downspouts to grade. Field installed.
Air Conditioning Unit	(1) Bard Model W***-H1-A-**-V-P-X-X-R electric heat pump unit, or Marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and heat strips sized as required by code.



## **Specifications - Restrooms, Technology and Janitor Closet**

THETTYORK	4,44,44,44,44,44,44,44,44,44,44,44,44,4
COMPONENT	DESCRIPTION
General	
Approved Manufacturers (Plant	See attached list of (15) approved manufacturers by "Geographic Regions"
Locations)	
Floor Plan/Drawing	Bidder to provide proposed floor plan with bid. Identify as #S64-3
Description Exterior Dimensions	(2) Restrooms (Boy's and Girl's), Staff restroom, Janitor Closet and Tech Closet. Center unit.  14' x 64' (896 sq-ft nominal).
Classroom Dimensions	14 x 04 (050 \$Q-1( HOHIMIA).  N/A  N/A
Shipping Height	14' 6" or less. 14'2" or less in Northeast Region only.
State Approvals	As Required.
Regional Availability	All except State of California
Construction Type	V-B
Occupancy Classification	E - Education.
Floors	Outside suith arising its at 700 and a suite at the suite
Frame Type Floor Framing	Outrigger with main rails at 72" on center or as required by code.  3/4" tongue and groove plywood over 2" x 6" (SPF#2) or 2" x 8" (SPF#2) at 16" on center or as required by code. Double side rails below all exterior and
1 loor 1 running	mate line walls.
Underlayment	Factory-installed, 1/4" or 1/2" hardibacker throughout.
Insulation	Kraft-faced R-22 or as required by code.
Bottom Board	Natiraceu N-22 di as requireu by code. Plastic, roll type.
Floor Live Load	50 PSF or as required by code in Office, Boy's, Girl's and Staff restrooms and Janitor and Technology Closets. 100 PSF in corridor.
Floor Covering - Corridor	12" x 12" x 1/8" standard "Excelon Imperial" vinyl composition tile as manufactured by Armstrong, or equal.
Floor Covering - Restrooms	Factory installed, 80 mil, commercial grade "Connection Corlon" heat welded vinyl roll goods as manufactured by Armstrong.
Floor Covering - Janitor and	Factory installed, 75 mil, commercial grade "Coin Pattern" vinyl roll goods as manufactured by Better Life Technologies.
Technology Closets	Today inclination of the committee of th
	The second secon
Cove Base - Corridor and	4" x .0125" Type TV thermoplastic vinyl as manufactured by Roppe , or equal.
Technology Closet	
	6" x .0125" Type TV thermoplastic vinyl as manufactured by Roppe , or equal.
Closet	
Walls	
Interior Wall Covering	Factory standard 1/2" or 5/8" vinyl covered gypsum. Battenless at vertical panel seams.
Interior Wall Finish	Group II, vinyl covered gypsum.
Inside and Outside Corners	Vinyl covered wood battens.
Outside Corners - Corridor Only	Model 169V 2" x 2" x 8' 6" vinyl with Model 168A metal track as manufactured by InPro, or equal.
	1 030" FRP over APA-rated substrate. Full wall height.
Janitor Closet	
Interior Wall Framing	2" x 4" (SPF#2) at 16" on center to 8'6" minimum nominal wall height. Double top plate and single bottom plate.
Sound Insulation Exterior Wall Finish	Soundbatts® R-11 as manufactured by Owens Coming, or equal.  5/16" Hardipanel® with T-molding. Vapor barrier. 1/8" thermoply sheathing or as required by code.
Exterior Wall Framing	2"x 6" (SP#2) at 16" on center or as required by code. Double top plate and single bottom plate. 8'6" minimum nominal wall height.
Exterior Insulation	R-22 or as required by code.
Exterior Trim	Rough sawn cedar. 1" x 4" at corners, vertical mate lines, windows and doors. 1" x 6" at top and bottom of mansard and top of skirting.
Foundation Enclosure	5/16" Hardipanel® to 36" height above finish grade.
Foundation Vents	SolarTek Model "RA" automatic foundation vents. Quantity as required by code.
Mansard	5/16" Hardipanel® with T-molding. Vapor barrier. 1/8" thermoply sheathing or as required by code.
Corridor	1-hour rated walls and ceilings or as required by code.
Roof	into trated waits and ceilings or as required by code.
Roof Membrane	.045 mil black EPDM Rubber with 10-year warranty as manufactured by Mule Hide Products. 1/4":12" slope or as required by code.
Roof Framing	Factory standard (SPF#2). Snow load as required by code.
Roof Insulation	R-38 Kraft-faced or as required by code.
Roof Mansard	1 1/2" x 30" projection around full perimeter.
Roof Ventilation	As required by code. No rooftop vents.
Roof Drainage	Terminate EPDM per Mule Hide detail MDE-109 dated 9/22/08. Manufacturer to furnish and install flashing as shown.
Ceiling	Textured gypsum with no visible fasteners as manufactured by Sea Spray Drywall Textures, or equal. 8'6" nominal ceiling height.
Doors and Door Hardware	
Interior Doors	See attached door schedule.
Electrical - Line Voltage	100000140
Electrical Panel Electrical Raceway	120/208 VAC, single phase, 60 Hz panels sized as required by code. Location as shown.  90°C Romex. EMT or MC cable above suspended ceiling or as required by code.
Lighting	Section is a light of with cause above suspensed usefund or as required by code.  Electronic ballast with energy efficient lamps and infrared occupancy sensors.
Lighting - Corridor	Electronic ballast with energy efficient lamps and infrared occupancy sensors. Battery backup.
Lighting - Exit and Emergency	As required by code.
Fire Alarm, PA and Security	2" x 4" junction boxes with cover plate and 3/4" EMT with pull wire to above finished ceiling. Locations to be determined.
Switches and Receptacles	Ivory with unbreakable plastic cover plates.
Electrical - Other Electrical - Low Voltage	As required by code.
Fire Alarm System	Factory to install rough in junction boxes as required. System labor and material by Others.
Security System	Factory to install rough in junction boxes as required. System labor and material by Others.  Factory to install rough in junction boxes as required. System labor and material by Others.
PA System	System labor and material by Others.
HVAC	
Air Conditioning Unit	[1] Bard Model W***-A1-A-**-P-P-X-X-X-X electric heat/cool unit, or Marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and heat
UVAC Sustan Marrow	strips sized as required by code.  5-year parts and 1-year labor.
HVAC System Warranty Thermostat	3-year parts and 1-year labor. [1] Bard Model 8403-060 electronic thermostat with auto changeover and Model 8405-033 lockable, plastic cover or Marvair equal.
Diffuser	Tractory standard directional diffusers.
Smoke/Fire Dampers	
	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.
Smoke/Fire Dampers Exhaust Fan	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.
Smoke/Fire Dampers	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler Service Sink	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.  (1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.  (1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet  (6) Madera Model 2234.015 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler Service Sink Water Closet	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.  (1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet  (6) Madera Model 2234 015 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler Service Sink	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.  (1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet  (6) Madera Model 2234.015 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite.  (3) Madera Model 3043.102 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler Service Sink Water Closet	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.  (1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet  (6) Madera Model 2234 015 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler Service Sink Water Closet Urinal	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.  (1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet  (6) Madera Model 2234.015 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite.  (3) Madera Model 304.3 102 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite. ADA compliant. Stainless steel grab bars.  (2) Trimbrook Model vitreous china as manufactured by American Standard with Royal 186-1 Model flush valve as manufactured by Sloan.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler Service Sink Water Closet Water Closet	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.  (1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet  (6) Madera Model 2234.015 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite.  (3) Madera Model 3043.102 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite. ADA compliant. Stainless steel grab bars.  (2) Trimbrook Model vitreous china as manufactured by American Standard with Royal 186-1 Model flush valuve as manufactured by Sloan.  Floor-mounted, 1" thick HDPE, overhead braced toilet compartments as manufactured by Santana Products, Comtec Industries or Capitol Partitions. 15-ye.
Smoke/Fire Dampers Exhaust Fan Supply and Return Air Duct Plumbing Piping Water Cooler Service Sink Water Closet Urinal	Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code.  (2) Model L500 500 CFM and (1) Model 676 110 CFM ceiling mounted as manufactured by Broan. Wire to light switch.  Fiberglass. Galvanized as may be required by code in one-hour rated areas.  Type "L" copper supply. Schedule 40 PVC or ABS sanitary or as required by code.  (1) Model VRCTL8SC stainless steel as manufactured by Elkay.  (1) Model MSB-2424, floor-mounted fiberglass service sink as manufactured by Fiat. Includes (1) Model 897-CP faucet as manufactured by Chicago Faucet  (6) Madera Model 2234.015 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite.  (3) Madera Model 304.3 102 vitreous china with elongated bowl as manufactured by American Standard. Royal 111 Model flush valve as manufactured by Sloan. Heavy duty Model 95SSC plastic seat as manufactured by Olsenite. ADA compliant. Stainless steel grab bars.  (2) Trimbrook Model vitreous china as manufactured by American Standard with Royal 186-1 Model flush valve as manufactured by Sloan.

Lavatory Faucet	(1) Model 802-V665CP as manufactured by Chicago Faucet per lavatory.
Water Heater	(1) Electric water heater. Size as required by code.
Recirculating Pump	(1) Model UP15-42SF as manufactured by Grundfos.
Mirror	(1) 18" x 36" with stainless steel frame per lavatory.
Restroom Accessories	Soap, toilet paper, sanitary napkin and paper towel dispensers by Others.
Building Options/Upgrades	
Frame Type and Floor Framing	Perimeter with cross members at 48" on center or as required by code. Provide 3/4" tongue and groove plywood over 2" x 6" (SPF#2) framing at 16" on center
	or as required by code.
Roof Mansard	Around full perimeter. 1 1/2" x 30" projection on 64' walls and 24" x 30" projection on 14' walls. Hardisoffit® vented panels.
Ceiling	2' x 4' "Baroque" accoustical ceiling tile as manufactured by Certanteed, or equal. Includes Model "Snap Grid™ 200" 15/16" exposed ceiling grid as
	manufactured by Chicago Metallic, or equal. 8'6" nominal ceiling height. Provide Model FPD 24" x 24", 4-way directional diffusers as manufactured by Hart and Cooley. All junction boxes (quantity as specified above) with cover plate and 3/4" EMT with pull wire to above finished ceiling in lieu of below finished
Roof Drainage	floor.
	5" commercial, seamless aluminum gutters with 3" x 4" downspouts to grade. Field installed.
Air Conditioning Unit	(1) Bard Model W***-H1-A-**-V-P-X-X-X-R electric heat pump unit, or Marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and heat
	strips sized as required by code.



Perimeter with cross members at 48" on center or as required by code. Provide 3/4" tongue and groove plywood over 2" x 6" (SPF#2) framing at 16" on center or as required by code. Field installed "Associate" 24 oz., 100% solution dyed nylon, broadloom carpet with Teklok backing as manufactured by Shaw. Delete hardibacker

Field installed "Captivate", 100% solution dyed nylon, 24" x 24" carpet tile with Ecoworx backing as manufactured by Shaw. Delete hardibacker underlayment

Around full perimeter. 1 1/2" x 30" projection on 64' walls and 24" x 30" projection on 14' walls. Hardisoffit® vented panels.
2' x 4" "Baroque" accoustical ceiling tile as manufactured by Certanteed, or equal. Includes Model "Snap Grid™ 200" 15/16" exposed ceiling grid as manufactured by Chicago Metallic, or equal. 8'6" nominal ceiling height. Provide Model FPD 24" x 24", 4-way directional diffusers as manufactured by Hart and Cooley. All junction boxes (quantity as specified above) with cover plate and 3/4" EMT with pull wire to above finished ceiling in lieu of below finished

5" commercial, seamless aluminum gutters with 3" x 4" downspouts to grade. Field installe

Building Options/Upgrades
Frame Type and Floor Framing

Floor Covering - Classroom


Floor Covering - Classrooms

Roof Mansard Ceiling

Roof Drainage

underlayment

Air Conditioning Unit	(2) Bard Model W***-H1-A-**-V-P-X-X-R electric heat pump unit, or Marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and heat strips sized as required by code.
Carbon Dioxide Sensor	(2) Bard 8403-056 CO2 sensor, or Marvair equal, with vent demand relay.
Energy Management Controller	(2) Bard CS2000A, or Marvair equal.
Coat Hook Assembly	(2) 12" deep x 10' wide aluminum assembly with plastic coat hooks as manufactured by EMCO.
Markerboard	(2) Factory standard, 4' x 12' porcelain on steel white board with aluminum frame and map rail with (4) hooks.
Tackboard	(4) Factory standard, 4 'x 4' cork boards with aluminum frame.
Storage Closet	(2) 3' x 5' with wire shelving at 72" AFF.



(4) Bard Model 8403-060 electronic thermostat with auto changeover and Model 8405-033 lockable, plastic cover or Marvair equal

Fiberglass. Galvanized as may be required by code in one-hour rated areas.

Plenum wall. (1) Model 900 FG, interior 20" x 30" return air filter grille as manufactured by Shoemaker or Bard equal per classroom. Located at 12" AFF

Perimeter with cross members at 48" on center or as required by code. Provide 3/4" tongue and groove plywood over 2" x 6" (SPF#2) framing at 16" on cente or as required by code.
Field installed "Associate" 24 oz., 100% solution dyed nylon, broadloom carpet with Teklok backing as manufactured by Shaw. Delete hardibacker

Field installed "Captivate", 100% solution dyed nylon, 24" x 24" carpet tile with Ecoworx backing as manufactured by Shaw. Delete hardibacker underlaymen

Model D-315WB fire or Model D-502 smoke/fire as manufactured by Leader Industries, or equal. Provide as required by code

Around full perimeter. 1 1/2" x 30" projection on 64' walls and 24" x 30" projection on 14' walls. Hardisoffit® vented panels.

**HVAC System Warranty** 

Smoke/Fire Dampers Supply and Return Air Duct Return Air Plenum

Fire Extinguisher

Roof Mansard

Frame Type and Floor Framing

Floor Covering - Classrooms

Floor Covering - Classrooms

Factory standard directional diffusers

underlayment

(1) 10# ABC with semi-recessed cabinet per exit.

Thermostat Diffuser

Furnishings

Ceiling	2' x 4' "Baroque" accoustical ceiling tile as manufactured by Certanteed, or equal. Includes Model "Snap Grid™ 200" 15/16" exposed ceiling grid as manufactured by Chicago Metallic, or equal. 8'6" nominal ceiling height. Provide Model FPD 24" x 24", 4-way directional diffusers as manufactured by Hart and Cooley. All junction boxes (quantity as specified above) with cover plate and 3/4" EMT with pull wire to above finished ceiling in lieu of below finished floor.
Roof Drainage	5" commercial, seamless aluminum gutters with 3" x 4" downspouts to grade. Field installed.
Air Conditioning Unit	(4) Bard Model W***-H1-A-**-V-P-X-X-X-R electric heat pump unit, or Marvair equal. (***) = Cooling Capacity; (**) = Heating Capacity. Compressor and heat
	strips sized as required by code.
Carbon Dioxide Sensor	(4) Bard 8403-056 CO2 sensor, or Marvair equal, with vent demand relay.
Energy Management Controller	(4) Bard CS2000A, or Marvair equal.
Coat Hook Assembly	(4) 12" deep x 10' wide aluminum assembly with plastic coat hooks as manufactured by EMCO.
Markerboard	(4) Factory standard, 4' x 12' porcelain on steel white board with aluminum frame and map rail with (4) hooks.
Tackboard	(8) Factory standard, 4 'x 4' cork boards with aluminum frame.
Storage Closet	(4) 3' x 5' with wire shelving at 72" AFF.