



ARCHITECTURE
ENGINEERING

September 10, 2012

Re: **GEORGETOWN MIDDLE SCHOOL – AUDITORIUM RENOVATIONS**

Georgetown, Delaware
2012083.00

ADDENDUM THREE

The contract documents for the above referenced project, dated July 20, 2012, are amended as follows:

Date of bid is unchanged.

CLARIFICATION

1. Fasteners in wood floor of auditorium from previously removed seating will be removed by Owner prior to commencement of construction.
2. For brick masonry window infill, aesthetic intent is to match existing face brick and mortar color and texture.

PROJECT MANUAL

1. **SECTION 042113 BRICK MASONRY**
 - a. REVISE paragraph 2.2.B.1.a as follows: “Old Virginia Brick; Old Virginia Red Colonial Range Wood Mould Modular, to match existing adjacent brick color and texture.”
 - b. ADD paragraph 2.2.B.1.c, as follows: “Cushwa; 154 Montgomery, or 238 Lexington, to match existing adjacent brick color and texture.”
 - c. ADD paragraph 2.3.E.1.b, as follows: “Essroc; Flamingo Brixment, OC Old Colonial, or B-11 Clay, to match existing adjacent mortar color.”

DRAWINGS

1. n/a

END OF ADDENDUM NO. THREE

201208300_Addendum3.doc