

727510 - WOOD RAIL FENCE**Description:**

This work consists of furnishing all materials and constructing wood rail fence, including post excavation and backfilling, in accordance with the plans, details and specifications at the locations shown on the Plans and as directed by the Engineer. Contractor acknowledges that wood fence posts will be predominantly installed into existing rock subgrade.

Material and Construction Methods:

All materials, such as fence, posts, #57 stone, hardware and accessories shall be new. Concrete, if necessary, shall conform to Section 812, Class B of the Standard Specifications.

Lumber shall be grade 2, conforming to Subsection 601.02 of the Standard Specifications.

Lumber shall be treated in accordance with Subsection 814 (b) water borne preservative of the Standard Specifications.

All hardware shall conform to the requirements and Subsection 601.07 of the Standard Specifications.

Method of Measurement:

The quantity of wood rail fence will be a Lump Sum item of the actual fence constructed and accepted.

Basis of Payment:

The quantity of wood rail fence will be paid for as a Lump Sum item. Price and payment will constitute full compensation for all new materials and installing fence, concrete if required, excavation and backfilling, for all labor, tools, and incidentals necessary to complete the item.