



State of Delaware  
Department of Natural Resources and Environmental Control  
Delaware Division of Parks and Recreation  
89 Kings Highway  
Dover, Delaware 19901

## **CONTRACT DOCUMENTS & TECHNICAL SPECIFICATIONS ADDENDUM No. 3**

### **Rocky Run Bridge Replacement Contract No. 2015-BC-100 Project No. BC-12 May 6 2015**

This Addendum shall be attached to the specifications and/or drawings of the above named project and shall become part of the contract documents. All statements made herein shall supersede statements in the main body of the specifications and items shown on the drawings with which they are in conflict. Work and materials not specifically mentioned herein shall be as described in the main body of the specifications and as shown on the drawings. The bidder must acknowledge the receipt of this addendum on page 004113-4 of the Bid Form.

#### **CHANGES AND/OR ADDITIONS TO THE CONTRACT DOCUMENTS**

##### **Modifications to Drawings:**

Plan Sheet C1.1, Project Notes, include the following note:

“25. Material excavated during construction may be used as backfill for the bridge structure provided it is granular in nature, conforming to the Unified Soil Classification GW, GP, GM, SW, SP, or SM and shall be free of rocks/stones larger than three (3) inches in diameter. Backfill shall be placed in eight (8) inch lifts and compacted to 95 percent modified proctor maximum dry density in accordance with AASHTO T180. Additional backfill material required shall meet the requirements of Borrow, Type C, as specified in the State of Delaware Department of Transportation Standard Specifications.”

##### **Modifications to Specifications:**

Refer to Section 132950 Prefabricated Steel Bridge, Paragraph 2.1B: Big R Bridge shall be listed as an approved manufacturer and shall meet the specified requirements.

##### **Changes to Bid Documents:**

None

