



GatorDock

Marine Access Solutions

SCOPE OF SUPPLIES

Project:

Woodland Wharf

List Created By:

Reese Patten

Date:

9/11/2018

Item	Description	Size	Quantity
FLOATING DOCK	Full Float, Aluminum Deck, PT Fender, D-Bumper, Tube Curb, Cleats, & Hinge Connections	6'x25'	2
GANGWAY	DR1 with Aluminum Deck, Grabrail, Midrail, Toerail, & Compensation Float	5'x30'	1
EASY KAYAK LAUNCH	Handrails on Both Sides	-	1
EXTERNAL PILE GUIDE	4-Roller	12"Ø Pile	4
EXTERNAL PILE GUIDE	1-Roller	15"Ø Pile	4
NARRAGANSETT HINGE	-	6'	1

Only four external pile guides will be installed as there will only be 4 timber guide piles. An in the field decision will be made as to which roller (4-roller or 1 roller) design will be used.