
STATE OF DELAWARE DEPARTMENT OF NATURAL RESOURCES AND ENVIRONMENTAL CONTROL DIVISION OF PARKS AND RECREATION




HOLTS LANDING BOARDWALK & TRAIL IMPROVEMENTS





LOCATION MAP




SITE MAP



ROJE TWO. HL-100


SEPTEMBER 2018




BID DOCUMENTS



NO TITLE
C300 - COVER SHEET
C301 - PROJECT NOTES & LEGEND
C302 - OVERAL SITE LAYOUT
C303 - TRAIL ALIGNMENTS #1, #2, #3
C304 - TRAIL ALIGNMENTS #4, #5
C305 - PARKING LOT SITE PLAN
C306 - SIGNING & STRIPING PLAN
C307 - BOARDWALK PROFILES
C308 - STRUCTURAL DETAILS
C309 - CONSTRUCTION DETAILS
SSMP500 - SEDIMENT & STORMWATER MANAGEMENT PLAN
SSMP501 - EROSION & SEDIMENT CONTROL DETAILS
SSMP502 - EROSION & SEDIMENT CONTROL DETAILS



USGS QUADRANGLE MAP



PROJECT NOTES

- 1. THE INTENT OF THIS PROJECT IS TO PROVIDE THE FOLLOWING IMPROVEMENTS AT THE HOLTS LANDING STATE PARK: CONSTRUCTION OF 4.416 L.F. OF GRAVEL TRAIL IN PLACE OF THE EXISTING SEA HAWK TRAIL ALIGNMENT.
- CONSTRUCTION OF 1,304 L.F. OF NEW GRAVEL TRAIL TO RELOCATE PORTIONS OF THE EXISTING SEA HAWK TRAIL.
- CONSTRUCTION OF 629 L.F. OF NEW GRAVEL TRAIL ALONG THE SOUTHERN EDGE OF THE EXISTING PARKING LOT. 1.3. CONSTRUCTION OF ONE (1) 600' LONG BOARDWALK. 1.4. CONSTRUCTION OF ONE (1) 60' LONG BOARDWALK.
- 2. THESE PLANS HAVE BEEN DEVELOPED IN ACCORDANCE WITH THE CURRENT EDITION OF THE "ACCESSIBILITY STANDARDS FOR FEDERAL OUTDOOR DEVELOPED AREAS".
- 3. PARCEL AND BOUNDARY LINES REFERENCED FROM GIS INFORMATION. NO BOUNDARY SURVEY WAS REQUESTED OR PERFORMED FOR THIS PROJECT.
- 4. THESE PLANS UTILIZE 2-FOOT LIDAR TOPOGRAPHY REFERENCED FROM THE STATE OF DELAWARE. CONVENTIONAL FIELD SURVEY WAS PROVIDED BY CENTURY ENGINEERING USING THE STATE PLANE COORDINATE SYSTEM FOR THE AREA OF THE PROPOSED 600' BOARDWALK ON THE NORTH END OF THE SITE LABELED AS NEW TRAIL ALIGNMENT #5. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL ADDITIONAL PHYSICAL CONTROL AS REQUIRED TO COMPLETE THE WORK AT NO
- 5. EXISTING UTILITIES SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE AT THE TIME THIS PLAN WAS DEVELOPED. COMPLETENESS OR CORRECTNESS OF THE UTILITIES SHOWN THEREOF IS NOT GUARANTEED. THE CONTRACTOR IS RESPONSIBLE FOR EMPLOYING AN UNDERGROUND UTILITY LOCATOR TO LOCATE AND MARK EXISTING UTILITIES WITHIN THE LIMIT OF DISTURBANCE PRIOR TO BEGINNING CONSTRUCTION.
- 6. THE CONTRACTOR SHALL STAKE OUT THE ALIGNMENT FOR REVIEW AND APPROVAL BY THE ENGINEER PRIOR TO BEGINNING CONSTRUCTION. MINOR ADJUSTMENT IN THE ALIGNMENT AND/OR PROFILE MAY BE REQUIRED BY THE ENGINEER IN THE FIELD TO AVOID EXISTING FEATURES TO REMAIN, INCLUDING TREES, OR TO PROVIDE OPTIMUM ALIGNMENT. INDIVIDUAL TREES WERE NOT SURVEY LOCATED.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR TEMPORARY RELOCATION OR SUPPORT OF ANY ELECTRICAL AND/OR COMMUNICATION LINES, AND ELECTRICAL/COMMUNICATION PEDESTALS THAT INTERFERE WITH THE PROPOSED WORK AT NO ADDITIONAL COST TO THE PROJECT, AS DIRECTED BY THE ENGINEER. WORK SHALL INCLUDE, BUT IS NOT LIMITED TO, EXCAVATION/TRENCHING, MATERIALS, AND ALL LABOR.
- 8. PORTIONS OF THIS CONTRACT ARE TO BE CONSTRUCTED IN ACCORDANCE WITH DELAWARE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (STANDARD SPECIFICATIONS) DATED AUGUST 2016 INCLUDING ALL REVISIONS UP TO ADVERTISEMENT OF THIS PROJECT, UNLESS NOTED OTHERWISE IN THESE PLANS OR THE SPECIFICATIONS. ITEMS INCLUDING, BUT NOT LIMITED TO, ASPHALT PAVEMENT, AND EXCAVATION AND EMBANKMENT, ARE TO REFER TO THE "STANDARD SPECIFICATIONS" FOR MATERIALS AND METHOD OF CONSTRUCTION.
- 9. LEAF LITTER SHALL BE PULLED BACK AND STOCKPILED AT THE EDGE OF THE LOD TO BE USED TO STABILIZE AND DRESS-UP EDGES/SHOULDERS FOLLOWING GRADING OF SHOULDERS.
- 10. TOPSOIL SHALL BE STRIPPED, STOCKPILED, AND STABILIZED FOR FUTURE USE ON THIS PROJECT IN ACCORDANCE WITH THE DELAWARE EROSION & SEDIMENT CONTROL HANDBOOK, CURRENT EDITION. STOCKPILE AREAS TO BE WITHIN HOLTS LANDING CREEK STATE PARK AT LOCATIONS SHOWN ON THESE PLANS, OR AT AREAS DETERMINED BY THE ENGINEER IN THE FIELD.
- 11. EXCAVATED TOPSOIL SHALL BE USED AS SHOULDER MATERIAL ALONG ENTIRE LENGTH OF TRAIL. ADDITIONALLY, EXCAVATED MATERIAL AT NEW TRAIL CONSTRUCTION SHALL BE SPREAD ON PORTIONS OF THE EXISTING TRAIL(S) TO BE ABANDONED, EXCEPT IN LOCATIONS WHERE THE EXISTING TRAIL IS LOCATED WITHIN WETLANDS. EXCESS EXCAVATED MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE LEGALLY DISPOSED OF OFF SITE.
- 12. CLEARING AND GRUBBING IS ASSUMED TO EXTEND A MINIMUM OF EIGHTEEN (18) INCHES BELOW EXISTING GRADE FOR FOR ALL NEW PAVED AREAS. CLEARING AND GRUBBING WITHIN THE LIMITS OF DISTURBANCE (LOD) SHALL CONSIST OF CLEARING, GRUBBING, REMOVING AND DISPOSING OF ALL TREES, ROOTS, VEGETATION AND
- DEBRIS OFF SITE, UNLESS OTHERWISE INDICATED AND/OR EXCEPT SUCH OBJECT(S) THAT ARE DESIGNATED TO REMAIN. 13. ALL TREE REMOVAL AND TREE TRIMMING WITHIN THE LIMITS OF DISTURBANCE, REGARDLESS OF SIZE, SHALL BE INCIDENTAL TO THE CONTRACT. INDIVIDUAL TREES ARE NOT SHOWN ON THE DRAWINGS BUT MAY BE REMOVED BY THE CONTRACTOR AS NECESSARY AND WITH APPROVAL OF THE ENGINEER WITHIN THE LIMITS OF
- 14. TREES NOT DESIGNATED TO BE REMOVED SHALL BE PROTECTED FROM CONSTRUCTION EQUIPMENT AND COMPACTION OF SOIL WITHIN THE DRIP LINE BY MEANS OF 3'-0" HIGH SENSITIVE AREA PROTECTION (SAP) FENCE, AS SHOWN ON THE EROSION AND SEDIMENT CONTROL PLANS.

DISTURBANCE. TREES GREATER THAN 6" IN DIAMETER SHALL BE FLAGGED BY THE CONTRACTOR FOR REVIEW AND APPROVAL BY THE ENGINEER PRIOR TO REMOVAL.

- 15. CROSS SLOPE OF ALL NEW WALKWAYS AND TRAILS SHALL NOT EXCEED A SLOPE OF 1:50. LONGITUDINAL SLOPES OF ALL NEW WALKWAYS AND TRAILS SHALL NOT EXCEED 1:20, UNLESS AS SHOWN ON THE CONTRACT PLANS.
- 16. THE CONTRACTOR MAY STORE AND/OR STOCKPILE EQUIPMENT AND MATERIALS WITHIN THE PROJECT SITE LIMIT OF DISTURBANCE (LOD) SHOWN ON PLAN.
- 17. THE CONTRACTOR IS ADVISED THAT CONTRACTOR EMPLOYEE PARKING SHALL BE LIMITED TO THE EXISTING PAVED PARK PARKING AREAS, UNLESS APPROVED BY THE ENGINEER. VEHICLE PARKING SHALL NOT BE ALLOWED ON UNPAVED AREAS.
- 18. FEATURES NOT SPECIFICALLY DESIGNATED FOR DEMOLITION OR REMOVAL THAT ARE DAMAGED BY THE CONTRACTOR OR THE CONTRACTOR'S SUBCONTRACTORS SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE STATE. THE COST FOR REPAIRS OR REPLACEMENT SHALL BE ESTABLISHED BY THE STATE INSURANCE PROVIDER.
- 20. NO CONSTRUCTION, EQUIPMENT, WORK, OR TEMPORARY FILLS SHALL BE ALLOWED WITHIN THE WETLANDS EXCEPT WITHIN THE LOD.
- 22. TEMPORARY CONSTRUCTION MATTING SHALL BE USED FOR ALL EQUIPMENT AND WORKER ACCESS WITHIN THE WETLANDS.


THE ENGINEER WILL NOT ACCEPT REMOVAL OF TREES INTENDED TO BE PROTECTED.

- 21. THE LOC SHALL BE NO WIDER THAN 18'-0" WITHIN THE WETLANDS. THIS INCLUDES: THE PROPOSED 8' WIDE BOARDWALK, A 2' GAP, AND 8' WIDE TEMPORARY CONSTRUCTION MATTING.
- 23. WETLANDS DISTURBED BY CONSTRUCTION SHALL BE RESTORED TO MATCH ADJACENT AREA. WETLAND PLANTS SHALL BE PLANTED AS NOTED ON THE EROSION & SEDIMENT CONTROL PLANS.
- 24. THE CONTRACTOR SHALL PROVIDE AND INSTALL TEMPORARY BARRICADES ON TRAILS AND AROUND EQUIPMENT TO DISCOURAGE ACCESS BY PARK PATRONS TO WORK AREAS, ADVANCE WARNING SIGNS SHALL BE PLACED AT TRAIL HEADS TO WARN PEDESTRIANS OF ANY TRAIL CLOSURES.
- 25. SEGMENTS OF THE TRAIL ARE LOCATED WITHIN THE PREHISTORIC ARCHAEOLOGICAL SENSITIVITY—AREA AND SHALL BE MONITORED BY DNREC PERSONN EXCAVATION AT THOSE LOCATIONS FOR THE PURPOSE OF COLLECTING DISPLACED ARTIFACTS AND TO LOOK FOR SUBSURFACE FEATURES, SO THAT EVALUATED AND DOCUMENTED AS APPROPRIATE. POTENTIAL FOR WORK STOPPAGE, IN THE EVENT THAT THE CONTRACTOR UNCOVERS ANYTHING REQUIR, REVIEW FOR PRESERVATION, MAY OCCUR.
- 26. TEMPORARY LAYDOWN, TURNAROUND AREAS, AND HAUL ROADS ARE TO BE VERIFIED IN FIELD BY DNREC PARKS STAFFS.

BRINGING ANY DIMENSIONAL DISCREPANCIES TO THE ATTENTION OF THE ENGINEER FOR CLARIFICATION.

GENERAL NOTES

- 1. THE TERM "ENGINEER," "STATE," AND/OR "ARCHITECT" NOTED THROUGHOUT THE CONTRACT PLANS AND SPECIFICATIONS SHALL REFER TO DNREC / STATE THEIR APPOINTED REPRESENTATIVE. THE TERM "SITE" AND "PARK" MAY BE USED INTERCHANGEABLY THROUGHOUT THESE DOCUMENTS AS A MEANS
- 2. THE CONTRACTOR SHALL RESTORE ALL AREAS AFFECTED BY THE CONSTRUCTION SHOWN HEREON AS SHOWN ON THESE PLANS AND SPECIFICATIONS, TO A CONDITION COMPARABLE TO THAT EXISTING PRIOR TO CONSTRUCTION, AND TO THE SATISFACTION OF DNREC.
- 3. THE CONTRACTOR SHALL PROVIDE NECESSARY FACILITIES, INCLUDING BUT NOT LIMITED TO RESTROOMS, DURING CONSTRUCTION. PARK FACILITIES SHALL NOT BE
- 6. THE CONTRACTOR SHALL NOTE THAT IN CASE OF DISCREPANCY BETWEEN THE SCALED AND THE FIGURED DIMENSIONS SHOWN ON THE PLANS, THE FIGURED DIMENSIONS SHALL GOVERN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONFIRMING ALL DIMENSIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR
- 7. BEFORE EXCAVATION IS STARTED, THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES. ALL EXISTING UTILITIES SHALL BE PROTECTED AND TEMPORARILY SUPPORTED OR RELOCATED AS NECESSARY TO COMPLETE THE WORK IN ACCORDANCE WITH THE PERTINENT OWNER/UTILITY COMPANY REQUIREMENTS. ANY UTILITIES DAMAGED BY THE CONTRACTOR SHALL BE PROMPTLY AND FULLY RESTORED TO THE SATISFACTION OF THE OWNER.
- 8. THE CONTRACTOR SHALL DESIGNATE A PERSON WHO SHALL BE RESPONSIBLE FOR IMPLEMENTING AND MAINTAINING THE EROSION AND SEDIMENT CONTROL PLANS, A PERSON WHO SHALL BE RESPONSIBLE FOR IMPLEMENTING AND MAINTAINING THE TRAFFIC CONTROL, AND A PERSON WHO SHALL BE RESPONSIBLE FOR WORKER SAFETY. THE PERSON RESPONSIBLE FOR IMPLEMENTING AND MAINTAINING THE EROSION AND SEDIMENT CONTROL PLANS SHALL BE CERTIFIED BY DNREC FOR EROSION AND SEDIMENT CONTROL RESPONSIBILITY (CERTIFIED CONSTRUCTION REVIEWER).
- 9. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE AREA WITHIN THE LIMITS OF CONSTRUCTION TO PROHIBIT PUBLIC ACCESS UNTIL COMPLETION OF THE PROJECT. THE CONTRACTOR'S PROCEDURE/METHOD FOR LIMITING ACCESS SHALL BE REVIEWED BY, AND COORDINATED WITH DNREC PRIOR TO THE START OF WORK. THE COST TO INSTALL, RELOCATE, AND MAINTAIN SITE SECURITY SHALL BE INCIDENTAL TO THE CONTRACT.
- 10. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR OBTAINING OFF-SITE SPOIL AREAS FOR LEGAL DISPOSAL OF EXCESS MATERIAL NOT ACCEPTED BY THE PARK AND/OR UNSUITABLE MATERIALS AS NECESSARY IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REQUIREMENTS. ALL COST FOR RECYCLING, TRANSPORTING TO, PROCURING AND UTILIZING THE OFF-SITE SPOIL AREAS ARE TO BE INCIDENTAL TO THE CONTRACT.
- 11. IN CASE OF CONFLICT BETWEEN THE "MANUFACTURER'S RECOMMENDATIONS" FOR AN APPROVED MATERIAL AND THE GOVERNING "CONTRACT SPECIFICATIONS" FOR THE MATERIAL, THE MORE RESTRICTIVE OF THE TWO SHALL PREVAIL, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 12. THE CONSTRUCTION PLANS PRESENT A CONCEPT OF THE RELATIONSHIP BETWEEN TRAFFIC CONTROL, EROSION CONTROL, ETC. ANY REVISION TO THE DETAILS OR SEQUENCE SHOWN ON THE CONSTRUCTION PLANS SHALL BE PREPARED BY THE CONTRACTOR ON STANDARD DNREC PLAN SHEETS AND SUBMITTED FOR REVIEW AND APPROVAL BY THE ENGINEER. THE PLANS SHALL BE PREPARED IN ACCORDANCE WITH CURRENT DELDOT AND DNREC STANDARDS FOR TRAFFIC CONTROL, EROSION AND SEDIMENT CONTROL (PREPARED BY A CERTIFIED CONSTRUCTION REVIEWER), STORM WATER MANAGEMENT, ETC. AND SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF DELAWARE. ALL REQUIRED CALCULATIONS, REPORTS, ETC. SHALL ALSO ACCOMPANY THE SUBMISSION. THE NUMBER OF COPIES REQUIRED TO BE SUBMITTED FOR REVIEW SHALL BE DETERMINED BY DNREC, DEPENDING ON THE NATURE OF THE PROPOSED REVISION. THE CONTRACTOR SHALL NOTE THAT THE REVISIONS TO THE CONSTRUCTION PLANS, AS WELL AS REVIEW TIME BY DNREC, WILL NOT JUSTIFY A DELAY IN THE CONSTRUCTION SCHEDULE. REVISIONS INVOLVING UTILITIES WILL REQUIRE THE COMPLETION OF A UTILITY STATEMENT APPROVED BY THE RESPECTIVE UTILITIES AS PART OF THE PLAN DOCUMENTS. ALL COSTS INVOLVED IN PREPARING THE PLAN REVISIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 13. THESE DRAWINGS DO NOT INCLUDE NECESSARY ELEMENTS OF CONSTRUCTION SAFETY. ALL CONSTRUCTION, INCLUDING EXCAVATION, MUST BE COMPLETED IN ACCORDANCE WITH THE REQUIREMENTS OF THE OCCUPATIONAL SAFETY AND HEALTH ACT, CFR \$1926.652(b)(2), AND ALL FEDERAL, STATE AND LOCAL REQUIREMENTS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR ALL WORK SITE SAFETY.
- 14. NO DEBRIS SHALL BE BURIED OR BURNED ON THE SITE UNLESS SPECIFICALLY NOTED WITHIN THESE PLANS OR SPECIFICATIONS.
- 15. THE CONTRACTOR SHALL CONTACT MISS UTILITY TWO (2) CONSECUTIVE WORKING DAYS PRIOR TO EXCAVATION, OR AS REQUIRED BY LAW, AT 1-800-282-8555.



2. SUBGRADE SHALL BE LEVELED WITH A GRADER OR OTHER

SUITABLE SCRAPER BLADE, AND PROOF ROLLED VIA

3. SURFACE COURSE (DELAWARE #10 STONE) SHALL BE

DRUM ROLLER - VIBRATORY COMPACTOR.


MINIMUM TWO PASSES WITH A WALK BEHIND, DOUBLE

COMPACTED WITH A MINIMUM OF 4 PASSES OF A TWO DRUM VIBRATORY ROLLER WEIGHING AT LEAST 2500 LBS.

TYPICAL SECTION: 4' WIDE GRAVEL TRAIL

(PARKING LOT AREA)

N.T.S.



		DATA	A COLUMN		
1.	COUNTY TAX MAP:	134-3.00-6.00 134-4.00-1.00			
2.	DNREC PROJECT NUMB	ER:			
3.	ADDRESS OF SITE:	HOLTS LANDING STAT DAGSBORO, DE 1993		IDING ROAD	
4.	SITE COORDINATES AT	CENTER OF PROJECT SITE: L	ATITUDE: 38.589 ONGITUDE: -75.130		
5.	ZONING:	EXISTING: ST PROPOSED: ST			
LOT	AREA:	TAX PARCEL NO. 134-3.00-6.00 134-4.00-1.00	<u>EXISTING</u> 111.86 AC 59.44 AC	<u>PROPOSED</u> 111.86 AC 59.44 AC	
SOU	RCE OF TITLE:	TAX PARCEL NO. 134-3.00-6.00 134-4.00-1.00	DEED RECORD, 	/INSTRUMENT_NUMBER 	
6.	EXISTING USE:	STATE PARK			
7.	PROPOSED USE:	STATE PARK			
8.	DATUM:	EXISTING VERTICAL — NAVD 88 HORIZONTAL — NAD 83			
9.	Existing condit Trail Forest Open spa Total	0.41 ACRES 0.57 ACRES CE 0.20 ACRES 1.18 ACRES	<u>PROPOSED COI</u> TRIAL FOREST	NDITIONS 0.59 ACRES 0.44 ACRES 0.15 ACRES 1.18 ACRES	
	IMPERVIOU	S CONDITIONS EXISTING 35%		PROPOSED 50%	
10.				THIS SITE LIES WITHIN ZONE AE. FLOOD ELEVATION (BFE) VARIES FROM	1 6 T(
11.	WATER RESOURCE PRO	TECTION			
12.	TOTAL LAND DISTURBAN	NCE DISTURBANCE PROPOSED BY	THIS PLAN IS 1.18	± ACRES (50,792± S.F.)	
13.	LIMITS OF CONSTRUCTION		CITE IC 4 70 L AO	DEC (57 3021 CT)	
14.		S OF CONSTRUCTION FOR THE TRAIL: 6,349 FT. (1.20 MILES		NEO (07,0321 3.F.)	
15.		BOARDWALK: 660 FT. (0.125			
16.	WETLANDS	ANDS EXISTING WITHIN THE LII		CE IS O± ACRES (O± S.F.)	
17.	OWNER/DEVELOPER:	STATE OF DELAWARE DNREC, DIVISION OF PARKS 89 KINGS HIGHWAY, DOVER PHONE: 302-739-9210 FAX: 302-739-3817			
18.	CIVIL ENGINEER:	CENTURY ENGINEERING, INC 4134 NORTH DUPONT HIGH WALTER J. HOEY,III, P.E. PHONE: (302) 734–9188 FAX: (302) 734–4589		901	

ITEMS LEGEND

- (1) ITEM 301001 GRADED AGGREGATE BASE COURSE, TYPE B 4" EXISTING TRAILS, 6" - RELOCATED/NEW TRAILS
- (2) ITEM 302004 DELAWARE NO. 10 STONE
- (3) ITEM 708002 SEPARATION GEOTEXTILE [TO BE NON-WOVEN SEPARATION FABRIC (ASSHTO M 288, CLASS 2 - Mirafi 140n, OR EQUIVALENT) BETWEEN PREPARED SUBGRADE AND GABC BASE COURSE.]
- (4) ITEM 905001 SILT FENCE OR COMPOST FILTER LOG(MIN. 18"Ø) [REFER TO SHEET SSMP500 FOR INSTALLATION REQUIREMENTS AND ADDITIONAL EROSION AND SEDIMENT
- ITEM NUMBERS UTILIZE THE CURRENT 2016 DELDOT STANDARD SPECIFICATIONS. ITEM NUMBERS THAT HAVE A "O" FOR THE FOURTH DIGIT, REFER TO DELDOT "STANDARD SPECIFICATIONS". IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN THE DELDOT STANDARD SPECIFICATIONS EITHER ONLINE OR HARD COPY FROM DELDOT TO REFERENCE THESE ITEMS.


REVISIONS:	DATE: DESCRIPTION						
HOLTS LANDING BOARDWALK & TRAIL IMPROVEMENTS							
SEAL: NO. 11204 * NO. 11204 * ROYONAL ENGINEER:							
CIVIL ENGINEER: CENTURY ENGINEERS, SURVEYOR 4134 N. DUPONT HWY. DOVER, DELAWARE 19901 CEI CONTRACT NO.: 125002.25							RS
	AND AND		NT OF	\bigwedge		NRC'S	$\bigg)$
DES	SIGNE		r: VJI	+			
DRA	AWN E)FS	3			
CHE	ECKEI		: \E	3			
DAT	E: EPT	E۱	/IBI	ΞR	20	18	
SCA	ALE:	N	ON	E			
SHE	EET N			_			=

CONTRACT NO.: 2018-HL-200






1. SEE SHEET C301 FOR TYPICAL SECTIONS.



— EXISTING TRAIL TO BE ABANDONED - EXISTING SEA HAWK TRAIL TO BE RECONSTRUCTED (SEE TYP. SECTION B) NEW TRAIL ALIGNMENT #2 (SEE TYP. SECTION A) EXISTING SEA HAWK TO TO BE RECONSTRUCTO (SEE TYP. SECTION B)



TRAIL ALIGNMENT #2

TRAIL ALIGNMENT #3

HORIZONTAL ALIGNMENT #1 (LINE & CURVE TABLE)						
ID	LENGTH/ARC	CHORD LENGTH	RADIUS	LINE/CORD BEARING	START NORTHING	
C10	17.91	17.59	27.00	S63° 40' 39"E	214387.0919	73. 1
L10	69.06			S44° 40' 11"E	214379.2931	73769
C11	25.25	24.34	27.00	S17° 52' 52"E	214330.1764	737739.2
L11	24.79			S8° 54' 27"W	214307.0143	737746.756
C12	25.91	24.93	27.00	S18° 34' 59"E	214282.5209	737742.9178
L12	15.49			S46° 04' 25"E	214258.8940	737750.8613
C13	11.50	11.41	27.00	S33° 52' 33"E	214248.1512	737762.0145
L13	1.01			S21° 40' 40"E	214238.6784	737768.3741
C14	30.55	28.94	27.00	S54° 05' 20"E	214237.7437	737768.7456
L14	6.68			S86° 29' 59"E	214220.7675	737792.1877
C15	7.55	7.53	27.00	S78° 29' 21"E	214220.3600	737798.8509
L15	50.86			S70° 28' 42"E	214218.8583	737806.2249
C16	17.59	17.28	27.00	S51° 48' 47"E	214201.8632	737854.1598
L16	16.27			S33° 08' 52"E	214191.1789	737867.7435
C17	9.62	9.57	27.00	S43° 21' 21"E	214177.5530	737876.6422
L17	6.60			S53° 33' 51"E	214170.5944	737883.2125
END					214166.6768	737888.5192

TRAIL ALIGNMENT #1

NOTE:

ALIGNMENT #1 TO BE MONITORED BY THE STATE PARK ARCHAEOLOGIST DURING CONSTRUCTION.


HORIZONTAL ALIGNMENT #2 (LINE & CURVE TABLE)							
ID	LENGTH/ARC	CHORD LENGTH	RADIUS	LINE/CORD BEARING	START NORTHING	START EASTING	
C20	15.72	15.50	27.00	N15° 33' 15"E	213597.2845	738508.5850	
L20	74.34			N32° 14' 16"E	213612.2194	738512.7420	
C21	70.14	68.71	100.00	N12° 08' 37"E	213675.0979	738552.3965	
L21	40.80			N7° 57' 01"W	213742.2724	738566.8511	
C22	17.33	17.03	27.00	N26° 20' 09"W	213782.6810	738561.2078	
L22	15.21			N44° 43′ 18″W	213797.9455	738553.6517	
C23	26.20	25.18	27.00	N16° 55' 20"W	213808.7523	738542.9495	
L23	95.62			N10° 52′ 37″E	213832.8461	738535.6190	
C24	10.46	10.39	27.00	N21° 58' 29"E	213926.7447	738553.6620	
END					213936.3836	738557.5514	

HORIZONTAL ALIGNMENT #3 (LINE & CURVE TABLE)							
ID	LENGTH/ARC	CHORD LENGTH	RADIUS	LINE/CORD BEARING	START NORTHING	START EASTING	
C20	15.72	15.50	27.00	N15° 33' 15"E	213597.2845	738508.5850	
L20	74.34			N32° 14' 16"E	213612.2194	738512.7420	
C21	70.14	68.71	100.00	N12° 08' 37"E	213675.0979	738552.3965	
L21	40.80			N7° 57' 01"W	213742.2724	738566.8511	
C22	17.33	17.03	27.00	N26° 20' 09"W	213782.6810	738561.2078	
L22	15.21			N44° 43' 18"W	213797.9455	738553.6517	
C23	26.20	25.18	27.00	N16° 55' 20"W	213808.7523	738542.9495	
L23	95.62			N10° 52' 37"E	213832.8461	738535.6190	
C24	10.46	10.39	27.00	N21° 58' 29"E	213926.7447	738553.6620	
END					213936.3836	738557.5514	


CONSTRUCTION NOTES:

- 1. NEW TRAIL SHALL BE PLACED SO THAT TRAIL GRADES MATCH EXISTING GROUND ELEVATION +3".
- 2. EXCAVATED MATERIAL SHALL BE RE—SPREAD ON PORTIONS OF THE TRAIL TO BE ABANDONED, EXCEPT IN LOCATIONS WHERE THE EXISTING TRAIL IS LOCATED WITHIN WETLANDS.
- 3. NO MATERIAL SHALL BE PLACED WITHIN WETLANDS OR AREAS OUTSIDE THE PROJECT LOC.

- 1. PARCEL LINES REFERENCED FROM STATE OF DELAWARE (FIRSTMAP.DELWARE.GOV).
- 2. 2' LIDAR CONTOURS REFERENCED FROM STATE OF DELAWARE (FIRSTMAP.DELWARE.GOV).
- 3. WETLANDS SHOWN ARE ONLY THOSE IDENTIFIED WITHIN THE LIMITS OF INVESTIGATION AND SHOULD NOT BE CONSIDERED AS ALL INCLUSIVE.




& TRAIL IMPROVEMENTS Ñ TRAIL ALIGNMENTS HOLTS LANDING BOARDWALK



CIVIL ENGINEER:

CENTURY ENGINEERING CONSULTING ENGINEERS, SURVEYORS 4134 N. DUPONT HWY. DOVER, DELAWARE 19901

CEI CONTRACT NO.: 125002.25



DESIGNED BY:

DRAWN BY:


CHECKED BY:


SEPTEMBER 2018


SCALE: 1"=50'

SHEET NO.:


CONTRACT NO.: 2018-HL-200



















Effective April 2016

Standard Detail & Specifications Construction Site Waste Mgt & Spill Control

Pollution Prevention - Spill Prevention

- . Fueling should only take place in signed designated areas, away from downstream drainage facilities and watercourses.
- Fueling must be with nozzles equipped with automatic shut-off to control drips. Do not top off.
- 3. Protect the areas where equipment or vehicles are being repaired, maintained, fueled or parked from storm water run-on and runoff.
- 4. Use barriers such as berms to prevent storm water run-on and runoff, and to contain spills.
- 5. Place a "Fueling Area" sign next to each fueling area.
- 6. Store hazardous materials such as fuel, solvents, oil and chemicals in secondary containment.
- 7. Inspect vehicles and equipment for leaks on each day of use. Repair fluid and oil leaks
- 8. Absorbent spill clean-up materials and spill kits must be available in fueling areas and on fuel trucks.
- 9. If fueling is to take place at night, make sure the fueling area is sufficiently illuminated.
- 10. Properly dispose of used oil, fluids, lubricants and spill clean-up materials. **CLEAN UP SPILLS**
- 1. If it is safe to do so, immediately contain and clean up any chemical and/or hazardous material
- 2. Properly dispose of used oil, fluids, lubricants and spill clean-up materials.
- 3. Do not bury spills or wash them down with water.
- LEAKS AND DRIPS 1. Use drip pans or absorbent pads at all times. Place under and around leaky equipment.
- 2. Do not allow oil, grease, fuel or chemicals to drip onto the ground.
- Have spill kits and clean up material on-site.
- Repair leaky equipment promptly or remove problem vehicles and equipment from the site. Clean up contaminated soil immediately
- Store contaminated waste in sealed containers constructed of suitable material. Label these
- containers properly.

6. Clean up all spills and leaks. Promptly dispose of waste and spent clean up materi					
Source:	Symbol:	Detail No.			
		DE	6.1		
Delaware ESC Handbook		She			

Effective A

Standard Detail & Specifications

Construction Site Waste Mgt &

Notes:

The Construction Site Pollution Prevention Plan should include the following elements:

1. Material Inventory

Document the storage and use of the following materials:

- a. Concrete
- b. Detergents

Spill Control

- c. Paints (enamel and latex)
- d. Cleaning solvents
- e. Pesticides
- f. Wood scraps
- g. Fertilizers h. Petroleum based products

2. Good housekeeping practices

- a. Store only enough product required to do the All materials shall be stored in a neat, orderly ma and covered.
- Substances shall not be mixed.
- ct shall be used up prior d. When possi
- r disposal shall be strictly adhered to s instructi
- anate someone to inspect all BA

- s shall be collected and storagin securely lidded dumpsters in a location to a waterbody.
- all be salve a and/or recycled whenever possible.
- umpsters shall be amptied a minimum of twice per week, or more if necessary. The is responsible for cleaning out dumpsters.

DE-ESC-3.6.1 Sheet 3 of 5

Effective April 2016

Standard Detail & Specifications

Construction Site Waste Mgt & Spill Control

Notes (cont.)

- d. Trash shall be disposed of in accordance with all applicable Delaware laws.
- e. Trash cans shall be placed at all lunch spots and littering is strictly prohibited. Recycle bins shall be placed near the construction trailer.
- If fertilizer bags can not be stored in a weather-proof location, they shall be kept on a pallet and covered with plastic sheeting which is overlapped and anchored.

Equipment maintenance practices

- a. If possible, equipment should be taken to off-site commercial facilities for washing and
- if erformed on-site, vehicles shall be washed with high-pressure water spray without detergents in an area contained by an impervious berm.
- Drip pans shall be used for all equipment maintenance.
- d. Equipment shall be inspected for leaks on a daily basis.
- e. Washout from concrete trucks shall be disposed of in a temporary pit for hardening and proper disposal.
- Fuel nozzles shall be equipped with automatic shut-off valves.
- a. All used products such as oil, antifreeze, solvents and tires shall be disposed of in accordance with manufacturers' recommendations and local, state and federal laws and regulations.

5. Spill prevention practices

- a. Potential spill areas shall be identified and contained in covered areas with no connection to the storm drain system.
- b. Warning signs shall be posted in hazardous material storage areas.
- c. Preventive maintenance shall be performed on all tanks, valves, pumps, pipes and other equipment as necessary.
- Low or non-toxic substances shall be prioritized for use.

Source:	Symbol:	Defail No.
Adapted from USEPA		DE-ESC-3.6.1
Pub. 840-B-92-002		Sheet 4 of 5

Effective April 2016

Standard Detail & Specifications Construction Site Waste Mgt & Spill Control



e. Contact information for reporting spills through the DNREC 24-Hour Toll Free Number shall be prominently posted.

6. Education

- a. Best management practices for construction site pollution control shall be a part of regular progress meetings.
- b. Information regarding waste management, equipment maintenance and spill prevention shall be prominently posted in the construction trailer.


CONTACT INFORMATION

DNREC 24-Hour Toll Free Number 800-662-8802 **DNREC Solid & Hazardous Waste Branch**

302-739-9403

ource:	Symbol:	Detail No.
Adapted from USEPA Pub. 840-B-92-002		DE-ESC-3.6.1 Sheet 5 of 5

Effective April 2016



DE-ESC-3.7.2 Adapted from Sheet 1 of 3 **VA ESC Handbook**

Effective April 2016

EROSION Standard Detail & Specifications Sensitive Area Protection

Construction Notes:

Fencing shall be installed at the extents of all sensitive areas. For trees, the fencing shall be installed outside the dripline (mature canopy) and at no time within 5 feet of the trunk. Personnel must be instructed to honor protective devices. The devices described are suggested only, and are not intended to exclude the use of other devices which will protect the trees to be retained. If silt fence is to be used for demarcation purposes, appropriate signage shall be provided a minimum of every 20 feet denoting the area as a sensitive area protection zone.

Materials:

- . Snow Fence Standard 40-inch high snow fence shall be placed at the limits of clearing or construction on standard steel posts set 6 feet apart.
- 2. Board Fence Board fencing consisting of 4-inch square posts set securely in the ground and protruding at least 4 feet above the ground shall be placed at the limits of clearing with a minimum of two horizontal boards between posts. For tree protection, if it is not practical to erect a fence at the drip line, construct a triangular fence nearer the trunk. The limits of clearing will still be located at the drip line, since the root zone within the drip line will still require protection.
- Plastic Fencing 40-inch high "international orange" plastic (polyethylene) web fencing secured to conventional metal "T" or "U" posts driven to a minimum depth of 18 inches on 6-foot minimum centers shall be installed at the limits of clearing. The fence should have the following minimum physical qualities:

Average 2,000 lbs. per 4-foot width (ASTM D638) Tensile yield:

Average 2,900 lbs. per 4-foot width (ASTM D638)

Inert to most chemicals and acids

Elongation at break (%): Greater than 1000% (ASTM D638)

Ultimate tensile yield:

Chemical resistance:

Source: Symbol: DE-ESC-3.7.2 Adapted from Sheet 2 of 3 VA ESC Handbook

Effective April 2016

Standard Detail & Specifications Sensitive Area Protection



- 4. Cord Fence Posts with a minimum size of 2 inches square or 2 inches in diameter set securely in the ground and protruding at least 4 feet above the ground shall be placed at the limits of clearing with two rows of cord 1/4-inch or thicker at least 2 feet apart running between posts with strips of colored surveyor's flagging tied securely to the string at intervals no greater than 3 feet.
- 5. Earth Berms Temporary earth berms shall be constructed according to specifications for a Temporary Earth Dike with the base of the berm on the sensitive area side located along the limits of clearing. Earth berms may not be used for this purpose if their presence will conflict with drainage patterns.
- 6. Trunk Armoring (Tree Protection Only) As a last resort, a tree trunk can be armored with burlap wrapping and 2-inch studs wired vertically no more than 2 inches apart to a height of 5 feet encircling the trunk. If this alternative is used, the root zone within the drip line will still require protection. Nothing should ever be nailed to a tree.


Maintenance:

Fencing and armoring devices shall be in place before any excavation or grading is begun, shall be kept in good repair for the duration of construction activities, and shall be the last items removed during the final cleanup after the completion of the project.

Source: DE-ESC-3.7.2 Adapted from Sheet 3 of 3 VA ESC Handbook

Effective April 2016

TRAIL IMPROVEMENTS DETAILS CONTROL ∞ಶ BOARDWALK S LANDING HOLTS



CIVIL ENGINEER:

CENTURY ENGINEERING CONSULTING ENGINEERS, SURVEYORS 4134 N. DUPONT HWY. DOVER, DELAWARE 19901



DESIGNED BY:

DRAWN BY:

CHECKED BY:


SEPTEMBER 2018

SCALE: NONE


SHEET NO.:


SSMP501 CONTRACT NO.:

2018-HL-200




















Standard


at the desire

il & Sectifications


Compose Filter Log

rea of obstructions including rocks or debris larger than 1 inch

mg a pneumatic blower so that the logs are rigid and do not deform. Terminate



Effective April 2016



REVISIONS: DATE: DESCR TRAIL IMPROVEMENTS **DETAILS** CONTROL ∞ర BOARDWALK EDIMENT S HOLTS LANDING ∞ಶ **EROSION** NO. 11204 CIVIL ENGINEER: CENTURY ENGINEERING CONSULTING ENGINEERS. SURVEYORS 4134 N. DUPONT HWY. DOVER, DELAWARE 19901 CEI CONTRACT NO.: 125002.25 **DESIGNED BY:** WJH DRAWN BY: CHECKED BY: DATE: SEPTEMBER 2018 SCALE: NONE SHEET NO.:

בא האינה בין בין האינה בין בין האינה בין

SSMP502

CONTRACT NO.:

2018-HL-200