



Gipe Associates, Inc.

CONSULTING ENGINEERS

W.O. #: 19003

ADDENDUM NO. 2 – SEPTEMBER 27, 2019

RE: **DELCASTLE HIGH SCHOOL CHILLER/COOLING TOWER
REFURBISHMENT (CONTRACT NUMBER – 1907)**
GAI # 19003

FROM: Gipe Associates, Inc.
8719 Brooks Drive,
Easton, MD 21601


TO: Prospective Bidders

This addendum forms a part of the contract documents and modifies the original bidding documents dated **August 5, 2019** as noted below. Acknowledge receipt of this Addendum on the Bid Form. Failure to do so may subject bidder to disqualification.

This Addendum consists of one page and the attached photos for information (2 pages).

CLARIFICATIONS

RFI #	Question	Answer
RFI #1	I noticed the cooling tower had a FM wall in the fill. This is for fire code. Marley used to put these in all their towers. The one thing I want to point out is they spec non OEM fill media which would take away the FM rating. Will this be ok?	Fire retardant fill media is not required for the cooling tower.
RFI #2	Can you please provide more information on the 1600 amp breaker that is to be removed?	As indicated on the Contract Drawings, the existing main switchboard manufacturer is Cutler-Hammer, Type CVB, Serial no. PF-667 580. See attached photos for additional information.



Gipe Associates, Inc.
CONSULTING ENGINEERS

W.O. #: 19003



Photograph #1 – Switchboard Nameplate Data



Photograph #2 – Main Chiller Unit 1600A Circuit Breaker

1220 East Joppa Road
Suite 223
Towson, Maryland 21286
TEL 410.832.2420
FAX 410.832.2418

8719 Brooks Drive,
Post Office Box 1147
Easton, Maryland 21601
TEL 410.822.8688
FAX 410.822.6306



Photograph #3 – Main Chiller Unit Circuit Breaker



Photograph #4 – Main Chiller Unit Circuit Breaker Rating