



# Gipe Associates, Inc.

CONSULTING ENGINEERS

W.O. #: 20009

## ADDENDUM NO. 2 – MAY 19, 2020

RE: **DELCASTLE HIGH SCHOOL WELDING LAB  
(CONTRACT NUMBER – 2005)  
GAI # 20009**

FROM: Gipe Associates, Inc.  
8719 Brooks Drive,  
Easton, MD 21601

TO: Prospective Bidders

This addendum forms a part of the contract documents and modifies the original bidding documents dated **APRIL 17, 2020** as noted below. Acknowledge receipt of this Addendum on the Bid Form. Failure to do so may subject bidder to disqualification.

This Addendum consists of one page.

### REQUEST FOR INFORMATION AND RESPONSE:

1. The verbiage on the welded duct seems is a bit confusing. Can you clarify the welding process on the duct seams....do all seams get TIG or MIG welded?

**Response: Yes, all seams shall be either TIG or MIG welded in accordance with SMACNA standards.**

2. Section 23300, page 5, note 17, states all exterior ductwork to be single wall type with a field applied insulation jacket. However, section 23300, page 7, note 2.9B, states all internal lining shall receive an interior perforated liner. My question is does the lined ductwork on the roof require a perforated inner liner?

**Response: Soundlined ductwork does receive perforated liner covering the same on inside of ductwork. All exterior ductwork (single wall or soundlined) shall be provided with exterior ductwork insulation system and jacket.**

Addendum #2– Page #1

**END OF ADDENDUM**