

10. General Contractor is responsible for providing line voltage to all locations indicated as having Access Control.
11. General Contractor is responsible for providing electric strikes to all locations indicated as having Access Control.
12. Provide solid surface counter top Grade B in Break Room renovation Alternate #1.
13. Where new carpet is indicated general contractor is to provide new rubber base.
14. Electrical Contractor is to provide (4) additional data drops (box and conduit) in the 1st floor office renovation Alternate #2 location to be determined in the field.
15. Electrical Contractor is to provide (4) additional duplex outlets in the 1st floor office renovation Alternate #2 location to be determined in the field.
16. Electrical Contractor is to provide an emergency light in the Corridor in the 1st floor office renovation Alternate #2 location to be determined in the field.
17. Electrical Contractor is to provide (1) additional data drops (box and conduit) in Room 582, 583, 584, 586,587, 588, Library 581(fish pull string in existing walls), Files/Storage 589 (fish existing walls), and Existing Break Room (fish pull string in existing walls), location to be determined in the field.
18. Electrical Contractor is to provide (1) additional duplex outlet in Room 502A, 582, 583, 584, 586, 587, 588, Library 581(fish in existing walls), Files/Storage 589 (fish in existing walls), Existing Break Room (fish in existing walls), and Room 585A locations to be determined in the field.
19. General Contractor is responsible for removing and replacing all ceilings necessary to distribute all electrical and plumbing scopes of work as required to complete the work.
20. Electrical Contractor is to include relocation of (1) Fire Alarm device in the 1st floor office renovation Alternate #2 location to be determined in the field.
21. Electrical Contractor is to include relocation of (1) Fire Alarm device in the Break Room renovation Alternate #1 location to be determined in the field.
22. Electrical Contractor is to provide (2) new light switches to control lighting in rooms 502A, 585A and 586.
23. Solid Carpet at Door infills to be Rock Solid II over Flex Aire Modular as manufactured by Tandus.

END