



Pennsylvania
Duane Morris Plaza
30 S. 17th Street
Suite 830
Philadelphia, PA 19103
Phone
267.804.7286

Delaware
315 S. Chapel Street
Newark, DE 19711
Phone
302.738.7172
Fax
302.738.7175
www.dedc-eng.com

CSOB 12TH FLOOR CORE HVAC
OMB/DFM CONTRACT #'S MC1002000378
ADDENDUM #2

QUESTIONS:

A. Drawing M-112A indicates a new louver is to be installed for AC-28. What material is the exterior face of this wall?

Answer: The exterior face of this wall is limestone.

B. Is the intent to demolish all existing ductwork in this space?

Answer: No. There is existing exhaust ductwork as well as existing transfer grilles that are to be left existing.

C. During the walkthrough, existing heating hot water taps were observed to be capped and abandoned in the mechanical room. May these be tied into in the new work?

Answer: Yes.

D. When may we shut down the building HVAC for piping tie-ins?

Answer: All necessary building shut downs are to occur during off hours. These are to be coordinated with DFM and should be identified on the project schedule.

E. Where are the new thermostats to be installed?

Answer: New thermostats are to be installed in the same location as existing thermostats that are to be removed.

F. Are duct shop drawings required?

Answer: Yes.

Addendum #2

1. Addendum #2 (this document) (1 page)

Summarized By: DEDC, LLC
Matt Lano

Date: February 12, 2018