



Delaware
315 S. Chapel Street
Newark, DE 19711
Phone
302.738.7172
Fax
302.738.7175

Pennsylvania
United Plaza
30 S. 17th Street
Suite 830
Philadelphia, PA 19103
Phone
267.804.7286
www.dedc-eng.com

**State of Delaware Office of Management and Budget
OMB/DFM Contract No. MC1002000386
Carvel State Office Building - Wilmington, Delaware
Installation of 12 kV Main Disconnect Switches**

ADDENDUM #2

RFI Questions:

1. **QUESTION:** *E-200 says to replace the doors, but doesn't mention the frames. Are the frames to be replaced?*

ANSWER: Yes, the door frames are to be replaced as well. Specifications for the door frames are covered in specification section 08 17 00 – *Integrated Door Opening Assemblies*.

2. **QUESTION:** *Specification Section 26 05 13 (Page 2), 2.02E mentions load break elbows. Drawing E-100 (Note 3) & Drawing E-200 (Note 1 & 2) reference “600A Load Break Elbows”. Please confirm that you mean 600A Deadbreak Elbows.*

ANSWER: Correct; the Contractor shall provide 600A deadbreak elbows. Loadbreak elbows are unnecessary. In Addendum #1, all references to new “loadbreak” elbows being installed on new 15kV cables should also be changed to “deadbreak” elbows. The Contractor shall coordinate with Delmarva Power for required terminations for connecting the new 15kV cables to the utility grid.

3. **QUESTION:** *Per Addendum #1, in conjunction with pulling the medium voltage cables during normal work hours, please confirm that all work not requiring an outage (LV raceways, lighting, pendant enclosure mounting, doors and frames, etc.) can be done during normal work hours.*

ANSWER: Correct; all work that does not require an outage may be performed during normal work hours, subject to coordination and approval by the Owner. Work that requires outages must be done on weekends. The Owner shall be given three weeks prior notice of all anticipated outages.

4. QUESTION: *Is it required that the contractor follow the work schedule exactly as spelled out in Addendum #1?*

ANSWER: No, the contractor does not need to follow the schedule exactly as specified in Addendum #1, as long as all power outages are kept to weekends, and as long as the work does not interrupt the normal operations of the Carvel Building, subject to coordination and approval by the Owner. The Owner shall be given three weeks prior notice of all anticipated outages.

Summarized by: DEDC, LLC
Alexander Heist, P.E.

Date: April 20, 2018