STUDIO JAED
www.studiojaed.com

Addendum #1

Date: May 9, 2018

Project: Carvel State Office Building
Elevator Cab Lighting and Lobby Upgrades

Project #: MC1002000398

The work herein shall be considered part of the bid documents for the referenced project and carried out in accordance with the following supplemental instructions issued in accordance with the Contract Documents without change in Contract Sum or Contract Time. Acknowledge receipt of addendum on the bid form as indicated.

General

1. Bids due 2:00pm on May 22nd, 2018 at the OMB/DFM office located in the Thomas Collins Building at 540 S. DuPont Highway, Suite 1, 3rd Floor in Dover.
2. See attached list of all attendees.
3. The deadline for RFIs to StudioJAED is Thursday, May 15th, 2018 at 4:00 pm.
4. Final Addendum will be issued May 20th, 2018.
5. RFI and questions are to be submitted via email to Gabe Cheung and Philip Conte at StudioJAED. cheungg@studiojaed.com contep@studiojaed.com

Pre Bid Meeting Minutes

1. Introductions
   Gabe Cheung, Project Manager, StudioJAED

2. Reviewed Scope

   Scope of Work
   Project involves the replacement of ceiling and lights in the 5 passenger elevators and 1 freight elevator at the Carvel State Building in Wilmington, DE. All elevators will need general clean up. Lobbies 3 through 11 will have general patching and painting of the walls, soffits, elevator door and trim. Floor and base tiles that are damaged or missing will be replaced in kind to match. The short lobby wall will have a wall guard installed to prevent recycle containers from scuffing up the wall. All ceiling light fixtures will be replaced with LED. Area of flooring that is carpet or LVT will be replaced with new LVT.

3. Reviewed Bid Form
   a. Complete forms as presented, do not edit or alter.
   b. Provide all information requested in full or bid will not be accepted.
   c. Employee drug testing form is required from general contractor.
   d. Acknowledge all addendums as individual items.
   e. Include a copy of your business license, not just a number.

4. Reviewed Sub Contractor List
   a. Electrical, Flooring, Painting

5. Reviewed Alternates
   a. Alternate: There will be alternate issued via addendum.

6. Reviewed Allowances
   a. Allowance: $10,000

7. Prevailing Wage Project

a. Rates included in specifications.

8. Schedule
   a. Anticipate prompt award and commencement after bids are received.
   b. Exact date of completion will be issued via addendum.

9. Lay Down Area, Security and Occupancy
   a. All immediate areas adjacent to construction will be occupied for the duration of the project by staff. Contractor is responsible for coordinating with the administration on each floor, capitol police, facilities, on a daily basis as to location of work etc. Contractor to provide all measures for safe occupant passage for project duration.

10. Walkthrough of the area of work can be done at any time. The building has public access.

11. Clarifications:
    1. Although work is cosmetic in nature, it may be an elevator inspection may be required, check with appropriate agencies.
    2. There is an alternate to the base bid. See description below.

12. Changes to drawings
    a. Sheet A3.1 – Display rail to remain, finish legend to update to refer to specs for make, note to flash patch flooring such that elevation of new flooring aligns with existing, furnish and install new stainless steel corner guard, wall guard to maintain 3'-0" height and adjust plaque as needed.
    b. Sheet A3.2 – As an alternate, at floors 3-11, for corridor adjacent to elevator lobbies, remove wallpaper, patch repair walls as required, and prepare wall to accept new painting. Remove and install new rubber base. Paint all door and frames, corridor side only. Work to extend into rooms that are open to common corridor. For freight elevator corridor, patch and repair walls as required and paint all walls to match existing. Remove all corner guards and install new. Install new corner guards where there was none. Remove and install new rubber base.
13. Changes to specifications:
    a. Remove Section 10 26 01 – Wall and Corner Guards
    b. Added Section 10 26 00 – Stainless Steel Corner Guards
    c. Added Section 10 26 16.13 – 50SS Stainless Steel Wall Guard
    d. Added Section 10 26 13 – High Impact Corner Guard Wall Protection
    e. See attached execution and product info for cleaning granite panels in elevator and stainless steel.

End

STUDIO JAED
www.studiojaed.com

HEADQUARTERS
2500 WRANGLE HILL ROAD
FOX RUN OFFICE PLAZA, SUITE 110
BEAR, DE 19701

302.832.1652 PHONE
302.832.1423 FAX

ARCHITECTS ENGINEERS FACILITIES SOLUTIONS

Project: State of Delaware
Project No.: MC1005000398 / 17084
Date: May 3, 2018

PRE-BID
SIGN IN SHEET

	REPRESENTATIVE	FIRM / PHONE / FAX / EMAIL
1.	Vernon Reisinger	Don Reisinger, Inc. 610-696-6921 610-696-2352 pollyderinc@gmail.com
2.	John Rozich	Harbor Stone Construction 610-467-0872 610-467-0692 jrozich@harborstonecc.com
3.	Bill Booth	Commonwealth Construction Co. 302-654-6611 No Fax bbooth@itscommonwealth.com
4.	Stacy Bush	Amakor, Inc. 302-834-8664 302-834-8681 amakor@aol.com
5.	Tony Orga	Deldeo Builders, Inc. 302-791-0243 302-791-0245 loudeldeo@comcast.net

STUDIO JAED
www.studiojaed.com

HEADQUARTERS
2500 WRANGLE HILL ROAD
FOX RUN OFFICE PLAZA, SUITE 110
BEAR, DE 19701

302.832.1652 PHONE
302.832.1423 FAX

ARCHITECTS ENGINEERS FACILITIES SOLUTIONS

Project: State of Delaware
Project No.: MC1005000398 / 17084
Date: May 3, 2018

PRE-BID
SIGN IN SHEET

	REPRESENTATIVE	FIRM / PHONE / FAX / EMAIL
6.	Neal Williams	BSS Contractors 484-256-4986 No Fax bsmith@bsscontractor.com
7.	Michael Travers, Sr.	State of Delaware OMB/DFM 302-270-8641 michael.travers@state.de.us
8.	Gabe Cheung	StudioJAED Architects & Engineers 302-832-1652 302-832-1423 cheungg@studiojaed.com
9.	Rob DelCampo	State of Delaware OMB/DFM 302-535-3933 302-744-1178 robert.delcampo@state.de.us

Elevator Cab Granite Cleaning Instructions:

1. Wipe down granite surfaces with warm soapy water and cloth.
2. Dry and buff granite surfaces thoroughly with a microfiber cloth or soft terry cloth towel to avoid streaking.
3. Mix together a 50:50 solution of water and 91% isopropyl alcohol.
4. Spray the solution onto the granite, allow it to sit for 3-5 minutes, then rinse with water and dry with a clean microfiber cloth.

February 2013

Technical Data

3M™ Stainless Steel Cleaner & Polish

Description

3M™ Stainless Steel Cleaner and Polish is a ready-to-use cleaner and polish packaged in an aerosol container. The product is dispensed as a white, non-evaporating foam.

Special Features

- Cleans and polishes in one step
- Leaves no greasy build-up on surfaces
- Pleasant citrus fragrance
- Leaves a light protective film
- Masks blemishes
- Slows resoiling
- Reduces fingerprinting
- Resists streaking
- Empty containers may be disposed of in sanitary landfills in accordance with local regulations
- NSF® Certified for use in federally-inspected meat and poultry processing plants

Applications

- Suitable for use on stainless steel, chrome, architectural aluminum, and other interior metal surfaces
- Not intended as a glass cleaner

Packaging

- 21-ounce (600 g) aerosol can
- 10-ounce aerosol can
- 12 cans per case

General Use Directions

Light soil

1. Shake can well.
2. Turn spray tip so arrow points to dot on can rim.
3. Hold can upright 6-12 inches from surface.
4. Spray area lightly directly on surface or on a clean, dry cloth.
5. Wipe area and polish until dry.

Heavy soil

1. Spray 3M™ Stainless Steel Cleaner and Polish onto a Scotch-Brite™ Light Duty Scrubbing Pad 9030 or Scotch-Brite™ Light Duty Scrub Sponge 63.
2. Vigorously rub the surface to remove the heavy soil. Always rub stainless steel in the direction of the grain.
3. Wipe surface with a clean, dry cloth to remove any excess cleaner.
4. Using a clean dry cloth, buff in the direction of the grain to achieve maximum shine.

NOTE:
Refer to product Material Safety Data Sheet for specific physical properties, health hazard, first aid and precautionary information.

3M™ Stainless Steel Cleaner and Polish:

- 10-2819-0

3M Branch Sales Offices

ANCHORAGE

11151 Calaska Circle
Anchorage, AK 99515

Telephone: 907/522-5200
Facsimile 907/522-1645

HONOLULU

4443 Malaai Street
Honolulu, HI 96818
Mail to: P.O. Box 30048
Honolulu, HI 96820

Telephone: 808/422-2721
Facsimile 808/422-9557

CONTINENTAL UNITED STATES

Customer Service Department
3M Center Building 223-5S-07
St. Paul, MN 55144-1000

Order Entry 1-800-852-9722
Facsimile 1-800-447-0408

CANADA

1840 Oxford Street East
London, Ontario, Canada
N5V 3G2
Mail to: P.O. Box 5757
London, Ontario, Canada
N6A 4T1

Telephone: 800/364-3577
Facsimile: 800/479-4453

Important Notice to User

Technical Information: The technical information, recommendations and other statements contained in this document are based upon tests or experience that 3M believes are reliable, but the accuracy or completeness of such information is not guaranteed.

Product Use: Many factors beyond 3M's control and uniquely within user's knowledge and control can affect the use and performance of a 3M product in a particular application. Given the variety of factors that can affect the use and performance of a 3M product, user is solely responsible for evaluating the 3M product and determining whether it is fit for a particular purpose and suitable for user's method of application.

Warranty and Limited Remedy: 3M warrants that each 3M product will be free from defects in material and manufacture for 90 days from the date of purchase from 3M's authorized distributor. 3M MAKES NO OTHER EXPRESS OR IMPLIED WARRANTIES, INCLUDING ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. If a 3M product does not conform to this warranty, the sole and exclusive remedy is, at 3M's option, replacement of the 3M product or refund of the purchase price. Limitation of Liability: Except where prohibited by law, 3M will not be liable for any loss or damage arising from the 3M product, whether direct, indirect, special, incidental or consequential, regardless of the legal theory asserted.

Building and Commercial
Services Division
St. Paul, MN 55144-1000
1-800-852-9722
www.3M.com/facility

NSF and the mark are registered trademarks of NSF International.
3M and Scotch-Brite are trademarks of 3M Company.
Used under license in Canada.
© 3M 2013. All rights reserved.
60140

Division 10 26 00

STAINLESS STEEL CORNER GUARDS

PART 1 - GENERAL

1.01 SUMMARY
A. Corner guard system for wall protection:

1.02 SECTION INCLUDES
A. Stainless Steel Corner Guard Systems

1.03 SUBMITTALS
A. Product data for each type of corner guard specified.
B. Detail drawings indicating mounting details with the appropriate fasteners for specific project substrates.
C. Samples for verification purposes of corner guard, 6" (152mm) long, in full size profiles of each type and color indicated.
D. Cleaning and maintenance instructions for door and wall protection systems.

1.04 DELIVERY, STORAGE AND HANDLING
A. Deliver materials in unopened factory packaging to the jobsite and store in original packaging in a climate controlled location away from direct sunlight.

1.05 PROJECT CONDITIONS
A. Products must be installed in an interior climate controlled environment.

1.06 WARRANTY
A. Standard IPC Limited Lifetime Warranty against material and manufacturing defects.

PART 2 - PRODUCTS

2.01 MANUFACTURER
A. Acceptable Manufacturer: IPC Door and Wall Protection Systems,
InPro Corporation, PO Box 406 Muskego, WI 53150 USA;
Telephone: 800-222-5556, Fax: 888-715-8407,
Internet address: http://www.inprocorp.com
B. Substitutions: Not permitted
C. Provide all corner guards and wall protection from a single source.

2.02 MANUFACTURED UNITS
A. Corner Guards
183124H-304, 3½" x 3½" x 96" , ⅛" radius, Screw-on, 304 Stainless Steel, 16 gauge

DRAWINGS REDACTED

Division 10 26 00

STAINLESS STEEL CORNER GUARDS

2.03 MATERIALS
A. Stainless Steel: Corner Guards shall be manufactured from Type 304, 16 gauge Stainless Steel.

2.04 COMPONENTS
A. Attachment
1. Fasteners: Pre-drilled beveled holes and Phillips head screws.

2.05 FINISHES
A. Stainless steel: No. 4 satin finish.

PART 3 - EXECUTION

3.01 EXAMINATION
A. Examine areas and conditions in which the corner guard systems will be installed.
1. Complete all finishing operations, including painting, before beginning installation of corner guards.
B. Wall surface shall be dry and free from dirt, grease and loose paint.

3.02 PREPARATION
A. General: Prior to installation, clean substrate to remove dust, debris and loose particles.

3.03 INSTALLATION
A. General: Locate the corner guard as indicated on the approved detail drawing for the appropriate substrate and in compliance with the IPC installation instructions. Install corner guard level and plumb at the height indicated on the drawings.
B. Installation of Stainless Steel Corner Guards:
1. Surface must be dry, clean and properly sealed.
2. Cement on: Apply a bead of PL Premium Heavy Duty Adhesive in a zigzag pattern over the back of each wing of the corner guard. Position corner guard on the wall and apply pressure until a tight fit is achieved.
3. Screw on: Position the corner guard on the wall and attach it using the supplied screws.
4. Remove the protective plastic covering from the exposed surface of the corner guard.

3.04 CLEANING
A. At completion of the installation, clean surfaces in accordance with the IPC clean up and maintenance instructions.

END OF SECTION

Division 10 26 13
HIGH IMPACT CORNER GUARD WALL PROTECTION

PART 1 – GENERAL

1.01 SUMMARY

A. Corner guard system for wall protection

1.02 SECTION INCLUDES

A. 130 BluNose High Impact Surface Mount Corner Guard System

1.03 REFERENCES

A. American Society for Testing and Materials (ASTM)
B. National Building Code of Canada (NBC)
C. National Fire Protection Association (NFPA)
D. Society of Automotive Engineers (SAE)
E. Underwriters Laboratory (UL)
F. Underwriters Laboratory of Canada (ULC)
G. Uniform Building Code (UBC)

1.04 SYSTEM DESCRIPTION

A. Performance Requirements: Provide corner guard systems that conform to the following requirements of regulatory agencies and the quality control of IPC Door and Wall Protection Systems, InPro Corporation.

1. Fire Performance Characteristics: Provide UL Classified corner guards conforming with NFPA Class A fire rating. Surface burning characteristics, as determined by UL-723 (ASTM E-84), shall be flame spread of 10 and smoke development of 350 - 450. Provide ULC (Canada) listed corner guards conforming to the requirements of the National Building Code of Canada 2010, Subsection 3.1.13. Surface burning characteristics, as determined by CAN/ULC-S102.2, shall be flame spread of 15 and smoke developed of 35.
2. Self Extinguishing: Provide corner guards with a CC1 classification, as tested in accordance with the procedures specified in ASTM D-635-74, Standard Test Method for Rate of Burning and/or Extent and Time of Burning of Self-Supporting Plastics in a Horizontal Position, as referenced in UBC 52-4-1988.
3. Impact Strength: Provide rigid vinyl profile materials that have an Impact Strength of 30.2 ft-lbs/inch of thickness as tested in accordance with the procedures specified in ASTM D-256-90b, Impact Resistance of Plastics.
4. System Impact Resistance: Provide a corner guard system that resists an impact of 153.9 ft-lbs while producing no visual blemishes upon the vinyl cover surface and no deformations in the vinyl retainers, as tested in accordance with the applicable provisions of ASTM F 476-84, paragraph 18, Impact Test.
5. GREENGUARD Certified: Provide GREENGUARD Certified material. Profiles shall meet the requirements of GREENGUARD Certification Standards for Low-

Emitting Products and GREENGUARD Product Emission Standard for Children & Schools.
6. Chemical and Stain Resistance: Provide corner guards that show resistance to stain when tested in accordance with applicable provisions of ASTM D-543.
7. Fungal and Bacterial Resistance: Provide rigid vinyl that does not support fungal or bacterial growth as tested in accordance with ASTM G-21 and ASTM G-22.
8. Color Consistency: Provide components matched in accordance with SAE J-1545 - (Delta E) with a color difference no greater than 1.0 units using CIE Lab, CIE CMC, CIE LCh, Hunter Lab or similar color space scale systems.

1.05 SUBMITTALS

A. Product Data: Manufacturer's printed product data for each type of corner guard specified.
B. Detail Drawings: Mounting details with the appropriate fasteners for specific project substrates.
C. Samples: Verification samples of corner guard, 8" (203mm) long, in full size profiles of each type and color indicated.
D. Manufacturer's Installation Instruction: Printed installation instructions for each corner guard.

1.06 DELIVERY, STORAGE AND HANDLING

A. Deliver materials in unopened factory packaging to the jobsite
B. Inspect materials at delivery to assure that specified products have been received.
C. Store in original packaging in a climate controlled location away from direct sunlight.

1.07 PROJECT CONDITIONS

A. Environmental Requirements: Products must be installed in an interior climate controlled environment.

1.08 WARRANTY

A. Standard IPC Limited Lifetime Warranty against material and manufacturing defects.

PART 2 - PRODUCTS

2.01 MANUFACTURER

A. Acceptable Manufacturer: IPC Door and Wall Protection Systems,
InPro Corporation, PO Box 406 Muskego, WI 53150 USA;
Telephone: 800-222-5556, Fax: 888-715-8407,
Internet address: http://www.inprocorp.com
B. Provide all corner guards and wall protection from a single source.

Division 10 26 13
HIGH IMPACT CORNER GUARD WALL PROTECTION

2.02 MANUFACTURED UNITS

A. Corner Guard System

1. 130BN BluNose High Impact Surface Mount Corner Guard Profile
3" x 3" , 135 degree
8' standard heights

2.03 MATERIALS

A. Vinyl Covers: Snap on cover of .080" (2mm) thickness shall be extruded from chemical and stain resistant polyvinyl chloride with the addition of impact modifiers. No plasticizers shall be added
(plasticizers may aid in bacterial growth).

B. Vinyl Retainers: Continuous vinyl retainers of .070" (1.8mm) thickness with a co-extruded Biopolymer Flex apex shall be fabricated from polyvinyl chloride with the addition of impact modifiers.

2.04 COMPONENTS

A. Top caps and bottom caps shall be made of injection molded thermoplastics.

B. Fasteners: All mounting system accessories appropriate for substrates indicated on the drawings shall be provided.

C. Optional flexible top caps shall be made of injection molded Biopolymer Flex PVC.

2.05 FINISHES

A. Vinyl Covers: Colors of the corner guard to be selected by the architect from the IPC finish selection. Surface shall have a pebblette texture.

B. Molded Components: Top caps and bottom caps shall be of a color matching the corner guards. Surface shall have a pebblette texture.

PART 3 - EXECUTION

3.01 EXAMINATION

A. Examine areas and conditions in which the corner guard systems will be installed.

1. Complete all finishing operations, including painting, before beginning installation of corner guard system materials.

B. Wall surface shall be dry and free from dirt, grease and loose paint.

3.02 PREPARATION

A. General: Prior to installation, clean substrate to remove dust, debris and loose particles.

Division 10 26 13
HIGH IMPACT CORNER GUARD WALL PROTECTION

3.03 INSTALLATION

A. General: Locate corner guard as indicated on approved detail drawings for the appropriate substrate and in compliance with the IPC installation instructions. Install corner guard level and plumb at the height indicated on drawings.

B. Installation of 130BN BluNose High Impact Surface Mount Corner Guard:

1. Retainer Installation:

Position the vinyl retainer against the wall, allowing 5/16" (8mm) from the bottom of the retainer to the top of the cove base or baseboard for the bottom cap.

Drywall: Secure the retainer to the wall using #8 x 1-1/4" Phillips round head, self-tapping screws. Stagger the fasteners on each wing of the retainer. Use 4 screws per 3' (.91m) length, 6 screws per 4' (1.22m) length, 10 screws per 8' (2.44m) length, or 12 screws per 9' (2.74m) length.

Concrete: Drill 1/4" (6.5mm) holes into the ends of the retainer for the top and bottom caps. Stagger the holes on each wing of the cap. Use the slotted tabs on the top and bottom cap to transfer hole location to the retainer. Drill 1/4" (6.5mm) holes on the two wings of the retainer. Stagger the fasteners on each wing of the retainer. Drill 4 holes per 3' (.91m) length, 6 holes per 4' (1.22m) length, 10 holes per 8' (2.44m) length, or 12 holes per 9' (2.74m) length. Transfer the location of all mounting holes to the wall. Drill 1/4" (6.5mm) holes and position ALLIGATOR anchors into the holes on the wall. Mount the retainer with #10 x 1-3/4" Phillips pan head screws and tighten to secure the retainer to the wall.

2. Top and Bottom Cap Installation:

Drywall: Overlap the retainer with the mounting tabs of the top and bottom caps and attach them to the retainer using two, #8 x 1-1/4" phillips flat head, self tapping screws per cap. Stagger the fasteners on each wing of the cap.

Concrete: Overlap the retainer with the mounting tabs of the top and bottom caps and attach them to the retainer and into the ALLIGATOR anchors using two, #8 x 1-1/2" phillips flat head screws per cap. When installing flexible top caps on custom angle corner guards, use cup washers and flat head screws to fasten the top caps to the retainer.

3. Position the vinyl cover on the retainer to check the fit. Adjust the top cap on the retainer to obtain a tight fit with the vinyl cover. Starting at the top, push the vinyl cover over the retainer pressing over the entire length until the cover snaps securely into place.

INSTALLATION NOTE: Vinyl retainers can be field bent to angles 10° wider or 10° tighter than 135°. When doing so top and bottom caps cannot be used and the installation should be full height from floor to ceiling. When doing so use flexible top and bottom caps or the installation should be full height from floor to ceiling.

Division 10 26 13
HIGH IMPACT CORNER GUARD WALL PROTECTION

3.04 CLEANING

A. At completion of the installation, clean surfaces in accordance with the IPC clean-up and maintenance instructions.

END OF SECTION

DIVISION 10 26 16.13
50SS STAINLESS STEEL WALL GUARD

PART 1 - GENERAL

1.01 SUMMARY
A. Stainless Steel Wall Guard system for wall protection

1.02 SECTION INCLUDES
A. 50SS Stainless Steel Wall Guard Systems

1.03 SUBMITTALS
A. Product data for each type of wall guard specified.
B. Detail drawings indicating mounting details with the appropriate fasteners for specific project substrates.
C. Samples for verification purposes of wall guard, 6" (152mm) long, in full size profiles of each type indicated.
D. Cleaning and maintenance instructions for door and wall protection systems.

1.04 DELIVERY, STORAGE AND HANDLING
A. Deliver materials in unopened factory packaging to the jobsite and store in original packaging in a climate controlled location away from direct sunlight.

1.05 PROJECT CONDITIONS
A. Products must be installed in an interior climate controlled environment.

1.06WARRANTY
A. Standard IPC Limited Lifetime Warranty against material and manufacturing defects.

PART 2 – PRODUCTS

2.01 MANUFACTURER
A. Acceptable Manufacturer:
IPC Door and Wall Protection Systems,
InPro Corporation, PO Box 406 Muskego, WI 53150 USA;
Telephone: 800-222-5556, Fax: 888-715-8407,
www.inprocorp.com
B. Substitutions: Not permitted
C. Provide all wall guards and wall protection from a single source.

Inprocorp.com • 800.222.5556 • 262.679.9010
World Headquarters S80 W18766 Apollo Drive, Muskego, WI 53150 USA

2.02 MANUFACTURED UNITS
A. Wall Guards
1. Stainless Steel Wall Guard
Model Size
50SS, 4" (102mm) h x 3-5/16" (84mm) deep,
Fabricated to field verified dimensions

2.03 MATERIALS
A. Stainless Steel: Wall Guard shall be manufactured from type 304 Stainless Steel.

2.04 FINISHES
A. Stainless Steel: Stainless steel wall guard shall have a #4 satin finish.

PART 3 - EXECUTION

3.01 EXAMINATION
A. Examine areas and conditions in which the wall guard systems will be installed.
1. Complete all finishing operations, including painting, before beginning installation of wall guards.
B. Wall surface shall be dry and free from dirt, grease and loose paint.

3.02 PREPARATION
A. General: Prior to installation, clean substrate to remove dust, debris and loose particles.

3.03 INSTALLATION
A. General: Locate the wall guard as indicated on the approved detail drawing for the appropriate substrate and in compliance with the IPC installation instructions. Install wall guard level and plumb at the height indicated on the drawings.
B. Installation of Stainless Steel Wall Guards:
Note: The 50SS Stainless Steel Wall Guard is manufactured to lengths specified by the customer. Returns and corners must be joined to the straight lengths with splices. When determining bracket locations, brackets cannot be installed in the spot where a splice occurs.
1. Determine height of wall guard. Deduct 1/4" and snap chalk line. Position the top edge of bracket against chalk line. Transfer mounting holes to wall.
2. Drill marked holes with 3/4" drill bit for toggle bolts (drywall installation) or 1/2" drill bit for lead anchor (concrete wall installation). Mount brackets to wall, tighten screws to secure.

Inprocorp.com • 800.222.5556 • 262.679.9010
World Headquarters S80 W18766 Apollo Drive, Muskego, WI 53150 USA

IPC™
DOOR + WALL PROTECTION SYSTEMS
A DIVISION OF INPRO®

3. Attach the returns and corners to the straight lengths using splices. Position the splice so the mounting tab of the wall guard aligns with the holes on the splice and bolt the assembly together.
4. Position wall guard into mounting brackets. Tighten the wall guard into the brackets with set screws.

3.04 CLEANING
A. At completion of the installation, clean surfaces in accordance with the IPC clean up and maintenance instructions.

END OF SECTION

Inprocorp.com • 800.222.5556 • 262.679.9010
World Headquarters S80 W18766 Apollo Drive, Muskego, WI 53150 USA

IPC™
DOOR + WALL PROTECTION SYSTEMS
A DIVISION OF INPRO®