

*Michael R. Wigley, AIA, LEED®AP  
W. Zachary Crouch, P.E.  
Michael E. Wheedleton, AIA  
Jason P. Loar, P.E.  
Ring W. Lardner, P.E.*

**NEW SECURE ENTRY  
AT  
STOCKLEY CENTER  
26351 PATRIOTS WAY  
GEORGETOWN, DELAWARE 19947  
DBF #586B035.GG1 ♦ DFM # MC3511000031**

**SEPTEMBER 24, 2018**

**ADDENDUM NO. 2**

The following items shall become a part of the contract documents. Contractor must acknowledge receipt of this addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

- Item No. 1     The Bid date has been extended to October 4<sup>th</sup> at 1:30 p.m. The last day for questions has been extended to September 27<sup>th</sup>.
- Item No. 2     The electrical contractor shall include in their base bid two (2) 1" conduits ran from the center of the west wall to the 12" wide concrete median near the gate arm ( $\pm$  38 feet run) for a card reader. The contractor shall provide electric per manufacturer's instructions.
- Item No. 3     The outbound gate shall be equipped with a ground loop to allow for vehicle detection and automatically operate the gate.
- Item No. 4     The electrical contractor shall include conduit and four (4) junction boxes to be mounted on the guardhouse fascia for security cameras. The security camera will be provided by others.
- Item No. 5     Clarification for flag poles. Refer to drawing SSM-02 – Key Legend DL and Plan E1 on Sheet A1: The three (3) flag poles are new. One flag pole is 30 feet high and two flag poles are 25 feet high.

**END OF ADDENDUM**