

ADDENDUM NO. 2

ELECTRIC SERVICE REPLACEMENT AT DHSS-NORTHEAST STATE SERVICE CENTER

1624 JESSUP ST. WILMINGTON DE 19802

OMB/DFM PROJECT #: MC3512000018

Date of Issue: July 21, 2017

- 1.0 This Addendum, Addendum #2 shall be made part of the Project Manual and Drawings dated June 24, 2017 for the Electric Service Replacement at DHSS-Northeast State Service Center.
- 2.0 A walkthrough of the project was conducted at 10:00 a.m., on Tuesday 7/18/17 for registered contractors. Based on the walkthrough, there are no changes to the contract documents.
- 3.0 Changes to Drawings
- 3.1 E20-01-Single Line Diagram, New Work
- A. Identify fused disconnect switch serving elevator as 3P-200A Elevator Duty Switch with 125A fuses. Actual fuse size to be confirmed in the field. Modify existing conduit and feeders to accommodate new disconnect switch. Switch shall be provided with auxiliary contact for elevators.
- 4.0 Changes to Specifications
- 4.1 No Changes to Specifications.
- 5.0 Questions/Clarifications:
- 5.1 The new work Single Line on Drawing E20-01 shows what I believe is a new fused disconnect for the Elevator. However it does show the size of the disconnect and fuses. Can you clarify.
- Reply: See Changes to Drawings above.

END OF ADDENDUM #2

16-1232 Addendum #2

cc: All Registered Plan Holders
P-File