

*Michael R. Wigley, AIA, LEED®AP
W. Zachary Crouch, P.E.
Michael E. Wheedleton, AIA
Jason P. Loar, P.E.
Ring W. Lardner, P.E.*

**SPRINKLER / CEILING REPLACEMENT
AT
ADMINISTRATION BUILDING
FERRIS CAMPUS
1825 FAULKLAND ROAD
WILMINGTON, DELAWARE 19805
DBF #586B034.B03 ♦ DFM # MC3701000065
SEPTEMBER 28, 2017**

ADDENDUM NO. 3

The following items shall become a part of the contract documents. Contractor must acknowledge receipt of this addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

- Item No. 1: The BID DATE is extended to **October 12, 2017**. The time and place will remain unchanged.
- Item No. 2: The scope of work has changed to provide a new wet system on the second floor and a new dry system in the attic. Refer to the attached drawings for specific information.
- Item No. 3: Refer to attached revised specification section 21 13 00 – FIRE SUPPRESSION SPRINKLERS for wet system requirements.
- Item No. 4: Contact Michael Bauman @ mpb@dbfinc.com if a site visit is needed.

END OF ADDENDUM

Section 21 1300

Fire Suppression Sprinklers

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Wet-pipe sprinkler system.
- B. Dry-pipe sprinkler system.
- C. System design, installation, and certification.

1.2 RELATED REQUIREMENTS

- A. Section 07 8400 - Firestopping.
- B. Section 21 0500 - Common Work Results for Fire Suppression: Pipe, fittings, and valves.

1.3 REFERENCE STANDARDS

- A. ICC-ES AC01 - Acceptance Criteria for Expansion Anchors in Masonry Elements; 2012.
- B. ICC-ES AC106 - Acceptance Criteria for Predrilled Fasteners (Screw Anchors) in Masonry Elements; 2012.
- C. ICC-ES AC193 - Acceptance Criteria for Mechanical Anchors in Concrete Elements; 2013.
- D. ICC-ES AC308 - Acceptance Criteria for Post-Installed Adhesive Anchors in Concrete Elements; 2013.
- E. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.
- F. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

1.4 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Convene one week before starting work of this section.

1.5 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on sprinklers, valves, and specialties, including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.

- C. Shop Drawings:
 - 1. Indicate hydraulic calculations, detailed pipe layout, hangers and supports, sprinklers, components and accessories. Indicate system controls.
 - 2. Submit shop drawings to Authority Having Jurisdiction for approval. Submit proof of approval to Architect.
- D. Project Record Documents: Record actual locations of sprinklers and deviations of piping from drawings. Indicate drain and test locations.

1.6 QUALITY ASSURANCE

- A. Conform to UL (DIR) requirements.
- B. Designer Qualifications: Design system under direct supervision of a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.
- C. Installer Qualifications: Company specializing in performing the work of this section documented experience and approved by manufacturer.
- D. Equipment and Components: Provide products that bear UL (DIR) label or marking.
- E. Products Requiring Electrical Connection: Listed and classified by UL (DIR) as suitable for the purpose specified and indicated.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Store products in shipping containers and maintain in place until installation. Provide temporary inlet and outlet caps. Maintain caps in place until installation.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Sprinklers, Valves, and Equipment:
 - 1. Tyco Fire Protection Products, a Tyco Business: www.tyco-fire.com.
 - 2. Viking Corporation: www.vikinggroupinc.com.

2.2 SPRINKLER SYSTEM

- A. Sprinkler System: Provide coverage for building areas noted.
- B. Occupancy: Light hazard; comply with NFPA 13.
- C. Water Supply: Determine volume and pressure from water flow test data.

- D. Interface system with building fire and smoke alarm system.
- E. Pipe Hanger Fasteners: Attach hangers to structure using appropriate fasteners, as follows:
 - 1. Concrete Wedge Expansion Anchors: Complying with ICC-ES AC193.
 - 2. Masonry Wedge Expansion Anchors: Complying with ICC-ES AC01.
 - 3. Concrete Screw Type Anchors: Complying with ICC-ES AC193.
 - 4. Masonry Screw Type Anchors: Complying with ICC-ES AC106.
 - 5. Concrete Adhesive Type Anchors: Complying with ICC-ES AC308.

2.3 SPRINKLERS

- A. Suspended Ceiling Type: Semi-recessed pendant type with matching push on escutcheon plate.
 - 1. Response Type: Quick.
 - 2. Coverage Type: Standard.
 - 3. Fusible Link: Fusible solder link type temperature rated for specific area hazard.
- B. Dry Sprinklers: Concealed pendant type with matching push on escutcheon plate.
 - 1. Response Type: Quick.
 - 2. Coverage Type: Extended.
 - 3. Fusible Link: Fusible solder link type temperature rated for specific area hazard.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Install in accordance with referenced NFPA design and installation standard.
- B. Install equipment in accordance with manufacturer's instructions.
- C. Place pipe runs to minimize obstruction to other work.
- D. Place piping in concealed spaces above finished ceilings.
- E. Center sprinklers in two directions in ceiling tile and provide piping offsets as required.

- F. Apply masking tape or paper cover to ensure concealed sprinklers, cover plates, and sprinkler escutcheons do not receive field paint finish. Remove after painting. Replace painted sprinklers.
- G. Flush entire piping system of foreign matter.
- H. Hydrostatically test entire system.
- I. Require test be witnessed by Fire Marshal.

End of Section