



**Addendum 02**

---

Webb Community Correctional Center – Fire Alarm Replacement & Electrical Modifications  
OMB/DFM/DOC Contract No: MC3804000054

Tt Project No. 200-26912-13019

Addendum No. 2  
to  
Drawings and Project Manual

May 2, 2014

---

To: ALL BIDDERS

This ADDENDUM forms a part of the BIDDING AND CONTRACT DOCUMENTS and modifies the following documents:

Original DRAWINGS dated April 4, 2014,  
PROJECT MANUAL dated April 4, 2014, and  
Addendum No. 1 dated April 14, 2014

Acknowledge receipt of the ADDENDUM in the space provided on the FORM OF PROPOSAL

This ADDENDUM consists of two (2) pages.

**PROJECT MANUAL MODIFICATIONS**

2.1 Specification Section 260533 Raceways and Boxes for Electrical Systems

- A. Part 2 Products, Article 2.1 Metal Conduit and Tubing, **DELETE** Paragraphs C, D, E, F & G in their entirety. All wiring shall be installed in Rigid Steel Conduit.
- B. Part 3 Execution, Article 3.1 Raceway Applications, Paragraph B, **DELETE** Subparagraphs 1 and 2 in their entirety.

2.2 Specification Section 28 31 11 Digital Addressable Fire Alarm System

- A. Article 2.1 Manufacturers; Paragraph A, **ADD** Model No. 5808 for the Silent Knight Standard of Design.
- B. Article 2.12 Device Guards **DELETE** Paragraphs A, B and C in their entirety and **REPLACE** with the following paragraphs:
  - “A. DEVICE GUARDS

- 1. Safety Technology International, Inc. Models 9600/9700 as the Standard of Design and Construction.

2. STI, Inc. (Safety Technology International, Inc.) 2306 Airport Road, Waterford, Michigan, 48327-1209. Phone: (248) 673-9898; Fax (248) 673-1246; Toll Free (800) 888-4184; [www.sti-usa.com](http://www.sti-usa.com).
3. Nine (9) gauge steel wire coated with corrosion resistant (white on red) polyester.
4. Sizes to match device that is being protected.”

#### **CLARIFICATIONS/RFI'S**

##### 2.3 Delcollo Electric email: Tuesday, April 22, 2014

- A. Need mounting method for the devices guards for smoke and heat detector in the drop ceiling on first floor.

Response: Mount 24”x 24”, 22-gauge panel of sheet metal behind ceiling tile. Mount device guard using tamper proof screw/bolts and nuts.

##### 2.4 Delcollo Electric email, dated May 1, 2014

- A. The fire alarm panel in spec is Silent Night proprietary line. Need Direction.

Response: Model Number added to the specification for a non-proprietary system.

- B. Note 2 on the drawing FA 102 talks about key. What does the key do? Do you need the key to set off the alarm or is the key just to reset the pull station?

Response: The key or keys are for the Correctional Officers to set the Alarm and then to reset the Pull Station. Standard operating procedure is for a Correctional Officer to visually check an alarm before setting off a general alarm and calling in the Fire Department.

##### 2.5 Delcollo Electric question during walk-thru April 23, 2014

- A. Can plenum rated wire be used above the 1<sup>st</sup> floor dropped ceiling?

Response: For bidding purposes use rigid conduit.

#### **END OF ADDENDUM 02**

Attachments: None