



240 Continental Drive, Suite 200
Newark, Delaware 19713
Tel. (302) 738-7551
Fax (302) 454-5989/5988

Addendum

JAMES T. VAUGHN CORRECTIONAL CENTER 'D' BUILDING SHOWER IMPROVEMENTS

OMB/DFM/DOC Contract No.: MC3804000024
Tt Project No. 26912-15005

Addendum No. 2

October 6, 2015

To: ALL BIDDERS

This ADDENDUM forms a part of the BIDDING AND CONTRACT DOCUMENTS and modifies the following documents:
Original DRAWINGS and PROJECT MANUAL dated Sept. 15, 2015

Acknowledge receipt of the ADDENDUM in the space provided on the FORM OF PROPOSAL

This ADDENDUM consists of three (3) pages, including the attachments:

1.0 GENERAL:

- 1.1 Bid due Date – Unchanged from Advertisement – 2:00pm Thursday, October 8, 2015
- 1.2 Deadline for Questions – Close of Business Friday, October 1, 2015
- 1.3 Documents can be obtained / purchased at the office of Tetra Tech in Newark

2.0 CHANGES to the PROJECT MANUAL

2.1 SECTION 097110 – RESINOUS FLOORING –

Note that the product performance is changing from a standard urethane epoxy coating that requires a 28 day cure period for new/"green" concrete sub-straight, to a troweled cementitious urethane system that allows for application over "green" concrete in 7 days. In addition, the final top coat shall have a non-skid surface finish.

CHANGE SECTION as follows: PART 2 Products, Paragraph 1.2.B: **DELETE** Basis of Design Stonehard SLT. **ADD** the following approved products: Base cementitious coat shall be ¼" minimum thickness.

- 2.1.1. Sherwin Williams/General Polymers, "FasTop 12S Urethane Slurry System" with GP 4090 FasTop 12TC urethane top coating.
- 2.1.2. Dex-O-Tex, "Tek-Crete TT" with non-slip medium texture broadcast, and "Positred CR" Topcoat
- 2.1.3 Dura-Flex, "Polycrete SLB" with "Novalac" topcoat.

2.2 SECTION 01 11 00 SUMMARY –

Paragraph 1.10 WORK RESTRICTIONS- **ADD** the following Paragraph "B" PHASING – Along with full access to the mechanical penthouse for the duration of the project, the contractor shall have simultaneous access to two tiers/shower rooms at all times. Note that this is a change from the Phasing requirement discussed in the Pre-bid and walk thru meetings, of access to one tier at time.

3.0 CHANGES to the DRAWINGS :

3.1 TIER CORRIDOR PAINTING **CLARIFICATION:** The tier corridor walls shall be painted floor to ceiling from the frame of the new windows to the corner of tier entrance wall. Typical for all shower rooms. See attached sketch C-SK-1, 10/5/15.

3.2 A-101

3.2.1 Detail 8 & 9 – **CHANGE** – Glass to ¾” Polycarbonate/Security glass- typical for all windows

ATTACHMENT LIST – Sketch – C-SK-1_ 10/5/15

cc: All plan holders, E. Kulhanek

END OF ADDENDUM No. 2

j:\er\26912\200-26912-15005\construction\bidsupport\addenda\26912-15005 addenda 02_2015-05-15.doc

DRAWING REDACTED