



Delaware
315 S. Chapel Street
Newark, DE 19711
Phone
302.738.7172
Fax
302.738.7175

Pennsylvania
One Liberty Place
1650 Market Street
36th Floor
Philadelphia, PA 19103
Phone
267.386.4885
www.dedc-eng.com

HOWARD R. YOUNG CORRECTIONAL INSTITUTION
AIR HANDLING UNIT REPLACEMENT
OMB/DFM # MC3804000090

ADDENDUM #3

QUESTIONS:

1. What are the Liquidated Damages for this project?

Answer: There are no liquidated damages associated with this project.

2. Who is responsible for roof protection?

Answer: The successful contractor shall provide ½” thick plywood sheets (or similar type protection) on roof surfaces utilized to demolish and install new equipment.

3. What do we do with the existing supply air dampers and actuators?

Answer: Contractor shall measure the airflow through each damper prior to demolition, demolish damper and actuator, and install new manually operated volume damper. New damper to be balanced to prior measured value.

4. What material and gauge should the orifice plate be made out of?

Answer: the orifice plate shall be made out of 16 gauge G90 galvanized sheet metal.

A. Addendum #3

1. Addendum #3 (this document) (1 page)

Summarized By: DEDC, LLC

Matt Lano

Date: 07/27/18