

**Addendum
No. 3**

Addendum Date: November 22, 2017
Project: Autopsy HVAC Replacement at DFS Wilmington
DFM Project No: MC4501000001

The work herein shall be considered part of the bid documents for the referenced project and carried out in accordance with the following supplemental instructions issued in accordance with the Contract Documents without change in Contract Sum or Contract Time. Acknowledge receipt of addendum on the bid form as indicated.

Clarifications/General:

1. Bid Form Clarifications. Two completed copies of the bid form must be provided with each bid submission. This includes the Subcontractor List and the Non-Collusion Statement. Only one set of drug testing affidavits and bid bonds need to be provided.
2. As a clarification, architectural site plans require the installation of concrete stairs with a steel hand rail and a concrete slab. The makeup air unit with structural, 36" side-discharge curb is to be fastened to the slab. Mechanical plans require the installation of a 36" high, stainless steel service platform with steps fastened to the concrete slab.

Changes to Drawings:

1. *Drawing M8.1* – At detail 1/8.1, add note – “The structural, side-discharge curb shall be constructed of stainless steel.” No sketch is issued to reflect this change.
2. *Drawing M8.1* – At Ground Floor Mechanical Plan, add note – “The stainless steel service platform is to be fastened to concrete slab.” No sketch is issued to reflect this change.

Changes to Specifications:

1. *None.*

END