

3588 Peachtree Run Dover, DE 19901 (302) 697-7694 Fax: (302) 697-1328

PRE-BID MEETING MINUTES DELAWARE EMERGENCY MANAGEMENT AGENCY / DELDOT DEMA / TMC GENERATOR REDUNDANCY PROJECT SMYRNA, DELAWARE OMB/DFM #: MC5508000001 DSE #:17-2-0155 DECEMBER 06, 2018

ADDENDUM NO. 3

The following items shall become a part of the contract documents. Contractor must acknowledge receipt of this addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

Item No.1: The following questions / requests for clarification were received. The responses are in **bold** text:

A. DVL would like to provide the Network Switch and Fiber Optic Patch Panel within the AGSS. Low voltage cabling contractor to land fiber cable in AGSS for communication to Network Rack in DEMA LAN Room 215. Is this acceptable?

Response:

The State will utilize a State approved telecommunications vendor to provide the network switch and fiber optic patch panel in the AGSS controls compartment. The successful bidder shall coordinate with the State telecommunications approved vendor for network equipment space requirements within the AGSS controls compartment.

B. Is a Factory Witness Test required of the AGSS prior to shipment?

Response:

Please refer to the Project Manual, Specification Section 26 23 16, Automated Generator Selector Switchboard, Article 3.2 "Factory Testing", Paragraph D. The referenced paragraph indicates, factory witness testing shall be provided for an Owner's representative. The Owner does intend to provide a representative to witness the factory testing. C. Is witnessed NETA Testing of the AGSS components required?

Response:

Please refer to the response under Item No. 1 (B).

All testing critical to the operation and functionality of the AGSS, including the required NETA testing, shall be witnessed by the Owner's representative at the factory.

END OF ADDENDUM