

DELDOT Administration Building
Roof Replacement and Repairs
800 Bay Road
Dover, Delaware

ADDENDUM No. 2
February 4, 2014

OMB/DFM Contract No. MC551100007

The following document is intended to amend the revised Project Manual and Drawings (revised 1/2/2014 and issued for bidding 1/21/2014) for the above-referenced project.

1. Interested contractors may visit the site on **Thursday, February 6, 2014 at 1:00 PM.** If interested, call John Dunham at (302) 744-1185 by mid-day Wednesday, February 5, 2014.
2. Drawings:
 - A. Add the following "Scope of Roof Repairs" to drawing A000.

Scope of Roof Repairs:

The repair work shall include, but not be limited to, the various types of repairs called for and noted on roof areas R1, R2, R3, R4, R5, R6, R7, R8, R9, R10, and R11 indicated on drawings A100, A101, A012, and A103.

Types of Repairs and approximate quantities to be included are as follows:

1. Repair seams in membrane flashings.....100 L.F.
2. Repair seams in membrane flashings at mechanical units and unused curbs.....50 L.F.
3. Repair open seams in built up roof and EPDM membranes.....150 L.F.
4. Remove and replace deteriorated joint sealant.....150 L.F.
5. Remove and replace broken or spalled face brick.....10 Brick
6. Patch point loose and/or missing face brick Mortar joints.....100 S.F.

Required repairs in excess of the above listed quantities shall be performed at the agreed unit prices indicated on the bid form.

3. Project Manual:
 - A. Section 077100 – Roof Specialties, Page 077100-5, Paragraph 2.4 Copings, Sub-paragraph A.1.Manufacturers:

Add item 'i' as follows:

"i. W.P. Hickman Company, Permasnap Parapet Wall Coping".

*** End of Addendum No. 2 ***