

**Addendum
No. 2**

Addendum Date: July 27, 2018
Project: Lower Level IT Reconfiguration at DeIDOT Admin Building
DFM Project No: MC5511000019

The work herein shall be considered part of the bid documents for the referenced project and carried out in accordance with the following supplemental instructions issued in accordance with the Contract Documents without change in Contract Sum or Contract Time. Acknowledge receipt of addendum on the bid form as indicated.

Clarifications / Scope Revisions:

1. All ceiling mounted devices are to be centered in ceiling tiles, including sprinkler heads.
2. The owner will remove the existing Computer Room AC (CRAC) unit and associated air cooled condenser. The contractor shall demolish all other appurtenances including associated refrigerant piping, and provide mortar infill at existing wall penetrations.
3. The contractor shall demolish the entire electrical circuit serving the existing CRAC unit, including breakers, wiring, conduit, and disconnects.
4. The owner will remove the existing FM-200 bottle. The contractor is to demolish all FM-200 piping and heads.
5. The original manufacturer of the existing raised floor system is unknown and no documentation is available from the owner. The contractor is responsible for providing a floor system to match existing or provide a compatible system / solution.
6. Door Hardware Set #1 to include:
 - Hollow metal frame and hollow metal doors Doors D01 and D02
 - Standard Hinge Stanly CB168 4-1/2"x4-1/2" US26D
 - Lockset Best 9K 3 (Pat.) 7B 14D S3 626 BPPK Coremax
 - Door Silencers Rockwood 608
 - Floor Door Stop Rockwood 441CU US26D
 - Closer LCN 4041XP x H 689Note:
In addition to Hardware Set #1, provide an Electric Strike for door D01 only

Changes to Specifications:

None.

Changes to Drawings:

None.

END