This copy is for information only; you must purchase a set of documents in order to submit a bid.

ROOF REPAIR, RESTORATION AND REPLACEMENT SPECIFICATIONS

FOR



Delaware Health and Social Services

State of Delaware
Office of Management and Budget
540 South Dupont Highway, Suite 1
Dover, Delaware 19901

AT

The Emily P. Bissell Hospital Main & 1912 Buildings 3000 Newport Gap Pike Wilmington, DE 19808

Contract #MJ3514000010

FROM

fessional

229 Lake Drive

Consultants, Planners

Newark, DE 19702

Service?



RHETT H. JONES, ARCHITECT

389 CHURCH ROAD DEVON, PA. 19333

610-329-5151

August 2015

STATE OF DELAWARE DEPARTMENT OF FACILITIES MANAGEMENT CONTRACT # MJ3514000010

SPECIFICATIONS FOR THE

ROOF REPAIR, RESTORATION AND REPLACEMENT PROJECT AT THE EMILY P. BISSELL HOSPITAL

3000 Newport Gap Pike Wilmington, DE 19808

PREPARED BY

Professional Roof Services, Inc. 9 Fairview Avenue Middletown, DE 19709

> ISSUED FOR BID August 19, 2015

TABLE OF CONTENTS

A. Specifications for this project are arranged in accordance with the Construction Specification Institute numbering system and format. Section numbering is discontinuous and all numbers not appearing in the Table of Contents are not used for this Project.

B. DOCUMENTS BOUND HEREWITH

DIVISION 00 – PROCUREMENT AND CONTRACT REQUIREMENTS	
INTRODUCTORY INFORMATION	,
00 01 01 – PROJECT TITLE PAGE	1 page
00 01 10 – TABLE OF CONTENTS	2 pages
00 01 15 – LIST OF DRAWING SHEETS	1 page
PROCUREMENT REQUIREMENTS	
00 11 16 – INVITATION TO BID	1 page
00 21 13 – INSTRUCTIONS TO BIDDERS	12 pages
00 41 13 – BID FORM	4 pages
00 43 13 – BID BOND	1 page
CONTRACTING REQUIREMENTS	
00 52 13 – STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR	1 page
(SAMPLE AIA A101)	8 pages
00 54 13 – SUPPLEMENT TO AGREEMENT BETWEEN OWNER & CONTRACTOR A101-2007	1 page
00 61 13.13 – PERFORMANCE BOND	2 pages
00 61 13.16 – PAYMENT BOND	2 pages
00 62 76 – APPLICATION AND CERTIFICATE FOR PAYMENT FORMS	1 page
(SAMPLE AIA G702 & G703)	2 pages
00 72 13 - GENERAL CONDITIONS TO THE CONTRACT	1 page
(SAMPLE AIA A201)	40 pages

TABLE OF CONTENTS (Con't)

	00 73 13 - SUPPLEMENTARY GENERAL CONDITIONS	10 pages
	00 73 46 – WAGE RATE REQUIREMENTS	2 pages
	00 81 13 – GENERAL REQUIREMENTS	15 pages
	00 90 10 - CERTIFICATE OF ANALYSIS - ASBESTOS CONTENT	2 pages
	a.) MAIN BUILDING REPORT b.) 1912 BUILDING REPORT	40 pages 47 pages
	00 90 20 – SUPPLEMENTARY ROOFING CONDITIONS	11 pages
	00 90 30 - CONSTRUCTION WASTE MANAGEMENT	7 pages
	DIVISION 07 – THERMAL & MOISTURE PROTECTION SECTION ONE – MAIN HOSPITAL BUILDING	
	07 31 15 – EPDM & MODIFIED ROOF REPAIRS	3 pages
	07 50 71 – EPDM ROOF RESTORATION SPECIFICATION & DETAILS	24 pages
	07 52 20 - MODIFIED ROOF REPLACEMENT SPECIFICATION & DETAILS	126 pages
	SECTION TWO – 1912 BUILDING	
	07 50 70 - EPDM ROOF RESTORATION SPECIFICATION & DETAILS	30 pages
	07 50 75 - MODIFIED ROOF RESTORATION SPECIFCATIONS & DETAILS	28 pages
	07 31 13 – SHINGLE ROOF REPAIRS	3 pages
	07 52 16 - MODIFIED ROOF REPLACEMENT SPECIFICATIONS & DETAILS	58 pages
	END OF SECTION	
(

LIST OF DRAWING SHEETS

COVER SHEET – G-001
ROOF SPECIFICATION DRAWING MAIN HOSPITAL – PRSI13509DHS
ROOF SPECIFICATION DRAWING 1912 BUILDING – PRSI13511DHS
TAPERED INSULATION DRAWING

INVITATION TO BID

Document 001000

Sealed bids for OMB/DFM Contract No. <u>MJ3514000010</u>, The Emily P. Bissell Hospital Main and 1912 <u>Building Roof Repair</u>, Restoration and Replacement Project, will be received by the State of Delaware, Office of Management and Budget, Division of Facilities Management, at the <u>DFM Large Conference Room</u> (3rd Floor, Thomas Collins Building) 540 South DuPont Highway, Suite 1, Dover, Delaware 19901 until 2:00 <u>P.M.</u> local time on <u>September 3, 2015</u>, at which time they will be publicly opened and read aloud in the Conference Room. Bidder bears the risk of late delivery. Any bids received after the stated time will be returned unopened.

Project involves the replacement of designated roofs with a two-ply cold process modified roof with a flood and gravel surface as well as an alternate for a three-ply modified hot applied roofing system. New perimeter and projection flashings will be installed along with new drains and edge metals. Restoration will include roof repairs and the installation of a white liquid applied coating. Other roof sections will receive miscellaneous roof repairs.

Attention is called to construction schedule as detailed in the Bid Documents. The buildings are located at 3000 Newport Gap Pike, Wilmington, Delaware 19808.

A **MANDATORY** Pre-Bid Meeting will be held on August 19, 2015, at 10:00 A.M. at the Emily P. Bissell Hospital's "G" Building, 3000 Newport gap Pike, Wilmington, Delaware 19808 for the purpose of establishing the listing of subcontractors and to answer questions. Representatives of each party to any Joint Venture must attend this meeting. **ATTENDANCE OF THIS MEETING IS A PREREQUISITE FOR BIDDING ON THIS CONTRACT.**

Sealed bids shall be addressed to the Division of Facilities Management 540 South DuPont Highway, Suite 1, Dover, DE 19901. The outer envelope should clearly indicate: "OMB/DFM CONTRACT NO. MJ3514000010, EMILY P. BISSELL HOSPITAL MAIN AND 1912 BUILDING — ROOF REPAIR, RESTORATION AND REPLACEMENT PROJECT - SEALED BID - DO NOT OPEN."

Contract documents may be obtained at the office of Professional Roof Services, 9 Fairview Avenue, Middletown, DE 19709 (please phone ahead to (302) 376-5220 to confirm availability) upon receipt of \$100.00 per set/non-refundable. Checks are to be made payable to "Professional Roof Services."

Construction documents will be available for review at the following locations: <u>Professional Roof Services</u>, Delaware Contractors Association and the Associated Builders and Contractors.

Minority Business Enterprises (MBE), Disadvantaged Business Enterprises (DBE) and Women-Owned Business Enterprises (WBE) will be afforded full opportunity to submit bids on this contract and will not be subject to discrimination on the basis of race, color, national origin or sex in consideration of this award. Each bid must be accompanied by a bid security equivalent to ten percent of the bid amount and all additive alternates. The successful bidder must post a performance bond and payment bond in a sum equal to 100 percent of the contract price upon execution of the contract. The Owner reserves the right to reject any or all bids and to waive any informalities therein. The Owner may extend the time and place for the opening of the bids from that described in the advertisement, with not less than two calendar days notice by certified delivery, facsimile machine or other electronic means to those bidders receiving plans.

INV-1 INV-1

INSTRUCTIONS TO BIDDERS

TABLE OF ARTICLES

- 1. DEFINITIONS
- 2. BIDDER'S REPRESENTATION
- 3. BIDDING DOCUMENTS
- 4. BIDDING PROCEDURES
- 5. CONSIDERATION OF BIDS
- 6. POST-BID INFORMATION
- 7. PERFORMANCE BOND AND PAYMENT BOND
- 8. FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

ARTICLE 1: GENERAL

- 1.1 DEFINITIONS
- 1.1.1 Whenever the following terms are used, their intent and meaning shall be interpreted as follows:
- 1.2 STATE: The State of Delaware.
- 1.3 AGENCY: Contracting State Agency as noted on cover sheet.
- 1.4 DESIGNATED OFFICIAL: The agent authorized to act for the Agency.
- 1.5 BIDDING DOCUMENTS: Bidding Documents include the Bidding Requirements and the proposed Contract Documents. The Bidding Requirements consist of the Advertisement for Bid, Invitation to Bid, Instructions to Bidders, Supplementary Instructions to Bidders (if any), General Conditions, Supplementary General Conditions, General Requirements, Special Provisions (if any), the Bid Form (including the Non-collusion Statement), and other sample bidding and contract forms. The proposed Contract Documents consist of the form of Agreement between the Owner and Contractor, as well as the Drawings, Specifications (Project Manual) and all Addenda issued prior to execution of the Contract.
- 1.6 CONTRACT DOCUMENTS: The Contract Documents consist of the, Instructions to Bidders, Supplementary Instructions to Bidders (if any), General Conditions, Supplementary General Conditions, General Requirements, Special Provisions (if any), the form of agreement between the Owner and the Contractor, Drawings (if any), Specifications (Project Manual), and all addenda.
- 1.7 AGREEMENT: The form of the Agreement shall be AIA Document A101, Standard Form of Agreement between Owner and Contractor where the basis of payment is a STIPULATED SUM. In the case of conflict between the instructions contained therein and the General Requirements herein, these General Requirements shall prevail.
- 1.8 GENERAL REQUIREMENTS (or CONDITIONS): General Requirements (or conditions) are instructions pertaining to the Bidding Documents and to contracts in general. They contain, in summary, requirements of laws of the State; policies of the Agency and instructions to bidders.
- 1.9 SPECIAL PROVISIONS: Special Provisions are specific conditions or requirements peculiar to the bidding documents and to the contract under consideration and are supplemental to the General Requirements. Should the Special Provisions conflict with the General Requirements, the Special Provisions shall prevail.
 - ADDENDA: Written or graphic instruments issued by the Owner/Architect prior to the execution of the contract which modify or interpret the Bidding Documents by additions, deletions, clarifications or corrections.
- BIDDER OR VENDOR: A person or entity who formally submits a Bid for the material or Work contemplated, acting directly or through a duly authorized representative who meets the requirements set forth in the Bidding Documents.
- 1.12 SUB-BIDDER: A person or entity who submits a Bid to a Bidder for materials or labor, or both for a portion of the Work.
- 1.13 BID: A complete and properly executed proposal to do the Work for the sums stipulated therein, submitted in accordance with the Bidding Documents.

1.14 BASE BID: The sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents as the base, to which Work may be added or from which Work may be deleted for sums stated in Alternate Bids (if any are required to be stated in the bid). ALTERNATE BID (or ALTERNATE): An amount stated in the Bid, where applicable, to be 1.15 added to or deducted from the amount of the Base Bid if the corresponding change in the Work, as described in the Bidding Documents is accepted. UNIT PRICE: An amount stated in the Bid, where applicable, as a price per unit of 1.16 measurement for materials, equipment or services or a portion of the Work as described in the Bidding Documents. SURETY: The corporate body which is bound with and for the Contract, or which is liable, 1.17 and which engages to be responsible for the Contractor's payments of all debts pertaining to and for his acceptable performance of the Work for which he has contracted. 1.18 BIDDER'S DEPOSIT: The security designated in the Bid to be furnished by the Bidder as a guaranty of good faith to enter into a contract with the Agency if the Work to be performed or the material or equipment to be furnished is awarded to him. CONTRACT: The written agreement covering the furnishing and delivery of material or work 1.19 to be performed. CONTRACTOR: Any individual, firm or corporation with whom a contract is made by the 1.20 Agency. SUBCONTRACTOR: An individual, partnership or corporation which has a direct contract 1.21 with a contractor to furnish labor and materials at the job site, or to perform construction labor and furnish material in connection with such labor at the job site. CONTRACT BOND: The approved form of security furnished by the contractor and his 1.22 surety as a guaranty of good faith on the part of the contractor to execute the work in accordance with the terms of the contract. **BIDDER'S REPRESENTATIONS ARTICLE 2:** PRE-BID MEETING 2.1 2.1.1 A pre-bid meeting for this project will be held at the time and place designated. Attendance at this meeting is a pre-requisite for submitting a Bid, unless this requirement is specifically waived elsewhere in the Bid Documents. By submitting a Bid, the Bidder represents that:

The Bidder has read and understands the Bidding Documents and that the Bid is made in

The Bidder has visited the site, become familiar with existing conditions under which the Work is to be performed, and has correlated the Bidder's his personal observations with the

The Bid is based upon the materials, equipment, and systems required by the Bidding

INSTRUCTIONS TO BIDDERS

2.2.3

accordance therewith.

Documents without exception.

requirements of the proposed Contract Documents.

2.3 JOINT VENTURE REQUIREMENTS 2.3.1 For Public Works Contracts, each Joint Venturer shall be qualified and capable to complete the Work with their own forces. 2.3.2 Included with the Bid submission, and as a requirement to bid, a copy of the executed Join Venture Agreement shall be submitted and signed by all Joint Venturers involved. All required Bid Bonds, Performance Bonds, Material and Labor Payment Bonds must 2.3.3 executed by both Joint Venturers and be placed in both of their names. 2.3.4 All required insurance certificates shall name both Joint Venturers. 2.3.5 Both Joint Venturers shall sign the Bid Form and shall submit a copy of a valid Delaware Business License with their Bid. 2.3.6 Both Joint Venturers shall include their Federal E.I. Number with the Bi In the event of a mandatory Pre-bid Meeting, each Joint Venturer shall have a representative 2.3.7 in attendance. 2.3.8 Due to exceptional circumstances and for good cause shown, one or more of these provisions may be waived at the discretion of the State. ASSIGNMENT OF ANTITRUST CLAIMS 2.4 As consideration for the award and execution by the Owner of this contract, the Contractor 2.4.1 hereby grants, conveys, sells, assigns and transfers to the State of Delaware all of its right, title and interests in and to all known or unknown causes of action it presently has or may now or hereafter acquire under the antitrust laws of the United States and the State of Delaware, relating to the particular goods or services purchased or acquired by the Owner pursuant to this contract. **BIDDING DOCUMENTS ARTICLE 3:** COPIES OF BID DOCUMENTS 3.1 obtain complete sets of the 3.1.1 Bidders Bidding Documents from Architectural/Engineering firm designated in the Advertisement or Invitation to Bid in the number and for the deposit sum, if any, stated therein. 3.1.2 Bidders shall use complete sets of Bidding Documents for preparation of Bids. The issuing Agency nor the Architect assumes no responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents. Any errors, inconsistencies or omissions discovered shall be reported to the Architect immediately.

The Agency and Architect may make copies of the Bidding Documents available on the above terms for the purpose of obtaining Bids on the Work. No license or grant of use is

conferred by issuance of copies of the Bidding Documents.

3.2 INTERPRETATION OR CORRECTION OF BIDDING DOCUMENTS

- 3.2.1 The Bidder shall carefully study and compare the Bidding Documents with each other, and with other work being bid concurrently or presently under construction to the extent that it relates to the Work for which the Bid is submitted, shall examine the site and local conditions, and shall report any errors, inconsistencies, or ambiguities discovered to the Architect.
- 3.2.2 Bidders or Sub-bidders requiring clarification or interpretation of the Bidding Documents shall make a written request to the Architect at least seven days prior to the date for receipt of Bids. Interpretations, corrections and changes to the Bidding Documents will be made by written Addendum. Interpretations, corrections, or changes to the Bidding Documents made in any other manner shall not be binding.
- 3.2.3 The apparent silence of the specifications as to any detail, or the apparent omission from it of detailed description concerning any point, shall be regarded as meaning that only the best commercial practice is to prevail and only material and workmanship of the first quality are to be used. Proof of specification compliance will be the responsibility of the Bidder.
- 3.2.4 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for all permits, labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for the proper execution and completion of the Work.
- 3.2.5 The Owner will bear the costs for all impact and user fees associated with the project.

3.3 SUBSTITUTIONS

- 3.3.1 The materials, products and equipment described in the Bidding Documents establish a standard of quality, required function, dimension, and appearance to be met by any proposed substitution. The specification of a particular manufacturer or model number is not intended to be proprietary in any way. Substitutions of products for those named will be considered, providing that the Vendor certifies that the function, quality, and performance characteristics of the material offered is equal or superior to that specified. It shall be the Bidder's responsibility to assure that the proposed substitution will not affect the intent of the design, and to make any installation modifications required to accommodate the substitution.
- 3.3.2 Requests for substitutions shall be made in writing to the Architect at least ten days prior to the date of the Bid Opening. Such requests shall include a complete description of the proposed substitution, drawings, performance and test data, explanation of required installation modifications due the substitution, and any other information necessary for an evaluation. The burden of proof of the merit of the proposed substitution is upon the proposer. The Architect's decision of approval or disapproval shall be final. The Architect is to notify Owner prior to any approvals.
- If the Architect approves a substitution prior to the receipt of Bids, such approval shall be set forth in an Addendum. Approvals made in any other manner shall not be binding.
- The Architect shall have no obligation to consider any substitutions after the Contract award.
- 3.4 ADDENDA
- 3.4.1 Addenda will be mailed or delivered to all who are known by the Architect to have received a complete set of the Bidding Documents.

- 3.4.2 Copies of Addenda will be made available for inspection wherever Bidding Documents are on file for that purpose.
- 3.4.3 No Addenda will be issued later than 4 days prior to the date for receipt of Bids except an Addendum withdrawing the request for Bids or one which extends the time or changes the location for the opening of bids.
- 3.4.4 Each bidder shall ascertain prior to submitting his Bid that they have received all Addenda issued, and shall acknowledge their receipt in their Bid in the appropriate space. Not acknowledging an issued Addenda could be grounds for determining a bid to be non-responsive.

ARTICLE 4: BIDDING PROCEDURES

- 4.1 PREPARATION OF BIDS
- 4.1.1 Submit the bids on the Bid Forms included with the Bidding Documents.
- 4.1.2 Submit the original Bid Form for each bid. Bid Forms may be removed from the project manual for this purpose.
- 4.1.3 Execute all blanks on the Bid Form in a non-erasable medium (typewriter or manually in ink).
- 4.1.4 Where so indicated by the makeup on the Bid Form, express sums in both words and figures, in case of discrepancy between the two, the written amount shall govern.
- 4.1.5 Interlineations, alterations or erasures must be initialed by the signer of the Bid.
- 4.1.6 BID ALL REQUESTED ALTERNATES AND UNIT PRICES, IF ANY. If there is no change in the Base Bid for an Alternate, enter "No Change". The Contractor is responsible for verifying that they have received all addenda issued during the bidding period. Work required by Addenda shall automatically become part of the Contract.
- 4.1.7 Make no additional stipulations on the Bid Form and do not qualify the Bid in any other manner.
- Each copy of the Bid shall include the legal name of the Bidder and a statement whether the Bidder is a sole proprietor, a partnership, a corporation, or any legal entity, and each copy shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid by a corporation shall further give the state of incorporation and have the corporate seal affixed. A Bid submitted by an agent shall have a current Power of Attorney attached, certifying agent's authority to bind the Bidder.
- 4.1.9 Bidder shall complete the Non-Collusion Statement form included with the Bid Forms and include it with their Bid.
- In the construction of all Public Works projects for the State of Delaware or any agency thereof, preference in employment of laborers, workers or mechanics shall be given to bona fide legal citizens of the State who have established citizenship by residence of at least 90 days in the State.
- 4.1.11 Each bidder shall include in their bid a copy of a valid Delaware Business License.'

4.2 BID SECURITY

- 4.2.1 All bids shall be accompanied by a deposit of either a good and sufficient bond to the agency for the benefit of the agency, with corporate surety authorized to do business in this State, the form of the bond and the surety to be approved by the agency, or a security of the bidder assigned to the agency, for a sum equal to at least 10% of the bid plus all add alternates, or in lieu of the bid bond a security deposit in the form of a certified check, bank treasurer's check, cashier's check, money order, or other prior approved secured deposit assigned to the State. The bid bond need not be for a specific sum, but may be stated to be for a sum equal to 10% of the bid plus all add alternates to which it relates and not to exceed a certain stated sum, if said sum is equal to at least 10% of the bid. The Bid Bond form used shall be the standard OMB form (attached).
- 4.2.2 The Agency has the right to retain the bid security of Bidders to whom an award is being considered until either a formal contract has been executed and bonds have been furnished or the specified time has elapsed so the Bids may be withdrawn or all Bids have been rejected.
- 4.2.3 In the event of any successful Bidder refusing or neglecting to execute a formal contract and bond within 20 days of the awarding of the contract, the bid bond or security deposited by the successful bidder shall be forfeited.

4.3 SUBCONTRACTOR LIST

- 4.3.1 As required by <u>Delaware Code</u>, Title 29, section 6962(d)(10)b, each Bidder shall submit with their Bid a completed List of Sub-Contractors included with the Bid Form. NAME ONLY ONE SUBCONTRACTOR FOR EACH TRADE. A Bid will be considered non-responsive unless the completed list is included.
- 4.3.2 Provide the Name and Address for each listed subcontractor. Addresses by City, Town or Locality, plus State, will be acceptable.
- 4.3.3 It is the responsibility of the Contractor to ensure that their Subcontractors are in compliance with the provisions of this law. Also, if a Contractor elects to list themselves as a Subcontractor for any category, they must specifically name themselves on the Bid Form and be able to document their capability to act as Subcontractor in that category in accordance with this law.

4.4 EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS

4.4.1 During the performance of this contract, the contractor agrees as follows:

The Contractor will not discriminate against any employee or applicant for employment because of race, creed, sex, color, sexual orientation, gender identity or national origin. The Contractor will take affirmative action to ensure the applicants are employed, and that employees are treated during employment, without regard to their race, creed, sex, color, sexual orientation, gender identity or national origin. Such action shall include, but not be limited to, the following: Employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.

B. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, sex, color, sexual orientation, gender identity or national origin."

4.5 PREVAILING WAGE REQUIREMENT

- 4.5.1 Wage Provisions: In accordance with <u>Delaware Code</u>, Title 29, Section 6960, renovation projects whose total cost shall exceed \$15,000, and \$100,000 for new construction, the minimum wage rates for various classes of laborers and mechanics shall be as determined by the Department of Labor. Division of Industrial Affairs of the State of Delaware.
- 4.5.2 The prevailing wage shall be the wage paid to a majority of employees performing similar work as reported in the Department's annual prevailing wage survey or in the absence of a majority, the average paid to all employees reported.
- 4.5.3 The employer shall pay all mechanics and labors employed directly upon the site of work, unconditionally and not less often than once a week and without subsequent deduction or rebate on any account, the full amounts accrued at time of payment, computed at wage rates not less than those stated in the specifications, regardless of any contractual relationship which may be alleged to exist between the employer and such laborers and mechanics.
- 4.5.4 The scale of the wages to be paid shall be posted by the employer in a prominent and easily accessible place at the site of the work.
- 4.5.5 Every contract based upon these specifications shall contain a stipulation that sworn payroll information, as required by the Department of Labor, be furnished weekly. The Department of Labor shall keep and maintain the sworn payroll information for a period of 6 months from the last day of the work week covered by the payroll.

4.6 SUBMISSION OF BIDS

- 4.6.1 Enclose the Bid, the Bid Security, and any other documents required to be submitted with the Bid in a sealed opaque envelope. Address the envelope to the party receiving the Bids. Identify with the project name, project number, and the Bidder's name and address. If the Bid is sent by mail, enclose the sealed envelope in a separate mailing envelope with the notation "BID ENCLOSED" on the face thereof. The State is not responsible for the opening of bids prior to bid opening date and time that are not properly marked.
- 4.6.2 Deposit Bids at the designated location prior to the time and date for receipt of bids indicated in the Advertisement for Bids. Bids received after the time and date for receipt of bids will be marked "LATE BID" and returned.
- 4.6.3 Bidder assumes full responsibility for timely delivery at location designated for receipt of bids.
- 1.6.4 Oral, telephonic or telegraphic bids are invalid and will not receive consideration.
- 4.6.5 Withdrawn Bids may be resubmitted up to the date and time designated for the receipt of Bids, provided that they are then fully in compliance with these Instructions to Bidders.

4.7 MODIFICATION OR WITHDRAW OF BIDS

- 4.7.1 Prior to the closing date for receipt of Bids, a Bidder may withdraw a Bid by personal request and by showing proper identification to the Architect. A request for withdraw by letter or fax, if the Architect is notified in writing prior to receipt of fax, is acceptable. A fax directing a modification in the bid price will render the Bid informal, causing it to be ineligible for consideration of award. Telephone directives for modification of the bid price shall not be permitted and will have no bearing on the submitted proposal in any manner.
- 4.7.2 Bidders submitting Bids that are late shall be notified as soon as practicable and the bid shall be returned.
- 4.7.3 A Bid may not be modified, withdrawn or canceled by the Bidder during a thirty (30) day period following the time and date designated for the receipt and opening of Bids, and Bidder so agrees in submitting their Bid. Bids shall be binding for 30 days after the date of the Bid opening.

ARTICLE 5: CONSIDERATION OF BIDS

5.1 OPENING/REJECTION OF BIDS

- 5.1.1 Unless otherwise stated, Bids received on time will be publicly opened and will be read aloud. An abstract of the Bids will be made available to Bidders.
- 5.1.2 The Agency shall have the right to reject any and all Bids. A Bid not accompanied by a required Bid Security or by other data required by the Bidding Documents, or a Bid which is in any way incomplete or irregular is subject to rejection.
- 5.1.3 If the Bids are rejected, it will be done within thirty (30) calendar day of the Bid opening.

5.2 COMPARISON OF BIDS

- 5.2.1 After the Bids have been opened and read, the bid prices will be compared and the result of such comparisons will be made available to the public. Comparisons of the Bids may be based on the Base Bid plus desired Alternates. The Agency shall have the right to accept Alternates in any order or combination.
- 5.2.2 The Agency reserves the right to waive technicalities, to reject any or all Bids, or any portion thereof, to advertise for new Bids, to proceed to do the Work otherwise, or to abandon the Work, if in the judgment of the Agency or its agent(s), it is in the best interest of the State.
- 5.2.3 An increase or decrease in the quantity for any item is not sufficient grounds for an increase or decrease in the Unit Price.
- The prices quoted are to be those for which the material will be furnished F.O.B. Job Site and include all charges that may be imposed during the period of the Contract.
- No qualifying letter or statements in or attached to the Bid, or separate discounts will be considered in determining the low Bid except as may be otherwise herein noted. Cash or separate discounts should be computed and incorporated into Unit Bid Price(s).

5.3 DISQUALIFICATION OF BIDDERS

5.3.1 An agency shall determine that each Bidder on any Public Works Contract is responsible before awarding the Contract. Factors to be considered in determining the responsibility of a Bidder include:

- A. The Bidder's financial, physical, personnel or other resources including Subcontracts:
- B. The Bidder's record of performance on past public or private construction projects, including, but not limited to, defaults and/or final adjudication or admission of violations of the Prevailing Wage Laws in Delaware or any other state;
- C. The Bidder's written safety plan;
- D. Whether the Bidder is qualified legally to contract with the States
- E. Whether the Bidder supplied all necessary information concerning its responsibility; and,
- F. Any other specific criteria for a particular procurement, which an agency may establish; provided however, that, the criteria be set forth in the Invitation to Bid and is otherwise in conformity with State and/or Federal law.
- 5.3.2 If an agency determines that a Bidder is nonresponsive and/or nonresponsible, the determination shall be in writing and set forth the basis for the determination. A copy of the determination shall be sent to the affected Bidder within five (5) working days of said determination.
- 5.3.3 In addition, any one or more of the following causes may be considered as sufficient for the disqualification of a Bidder and the rejection of their Bid or Bids.
- 5.3.3.1 More than one Bid for the same Contract from an individual, firm or corporation under the same or different names.
- 5.3.3.2 Evidence of collusion among Bidders.
- 5.3.3.3 Unsatisfactory performance record as evidenced by past experience.
- 5.3.3.4 If the Unit Prices are obviously unbalanced either in excess or below reasonable cost analysis values.
- 5.3.3.5 If there are any unauthorized additions, interlineation, conditional or alternate bids or irregularities of any kind which may tend to make the Bid incomplete, indefinite or ambiguous as to its meaning.
- 5.3.3.6 If the Bid is not accompanied by the required Bid Security and other data required by the Bidding Documents.
- 5.3.3.7 If any exceptions or qualifications of the Bid are noted on the Bid Form.
- 5.4 ACCEPTANCE OF BID AND AWARD OF CONTRACT
- 5.4.1 A formal Contract shall be executed with the successful Bidder within twenty (20) calendar days after the award of the Contract.

- Per Section 6962(d)(13) a., Title 29, Delaware Code, "The contracting agency shall award any public works contract within thirty (30) days of the bid opening to the lowest responsive and responsible Bidder, unless the Agency elects to award on the basis of best value, in which case the election to award on the basis of best value shall be stated in the Invitation To Bid."
- 5.4.3 Each Bid on any Public Works Contract must be deemed responsive by the Agency to be considered for award. A responsive Bid shall conform in all material respects to the requirements and criteria set forth in the Contract Documents and specifications.
- 5.4.4 The Agency shall have the right to accept Alternates in any order or combination, and to determine the low Bidder on the basis of the sum of the Base Bid, plus accepted Alternates.
- The successful Bidder shall execute a formal contract, submit the required Insurance Certificate, and furnish good and sufficient bonds, unless specifically waived in the General Requirements, in accordance with the General Requirement, within twenty (20) days of official notice of contract award. Bonds shall be for the benefit of the Agency with surety in the amount of 100% of the total contract award. Said Bonds shall be conditioned upon the faithful performance of the contract. Bonds shall remain in affect for period of one year after the date of substantial completion.
- If the successful Bidder fails to execute the required Contract and Bond, as aforesaid, within twenty (20) calendar days after the date of official Notice of the Award of the Contract, their Bid guaranty shall immediately be taken and become the property of the State for the benefit of the Agency as liquidated damages, and not as a forfeiture or as a penalty. Award will then be made to the next lowest qualified Bidder of the Work or readvertised, as the Agency may decide.
- Each bidder shall supply with its bid its taxpayer identification number (i.e., federal employer identification number or social security number) and a copy of its Delaware business license, and should the vendor be awarded a contract, such vendor shall provide to the agency the taxpayer identification license numbers of such subcontractors. Such numbers shall be provided on the later of the date on which such subcontractor is required to be identified or the time the contract is executed. The successful Bidder shall provide to the agency to which it is contracting, within 30 days of entering into such public works contract, copies of all Delaware Business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the Bidder entered the public works contract the Delaware Business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.
- 5.4.8 The Bid Security shall be returned to the successful Bidder upon the execution of the formal contract. The Bid Securities of unsuccessful bidders shall be returned within thirty (30) calendar days after the opening of the Bids.

ARTICLE 6: POST-BID INFORMATION

- 6.1 CONTRACTOR'S QUALIFICATION STATEMENT
- 6.1.1 Bidders to whom award of a Contract is under consideration shall, if requested by the Agency, submit a properly executed AIA Document A305, Contractor's Qualification Statement, unless such a statement has been previously required and submitted.

- 6.2 BUSINESS DESIGNATION FORM
- 6.2.1 Successful bidder shall be required to accurately complete an Office of Management and Budget Business Designation Form for Subcontractors.

ARTICLE 7: PERFORMANCE BOND AND PAYMENT BOND

- 7.1 BOND REQUIREMENTS
- 7.1.1 The cost of furnishing the required Bonds that are stipulated in the Bidding Documents shall be included in the Bid.
- 7.1.2 If the Bidder is required by the Agency to secure a bond from other than the Bidder's usual sources, changes in cost will be adjusted as provide in the Contract Documents.
- 7.1.3 The Performance and Payment Bond forms used shall be the standard OMB forms (attached).
- 7.2 TIME OF DELIVERY AND FORM OF BONDS
- 7.2.1 The bonds shall be dated on or after the date of the Contract.
- 7.2.2 The Bidder shall require the attorney-in-fact who executes the required bonds on behalf of the surety to affix a certified and current copy of the power of attorney.

ARTICLE 8: FORM OF AGREEMENT BETWEEN AGENCY AND CONTRACTOR

Unless otherwise required in the Bidding Documents, the Agreement for the Work will be written on AIA Document A101, Standard Form of Agreement Between Owner and Contractor Where the Basis of Payment is a Stipulated Sum.

END OF INSTRUCTIONS TO BIDDERS

Emily P. Bissell Hospital Main and 1912 Building Roof Repair, Restoration and Replacement Contract #MJ3514000010

BID FORM

For Bids Due:	April 16, 2015 at 2:30 P.M.	To:	State of Delaware Office of Management & Budget 540 South DuPont Highway Suite 1 Dover, DE 19901	AMC
Name of Bidder	::			
Delaware Busin (A copy of Bidd	ess License No.:_ er's Delaware Business License must	be attached	Taxpayer ID No.:	<u>) </u>
(Other License	Nos.):		\sim	
Phone No.: ()	F:		
REPLACE Replacemen perimeter an the installation	MENT: t of designated roofs with a two-ply cold d projection flashings will be installed al on of a white liquid applied coating. Des	process modifiong with new	led roof with a flood and gravel surface. New drains and edge metals. Restoration will include ill receive miscellaneous roof repairs.	v
)		
2. ALTERNA RESTORA Replacemen perimeter an	TE #1 - EMILY P. BISSELL HOSPI TION AND REPLACEMENT: at of designated roofs with a three-ply band projection flashings will be installed	uilt-up modifie along with ne	AND 1912 BUILDING ROOF REPAIR, d bituminous roof system with a flood and w drains and edge metals. Restoration will roofs will receive miscellaneous roof repair	gravel surface. New include roof repairs
\$In Words:				
()	PRICES: form to applicable project specification s	section. Refer	to the specifications for a complete descrip	tion of the following
a.	Submit a square foot price for repair of Base price on prepping and priming the (Labor and Material)	he existing dec		uded in the base bid. /S.F.

BID FORM 00 41 13-1

b.		replacement of existing metal decking, over 'nesting' new decking over existing.	and above, the 400	square feet included
		new decking over existing.	+\$	/S.F.
c.	Submit a square foot price for	repair of concrete decking, over and above t	the 200 square feet	included in the base
•	bid. Base price on ½ inch thick		200 Square 1000	
			+\$	/S.F.
d.	Submit a square foot price for a	replacement of existing wood decking, over	and above the 50 s	square feet
	included in the base bid. Base j	price on 5/8 inch CDX plywood.		
	(Labor and Material)		+\$	/S.F.
e.	Submit a square foot price for a	replacement of lightweight concrete insulati	on, over and above	the 1,200 square feet
		price on 3 1/2 inches of polyisocyanurate and		
	concrete decking.			
	(Labor and Material)		+\$	/S.F.
I/We acknowl	edge Addendums numbered	and the price(s) submitted include any	cost/schedule imp	act they may have.
This hid shall	remain valid and cannot be withd	rawn for sixty (60) days from the date of c	onening of bids an	d the undersioned shal
		Bid Security is attached to this Bid.	pening of olds, an	a the undersigned shar
TI O 1	11.1 (1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.	01:1	1 7 1 111	
The Owner sh	all have the right to reject any or al	Il bids, and to waive any informality or irreg	ularity in any bid r	eceived.
This bid is bas	sed upon work being accomplished	by the Sub-Contractors named on the list a	ttached to this bid.	
Should I/We b	be awarded this contract, I/We pled	ge to achieve substantial completion of all t	he work within	calendar days o
the Notice to 1				
The undersion	and raprocents and warrants that h	e has complied and shall comply with all	requirements of le	ocal state and nationa
		be violated in making or accepting this bid		
		s legal and firm; that he has not, directly		
participated in	any collusion, or otherwise taken	action in restraint of free competitive biddir	ıg.	
Upon receipt	of written notice of the acceptance	of this Bid, the Bidder shall, within twenty	(20) calendar days	execute the agreemen
		nds, and Insurance Certificates, required by		
I am / We are	an Individual / a Partnership / a Co	progration		
By	dual's / General Partner's / Corpora	Trading as		
(11101111	dual s/ General Partilet s/ Corpora	ate Name)		
(State o	of Corporation)			
Business Add	ress:			
Dusiness Add	1033.			
	16			
-	7,			
Witness:		By:		
(SEAL)		(Authorized Signature)	
SLAL		(Title)		
		Doto		

BID FORM 00 41 13-2

ATTACHMENTS

Sub-Contractor List Non-Collusion Statement Bid Security (Others as Required by Project Manuals)



Emily P. Bissell Hospital Main and 1912 Buildings Roof Repair, Restoration and Replacement Contract #MJ3514000010

BID FORM

SUBCONTRACTOR LIST

In accordance with Title 29, Chapter 6962 (d)(10)b <u>Delaware Code</u>, the following sub-contractor listing must accompany the bid submittal. The name, address and Subcontractors tax payer ID# or Delaware Business License# **must** be listed for each category where the bidder intends to use a sub-contractor to perform that category of work. In order to provide full disclosure and acceptance of the bid by the *Owner*, it is required that bidders list themselves as being the sub-contractor for all categories where he/she is qualified and intends to perform such work.

Subcontractor Category	Subcontractor	Address (City & State)	Subcontractors tax payer ID # or Delaware Business license #
1. Roofing Contractor			——————————————————————————————————————
2. Carpentry			
3. Mechanical (Drains)			
4. Sheet Metal			
5. Mechanical (Units)			
6. Masonry			

BID FORM 00 41 13-4

Emily P. Bissell Hospital Main and 1912 Buildings Roof Repair, Restoration and Replacement Contract #MJ3514000010

BID FORM

NON-COLLUSION STATEMENT

This is to certify that the undersigned bidder has neither directly nor indirectly, entered into any agreement, participated in any collusion or otherwise taken any action in restraint of free competitive bidding in connection with this proposal submitted this date to the Office of Management and Budget, Division of Facilities Management.

All the terms and conditions of the Emily P. Bissell Hospital Main and 1912 Building Roof Repair, Restoration and Replacement Project have been thoroughly examined and are understood.

NAME OF BIDDER:		,
AUTHORIZED REPRESENTATIVE (TYPED):		
AUTHORIZED REPRESENTATIVE (SIGNATURE):		
TITLE:		
ADDRESS OF BIDDER:	<u>S</u>	
E-MAIL:		
PHONE NUMBER:		
Sworn to and Subscribed before me this	day of	20
My Commission expires	. NOTARY PUBLIC	

THIS PAGE MUST BE SIGNED AND NOTARIZED FOR YOUR BID TO BE CONSIDERED.

BID FORM 00 41 13-5

STATE OF DELAWARE OFFICE OF MANAGEMENT AND BUDGET

BID BOND

TO ACCOMPANY PROPOSAL (Not necessary if security is used)

KNOW AL	L MEN BY THES	SE PRESE	NTS That:		
	of			in the County of	<u>) `</u>
and	I State of			as Principal, andin the County ofto do business in the State of	
	of			in the County of	
and State of	as S	Surety, leg	gally authorized	to do business in the State of	Delawar
(" State "), are held a	nd firmly unto the	e State in t	he sum of	percent not to exceed	
	Dollars (\$), or	percent not to exceed	
- C C1.: 1	Canton at Na			Dollars (\$)
on amount of bid on	Contract No		(in a aut	, to be paid to the State for the	e use an
well and truly to be	made we do his	nd ourselve	(<i>inseri</i>	State agency name) for which of our heirs, executors, administration	i payillei ratore an
successors, jointly a					rators, an
NOW THE	CONDITION OF	E THIS OI	DI ICATION IS	SUCH That if the above bonded	Duinaine
who has submitted t	o the			(insert State agency	name)
certain proposal to	enter into this co	ntract for t	the furnishing of	f certain material and/or services	within th
				ll well and truly enter into and ex	
				proved by the	
				et to be entered into within twenty	
				with the terms of said proposal	, then the
obligation shall be v	old or else to be a	and remain	in full force and	virtue.	
0 1 1 1:4	1 11	.1.41:	1 0	1	т 1,
Sealed withthousand and	seal and date	a this	day of	in the year of our	r Lora tw
.iiousaiiu aiiu	0	(20	_).		
SEALED, AND DE	LIVERED IN TH	IF.			
SEMELD, MIND DE	Presence of	LL			
•	Tresence of				
			-	Name of Bidder (Organization)	
				(2)	
Cor	porate	By:			
	Seal			Authorized Signature	
				_	
Attest			-		
Y				Title	
/					
				Name of Surety	
Witness		D			
Witness:		By:			
				Title	

BID BOND 00 43 13

STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR A101-2007

The contract to be utilized on this project shall be the "Standard Form of Agreement Between Owner and Contractor" AIA Document A101-2007.

SUPPLEMENT TO AGREEMENT BETWEEN OWNER AND CONTRACTOR A101-2007

The following supplements modify the "Standard Form of Agreement Between Owner and Contractor," AIA Document A101-2007. Where a portion of the Standard Form of Agreement is modified or deleted by the following, the unaltered portions of the Standard Form of Agreement shall remain in effect.

ARTICLE 5: PAYMENTS

- 5.1 PROGRESS PAYMENTS
- 5.1.3 Delete paragraph 5.1.3 in its entirety and replace with the following:

"Provided that a valid Application for Payment is received by the Architect that meets all requirements of the Contract, payment shall be made by the Owner not later than 30 days after the Owner receives the valid Application for Payment."

ARTICLE 6: DISPUTE RESOLUTION

6.2 BINDING DISPUTE RESOLUTION

Check Other – and add the following sentence:

"Any remedies available in law or in equity."

ARTICLE 8: MISCELLANEOUS PROVISIONS

8.2 Insert the following:

"Payments are due 30 days after receipt of a valid Application for Payment. After that 30 day period, interest may be charged at the rate of 1% per month not to exceed 12% per annum."

8.5 Delete paragraph 8.5 in its entirety and replace with the following:

"The Contractor's representative shall not be changed without ten days written notice to the Owner."

END OF SUPPLEMENT TO AGREEMENT BETWEEN OWNER AND CONTRACTOR

STATE OF DELAWARE OFFICE OF MANAGEMENT AND BUDGET

PERFORMANCE BOND

	Bond Number:	
KNOW ALL PERSONS BY THESE PRESENTS, that w	ve,	, as principal
("Principal"), and, a,	c	corporation, legally
(" Principal "), and, a, a authorized to do business in the State of Delaware, as su	rety ("Surety"), are held	d and firmly bound
unto the (\$	("Owner") (<i>ii</i>	nsert State agency
name), in the amount of(\$), to be paid to	Owner, for which
payment well and truly to be made, we do bind oursel	ves, our and each and	every of our heirs,
executors, administrations, successors and assigns, join	ntly and severally, for	and in the whole,
firmly by these presents.		ŕ
Sealed with our seals and dated this day of _	. 20 .	
		
NOW THE CONDITION OF THIS OBLIGATION IS	SUCH, that if Princi	pal, who has been
awarded by Owner that certain contract known as	s Contract No.	dated the
day of, 20 (the "Contract"), which Contract is inco	orporated herein by
reference, shall well and truly provide and furnish all may		
the work required under and pursuant to the terms and c		-
Documents (as defined in the Contract) or any changes		
provided, shall make good and reimburse Owner sufficient		
Contract that Owner may sustain by reason of any failu	1 2	1 0
shall also indemnify and save harmless Owner from all		1 /
or by reason of the performance of the Contract and for		
this obligation shall be void, otherwise to be and remain i		are contract, then
this confection shall be void, build wise to be and remain i	in fair force and effect.	

Surety, for value received, hereby stipulates and agrees, if requested to do so by **Owner**, to fully perform and complete the work to be performed under the Contract pursuant to the terms, conditions and covenants thereof, if for any cause **Principal** fails or neglects to so fully perform and complete such work.

Surety, for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of **Surety** and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition or change in or to the Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any work to be performed or any monies due or to become due thereunder; and **Surety** hereby waives notice of any and all such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers and hereby expressly stipulates and agrees that any and all

Performance Bond 00 61 13.13

STATE OF DELAWARE Contract #MJ3514000010 The Emily P. Bissell Hospital DIVISION OF FACILITIES MANAGEMENT Department of Health and Social Services Roof Repair, Restoration & Replacement Project

things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to **Surety** as though done or omitted to be done by or in relation to **Principal**.

Surety hereby stipulates and agrees that no modifications, omissions or additions in or to the terms of the Contract shall in any way whatsoever affect the obligation of **Surety** and its bond.

Any proceeding, legal or equitable, under this Bond may be brought in any court of competent jurisdiction in the State of Delaware. Notices to **Surety** or Contractor may be mailed or delivered to them at their respective addresses shown below.

IN WITNESS WHEREOF, **Principal** and **Surety** have hereunto set their hand and seals, and such of them as are corporations have caused their corporate seal to be hereto affixed and these presents to be signed by their duly authorized officers, the day and year first above written.

	PRINCIPAL	
	Name:	
Witness or Attest: Address:		
	By:	(SEAL)
Name:	Name: Title:	
(Corporate Seal)	Title.	
	SURETY	
, &	Name:	
Witness or Attest: Address:		
	By:	(SEAL)
Name:	Name:	
(Corporate Seal)	Title:	
, V		

Performance Bond 00 61 13.13

DIVISION OF FACILITIES MANAGEMENT
Department of Health and Social Services
Roof Repair, Restoration & Replacement Project

STATE OF DELAWARE OFFICE OF MANAGEMENT AND BUDGET

PAYMENT BOND

Bond Number:
KNOW ALL PERSONS BY THESE PRESENTS, that we,as principal
"Principal"), and, a corporation, legally uthorized to do business in the State of Delaware, as surety ("Surety"), are held and firmly bound
nnto the ("Owner") (insert State agency name), in the amount of (\$
payment well and truly to be made, we do bind ourselves, our and each and every of our heirs.
executors, administrations, successors and assigns, jointly and severally, for and in the whole firmly
by these presents.
Sealed with our seals and dated this day of, 20
Sealed with our seals and dated this day of, 20
NOW THE CONDITION OF THIS OBLIGATION IS SUCH, that if Principal, who has been
warded by Owner that certain contract known as Contract Nodated the
lay of, 20 (the "Contract"), which Contract is incorporated herein by reference,
hall well and truly pay all and every person furnishing materials or performing labor or service in
nd about the performance of the work under the Contract, all and every sums of money due him,
er, them or any of them, for all such materials, labor and service for which Principal is liable
hall make good and reimburse Owner sufficient funds to pay such costs in the completion of the
Contract as Owner may sustain by reason of any failure or default on the part of Principal, and
hall also indemnify and save harmless Owner from all costs, damages and expenses arising out of
or by reason of the performance of the Contract and for as long as provided by the Contract; then
his obligation shall be void, otherwise to be and remain in full force and effect.

Surety, for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of **Surety** and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition or change in or to the Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any work to be performed or any monies due or to become due thereunder; and **Surety** hereby waives notice of any and all such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to **Surety** as though done or omitted to be done by or in relation to **Principal**.

Payment Bond 00 61 13.16

STATE OF DELAWARE Contract #MJ3514000010 The Emily P. Bissell Hospital DIVISION OF FACILITIES MANAGEMENT Department of Health and Social Services Roof Repair, Restoration & Replacement Project

Surety hereby stipulates and agrees that no modifications, omission or additions in or to the terms of the Contract shall in any way whatsoever affect the obligation of **Surety** and its bond.

Any proceeding, legal or equitable, under this Bond may be brought in any court of competent jurisdiction in the State of Delaware. Notices to **Surety** or Contractor may be mailed or delivered to them at their respective addresses shown below.

IN WITNESS WHEREOF, **Principal** and **Surety** have hereunto set their hand and seals, and such of them as are corporations have caused their corporate seal to be hereto affixed and these presents to be signed by their duly authorized officers, the day and year first above written.

	PRINCIPAL	V
	Name:	_
Witness or Attest: Address:		
	By:	(SEAL)
Name:	Name: Title	
(Corporate Seal)	5	
	SURETY	
	Name:	
Witness or Attest: Address:		
,	By:	(SEAL)
Name: (Corporate Seal)	Name: Title:	

Payment Bond 00 61 13.16

APPLICATION AND CERTIFICATE FOR PAYMENT

The enclosed are the Application and Certificate for Payment (G702) and the Continuation Sheet (G703) Forms that will be used for all requests for payments. The Contractor is required to purchase these forms through the American Institute of Architect.

CANNOT BE USED FOR BIDDING

GENERAL CONDITIONS

TO THE

CONTRACT

The General Conditions of this Contract are as stated in the American Institute of Architects Document AIA A201 (2007 Edition) entitled <u>General Conditions of the Contract for Construction</u> and is part of this project manual as if herein written in full.

SUPPLEMENTARY GENERAL CONDITIONS A201-2007

The following supplements modify the "General Conditions of the Contract for Construction," AIA Document A201-2007. Where a portion of the General Conditions is modified or deleted by the Supplementary Conditions, the unaltered portions of the General Conditions shall remain in effect.

TABLE OF ARTICLES

- GENERAL PROVISIONS
- 2. OWNER
- CONTRACTOR
- 4. ADMINISTRATION OF THE CONTRACT
- 5. SUBCONTRACTORS
- 6. CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS
- CHANGES IN THE WORK
- 8. TIME
- 9. PAYMENTS AND COMPLETION
- 10. PROTECTION OF PERSONS AND PROPERTY
- 11. INSURANCE AND BONDS
- 12. UNCOVERING AND CORRECTION OF WORK
- 13. MISCELLANEOUS PROVISIONS
- 14. TERMINATION OR SUSPENSION OF THE CONTRACT

ARTICLE 1: GENERAL PROVISIONS

1.1 BASIC DEFINITIONS

1.1.1 THE CONTRACT DOCUMENTS

Delete the last sentence in its entirety and replace with the following:

"The Contract Documents also include Advertisement for Bid, Instructions to Bidder sample forms, the Bid Form, the Contractor's completed Bid and the Award Letter."

Add the following Paragraph:

1.1.1.1 In the event of conflict or discrepancies among the Contract Documents, the Documents prepared by the State of Delaware, Division of Facilities Management shall take precedence over all other documents.

1.2 CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

Add the following Paragraphs:

- 1.2.4 In the case of an inconsistency between the Drawings and the Specifications, or within either document not clarified by addendum, the better quality or greater quantity of work shall be provided in accordance with the Architect's interpretation.
- 1.2.5 The word "PROVIDE" as used in the Contract Documents shall mean "FURNISH AND INSTALL" and shall include, without limitation, all labor, materials, equipment, transportation, services and other items required to complete the Work.
- 1.2.6 The word "PRODUCT" as used in the Contract Documents means all materials, systems and equipment.
- 1.5 OWNERSHIP AND USE OF DRAWINGS, SPECIFICATIONS AND OTHER INSTRUMENTS OF SERVICE

Delete Paragraph 1.5.1 in its entirety and replace with the following:

"All pre-design studies, drawings, specifications and other documents, including those in electronic form, prepared by the Architect under this Agreement are, and shall remain, the property of the Owner whether the Project for which they are made is executed or not. Such documents may be used by the Owner to construct one or more like Projects without the approval of, or additional compensation to, the Architect. The Contractor, Subcontractors, Sub-subcontractors and Material or Equipment Suppliers are authorized to use and reproduce applicable portions of the Drawings, Specifications and other documents prepared by the Architect and the Architect's consultants appropriate to and for use in the execution of their Work under the Contract Documents. They are not to be used by the Contractor or any Subcontractor, Sub-subcontractor or Material and Equipment Supplier on other Projects or for additions to this Project outside the scope of the Work without the specific written consent of the Owner, Architect and Architect's consultants.

The Architect shall not be liable for injury or damage resulting from the re-use of drawings and specifications if the Architect is not involved in the re-use Project. Prior to re-use of construction documents for a Project in which the Architect is not also involved, the Owner will remove from such documents all identification of the original Architect, including name, address and professional seal or stamp."

Delete Paragraph 1.5.2 in its entirety.

ARTICLE 2: OWNER

2.2 INFORMATION AND SERVICES REQUIRED OF THE OWNER

To Subparagraph 2.2.3 – Add the following sentence:

"The Contractor, at their expense shall bear the costs to accurately identify the location of all underground utilities in the area of their excavation and shall bear all cost for any repairs required, out of failure to accurately identify said utilities."

Delete Subparagraph 2.2.5 in its entirety and substitute the following:

2.2.5 The Contractor shall be furnished free of charge up to five (5) sets of the Drawings and Project Manuals. Additional sets will be furnished at the cost of reproduction, postage and handling.

ARTICLE 3: CONTRACTOR

3.2 REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR

Amend Paragraph 3.2.2 to state that any errors, inconsistencies or omissions discovered shall be reported to the Architect and Owner immediately.

Delete the third sentence in Paragraph 3.2.3.

3.3 SUPERVISION AND CONSTRUCTION PROCEDURES

Add the following Paragraphs:

The Contractor shall immediately remove from the Work, whenever requested to do so by the Owner, any person who is considered by the Owner or Architect to be incompetent or disposed to be so disorderly, or who for any reason is not satisfactory to the Owner, and that person shall not again be employed on the Work without the consent of the Owner or the Architect.

The Contractor must provide suitable storage facilities at the Site for the proper protection and safe storage of their materials. Consult the Owner and the Architect before storing any materials.

3.3.5 When any room is used as a shop, storeroom, office, etc., by the Contractor or Subcontractor(s) during the construction of the Work, the Contractor making use of these areas will be held responsible for any repairs, patching or cleaning arising from such use.

3.4 LABOR AND MATERIALS

Add the Following Paragraphs:

- 3.4.4 Before starting the Work, each Contractor shall carefully examine all preparatory Work that has been executed to receive their Work. Check carefully, by whatever means are required, to insure that its Work and adjacent, related Work, will finish to proper contours, planes and levels. Promptly notify the General Contractor/Construction Manager of any defects or imperfections in preparatory Work which will in any way affect satisfactory completion of its Work. Absence of such notification will be construed as an acceptance of preparatory Work and later claims of defects will not be recognized.
- Under no circumstances shall the Contractor's Work proceed prior to preparatory Work proceed prior to preparatory Work having been completely cured, dried and/or otherwise made satisfactory to receive this Work. Responsibility for timely installation of all materials rests solely with the Contractor responsible for that Work, who shall maintain coordination at all times.

3.5 WARRANTY

Add the following Paragraphs:

- 3.5.1 The Contractor will guarantee all materials and workmanship against original defects, except injury from proper and usual wear when used for the purpose intended, for two years after Acceptance by the Owner, and will maintain all items in perfect condition during the period of guarantee.
- 3.5.2 Defects appearing during the period of guarantee will be made good by the Contractor at his expense upon demand of the Owner, it being required that all work will be in perfect condition when the period of guarantee will have elapsed.
- 3.5.3 In addition to the General Guarantee there are other guarantees required for certain items for different periods of time than the two years as above, and are particularly so stated in that part of the specifications referring to same. The said quarantees will commence at the same time as the General Guarantee.
- If the Contractor fails to remedy any failure, defect or damage within a reasonable time after receipt of notice, the Owner will have the right to replace, repair, or otherwise remedy the failure, defect or damage at the Contractor's expense.

DOCUMENTS AND SAMPLES AT THE SITE

Add the following Paragraphs:

- 3.11.1 During the course of the Work, the Contractor shall maintain a record set of drawings on which the Contractor shall mark the actual physical location of all piping, valves, equipment, conduit, outlets, access panels, controls, actuators, including all appurtenances that will be concealed once construction is complete, etc., including all invert elevations.
- 3.11.2 At the completion of the project, the Contractor shall obtain a set of reproducible drawings from the Architect, and neatly transfer all information outlined in 3.11.1 to provide a complete record of the as-built conditions.

- 3.11.3 The Contractor shall provide two (2) prints of the as-built conditions, along with the reproducible drawings themselves, to the Owner and one (1) set to the Architect. In addition, attach one complete set to each of the Operating and Maintenance Instructions/Manuals.
- In the second sentence of the paragraph, insert "indemnify" between "shall" and "hold".

ARTICLE 4: ADMINISTRATION OF THE CONTRACT

4.2 ADMINISTRATION OF THE CONTRACT

Delete the first sentence of Paragraph 4.2.7 and replace with the following

The Architect will review and approve or take other appropriate action upon the Contractor's submittals such as Shop Drawings, Product Data and Samples for the purpose of checking for conformance with the Contract Documents.

Delete the second sentence of Paragraph 4.2.7 and replace with the following:

The Architect's action will be taken with such reasonable promptness as to cause no delay in the Work in the activities of the Owner, Contractor or separate Contractors, while allowing sufficient time in the Owner's professional judgment to permit adequate review.

Add the following Paragraph:

4.2.10.1 There will be no full-time project representative provided by the Owner or Architect on this project.

Add to Paragraph 4.2.13 "and in compliance with all local requirements." to the end of the sentence

ARTICLE 5: SUBCONTRACTORS

5.2 AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK

Delete Paragraph 5.2.3 in its entirety and replace with the following:

If the Owner or Architect has reasonable objection to a person or entity proposed by the Contractor, the Contractor shall propose another to whom the Owner or Architect has no reasonable objection, subject to the statutory requirements of 29 <u>Delaware Code</u> § 6962(d)(10)b.3 and 4.

ARTICLE 6: CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

6.1 OWNER'S RIGHT TO PERFORM CONSTRUCTION AND TO AWARD SEPARATE CONTRACTS

Delete Paragraph 6.1.4 in its entirety.

- 6.2 MUTUAL RESPONSIBILITY
 - 6.2.3 In the second sentence, strike the word "shall" and insert the word "may".

ARTICLE 7: CHANGES IN THE WORK

(SEE ARTICLE 7: CHANGES IN WORK IN THE GENERAL REQUIREMENTS)

ARTICLE 8: TIME

8.2 PROGRESS AND COMPLETION

Add the following Paragraphs:

- 8.2.1.1 Refer to Specification Section SUMMARY OF WORK for Contract time requirements.
- 8.2.4 If the Work falls behind the Progress Schedule as submitted by the Contractor, the Contractor shall employ additional labor and/or equipment necessary to bring the Work into compliance with the Progress Schedule at no additional cost to the Owner.

8.3 DELAYS AND EXTENSION OF TIME

8.3.1 Strike "arbitration" and insert "remedies at law or in equity".

Add the following Paragraph:

8.3.2.1 The Contractor shall update the status of the suspension, delay, or interruption of the Work with each Application for Payment. (The Contractor shall report the termination of such cause immediately upon the termination thereof.) Failure to comply with this procedure shall constitute a waiver for any claim for adjustment of time or price based upon said cause.

Delete Paragraph 8.3,3 in its entirety and replace with the following:

8.3.3 Except in the case of a suspension of the Work directed by the Owner, an extension of time under the provisions of Paragraph 8.3.1 shall be the Contractor's sole remedy in the progress of the Work and there shall be no payment or compensation to the Contractor for any expense or damage resulting from the delay.

Add the following Paragraph:

By permitting the Contractor to work after the expired time for completion of the project, the Owner does not waive their rights under the Contract.

ARTICLE 9: PAYMENTS AND COMPLETION

SCHEDULE OF VALUES

Add the following Paragraphs:

- 9.2.1 The Schedule of Values shall be submitted using AIA Document G702, Continuation Sheet to G703.
- 9.2.2 The Schedule of Values is to include a line item for Project Closeout Document Submittal. The value of this item is to be no less than 1% of the initial contract amount.

9.3 APPLICATIONS FOR PAYMENT

Add the following Paragraph:

9.3.1.3 Application for Payment shall be submitted on AIA Document G702 "Application and Certificate for Payment", supported by AIA Document G703 "Continuation Sheet". Said Applications shall be fully executed and notarized.

Add the following Paragraphs:

- 9.3.4 Until Closeout Documents have been received and outstanding items completed the Owner will pay 95% (ninety-five percent) of the amount due the Contractor on account of progress payments.
- 9.3.5 The Contractor shall provide a current and updated Progress Schedule to the Architect with each Application for Payment. Failure to provide Schedule will be just cause for rejection of Application for Payment.

9.5 DECISIONS TO WITHHOLD CERTIFICATION

Add the following to 9.5.1:

- .8 failure to provide a current Progress Schedule;
- .9 a lien or attachment is filed;
- .10 failure to comply with mandatory requirements for maintaining Record Documents.

9.6 PROGRESS PAYMENTS

Delete Paragraph 9.6.1 in its entirety and replace with the following:

9.6.1 After the Architect has approved and issued a Certificate for Payment, payment shall be made by the Owner within 30 days after Owner's receipt of the Certificate for Payment.

9.7 FAILURE OF PAYMENT

In first sentence, strike "seven" and insert "thirty (30)". Also strike "binding dispute resolution" and insert "remedies at law or in equity".

9.8 SUBSTANTIAL COMPLETION

To Subparagraph 9.8.3 - Add the following sentence:

"If the Architect is required to make more than 2 inspections of the same portion of work, the Contractor shall be responsible for all costs associated with subsequent inspections including but not limited to any Architect's fees."

9.8.5 In the second sentence, strike "shall" and insert "may".

ARTICLE 10: PROTECTION OF PERSONS AND PROPERTY

10.1 SAFETY PRECAUTIONS AND PROGRAMS

Add the following Paragraphs:

- 10.1.1.1.1 Each Contractor shall develop a safety program in accordance with the Occupational Safety and Health Act of 1970. A copy of said plan shall be furnished to the Owner and Architect prior to the commencement of that Contractor's Work.
- 10.1.2 Each Contractor shall appoint a Safety Representative. Safety Representatives shall be someone who is on site on a full time basis. If deemed necessary by the Owner or Architect, Contractor Safety meetings will be scheduled. The attendance of all Safety Representatives will be required. Minutes will be recorded of said meetings by the Contractor and will be distributed to all parties as well as posted in all job offices/trailers etc.

10.2 SAFETY OF PERSONS AND PROPERTY

Add the following Paragraph:

As required in the Hazardous Chemical Act of June 1984, all vendors supplying any material that may be defined as hazardous must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it has a caution warning on the label relating to a potential physical or health hazard, if it is known to be present in the work place, and if employees may be exposed under normal conditions or in foreseeable emergency situations. Material Safety Data Sheets shall be provided directly to the Owner, along with the shipping slips that include those products.

10.3 HAZARDOUS MATERIALS

Delete Paragraph 10.3.3 in its entirety.

Delete Paragraph 10.3.6 in its entirety.

ARTICLE 11: INSURANCE AND BONDS

11.1 CONTRACTOR'S LIABILITY INSURANCE

Strike "the Owner" immediately following "(1)" and strike "and (2) the Owner as an additional insured for claims caused in whole or in part by the Contractor's negligent acts or omissions during the Contractor's completed operations."

OWNER'S LIABILITY INSURANCE

Delete Paragraph 11.2 in its entirety.

11.3 PROPERTY INSURANCE

Delete Paragraph 11.3 in its entirety and replace with the following:

The State will not provide Builder's All Risk Insurance for the Project. The Contractor and all Subcontractors shall provide property coverage for their tools and equipment, as necessary. Any mandatory deductible required by the Contractor's Insurance shall be the responsibility of the Contractor.

11.4 PERFORMANCE BOND AND PAYMENT BOND

11.4.1 Add the following sentence: "The bonds will conform to those forms approved by the Office of Management and Budget."

ARTICLE 12: UNCOVERING AND CORRECTION OF WORK

12.2.2 AFTER SUBSTANTIAL COMPLETION

Add the following Paragraph:

- 12.2.2.1.1 At any time during the progress of the Work, or in any case where the nature of the defects will be such that it is not expedient to have corrected, the Owner, at its option, will have the right to deduct such sum, or sums, of money from the amount of the Contract as it considers justified to adjust the difference in value between the defective work and that required under contract including any damage to the structure.
- 12.2.2.1 Strike "one" and insert "two".
- 12.2.2.2 Strike "one" and insert "two".
- 12.2.2.3 Strike "one" and insert "two".
- 12.2.5 In second sentence, strike "one" and insert "two".

ARTICLE 13: MISCELLANEOUS PROVISIONS

13.1 GOVERNING LAW

Strike "except that, if the parties have selected arbitration as the method of binding dispute resolution, the Federal Arbitration Act shall govern Section 15.4."

3.6 INTEREST

Strike "the date payment is due at such rate as the parties may agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located." Insert "30 days of presentment of the authorized Certificate of Payment at the annual rate of 12% or 1% per month.

13.7 TIME LIMITS ON CLAIMS

Strike the last sentence.

Add the following Paragraph:

13.8 CONFLICTS WITH FEDERAL STATUTES OR REGULATIONS

13.8.1 If any provision, specifications or requirement of the Contract Documents conflict or is inconsistent with any statute, law or regulation of the government of the United State of America, the Contractor shall notify the Architect and Owner immediately upon discovery.

ARTICLE 14: TERMINATION OR SUSPENSION OF THE CONTRACT

14.4 TERMINATION BY THE OWNER FOR CONVENIENCE

Delete Paragraph 14.4.3 in its entirety and replace with the following:

14.4.3 In case of such termination for the Owner's convenience, the Contractor shall be entitled to receive payment for Work executed, and cost incurred by reason of such termination along with reasonable overhead.

ARTICLE 15: CLAIMS AND DISPUTES

- 15.1.2 Throughout the Paragraph strike "21" and insert "45"
- 15.1.6 CLAIMS FOR CONSEQUENTIAL DAMAGES

Delete Paragraph 15.1.6 in its entirety.

15.2 INITIAL DECISION

Delete Paragraph 15.2.5 in its entirety and replace with the following:

15.2.5 The Architect will approve or reject Claims by written decision, which shall state the reasons therefore and shall notify the parties of any change in the Contract Sum or Contract Time or both. The approval or rejection of a Claim by the Architect shall be subject to mediation and other remedies at law or in equity.

Delete Paragraph 15.2.6 and its subparagraphs in their entirety.

15.3 MEDIATION

Strike "binding dispute resolution" and insert "any or all remedies at law or in equity".

In the first sentence, delete "administered by the American Arbitration Association in accordance with its Construction Industry Mediation Procedure in effect on the date of the Agreement," Strike "binding dispute resolution" and insert "remedies at law and in equity".

15.4 ARBITRATION

Delete Paragraph 15.4 and its sub-sections in its entirety.

END OF SUPPLEMENTARY GENERAL CONDITIONS

SECTION 00 73 46

WAGE DETERMINATION SCHEDULE

- 1 GENERAL
- 1.1 DOCUMENT INCLUDES
 - A. State of Delaware Prevailing Wage Rates.
- 1.2 RELATED DOCUMENTS
 - A. General and Supplementary Conditions of the Contract.
- 2 PRODUCTS Not Used.
- 3 EXECUTION
- 3.1 WAGE RATES
 - A. See attached Prevailing Wage Rate predetermination for rates. This regulation and the general State of Delaware prevailing minimum wage rates, as adopted by the Department of Labor on April 3, 1992, as determined by the Division of Industrial Affairs, Office of Labor Law Enforcement, which shall be paid for each craft or classification of all workers needed to perform the Contract during the anticipated term therefore in the locality in which public work is performed, are made part of this Specification.

END OF DOCUMENT

STATE OF DELAWARE DEPARTMENT OF LABOR DIVISION OF INDUSTRIAL AFFAIRS OFFICE OF LABOR LAW ENFORCEMENT PHONE: (302) 451-3423

Mailing Address: 225 CORPORATE BOULEVARD SUITE 104 NEWARK, DE 19702 Located at: 225 CORPORATE BOULEVARD SUITE 104 NEWARK, DE 19702

PREVAILING WAGES FOR BUILDING CONSTRUCTION EFFECTIVE MARCH 13, 2015

CLASSIFICATION	NEW CASTLE	KENT	SUSSEX
ASBESTOS WORKERS	21.87	26.94	39.20
BOILERMAKERS	39.67	33.22	48,83
BRICKLAYERS	49.39	49.39	49.39
CARPENTERS	51.86	51.86	41.22
CEMENT FINISHERS	69.27	29.11	21,20
ELECTRICAL LINE WORKERS	43.49	37.29	28.44
ELECTRICIANS	63.60	63 60	37.29
ELEVATOR CONSTRUCTORS	80.31	40.93	30.55
GLAZIERS	67.35	67.35	20.15
INSULATORS	53.38	53.38	53.38
IRON WORKERS	60.12	60.12	60.12
LABORERS	40.95	40.95	40.95
MILLWRIGHTS	47.47	65.23	51.80
PAINTERS	43.04	44.94	44.94
PILEDRIVERS	71.17	37.64	30.45
PLASTERERS	21.60	28.55	17.50
PLUMBERS/PIPEFITTERS/STEAMFITTERS	62.20	36.66	54.49
POWER EQUIPMENT OPERATORS	43.88	58.31	24.13
ROOFERS-COMPOSITION	21.82	20.45	17.63
ROOFERS-SHINGLE/SLATE/TILE	17.59	13.72	14.10
SHEET METAL WORKERS	47.05	64.16	64.16
SOFT FLOOR LAYERS	48.57	48.57	48.57
SPRINKLER FITTERS	53.52	53.52	53.52
TERRAZZO/MARBLE/TILE FNRS	54.11	52.50	45.45
TERRAZZO/MARBLE/TILE/STRS	62.13	60.28	52.63
TRUCK DRIVERS	24.43	26.64	20.03

CERTIFIED:

BY: ADMENISTRATOR, OFFICE OF LABOR LAW ENFORCEMENT

NOTE:

THESE RATES ARE PROMULGATED AND ENFORCED PURSUANT TO THE PREVAILING WAGE REGULATIONS ADOPTED BY THE DEPARTMENT OF LABOR ON APRIL 3, 1992.

CLASSIFICATIONS OF WORKERS ARE DETERMINED BY THE DEPARTMENT OF LABOR. FOR ASSISTANCE IN CLASSIFYING WORKERS, OR FOR A COPY OF THE REGULATIONS OR CLASSIFICATIONS, PHONE (302) 451-3423.

NON-REGISTERED APPRENTICES MUST BE PAID THE MECHANIC'S RATE.

PROJECT: MJ3514000010 Emily Bissell Hospital-Roof Repair, Restoration, and Replacement, New Castle County

GENERAL REQUIREMENTS

TABLE OF ARTICLES

- GENERAL PROVISIONS
- 2. OWNER
- CONTRACTOR
- 4. ADMINISTRATION OF THE CONTRACT
- 5. SUBCONTRACTORS
- 6. CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS
- 7. CHANGES IN THE WORK
- 8. TIME
- 9. PAYMENTS AND COMPLETION
- 10. PROTECTION OF PERSONS AND PROPERTY
- 11. INSURANCE AND BONDS
- 12. UNCOVERING AND CORRECTION OF WORK
- 13. MISCELLANEOUS PROVISIONS
- 14. TERMINATION OR SUSPENSION OF THE CONTRACT

ARTICLE 1: GENERAL

1.1 CONTRACT DOCUMENTS

- 1.1.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary and what is required by one shall be as binding as if required by all. Performance by the Contractor shall be required to an extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the intended results.
- 1.1.2 Work including material purchases shall not begin until the Contractor is in receipt of a bonafide State of Delaware Purchase Order. Any work performed or material purchases prior to the issuance of the Purchase Order is done at the Contractor's own risk and cost.
- 1.2 EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS
- 1.2.1 For Public Works Projects financed in whole or in part by state appropriation the Contractor agrees that during the performance of this contract:
 - 1. The Contractor will not discriminate against any employee or applicant for employment because of race, creed, sex, color, sexual orientation, gender identity or national origin. The Contractor will take positive steps to ensure that applicants are employed and that employees are treated during employment without regard to their race, creed, sex, color, sexual orientation, gender identity or national origin. Such action shall include but not be limited to, the following: employment, upgrading, demotion or transfer, recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.
 - 2. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, sex, color, sexual orientation, gender identity or national origin."

ARTICLE 2: OWNER

(NO ADDITIONAL GENERAL REQUIREMENTS - SEE SUPPLEMENTARY GENERAL CONDITIONS)

ARTICLE 3: CONTRACTOR

Schedule of Values: The successful Bidder shall within twenty (20) days after receiving notice to proceed with the work, furnish to the Owner a complete schedule of values on the various items comprising the work.

Subcontracts: Upon approval of Subcontractors, the Contractor shall award their Subcontracts as soon as possible after the signing of their own contract and see that all material, their own and those of their Subcontractors, are promptly ordered so that the work will not be delayed by failure of materials to arrive on time.

- 3.3 Before commencing any work or construction, the General Contractor is to consult with the Owner as to matters in connection with access to the site and the allocation of Ground Areas for the various features of hauling, storage, etc.
- 3.4 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for and have control over construction means, methods, techniques, sequences and procedures and for coordinating all portions of the Work under the Contract, unless the Contract Documents give other specific instructions.
- 3.5 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Contract. The Contractor shall not permit employment of unfit persons or persons not skilled in tasks assigned to them.
- The Contractor warrants to the Owner that materials and equipment furnished will be new and of good quality, unless otherwise permitted, and that the work will be free from defects and in conformance with the Contract Documents. Work not conforming to these requirements, including substitutions not properly approved, may be considered defective. If required by the Owner, the Contractor shall furnish evidence as to the kind and quality of materials and equipment provided.
- 3.7 Unless otherwise provided, the Contractor shall pay all sales, consumer, use and other similar taxes, and shall secure and pay for required permits, fees, licenses, and inspections necessary for proper execution of the Work.
- The Contractor shall comply with and give notices required by laws, ordinances, rules, regulations, and lawful orders of public authorities bearing on performance of the Work. The Contractor shall promptly notify the Owner if the Drawings and Specifications are observed to be at variance therewith.
- 3.9 The Contractor shall be responsible to the Owner for the acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons performing portions of the Work under contract with the Contractor.
- 3.10 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under the Contract. At completion of the Work the Contractor shall remove from and about the Project all waste materials, rubbish, the Contractor's tools, construction equipment, machinery and surplus materials. The Contractor shall be responsible for returning all damaged areas to their original conditions.

3.11 STATE LICENSE AND TAX REQUIREMENTS

- Each Contractor and Subcontractor shall be licensed to do business in the State of Delaware and shall pay all fees and taxes due under State laws. In conformance with Section 2503, Chapter 25, Title 30, <u>Delaware Code</u>, "the Contractor shall furnish the Delaware Department of Finance within ten (10) days after entering into any contract with a contractor or subcontractor not a resident of this State, a statement of total value of such contract or contracts together with the names and addresses of the contracting parties."
- 3.12. The Contractor shall comply with all requirements set forth in Section 6962, Chapter 69, Title 29 of the Delaware Code.

ARTICLE 4: ADMINISTRATION OF THE CONTRACT

- 4.1 CONTRACT SURETY
- 4.1.1 PERFORMANCE BOND AND LABOR AND MATERIAL PAYMENT BOND
- 4.1.2 All bonds will be required as follows unless specifically waived elsewhere in the Bidding Documents.
- 4.1.3 Contents of Performance Bonds The bond shall be in the form approved by the Office of Management and Budget. The bond shall be conditioned upon the faithful compliance and performance by the successful bidder of each and every term and condition of the contract and the proposal, plans, specifications, and bid documents thereof. Each term and condition shall be met at the time and in the manner prescribed by the Contract, Bid documents and the specifications, including the payment in full to every person furnishing materiel or performing labor in the performance of the Contract, of all sums of money due the person for such labor and materiel. (The bond shall also contain the successful bidder's guarantee to indemnify and save harmless the State and the agency from all costs, damages and expenses growing out of or by reason of the Contract in accordance with the Contract.)
- 4.1.4 Invoking a Performance Bond The agency may, when it considers that the interest of the State so require, cause judgement to be confessed upon the bond.
- 4.1.5 Within twenty (20) days after the date of notice of award of contract, the Bidder to whom the award is made shall furnish a Performance Bond and Labor and Material Payment Bond, each equal to the full amount of the Contract price to guarantee the faithful performance of all terms, covenants and conditions of the same. The bonds are to be issued by an acceptable Bonding Company licensed to do business in the State of Delaware and shall be issued in duplicate.
- 4.1.6 Performance and Payment Bonds shall be maintained in full force (warranty bond) for a period of two (2) years after the date of the Certificate for Final Payment. The Performance Bond shall guarantee the satisfactory completion of the Project and that the Contractor will make good any faults or defects in his work which may develop during the period of said guarantees as a result of improper or defective workmanship, material or apparatus, whether furnished by themselves or their Sub-Contractors. The Payment Bond shall guarantee that the Contractor shall pay in full all persons, firms or corporations who furnish labor or material or both labor and material for, or on account of, the work included herein. The bonds shall be paid for by this Contractor. The Owner shall have the right to demand that the proof parties signing the bonds are duly authorized to do so.
- 4.2 FAILURE TO COMPLY WITH CONTRACT
 - If any firm entering into a contract with the State, or Agency that neglects or refuses to perform or fails to comply with the terms thereof, the Agency which signed the Contract may terminate the Contract and proceed to award a new contract in accordance with this Chapter 69, Title 29 of the Delaware Code or may require the Surety on the Performance Bond to complete the Contract in accordance with the terms of the Performance Bond. Nothing herein shall preclude the Agency from pursing additional remedies as otherwise provided by law.

4.3 CONTRACT INSURANCE AND CONTRACT LIABILITY

- In addition to the bond requirements stated in the Bid Documents, each successful Bidder shall purchase adequate insurance for the performance of the Contract and, by submission of a Bid, agrees to indemnify and save harmless and to defend all legal or equitable actions brought against the State, any Agency, officer and/or employee of the State, for and from all claims of liability which is or may be the result of the successful Bidder's actions during the performance of the Contract.
- 4.3.2 The purchase or nonpurchase of such insurance or the involvement of the successful Bidder in any legal or equitable defense of any action brought against the successful Bidder based upon work performed pursuant to the Contract will not waive any defense which the State, its agencies and their respective officers, employees and agents might otherwise have against such claims, specifically including the defense of sovereign immunity, where applicable, and by the terms of this section, the State and all agencies, officers and employees thereof shall not be financially responsible for the consequences of work performed, pursuant to said contract.

4.4 RIGHT TO AUDIT RECORDS

- 4.4.1 The Owner shall have the right to audit the books and records of a Contractor or any Subcontractor under any Contract or Subcontract to the extent that the books and records relate to the performance of the Contract or Subcontract.
- 4.4.2 Said books and records shall be maintained by the Contractor for a period of seven (7) years from the date of final payment under the Prime Contract and by the Subcontractor for a period of seven (7) years from the date of final payment under the Subcontract.

ARTICLE 5: SUBCONTRACTORS

5.1 SUBCONTRACTING REQUIREMENTS

5.1.1 All contracts for the construction, reconstruction, alteration or repair of any public building (not a road, street or highway) shall be subject to the following provisions:

A contract shall be awarded only to a Bidder whose Bid is accompanied by a statement containing, for each Subcontractor category, the name and address (city or town and State only – street number and P.O. Box addresses not required) of the subcontractor whose services the Bidder intends to use in performing the Work and providing the material for such Subcontractor category.

A Bid will not be accepted nor will an award of any Contract be made to any Bidder which, as the Prime Contractor, has listed itself as the Subcontractor for any Subcontractor unless:

- A. It has been established to the satisfaction of the awarding Agency that the Bidder has customarily performed the specialty work of such Subcontractor category by artisans regularly employed by the Bidder's firm:
- B. That the Bidder is duly licensed by the State to engage in such specialty work, if the State requires licenses; and

- C. That the Bidder is recognized in the industry as a bona fide Subcontractor or Contractor in such specialty work and Subcontractor category.
- 5.1.2 The decision of the awarding Agency as to whether a Bidder who list itself as the Subcontractor for a Subcontractor category shall be final and binding upon all Bidders, and no action of any nature shall lie against any awarding agency or its employees or officers because of its decision in this regard.
- 5.1.3 After such a Contract has been awarded, the successful Bidder shall not substitute another Subcontractor for any Subcontractor whose name was set forth in the statement which accompanied the Bid without the written consent of the awarding Agency.
- 5.1.4 No Agency shall consent to any substitution of Subcontractors unless the Agency is satisfied that the Subcontractor whose name is on the Bidders accompanying statement:
 - A. Is unqualified to perform the work required;
 - B. Has failed to execute a timely reasonable Subcontract
 - C. Has defaulted in the performance on the portion of the work covered by the Subcontract; or
 - D. Is no longer engaged in such business.
- 5.1.5 Should a Bidder be awarded a contract, such successful Bidder shall provide to the agency the taxpayer identification license numbers of such subcontractors. Such numbers shall be provided on the later of the date on which such subcontractor is required to be identified or the time the contract is executed. The successful Bidder shall provide to the agency to which it is contracting, within 30 days of entering into such public works contract, copies of all Delaware Business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the Bidder entered the public works contract the Delaware Business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.

5.2 PENALTY FOR SUBSTITUTION OF SUBCONTRACTORS

Should the Contractor fail to utilize any or all of the Subcontractors in the Contractor's Bid statement in the performance of the Work on the public bidding, the Contractor shall be penalized in the amount of (project specific amount*). The Agency may determine to deduct payments of the penalty from the Contractor or have the amount paid directly to the Agency. Any penalty amount assessed against the Contractor may be remitted or refunded, in whole or in part, by the Agency awarding the Contract, only if it is established to the satisfaction of the Agency that the Subcontractor in question has defaulted or is no longer engaged in such business. No claim for the remission or refund of any penalty shall be granted unless an application is filed within one year after the liability of the successful Bidder accrues. All penalty amounts assessed and not refunded or remitted to the contractor shall be reverted to the State.

*one (1) percent of contract amount not to exceed \$10,000

- 5.3 ASBESTOS ABATEMENT
- 5.3.1 The selection of any Contractor to perform asbestos abatement for State-funded projects shall be approved by the Office of Management and Budget, Division of Facilities Management pursuant to Chapter 78 of Title 16.
- 5.4 STANDARDS OF CONSTRUCTION FOR THE PROTECTION OF THE PHYSICALLY HANDICAPPED
- 5.4.1 All Contracts shall conform with the standard established by the Delaware Architectural Accessibility Board unless otherwise exempted by the Board.
- 5.5 CONTRACT PERFORMANCE
- Any firm entering into a Public Works Contract that neglects or refuses to perform or fails to comply with its terms, the Agency may terminate the Contract and proceed to award a new Contract or may require the Surety on the Performance Bond to complete the Contract in accordance with the terms of the Performance Bond.

ARTICLE 6: CONSTRUCTION BY OWNER OR SEPARATE CONTRACTORS

- The Owner reserves the right to simultaneously perform other construction or operations related to the Project with the Owner's own forces, and to award separate contracts in connection with other portions of the Project or other Projects at the same site.
- The Contractor shall afford the Owner and other Contractors reasonable opportunity for access and storage of materials and equipment, and for the performance of their activities, and shall connect and coordinate their activities with other forces as required by the Contract Documents.

ARTICLE 7: CHANGES IN THE WORK

- 7.1 The Owner, without invalidating the Contract, may order changes in the Work consisting of Additions, Deletions, Modifications or Substitutions, with the Contract Sum and Contract completion date being adjusted accordingly. Such changes in the Work shall be authorized by written Change Order signed by the Professional, as the duly authorized agent, the Contractor and the Owner.
- 7.2 The Contract Sum and Contract Completion Date shall be adjusted only by a fully executed Change Order.
- 7.3 The additional cost, or credit to the Owner resulting from a change in the Work shall be by mutual agreement of the Owner, Contractor and the Architect. In all cases, this cost or credit shall be based on the 'DPE' wages required and the "invoice price" of the materials/equipment needed.
- "DPE" shall be defined to mean "direct personnel expense". Direct payroll expense includes direct salary plus customary fringe benefits (prevailing wage rates) and documented statutory costs such as workman's compensation insurance, Social Security/Medicare, and unemployment insurance (a maximum multiplier of 1.35 times DPE).

- 7.3.2 "Invoice price" of materials/equipment shall be defined to mean the actual cost of materials and/or equipment that is paid by the Contractor, (or subcontractor), to a material distributor, direct factory vendor, store, material provider, or equipment leasing entity. Rates for equipment that is leased and/or owned by the Contractor or subcontractor(s) shall not exceed those listed in the latest version of the "Means Building Construction Cost Data" publication.
- 7.3.3 In addition to the above, the General Contractor is allowed a fifteen percent (15%) markup for overhead and profit for additional work performed by the General Contractor's own forces. For additional subcontractor work, the Subcontractor is allowed a fifteen (15) percent overhead and profit on change order work above and beyond the direct costs stated previously. To this amount, the General Contractor will be allowed a mark-up not exceeding seven and one half percent (7.5%) on the subcontractors work. These mark-ups shall include all costs including, but not limited to: overhead, profit, bonds, insurance, supervision, etc. No markup is permitted on the work of the subcontractors subcontractor. No additional costs shall be allowed for changes related to the Contractor's onsite superintendent/staff, or project manager, unless a change in the work changes the project duration and is identified by the CPM schedule. There will be no other costs associated with the change order.

ARTICLE 8: TIME

8.4.1

- 8.1 Time limits, if any, are as stated in the Project Manual. By executing the Agreement, the Contractor confirms that the stipulated limits are reasonable, and that the Work will be completed within the anticipated time frame.
- 8.2 If progress of the Work is delayed at any time by changes ordered by the Owner, by labor disputes, fire, unusual delay in deliveries, abnormal adverse weather conditions, unavoidable casualties or other causes beyond the Contractor's control, the Contract Time shall be extended for such reasonable time as the Owner may determine.
- Any extension of time beyond the date fixed for completion of the construction and acceptance of any part of the Work called for by the Contract, or the occupancy of the building by the Owner, in whole or in part, previous to the completion shall not be deemed a waiver by the Owner of his right to annul or terminate the Contract for abandonment or delay in the matter provided for, nor relieve the Contractor of full responsibility.

8.4 SUSPENSION AND DEBARMENT

Per Section 6962(d)(14), Title 29, Delaware Code, "Any Contractor who fails to perform a public works contract or complete a public works project within the time schedule established by the Agency in the Invitation To Bid, may be subject to Suspension or Debarment for one or more of the following reasons: a) failure to supply the adequate labor supply ratio for the project; b) inadequate financial resources; or, c) poor performance on the Project."

"Upon such failure for any of the above stated reasons, the Agency that contracted for the public works project may petition the Director of the Office of Management and Budget for Suspension or Debarment of the Contractor. The Agency shall send a copy of the petition to the Contractor within three (3) working days of filing with the Director. If the Director concludes that the petition has merit, the Director shall schedule and hold a hearing to determine whether to suspend the Contractor, debar the Contractor or deny the petition. The Agency shall have the burden of proving, by a preponderance of the

evidence, that the Contractor failed to perform or complete the public works project within the time schedule established by the Agency and failed to do so for one or more of the following reasons: a) failure to supply the adequate labor supply ratio for the project; b) inadequate financial resources; or, c) poor performance on the project. Upon a finding in favor of the Agency, the Director may suspend a Contractor from Bidding on any project funded, in whole or in part, with public funds for up to 1 year for a first offense, up to 3 years for a second offense and permanently debar the Contractor for a third offense. The Director shall issue a written decision and shall send a copy to the Contractor and the Agency. Such decision may be appealed to the Superior Court within thirty (30) days for a review on the record."

8.5 RETAINAGE

- 8.5.1 Per Section 6962(d)(5) a.3, Title 29, Delaware Code: The Agency may at the beginning of each public works project establish a time schedule for the completion of the project. If the project is delayed beyond the completion date due to the Contractor's failure to meet their responsibilities, the Agency may forfeit, at its discretion, all or part of the Contractor's retainage.
- This forfeiture of retainage also applies to the timely completion of the punchlist. A punchlist will only be prepared upon the mutual agreement of the Owner, Architect and Contractor. Once the punchlist is prepared, all three parties will by mutual agreement, establish a schedule for its completion. Should completion of the punchlist be delayed beyond the established date due to the Contractor's failure to meet their responsibilities, the Agency may hold permanently, at its discretion, all or part of the Contractor's retainage.

ARTICLE 9: PAYMENTS AND COMPLETION

9.1 APPLICATION FOR PAYMENT

- 9.1.1 Applications for payment shall be made upon AIA Document G702. There will be a five percent (5%) retainage on all Contractor's monthly invoices until completion of the project. This retainage may become payable upon receipt of all required closeout documentation, provided all other requirements of the Contract Documents have been met.
- 9.1.2 A date will be fixed for the taking of the monthly account of work done. Upon receipt of Contractor's itemized application for payment, such application will be audited, modified, if found necessary, and approved for the amount. Statement shall be submitted to the Owner.
- 9.1.3 Section 6516, Title 29 of the <u>Delaware Code</u> annualized interest is not to exceed 12% per annum beginning thirty (30) days after the "presentment" (as opposed to the date) of the invoice.

PARTIAL PAYMENTS

- Any public works Contract executed by any Agency may provide for partial payments at the option of the Owner with respect to materials placed along or upon the sites or stored at secured locations, which are suitable for use in the performance of the contract.
- 9.2.2 When approved by the agency, partial payment may include the values of tested and acceptable materials of a nonperishable or noncontaminative nature which have been produced or furnished for incorporation as a permanent part of the work yet to be completed, provided acceptable provisions have been made for storage.

9.2.2.1 Any allowance made for materials on hand will not exceed the delivered cost of the materials as verified by invoices furnished by the Contractor, nor will it exceed the contract bid price for the material complete in place. 9.2.3 If requested by the Agency, receipted bills from all Contractors, Subcontractors, and material, men, etc., for the previous payment must accompany each application for payment. Following such a request, no payment will be made until these receipted bills have been received by the Owner. 9.3 SUBSTANTIAL COMPLETION When the building has been made suitable for occupancy, but still requires small items of 9.3.1 miscellaneous work, the Owner will determine the date when the project has been substantially completed. 9.3.2 If, after the Work has been substantially completed, full completion thereof is materially delayed through no fault of the Contractor, and without terminating the Contract, the Owner may make payment of the balance due for the portion of the Work fully completed and accepted. Such payment shall be made under the terms and conditions governing final payment that it shall not constitute a waiver of claims On projects where commissioning is included the commissioning work as defined in the 9.3.3 specifications must be complete prior to the issuance of substantial completion. 9.4 FINAL PAYMENT Final payment, including the five percent (5%) retainage if determined appropriate, shall be 9.4.1 made within thirty (30) days after the Work is fully completed and the Contract fully performed and provided that the Contractor has submitted the following closeout documentation (in addition to any other documentation required elsewhere in the Contract Documents): 9.4.1.1 Evidence satisfactory to the Owner that all payrolls, material bills, and other indebtedness connected with the work have been paid, An acceptable RELEASE OF LIENS, 9.4.1.2 9.4.1.3 Copies of all applicable warranties, 9.4.1.4 As-built drawings, 9.4.1.5 Operations and Maintenance Manuals, Instruction Manuals, Consent of Surety to final payment. The Owner reserves the right to retain payments, or parts thereof, for its protection until the foregoing conditions have been complied with, defective work corrected and all unsatisfactory conditions remedied.

ARTICLE 10: PROTECTION OF PERSONS AND PROPERTY

- The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract. The Contractor shall take all reasonable precautions to prevent damage, injury or loss to: workers, persons nearby who may be affected, the Work, materials and equipment to be incorporated, and existing property at the site or adjacent thereto. The Contractor shall give notices and comply with applicable laws ordinances, rules regulations, and lawful orders of public authorities bearing on the safety of persons and property and their protection from injury, damage, or loss. The Contractor shall promptly remedy damage and loss to property at the site caused in whole or in part by the Contractor, a Subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable.
- The Contractor shall notify the Owner in the event any existing hazardous material such as lead, PCBs, asbestos, etc. is encountered on the project. The Owner will arrange with a qualified specialist for the identification, testing, removal, handling and protection against exposure or environmental pollution, to comply with applicable regulation laws and ordinances. The Contractor and Architect will not be required to participate in or to perform this operation. Upon completion of this work, the Owner will notify the Contractor and Architect in writing the area has been cleared and approved by the authorities in order for the work to proceed. The Contractor shall attach documentation from the authorities of said approval.
- As required in the Hazardous Chemical Information Act of June 1984, all vendors supplying any materials that may be defined as nazardous, must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it has a warning caution on the label relating to a potential physical or health hazard, if it is known to be present in the work place, and if employees may be exposed under normal conditions or in any foreseeable emergency situation. Material Safety Data Sheets must be provided directly to the Owner along with the shipping slips that include those products.
- The Contractor shall certify to the Owner that materials incorporated into the Work are free of all asbestos. This certification may be in the form of Material Safety Data Sheet (MSDS) provided by the product manufacturer for the materials used in construction, as specified or as provided by the Contractor.

ARTICLE 11: INSURANCE AND BONDS

- The Contractor shall carry all insurance required by law, such as Unemployment Insurance, etc. The Contractor shall carry such insurance coverage as they desire on their own property such as a field office, storage sheds or other structures erected upon the project site that belong to them and for their own use. The Subcontractors involved with this project shall carry whatever insurance protection they consider necessary to cover the loss of any of their personal property, etc.
 - Upon being awarded the Contract, the Contractor shall obtain a minimum of two (2) copies of all required insurance certificates called for herein, and submit one (1) copy of each certificate, to the Owner, within 20 days of contract award.
 - Bodily Injury Liability and Property Damage Liability Insurance shall, in addition to the coverage included herein, include coverage for injury to or destruction of any property arising out of the collapse of or structural injury to any building or structure due to demolition work and evidence of these coverages shall be filed with and approved by the Owner.

- 11.4 The Contractor's Property Damage Liability Insurance shall, in addition to the coverage noted herein, include coverage on all real and personal property in their care, custody and control damaged in any way by the Contractor or their Subcontractors during the entire construction period on this project.
- Builders Risk (including Standard Extended Coverage Insurance) on the existing building during the entire construction period, shall not be provided by the Contractor under this contract. The Owner shall insure the existing building and all of its contents and all this new alteration work under this contract during entire construction period for the full insurable value of the entire work at the site. Note, however, that the Contractor and their Subcontractors shall be responsible for insuring building materials (installed and stored) and their tools and equipment whenever in use on the project, against fire damage, theft, vandalism, etc.
- 11.6 Certificates of the insurance company or companies stating the amount and type of coverage, terms of policies, etc., shall be furnished to the Owner, within 20 days of contract award.
- 11.7 The Contractor shall, at their own expense, (in addition to the above) carry the following forms of insurance:

11.7.1 <u>Contractor's Contractual Liability Insurance</u>

Minimum coverage to be:

Bodily Injury	\$500,000	for each person
	\$1,000,000	for each occurrence
	\$1,000,000	aggregate

Property Damage \$500,000 for each occurrence aggregate

11.7.2 Contractor's Protective Liability Insurance

Minimum coverage to be:

Bodily Injury	\$500,000 \$1,000,000 \$1,000,000	for each person for each occurrence aggregate
Property Damage	\$500.000	for each occurrence

Property Damage \$500,000 for each occurrence \$500,000 aggregate

Automobile Liability Insurance

Minimum coverage to be:

Bodily Injury	\$1,000,000	for each person
	\$1,000,000	for each occurrence
Property Damage	\$500,000	per accident

- 11.7.4 Prime Contractor's and Subcontractors' policies shall include contingent and contractual liability coverage in the same minimum amounts as 11.7.1 above.
- 11.7.5 Workmen's Compensation (including Employer's Liability):

- 11.7.5.1 Minimum Limit on employer's liability to be as required by law.
- 11.7.5.2 Minimum Limit for all employees working at one site.
- 11.7.6 Certificates of Insurance must be filed with the Owner <u>guaranteeing</u> fifteen (15) days prior notice of cancellation, non-renewal, or any change in coverages and limits of liability shown as included on certificates.

11.7.7 <u>Social Security Liability</u>

- 11.7.7.1 With respect to all persons at any time employed by or on the payroll of the Contractor or performing any work for or on their behalf, or in connection with or arising out of the Contractor's business, the Contractor shall accept full and exclusive liability for the payment of any and all contributions or taxes or unemployment insurance, or old age retirement benefits, pensions or annuities now or hereafter imposed by the Government of the United States and the State or political subdivision thereof, whether the same be measured by wages, salaries or other remuneration paid to such persons or otherwise.
- 11.7.7.2 Upon request, the Contractor shall furnish Owner such information on payrolls or employment records as may be necessary to enable it to fully comply with the law imposing the aforesaid contributions or taxes.
- 11.7.7.3 If the Owner is required by law to and does pay any and/or all of the aforesaid contributions or taxes, the Contractor shall forthwith reimburse the Owner for the entire amount so paid by the Owner.

ARTICLE 12: UNCOVERING AND CORRECTION OF WORK

- The Contractor shall promptly correct Work rejected by the Owner or failing to conform to the requirements of the Contract Documents, whether observed before or after Substantial Completion and whether or not fabricated, installed or completed, and shall correct any Work found to be not in accordance with the requirements of the Contract Documents within a period of two years from the date of Substantial Completion, or by terms of an applicable special warranty required by the Contract Documents. The provisions of this Article apply to work done by Subcontractors as well as to Work done by direct employees of the Contractor.
- At any time during the progress of the work, or in any case where the nature of the defects shall be such that it is not expedient to have them corrected, the Owner, at their option, shall have the right to deduct such sum, or sums, of money from the amount of the contract as they consider justified to adjust the difference in value between the defective work and that required under contract including any damage to the structure.

ARTICLE 13: MISCELLANEOUS PROVISIONS

- 13.1 CUTTING AND PATCHING
- The Contractor shall be responsible for all cutting and patching. The Contractor shall coordinate the work of the various trades involved.
- 13.2 DIMENSIONS
- All dimensions shown shall be verified by the Contractor by actual measurements at the project site. Any discrepancies between the drawings and specifications and the existing conditions shall be referred to the Owner for adjustment before any work affected thereby has been performed.

13.3 LABORATORY TESTS

- Any specified laboratory tests of material and finished articles to be incorporated in the work shall be made by bureaus, laboratories or agencies approved by the Owner and reports of such tests shall be submitted to the Owner. The cost of the testing shall be paid for by the Contractor.
- The Contractor shall furnish all sample materials required for these tests and shall deliver same without charge to the testing laboratory or other designated agency when and where directed by the Owner.

13.4 ARCHAEOLOGICAL EVIDENCE

Whenever, in the course of construction, any archaeological evidence is encountered on the surface or below the surface of the ground, the Contractor shall notify the authorities of the Delaware Archaeological Board and suspend work in the immediate area for a reasonable time to permit those authorities, or persons designated by them, to examine the area and ensure the proper removal of the archaeological evidence for suitable preservation in the State Museum.

13.5 GLASS REPLACEMENT AND CLEANING

The General Contractor shall replace without expense to the Owner all glass broken during the construction of the project. If job conditions warrant, at completion of the job the General Contractor shall have all glass cleaned and polished.

13.6 WARRANTY

For a period of two (2) years from the date of substantial completion, as evidenced by the date of final acceptance of the work, the contractor warrants that work performed under this contract conforms to the contract requirements and is free of any defect of equipment, material or workmanship performed by the contractor or any of his subcontractors or suppliers. However, manufacturer's warranties and guarantees, if for a period longer than two (2) years, shall take precedence over the above warranties. The contractor shall remedy, at his own expense, any such failure to conform or any such defect. The protection of this warranty shall be included in the Contractor's Performance Bond.

ARTICLE 14: TERMINATION OF CONTRACT

If the Contractor defaults or persistently fails or neglects to carry out the Work in accordance with the Contract Documents or fails to perform a provision of the Contract, the Owner, after seven days written notice to the Contractor, may make good such deficiencies and may deduct the cost thereof from the payment then or thereafter due the Contractor. Alternatively, at the Owner's option, and the Owner may terminate the Contract and take possession of the site and of all materials, equipment, tools, and machinery thereon owned by the Contractor and may finish the Work by whatever method the Owner may deem expedient. If the costs of finishing the Work exceed any unpaid compensation due the Contractor, the Contractor shall pay the difference to the Owner.

"If the continuation of this Agreement is contingent upon the appropriation of adequate state, or federal funds, this Agreement may be terminated on the date beginning on the first fiscal year for which funds are not appropriated or at the exhaustion of the appropriation. The Owner may terminate this Agreement by providing written notice to the parties of such non-appropriation. All payment obligations of the Owner will cease

GENERAL REQUIREMENTS

upon the date of termination. Notwithstanding the foregoing, the Owner agrees that it will use its best efforts to obtain approval of necessary funds to continue the Agreement by taking appropriate action to request adequate funds to continue the Agreement."

END OF GENERAL REQUIREMENTS

Section 00 90 10

ASBESTOS CONTENT

1. The following asbestos containing material was found within the existing roofing and flashing systems:

1912 Building

Summary Of Materials Assessed

ID	Material Description	Analytical Results	Quantity	
001	Roof Material (Modified Mop Down)	No Asbestos Detected	440 SF	
002	Roof Flashing	10% Chrysotile Asbestos	8 SF	
003	Roof Material (Modified Mop Down)	No Asbestos Detected	777 SF	
004	Mechanical Flashing	No Asbestos Detected	32 SF	
005	Roof Flashing	10% Chrysotile Asbestos	21 SF	
006	Roof Material (EPDM)	No Asbestos Detected	96 SF	
007	Roof Material (EPDM)	No Asbestos Detected	480 SF	
008	Roof Flashing	10% Chrysotile Asbestos	7 SF	
009	Roof Material (EPDM)	No Asbestos Detected	880 SF	
010	Roof Flashing	No Asbestos Detected	126 SF	
011	Roof Material (EPDM)	No Asbestos Detected	1,739 SF	
012	Roof Material (Modified Mop Down)	No Asbestos Detected	627 SF	
013	Roof Flashing (Seam)	No Asbestos Detected	32 SF	
014	Mechanical Flashing	No Asbestos Detected	32 SF	
015	Roof Material (Modified Mop Down)	No Asbestos Detected	627 SF	
016	Roof Flashing (Seam)	No Asbestos Detected		
017	Mechanical Flashing	No Asbestos Detected	32 SF	
018	Roof Material (EPDM)	No Asbestos Detected	714 SF	
019	Roof Flashing	No Asbestos Detected	76 SF	
020	Roof Material	No Asbestos Detected	464 SF	
021	Roof Flashing	10% Chrysotile Asbestos	16 SF	
022	Roof Material - Roof #12	No Asbestos Detected	1,272 SF	
023	Roof Shingle - Roof #12	No Asbestos Detected	2,296 SF	
024	Roof Felt Paper - Roof #12	No Asbestos Detected	2,296 SF	
025	Roof Material - Roof #12	2% Chrysotile Asbestos	1,272 SF	
026	Roof Material - Roof #12	5% Chrysotile Asbestos	1,272 SF	

Main Hospital

Summary Of Materials Assessed

ID	Material Description	Analytical Results	Quantity
001	Roof Material (EPDM Seam Caulk	No Asbestos Detected	576 SF
002	Roof Material (Modified Mop Down)	No Asbestos Detected	864 SF
003	Roof Material (EPDM Seam Caulk)	No Asbestos Detected	2,132 SF
004	Roof Material (EPDM Seam Tape)	No Asbestos Detected	3,825 SF
005	Roof Flashing	5% Chrysotile Asbestos	20 SF
006	Roof Material (EPDM Seam Caulk)	No Asbestos Detected	6,063 SF
007	Shingle Boards (Carei Tread) Green	No Asbestos Detected	192 SF
008	Shingle Boards (Carei Tread) Black	3% Chrysotile Asbestos	192 SF
009	Roof Flashing (Around Fan Units)	5% Chrysotile Asbestos	88 SF
010	Roof Material (EPDM Seam Tape)	No Asbestos Detected	300 SF
011	Roof Material	No Asbestos Detected	888 SF
012	Roof Material (Built up-F/G Felt)	No Asbestos Detected	2,295 SF
013	Roof Flashing	No Asbestos Detected	102 SF
014	Mechanical Flashing	No Asbestos Detected	20 SF
015	Roof Material (Built up F/G Felt)	No Asbestos Detected	2,600 SF
016	Roof Flashing	5% Chrysotile Asbestos	130 SF
017	Roof Material (Built up F/G Felt)	No Asbestos Detected	648 SF
018	Roof Flashing	10% Chrysotile Asbestos	10 SF
019	Roof Material (Built up)	No Asbestos Detected	132 SF

- 2. The roofing contractor will be responsible to coordinate the asbestos removal so the correct amount of roofing can be installed to keep the buildings watertight.
- 3. The roofing contractor will be responsible to temporally flash all areas where asbestos material has been removed.



760 Pulaski Highway Bear, DE 19701 1-302-326-2333

Emily P. Bissell Hospital 1912 Building

Asbestos Roof Inspections

Wilmington, DE

FINAL REPORT – 4/26/13 Harvard Project # 12015

Prepared For: Daniel Episcopo

State of Delaware Division of Facilities Management

1901 N. Dupont Highway New Castle, DE 19720

Prepared By: Harvard Environmental, Inc.

760 Pulaski Highway Bear Delaware 19701 302-326-2333

Written By: Michael Sanders
Operations Manager
Harvard Environmental, Inc.

Released By: W.G. Morrison, Jr.

President

Table Of Contents

Introductions & Executive Summary

Appendix A

Certifications & Accreditations

Homogeneous Characterizations Report

117.0

Schematic Diagrams/Sample Locations & Material Inventory Report

Appendix D

Laboratory Analysis

Introductions & Executive Summary

Harvard Environmental, Inc. herein presents data associated with inspections performed at the Main Building of the Emily P. Bissell Hospital located at 3000 Newport Gap Pike in Wilmington, DE 19808. This inspection was performed to provide compliance with 40 CFR Part 61, "Asbestos NESHAP. These Environmental Protection Agency, (EPA), regulations require inspections to be performed by certified asbestos building inspectors prior to renovations and/or demolition of facilities. This effort was performed at the request of State of Delaware Health & Social Services and Division of Facilities Management.

This project was performed in order to identify asbestos containing roofing materials that may impacted during future roofing repair projects to the 1912 Building. Harvard Environmental Inc, assessed the impacted building materials which would be considered suspect asbestos containing. A listing of locations, systems and/or materials which were not assessed may be found under "Non Assessed Conditions" found further in this report.

Harvard requested drawings of the existing facility layouts/designs to assist in documenting field assessments and to provide insight as to the location of suspect materials which may be associated with the facility. Floor plans of the facility were not available.

The last day of visitation to the site was performed on 1/30/13. Conditions described within this document are accurate as of the date of last visitation. Mr. Jeffrey Hogate was the responsible Harvard Environmental, Inc. employee which led the field efforts associated with the work.

Representative sampling of suspect asbestos building materials was performed on impacted building materials. The sampling effort was conducted in accordance with EPA regulations and industry accepted standards.

Asbestos analysis was completed utilizing Polarized Light Microscopy, (PLM). PLM utilizes an optical microscope equipped with a polarizing lens through which trained microscopist can identify asbestos fibers according to their crystalline structure. This method of analysis is recognized throughout the industry as standard practice. Prior to determining the type of fiber, the sample was placed under a "Stereo Microscope" at approximately 150X magnification for purposes of visual estimation. Various fiber types were pulled from the sample and oils applied to determine refractive indices under the polarized light microscope.

This recognized method of analysis has a detection limit of 1% by volume. Percentages of asbestos < 1% are reported as "trace" and are not considered asbestos containing materials under EPA regulations.

In order to best document the assessment, Harvard Environmental, Inc. assessed the layout and design of locations requiring assessment and assigned each geographic area a unique alpha/numeric "grid" identifier. These identifiers are specific locations of the assessment and are the basis for orientation of the data.

<u>Based on the information provided to Harvard Environmental, Inc., coupled with field inspections and laboratory analysis of samples collected, asbestos was present on five (5) roof sections.</u>

Provided is a summary listing of materials assessed under this inspection. The detailed inspection data is provided as appendices further in the report.

Summary Of Materials Assessed

ID	Material Description	Analytical Results	Quantity
001	Roof Material (Modified Mop Down)	No Asbestos Detected	440 SF
002	Roof Flashing	10% Chrysotile Asbestos	8 SF
003	Roof Material (Modified Mop Down)	No Asbestos Detected	777 SF
004	Mechanical Flashing	No Asbestos Detected	32 SF
005	Roof Flashing	10% Chrysotile Asbestos	21 SF
006	Roof Material (EPDM)	No Asbestos Detected	96 SF
007	Roof Material (EPDM)	No Asbestos Detected	480 SF
008	Roof Flashing	10% Chrysotile Asbestos	7 SF
009	Roof Material (EPDM)	No Asbestos Detected	880 SF
010	Roof Flashing	No Asbestos Detected	126 SF
011	Roof Material (EPDM)	No Asbestos Detected	1,739 SF
012	Roof Material (Modified Mop Down)	No Asbestos Detected	627 SF
013	Roof Flashing (Seam)	No Asbestos Detected	32 SF
014	Mechanical Flashing	No Asbestos Detected	32 SF
015	Roof Material (Modified Mop Down)	No Asbestos Detected	627 SF
016	Roof Flashing (Seam)	No Asbestos Detected	32 SF
017	Mechanical Flashing	No Asbestos Detected	32 SF
018	Roof Material (EPDM)	No Asbestos Detected	714 SF
019	Roof Flashing	No Asbestos Detected	76 SF
020	Roof Material	No Asbestos Detected	464 SF
021	Roof Flashing	10% Chrysotile Asbestos	16 SF
022	Roof Material - Roof #12	No Asbestos Detected	1,272 SF
023	Roof Shingle - Roof #12	No Asbestos Detected	2,296 SF
024	Roof Felt Paper - Roof #12	No Asbestos Detected	2,296 SF
025	Roof Material - Roof #12	2% Chrysotile Asbestos	1,272 SF
026	Roof Material - Roof #12	5% Chrysotile Asbestos	1,272 SF

Non Assessed Conditions

Systems and/or materials provided on the list below were not assessed under this inspection and therefore should not be disturbed. In the event disturbance is required to accomplish the project objectives additional investigations will be required.

• This inspection was limited to the roof areas and materials identified within the appendices of this report.

Recommendations


Based on the findings of the inspection, Harvard Environmental, Inc. is providing the following recommendations.

- If over the course of project execution, materials of questionable content are discovered, or should the Scope of Work expand beyond the parameters communicated to Harvard Environmental, Inc., additional inspections will be required in order to maintain compliance with Federal and State regulations.
- Abatement of all asbestos containing building materials must be performed prior to any demolition or renovations of those areas containing the materials. Harvard Environmental, inc. can further assist your needs for compliance with state regulations regarding asbestos abatement projects.

This report is intended to provide "basic data" only. It is assumed that individuals reading and interpreting the sample locations and results, methods of analysis and hazards associated with the materials, are knowledgeable in all areas of discussion. Should any questions arise regarding the content of the information presented, contact should be exclusively to Harvard Environmental, Inc., Bear, Delaware, 1-302-326-2333. This document should be archived by the Owner for historical reference.

Certifications And Accreditations

Appendix A



DATE ISSUED: 01/10/11

LICENSE FEE: \$ 225.00

MAILING ADDRESS

BUSINESS LICENSE

"VALIDATED"

#BWNKHPS #18MO X3V0 1LM0 8IB0# HARVARD ENVIRONMENTAL INC 760 PULASKI HWY

BEAR DE 19701-5200

HARVARD ENVIRONMENTAL INC 760 PULASKI WY BEAR DE 9/01-5260

IS HEREBY LICENSED TO PRACTICE, COMDUCT OR ENGAGE IN THE OCCUPATION OR BUSINESS ACTIVITY INDICATED ABOVE IN ACCORDANCE WITH THE LICENSE APPLICATION DILLY FILED PURSUANT TO TITLE 30, DEL CODE

RICK T. CARTER



Certifications And Accreditations

CENTRAL DELAWARE TRAINING ACADEMY, INC.

JEFFREY W. HOGATE

has successfully completed EPA APPROVED

AHERA BUILDING INSPECTOR REFRESHER TRAINING

COURSE LENGTH 4 HOURS

on June 19th, Two Thousand-Twelve

CDTA P.O. BOX 1344 DOVER, DE 19903-1344 (302) 677-1534

EXAM DATE: 061912

Control Control

DAVID T. STANLEY, PRESIDENT

RONALD & HERCHA, VICE PRESIDENT

EXPIRE DATE: 061913 ID NUMBER (

ID NUMBER CB120619-0083

United States Department of Commerce
National Institute of Standards and Technology



Certificate of Accreditation to ISO/IEC 17025:2005

NVLAP LAB CODE: 200885-0

Harvard Environmental, Inc.

Bear, DE

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

BULK ASBESTOS FIBER ANALYSIS

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005.

This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2012-07-01 through 2013-06-30

Effective dates



or the National Institute of Standards and Techno

NVLAP-01C (REV. 2009-01-28)

Homogeneous Characterizations Report

Appendix B

Delaware Health and Social Services

Emily P. Bissell Hospital - 1912 Building Asbestos Roof Inspection



Homogeneous Systems Report

				, <u> </u>			
Homogeneous System 001		440 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 001A	RM 001B	RM 001C			
No Asbestos Detected	Collection Point Grid	R-1	R-1	R-1	V)		_
Description Roof Material (Modified Mop Down)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected	Q-		
Homogeneous System 002		8 SF	✓ Asbestos	PACM	Non-Asbestos	■ Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 002A	RF 002B	RF 002C			
10% Chrysotile Asbestos	Collection Point Grid	R-1	R-1	R-I			
Description Roof Flashing	Analytical Results	10% Chrysotile Asbestos	Sample Not Analyzed	Sample Not Analyzed			
Homogeneous System 003		777 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 003A	RM 003B	RM 003C			
No Asbestos Detected	Collection Point Grid	R-2	R-2	R-2			
Description Roof Material (Modified Mop Down)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 004		32 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	MF 004A	MF 004B	MF 004C			
No Asbestos Detected	Collection Point Grid	R-2	R-2	R-2			
Description Mechanical Flashing	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			

Notes

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Delaware Health and Social Services

Emily P. Bissell Hospital - 1912 Building Asbestos Roof Inspection



Homogeneous Systems Report

Homogeneous System 005		21 SF	✓ Asbestos	PACM	Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 005A	RF 005B	RF 005C			
10% Chrysotile Asbestos	Collection Point Grid	R-2	R-2	R-2	V)		
Description Roof Flashing	Analytical Results	10% Chrysotile Asbestos	Sample Not Analyzed	Sample Not Analyzed	2		
Homogeneous System 006		96 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 006A	RM 006B	RM 006C			
No Asbestos Detected	Collection Point Grid	R-3	R-3	R-3			
Description Roof Material (EPDM)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Aspestos Detected			
Homogeneous System 007		480 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 007A	RM 007B	RM 007C			
No Asbestos Detected	Collection Point Grid	R-4	R-4	R-4			
Description Roof Material (EPDM)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 008		7 SF	✓ Asbestos	PACM	Non-Asbestos	■ Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 008A	RF 008B	RF 008C			
10% Chrysotile Asbestos	Collection Point Grid	R-4	R-4	R-4			
Description	Analytical Results	10% Chrysotile	Sample Not	Sample Not			

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing terial - Sampling Not Performed.

Emily P. Bissell Hospital - 1912 Building Asbestos Roof Inspection



Homogeneous Systems Report

			0 ,	•			
Homogeneous System 009		880 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 009A	RM 009B	RM 009C			
No Asbestos Detected	Collection Point Grid	R-5	R-5	R-5	(V)		
Description Roof Material (EPDM)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected	Q-		
Homogeneous System 010		126 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 010A	RF 010B	RF 010C			
No Asbestos Detected	Collection Point Grid	R-5	R-5	R-5			
Description Roof Flashing	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 011		1739 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 011A	RM 011B	RM 011C			
No Asbestos Detected	Collection Point Grid	R-7	R-7	R-7			
Description Roof Material (EPDM)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 012		627 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 012A	RM 012B	RM 012C			
No Asbestos Detected	Collection Point Grid	R-8	R-8	R-8			
Description oof Material (Modified Mop Down)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			

Notes:

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Emily P. Bissell Hospital - 1912 Building Asbestos Roof Inspection



Homogeneous Systems Report

				, stems ztep ett			
Homogeneous System 013		32 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 013A	RF 013B	RF 013C			
No Asbestos Detected	Collection Point Grid	R-8	R-8	R-8	V)		
Description Roof Flashing (Seam)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected	Q-		
Homogeneous System 014		32 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	MF 014A	MF 014B	MF 014C			
No Asbestos Detected	Collection Point Grid	R-8	R-8	R-8			
Description Mechanical Flashing	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 015		627 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 015A	RM 015B	RM 015C			
No Asbestos Detected	Collection Point Grid	R-9	R-9	R-9			
Description oof Material (Modified Mop Down)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 016		32 SF	Asbestos	PACM	✓ Non-Asbestos	■ Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 016A	RF 016B	RF 016C			
No Asbestos Detected	Collection Point Grid	R-9	R-9	R-9			
Description Roof Flashing (Seam)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing terial - Sampling Not Performed.

Emily P. Bissell Hospital - 1912 Building Asbestos Roof Inspection



Homogeneous Systems Report

				•			
Homogeneous System 017		32 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	MF 017A	MF 017B	MF 017C			
No Asbestos Detected	Collection Point Grid	R-9	R-9	R-9	(V)		
Description Mechanical Flashing	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected	Q-		
Homogeneous System 018		714 SF	■ Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 018A	RM 018B	RM 018C			
No Asbestos Detected	Collection Point Grid	R-10	R-10	R-10			
Description Roof Material (EPDM)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 019		76 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 019A	RF 019B	RF 019C			
No Asbestos Detected	Collection Point Grid	R-10	R-10	R-10			
Description Roof Flashing	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 020		464 SF	Asbestos	■ PACM	✓ Non-Asbestos	■ Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 020A	RM 020B	RM 020C			
No Asbestos Detected	Collection Point Grid	R-11	R-11	R-11			
Description Roof Material	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			

Notes:

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Emily P. Bissell Hospital - 1912 Building Asbestos Roof Inspection



Homogeneous Systems Report

				, F			
Homogeneous System 021		16 SF	✓ Asbestos	PACM	Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 021A	RF 021B	RF 021C			
10% Chrysotile Asbestos	Collection Point Grid	R-11	R-11	R-11	W ,		
Description Roof Flashing	Analytical Results	10% Chrysotile Asbestos	Sample Not Analyzed	Sample Not Analyzed	Q-		
Homogeneous System 022		1272 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	022A	022B	022C			
No Asbestos Detected	Collection Point Grid	R-12	R-12	R-12			
Description Roof Material - Roof #12	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 023		2296 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RS 023 A	RS 023 B	RS 023 C			
No Asbestos Detected	Collection Point Grid	R-12	R-12	R-12			
Description Roof Shingle - Roof #12	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System 024		2296 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RFP 024 A	RFP 024 B	RFP 024 C			
No Asbestos Detected	Collection Point Grid	R-12	R-12	R-12			
Description Roof Felt Paper - Roof #12	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			

Notes:

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Description

No Suspected ACM Roofing Materials

Emily P. Bissell Hospital - 1912 Building Asbestos Roof Inspection



Homogeneous Systems Report Homogeneous System ✓ Asbestos ✓ Non-Friable 1272 SF PACM Non-Asbestos Friable 025 Sample Identification RM 025 A RM 025 B RM 025 C **Analytical Results** 2% Chrysotile Asbestos **Collection Point Grid** R-12 R-12 R-12 Description **Analytical Results** Sample Not Sample Not 2% Chrysotile Roof Material - Roof #12 Asbestos Analyzed Analyzed Homogeneous System 1272 SF ✓ Non-Friable ✓ Asbestos PACM Non-Asbestos Friable 026 RM 026 C Sample Identification RM 026 A RM 026 B **Analytical Results** 5% Chrysotile Asbestos R-11 **Collection Point Grid** R-12 Description Sample Not Sample Not **Analytical Results** 5% Chrysotile Roof Material - Roof #12 Asbestos Analyzed Analyzed Homogeneous System Non-Friable PACM Non-Asbestos Asbestos Friable NAS Sample Identification **Analytical Results Collection Point Grid**

Notes:

Analytical Results

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Schematic Diagrams/Sample Locations & Material Inventory Report

Appendix C

Harvard Environmental, Inc. 9



Grid Descriptions

R-1	Roof	11x40-modified mop down-concrete deck-4" OSO-1" Perlite
R-10	Roof	21x34-EPDM o/concrete
R-11	Roof	29x16-Carlisle roof-wood deck-tin roof under densdeck
R-12	Roof	24x53-Carlisle roof-wood deck-tin roof under densdeck-aluminum under tin roof
R-13	Roof	11x9-new roof-EPDM per PRS-not sampled
R-2	Roof	21x37-modified mop down-concrete deck-5 1/2" ISO-1/2" fiberboard-2 ply cap
R-3	Roof	6x16-EPDM-no seam-EPDM over plywood
R-4	Roof	12x40-concrete deck EPDM roof-1/2" Perlite-2" ISO
R-5	Roof	22x40-EPDM roof-plywood deck-1" Perlite-2" ISO
R-6	Roof	6x10-EPDM o plywood-no seam-not sampled
R-7	Roof	47x37-EPDM roof/ concrete deck-1" Perlite-3" ISO
R-8	Roof	33x19-wood deck-2" ISO-1" Perlite-2 ply cap
R-9	Roof	19x33-wood deck-2" ISO-1" Perlite-2 ply cap
R-9		19x33-wood deck-2" ISO-1" Perlite-2 ply cap




Materials Inventory Report

Grid		Homogeneous	Material	Description	Quanti	ty	Analytical Results
R-1	Roof						
	RM	001	Misc. Material	Roof Material (Modified Mop Down)	440	SF	No Asbestos Detected
_	RF	002	Misc. Material	Roof Flashing	8	SF	10% Chrysotile Asbestos
R-10	Roof						
	RM	018	Misc. Material	Roof Material (EPDM)	714	SF	No Asbestos Detected
_	RF	019	Misc. Material	Roof Flashing	76	SF	No Asbestos Detected
R-11	Roof						
	RM	020	Misc. Material	Roof Material	464	SF	No Asbestos Detected
_	RF	021	Misc. Material	Roof Flashing	16	SF	10% Chrysotile Asbestos
R-12	Roof						
	RM	022	Misc. Material	Roof Material - Roof #12	1272	SF	No Asbestos Detected
_	RS	023	Misc. Material	Roof Shingle - Roof #12	2296	SF	No Asbestos Detected
_	RFP	024	Mise. Material	Roof Felt Paper - Roof #12	2296	SF	No Asbestos Detected
_	RM	025	Misc. Material	Roof Material - Roof #12	1272	SF	2% Chrysotile Asbestos
	RM	026	Misc. Material	Roof Material - Roof #12	1272	SF	5% Chrysotile Asbestos
R-13	Roof						
K-13	NAS	NAS		No Suspected ACM Roofing Materials			
R-2	Roof						
	RM	003	Misc. Material	Roof Material (Modified Mop Down)	777	SF	No Asbestos Detected
U -	MF	004	Misc. Material	Mechanical Flashing	32	SF	No Asbestos Detected
	RF	005	Misc. Material	Roof Flashing	21	SF	10% Chrysotile Asbestos



Materials Inventory Report

Grid	_	Homogeneous	Material	Description	Quanti	ty	Analytical Results
R-3	Roof	00.5	3.5		0.6	ar.	
	RM	006	Misc. Material	Roof Material (EPDM)	96	SF	No Asbestos Detected
R-4	Roof						
	RM	007	Misc. Material	Roof Material (EPDM)	480	SF	No Asbestos Detected
	RF	008	Misc. Material	Roof Flashing	7	SF	10% Chrysotile Asbestos
R-5	Roof						
	RM	009	Misc. Material	Roof Material (EPDM)	880	SF	No Asbestos Detected
_	RF	010	Misc. Material	Roof Flashing	126	SF	No Asbestos Detected
R-6	Roof						
	NAS	NAS		No Suspected ACM Rooting Materials			
R-7	Roof						
	RM	011	Misc. Material	Roof Material (EPDM)	1739	SF	No Asbestos Detected
R-8	Roof		,				
	RM	012	Mise. Material	Roof Material (Modified Mop Down)	627	SF	No Asbestos Detected
_	RF	013	Misc. Material	Roof Flashing (Seam)	32	SF	No Asbestos Detected
_	MF	014	Misc. Material	Mechanical Flashing	32	SF	No Asbestos Detected
R-9	Roof						
	RM	015	Misc. Material	Roof Material (Modified Mop Down)	627	SF	No Asbestos Detected
7	RF	016	Misc. Material	Roof Flashing (Seam)	32	SF	No Asbestos Detected
\bigcirc^{\dagger}	MF	017	Misc. Material	Mechanical Flashing	32	SF	No Asbestos Detected



General Notes:

- 1. Presentation of information is based on best available information. Drawing schematics were provided to Harvard Environmental by the State of Delaware.
- 2. Project #12015 involved asbestos inspections for purposes of identifying asbestos roofing materials located on 1912 Building. These Drawings are not to be considered to scale and are intended to be used for orientation purposes only and identifying the locations of roofing sections and bulk samples.

Legend:

(R-1) Roof Grid ID

PLM Bulk Sample Location


State of Delaware Office Of Management & Budget



Rew By: MPS Dwg By: WJTM 4-26-13

> PF-12015 DWG 1 of 2

Emily P. Bissell Hospital 1912 Building Asbestos Roof Inspection PLM Bulk Sample Locations



General Notes:

- Presentation of information is based on best available information. Drawing schematics were provided to Harvard Environmental by the State of Delaware.
- 2. Project #12015 involved asbestos inspections for purposes of identifying asbestos roofing materials located on 1912 Building. These Drawings are not to be considered to scale and are intended to be used for orientation purposes only and identifying the locations of roofing sections and bulk samples.

Legend:

(R-1) Roof Grid ID

Asbestos Roof Flashing Tar
35 Total SF

Asbestos Roof Material Tar 1,272 SF



DHSS-DPH Emily P. Bissell Hospital 3000 Newport Gap Pike Wilmington, DE 19808

Rew By: MPS Dwg By: WJTM 4-26-13

PF-12015 DWG 2 of 2

Emily P. Bissell Hospital 1912 Building Asbestos Roof Inspection ACM Locations

> Environmental, Inc. 760 Pulaski Highway Bear, Delaware 1970!

Laboratory Analysis

Appendix D

CAMMOT BE. USED

Harvard Environmental, Inc. 10



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/31/2013

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 002A

COC Description: Roof Flashing - Roof #1

Asbestos Type

10 Chrysotile % Other Fibrous Type

% Non Fibrous Type

90

LAB SAMPLE ID

Homogenity: Homogeneous

alment: Dissolved

Texture: Firm

Sample Number: 002B

COC Description: Roof Flashing - Roof #1

Asbestos Type

Not Analyzed

% Other Fibrous Type

on Fibrous Type

LAB SAMPLE ID

69898

Color:

Other Color Homogenity:

'reatment

Texture:

Sample Number: 002C

COC Description: Roof Flashing - Roof #1

Asbestos Type

Not Analyzed

Other Fibrous Typ

Non Fibrous Type

LAB SAMPLE ID 69899

Color: Other Color

Homogenity:

'realment:

Texture:

Sample Number: 003A

COC Description: Roof Material - Roof #2

Asbestos Type

None Detected

Other Fibrous Type

Cellulose

% Non Fibrous Type

80

LAB SAMPLE ID

69900

Color: Black

Other Color Grey

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 800 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 1 of 20



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/31/2013

Analyzed Asghar Keyvanfar

2/1/2013

LAB SAMPLE ID

Sample Number: 003B

COC Description: Roof Material - Roof #2

Asbestos Type

None Detected

% Other Fibrous Type

20 Cellulose

80

Non Fibrous Type

Homogenity: Homogeneous

atment: Dissolved

Texture: Firm

Sample Number: 003C

COC Description: Roof Material - Roof #2

Asbestos Type None Detected

Other Fibrous Type

Cellulose

10

lon Fibrous

LAB SAMPLE ID

69902

LAB SAMPLE ID

69903

Color: Black

Other Color Grey

Homogenity: Homogeneous reatment: Dissolved

Texture: Firm

Sample Number: 004A

COC Description: Mechanical Flashing - Roof #2

Asbestos Type

None Detected

Other Fibrous Typ

Cellulose

90

Non Fibrous Type

Color: Black

Other Color Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 004B

COC Description: Mechanical Flashing - Roof #2

None Detected

Asbestos Type

Other Fibrous Type

Cellulose

% Non Fibrous Type

90

69904

LAB SAMPLE ID

Color: Black Other Color

Homogeneous

reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by MIST-NVLAP or any agency of the U.S. government.

This report shall not be repreduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbastos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 2 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 004C

COC Description: Mechanical Flashing - Roof #2

% Asbestos Type None Detected

% Other Fibrous Type

10 Cellulose

Non Fibrous Type %

90

LAB SAMPLE ID

Color:

Homogenity: Homogeneous

stment: Dissolved

Texture: Firm

Sample Number: 005A

COC Description: Roof Flashing - Roof #2

% **Asbestos Type** Chrysotile

% Other Fibrous Type

lon Fibrous Type

LAB SAMPLE ID

69906

Color: Black

Other Color

Homogenity: Homogeneous 'reatment: Dissolved Texture: Firm

Sample Number: 005B

10

COC Description: Roof Flashing - Roof #2

Asbestos Type

Not Analyzed

Other Fibrous Typ

Non Fibrous Type

69907

LAB SAMPLE ID

Color:

Other Color Homogenity:

reatment:

Texture:

Sample Number: 005C

COC Description: Roof Flashing - Roof #2

Asbestos Type Not Analyzed

Other Fibrous Type

Non Fibrous Type

LAB SAMPLE ID

69908

Color; Other Color

Homogenity: 'realment

Texture:

This confidential report relates only to those item(s) fested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical inferescope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analysts specific measurements of uncertainty at lower concentrations are available upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. In reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvantar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 3 of 20



Bear Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 006A

COC Description: Roof Material - Roof #3

Asbestos Type

% Other Fibrous Type

None Detected

Non Fibrous Type

Homogenity: Homogeneous

tment: Healed Texture: Firm

Sample Number: 006B

%

COC Description: Roof Material - Roof #3

Asbestos Type None Detected

% Other Fibrous Type

Ion Fibrous Type

LAB SAMPLE ID

LAB SAMPLE ID

69910

Color: Black

Other Color

Homogenity: Homogeneous 'reatment: Healed

Texture: Firm

Sample Number: 006C

COC Description: Roof Material - Roof #3

Asbestos Type

None Detected

Other Fibrous Typ

Non Fibrous Type

100

100

LAB SAMPLE ID

69911

Color: Black

Other Color

Homogenity: Homogeneous

'restment: Heated Texture: Firm

Sample Number: 007A

COC Description: Roof Material - Roof #4

Asbestos Type

None Detected

Other Fibrous Type

Non Fibrous Type

100

LAB SAMPLE ID

69912

Color: Black

Other Color

Homogenity: Homogeneous

'reatment: Healed

Texture: Firm

This confidential report relates only to those litern(s) tested and does not represent an endorsament by NIST-NVLAP or any agency of the U.S. government,
This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be gueranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are availations are availation por request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 4 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013 78 1/31/2013

Logged Ashley Mote Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 007B

COC Description: Roof Material - Roof #4

Asbestos Type %

None Detected

% Other Fibrous Type

Non Fibrous Type %

100

Color:

genity: Homogeneous

ntment: Healed Texture: Firm

Sample Number: 007C

COC Description: Roof Material - Roof #4

% **Asbestos Type** None Detected

% Other Fibrous Type

ion Fibrous Type

LAB SAMPLE ID

LAB SAMPLE ID

69914

Color; Black

Homogenity: Homogeneous 'reatment: Heated

Texture: Firm

Sample Number: 008A

10

COC Description: Roof Flashing - Roof #4

Asbestos Type

Chrysotile

Other Fibrous Typ

Non Fibrous Type

69915

Color: Black

LAB SAMPLE ID

Other Color

Homogenity: Homogeneous

'reafment: Dissolved

Texture: Firm

Sample Number: 008B

COC Description: Roof Flashing - Roof #4

Asbestos Type Not Analyzed

Other Fibrous Type

Non Fibrous Type

LAB SAMPLE ID

69916

Color: Other Color

Homogenity:

reatment:

Texture:

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NYLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated, Small asbasios fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming lochnique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is pessible with this method. Analysis specific measurements of uncertainty at two reconcentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 800 Method. It is not be analyzed.

Asghar Keyvantar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 5 of 20.



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/31/2013

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 008C

COC Description: Roof Flashing - Roof #4

Not Analyzed

Asbestos Type

% Other Fibrous Type

Non Fibrous Type

LAB SAMPLE ID

Sample Number: 009A

COC Description: Roof Material - Roof #5

Asbestos Type

None Detected

% Other Fibrous Type

lon Fibrous Type

LAB SAMPLE ID 69918

Color: Black

Other Color

Homogenity: Homogeneous reatment: Heated

Texture: Firm

Sample Number: 009B

COC Description: Roof Material - Roof #5

Asbestos Type

None Detected

Other Fibrous Typ

Non Fibrous Type

100

100

69919

LAB SAMPLE ID

LAB SAMPLE ID

Color: Black

Other Color Homogenity: Homogeneous

'reatment: Heated Texture: Firm

Sample Number: 009C

COC Description: Roof Material - Roof #5

Asbestos Type

None Detected

Other Fibrous Type

Non Fibrous Type

69920

Color: Black

Other Color

Homogenity: Homogeneous

reatment. Healed

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannol be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 6 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

LAB SAMPLE ID

Logged Ashley Mote

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 010A

COC Description: Roof Flashing - Roof #5

Asbestos Type None Detected

Other Fibrous Type

%

100

Non Fibrous Type

Color:

lomogenity: Homogeneous

atment: Dissolved

Texture: Firm

Sample Number: 010B

COC Description: Roof Flashing - Roof #5

Asbestos Type

% Other Fibrous Type

on Fibrous Type

None Detected

69922 Color: Black

LAB SAMPLE ID

Other Color

Homogenity: Homogeneous reatment: Dissolved

Texture: Firm

Sample Number: 010C

COC Description: Roof Flashing - Roof #5

Asbestos Type

None Detected

Other Fibrous Typ

Non Fibrous Type

100

69923

LAB SAMPLE ID

Color: Black

Other Color

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 011A

COC Description: Roof Material - Roof #7

Asbestos Type

None Detected

Other Fibrous Type

% Non Fibrous Type

100

LAB SAMPLE ID

69924

Color: Black Other Color

Homogenity: Homogeneous

'realment: Healed

Texture: Firm

only to (hose item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government. This report shall not be reproduced except in fult, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be gueranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analysi specific measurements of uncertainty at lower concentrations are availations are availations are availations are availations are availated or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVI AP Lab Code 200885-0

Approved For Releas

Page 7 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013 78

Logged Ashley Mote Analyzed Asghar Keyvanfar

2/1/2013

LAB SAMPLE ID

Sample Number: 011B

COC Description: Roof Material - Roof #7

Asbestos Type

% Other Fibrous Type

None Detected

%

100

Non Fibrous Type

Homogenity: Homogeneous

LAB SAMPLE ID

69926

ment: Heated

Texture: Firm

Color:

Sample Number: 011C

COC Description: Roof Material - Roof #7

None Detected

Asbestos Type

% Other Fibrous Type

ion Fibrous Type

Color: Black

Homogenity: Homogeneous reatment: Heated

Texture: Firm

Sample Number: 012A

COC Description: Roof Material - Roof #8

Asbestos Type

None Detected

Other Fibrous Typ

Glass 10

Non Fibrous Type

Binder

69927

Color: Black

LAB SAMPLE ID

Other Color

Homogenity: Heterogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 012B

COC Description: Roof Material - Roof #8

Asbestos Type None Detected

Other Fibrous Type

Glass

Non Fibrous Type

90 Binder LAB SAMPLE ID

69928

Color: Black

Other Color

Homogenity: Heterogeneous

reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsoment by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be gueranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analysts specific measurements of uncertainty at tower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 8 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/31/2013

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 012C

COC Description: Roof Material - Roof #8

Asbestos Type

None Detected

% Other Fibrous Type

Cellulose

%

95

95

95

Non Fibrous Type

LAB SAMPLE ID

LAB SAMPLE ID

LAB SAMPLE ID

69931

LAB SAMPLE ID

69932

Homogenity: Heterogeneous

atment: Dissolved

Texture: Firm

Sample Number: 013A

COC Description; Roof Flashing - Roof #8

Asbestos Type

Other Fibrous Type

None Detected Cellulose lon Fibrous

69930 Color: Black

Other Color

Homogeneous 'reatment: Dissolved

Texture: Firm

Sample Number: 013B

COC Description: Roof Flashing - Roof #8

Asbestos Type

None Detected

Other Fibrous Typ

Cellulose

Non Fibrous Type

Color; Black

Olher Color Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 013C

COC Description: Roof Flashing - Roof #8

Asbestos Type

None Detected

Other Fibrous Type

Cellulose

% Non Fibrous Type

Other Color

Homogenity: Homogeneous

reatment: Dissolved

Color: Black

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Court Method performed. Method not performed untess stated, Small asbestos libers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 9 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

Re: DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

QI

Recieved Ashley Mote

1/30/2013 78

Logged Ashley Mote

/31/2013 78

Analyzed Asghar Keyvanfar

2/1/2013 66

Sample Number: 014A

COC Description: Mechanical Flashing - Roof #8

% Asbestos Type
None Detected

% Other Fibrous Type

5 Cellulose

% Non Fibrous Type

95

Non Fibrous Ty

LAB SAMPLE ID

Color: Blac

omogenity: Homogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 014B

COC Description: Mechanical Flashing - Roof #8

% Asbestos Type
None Detected

% Other Fibrous Type

5 Cellulose

% Non Fibrous Type

LAB SAMPLE ID 69934

Color; Black

Other Color

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 014C

COC Description: Mechanical Flashing - Roof #8

% Asbestos Type
None Detected

% Other Fibrous Type

5 Cellulose

% Non Fibrous Type

Color: Black

Other Color

Homogenity: Homogeneous

LAB SAMPLE ID

69935

LAB SAMPLE ID

69936

'reatment: Dissolved

Texture: Firm

Sample Number: 015A

COC Description: Roof Material - Roof #9

Asbestos Type

None Detected

% Other Fibrous Type

0 Glass

% Non

95

Non Fibrous Type

Binder

Color: Black

Other Color Tan

Homogenity: Helerogeneous

reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming lochnique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas . . .

Page 10 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013 78

Logged Ashley Mote

Analyzed Asghar Keyvanfar

Sample Number: 015B

COC Description: Roof Material - Roof #9

Asbestos Type None Detected

% Other Fibrous Type

10 Glass Non Fibrous Type

Binder

LAB SAMPLE ID

genity: Heterogeneous

tmant: Dissolved

Texture: Firm

Sample Number: 015C

COC Description: Roof Material - Roof #9

Asbestos Type None Detected

% Other Fibrous Type

Glass 10

Non Fibrous Type

Binder

LAB SAMPLE ID

69938

LAB SAMPLE ID

69939

LAB SAMPLE ID 69940

Color: Black

Other Color Grey

Homogenity: Helerogeneous 'reatment: Dissolved

Texture: Firm

Sample Number: 016A

COC Description: Roof Flashing - Roof #9

Asbestos Type

None Detected

Other Fibrous Typ

Cellulose

Non Fibrous Type

Color: Black

Other Color

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 016B

COC Description: Roof Flashing - Roof #9

Asbestos Type

None Detected

Other Fibrous Type

Cellulose

95

Non Fibrous Type

Other Color

Homogenity: Homogeneous

Color: Black

reatment: Dissolved

Texture: Firm

This confidential report relates only to those liem(s) lested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written appreval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analysis specific measurements of uncordatiny at flower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 11-of-20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof Re:

Sample Number: 016C

COC Description: Roof Flashing - Roof #9

Asbestos Type None Detected

% Other Fibrous Type

Cellulose

Non Fibrous Type

lon Fibrous Type

95

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013 Logged Ashley Mote

1/31/2013

Analyzed Asghar Keyvanfar

2/1/2013

LAB SAMPLE ID

Color:

Homogenity: Homogeneous

ent: Dissolved

Texture: Firm

Sample Number: 017A

%

COC Description: Mechanical Flashing - Roof #9

Asbestos Type None Detected

% Other Fibrous Type

LAB SAMPLE ID

69942

Color: Black

Homogenity: Homogeneous 'reatment: Dissolved

Texture: Firm

Sample Number: 017B

COC Description: Mechanical Flashing - Roof #9

None Detected

Asbestos Type

Other Fibrous Type

Non Fibrous Type

100

LAB SAMPLE ID

LAB SAMPLE ID

69944

69943

Color: Black

Other Color

Homogenity: Homogeneous

'reatment: Dissolved

Texture: Firm

Sample Number: 017C

COC Description: Mechanical Flashing - Roof #9

Asbestos Type

None Detected

Other Fibrous Type

%

100

Non Fibrous Type

Homogenity: Homogeneous

reatment: Dissolved

Color: Black

Texture: Firm

only to those item(s) tested and does not represent an endorsament by NIST-NVLAP or any agency of the U.S. government. This report shell not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Smell asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are evaliable upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. If not peparable or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 12 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013 78

Logged Ashley Mote

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 018A

COC Description: Roof Material - Roof #10

Asbestos Type

% Other Fibrous Type

None Detected

Non Fibrous Type %

100

Color:

genity: Homogeneous

iment: Healed

Texture: Firm

Sample Number: 018B

%

COC Description: Roof Material - Roof #10

Asbestos Type None Detected

% Other Fibrous Type

lon Fibrous Type

LAB SAMPLE ID 69946

LAB SAMPLE ID

69947

LAB SAMPLE ID 69948

LAB SAMPLE ID

Color: Black

Other Color

Homogenity: Homogeneous

'realment: Healed

Texture: Firm

Sample Number: 018C

COC Description: Roof Material - Roof #10

Asbestos Type

None Detected

Other Fibrous Typ

100

Non Fibrous Type

Color: Black

Other Color Homogenity: Homogeneous

reatment: Heated Texture: Firm

Sample Number: 019A

COC Description: Roof Flashing - Roof #10

Asbestos Type

None Detected

Other Fibrous Type

100

Non Fibrous Type

Other Color

Homogenity: Homogeneous

realment: Dissolved

Texture: Firm

Color: Black

This confidential report relates only to those litem(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at tower concentrations are available upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar,

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 13 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

LAB SAMPLE ID

LAB SAMPLE ID 69950

LAB SAMPLE ID 69951

Logged Ashley Mote

1/31/2013

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 019B

COC Description: Roof Flashing - Roof #10

Asbestos Type None Detected

% Other Fibrous Type

Non Fibrous Type

Color:

Homogeneous atment: Dissolved

Texture: Firm

Sample Number: 019C

%

COC Description: Roof Flashing - Roof #10

Asbestos Type None Detected

% Other Fibrous Type

100

ion Fibrous Type

Color: Black

Other Color

Homogenity: Homogeneous reatment: Dissolved Texture: Firm

Sample Number: 020A

COC Description: Roof Material - Roof #11

Asbestos Type

None Detected

Other Fibrous Typ

Non Fibrous Type

100

Color: Black

Other Color

Homogenity: Homogeneous

reatment: Healed Texture: Firm

Sample Number: 020B

COC Description: Roof Material - Roof #11

Asbestos Type

None Detected

Other Fibrous Type

Non Fibrous Type

100

LAB SAMPLE ID

69952

Color: Black

Other Color Homogenity: Homogeneous

reatment: Healed

Texture: Firm

This confidential report relates only to those ltem(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government. This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are aveilable upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that if not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 14 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013 78

Logged Ashley Mote

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 020C

COC Description: Roof Material - Roof #11

Asbestos Type None Detected

% Other Fibrous Type

100

Non Fibrous Type

Color:

tomogenity: Homogeneous

LAB SAMPLE ID

LAB SAMPLE ID

69954

atment: Healed Texture; Firm

Sample Number: 021A

10

COC Description: Roof Flashing - Roof #11

% **Asbestos Type** Chrysotile

% Other Fibrous Type

Ion Fibrous Type

Color: Black

Other Color

Homogenity: Homogeneous

'reatment: Dissolved Texture: Firm

Sample Number: 021B

COC Description: Roof Flashing - Roof #11

Asbestos Type Not Analyzed

Other Fibrous Typ

Non Fibrous Type

69955

Color:

LAB SAMPLE ID

Other Color

Homogenity:

reatment:

Texture:

Sample Number: 021C

COC Description: Roof Flashing - Roof #11

Asbestos Type Not Analyzed

Other Fibrous Type

Non Fibrous Type

LAB SAMPLE ID

69956

Color: Other Color

Homogenity: 'reatment

Texture:

This confidential report relates only to those liem(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small assestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannol be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with his method, Analysts pecific measurements of uncertainty at lower concentrations are evailable upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be enalyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 15 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof Re:

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013 78

Logged Ashley Mote

Analyzed Asghar Keyvanfar

Sample Number; 022A

COC Description: Roof Material - Roof #12

Asbestos Type

% Other Fibrous Type

None Detected

% Non Fibrous Type

100

LAB SAMPLE ID

Color:

Homogenity: Homogeneous

ment Heated

Texture: Firm

Sample Number: 022B

%

COC Description: Roof Material - Roof #12

Asbestos Type None Detected

% Other Fibrous Type

Ion Fibrous Type

LAB SAMPLE ID 69958

Color: Black

Homogenity: Homogeneous 'realment: Heated

Texture: Firm

Sample Number: 022C

COC Description: Roof Material - Roof #12

Asbestos Type

None Detected

% Other Fibrous Typ

100

LAB SAMPLE ID

69959

Color: Black

Other Color Homogenity: Homogeneous

reatment: Heated Texture: Firm

Sample Number: 023A

COC Description: Roof Shingle - Roof #12

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

Non Fibrous Type

90 Binder LAB SAMPLE ID

69960

Color: Purple

Other Color

Homogenity: Heterogeneous

reatment: Dissolved

Texture: Firm

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with Ihis method. Analysis specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 16 of 20



Lab Project Number: 9888

Recieved Ashley Mote

Logged Ashley Mote Analyzed Asghar Keyvanfar

Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

DHSS - EPBH - 1912 Building - Asbestos Roof Re:

Sample Number: 023B

COC Description: Roof Shingle - Roof #12

Asbestos Type

None Detected

% Other Fibrous Type

Glass

%

Non Fibrous Type

90 Binder LAB SAMPLE ID

1/30/2013 78

Monday, February 04, 2013

Homogenity: Helerogeneous

iment: Dissolved

Texture: Firm

Sample Number: 023C

COC Description: Roof Shingle - Roof #12

% **Asbestos Type** None Detected

Glass 10

Other Fibrous Type

Non Fibrous Type

Binder

LAB SAMPLE ID

69962

LAB SAMPLE ID 69963

Color: Purple

Other Color

Homogenity: Heterogeneous reatment: Dissolved

Texture: Firm

Sample Number: 024A

COC Description: Roof Felt Paper - Roof #12

Asbestos Type

None Detected

% Other Fibrous Typ

30 Cellulose Non Fibrous Type

Color: Black

Other Color

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 024B

COC Description: Roof Felt Paper - Roof #12

Asbestos Type

None Detected

Other Fibrous Type

Cellulose

% Non Fibrous Type

70

70

LAB SAMPLE ID

69964

Color: Black Other Color

Homogenity: Homogeneous

'reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NiST-NVLAP or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negality PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quentification at <1% by volume is possible with hits method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 17 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013 78

Logged Ashley Mote

1/31/2013

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 024C

COC Description: Roof Felt Paper - Roof #12

None Detected

Asbestos Type

% Other Fibrous Type

Cellulose

Non Fibrous Type

70

SAMPLE ID

ant: Dissolved

Texture: Firm

Sample Number: 025A

COC Description: Roof Material - Roof #12

% Asbestos Type Chrysotile

lon Fibrous Type Other Fibrous Type

Cellulose

69966

LAB SAMPLE ID

LAB SAMPLE ID 69967

LAB SAMPLE ID

Color: Black

Other Color

Homogenity: Homogeneous reatment: Dissolved Texture: Firm

Sample Number: 025B

2

COC Description: Roof Material - Roof #12

Asbestos Type

Not Analyzed

Other Fibrous Type

Non Fibrous Type

Color:

Other Color

Homogenity:

'reafment

Texture:

Sample Number: 025C

COC Description: Roof Material - Roof #12

Asbestos Type Not Analyzed

Other Fibrous Type

Non Fibrous Type

69968

Color:

Other Color Homogenity:

Texture:

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory LImil is based on the sample matrix. Quentification at <1% by volume is possible with this method. Analysts pecific measurements of uncertainty at fower concentrations are availations are availations are availations are availation. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. If not reperted or otherwise noted, layer is either not present or the citeral has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

Comments:

NVLAP Lab Code 200885-0

Approved For Releas

Page 18 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

19720-

DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/31/2013

Analyzed Asghar Keyvanfar

2/1/2013

Sample Number: 026A

5

COC Description: Roof Material - Roof #12

% Asbestos Type

Chrysotile

Other Fibrous Type Cellulose

90

Non Fibrous Type

Homogenity: Homogeneous

atment: Dissolved

Texture: Firm

Sample Number: 026B

COC Description: Roof Material - Roof #12

Not Analyzed

Asbestos Type

% Other Fibrous Type

on Fibrous

LAB SAMPLE ID

69970

LAB SAMPLE ID

Color:

Other Color Homogenity:

Texture:

Sample Number: 026C

COC Description: Roof Material - Roof #12

Asbestos Type

Not Analyzed

Other Fibrous Typ

Non Fibrous Type

LAB SAMPLE ID

69971

Color:

Other Color

Homogenity:

reatment:

Texture:

Sample Number: 001A

COC Description: Roof Material - Roof #1

Asbestos Type None Detected

Other Fibrous Type

Cellulose

% Non Fibrous Type

80

LAB SAMPLE ID

69972

Color: Black

Other Color Grey

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

This confidential report relates only to those liem(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, willout written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method, Analysts peedin measurements of uncertainty at lower concentrations are availations are availations. Analysts indicates ell distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 19 of 20



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12015

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

19720-

Re: DHSS - EPBH - 1912 Building - Asbestos Roof

Monday, February 04, 2013

Lab Project Number: 9888

QTY

Recieved Ashley Mote

1/30/2013 78

Logged Ashley Mote

1/31/2013 78

Analyzed Asghar Keyvanfar

2/1/2013 66

Sample Number: 001B

COC Description: Roof Material - Roof #1

%

Asbestos Type

None Detected

% Other Fibrous Type

20 Cellulose

% Non Fibrous Type

80

LAB SAMPLE ID

lor: Black

ther Color Grev

lomogenity: Homogeneo

Homogenity: Homogeneous

reatment: Dissolved
Texture: Firm

Sample Number: 001C

COC Description: Roof Material - Roof #1

% Asbestos Type

Type % Other Fibrous Type

5

None Detected

20 Cellulose

% Non Fibrous Type

LAB SAMPLE ID

69974

Color: Black

Other Color Grey

Homogenity: Homogeneous

'reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. gevernment.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample metrix. Quantification at <1% by volume is possible with this method. Analysts perfit measurements of uncertainty at tower concentrations are available upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 20 of 20



Issued: 5/21/09 Page ___ of ___ File ID: FS-001 Revision No. 3

Analytical Laboratory Name: Haward Enor Inc.

REPORT TO: Organization	nn'	, man, man, man, man, man, man, man, man	Invoice/Re	sults To:		PROJECT NO	12015
Address:	<u> </u>		Address:			PROJECT NA	ME: DHSS-EPBH
City:	State:	Zip Code:	City:	State:	Zip Code:		1912 BIDE,
ATTN: Mike Son	rdeis		ATTN:				wilm, DE
PHONE:	FAX:						m: (0) (0, 1)
Collected By: 0. 2000		1/30/13 Time: 13/0	REMARKS		· · · · · · · · · · · · · · · · · · ·	Same Day	Time (Circle One) 4 Hours 48 Hours
Relinquished By: 260	Date:	1/30/13 Time:14/30					Days 1 Week
Received By:	Date:	130 Time: 153				2 Weeks 3 OTHER	Hr Rush 6 Hr Rush
Received In Lab:		2-1-Mne:			V		
SAMPLE SYS ID CODE	OSSS Lab ID# (Lab Use Only)	DESCRIPTIONS		LOCATION	Analyze TEM	Results (Lab Use Only)	OTHER INSTRUCTIONS 1 2 3
001-A Rm	090,70 Ra	of material		Purp #1		MAD	
8	09973					W = 2	
ve v	19974					MAD	
002-A RF	09291 200	& Blosning	10	2001 #1		10 % CHRY	
B	~9298 T			- 4		-	
VeV	19899			V			
003-A Rm	19900 20	of motorial		Poct #2		was	
8	129901			1		~~	
VeV	19902	, X2		V		man	
OH-A MF	49903 me	chiancal fla	shing	2001 # 2		Mos	
B	109904	0		4		NAD	
V C V	69905					mm	
005-A RF	69906 22	& floshing	_	Roof #2		10 %. (624	
B	69903	1					·
VCV	69908	√		<u> </u>			
Release Results Via: Fax	Email 🗌 Verbal 📙 1	Го:	Date:		Time:	Signature:	



Issued: 5/21/09 Page **2** of **6**File ID: **F5-001** Revision No. **3**

#12015

1/20/13

	1			·	İ			
SAMF	LE ID	SYS CODE	Lab ID#	DESCRIPTIONS	LOCATION	No Layered Analysis	ABC Positive Stop If Megalive PLM Analyze TEM	1. 2. 3
		2,00	1,9909	Roof material	Poop#3	X		Way
000	5-A B	Rm	1,9910	,		2		MS
	/ C		1,991	V				NAO
00	7- A	BM	109910	loof material	Roof #4	-		MO
	B	<u> </u>	109913				/	Ma
	/: c	V	109914	V	4 26		<u> </u>	(0 %. cress
00	8-14	RF	19913	Roof flashing	2008 # 4			-
	B		19914					
	/ c	\ <u>\</u>	109764	2 4 4 : 0	Poop#5	-		mas
od	9-A	RM	1,09.91.8	2006 material				m
	B		109920					m
	V c	<u>V</u>	1,9901	Roof blashing	Post #5			Mas
01	0 - A	RF	In QQ QQ	7				~
	/ C		109933	V	\			MO



Issued: 5/21/09 Page <u>3</u> of <u>6</u>

File ID: FS 001 Revision No. 3

* 12015 1/30/13

		•						
SAMPLE ID	SYS CODE	Lab ID#	DESCRIPTIONS	LOCATION	No Layered Analysis	ABC Positive Stop	If Negative PLM Analyze TEM	OTHER INSTRUCTIONS 1. 2 3. 3.
		1,0000	Roof Material	Pool # 7		Ò		Was
OIL-A	Rm	199006	KOG Maceriae		2	~		ma
B		1,9984				~		MB
012-A	BM	69927	Roof material	200648	<u> </u>	./		mo
B	 	1 10000				~		m
V C	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	1,9921)	Took flashing	200f#8		~		Men
013-A B	RF_	19931	her prospersy			V		m
Ve	+	1,9930	V	V	 	~		MO
014-A	mF	1,9933	mechianes flashing	Poof#E	<u> </u>	r		mo mo
B		19934			+-	1 V	-	mp
Ve	\\ \\ _	1,0021	2 1 material	Roof #9		V	1	MAD
015-A	RM	1,9930	Roof Material			γ		Nos
B C	+-	19938		1 1		V		MHO



Issued: 5/21/09	Page 5 of 6
File ID: FS-001	Revision No. 3

#12015 1/30/13

SAMPLE ID	SYS CODE	Lab ID#	DESCRIPTIONS	LOCATION	Analysis ABC Positive Stop If Negative PLM Analyze TEM	1
021-A	RF	1,9954	Roof Clasning	Post #11)		10 %. CHAPS
8		49955				
Ve		69956	Took material	Ruof # 12		MAO
022-A B	Rm	69958	100/1100			Non
Ve		169959		V 14:0		Mado
023-A	R5	1,9960	Roof Shingle	200f#12		MB
V C		69968				mb
034-A	AFP	69963	for felt fager	2008 2 12		my
8		19910				noo
025-A	Bm_	1.99 lele	Boof Material	Doof#12		2%. CHAB
B		109918-				
V C		69964	<u>), </u>			

	· ·			÷
HAR				ľ
	• 7 ▲ :	5		в
1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	V/- /W	100		и
	V	LIAN X		ľ
				ŀ
Environm		12	F	
- F HVIFOIHI	em:	112.		
TILL LAW CALLE	~~~	7-		•

PLM CHAIN OF CUSTODY

 Issued:
 5/21/09
 Page 6 of 6

 File ID:
 FS-001
 Revision No. 3

12015 1/30/13

<u> </u>	<u>. </u>			7				
SAMPLE ID	SYS CODE	Lab ID#	DESCRIPTIONS	LOCATION	No Layered Analysis	ABC Positive Stop	If Negative PLM Analyze TEM	OTHER INSTRUCTIONS 1 2. 3.
026-A	Bun	69969	Roof material	Ring # 12		2		5 Y. CHAP
8		69970				7	<u>, </u>	
Ve	V	69911	V			<i>Y</i>	-	
		-	C					
			, V			_		
		Ó						,
		1,2			<u> </u>			
		17,						



760 Pulaski Highway Bear, DE 19701 1-302-326-2333

Emily P. Bissell Hospital Main Building

Asbestos Roof Inspections

Wilmington, DE

FINAL REPORT – 4/26/13 Harvard Project # 12016

Prepared For: Daniel Episcopo

State of Delaware Division of Facilities Management

1901 N. Dupont Highway New Castle, DE 19720

Prepared By: Harvard Environmental, Inc

760 Pulaski Highway Bear Delaware 19701 302-326-2333

Written By: Michael Sanders

Operations Manager

Harvard Environmental, Inc.

Released By: 6

President

Table Of Contents

Introductions & Executive Summary

Appendix A

Certifications & Accreditations

Homogeneous Characterizations Report

Appendix B

Appendix C

Schematic Diagrams/Sample Locations & Material Inventory Report

Appendix D

Laboratory Analysis

Introductions & Executive Summary

Harvard Environmental, Inc. herein presents data associated with inspections performed at the Main Building of the Emily P. Bissell Hospital located at 3000 Newport Gap Pike in Wilmington, DE 19808. This inspection was performed to provide compliance with 40 CFR Part 61, "Asbestos NESHAP. These Environmental Protection Agency, (EPA), regulations require inspections to be performed by certified asbestos building inspectors prior to renovations and/or demolition of facilities. This effort was performed at the request of State of Delaware Health & Social Services and Division of Facilities Management.

This project was performed in order to identify asbestos containing roofing materials that may impacted during future roofing repair projects to the Main Building. Harvard Environmental Inc, assessed the impacted building materials which would be considered suspect asbestos containing. A listing of locations, systems and/or materials which were not assessed may be found under "Non Assessed Conditions" found further in this report.

Harvard requested drawings of the existing facility layouts/designs to assist in documenting field assessments and to provide insight as to the location of suspect materials which may be associated with the facility. Floor plans of the facility were not available.

The last day of visitation to the site was performed on 1/29/13. Conditions described within this document are accurate as of the date of last visitation. Mr. Jeffrey Hogate was the responsible Harvard Environmental, Inc. employee which led the field efforts associated with the work.

Representative sampling of suspect asbestos building materials was performed on impacted building materials. The sampling effort was conducted in accordance with EPA regulations and industry accepted standards.

Asbestos analysis was completed utilizing Polarized Light Microscopy, (PLM). PLM utilizes an optical microscope equipped with a polarizing lens through which trained microscopist can identify asbestos fibers according to their crystalline structure. This method of analysis is recognized throughout the industry as standard practice. Prior to determining the type of fiber, the sample was placed under a "Stereo Microscope" at approximately 150X magnification for purposes of visual estimation. Various fiber types were pulled from the sample and oils applied to determine refractive indices under the polarized light microscope.

This recognized method of analysis has a detection limit of 1% by volume. Percentages of asbestos < 1% are reported as "trace" and are not considered asbestos containing materials under EPA regulations.

In order to best document the assessment, Harvard Environmental, Inc. assessed the layout and design of locations requiring assessment and assigned each geographic area a unique alpha/numeric "grid" identifier. These identifiers are specific locations of the assessment and are the basis for orientation of the data.

Based on the information provided to Harvard Environmental, Inc., coupled with field inspections and laboratory analysis of samples collected, asbestos was present on four (4) roof sections.

Provided is a summary listing of materials assessed under this inspection. The detailed inspection data is provided as appendices further in the report.

Summary Of Materials Assessed

ID	Material Description	Analytical Results	Quantity
001	Roof Material (EPDM Seam Caulk	No Asbestos Detected	576 SF
002	Roof Material (Modified Mop Down)	No Asbestos Detected	864 SF
003	Roof Material (EPDM Seam Caulk)	No Asbestos Detected	2,132 SF
004	Roof Material (EPDM Seam Tape)	No Asbestos Detected	3,825 SF
005	Roof Flashing	5% Chrysotile Asbestos	20 SF
006	Roof Material (EPDM Seam Caulk)	No Asbestos Detected	6,063 SF
007	Shingle Boards (Carei Tread) Green	No Asbestos Detected	192 SF
008	Shingle Boards (Carei Tread) Black	3% Chrysotile Asbestos	192 SF
009	Roof Flashing (Around Fan Units)	5% Chrysotile Asbestos	88 SF
010	Roof Material (EPDM Seam Tape)	No Asbestos Detected	300 SF
011	Roof Material	No Asbestos Detected	888 SF
012	Roof Material (Built up-F/G Felt)	No Asbestos Detected	2,295 SF
013	Roof Flashing	No Asbestos Detected	102 SF
014	Mechanical Flashing	No Asbestos Detected	20 SF
015	Roof Material (Built up F/G Felt)	No Asbestos Detected	2,600 SF
016	Roof Flashing	5% Chrysotile Asbestos	130 SF
017	Roof Material (Built up F/G Felt)	No Asbestos Detected	648 SF
018	Roof Flashing	10% Chrysotile Asbestos	10 SF
019	Roof Material (Built up)	No Asbestos Detected	132 SF

Non Assessed Conditions

Systems and/or materials provided on the list below were not assessed under this inspection and therefore should not be disturbed. In the event disturbance is required to accomplish the project objectives additional investigations will be required.

This inspection was limited to the roof areas and materials identified within the appendices of this
report.

Recommendations

Based on the findings of the inspection, Harvard Environmental, Inc. is providing the following recommendations.

- If over the course of project execution, materials of questionable content are discovered, or should the Scope of Work expand beyond the parameters communicated to Harvard Environmental, Inc., additional inspections will be required in order to maintain compliance with Federal and State regulations.
- Abatement of all asbestos containing building materials must be performed prior to any demolition or renovations of those areas containing the materials. Harvard Environmental, inc. can further assist your needs for compliance with state regulations regarding asbestos abatement projects.

This report is intended to provide "basic data" only. It is assumed that individuals reading and interpreting the sample locations and results, methods of analysis and hazards associated with the materials, are knowledgeable in all areas of discussion. Should any questions arise regarding the content of the information presented, contact should be exclusively to Harvard Environmental, Inc., Bear, Delaware, 1-302-326-2333. This document should be archived by the Owner for historical reference.

Certifications And Accreditations

Appendix A



IS HEREBY LICENSED TO PRACTICE, COMDUCT OR ENGAGE IN THE OCCUPATION OR BUSINESS ACTIVITY INDICATED ABOVE IN ACCORDANCE WITH THE LICENSE APPLICATION DILLY FILED PURSUANT TO TITLE 30, DEL CODE

BEAR DE 19701-5200

RICK T. CARTER



Certifications And Accreditations

CENTRAL DELAWARE TRAINING ACADEMY, INC.

JEFFREY W. HOGATE

has successfully completed EPA APPROVED

AHERA BUILDING INSPECTOR REFRESHER TRAINING

COURSE LENGTH 4 HOURS

on June 19th, Two Thousand-Twelve

CDTA P.O. BOX 1344 DOVER, DE 19903-1344 (302) 677-1534

EXAM DATE: 061912

DAVID TO STANLEY, PRESIDENT

RONALD S. HERCHA, VICE PRESIDENT

EXPIRE DATE: 061913 ID NUMBER CB120619-0083

United States Department of Commerce
National Institute of Standards and Technology

NVLAP®

Certificate of Accreditation to ISO/IEC 17025:2005

NVLAP LAB CODE: 200885-0

Harvard Environmental, Inc.

Bear, DE

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

BULK ASBESTOS FIBER ANALYSIS

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005.

This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2012-07-01 through 2013-06-30

Effective dates



For the National Institute of Standards and Technolog

NVLAP-01C (REV. 2009-01-28)

Homogeneous Characterizations Report

Appendix B

Emily P. Bissell Hospital

Asbestos Roof Inspection - Main Bldg.



Homogeneous Systems Report

				J			
Homogeneous System 001		576 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 001A	RM 001B	RM 001C			
No Asbestos Detected	Collection Point Grid	R-1	R-1	R-1	VO'		
Description Roof Material (EPDM Seam Caulk	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected	Q-		
Homogeneous System 002		864 SF	■ Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 002B	RM 002B	RM 002C			
No Asbestos Detected	Collection Point Grid	R-2	R-2	R-2			
Description Roof Material (Modified Mop Down)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Aspestos Detected			
Homogeneous System 003		2132 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 003A	RM 003B	RM 003C			
No Asbestos Detected	Collection Point Grid	R-3	R-3	R-3			
Description Roof Material (EPDM Seam Caulk)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			

Notes

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Emily P. Bissell Hospital

Asbestos Roof Inspection - Main Bldg.



Homogeneous Systems Report

Homogeneous System 004		3825 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 004A	RM 004B	RM 004C		,	
No Asbestos Detected	Collection Point Grid	R-4	R-4	R-4	V)		
Description Roof Material (EPDM Seam Tape)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected	Q-		
Homogeneous System 005		20 SF	✓ Asbestos	PACM	Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 005A	RF 005B	RF 005C			
5% Chrysotile Asbestos	Collection Point Grid	R-4	R-4	R-4			
Description Roof Flashing - Roof #4	Analytical Results	5% Chrysotile Asbestos	Sample Not Analyzed	Sample Not Analyzed			
Homogeneous System 006		6063 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 006A	RM 006B	RM 006C			
No Asbestos Detected	Collection Point Grid	R-8	R-8	R-8			
Description Roof Material (EPDM Seam Caulk)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			

Notes:

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Emily P. Bissell Hospital

Asbestos Roof Inspection - Main Bldg.



Homogeneous Systems Report

T				-			
Homogeneous System 007		192 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM OO7A	RM 007B	RM 007C			
No Asbestos Detected	Collection Point Grid	R-8	R-8	R-8	()		
Description Shingle Boards (Carei Tread) Green	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected	Q-		
Homogeneous System 008		192 SF	✓ Asbestos	PACM	Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 008A	RM 008B	RM 008C			
3% Chrysotile Asbestos	Collection Point Grid	R-8	R-8	R-8			
Description Shingle Boards (Carei Tread) Black	Analytical Results	No Asbestos Detected	3% Chrysotile Asbestos	Sample Not Analyzed			
Homogeneous System 009		88 SF	✓ Asbestos	PACM	Non-Asbestos	■ Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 009A	RF 009B	RF 009C			
5% Chrysotile Asbestos	Collection Point Grid	R-8	R-8	R-8			
Description oof Flashing (Around Fan Units)	Analytical Results	5% Chrysotile Asbestos	Sample Not Analyzed	Sample Not Analyzed			

Notes

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Emily P. Bissell Hospital

Asbestos Roof Inspection - Main Bldg.



Homogeneous Systems Report Homogeneous System 300 SF Asbestos PACM ✓ Non-Asbestos ✓ Non-Friable Friable 010 Sample Identification RM 010A RM 010B RM 010C **Analytical Results** No Asbestos Detected **Collection Point Grid** R-9 R-9 R-9 Description **Analytical Results** No Asbestos No Asbestos No Asbestos Roof Material (EPDM Seam Detected Detected Detected Tape) Homogeneous System 888 SF Asbestos PACM ✓ Non-Asbestos Friable ✓ Non-Friable 011 RM 0110 Sample Identification RM 011A RM 011B **Analytical Results** No Asbestos Detected R-7 R-7 **Collection Point Grid** Description **Analytical Results** No Asbestos No Asbestos Roof Material Detected Detected Detected Homogeneous System SF Asbestos PACM ✓ Non-Asbestos Friable ✓ Non-Friable 2295 012 RM 012C Sample Identification RM 012A RM 012B **Analytical Results** No Asbestos Detected **Collection Point Grid** R-15 R-15 Description **Analytical Results** No Asbes No Asbestos No Asbestos Roof Material (Built up-F/G Felt) Detected Detected Homogeneous System SF PACM ✓ Non-Asbestos Friable ✓ Non-Friable 102 Asbestos 013 RF 013A Sample Identification RF 013B RF 013C **Analytical Results** No Asbestos Detected **Collection Point Grid** R-15 R-15 R-15 Description **Analytical Results** No Asbestos No Asbestos No Asbestos Roof Flashing Detected Detected Detected

Notes:

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed

Emily P. Bissell Hospital

Asbestos Roof Inspection - Main Bldg.



		1	Homogeneous S	systems Report		O_{II}	
Homogeneous System 014		20 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	MF 014A	MF 014B	MF 014C			
No Asbestos Detected	Collection Point Grid	R-15	R-15	R-15	V)		
Description Mechanical Flashing	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected	Q-		
Homogeneous System 015		2600 SF	■ Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 015A	RM 015B	RM 015C			
No Asbestos Detected	Collection Point Grid	R-16	R-16	R-16			
Description Roof Material (Built up F/G Felt)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Aspestos Detected			
Homogeneous System 016		130 SF	✓ Asbestos	PACM	Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 016A	RF 016B	RF 016C			
5% Chrysotile Asbestos	Collection Point Grid	R-16	R-16	R-16			
Description Roof Flashing	Analytical Results	5% Chrysotile Asbestos	Sample Not Analyzed	Sample Not Analyzed			
Homogeneous System 017		648 SF	Asbestos	PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 017A	RM 017B	RM 017C			
No Asbestos Detected	Collection Point Grid	R-17	R-17	R-17			
Description Roof Material (Built up F/G Felt)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			

Notes

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Emily P. Bissell Hospital

Asbestos Roof Inspection - Main Bldg.



		H	Homogeneous S	ystems Report	<		
Homogeneous System 018		10 SF	✓ Asbestos	PACM	Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RF 018A	RF 018B	RF 018C			
10% Chrysotile	Collection Point Grid	R-17	R-17	R-17	V).		_
Description Roof Flashing	Analytical Results	10% Chrysotile Asbestos	Sample Not Analyzed	Sample Not Analyzed	Q-		
Homogeneous System 019		132 SF	■ Asbestos	■ PACM	✓ Non-Asbestos	Friable	✓ Non-Friable
Analytical Results	Sample Identification	RM 019A	RM 019B	RM 019C			
No Asbestos Detected	Collection Point Grid	R-17	R-17	R-17			
Description Roof Material (Built up)	Analytical Results	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected			
Homogeneous System NAS			Asbestos	PACM	✓ Non-Asbestos	Friable	Non-Friable
Analytical Results	Sample Identification						
No Asbestos Detected	Collection Point Grid						
Description To Asbestos Suspected in the Roofing Materials	Analytical Results						

Notes

^{1. &}quot;Total Materials" reflects the quantity of materials evaluated under this assessment. This value may not reporesent a complete inventory of all materials associated with a system, grid or building. Reference should be made to the descriptions provided in the "Executive Summary", to qualify the value indicated in this field. If no value is provided in this field, quantification of the material was not performed.

^{2. &}quot;PACM" - Presumed Asbestos Containing Material - Sampling Not Performed.

Schematic Diagrams/Sample Locations & Material Inventory Report

Appendix C

Grid Descriptions

R-1	Roof	18x32-EPDM over lightweight concrete-new
R-10	Roof	8x10-EPDM-no seam-1 sheet-not sampled
R-11	Roof	6x10-EPDM-no seam-1 sheet-not sampled
R-12	Roof	12x54-built up-F/G felt-2" Perlite-1" ISO-concrete deck
R-13	Roof	8x13-EPDM-new roof per PRS-no seam-not sampled
R-14	Roof	VOID-part of 1912 Bldg. roof
R-15	Roof	51x45-built up-F/G felt-lightwerght fill-concrete deck
R-16	Roof	40x65-built up-F/G felt-lightweight-concrete fill deck
R-17	Roof	6x22built up o/concrete deck
R-2	Roof	24x36-modified roof-metal.deck-2" ISO-1" Perlite-2 ply + cap mop down
R-3	Roof	41x52 / EPDM-1* 180 o/(DENSDECK)
R-4	Roof	75x51-EPDM-(Seam Tape) over 4 1/2" ISO- (DENSDECK) stone covered
R-5	Roof	12x17-EPDM-Seam tape over 4 1/2" ISO- (DENSDECK) stone covered-not sampled
R-6	Roof	17x17-no samples-New EPDM roof per PRS
R-7	Roof	25x32-modified mop down-concrete deck-7" ISO-1" Perlite-3 Ply w/cap
R-8	Roof	129x47-EPDM-concrete deck-lightweight fabric- stone covered-6x16x2 (carei board)
R-9	Roof	20x46-EPDM-vapor retarder poly-1 1/2" ISO-metal deck



Materials Inventory Report

Grid		Homogeneous	Material	Description	Quanti	ty	Analytical Results	
R-1	Roof RM			Roof Material (EPDM Seam Caulk	576 SF		No Asbestos Detected	
R-10	Roof							
	NAS	NAS		No Asbestos Suspected in the Roofing Materials			No Asbestos Detected	
R-11	Roof							
	NAS	NAS		No Asbestos Suspected in the Roofing Materials	<	9,	No Asbestos Detected	
R-12	Roof							
	RM	017	Misc. Material	Roof Material (Built up F/G Felt)	648	SF	No Asbestos Detected	
R-13	Roof							
	NAS	NAS		No Asbestos Suspected in the Roofing Materials			No Asbestos Detected	
R-14	Roof							
	NAS	NAS		No Asbestos Suspected in the Roofing Materials			No Asbestos Detected	
R-15	Roof							
	RM	012	Misc. Material	Roof Material (Built up-F/G Felt)	2295	SF	No Asbestos Detected	
_	RF	013	Misc. Material	Roof Flashing	102	SF	No Asbestos Detected	
_	MF	014	Misc. Material	Mechanical Flashing	20	SF	No Asbestos Detected	
R-16	Roof							
	RM	015	Misc. Material	Roof Material (Built up F/G Felt)	2600	SF	No Asbestos Detected	
_	RF	016	Misc. Material	Roof Flashing	130	SF	5% Chrysotile Asbestos	
R-17	Roof							
	RF	018	Misc. Material	Roof Flashing	10	SF	10% Chrysotile	
_	ROP	019	Misc. Material	Roof Material (Built up)	132	SF	No Asbestos Detected	



Materials Inventory Report

Grid	System Homogeneous		Material	Description	Quanti	ty	Analytical Results
R-2	Roof						
	RM	002	Misc. Material	Roof Material (Modified Mop Down)	864	SF	No Asbestos Detected
R-3	Roof						
	RM	003	Misc. Material	Roof Material (EPDM Seam Caulk)	2132	SF	No Asbestos Detected
R-4	Roof						
	RM	004	Misc. Material	Roof Material (EPDM Seam Tape)	3825	SF	No Asbestos Detected
_	RF	005	Misc. Material	Roof Flashing - Roof #4	20	SF	5% Chrysotile Asbestos
R-5	Roof						
	NAS	NAS		No Asbestos Suspected in the Roofing Materials			No Asbestos Detected
R-6	Roof						
	NAS	NAS		No Asbestos Suspected in the Roofing Materials			No Asbestos Detected
R-7	Roof						
	RM	011	Misc. Material	Roof Material	888	SF	No Asbestos Detected
R-8	Roof						
	RM	006	Misc. Material	Roof Material (EPDM Seam Caulk)	6063	SF	No Asbestos Detected
_	RM	007	Misc. Material	Shingle Boards (Carei Tread) Green	192	SF	No Asbestos Detected
_	RM	008	Misc. Material	Shingle Boards (Carei Tread) Black	192	SF	3% Chrysotile Asbestos
	RF	009	Misc. Material	Roof Flashing (Around Fan Units)	88	SF	5% Chrysotile Asbestos
R-9	Roof						
-]	RM	010	Misc. Material	Roof Material (EPDM Seam Tape)	300	SF	No Asbestos Detected

General Notes:

- 1. Presentation of information is based on best available information. Drawing schematics were provided to Harvard Environmental by the State of Delaware.
- 2. Project #12016 involved asbestos inspections for purposes of identifying asbestos roofing materials located on the Main Building. These Drawings are not to be considered to scale and are intended to be used for orientation purposes only and identifying the locations of roofing sections and bulk samples.

Legend:

(R-1) Roof Grid ID

PLM Bulk Sample Location

State of Delaware Office Of Management & Budget



Rew By: MPS Dwg By: WJTM

4-26-13 PF-12016

DWG 1 of 2

Emily P. Bissell Hospital Main Building Asbestos Roof Inspection PLM Bulk Sample Locations

General Notes:

- Presentation of information is based on best available information. Drawing schematics were provided to Harvard Environmental by the State of Delaware.
- 2. Project #12015 involved asbestos inspections for purposes of identifying asbestos roofing materials located on the Main Building. These Drawings are not to be considered to scale and are intended to be used for orientation purposes only and identifying the locations of ACM.

Legend:



Asbestos Roof Flashing Tar 440 Total SF



DHSS-DPH
Emily P. Bissell Hospit
3000 Newport Gap Pik

Rew By: MPS
Dwg By: WJTM
4-26-13

PF-12016 DWG 2 of 2

Emily P. Bissell Hospital Main Building Asbestos Roof Inspection ACM Locations

> Environmental, Inc. 760 Pulaski Highway Bear, Delawer 19701

Laboratory Analysis

Appendix D



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 001A

COC Description: Roof Material - Roof #1

None Detected

Asbestos Type

% Other Fibrous Type

Non Fibrous Type

100

LAB SAMPLE ID

lomogenity: Homogeneous

stment: Heated

Texture: Firm

Sample Number: 001B

COC Description: Roof Material - Roof #1

None Detected

Asbestos Type

% Other Fibrous Type

Non Fibrous Type

LAB SAMPLE ID 69831

Color: Black

Homogenity: Homogeneous

'realment: Healed

Other Color

Texture: Firm

Sample Number: 001C

COC Description: Roof Material - Roof #1

Asbestos Type

None Detected

Other Fibrous Type

100

Non Fibrous Type

Color: Black

Other Color Homogenity: Homogeneous

LAB SAMPLE ID

69832

LAB SAMPLE ID 69833

'reatment: Heated Texture: Firm

Sample Number: 002A

COC Description: Roof Material - Roof #2

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

Binder 95

Color: Black

Other Color

Homogenity: Heterogeneous

'reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. govern.
This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming lectnique, Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analysts specific measurements of uncertainty at lower concentrations are availations are availations are availations are availations are availation and the properties of order to be a supported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 1 of 15



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 002B

COC Description: Roof Material - Roof #2

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

Binder 95

LAB SAMPLE ID

lomogenity: Heterogeneous

alment: Dissolved Texture: Firm

Sample Number: 002C

COC Description: Roof Material - Roof #2

Asbestos Type

None Detected

Other Fibrous Type

Glass

on Fibrous

Binder

LAB SAMPLE ID 69835

Color: Black

Other Color

Homogenity: Heterogeneous 'realment: Dissolved

Texture: Firm

Sample Number: 003A

COC Description: Roof Material - Roof #3

Asbestos Type

None Detected

Other Fibrous Type

Non Fibrous Type

Color: Black

Other Color

Homogenity: Homogeneous

LAB SAMPLE ID 69836

LAB SAMPLE ID 69838

reatment: Heated Texture: Firm

Sample Number: 003B

COC Description: Roof Material - Roof #3

Asbestos Type

None Detected

Other Fibrous Type

100

100

Non Fibrous Type

Color: Black

Other Color

Homogenity: Homogeneous

'reatment: Healed

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be gueranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

Approved For Releas

NVLAP Lab Code 200885-0

Page 2 of 15



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 003C

COC Description: Roof Material - Roof #3

Asbestos Type

None Detected

Other Fibrous Type

Non Fibrous Type

100

LAB SAMPLE ID

Homogenity: Homogeneous

Texture: Firm

Sample Number: 004A

COC Description: Roof Material - Roof #4

None Detected

Asbestos Type

Other Fibrous Type

Glass

Ion Fibrous

Binder

LAB SAMPLE ID

69840

Color: Black

Other Color

Homogenity: Heterogeneous

reatment: Heated Texture: Firm

Sample Number: 004B

COC Description: Roof Material - Roof #4

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

Binder

69841

LAB SAMPLE ID

Color: Black

Other Color Homogenity; Heterogeneous

reatment: Heated Texture: Firm

Sample Number: 004C

COC Description: Roof Material - Roof #4

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

Binder

LAB SAMPLE ID

69842

Color: Black

Other Color

Homogenity: Heterogeneous

reatment: Heated

Texture: Firm

This confidential report relates only to those liem(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be repreduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concontrations are available upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 3 of 45



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 005A

5

COC Description: Roof Flashing - Roof #4

% Asbestos Type Chrysotile

% Other Fibrous Type

Non Fibrous Type

95

Texture: Firm

alment: Dissolved

Sample Number: 005B

COC Description: Roof Flashing - Roof #4

Asbestos Type Not Analyzed

% Other Fibrous Type

lon Fibrous

LAB SAMPLE ID

69844

LAB SAMPLE ID 69845

LAB SAMPLE ID

Color:

Other Color Homogenity:

realment:

Texture:

Sample Number: 005C

COC Description: Roof Flashing - Roof #4

Asbestos Type Not Analyzed

Other Fibrous Type

Non Fibrous Type

Other Color

Homogenity:

reatment:

Texture:

Sample Number: 006A

COC Description: Roof Material - Roof #8

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

97 Binder LAB SAMPLE ID

69846

Color: Black

Other Color

Homogenity: Helerogeneous

reatment: Healed

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NtST-NVLAP or any agency of the U.S. govornment This report shall not be reproduced except in full, without written approval of the laboratory

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 4 of 15



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 006B

COC Description: Roof Material - Roof #8

Asbestos Type

None Detected

% Other Fibrous Type

Glass

Non Fibrous Type

97 Binder LAB SAMPLE ID

lomogenity: Heterogeneous

itment: Healed Texture: Firm

Sample Number: 006C

COC Description: Roof Material - Roof #8

None Detected

Asbestos Type

Other Fibrous Type

Glass

on Fibrous Type

Binder

LAB SAMPLE ID

69848

LAB SAMPLE ID 69849

Color: Black

Other Color

Homogenity: Heterogeneous

reatment: Heated Texture: Firm

Sample Number: 007A

COC Description: Roof Material - Roof #8

Asbestos Type

None Detected

Cellulose 3

Other Fibrous Type

Glas

Non Fibrous Type

Binder

Color: Black

Other Color

Homogenity: Heterogeneous

reatment: Dissolved

Texture: Firm

Sample Number: 007B

COC Description: Roof Material - Roof #8

Asbestos Type

None Detected

Other Fibrous Type

Cellulose

Glass

Non Fibrous Type

95 Binder 69850

LAB SAMPLE ID

Color: Black

Other Color

Homogenity: Heterogeneous

'reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted. Tayer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 5 of 15



760 Pulaski Highway

Bear, Delaware 19701

Phone: 302-326-2333 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

Logged Ashley Mote

1/30/2013 1/30/2013

LAB SAMPLE ID

LAB SAMPLE ID 69852

LAB SAMPLE ID

69853

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 007C

COC Description: Roof Material - Roof #8

Asbestos Type

None Detected

Other Fibrous Type

Cellulose 3

Glass

Non Fibrous Type

95 Binder Color:

omogenity: Heterogeneous

atment: Dissolved Texture: Firm

Sample Number: 008A

COC Description: Roof Material - Roof #8

Asbestos Type

None Detected

Other Fibrous Type

3 Cellulose

2 Glass

Color: Black

Other Color

Homogenity: Heterogeneous

reatment: Dissolved

Texture: Firm

Sample Number; 008B

3

COC Description: Roof Material - Roof #8

Asbestos Type

Chrysotile

Other Fibrous Type

Glass

Non Fibrous Type

Binder

on Fibrous Type

Binder

Color: Black

Other Color

Homogenity: Heterogeneous

'reatment: Dissolved

Texture: Firm

Sample Number: 008C

COC Description: Roof Material - Roof #8

Asbestos Type Not Analyzed

Other Fibrous Type

Non Fibrous Type

LAB SAMPLE ID

69854

Color:

Other Color

Homogenity:

'realment:

Texture:

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbostos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample metrix. Quantification at <1% by volume is possible with this method. Analysis specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable tayers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that if not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 6 of 15



760 Pulaski Highway

Bear, Delaware 19701

Phone: 302-326-2333 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 009A

COC Description: Roof Flashing - Roof #8

5

Asbestos Type

Chrysotile

% Other Fibrous Type

% Non Fibrous Type

95

LAB SAMPLE ID

łomogenity; Homogeneous

itment: Dissolved Texture; Firm

Sample Number: 009B

COC Description: Roof Flashing - Roof #8

Asbestos Type

Not Analyzed

% Other Fibrous Type

Fibrous Type

LAB SAMPLE ID 69856

Color:

Other Color

Homogenity: reatment:

Texture:

Sample Number: 009C

COC Description; Roof Flashing - Roof #8

Asbestos Type

Not Analyzed

Other Fibrous Type

Non Fibrous Type

69857

LAB SAMPLE ID

LAB SAMPLE ID

69858

Color: Other Color

Homogenity:

reatment:

Texture:

Sample Number: 7

COC Description: Roof Material - Roof #9

Asbestos Type

None Detected

Other Fibrous Type

% 100 Non Fibrous Type

Other Color

Homogenity: Homogeneous

reatment: Heated

Color: Black

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments

(PC) Indicates Point Count Method performed, Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negetive PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncartainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the citient has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 7 of 15



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

Logged Ashley Mote

1/30/2013

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

LAB SAMPLE ID

Sample Number: 010B

COC Description; Roof Material - Roof #9

Asbestos Type

None Detected

% Other Fibrous Type

% Non Fibrous Type

100

Color:

lomogenity; Homogeneous

Heated Texture: Firm

Sample Number: 010C

COC Description: Roof Material - Roof #9

Asbestos Type None Detected

Other Fibrous Type

on Fibrous

LAB SAMPLE ID 69860

Color: Black

Other Color

Homogenity: Homogeneous restment. Heated

Texture: Firm

Sample Number: 011A

COC Description: Roof Material - Roof #7

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

Binder

Color: Black

Other Color

Homogenity: Helerogeneous

'reatment: Dissolved

Texture: Firm

Sample Number: 011B

COC Description: Roof Material - Roof #7

Asbestos Type None Detected

Other Fibrous Type

Glass

Non Fibrous Type

95 Binder LAB SAMPLE ID

LAB SAMPLE ID

69861

69862

Color: Black

Other Color

Homogenity: Helerogeneous

'maiment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written appreval of the laboratory.

Analysis Method: EPA 600/R-93/116

Comments:

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted. layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 8 of 15



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 011C

COC Description: Roof Material - Roof #7

Asbestos Type

% Other Fibrous Type

None Detected

Glass

Non Fibrous Type %

95 Binder LAB SAMPLE ID

omogenity: Helerogeneous

tment: Dissolved

Texture: Firm

Sample Number: 012A

COC Description: Roof Material - Roof #15

None Detected

Asbestos Type

Other Fibrous Type

Glass

on Fibrous Type

Binder

LAB SAMPLE ID 69864

Color: Black

Other Color

Homogenity: Heterogeneous reatment: Dissolved

Texture: Firm

Sample Number: 012B

COC Description: Roof Material - Roof #15

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

Binder

69865

LAB SAMPLE ID

Color: Black

Other Color

Homogenity: Heterogeneous reatment: Dissolved

Texture: Firm

Sample Number: 012C

COC Description: Roof Material - Roof #15

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

95 Binder LAB SAMPLE ID

69866

Color: Black

Other Color

Homogenity: Helerogeneous

Texture: Firm

reatment: Dissolved

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government
This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample metrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysts indicates all distinct separable levers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 9 of 15



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mir Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 013A

COC Description: Roof Flashing - Roof #15

Asbestos Type

None Detected

Other Fibrous Type

Glass

% Non Fibrous Type

97 Binder LAB SAMPLE ID

mogenity: Helerogeneous

Iment: Dissolved

Texture: Firm

Sample Number: 013B

COC Description: Roof Flashing - Roof #15

Asbestos Type None Detected

Other Fibrous Type

Glass

on Fibrous Type

Binder

LAB SAMPLE ID

69868

Color: Black

Other Color

Homogenity: Helerogeneous reatment: Dissolved

Texture: Firm

Sample Number: 013C

COC Description: Roof Flashing - Roof #15

Asbestos Type

None Detected

Other Fibrous Type

Glass

Non Fibrous Type

Binder

Color: Black

Other Color

Homogenity: Heterogeneous

LAB SAMPLE ID

69869

reatment: Dissolved

Texture: Firm

Sample Number: 014A

COC Description: Mechanical Flashing - Roof #15

Asbestos Type None Detected

Other Fibrous Type

Non Fibrous Type

100

LAB SAMPLE ID

69870

Color: Black

Other Color Silver

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.
This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed untess stated. Small asbesios fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analysi specific measurements of uncertainty at lower concentrations are available upon request. Analysis Indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 10 of 15



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

LAB SAMPLE ID

Sample Number: 014B

COC Description: Mechanical Flashing - Roof #15

None Detected

Asbestos Type

% Other Fibrous Type

Non Fibrous Type %

100

ogenity: Homogeneous

alment: Dissolved

Texture: Firm

Sample Number: 014C

COC Description: Mechanical Flashing - Roof #15

Asbestos Type None Detected

% Other Fibrous Type

on Fibrous Type

69872 Color: Black

LAB SAMPLE ID

Other Color Silver

Homogenity: Homogeneous reatment: Dissolved

Texture: Firm

Sample Number: 015A

COC Description: Roof Material - Roof #16

Asbestos Type

None Detected

Other Fibrous Type

Non Fibrous Type

69873

Color: Black

LAB SAMPLE ID

Homogenity: Homogeneous reatment: Dissolved

Texture: Firm

Sample Number: 015B

COC Description: Roof Material - Roof #16

Asbestos Type None Detected

Other Fibrous Type

Non Fibrous Type

100

100

LAB SAMPLE ID

69874

Color: Black

Other Color

Homogenity: Homogeneous

realment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncartainty at lower concentrations are available upon request. Analysts indicates all distinct separable layers (n accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 11 of 15



Bear, Delaware 19701

Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway

New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 015C

COC Description: Roof Material - Roof #16

Asbestos Type

None Detected

% Other Fibrous Type

Non Fibrous Type %

LAB SAMPLE ID

Other Color

lomogenity: Homogeneous

tment: Dissolved Texture: Firm

Sample Number: 016A

5

COC Description: Roof Flashing - Roof #16

Asbestos Type Chrysotile

% Other Fibrous Type

on Fibrous

100

LAB SAMPLE ID

69876

Color: Black

Homogenity: Homogeneous

'reatment: Dissolved

Texture: Firm

Sample Number: 016B

COC Description: Roof Flashing - Roof #16

Asbestos Type

Not Analyzed

Other Fibrous Type

Non Fibrous Type

LAB SAMPLE ID

69877

Color:

Other Color Homogenity:

realment:

Texture:

Sample Number: 016C

COC Description: Roof Flashing - Roof #18

Asbestos Type Not Analyzed

Other Fibrous Type

Non Fibrous Type

LAB SAMPLE ID

69878

Color:

Other Color

Homogenity:

reatment: Texture:

Analysis Method: EPA 600/R-93/116

(PC) Indicates Poial Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analyst specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NYLAP or any agency of the U.S. government.

This report shall not be reproduced except in tult, without written approval of the laboratory.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 12 of 15



Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

19720-

DHSS - EPBH - Main Building - Asbestos Roof

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013

Logged Ashley Mote

1/30/2013

Analyzed Asghar Keyvanfar

1/30/2013

Sample Number: 017A

COC Description: Roof Material - Roof #12

Asbestos Type

Other Fibrous Type

None Detected

Glass

% Non Fibrous Type

90 Binder LAB SAMPLE ID

lomogenity: Heterogeneous atment: Dissolved

Texture: Firm

Sample Number: 017B

COC Description: Roof Material - Roof #12

Asbestos Type

None Detected

% Other Fibrous Type

10 Glass on Fibrous

Binder

LAB SAMPLE ID

69880

LAB SAMPLE ID 69881

LAB SAMPLE ID 69882

Color: Black

Other Color

Homogenity: Heterogeneous

'reatment: Dissolved

Texture: Firm

Sample Number: 017C

COC Description: Roof Material - Roof #12

Asbestos Type

None Detected

Other Fibrous Type

10 Glass

Binder

Non Fibrous Type

Other Color

Homogenity; Heterogeneous

Color: Black

reatment: Dissolved

Texture: Firm

Sample Number: 018A

COC Description: Roof Flashing - Roof #17

% **Asbestos Type**

10 Chrysotile Other Fibrous Type

90

Non Fibrous Type

Color: Black

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be gueranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification et <1% by volume is possible with this method. Analysis specific measurements of uncertainty at lower concentrations are available upon request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 13 of 15



Lab Project Number: 9883

Recieved Ashley Mote

Logged Ashley Mote

Analyzed Asghar Keyvanfar

Bear, Delaware 19701 Fax: 302-326-2335

1/30/2013

1/30/201

1/30/2013

LAB SAMPLE ID

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

DHSS - EPBH - Main Building - Asbestos Roof

Sample Number: 018B

COC Description: Roof Flashing - Roof #17

Asbestos Type

Not Analyzed

% Other Fibrous Type

Non Fibrous Type

Color

Thursday, January 31, 2013

Sample Number: 018C

COC Description: Roof Flashing - Roof #17

Asbestos Type

Not Analyzed

% Other Fibrous Type

on Fibrous Type

LAB SAMPLE ID

69884

Color:

Other Color

Homogenity: reatment:

Texture:

Sample Number: 019A

COC Description: Roof Material - Roof #17

Asbestos Type

None Detected

Other Fibrous Type

Cellulosa

Non Fibrous Type

90

69885

LAB SAMPLE ID

Color; Black

Other Color

Homogenity: Homogeneous

'realment: Dissolved

Texture: Firm

Sample Number: 019B

COC Description: Roof Material - Roof #17

Asbestos Type None Detected

Other Fibrous Type

Non Fibrous Type

100

LAB SAMPLE ID

69886

Color: Black Other Color

Homogenity: Homogeneous

reatment: Dissolved

Texture: Firm

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Analysis Method: EPA 600/R-93/116

(PC) indicates Point Count Method performed. Method not performed unless stated, Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method, Analysts perific measurements of uncertainty at lower concentrations are available upon request. Analysts indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed.

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 14-of 15



760 Pulaski Highway Phone: 302-326-2333

Bear, Delaware 19701 Fax: 302-326-2335

CERTIFICATE OF ANALYSIS

12016

To: Mr Danny Episcopo

DHSS - Div of Facilities Mgmt

1901 North DuPont Highway New Castle, DE

DHSS - EPBH - Main Building - Asbestos Roof

Sample Number: 019C

COC Description: Roof Material - Roof #17

Asbestos Type

Thursday, January 31, 2013

Lab Project Number: 9883

Recieved Ashley Mote

1/30/2013 5

Logged Ashley Mote

Non Fibrous Type

1/30/201

Analyzed Asghar Keyvanfar

LAB SAMPLE ID

tment: Dissolved

Texture: Firm

None Detected

% Other Fibrous Type

100

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory

Analysis Method: EPA 600/R-93/116

(PC) Indicates Point Count Method performed. Method not performed unless stated. Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, negative PLM results cannot be guaranteed. Electron Microscopy can be used as a confirming technique. Regulatory Limit is based on the sample matrix. Quantification at <1% by volume is possible with this method. Analysis specific measurements of uncertainty at lower concentrations are evailations are availation on request. Analysis indicates all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed. Comments:

Asghar Keyvanfar

Analyst

NVLAP Lab Code 200885-0

Approved For Releas

Page 15 of 15



Issued: 5/21/09 Page 1 of 4

File ID: **FS-001** Revision No. 3

Analytical Laboratory Name: Howard Env. mc PROJECT NO: 12016 Invoice/Results To: **REPORT TO:** Organization: PROJECT NAME: DHSS- EPBH-Address: Address: wilm, DE Zip Code: City: State: Zip Code: State: ATTN: mike scenders
FAX: ATTN: PHONE: Turn Around Time (Circle One) REMARKS Collected By: J. Noccol Date: 1/24/13 Time: 1626 Same Day 24 Hours 48 Hours 72 Hours 4 Days 1 Week Relinquished By: A. 2kgc.Co Date: 129/13 Time: 1702 2 Weeks 3 Hr Rush 6 Hr Rush Received By: Date: 1/30 Time: 822 OTHER _____ Received In Lab: OTHER INSTRUCTIONS Results LOCATION DESCRIPTIONS SAMPLE SYS (Lab Use Only) CODE (Lab Use Only) 1D WAD Root material Rm OOI-A В W Roof material WM 002-A MO B گ 2006 material 20L#3 M 003-A m) NO Rock material Mo RM OCH-A 5 % cons Rub#4

Release Results Via: Fax Email Verbal To: ______ Date: _____ Time: _____ Signature:____



Issued: 5/21/09 Page **2** of **4**File ID: **FS-001** Revision No. **3**

12016 1/29/13

i							75110
SAMPLE ID	SYS CODE	Lab ĮD#	DESCRIPTIONS	LOCATION	No Layered Analysis	ABC Positive Stop	OTHER INSTRUCTIONS 1. 2. 3.
		1000211	Roof Material	Puol #8			mag
006-A	RM	1.00 N 47	KOOZ MOLENCE			/	Wa
B	_	1.087848			•	/	mo
V C	Bm.	1 9 84849	Boof material	Publ = 8		/	MO
007-A	h///	1,904950				/	m)
		1.98385				/	mab
10		1,085	2006 material	2005 # 8		/	Mas
008-A	am	1.9 (2)	KOOS MICH			/	3 1. CM15
B		190581				/	
V C	 	1,000	Roof Blashing	Poop#8		✓	5 4. cust
009 - A	RF	1.00EX	Roof Glashing			/	
: B		1000				/	,
V C	<i>\</i>	1,000	2006 material	2vob#9		/	mo
010-A	RM	UYSON	1 1006 Michellia			/	m
B		10059	40	1		V	mo
V C	<u> </u>		<u> </u>				



Issued: 5/21/09 Page **3** of **4**File ID: **FS 001** Revision No. **3**

412016 1/29/13

							1/2413
SAMPLE ID	SYS CODE	Lab ID#	DESCRIPTIONS	LOCATION	No Layered Analysis	ABC Positive Stop	OTHER INSTRUCTIONS 1. 2 3. 3.
		1,900N1	2006 moterial	2001 ±7		0	NAS
011-A	Rm_	6/0189	7006		2	/	M
2		1098683				/	ma
012 - A	Bm	198084	Roof material	2602#15		<u>/</u>	nh.
В	<u> </u>	698645				/	m
v c		1098624			 	1	MB)
013 -A	RF	1.00.00	Roof floshing	Ports # 15		/	MIN
В		100000				/	May
<u> </u>	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	1,900	mechanical flushi	nc Poop #15		/	mo
014-A B	mF	119870	The state of the s		ļ	1	Ma
e		18980 V			-	/	MA
015-A	Rm	69818	Roof Material	Port #16		/	MAN
8		49818			<u> </u>	-	hm.
c		164871	5			<u> </u>	114-11

		~
		1
	2 T A A T T T T T T T T T T T T T T T T	
	7 / A (
/ / / / / / / / / / / / / / / / / / / /	V / V - N - N - C - N - N - N - N - N - N - N	ie.
HARY		r.
		1.
Environm		
	antole bio-	
TO LEVIL OF THE LITTLE	C 11.1.412. 1 11.0.	**
TO THE PERSON AND THE	·	

Issued: 5/21/09 Page 4 of 4
File ID: **FS-001** Revision No. **3**

1/2016

1								101110
SAMPLE ID	SYS CODE	Lab ID#	DESCRIPTIONS	LOCATION	No Layered Analysis	ABC Positive Stop	If Negative PLM Analyze TEM	1. 2 3
016 A	8F.	498154	Roof flooring	2016 # 16		Q		5%. CONS
В		1.98167			_			
J e		1098118	<u> </u>	5.0#		_/		
017-A	<u>Rm</u>	1.00490	Doof material	Roch # 12		/		MAD
B		1,02001				/		MAD
018-A	BF_	1098813	Roof Clashing	Roop #17		/	; :	10 %. CM/
В		498823			<u> </u>	/		_
Ve		698834				/		
019-4	Rm_	498845	Roof material	2005#17		1		MA
В		498834				\ <u>\</u>		(Mg)
V C	<u> </u>	49886	¥	_ _		'	-	
t 1		1						:
		4						

Section 00 90 20 SUPPLEMENTARY ROOFING CONDITIONS

1.0 Description

The work consists of furnishing and installing all roofing and related items as specified and diagrammed herein.

2.0 Concurrent Operations

Because other activities of the Emily P. Bissell Hospital (Hospital) will be proceeding at the same time as the work covered by these specifications, the contractor shall cooperate with the State of Delaware (State) Project Manager to insure that all contract work progresses in a manner that does not conflict with other activities of the Emily P. Bissell Hospital. Set up areas will be designated at the pre-bid meeting.

3.0 Workmanship

All workmen shall be certified in the particular trade and/or class in which they are employed. All work shall be done according to the specifications covering the class or type of work and shall meet the approval, in the field, of the State Project Manager. The contractor's representative or job supervisor shall have a complete copy of the specifications on the job site at all times. Any questions not covered in the method specifications shall be resolved and approved in writing by the State and the State's Technical Representative.

4.0 Number of Crews On-Site

In order that the work may be accomplished in the shortest possible time, the successful bidder, weather permitting, shall be required to have at least one crew of six (6) qualified personnel with its' own responsible foreman, at work on-site at all times. This seven (7) man crew shall remain on-site throughout the duration of the successful bidder's work. At no time shall less than this crew be at work without the express consent of the State Project Manager. The State Project Manager will be advised of changes in supervision.

5.0 Storage of Materials

All materials shall be stored on-site at a place designated by the State Project Manager. No materials shall be removed from the job site by the contractor for any reason, except where specifically authorized, in writing, by the State Project Manager. All materials shall be inventoried as soon as possible after delivery as possible by the State Project Manager and the contractor. Any items lost or stolen as a result of not being secured shall be the responsibility of the contractor to replace. All roofing felts, insulation and other absorbent roof material components must be maintained in dry condition.

ALL WET OR DAMP MATERIALS SHALL BE REMOVED from the job site and replaced with dry materials. Contractor shall be responsible for providing dry storage. **Tarpaulins** will be required for protection of all roof insulation. All plastic shipping wrappings will be removed from insulation prior to storage.

All equipment stored on the ground must be protected by a temporary fence or other approved structure.

6.0 Decks

Situations will develop where deck repair and deck replacement will be required. Contractor will include with all bids, a unit price for deck repair and a unit price for deck replacement.

7.0 Drains

Situations will develop where additional drainage is required. Contractors will include with all bids, a unit price for new installed drain assembly.

8.0 Insulation

Insulation shall have accurate dimensional stability so as to properly conform to the surfaces of the roof, cants, curbs, pipes, etc. Joints between boards shall be tight and insulation shall be held back 1/8 inch from vertical surfaces and sumps. INSULATION SHALL BE PROTECTED FROM THE WEATHER AT ALL TIMES.

9.0 Compliance

Non-compliance with the terms of this specification and ensuing contract can result in either cancellation of the contract or in complete reworking or replacement of defective areas at the contractor's expense. In the event of cancellation, the State shall not be obligated to compensate the contractor for any work, or any roof installed in a defective manner, or which fails to meet the specification criteria.

Furthermore, DAMAGE CAUSED BY WATER INFILTRATION RESULTING FROM THE FAILURE OF THE CONTRACTOR TO SECURE EACH DAY'S WORK IN A WATERTIGHT MANNER WILL BE CORRECTED AT THE CONTRACTOR'S EXPENSE. INCLUDED, AS DAMAGES WILL BE ALL LABOR COSTS INCURRED BY THE STATE AS A RESULT OF SUCH WATER INFILTRATION.

The standard of all work shall be to the specification of the State Project Manager. In the event of non-compliance or substandard or defective work, the State Project Manager or the delegated representative may, at his discretion, halt further work until discrepancies are rectified at the contractor's expense. The State Project Manager and the State's Technical Representative shall be the final authority in the interpretation of all specifications contained herein. **The roofing segment of work will not be subcontracted.**

10.0 Protection of Roof Membrane

Roof traffic is to be confined to the actual work area to the greatest extent possible. Where hauling over other areas is necessary, the roof will be protected with plywood. Contractor shall be responsible for repairs and leaks in traffic areas during and after the job.

11.0 Job Conditions

All surfaces to be treated shall be smooth, visually dry, and free from dirt, debris and foreign matter before any treatment is initiated. Weather temperatures will be a minimum of 40 degrees F. and rising during roofing operations, and protective tarpaulins will be available for emergency protection of roof work in progress during periods of changing weather. THE STANDARD OF SURFACE CLEANLINESS SHALL BE TO THE SATISFACTION OF THE STATE PROJECT MANAGER AND/OR STATE'S REPRESENTATIVE.

The Contractor is responsible to pump the existing and/or new roof in order to provide a suitable environment for roofing to proceed. Contractor shall include in his/her base bid all necessary costs associated with pumping of roof.

The contractor shall be responsible for exercising all reasonable precautions to avoid fires being started, and shall provide suitable fire extinguishers located where they can be promptly used when needed. Competent operators shall be in attendance at all times when equipment is in use. Materials and equipment shall be stored neatly in areas designated by the State Project Manager, and dispersed so as to insure a minimum fire hazard.

Loads placed on the roof at any point shall not exceed the safe loading for which the roof was designed.

Tarpaulins will be used to cover sides of building at all loading and chute locations.

12.0 Clean-Up

Roof drains, gutters, scuppers and downspouts, must be kept clean and free from debris and obstructions, and must be functional during the project and at the completion of the project. The job foreman shall be responsible for daily inspection of work area to assure that no floatable trash or materials are left to clog drains. **DRAINAGE MUST BE FREE FLOWING AT ALL TIMES.**

All other accumulating debris shall be removed daily to assure maximum safety and sanitation at all times. At completion of all work, the contractor shall remove excess materials and debris from the site and leave roof surfaces and work site free from accumulations of spoil, debris and other extraneous materials from windows, floors, walls, ladders and other finished surfaces. Any damage to buildings or grounds caused by the contractor shall be rectified at the contractor's expense to the satisfaction of the State Project Manager before final payment is made. Equipment and tools must meet OSHA and the State requirements. Barricades with tags will be installed as required by the State.

13.0 Temporary Electrical Power

The electrical power at the existing building will be available to the contractor. Cost of electricity will be paid for by the State.

14.0 Temporary Water

The water at the existing building will be available to the contractor. Cost of water will be paid for by the State.

15.0 Inspection of Work in Progress and Upon Completion

It shall be the responsibility of the Contractor to arrange an inspection of the job site with the State Project Manager, State's Technical Consultant, and the Materials Manufacturer's Field Representative at the following times:

Prior to start of work. Conditions at the time shall be noted. All necessary work permits must be obtained before work begins.

2. PRIOR TO FINAL FINISH TO THE APPLIED ROOF SYSTEM.

16.0 Core Samples

During application or upon completion, the State reserves the right to test materials and extract cores, within reason. Deficiencies will be considered less than the scope of the specification and payment will be withheld until proper corrections have been done.

17.0 Final Inspection

The representative of the contracting firm shall notify the State Project Manager when he is within five (5) working days of completing a particular project. A final inspection team consisting of the State Project Manager, the State's Technical Representative, the Representative of the Contracting Firm, the Contractor's Job Foreman, and Materials Manufacturer's Field Representative, shall inspect the work. Any defects noted in the work during the course of this final inspection shall be corrected to the satisfaction of the State Project Manager WITHIN 15 DAYS and prior to the removal of the contractor's equipment from the job site.

18.0 Final Payment

Retainage throughout the contract period will be five (5) percent. Final payment including the 5% retainage will not be approved until all punch list items are addressed and the warranty is delivered to the client and accepted.

19.0 Chemical Clearance

All materials to be used must have the State's chemical clearance before being brought to the job site. OSHA material data sheets must be submitted. All materials will be ASBESTOS FREE.

20.0 Insurance

Contractor shall submit certificates of insurance conforming to the laws of the state and to the satisfaction of the State.

21.0 Progress of Work

The contractor shall notify the State Project Manager, State's Technical Representative, and Material Manufacturer's Field Representative at least FIVE (5) WORKING DAYS IN ADVANCE OF THE DAY HE/SHE INTENDS TO BEGIN WORK.

All bidders shall state in their proposal:

- 1. IF AWARDED THE JOB, THE DATE THEY EXPECT TO BEGIN WORK.
- 2. ESTIMATED NUMBER OF WORKING DAYS.

For the purposes of progress payments, the State Project Manager and State's Technical Representative shall have final authority to determine the exact point of completion of any phase of work (i.e., ten percent, twenty percent, etc.).

22.0 Metal Samples

Color samples of all fascia and roofing metal will be submitted to the State for their approval.

23.0 Permits

The contractor shall furnish and pay for all permits, fees, and licenses required for proper execution and completion of this project.

24.0 Standard of Quality

The various materials and products specified in the specification documents by name or description are given to establish a standard of quality and cost for bid purposes. It is not the intent to limit acceptance to any one material or product specified, but rather to name or describe it as an <u>absolute minimum</u> standard that is desired and acceptable. A material or product of lesser quality would not be acceptable. Where proprietary names are used, whether or not followed by the words "or approved equal", they shall be subject to equals only as approved by the State.

25.0 Safety

Contractor must be in compliance with OSHA "Fall Protection" Standard, Subpart M (1926.500) that became effective February 6, 1995.

OSHA approved safety harnesses and warning lines must be utilized at outside edges of buildings.

Eye protection for workers will be required. Hardhats will be required for workers on ground level. Hardhats will also be required on workers when crane is in operation at any building.

All propane tanks are to be stored on the ground.

All torches (If applicable) shall be equipped with dead man's shut off.

A two (2) hour fire watch will be maintained after torch operations have ceased. Contractor will use hand held laser thermometers to check all areas covered by the day's work.

26.0 Scaffolding, Guardrails, Stairways & Chutes (If required)

Provide and maintain in a safe manner for duration of construction all required scaffolds, guardrails, handrails, stairways, covers for floor, roof and wall openings, and other temporary construction as necessary.

Scaffolding will have and interior stair unit with railings. No admittance into the building will be allowed unless an emergency exists. Fence with gate will surround scaffolding as noted on drawings. When workmen are not present on roof, gate will be locked.

Provide chutes for delivery of removal materials in demolition and removal to the ground level. Throwing or dumping from higher levels will not be permitted. Refer to all standard and specific OSHA and EPA requirements, as applicable to all work performed under this contract.

27.0 Landscaping

Contractor will be responsible to repair all "green areas". New clean topsoil will be used to level ground. Contractor shall apply to the disturbed areas, Agway's WearGreen Hydroseed at the rate of 5 to 7 pounds per 1000 square feet. All repaired landscaped areas must meet the State's satisfaction before final payment is made.

28.0 Toilet Facilities

Contractor must supply his or her own toilet facilities. Entry into the building will be prohibited.

29.0 Time Schedule

Contractor shall submit, with his/her bid, a detailed critical path "Time Schedule".

All work under the Prime Contract must follow the starting and completion schedule as set forth in the "Time Schedule".

Start date: October 26, 2015

Working hours: Weekdays - 7:00 A.M. to 3:30 P.M.

Weekends - With prior approval of the

State.

Substantial Completion Date: January 15, 2016

Punch List Inspection: January 15, 2016 Final Completion: January 22, 2016

The time schedules, as outlined above, shall be strictly maintained and adhered to and shall be used by the Contractor as a guide in preparing bids and in setting up work and delivery schedules. Revisions to Time Schedule may be required due to weather delays.

Prepare shop drawings and submittals in a timely manner.

All items requiring fabrication shall be released for fabrication and shipment to the job immediately upon approval of required submittal data.

30.0 Guarantee

Upon completing the project, the Contractor shall provide a two (2) year LABOR AND MATERIALS GUARANTEE TO THE STATE AND MANUFACTURER. IN ADDITION, THE PRIMARY ROOFING MANUFACTURER MUST PROVIDE THE FOLLOWING:

- MODIFIED ROOF REPLACEMENT = 25 YEAR NO DOLLAR LIMIT WARRANTY.
- 2. METAL EDGE SYSTEM = 215 MPH LIFETIME WIND WARRANTY.
- 3. ROOF RESTORATION ROOF COATING = 10 YEAR WARRANTY

Guarantee must cover both the labor and materials for all system components.

Warranty for the roofing and metal edge systems, must come from the manufacturers.

Warranty must be signed by the PARENT COMPANY. Officers of divisions or subsidiaries of a PARENT COMPANY are not acceptable personnel to sign a roofing warranty.

31.0 Drain Testing

A preconstruction and post construction drain inspection will be made by the Contractor and the State Project Manager. Any drains clogged before works begins will be opened by the State. The Contractor will be responsible to open any clogged drains found during work or at the completion of the project.

32.0 Pre-Approved Materials

Roofing Materials:

- A. Bissell Hospital Main and 1912 Buildings:
 - Modified Roofing:
 - a. Garland
 - b. Tremco
 - c. Soprema

2. Roof Restoration Coating:

- a. Garland
- b. Tremco
- c. GAF
- d. APOC

33.0 Disclosure of Materials

The materials outlined above are the type of materials that should be used in this project. The bidder must disclose, in his/her proposal, the manufacturer(s) that he/she intends to use on this project. Bidder will not be allowed to change materials after the bid opening date. In addition, if an alternate material is bid, the material must be equal or exceed the specifications within the Material Specifications section of this document. In addition, the bidder must submit, to the State's Project Manager and Consultant, the following information no later than 7 days before the bid opening. (Alternate materials only)

- 1. A certificate from an accredited testing laboratory comparing the physical and performance attributes of the proposed material with those materials denoted as pre-approved systems or the characteristics noted in the specification documents, including but not limited to the following:
 - a. Cold Process Membrane:
 - 1. Modified roofing membrane(s) and flashings substantiating Flexibility, Tensile Strength and Tear Strength. Test results must be dated, notarized and be on testing laboratory stationary. Testing for SBS membrane and must follow standard ASTM D 5147 test methods. Testing shall be performed at 73 Degrees. Test at 0 degrees shall not be considered.
 - A list of at least five (5) jobs where the proposed alternate material was used under similar conditions. These jobs shall be located within fifty (50) miles of the project. Each job must be at least five (5) years old, and each must be available for inspection by the State's Representative.
- 3. Consideration will be given only to those alternate materials and/or systems that have written approval 4 days before the bid opening.
- 4. Alternate supplier of roofing material must supply the following information to the State and conform to the following criteria:
 - a. Submittal of a quart sample of the coating.

- b. Material Manufacturer must supply the State with a \$2,000,000.00 Product Liability Policy.
- c. The manufacturer must have a current ratio of 2:1 (current assets to current liabilities) and demonstrate such with an **audited** financial statement supported by an affidavit from a third party.
- d. The materials installed for the waterproofing membrane must be manufactured and guaranteed by the material supplier.
- e. All products must be in accordance with the Health, Safety And Environmental Control (H, S & E) Regulations. e.g. No asbestos materials, no harmful solvent release materials, etc.
- f. In making a request for substitution, Bidder/Contractor represents:
 - a. He/she has personally investigated the proposed product or method, and determined that it is equal or superior in all respects to that specified.
 - b. He/she will provide the same guarantee for substitution as for the product and method specified.
 - c. He/she will coordinate installation of accepted substitution in work, making such changes as may be required for work to be completed in all respects.
 - d. He/she waives all claims for additional cost related to substitution, which consequently become apparent.
 - e. Cost data is complete and includes all related cost under his/her contract or other contracts, which may be affected by the substitution.
 - f. He will reimburse the Owner for all redesign cost by the Consultant/ Architect for accommodation of the substitute.
- 5. The State reserves the right to be the final authority on the acceptance or rejection of any or all bids, proposed alternate roofing systems or materials.

6. Alternate material submissions shall be sent to:

Professional Roof Services, Inc. 9 Fairview Avenue Middletown, DE 19709 Attention: Mr. Chris Moore (610) 662-7562

34.0 Final Completion & Inspections:

Except with the consent of the Owner, the Consultant will perform no more than one (1) inspection to determine whether the Work or a designated portion thereof has attained Final Completion in accordance with the Contract Documents. The Owner shall be entitled to deduct from the Contract Sum amount paid to the Consultant for any additional final inspections including costs to process change orders.

The Consultant will perform progress inspections up to the Final Completion Date as found in Section 30.0 "Time Schedule" above. All inspections, with the exception of one (1) final inspection, will be billed to the Owner at a rate of \$375.00 per inspection. The Owner shall be entitled to deduct from the Contract Sum amount paid to the Consultant for any additional inspections.

35.0 Contractor's Responsibility

The contractor is responsible for his or her own measurements and cores. The contractor is required to verify all field conditions. The core locations and related materials are included for convenience and are not intended to be construed as being the same material or construction across the entire roof surface. Negligence of the contractor not to verify all conditions will not be accepted as a justification for adjustment of the contract.

CONSTRUCTION WASTE MANAGEMENT SECTION 00 90 30

Part 1 – GENERAL:

1.1 SUMMARY:

A. Section includes: Administrative and procedural requirements for construction waste management activities.

1.2 DEFINITIONS:

- A. Construction, Demolition, and Land clearing (CDL) Waste: Includes all non-hazardous solid wastes resulting from construction, remodeling, alternations, repair, demolition and land clearing. Includes material that is recycled, reused, salvaged or disposed as garbage.
- B. Salvage: Recovery of materials for on-site reuse, sale or donation to a third party.
- C. Reuse: Making use of a material without altering its form. Materials can be reused on-site or reused on other projects off-site. Examples include, but are not limited to the following: Crushing or grinding of concrete for use as sub-base materials. Chipping of land clearing debris for use as mulch.
- D. Recycling: The process of sorting, cleaning, treating, and reconstituting materials for the purpose of using the material in the manufacture of a new product.
- E. Source-Separated CDL Recycling: The process of separating recyclable materials in separate containers as they are generated on the job-site. The separated materials are hauled directly to a recycling facility or transfer station.
- F. Co-mingled CDL Recycling: The process of collecting mixed recyclable materials in one container on-site. The container is taken to a material recovery facility where materials are separated for recycling.
- G. Approved Recycling Facility: Any of the following:
 - 1. A facility that can legally accept CDL waste materials for the purpose of processing the materials into an altered form for the manufacture of a new product.

2. Material Recovery Facility: A general term used to describe a waste-sorting facility. Mechanical, hand-separation, or a combination of both procedures, are used to recover recyclable materials.

1.3 SUBMITTALS:

- A. Contractor shall develop a Waste Management Plan: Submit 3 copies of plan within 14 days of date established for the Notice to Proceed.
- B. Contractor shall provide Waste Management Report: Concurrent with each Applications for Payment, submit 3 copies of report.

1.4 PERFORMANCE REQUIREMENTS:

- A. General: Divert a minimum of 75% CDL waste, by weight, from the landfill by one, or a combination of the following activities:
- 1. Salvage
- 2. Reuse
- 3. Source-Separated CDL Recycling
- 4. Co-mingled CDL Recycling
- B. CDL waste materials that can be salvaged, reused or recycled include, but are not limited to, the following:
- 1. Acoustical ceiling tiles
- 2. Asphalt
- 3. Asphalt shingles
- 4. Cardboard packaging
- 5. Carpet and carpet pad
- 6. Concrete
- 7. Drywall
- 8. Fluorescent lights and ballasts
- 9 Land clearing debris (vegetation, stumpage, dirt)
- 10. Metals
- 11. Paint (through hazardous waste outlets)
- 12. Wood
- 13. Plastic film (sheeting, shrink wrap, packaging)
- 14. Window glass
- 15. Field office waste, including office paper, aluminum cans, glass, plastic and office cardboard.

1.4 QUALITY ASSURANCE:

- A. Waste Management Coordinator Qualifications: Experienced firm, with a record of successful waste management coordination of projects with similar requirements, that employs a LEED Accredited Professional, certified by the USGBC as waste management coordinator.
- B. Refrigerant Recovery Technician Qualifications: Certified by EPA-approved certification program.
- C. Regulatory Requirements: Conduct construction waste management activities in accordance with hauling and disposal regulations of all authorities having jurisdiction and all other applicable laws and ordinances.
- D. Preconstruction Conference: Schedule and conduct meeting at Project site prior to construction activities.
- 1. Attendees: Inform the following individuals, whose presence is required, of date and time of meeting.
 - a. Owner
 - b. Architect
 - c. Contractor's superintendent
 - d. Major subcontractors
 - e. Waste Management Coordinator
 - f. Other concerned parties.
- 2. Agenda Items: Review methods and procedures related to waste management including, but not limited to, the following:
 - a. Review and discuss waste management plan including responsibilities of Waste Management Coordinator.
 - b. Review requirements for documenting quantities of each type of waste and its disposition.
 - c. Review and finalize procedures for materials separation and verify availability of containers and bins needed to avoid delays.
 - d. Review procedures for periodic waste collections and transportation to recycling and disposal facilities.
 - e. Review waste management requirements for each trade.
- 3. Minutes: Record discussion. Distribute meeting minutes to all participants. Note: If there is a Project Architect, they will perform this role.

- 1.5 WASTE MANAGEMENT PLAN Contractor shall develop and document the following:
 - A. Develop a plan to meet the requirements listed in this section at a minimum. Plan shall consist of waste identification, waste reduction plan and cost/revenue analysis. Distinguish between demolition and construction waste. Indicate quantities by weight throughout the plan.
 - B. Indicate anticipated types and quantities of demolition, site-cleaning and construction waste generated by the project. List all assumptions made for the quantities estimates.
 - C. List each type of waste and whether it will be salvages, recycled, or disposed of in a landfill. The plan should include the following information:
 - 1. Types of estimated quantities, by weight, of CDL waste expected to be generated during demolition and construction.
 - 2. Proposed methods for CDL waste salvage, reuse, recycling and disposal during demolition including, but not limited to, one or more of the following:
 - a. Contracting with a deconstruction specialist to salvage materials generated,
 - b. Selective salvage as part of demolition contractor's work,
 - c. Reuse of materials on-site or sale or donation to a third party.
 - 3. Proposed methods for salvage, reuse, recycling and disposal during construction including, but not limited to, one or more of the following:
 - a. Requiring subcontractors to take their CDL waste to a recycling facility.
 - b. Contracting with a recycling hauler to haul recyclable CDL waste to an approved recycling or material recovery facility;
 - c. Processing and reusing materials on-site;
 - d. Self-hauling to a recycling or material recovery facility.
 - 4. Name of recycling or material recovery facility receiving the CDL wastes.
 - 5. Handling and Transportation Procedures: Include method that will be used for separating recyclable waste including sizes of containers, container labeling, and designated location on project site where materials separation will be located.

- D. Cost/Revenue Analysis: Indicate total cost of waste disposal as if there was no waste management plan and net additional cost or net savings resulting from implementing waste management plan. Include the following:
 - 1. Total quantity of waste.
 - 2. Estimated cost of disposal (cost per unit). Include hauling and tipping fees and cost of collection containers for each type of waste.
 - 3. Total cost of disposal (with no waste management).
 - 4. Revenue from salvaged materials.
 - 5. Revenue from recycled materials.
 - 6. Savings in hauling and tipping fees by donating materials
 - 7. Savings in hauling and tipping fees that are avoided.
 - 8. Handling and transportation cost. Including cost of collection containers for each type of waste.
 - 9. Net additional cost or net savings from waste management plan.

Part 2 - PRODUCTS (Not Used)

Part 3 - EXECUTION:

3.1 CONSTRUCTION WASTE MANAGEMENT, GENERAL:

- A. Provide containers for CDL waste that is to be recycled clearly labeled as such with a list of acceptable and unacceptable materials. This list of acceptable materials must be the same as the materials recycled at the receiving materials recovery facility or recycling processor.
- B. The collection containers for recyclable CDL waste must contain no more that 10% non-recyclable material, by volume.
- C. Provide containers for CDL waste that is disposed in a landfill clearly labeled as such.
- D. Use detailed material estimates to reduce risk of unplanned and potentially wasteful cuts.
- E. To the greatest extent possible, include in material purchasing agreements a waste reduction provision requesting that materials and equipment be delivered in packaging made of recyclable material, that they reduce the amount of packaging, that packaging be taken back for reuse or recycling, and to take back all unused product. Insure that subcontractors require the same provisions in their purchase agreements.

F. Conduct regular visual inspections of dumpsters and recycling bins to remove contaminants.

3.2 SOURCE SEPARATION:

A. General: Contractor shall separate recyclable materials from CDL waste to the maximum extent possible.

Separate recyclable materials by type.

- 1. Provide containers, clearly labeled, by type of separated materials or provide other storage method for managing recyclable materials until they are removed from Project site.
- 2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water and to minimize pest attraction. Cover to prevent windblown dust.
- 3. Stockpile materials away from demolition area. Do not store with drip line of remaining trees.
- 4. Store components off the ground and protect from weather.

3.3 CO-MINDGLED RECYCLING:

A. General: Do not put CDL waste that will be disposed in a landfill into a comingled CDL waste recycling container.

3.4 REMOVAL OF CONSTRUCTION WASTE MATERIALS:

- A. Remove CDL waste materials from project site on a regular basis. Do not allow CDL waste to accumulate on-site.
- B. Transport CDL waste materials off Owner's property and legally dispose of them.
- C. Burning of CDL waste is not permitted.

END OF SECTION

WASTE MANAGEMENT PROGRESS REPORT								
MATERIAL CATEGORY	DISPOSED IN MUNICIPAL SOLID WASTE LANDFILL	DIVERTED FROM LANDFILL BY RECYCLING, SALVAGE OR REUSE						
		Recycled	1 :	Salvaged	Reused			
1. Acoustical Ceiling Tiles				. ()				
2. Asphalt								
3. Asphalt Shingles								
4. Cardboard Packaging								
5. Carpet and Carpet Pad								
6. Concrete			V					
7. Drywall								
8. Fluorescent Lights and								
Ballasts	4							
9. Land Clearing Debris (vegetation, stumpage, dirt)								
10. Metals								
11. Paint (through hazardous waste outlets)	C							
12. Wood								
13. Plastic Film (sheeting, shrink wrap, packaging)	3							
14. Window Glass								
15. Field Office Waste (office								
paper, aluminum cans, glass, plastic, coffee cardboard)								
16. Other (insert description)								
17. Other (insert description)								
Total (In Weight)		(TOTAL OF ALL ABOVE VALUES – IN WEIGHT)			UES – IN			
		entage of (TOTAL WASTE DIVIDED Diverted BY TOTAL DIVERTED)						