



*Michael R. Wigley, AIA, LEED®AP
Randy B. Duplechain, P.E.
Charles R. Woodward, Jr., LS
W. Zachary Crouch, P.E.
Michael E. Wheedleton, AIA
Jason P. Loar, P.E.
Ring W. Lardner, P.E.
Gerald G. Friedel, P.E.*

**DEPARTMENT OF HEALTH & SOCIAL SERVICES
DIVISION OF SUBSTANCE ABUSE & MENTAL HEALTH
PRICKETT BUILDING FIRST FLOOR RENOVATIONS
DELAWARE HOSPITAL FOR THE CHRONICALLY ILL
SMRYNA, DELAWARE
DBF #586B035.E01 □ OMB/DFM # MJ3514000012
MARCH 5, 2015**

ADDENDUM NO. 2

The following items shall become a part of the contract documents. Contractor must acknowledge receipt of this addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

- Item No. 1 Base bid shall include patching the walls where the wall base was removed during abatement in the following spaces: A1143, A1145, A1141, B1137, B1013, and Storage Room next to A1125.
- Item No. 2 No epoxy floor substitutions will be allowed.
- Item No. 3 Base bid shall include removing brick as needed at the floor level, grinding concrete level with the existing floor, removing all conduits and relocating any wiring as needed, and provide self-leveling floor compound at the location of the removed wall. See attached sketch SK-1.
- Item No. 4 In existing spaces 1124 and 1126 the base bid shall include removing a portion of terrazzo flooring at the joint, grinding as needed and providing self-leveling floor compound as needed in existing space 1126. See attached sketch SK-2.
- Item No. 5 In existing space A1141 the base bid shall include removing the ceramic wall tile, grout and chase walls at the toilet room, see attached sketch SK-1. Install new chase walls, repair the plaster wall at former ceramic tile location, sand, smooth and repaint. See attached sketch SK-3.

END OF ADDENDUM

DRAWINGS REDACTED