

Consultants, Planners



Infrared Scanning • Specifications

Data Base Information • Nuclear Surveys

February 17, 2017

To: All Contractors

From: Professional Roof Services (*enem*)

Re: Addendum #2

Delaware Hospital for the Chronically Ill

Medical Center Building

Roof Replacement & Repair Project

Contract # MJ3514000016

1. The scale on Sheet # 2 is referenced incorrectly as 1" = 20' it should be 1" = 5' a revised drawing with the correct scale is attached.

2. A video taken of Roof Area # 2 can be accessed via the link provided down below.

https://www.dropbox.com/sh/lgx7qncx0wah9fl/AAC00YdPV-9SYiLHsDhjGb-fa?dl=0

- 3. The Garland Company has notified P.R.S.I. that membrane seams cannot be heat welded when using Green Lock adhesive as specified on page 19 of Section 075216. Please check with additional manufacturers regarding the permissibility of heat welding with the adhesives used as part of their systems. In lieu of heat welding the membrane can be laid out in a shingle fashion with the appropriate bleed out of the membrane adhesive.
- 4. Bids are due on Tuesday, February 21, 2017 at 2:00 P.M. Location is the State of Delaware, Office of Management and Budget, Division of Facilities Management, at the Thomas Collins Building, 540 S. DuPont Highway, Suite 1 (Third Floor), Dover, DE 19901.

End of Addendum

Cc: Patrick McKenna, OMB State of DE

Rodney Holderbaum, State of DE, DHSS/DMS – D.H.C.I. Facility Operations

John S. Bell, State of DE, DHSS/DMS – D.H.C.I. Facility Operations

Brad Smith, PRSI

Blaine Chipola, PRSI

Mike McGonigle, PRSI

Ken Myers, PRSI

File