SECTION 074213 - METAL WALL PANELS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Metal wall panels with concealed fasteners at walls.
2. Soffit panels as indicated.

B. Related Sections include the following:

0. Division 5 Section "Structural Steel" for structural-steel framing.
1. Division 5 Section "Cold-Formed Metal Framing" for metal studs, bracing, anchorage, and framing accessories.
2. Division 6 Section "Rough Carpentry" for wood blocking.
3. Division 7 Section "Flashing and Sheet Metal" for metal flashing and trim not part of this Work.
4. Division 7 Section "Joint Sealants" for field-applied sealants.
5. Division 7 Section "Metal Wall Shingles" for wall shingles.
6. Division 8 Section "Louvers and Vents" for integral louvers.

1.3 PERFORMANCE REQUIREMENTS

A. General: Provide manufactured wall panel assemblies complying with performance requirements indicated and capable of withstanding structural movement, thermally induced movement, and exposure to weather without failure or infiltration of water into the building interior.

B. Air Infiltration: Provide manufactured wall panel assemblies with permanent resistance to air leakage through assembly of not more than 0.09 cfm/sq. ft. (0.45 L/s/sq. m) of fixed wall area when tested according to ASTM E 283 at a static-air-pressure difference of 4.0 lbf/sq. ft. (192 Pa).

C. Water Penetration: Provide manufactured wall panel assemblies with no water penetration as defined in the test method when tested according to ASTM E 331 at a minimum differential pressure of 20 percent of inward acting, wind-load design pressure of not less than 6.24 lb/sq. ft. (300 Pa) and not more than 12.0 lb/sq. ft. (575 Pa).

D. Structural Performance: Provide manufactured wall panel assemblies capable of withstanding design wind loads indicated under in-service conditions with deflection no greater than the following, based on testing manufacturer's standard units according to ASTM E 330 by a qualified independent testing and inspecting agency.

1. Maximum Deflection: 1/180 of the span.

1.4 SUBMITTALS

A. Product Data: Include manufacturer's product specifications, standard details, certified product test results, and general recommendations, as applicable to materials and finishes for each component and for total panel assemblies.

B. Shop Drawings: Show layouts of panels, details of corner conditions, joints, panel profiles, supports, anchorages, trim, flashings, closures, and special details. Distinguish between factory- and field-assembled work.

C. Samples for Initial Selection: Manufacturer's color charts or chips showing the full range of colors, textures, and patterns available for wall panels with factory-applied finishes.

D. Samples for Verification: Provide sample panels 12 inches (300 mm) long by actual panel width, in the profile, style, color, and texture indicated. Include clips, caps, battens, fasteners, closures, and other exposed panel accessories.

E. Qualification Data: For firms and persons specified in the "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.

F. Product Test Reports: Indicate compliance of manufactured wall panel assemblies and materials with performance and other requirements based on comprehensive testing of current products.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Engage an experienced installer who has completed metal wall panel projects similar in material, design, and extent to that indicated for this Project and with a record of successful in-service performance.

B. Fire-Test-Response Characteristics: Where fire-resistance-rated wall panel assemblies are indicated, provide materials and construction identical to those of assemblies tested for fire resistance per ASTM E 119 by an independent testing and inspecting agency acceptable to authorities having jurisdiction.

1. Fire-Resistance Ratings: As indicated by design designations in UL's "Fire Resistance Directory" or in the listing of another testing and inspecting agency acceptable to authorities having jurisdiction.

C. Mockups: Before installing wall panels, construct mockups for each form of construction and finish required to verify selections made under Sample submittals and to demonstrate aesthetic effects and qualities of materials and execution. Build mockups to comply with the following requirements, using exposed and concealed materials indicated for the completed Work.

1. Locate mockups in the location and of the size indicated or, if not indicated, as directed by Architect.
2. Notify Architect 7 days in advance of the dates and times when mockups will be constructed.
3. Demonstrate the proposed range of aesthetic effects and workmanship.
4. Obtain Architect's approval of mockups before proceeding with construction of wall panels.
5. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.

a. Approved mockups in an undisturbed condition at the time of Substantial Completion may become part of the completed Work.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver panels and other components so they will not be damaged or deformed. Package panels for protection against damage during transportation or handling.

B. Handling: Exercise care in unloading, storing, and erecting wall panels to prevent bending, warping, twisting, and surface damage.

C. Stack materials on platforms or pallets, covered with tarpaulins or other suitable weathertight and ventilated covering. Store panels to ensure dryness. Do not store panels in contact with other materials that might cause staining, denting, or other surface damage.

1.7 PROJECT CONDITIONS

A. Field Measurements: Verify location of structural members and openings in substrates by field measurements before fabrication and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1.8 WARRANTY

A. General Warranty: Special warranties specified in this Article shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by the Contractor under requirements of the Contract Documents.

B. Special Finish Warranty: Submit a written warranty, signed by manufacturer, covering failure of the factory-applied exterior finish on metal wall panels within the specified warranty period and agreeing to repair finish or replace wall panels that show evidence of finish deterioration. Deterioration of finish includes, but is not limited to, color fade, chalking, cracking, peeling, and loss of film integrity.

C. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Products:

1. Metal Wall Panel – 1: **(MWP-1)**
   a. Morin XC-12
   b. Centria CS-200
   c. Fabral HCF Series – 12-1C

2. Metal Wall Panel – 2: **(MWP-2)**
   a. Morin F-12-S
   b. Centria IW-10A

3. Insulated Metal Wall Panel: **(IWP-1)**
   a. Centria Dimension Series – 2" Vertical Flat
   b. Kingspan – Designwall 2000 – 2" Vertical Flat

2.2 METALS AND FINISHES

A. Exposed Finish for Exterior Panels: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations relative to applying and designating finishes. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturer's written instructions.

1. 2-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

   a. Color : Custom color.
   b. Gloss: 20-35 typical.

2.3 WALL PANEL ASSEMBLIES

A. Exterior Wall Panels: Fabricate panel face sheets to the profile or configuration indicated; and of the material,

finish, and thickness indicated. Design joints between panels to form weathertight seals. Panel configuration equivalent to products noted:

1. Provide corner trim panels.
2. Soffit Panels: .032" aluminum, alloy 3015-H14, flush panel, 11" o.c. with manufacturer's J channel trim.

2.4 MISCELLANEOUS MATERIALS

A. Fasteners: Self-tapping screws, bolts, nuts, self-locking rivets and bolts, end-welded studs, and other suitable fasteners designed to withstand design loads.

1. Use stainless-steel fasteners for exterior applications and galvanized steel fasteners for interior applications.

B. Accessories: Unless otherwise specified, provide components required for a complete wall panel assembly including trim, copings, fasciae, soffits, mullions, sills, corner units, clips, seam covers, flashings, louvers, sealants, gaskets, fillers, closure strips, and similar items. Match materials and finishes of panels.

1. Closure Strips: Closed-cell, self-extinguishing, expanded, cellular, rubber or cross-linked, polyolefin-foam flexible closure strips. Cut or premold to match configuration of panels. Provide closure strips where indicated or necessary to ensure weathertight construction.
2. Sealing Tape: Pressure-sensitive, 100 percent solids, polyisobutylene compound sealing tape with release paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape.
3. Joint Sealant: One-part elastomeric polyurethane, polysulfide, or silicone-rubber sealant as recommended by panel manufacturer.
4. Outside Corners: Shop assembled and mitered.

C. Bituminous Coating: Cold-applied asphalt mastic, SSPC-Paint 12, compounded for 15-mil (0.4-mm) dry film thickness per coat, unless otherwise indicated. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

2.5 FABRICATION

A. General: Fabricate and finish panels and accessories at the factory to greatest extent possible, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.

B. Sound Control: Where sound-absorption requirement is indicated, fabricate interior liner panels with 1/8-inch- (3-mm-) diameter holes uniformly spaced approximately 1000 holes per square foot (10 750 holes per square meter). Cover insulation with polyethylene film and provide inserts of wire mesh to form acoustical spacer grid.

C. Apply bituminous coating or other permanent separation materials on concealed panel surfaces where panels would otherwise be in direct contact with substrate materials that are noncompatible or could result in corrosion or deterioration of either materials or finishes.

D. Fabricate panel joints with captive gaskets or separator strips that provide a tight seal and prevent metal-to-metal contact, in a manner that will minimize noise from movements within panel assembly.

2.6 SECONDARY FRAMING

A. Panel Supports and Anchorage: Provide girts, furring channels, angles, plates, bracing, and other secondary framing members.

1. Girts: C- or Z-shaped sections fabricated from 0.0598-inch- (1.5-mm-) thick, shop-painted, roll-formed steel.
2. Flange and Sag Bracing: 1-5/8-by-1-5/8-inch (41-by-41-mm) angles, fabricated from 0.0598-inch- (1.5-mm-) thick, shop-painted, roll-formed steel.
3. Base or Sill Angles: Fabricate from 0.079-inch- (2.0-mm-) thick, cold-formed, galvanized steel sections.

4. Secondary structural members, except columns and beams, shall be manufacturer's standard sections fabricated from 0.079-inch- (2.0-mm-) thick, cold-formed galvanized steel.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements indicated for conditions affecting performance of metal panel walls.

1. Panel Supports and Anchorage: Examine wall framing to verify that girts, angles, and other secondary structural panel support members and anchorage have been installed to meet requirements of panel manufacturer.
2. Do not proceed with wall panel installation until unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Coordinate metal wall panels with rain drainage work; flashing; trim; and construction of soffits, roofing, parapets, walls, and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

B. Promptly remove protective film, if any, from exposed surfaces of metal panels. Strip with care to avoid damage to finish.

C. Secondary Structural Supports: Install girts, angles, and other secondary structural panel support members and anchorage according to the Light Gage Structural Institute's "Guide Specifications," Section 07410, "Manufactured Roof and Wall Panels."

3.3 PANEL INSTALLATION

A. General: Comply with panel manufacturer's written instructions and recommendations for installation, as applicable to project conditions and supporting substrates. Anchor panels and other components of the Work securely in place, with provisions for thermal and structural movement.

1. Field cutting exterior panels by torch is not permitted.
2. Install panels with concealed fasteners.
3. Install panels with exposed exterior and interior fasteners, prefinished to match panel finishes. Provide waterproof washers at all exposed fasteners.
4. Locate and space exposed fasteners in true vertical and horizontal alignment. Use proper tools to obtain controlled, uniform compression for positive seal without rupture of neoprene washer.
5. Install felt paper on substrate as required by manufacturer.

B. Accessories: Install components required for a complete wall panel assembly including trim, copings, fasciae, mullions, sills, corner units, clips, seam covers, flashings, louvers, sealants, gaskets, fillers, closure strips, and similar items.

C. Joint Sealers: Install gaskets, joint fillers, and sealants where indicated and where required for weatherproof performance of wall panel assemblies. Provide types of gaskets, fillers, and sealants indicated or, if not otherwise indicated, types recommended by panel manufacturer.

1. Install weatherseal to prevent air and moisture penetration. Flash and seal panels at ends and intersections with other materials with rubber, neoprene, or other closures to exclude weather.
2. Seal panel end laps with a bead of tape or sealant, full width of panel. Seal side joints where recommended

by panel manufacturer.

3. Prepare joints and apply sealants to comply with requirements of Division 7 Section "Joint Sealants."

D. Wall Panels: Apply elastomeric sealant continuously between metal base channel (sill angle) and concrete, and elsewhere as necessary for waterproofing. Handle and apply sealant and back-up according to sealant manufacturer's written instructions.

1. Align bottom of wall panels and fasten with blind rivets, bolts, or self-tapping screws. Fasten flashings and trim around openings and similar elements with self-tapping screws.
2. Install screw fasteners with power tools having controlled torque adjusted to compress neoprene washer tightly without damage to washer, screw threads, or panels. Install screws in predrilled holes.
3. Provide weatherproof escutcheons for pipe and conduit penetrating exterior walls.

E. Separate dissimilar metals by painting each metal surface in area of contact with a bituminous coating or by other permanent separation as recommended by manufacturers of dissimilar metals.

F. Coat back side of metal panels with bituminous coating where it will contact wood, ferrous metal, or cementitious construction.

G. Installation Tolerances: Shim and align panel units within installed tolerance of 1/4 inch in 20 feet (6 mm in 6 m) on level, plumb, and location lines as indicated and within 1/8-inch (3-mm) offset of adjoining faces and of alignment of matching profiles.

3.4 CLEANING AND PROTECTING

A. Damaged Units: Replace panels and other components of the Work that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

B. Cleaning: Remove temporary protective coverings and strippable films, if any, as soon as each panel is installed. On completion of panel installation, clean finished surfaces as recommended by panel manufacturer and maintain in a clean condition during construction.

END OF SECTION 074213