

Addendum No. 2

Date: March 20, 2018
Project: Caesar Rodney High School
Gym Roof Replacement
Contract No. SRS-18002-CRHSgymroof

The work herein shall be considered part of the bid documents for the referenced project and carried out in accordance with the following supplemental instructions issued in accordance with the Contract Documents without change in Contract Sum or Contract Time. Acknowledge receipt of addendum on the bid form as indicated.

RFI Responses

1. **Question:** With regard to tapered insulation – the drawing not on a3.1 states “MIN. 5” AVERAGE THICKNESS.” Are you looking for a minimum starting thickness of 5” or a minimum average R-value equal to 5” of Poly-Iso (R-30±)?
Response: Assuming R-5.7 per inch, minimum thickness may be 4” as long as the average roof insulation value exceeds R=25.
2. **Question:** With regard to skylights – The drawing note on A3.1 states “REMOVE EXISTING CURB-MOUNTED SKYLIGHT. INSTALL NEW SKYLIGHT TO FIT EXISTING CURB” but revised detail SK-A.01 calls for a new insulated skylight curb. Which is correct?
Answer: Provide new insulated skylight curb as indicated on detail 3/A6.1 and SK-A.01.

Changes to Drawings

1. Drawing A3.1 – ROOF PLAN
Revised Area N at New Roofing Notes to delete the phrase “Min. 5” average thickness” and replace it with the phrase “Minimum 4” thickness.”
No sketch issued.
2. Drawing A3.1 – ROOF PLAN
Revised skylight note at Roof Plan Legend to read as follows:
Remove existing curb-mounted skylight and curb. Install new curb, skylight and new fall protection screen. Wasco Ecosky or approved equivalent. See Detail 3/A6.1.
No sketch issued.

End