



ARCHITECTURE
ENGINEERING

Date: June 14, 2016

Re: **NEW CAESAR RODNEY ELEMENTARY SCHOOL**
Magnolia, Delaware
2017073.00

ADDENDUM TWO

The addendum forms a part of the contract documents and modifies the original bidding documents dated May 14, 2018, as noted below.

GENERAL/CLARIFICATION

1. Bid Date remains unchanged: June 26, 2018 at 3:00 PM.
2. Last Day for Bidder Questions: June 19, 2018.

BIDDER'S QUESTIONS

1. What is the construction type/specifications for the maintenance building? Wood pole barn? Steel Frame?
Response:
2. How is the tiered seating under the main stair constructed and what is the finish material on it?
Response:

PROJECT MANUAL VOLUMES 1, 2, 3 and 4

1. Table of Contents
 - a. ADD section 081600 Composite Doors
 - b. REMOVE section 115213 Projection Screens
 - c. ADD section 115213.19 Rear Projection Screens
2. Section 072736 Sprayed Foam Air Barriers
 - a. REMOVE paragraphs 1.5.A.1.a.1 and 1.5.A.1.a.3, and renumber remaining paragraphs
 - b. ADD paragraphs 1.5.A.1.a.3 and 1.5.A.1.a.4 as follows:
 - 3) Capital Insulation Services, 8265 Patuxent Range Road, Jessup, Maryland 20794. (240)712-1734. Attn: Robert Procida.
 - 4) Summit Insulation & Contracting, 8246 Beachwood Road, Baltimore, Maryland 21222. (410)644-8000. Attn: Dan Biser.
3. Section 075416 Ketone Ethylene Ester (KEE) Roofing
 - a. ADD paragraph 2.2.A.1.d as follows: "d. Versico Roofing Systems."
4. Section 077253 Snow Guards
 - a. ADD paragraph 2.2.A.1.b as follows: "b. Metal Roof Innovations, Ltd.; S-5! Color Guard."
5. Section 080671 Door Hardware Sets
 - a. Set 6.0: ADD door A132/2.
 - b. Set 7.0: REMOVE door A132/2 (set not used).
 - c. Set 9.0: ADD door A201B/1.
 - d. ADD set 17.1 as follows:



ARCHITECTURE
ENGINEERING

Set: 17.1

Doors: [A133/2](#)

6 Hinge (heavy weight)	T4A3786	US26D	MK
1 Removable Mullion	808	628	RU
2 Exit Device (storeroom)	ED5200(A) 125959 ACHS MK	630	RU
2 Exit Device (exit only)	ED5200(A) EO	630	RU
2 Surface Closer	(P/PRO)7500 M	689	NO
2 Kick Plate	K1050 10" 4BE CSK	US32D	RO
2 Door Stop	RM861/RM855	US26D	RO
1 Gasketing	S44BL (rated openings only)		PE
1 Astragal	18041CNB TKSP8 (rated openings only)		PE
2 Silencer	608 (at non rated openings)		RO

e. ADD set 17.2 as follows:

Set: 17.2

Doors: [A133/1](#)

3 Hinge (heavy weight)	T4A3786	US26D	MK
1 Exit Device (storeroom)	ED5200(A) 125959 ACHS MK	630	RU
1 Surface Closer	(P/PRO)7500 M	689	NO
1 Kick Plate	K1050 10" 4BE CSK	US32D	RO
1 Door Stop	RM861/RM855	US26D	RO
1 Gasketing	S44BL (rated openings only)		PE
3 Silencer	608 (at non rated openings)		RO

- f. Set 23.0: REMOVE door A133/2 (set not used).
 - g. Set 24.0: REMOVE door A133/2.
 - h. Set 26.0: REMOVE door A133/1.
 - i. Set 27.0: ADD door A101B/2.
 - j. Set 29.0: REMOVE door A118A/1 (set not used).
 - k. Set 31.0: ADD door A126A/1.
 - l. Set 33.0: REMOVE door A201B/1.
 - m. Set 37.0: ADD door C200B/1.
6. Section 081600 Composite Doors
- a. ADD section.
7. Section 088000 Glazing
- a. REVISE paragraph 3.10.A.1 to read as follows: "Basis-of-Design Product: PPG; Solarban z50 (2) Optiblue + Clear."
 - b. REVISE paragraph 3.10.A.5 to read as follows: "Interspace Content: 90% Argon, 10% Air."
 - c. REVISE paragraph 3.10.A.9 to read as follows: "Visible Light Transmittance: 50% minimum."
 - d. REVISE paragraph 3.10.A.10 to read as follows: "Solar Heat Gain Coefficient: 0.33 maximum."



ARCHITECTURE
ENGINEERING

8. Section 096566 Resilient Athletic Flooring
 - a. ADD paragraph 2.1.A.6 as follows: “6. Action Floor Systems.”
9. Section 099123 Interior Painting
 - a. REPLACE paragraphs 2.2.C.10 through 2.2.C.14 with the following:
 10. PT-10, exposed trusses and beams at Gym & Cafeteria: As selected by Architect from manufacturer's full range, semigloss.
 11. PT-11, exposed ductwork at Gym and Cafeteria: As selected by Architect from manufacturer's full range, TBD.
 12. PT-12, exposed columns and X bracing: color to match PT-1, semigloss.
 13. PT-13, TBD: As selected by Architect from manufacturer's full range, TBD.
 14. PT-14, TBD: As selected by Architect from manufacturer's full range, TBD.
 15. Steel lintels shall be same color as adjacent wall surface.
 16. Epoxy paint colors shall be same as equivalent paint system (e.g., PT-1 and EP-1 are both White Flour SW7102, eggshell).
10. Section 115213 Projection Screens
 - a. REMOVE section.
11. Section 115213.19 Rear Projection Screens
 - a. ADD section.
12. Section 116143 Stage Curtains
 - a. ADD paragraph 2.1.A.1.d as follows, and renumber subsequent paragraphs: “d. Janson Industries.”

DRAWINGS VOLUMES I AND II

1. G002 Cover Sheet – Volume 2
 - a. ADD sheet M103 Mechanical Roof Plan
2. G101 First Floor Life Safety Plan
 - a. Detail 1:
 - i. REVISE North wall in Corridor A100 to be a smoke partition.
 - ii. REVISE East wall in Corridor A101 to be a smoke partition.
 - iii. REVISE East, South and West walls in Stair C116 to not be rated.
 - iv. REVISE North, South and West walls in Int. Stor. A131A to be 1-hr rated.
 - b. Detail 2:: REVISE East, South, and West walls in Stair C116 to not be rated.
3. G102 Second Floor Life Safety Plan
 - a. Detail 1:
 - i. REVISE roof over Vest. A101A to show full extents.
 - ii. REVISE South wall of Jan A101B to be 1-hr rated.
 - iii. REVISE East, South and West walls in Stair C116 to not be rated.
 - b. Detail 2: REVISE East, South and West walls in Stair C116 to not be rated.
4. C-001 Cover Sheet
 - a. ADD General Note #16.
5. C-201, C-201B, C-202, C-202B Site Plan
 - a. REVISE General Construction note #23.
 - b. REVISE locations of site signage.
6. C-301, C-301B, C-302, C-302B Utility Plan
 - a. ADD Electric / Telecom Service Construction note “E-9”.
 - b. ADD Tag for note “E-8”.
 - c. REVISE Storm Sewer Construction Note “D-3”.

- d. REVISE Domestic water service size to 4", and revise associated Domestic Water System Construction Notes.
- 7. C-503 Post Construction S.W.M. Plan Facility #1
 - a. REVISE Stormdrain MH. 1A label to CB 1A.
- 8. C-504 Post Construction S.W.M. Plan Facility #2
 - a. REVISE Stormdrain MH. 1E label to CB 1E.
- 9. C-903 Construction Details
 - a. REVISE Dumpster Enclosure Detail.
- 10. A001 Construction Types – Exterior Walls, Slabs, Floors and Roofs
 - a. EXT-2 & EXT-2A: ADD note, "MASONRY VENEER TIE, TYP."
 - b. EXT-3: REVISE "GFRC" to "MSM-1"
 - c. EXT-4: REVISE "GFRC" to "MSM-1"
 - d. EXT-7
 - i. ADD masonry veneer ties.
 - ii. ADD note, "MASONRY VENEER TIE, TYP."
 - e. EXT-8
 - i. ADD masonry veneer ties.
 - ii. ADD note, "MASONRY VENEER TIE, TYP."
 - iii. REVISE flashing at cast stone cap
 - f. Detail 1: REVISE flashing at detail 1A and 1B
- 11. A002 Construction Types – Interior Walls, Railings, Ceilings and Details
 - a. ADD Railing Types 1A and 3A
 - b. ADD Ceiling Type 5.
- 12. A003 Construction Types – Fascia's, FRP Columns, Cornices, and Soffit
 - a. ADD Fascia Type 2.
 - b. ADD Soffit Type 2.
 - c. ADD notation of drawing scale for Soffit Type 1 and Special Shape Brick.
 - d. ADD cast stone band and sill details.
 - e. ADD Typical Interior FRP Trim: FRP-1 Detail.
- 13. A100 Foundation Plan
 - a. ADD floor drain in Toilet A107, Toilet C106C, and Janitor C106D.
 - b. ADD note, "12" DEEP FLOOR TROUGH – SEE KITCHEN" at Kitchen A122.
 - c. REVISE floor sinks in Kitchen A122 from (11) to (8).
- 14. A101A First Floor Plan – Area A
 - a. Detail 1:
 - i. ADD note, "DOOR PUSH BUTTON" to COL-1 by Vest. A1001A.
 - ii. ADD plan detail 3/A501 at Vestibule A100A.
 - iii. REVISE the following openings:
 - 1. HM-3A = SF-21A
 - 2. HM-4B = SF-22B
 - 3. HM- 4A = SF-22A
 - 4. HM-3B = SF-21B
 - iv. ADD tag SF-23 at A103/1.
 - v. REVISE (2) SF-12 from 12'-6" to 12'-0" long at Vest A101A.
 - vi. REVISE Cubicles in Nurse A114 and note "CUBICLE, TYP."
 - vii. REVISE note from "FEATURE WALL" to "DECORATIVE METAL SIGN" in Corridor A101.
 - viii. REVISE wall type 1C to 1E at North wall of Dishwashing A122B.
 - ix. REVISE wall type 1C to 1E at West wall of Office A122H.
 - x. ADD Detail callout 9/A403 at serving line.

- xi. ADD two (2) lockers at Locker A122K and REVISE note to read as follows:
“(5) LOCKER TYPE 1”.
 - xii. ADD wall type 1A at North wall of Vest A102A.
 - xiii. REVISE Interior Storage A131A North and West wall tags to be rated.
 - xiv. REVISE swing of door A122C/1, to match K-101.
 - xv. REVISE masonry opening of door A121A/1 from 3’-4” to 3’-8”.
 - xvi. ADD plan detail 7/A503 at Vestibule A101A.
15. A101B First Floor Plan – Area B
- a. Detail 1:
 - i. ADD note, “4’x8’ ¾” FRT PLYWOOD - SEE TECH” at IDF-1A B111.
 - ii. ADD wall section 5/A304 at Corridor B100.
16. A101C First Floor Plan – Area C
- a. Detail 1:
 - i. REVISE swing of door C106D/1.
 - ii. ADD note “4’x8’ ¾” FRT PLYWOOD - SEE TECH” at IDF-1B C111.
 - iii. REVISE wall tags EXT-2A to be EXT-2, non-rated at Stair C116.
17. A102 Overall Second Floor, Clerestory and Mezzanine Plans
- a. Detail 1:
 - i. REVISE dormer roofs in B wing to show full extents.
 - ii. ADD expansion joint line in roof.
 - b. Detail 3: ADD expansion joint line in roof.
18. A102C Second Floor Plan – Area C
- a. Detail 1:
 - i. REVISE swing of door C206D/1.
 - ii. ADD note “4’x8’ ¾” FRT PLYWOOD - SEE TECH” at IDF-2A C212.
 - iii. REVISE wall tags EXT-2A to be EXT-2, non-rated at Stair C116.
19. A103 Roof Plan
- a. Detail 1:
 - i. ADD notes for plumbing and mechanical equipment, and louvers at back face of sloped roof in Area A and North façade of Area C.
 - ii. REVISE note from “VENT/EXHAUST – SEE MECH” to “SIDEWALL DRYER VENT – SEE MECH”.
 - iii. ADD duct supports rails and VTR’s
 - iv. REVISE (13) downspouts “D.S.” to downspouts with condensate drain “D.S./C.”.
 - v. REVISE (1) conductor head “C.H.” to conductor head with condensate drain “C.H./C.”.
 - vi. ADD D.S. to West of C wing.
 - vii. REVISE locations of D.S. along West side of C wing.
 - b. Detail 2: REVISE detail to indicate condensate pipe connects to downspout at the first floor level.
 - c. ROOF LEGEND: ADD exhaust fan, rooftop unit, vent through roof, downspout w/ condensate drain, and conductor head w/ condensate drain.
20. A104A First Floor Reflected Ceiling Plan – Area A
- a. Detail 1:
 - i. ADD detail 3/A104A at Corridor A100.
 - ii. ADD detail 4/A104A at Media Center A125.
 - iii. ADD detail 5/A104A at Music A118.
 - iv. REVISE location of projection screen.
 - v. REVISE ceiling in Nurse Reception A114.
 - vi. REVISE ceiling in Music A118 to have bulkheads around curved ceiling.
 - vii. ADD note, “COORD. CLG HEIGHT OVER PASS THRU CABINETS W/ APPROVED EQPT., TYP.” At Serving A122A/ Kitchen A122.

- viii. REVISE ceiling in Main Stair A134.
 - b. ADD Details 3, 4, and 5.
- 21. A104C First Floor Reflected Ceiling Plan – Area C
 - a. DELETE note, “1-HR HORIZONTAL ASSEMBLY (UL DESIGN U-415” in Jan C105D.
- 22. A105 Overall Second Floor and Mezzanine Reflected Ceiling Plans
 - a. Detail 2:
 - i. ADD room tag for Eqpt Platform B200.
 - ii. ADD note, “PAINT DECK WHITE ABOVE MEZZ”.
 - b. Detail 2A:
 - i. ADD room tag for Eqpt Platform C300.
 - ii. ADD note, “PAINT DECK WHITE ABOVE MEZZ”.
- 23. A106A First Floor Finish Plan – Area A
 - a. Detail 1:
 - i. ADD transition strip CPT- VCT at Vest A101A – Corridor A101
 - ii. ADD transition strip CPT – VS at Hall A103A – Tlt A107
 - iii. ADD transition strip CPT – CONC at Hall A103A – Elec A103B
 - iv. ADD transition strip RAF – VCT at the following locations:
 - 1. Gymnasium A120 – Stage Access A119B
 - 2. Gymnasium A120 – Int. Stor. A120B
 - 3. Gymnasium A120 – Office A120A
 - 4. Gymnasium A120 – Furn. Stor. A121A
- 24. A106B First Floor Finish Plan – Area B
 - a. ADD expansion joint line per A101B.
 - b. ADD note, “2” EXP. JOINT” per A101B.
- 25. A106C First Floor Finish Plan – Area C
 - a. ADD expansion joint line per A101C.
 - b. ADD note, “2” EXP. JOINT” per A101C.
- 26. A107C Second Floor Finish Plan – Area C
 - a. ADD expansion joint line per A101C.
 - b. ADD note, “2” EXP. JOINT” per A101C.
- 27. A108 Alternate 1 – Plans, Elevations and Sections
 - a. Detail 1: REVISE wall types EXT-4 to EXT-2.
 - b. Detail 3: REVISE (2) downspouts “D.S.” to downspouts with condensate drain “D.S./C.”.
 - c. Detail 4: ADD control joints.
- 28. A109 Alternate 2 Plans
 - a. Detail 1: REVISE wall tags EXT-1A to be rated.
 - b. Detail 2: REVISE wall tags EXT-2A to be EXT-2, non-rated.
 - c. Detail 5: REVISE (2) downspouts “D.S.” to downspouts with condensate drain “D.S./C.”.
- 29. A201 Exterior Elevations
 - a. Detail 1A:
 - i. ADD note, “LOUVER AT C-WING BEYOND – SEE MECH”.
 - ii. ADD note, “PROVIDE CONTROL JOINT @ EA. D.S. AT NORTH END OF C-WING”
 - iii. ADD radius at Music Room roof.
 - b. Detail 1B: ADD note, “HOSE BIBB – SEE PLUMBING”.
 - c. Detail 2A:
 - i. ADD radius to Media Center roof.
 - ii. ADD note, “HOSE BIBB – SEE PLUMBING”.
 - iii. ADD note, “KNOX BOX – COORD. LOCATION W/ LOCAL F.D.”
 - d. Detail 2B:
 - i. REVISE D.S. location

- ii. ADD note, "HOSE BIBB – SEE PLUMBING".
 - iii. ADD control joint.
 - e. Detail 3:
 - i. ADD note, "KILN VENT – SEE MECH".
 - ii. ADD control joints.
 - f. Detail 4: ADD control joints.
- 30. A202 Exterior Elevations
 - a. Detail 1A: ADD control joints.
 - b. Detail 1B: ADD control joints.
 - c. Detail 2A:
 - i. ADD note, "HOSE BIBB- SEE PLUMBING"
 - ii. ADD control joints.
 - d. Detail 2B:
 - i. ADD control joints.
 - ii. ADD note, "HOSE BIBB – SEE PLUMBING"
 - iii. ADD note, "DOOR PUSH BUTTON"
 - iv. ADD note, "SEE MECH FOR PENETRATIONS"
 - v. ADD note, "LOUVER – SEE MECH."
 - e. Detail 4: ADD control joint.
 - f. Detail 5: REVISE storefront elevation.
- 31. A301 Building Sections
 - a. Detail 1A:
 - i. ADD note, "SEE MECH FOR PENETRATIONS"
 - ii. ADD detail callout at Media Center bulkhead.
- 32. A401 Enlarged Toilet Plans
 - a. Detail 1:
 - i. ADD arrow from note in MDF A128 to point at West wall.
 - ii. ADD floor drains.
 - b. Detail 2:
 - i. ADD note, "THERMOSTAT – SEE MECH."
 - ii. REVISE swing of door C106D/1.
 - iii. ADD floor drains.
 - c. Detail 4:
 - i. REVISE North wall tag of Tlt A130A to be rated.
 - ii. ADD floor drain.
 - d. Detail 3, 5, 6, 7, 8: ADD floor drain.
- 33. A402 Enlarged Plans and Sections
 - a. Detail 1: ADD head and sill detail callouts to Elev. Machine A135A.
 - b. Detail 2: ADD roof detail callout.
 - c. Detail 3:
 - i. REVISE wall tag at East wall of Elev C200B to be rated.
 - ii. REVISE railing types.
 - d. Detail 4:
 - i. ADD roof detail callout.
 - ii. REVISE note "GWB FASTENED TO UNDERSIDE OF STRINGER, TYP." To "GWB ON STUD AT UNDERSIDE OF STAIR, TYP."
 - iii. ADD window head and sill detail callouts.
 - e. Detail 5: REVISE note "SLOPE TO MATCH BOTTOM OF STAIR" to "SEATING TIER RISER TO UNDERSIDE OF STAIR.
 - f. Detail 6:

- i. REVISE East wall of column B3-AD chase to align with door A134/4 jamb.
 - ii. ADD door tag A134/4.
 - iii. ADD dimensions.
 - iv. REVISE dimension string at door A134/4.
 - g. ADD detail 7.
- 34. A403 Enlarged Plans and Sections
 - a. Detail 1:
 - i. ADD wall tag EXT-1 to West wall.
 - ii. ADD dimension string from door to column line A16.
 - iii. ADD elevation tag at top of stair.
 - b. Detail 2:
 - i. ADD note, "ROOF TYPE 1"
 - ii. ADD elevation tag at top of stair.
 - c. Detail 5:
 - i. REVISE East, South and West walls to be non-rated.
 - ii. REVISE railing types.
 - iii. ADD dimension string.
 - d. Detail 6:
 - i. REVISE East, South and West walls to be non-rated.
 - ii. REVISE railing types.
 - e. Detail 8:
 - i. ADD head and sill detail callouts.
 - ii. ADD note, "11R @ 7" " below dimension string.
 - f. ADD detail 9.
- 35. A404 Site Structures and Details
 - a. Detail 1: ADD note "FENCE – SEE CIVIL"
 - b. Detail 2: REVISE detail.
 - c. Detail 4:
 - i. REVISE detail sub-numbers.
 - ii. ADD dimension to south wall of kitchen.
 - iii. ADD thru-wall flashing note.
 - iv. ADD foundations and footings. Contractor shall coordinate footing size with approved shop drawings, and coordinate tie-in of drainage underground.
 - d. Detail 5:
 - i. REVISE scale to 1/8"
 - ii. REVISE diameter from 6' to 8'.
 - iii. ADD note, "PAVEMENT JOINTS, TYP. SUBMIT SHOP DRAWING FOR APPROVAL BASED ON APPROVED SITE FURNISHINGS, SIGN, ETC."
 - e. Detail 6 and 7: ADD foundation, footing, and bond beam.
 - f. Detail 9: REVISE detail:
 - i. REVISE detail titles,
 - ii. ADD submittal and code notes.
 - iii. ADD Fire extinguisher.
 - iv. REVISE notes at section and show truss.
 - g. Detail 11: REVISE detail.
- 36. A602 Door and Window Types and Schedule
 - a. REPLACE sheet.
- 37. FP000 Fire Protection Cover Sheet
 - a. REVISE Fire Protection Notes
- 38. FP101 Overall First Floor Fire Protection Plan

- a. REVISE location of standpipe in C116 Stair
- 39. FP102 Overall Second Floor Fire Protection Plan
 - a. REISE location of standpipe in C116 Stair
- 40. P000 Plumbing Cover Sheet
 - a. REVISE Instantaneous Domestic Hot Water Heater Schedule
- 41. P101A (S) First Floor Sanitary Plan – Area A
 - a. REVISE Sanitary Vent locations and Storm Water downspout locations
- 42. P101B (S) First Floor Sanitary Plan – Area B
 - a. REVISE Sanitary Vent locations, Alternate and Base
- 43. P102C (S) Second Floor Sanitary Plan – Area C
 - a. REVISE Sanitary Vent locations and route
- 44. P101C (DW) First Floor Domestic Water Plan – Area C
 - a. REVISE location of hose bib
- 45. P103 Plumbing Roof Plan
 - a. REVISE several locations of Sanitary Vents
- 46. M101A First Floor HVAC – Area A
 - a. REVISE location of Electric Cabinet Heater in Vestibule A101A
 - b. REVISE location of thermostat in Corridor A100 to Corridor A101
 - c. REVISE location of thermostat in Media Center
 - d. REVSIE location of thermostat in Receiving 122G
 - e. REVISE location thermostat in office/ Workroom A126 from North wall to West wall
 - f. REVISE location of thermostat in A123A away from door
 - g. REVISE location of thermostat in Receiving A134
 - h. REVISE size of R-13 transfer ducts to be 40’’ x 16’’
 - i. ADD 4’’ vent to roof with booster fan.
 - j. REVISE note M-10.
 - k. REVISE note M-11.
 - l. REVISE note, “BAS INTERFACE TO BE INSTALLED HERE. FINAL LOCATION TO BE COORDINATED WITH OWNER.”
 - m. REVISE location of exhaust air terminal into correct location in ceiling at Media Center A125
- 47. M101B First Floor HVAC – Area B
 - a. REVISE location of thermostats in all B-wing classrooms to the same location near door.
- 48. M101C First Floor HVAC – Area C
 - a. REVISE location of thermostats in all first floor C-wing classrooms to the same location near door.
 - b. REVISE location of thermostat in Tlt C106B to mirror Tlt C106A.
- 49. M102A Mechanical First Floor HVAC Upper Level Plan – Area A
 - a. REVISE location of R-8’s entry point to avoid windows in gym.
- 50. M102C Second Floor HVAC – Area C
 - a. REVISE location of thermostats in all second floor C-wing classrooms to the same location near door.
 - b. REVISE location of of thermostat in Tlt C206A and Tlt C206B
 - c. ADD of thermostat in classroom C211
- 51. M103 Mechanical Roof Plan
 - a. ADD sheet.
- 52. M104B First Floor– Area B (Add Alternate #1)
 - a. REVISE condensate piping.
- 53. M104C First And Second Floor– Area C (Add Alternate #2)
 - a. REVSIE condensate piping.
- 54. MP101A Refrigerant & Condensate Piping Second Floor Plan-Area A
 - a. REVISE condensate piping.
- 55. MP101B Refrigerant & Condensate Piping First Floor Plan-Area B

- a. REVISE condensate piping.
- 56. MP101C Refrigerant & Condensate Piping First Floor Plan-Area C
 - a. REVISE condensate piping.
 - b. ADD Mechanical piping note and utilization of chase for connection just at first floor.
- 57. MP102C Refrigerant & Condensate Piping Second Floor Plan-Area C
 - a. ADD mechanical piping note. Relocate condensate piping to chase down to first floor and tie into exterior downspout.
- 58. M600 Mechanical Schedules
 - a. REVISE R-13 on return grill schedule
- 59. E000 - Electrical Cover Sheet
 - a. ADD/ REVISE symbols in the electrical symbol legend.
 - b. REVISE Electrical General Note #28.
 - c. ADD lighting fixture type Y.
- 60. EL101A - First Floor Lighting Plan - Area A
 - a. REVISE lighting in the nurse suite.
 - b. ADD fixtures and dimmer switches to the nurse suite.
 - c. ADD lights to the music room.
 - d. ADD wallpacks and wallpack notes
 - e. ADD lights to the main stair.
- 61. EMP101A - First Floor Mechanical Power Plan - Area A
 - a. ADD booster fan circuit.
 - b. ADD circuits and switches for window shades.
- 62. EP101A - First Floor Power Plan - Area A
 - a. ADD floor box in Media Center.
 - b. REVISE receptacle quantities, locations, and circuits
 - c. REVISE basketball hoop controller note
 - d. ADD stage receptacle note
 - e. REVISE location of electric screen
- 63. EP101B - First Floor Power Plan - Area B
 - a. REVISE locations of AE receptacles
- 64. E601 - Electrical Panel Schedules
 - a. REVISE panel schedule(s)
- 65. E602 - Electrical Panel Schedules
 - a. REVISE panel schedule(s)
- 66. E603 - Electrical Panel Schedules
 - a. REVISE panel schedule(s)
- 67. E604 - Electrical Panel Schedules
 - a. REVISE panel schedule(s)
- 68. E700 - Electrical Site Plan
 - a. ADD a trough for the control boxes at the sewage pump.
- 69. T101A INFORMATION TECHNOLOGY FIRST FLOOR PLAN – AREA A
 - a. ADD Data floor box to Conf. Rm. A110
- 70. T300 INFORMATION TECHNOLOGY SITE PLAN
 - a. DELETE site sign from Information Technology Site Plan. Site sign to be covered by Electrical Contractor.

END OF ADDENDUM NO. ONE

Attachments: Becker Morgan Group, Inc. drawings G101, G102, A001, A002, A003, A100, A101A, A101B, A101C, A102, A102C, A103, A104A, A104C, A105, A106A, A106B, A106C, A107C, A108, A109,



ARCHITECTURE
ENGINEERING

A201, A202, A301, A401, A402, A403, A404, A602, issue block dated 06/14/18, and C-001, C-201, C-201B, C-202, C-202B, C-301, C-301B, C-302, C-302B, C-503, C-504, C-903, issued block dated 06/15/18

Studio JAED drawings FP000, FP101, FP102, P000, P101A(S), P101B(S), P101C(DW), P102C(S), P103, M101A, M101B, M101C, M102A, M102C, M103, M104B, M104C, M600, E000, EP101A, EP101B, EL101A, EMP101A, E601, E602, E603, E604, E700, T101A, T300, issue block dated 06.14.2018

Specification Sections 081600, 115213.19

201707300_Addendum2.doc