

STATE OF DELAWARE
INDIAN RIVER SCHOOL DISTRICT
CONTRACT #IRD25036-HVAC

PROJECT MANUAL
FOR

HEAT OF REJECTION EQUIPMENT REPLACEMENT
FOR

GEORGE WASHINGTON CARVER EDUCATIONAL CENTER
AND SELBYVILLE MIDDLE SCHOOL

IN

SUSSEX COUNTY, DELAWARE

PREPARED
BY

GIPE ASSOCIATES, INC.
8719 BROOKS DRIVE
EASTON, MD 21601

GIPE ASSOCIATES WORK ORDER #25021

SEPTEMBER 9, 2025

THIS PAGE LEFT INTENTIONALLY BLANK

STATE OF DELAWARE
INDIAN RIVER SCHOOL DISTRICT
CONTRACT #IRD25036-HVAC

PROJECT MANUAL
FOR

HEAT OF REJECTION EQUIPMENT REPLACEMENT
FOR

GEORGE WASHINGTON CARVER EDUCATIONAL CENTER
AND SELBYVILLE MIDDLE SCHOOL

IN

SUSSEX COUNTY, DELAWARE

PREPARED
BY

GIPE ASSOCIATES, INC.
8719 BROOKS DRIVE
EASTON, MD 21601

GIPE ASSOCIATES WORK ORDER #25021

SEPTEMBER 9, 2025

THIS PAGE LEFT INTENTIONALLY BLANK

SEALS PAGE

1.1 DESIGN PROFESSIONALS OF RECORD

SEAL

A. HVAC Engineer:

1. David R. Hoffman, P.E., LEED AP, CPD
2. Delaware Professional Engineer License #9773
3. President
4. Gipe Associates, Inc.
5. 8719 Brooks Drive
Easton, MD 21601
6. Tel: (410) 822-8688
Fax: (410) 822-6306
7. Email: dhoffman@gipe.net
Cell: (410) 310-6055
8. Responsible for: Division 00, Division 01, Division 22, and Division 23



B. Electrical Engineer:

1. Dina Dixon, P.E., LEED AP
2. Delaware Professional Engineer License #17123
3. Senior Vice President
4. Gipe Associates, Inc.
1220 East Joppa Road, Suite 223
Towson, MD 21286
5. Tel: (410) 832-2420
Fax: (410) 832-2418
6. Email: ddixon@gipe.net
Cell: (410) 924-7232
7. Responsible for Division 26



END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

TABLE OF CONTENTS

A. Specifications for this project are arranged in accordance with the Construction Specification Institute numbering system and format. Section numbering is discontinuous and all numbers not appearing in the Table of Contents are not used for this Project.

B. DOCUMENTS BOUND HERewith

DIVISION 00 – PROCUREMENT AND CONTRACT REQUIREMENTS

INTRODUCTORY INFORMATION

00 01 01 – PROJECT TITLE PAGE

00 01 07 – SEALS PAGE

00 01 10 – TABLE OF CONTENTS

00 01 15 – LIST OF DRAWING SHEETS

PROCUREMENT REQUIREMENTS

00 11 16 – INVITATION TO BID

00 21 13 – INSTRUCTIONS TO BIDDERS

00 41 13 – BID FORM

00 43 13 – BID BOND

CONTRACTING REQUIREMENTS

00 52 13 – STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR
A101- 2017 & AIA DOCUMENT A101 – 2017

00 54 13 – SUPPLEMENT TO AGREEMENT BETWEEN OWNER & CONTRACTOR A101-2017

00 61 13.13 – PERFORMANCE BOND

00 61 13.16 – PAYMENT BOND

00 62 11 – SUBMITTAL TRANSMITTAL FORM
CSI FORM 12.1A

00 62 73 – SCHEDULE OF VALUES
AIA DOCUMENT G703-1992

00 62 76 – APPLICATION AND CERTIFICATE FOR PAYMENT FORM
AIA DOCUMENT G702-1992

00 62 90 – CAD FILE RELEASE FORM

- 00 63 13 – REQUEST FOR INTERPRETATION FORM
CSI FORM 13.2A
- 00 63 14 – REQUEST FOR INTERPRETATION LOG
CSI LOG FORM 13.2B
- 00 63 25 – SUBSTITUTION REQUEST FORM (DURING CONSTRUCTION)
CSI FORM 13.1A
- 00 63 33 – ARCHITECT’S SUPPLEMENTAL INSTRUCTION FORM
AIA DOCUMENT G710-2017
- 00 63 46 – CONSTRUCTION CHANGE DIRECTIVE FORM
AIA DOCUMENT G714-2017
- 00 63 53 – PROPOSAL REQUEST FORM
AIA DOCUMENT G709-2018
- 00 63 63 – CHANGE ORDER FORM
AIA DOCUMENT G701-2017
- 00 63 73 – ALLOWANCE AUTHORIZATION FORM
- 00 65 16 – CERTIFICATE OF SUBSTANTIAL COMPLETION FORM
AIA DOCUMENT G704-2017
- 00 65 19.13 – AFFIDAVIT OF PAYMENTS AND DEBTS CLAIMS FORM
AIA DOCUMENT G706-1994
- 00 65 19.16 – AFFIDAVIT OF RELEASE OF LIENS FORM
AIA DOCUMENT G706A-1994
- 00 65 19.19 – CONSENT OF SURETY TO FINAL PAYMENT FORM
AIA DOCUMENT G707-1994
- 00 72 13 – GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION
AIA DOCUMENT A201-2017
- 00 73 13 – SUPPLEMENTARY GENERAL CONDITIONS
- 00 73 43 – WAGE RATE REQUIREMENTS AND WAGE DETERMINATION SCHEDULES
STATE OF DELAWARE WAGE RATE REQUIREMENTS LETTER
STATE OF DELAWARE WAGE RATE DETERMINATION SCHEDULE
- 00 81 13 – GENERAL REQUIREMENTS
- 00 81 14 – DRUG TESTING FORMS
- 00 81 15 – AFFADAVIT FOR CRAFT TRAINING COMPLIANCE

DIVISION 01 GENERAL REQUIREMENTS

01 11 00	SUMMARY OF WORK
01 14 00	WORK RESTRICTIONS
01 21 00	ALLOWANCES
01 23 00	ALTERNATES
01 25 00	SUBSTITUTION PROCEDURES
01 26 00	CONTRACT MODIFICATION PROCEDURES
01 29 00	PAYMENT PROCEDURES
01 31 00	PROJECT MANAGEMENT AND COORDINATION
01 32 00	CONSTRUCTION PROGRESS DOCUMENTATION
01 33 00	SUBMITTAL PROCEDURES
01 40 00	QUALITY REQUIREMENTS
01 50 00	TEMPORARY FACILITIES AND CONTROLS
01 60 00	PRODUCT REQUIREMENTS
01 73 00	EXECUTION
01 73 29	CUTTING AND PATCHING
01 74 19	CONSTRUCTION WASTE MANAGEMENT
01 77 00	CLOSEOUT PROCEDURES
01 78 23	OPERATION AND MAINTENANCE DATA
01 78 39	PROJECT RECORD DOCUMENTS
01 79 00	DEMONSTRATION AND TRAINING
01 91 13	GENERAL COMMISSIONING REQUIREMENTS
01 91 14	PLUMBING COMMISSIONING REQUIREMENTS
01 91 15	HVAC COMMISSIONING REQUIREMENTS

DIVISION 02 EXISTING CONDITIONS

02 41 19	SELECTIVE DEMOLITION

DIVISION 07 THERMAL AND MOISTURE PROTECTION

07 84 13 HVAC & PLUMBING PENETRATION FIRESTOPPING

DIVISION 22 PLUMBING

22 05 00 COMMON WORK RESULTS FOR PLUMBING

22 05 05 PLUMBING PIPING FITTINGS AND VALVES

22 07 01 PLUMBING INSULATION

22 40 05 PLUMBING EQUIPMENT

DIVISION 23 HEATING VENTILATING AND AIR CONDITIONING

23 05 00 COMMON WORK RESULTS FOR HVAC

23 05 05 HVAC PIPING, FITTING AND VALVES

23 05 48 VIBRATION CONTROLS FOR HVAC AND PLUMBING EQUIPMENT

23 05 93 TESTING, ADJUSTING & BALANCING FOR HVAC AND PLUMBING

23 06 00 HEATING, VENTILATING, AND AIR CONDITIONING EQUIPMENT

23 07 01 HVAC INSULATION

23 09 00 INSTRUMENTATION AND CONTROLS OF HVAC & PLUMBING SYSTEMS

23 65 15 CLOSED CIRCUIT EVAPORATIVE FLUID COOLERS

23 65 17 OPEN-CIRCUIT, LOW PROFILE, FORCED DRAFT COOLING TOWERS

DIVISION 26 ELECTRICAL

26 05 00 COMMON WORK RESULTS FOR ELECTRICAL

26 05 19 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

26 05 20 ELECTRIC HEATING CABLES

26 05 26 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

26 05 28 FIRESTOPPING FOR ELECTRICAL SYSTEMS

26 05 29 HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

26 05 33 RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

26 05 33.23 SURFACE RACEWAYS FOR ELECTRICAL SYSTEMS

26 05 53	IDENTIFICATION FOR ELECTRICAL SYSTEMS
26 05 73	POWER SYSTEM STUDIES
26 24 16	PANELBOARDS
26 27 26	WIRING DEVICES
26 28 13	FUSES
26 29 13	MOTOR CONTROLLERS

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

TABLE OF CONTENTS

A. Specifications for this project are arranged in accordance with the Construction Specification Institute numbering system and format. Section numbering is discontinuous and all numbers not appearing in the Table of Contents are not used for this Project.

B. DOCUMENTS BOUND HERewith

DIVISION 00 – PROCUREMENT AND CONTRACT REQUIREMENTS

INTRODUCTORY INFORMATION

00 01 01 – PROJECT TITLE PAGE

00 01 07 – SEALS PAGE

00 01 10 – TABLE OF CONTENTS

00 01 15 – LIST OF DRAWING SHEETS

PROCUREMENT REQUIREMENTS

00 11 16 – INVITATION TO BID

00 21 13 – INSTRUCTIONS TO BIDDERS

00 41 13 – BID FORM

00 43 13 – BID BOND

CONTRACTING REQUIREMENTS

00 52 13 – STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR
A101- 2017 & AIA DOCUMENT A101 – 2017

00 54 13 – SUPPLEMENT TO AGREEMENT BETWEEN OWNER & CONTRACTOR A101-2017

00 61 13.13 – PERFORMANCE BOND

00 61 13.16 – PAYMENT BOND

00 62 11 – SUBMITTAL TRANSMITTAL FORM
CSI FORM 12.1A

00 62 73 – SCHEDULE OF VALUES
AIA DOCUMENT G703-1992

00 62 76 – APPLICATION AND CERTIFICATE FOR PAYMENT FORM
AIA DOCUMENT G702-1992

00 62 90 – CAD FILE RELEASE FORM

- 00 63 13 – REQUEST FOR INTERPRETATION FORM
CSI FORM 13.2A
- 00 63 14 – REQUEST FOR INTERPRETATION LOG
CSI LOG FORM 13.2B
- 00 63 25 – SUBSTITUTION REQUEST FORM (DURING CONSTRUCTION)
CSI FORM 13.1A
- 00 63 33 – ARCHITECT’S SUPPLEMENTAL INSTRUCTION FORM
AIA DOCUMENT G710-2017
- 00 63 46 – CONSTRUCTION CHANGE DIRECTIVE FORM
AIA DOCUMENT G714-2017
- 00 63 53 – PROPOSAL REQUEST FORM
AIA DOCUMENT G709-2018
- 00 63 63 – CHANGE ORDER FORM
AIA DOCUMENT G701-2017
- 00 63 73 – ALLOWANCE AUTHORIZATION FORM
- 00 65 16 – CERTIFICATE OF SUBSTANTIAL COMPLETION FORM
AIA DOCUMENT G704-2017
- 00 65 19.13 – AFFIDAVIT OF PAYMENTS AND DEBTS CLAIMS FORM
AIA DOCUMENT G706-1994
- 00 65 19.16 – AFFIDAVIT OF RELEASE OF LIENS FORM
AIA DOCUMENT G706A-1994
- 00 65 19.19 – CONSENT OF SURETY TO FINAL PAYMENT FORM
AIA DOCUMENT G707-1994
- 00 72 13 – GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION
AIA DOCUMENT A201-2017
- 00 73 13 – SUPPLEMENTARY GENERAL CONDITIONS
- 00 73 43 – WAGE RATE REQUIREMENTS AND WAGE DETERMINATION SCHEDULES
STATE OF DELAWARE WAGE RATE REQUIREMENTS LETTER
STATE OF DELAWARE WAGE RATE DETERMINATION SCHEDULE
- 00 81 13 – GENERAL REQUIREMENTS
- 00 81 14 – DRUG TESTING FORMS
- 00 81 15 – AFFADAVIT FOR CRAFT TRAINING COMPLIANCE

DIVISION 01 – GENERAL REQUIREMENTS

01 11 00	SUMMARY OF WORK
01 14 00	WORK RESTRICTIONS
01 21 00	ALLOWANCES
01 23 00	ALTERNATES
01 25 00	SUBSTITUTION PROCEDURES
01 26 00	CONTRACT MODIFICATION PROCEDURES
01 29 00	PAYMENT PROCEDURES
01 31 00	PROJECT MANAGEMENT AND COORDINATION
01 32 00	CONSTRUCTION PROGRESS DOCUMENTATION
01 33 00	SUBMITTAL PROCEDURES
01 40 00	QUALITY REQUIREMENTS
01 50 00	TEMPORARY FACILITIES AND CONTROLS
01 60 00	PRODUCT REQUIREMENTS
01 73 00	EXECUTION
01 73 29	CUTTING AND PATCHING
01 74 19	CONSTRUCTION WASTE MANAGEMENT
01 77 00	CLOSEOUT PROCEDURES
01 78 23	OPERATION AND MAINTENANCE DATA
01 78 39	PROJECT RECORD DOCUMENTS
01 79 00	DEMONSTRATION AND TRAINING
01 91 13	GENERAL COMMISSIONING REQUIREMENTS
01 91 14	PLUMBING COMMISSIONING REQUIREMENTS
01 91 15	HVAC COMMISSIONING REQUIREMENTS

DIVISION 02 EXISTING CONDITIONS

02 41 19	SELECTIVE DEMOLITION

DIVISION 07 THERMAL AND MOISTURE PROTECTION

07 84 13 HVAC & PLUMBING PENETRATION FIRESTOPPING

DIVISION 22 PLUMBING

22 05 00 COMMON WORK RESULTS FOR PLUMBING

22 05 05 PLUMBING PIPING FITTINGS AND VALVES

22 07 01 PLUMBING INSULATION

22 40 05 PLUMBING EQUIPMENT

DIVISION 23 HEATING VENTILATING AND AIR CONDITIONING

23 05 00 COMMON WORK RESULTS FOR HVAC

23 05 05 HVAC PIPING, FITTING AND VALVES

23 05 48 VIBRATION CONTROLS FOR HVAC AND PLUMBING EQUIPMENT

23 05 93 TESTING, ADJUSTING & BALANCING FOR HVAC AND PLUMBING

23 06 00 HEATING, VENTILATING, AND AIR CONDITIONING EQUIPMENT

23 07 01 HVAC INSULATION

23 09 00 INSTRUMENTATION AND CONTROLS OF HVAC & PLUMBING SYSTEMS

23 65 15 CLOSED CIRCUIT EVAPORATIVE FLUID COOLERS

23 65 17 OPEN-CIRCUIT, LOW PROFILE, FORCED DRAFT COOLING TOWERS

DIVISION 26 ELECTRICAL

26 05 00 COMMON WORK RESULTS FOR ELECTRICAL

26 05 19 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

26 05 20 ELECTRIC HEATING CABLES

26 05 26 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

26 05 28 FIRESTOPPING FOR ELECTRICAL SYSTEMS

26 05 29 HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

26 05 33 RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

26 05 33.23 SURFACE RACEWAYS FOR ELECTRICAL SYSTEMS

26 05 53	IDENTIFICATION FOR ELECTRICAL SYSTEMS
26 05 73	POWER SYSTEM STUDIES
26 24 16	PANELBOARDS
26 27 26	WIRING DEVICES
26 28 13	FUSES
26 28 16	MOTOR CONTROLLERS

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

LIST OF DRAWING SHEETS

GENERAL:

CS001 COVER SHEET

MECHANICAL:

M001 LEGEND & ABBREVIATIONS - HVAC

MD101 CARVER EDUCATIONAL CENTER PARTIAL FLOOR PLAN – HVAC –
DEMOLITION

MD102 SELBYVILLE MIDDLE SCHOOL PARTIAL FLOOR PLAN – HVAC –
DEMOLITION

M100 CARVER EDUCATIONAL CENTER OVERALL FLOOR PLAN – HVAC –
NEW WORK

M101 CARVER EDUCATIONAL CENTER PARTIAL FLOOR PLAN – HVAC –
NEW WORK

M102 SELBYVILLE MIDDLE SCHOOL PARTIAL FLOOR PLAN – HVAC – NEW
WORK

M201 DETAILS – HVAC

M202 DETAILS – HVAC

M203 DETAILS – HVAC

M204 DETAILS – HVAC

M205 DETAILS – HVAC

M206 DETAILS – HVAC

M301 AUTOMATIC TEMPERATURE CONTROLS

M302 AUTOMATIC TEMPERATURE CONTROLS

M303 AUTOMATIC TEMPERATURE CONTROLS

M401 SCHEDULES – HVAC

M402 SCHEDULES – HVAC

ELECTRICAL:

E001 LEGEND & ABBREVIATIONS – ELECTRICAL

ED101 CARVER EDUCATIONAL CENTER PARTIAL FLOOR PLAN –
ELECTRICAL – DEMOLITION

ED102 SELBYVILLE MIDDLE SCHOOL PARTIAL FLOOR PLAN – ELECTRICAL
– DEMOLITION

ED301 SCHEDULES – ELECTRICAL – DEMOLITION

E101	CARVER EDUCATIONAL CENTER PARTIAL FLOOR PLAN – ELECTRICAL – NEW WORK
E102	SELBYVILLE MIDDLE SCHOOL PARTIAL FLOOR PLAN – ELECTRICAL – NEW WORK
E201	DETAILS – ELECTRICAL
E202	DETAILS – ELECTRICAL
E203	DETAILS - ELECTRICAL
E301	SCHEDULES – ELECTRICAL – NEW WORK

END OF SECTION

INVITATION TO BID

Sealed bids for Contract No. #IRD25036-HVAC, will be received electronically by Gipe Associates, Inc. until 1:30 PM local time on October 22, 2025 at which time they will be read privately. Bidder bears the risk of late delivery. Any bids received after the stated time will be returned unopened.

Project involves all labor, materials, tools, equipment, superintendence, transportation, and performing all work in strict accordance with the Specifications and Drawings for heat of rejection equipment replacement and supporting electrical work at George Washington Carver Educational Center and Selbyville Middle School. All work shall commence on the date of issuance of the Notice to Proceed and shall be completed, operational, and substantially complete within two hundred eighty (280) calendar days thereafter. Final completion shall be thirty (30) days thereafter.

A NON-MANDATORY Pre-Bid Meeting will be held on October 1, 2025 beginning at 9:00 a.m. at Selbyville Middle School, 80 Bethany Road, Selbyville, DE 19975, with a subsequent site visit to George Washington Carver Educational Center, 30207 Frankford School Rd, Frankford, DE 19945 for the purpose of establishing the listing of subcontractors and to answer questions. Representatives of each party to any Joint Venture must attend this meeting. ATTENDANCE OF THIS MEETING IS NOT A PREREQUISITE FOR BIDDING ON THIS CONTRACT.

Bids shall be delivered electronically to dhoffman@gipe.net and submittals@gipe.net with "IRD25036" and "Bid" clearly stated in the subject line.

Contract documents may be obtained from Gipe Associates, Inc. by e-mailing pmcquay@gipe.net. There will be no charge for an electronic copy set or a non-refundable cost of \$100.00 per hard copy set. Checks may be made payable to Gipe Associates, Inc.

Construction documents will be available for review at the following locations: Gipe Associates, Inc., 8719 Brooks Drive, Easton, Maryland and Indian River School District, Main Office, 31 Hosier Street, Selbyville, Delaware, 19975.

Bidders will not be subject to discrimination on the basis of race, creed, color, sex, sexual orientation, gender identity or national origin in consideration of this award, and Minority Business Enterprises, Disadvantaged Business Enterprises, Women-Owned Business Enterprises and Veteran-Owned Business Enterprises will be afforded full opportunity to submit bids on this contract. Each bid must be accompanied by a bid security equivalent to ten percent of the bid amount and all additive alternates. The successful bidder must post a performance bond and payment bond in a sum equal to 100 percent of the contract price upon execution of the contract. The Owner reserves the right to reject any or all bids and to waive any informalities therein. The Owner may extend the time and place for the opening of the bids from that described in the advertisement, with not less than two calendar days notice by certified delivery, facsimile machine or other electronic means to those bidders receiving plans.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

INSTRUCTIONS TO BIDDERS

TABLE OF ARTICLES

1. DEFINITIONS
2. BIDDER'S REPRESENTATION
3. BIDDING DOCUMENTS
4. BIDDING PROCEDURES
5. CONSIDERATION OF BIDS
6. POST-BID INFORMATION
7. PERFORMANCE BOND AND PAYMENT BOND
8. FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

ARTICLE 1: GENERAL

1.1 DEFINITIONS

1.1.1 Whenever the following terms are used, their intent and meaning shall be interpreted as follows:

1.2 STATE: The State of Delaware.

1.3 AGENCY: Contracting State Agency as noted on cover sheet.

1.4 DESIGNATED OFFICIAL: The agent authorized to act for the Agency.

1.5 BIDDING DOCUMENTS: Bidding Documents include the Bidding Requirements and the proposed Contract Documents. The Bidding Requirements consist of the Advertisement for Bid, Invitation to Bid, Instructions to Bidders, Supplementary Instructions to Bidders (if any), General Conditions, Supplementary General Conditions, General Requirements, Special Provisions (if any), the Bid Form (including the Non-collusion Statement), and other sample bidding and contract forms. The proposed Contract Documents consist of the form of Agreement between the Owner and Contractor, as well as the Drawings, Specifications (Project Manual) and all Addenda issued prior to execution of the Contract.

1.6 CONTRACT DOCUMENTS: The Contract Documents consist of the, Instructions to Bidders, Supplementary Instructions to Bidders (if any), General Conditions, Supplementary General Conditions, General Requirements, Special Provisions (if any), the form of agreement between the Owner and the Contractor, Drawings (if any), Specifications (Project Manual), and all addenda.

1.7 AGREEMENT: The form of the Agreement shall be AIA Document A101, Standard Form of Agreement between Owner and Contractor where the basis of payment is a STIPULATED SUM. In the case of conflict between the instructions contained therein and the General Requirements herein, these General Requirements shall prevail.

1.8 GENERAL REQUIREMENTS (or CONDITIONS): General Requirements (or conditions) are instructions pertaining to the Bidding Documents and to contracts in general. They contain, in summary, requirements of laws of the State; policies of the Agency and instructions to bidders.

1.9 SPECIAL PROVISIONS: Special Provisions are specific conditions or requirements peculiar to the bidding documents and to the contract under consideration and are supplemental to the General Requirements. Should the Special Provisions conflict with the General Requirements, the Special Provisions shall prevail.

1.10 ADDENDA: Written or graphic instruments issued by the Owner/Architect prior to the execution of the contract which modify or interpret the Bidding Documents by additions, deletions, clarifications or corrections.

1.11 BIDDER OR VENDOR: A person or entity who formally submits a Bid for the material or Work contemplated, acting directly or through a duly authorized representative who meets the requirements set forth in the Bidding Documents.

- 1.12 SUB-BIDDER: A person or entity who submits a Bid to a Bidder for materials or labor, or both for a portion of the Work.
- 1.13 BID: A complete and properly executed proposal to do the Work for the sums stipulated therein, submitted in accordance with the Bidding Documents.
- 1.14 BASE BID: The sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents as the base, to which Work may be added or from which Work may be deleted for sums stated in Alternate Bids (if any are required to be stated in the bid).
- 1.15 ALTERNATE BID (or ALTERNATE): An amount stated in the Bid, where applicable, to be added to or deducted from the amount of the Base Bid if the corresponding change in the Work, as described in the Bidding Documents is accepted.
- 1.16 UNIT PRICE: An amount stated in the Bid, where applicable, as a price per unit of measurement for materials, equipment or services or a portion of the Work as described in the Bidding Documents.
- 1.17 SURETY: The corporate body which is bound with and for the Contract, or which is liable, and which engages to be responsible for the Contractor's payments of all debts pertaining to and for his acceptable performance of the Work for which he has contracted.
- 1.18 BIDDER'S DEPOSIT: The security designated in the Bid to be furnished by the Bidder as a guaranty of good faith to enter into a contract with the Agency if the Work to be performed or the material or equipment to be furnished is awarded to him.
- 1.19 CONTRACT: The written agreement covering the furnishing and delivery of material or work to be performed.
- 1.20 CONTRACTOR: Any individual, firm or corporation with whom a contract is made by the Agency.
- 1.21 SUBCONTRACTOR: An individual, partnership or corporation which has a direct contract with a contractor to furnish labor and materials at the job site, or to perform construction labor and furnish material in connection with such labor at the job site.
- 1.22 CONTRACT BOND: The approved form of security furnished by the contractor and his surety as a guaranty of good faith on the part of the contractor to execute the work in accordance with the terms of the contract.
- 1.23 Whenever the word "Architect" shall appear on standard printed documents published by the American Institute of Architects (AIA), it shall mean "Engineer" and shall refer to Gipe Associates, Inc. or its appointed staff or sub-consultant.
- 1.24 Wherever the word "Owner" shall appear on standard printed document published by the American Institute of Architects (AIA), it shall mean the Indian River School District.

ARTICLE 2: BIDDER'S REPRESENTATIONS

2.1 PRE-BID MEETING

2.1.1 A pre-bid meeting for this project will be held at the time and place designated. Attendance at this meeting is a pre-requisite for submitting a Bid, unless this requirement is specifically waived elsewhere in the Bid Documents.

2.2 By submitting a Bid, the Bidder represents that:

2.2.1 The Bidder has read and understands the Bidding Documents and that the Bid is made in accordance therewith.

2.2.2 The Bidder has visited the site, become familiar with existing conditions under which the Work is to be performed, and has correlated the Bidder's his personal observations with the requirements of the proposed Contract Documents.

2.2.3 The Bid is based upon the materials, equipment, and systems required by the Bidding Documents without exception.

2.3 JOINT VENTURE REQUIREMENTS

2.3.1 For Public Works Contracts, each Joint Venturer shall be qualified and capable to complete the Work with their own forces.

2.3.2 Included with the Bid submission, and as a requirement to bid, a copy of the executed Joint Venture Agreement shall be submitted and signed by all Joint Venturers involved.

2.3.3 All required Bid Bonds, Performance Bonds, Material and Labor Payment Bonds must be executed by both Joint Venturers and be placed in both of their names.

2.3.4 All required insurance certificates shall name both Joint Venturers.

2.3.5 Both Joint Venturers shall sign the Bid Form and shall submit a copy of a valid Delaware Business License with their Bid.

2.3.6 Both Joint Venturers shall include their Federal E.I. Number with the Bid.

2.3.7 In the event of a mandatory Pre-bid Meeting, each Joint Venturer shall have a representative in attendance.

2.3.8 Due to exceptional circumstances and for good cause shown, one or more of these provisions may be waived at the discretion of the State.

2.4 ASSIGNMENT OF ANTITRUST CLAIMS

2.4.1 As consideration for the award and execution by the Owner of this contract, the Contractor hereby grants, conveys, sells, assigns and transfers to the State of Delaware all of its right, title and interests in and to all known or unknown causes of action it presently has or may now or hereafter acquire under the antitrust laws of the United States and the State of Delaware, relating to the particular goods or services purchased or acquired by the Owner pursuant to this contract.

ARTICLE 3: BIDDING DOCUMENTS

3.1 COPIES OF BID DOCUMENTS

- 3.1.1 Bidders may obtain complete sets of the Bidding Documents from the Architectural/Engineering firm designated in the Advertisement or Invitation to Bid in the number and for the deposit sum, if any, stated therein.
- 3.1.2 Bidders shall use complete sets of Bidding Documents for preparation of Bids. The issuing Agency nor the Architect assumes no responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.
- 3.1.3 Any errors, inconsistencies or omissions discovered shall be reported to the Architect immediately.
- 3.1.4 The Agency and Architect may make copies of the Bidding Documents available on the above terms for the purpose of obtaining Bids on the Work. No license or grant of use is conferred by issuance of copies of the Bidding Documents.

3.2 INTERPRETATION OR CORRECTION OF BIDDING DOCUMENTS

- 3.2.1 The Bidder shall carefully study and compare the Bidding Documents with each other, and with other work being bid concurrently or presently under construction to the extent that it relates to the Work for which the Bid is submitted, shall examine the site and local conditions, and shall report any errors, inconsistencies, or ambiguities discovered to the Architect.
- 3.2.2 Bidders or Sub-bidders requiring clarification or interpretation of the Bidding Documents shall make a written request to the Architect at least seven days prior to the date for receipt of Bids. Interpretations, corrections and changes to the Bidding Documents will be made by written Addendum. Interpretations, corrections, or changes to the Bidding Documents made in any other manner shall not be binding.
- 3.2.2a Direct inquiries and request for information (AIA G716) to: Gipe Associates, Inc. ATTN: David R. Hoffman, P.E., LEED AP, Email: dhoffman@gipe.net; Fax: 410-822-6306 no later than seven (7) days prior to bid due date.
- 3.2.3 The apparent silence of the specifications as to any detail, or the apparent omission from it of detailed description concerning any point, shall be regarded as meaning that only the best commercial practice is to prevail and only material and workmanship of the first quality are to be used. Proof of specification compliance will be the responsibility of the Bidder.
- 3.2.4 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for all permits, labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for the proper execution and completion of the Work.
- 3.2.5 The Owner will bear the costs for all impact and user fees associated with the project.

3.3 SUBSTITUTIONS

- 3.3.1 The materials, products and equipment described in the Bidding Documents establish a standard of quality, required function, dimension, and appearance to be met by any proposed substitution. The specification of a particular manufacturer or model number is not intended to be proprietary in any way. Substitutions of products for those named will be considered, providing that the Vendor certifies that the function, quality, and performance characteristics of the material offered is equal or superior to that specified. It shall be the Bidder's responsibility to assure that the proposed substitution will not affect the intent of the design, and to make any installation modifications required to accommodate the substitution.
- 3.3.2 Requests for substitutions shall be made in writing to the Architect at least ten days prior to the date of the Bid Opening. Such requests shall include a complete description of the proposed substitution, drawings, performance and test data, explanation of required installation modifications due the substitution, and any other information necessary for an evaluation. The burden of proof of the merit of the proposed substitution is upon the proposer. The Architect's decision of approval or disapproval shall be final. The Architect is to notify Owner prior to any approvals.
- 3.3.3 If the Architect approves a substitution prior to the receipt of Bids, such approval shall be set forth in an Addendum. Approvals made in any other manner shall not be binding.
- 3.3.4 The Architect shall have no obligation to consider any substitutions after the Contract award.
- 3.3.5 Refer to Section 016000 "Product Requirements" for additional requirements and procedures regarding substitutions.
- 3.4 ADDENDA
- 3.4.1 Addenda will be mailed or delivered to all who are known by the Architect to have received a complete set of the Bidding Documents.
- 3.4.2 Copies of Addenda will be made available for inspection wherever Bidding Documents are on file for that purpose.
- 3.4.3 No Addenda will be issued later than 2 calendar days prior to the date for receipt of Bids except an Addendum withdrawing the request for Bids or one which extends the time or changes the location for the opening of bids.
- 3.4.4 Each bidder shall ascertain prior to submitting his Bid that they have received all Addenda issued, and shall acknowledge their receipt in their Bid in the appropriate space. Not acknowledging an issued Addenda could be grounds for determining a bid to be non-responsive.

ARTICLE 4: BIDDING PROCEDURES

- 4.1 PREPARATION OF BIDS
- 4.1.1 Submit the bids on the Bid Forms included with the Bidding Documents.
- 4.1.2 Submit the original Bid Form for each bid. Bid Forms may be removed from the project manual for this purpose.

- 4.1.3 Execute all blanks on the Bid Form in a non-erasable medium (typewriter or manually in ink).
- 4.1.4 Where so indicated by the makeup on the Bid Form, express sums in both words and figures, in case of discrepancy between the two, the written amount shall govern.
- 4.1.5 Interlineations, alterations or erasures must be initialed by the signer of the Bid.
- 4.1.6 BID ALL REQUESTED ALTERNATES AND UNIT PRICES, IF ANY. If there is no change in the Base Bid for an Alternate, enter "No Change". The Contractor is responsible for verifying that they have received all addenda issued during the bidding period. Work required by Addenda shall automatically become part of the Contract.
- 4.1.7 Make no additional stipulations on the Bid Form and do not qualify the Bid in any other manner.
- 4.1.8 Each copy of the Bid shall include the legal name of the Bidder and a statement whether the Bidder is a sole proprietor, a partnership, a corporation, or any legal entity, and each copy shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid by a corporation shall further give the state of incorporation and have the corporate seal affixed. A Bid submitted by an agent shall have a current Power of Attorney attached, certifying agent's authority to bind the Bidder.
- 4.1.9 Bidder shall complete the Non-Collusion Statement form included with the Bid Forms and include it with their Bid.
- 4.1.10 In the construction of all Public Works projects for the State of Delaware or any agency thereof, preference in employment of laborers, workers or mechanics shall be given to bona fide legal citizens of the State who have established citizenship by residence of at least 90 days in the State.
- 4.1.11 Each bidder shall include in their bid a copy of a valid Delaware Business License.
- 4.1.12 Each bidder shall include a signed Affidavit for the Bidder certifying compliance with OMB Regulation 4104 - "Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on "Large Public Works Projects." "Large Public Works" is based upon the current threshold required for bidding Public Works as set by the Purchasing and Contracting Advisory Council.
- 4.2 BID SECURITY
 - 4.2.1 All bids shall be accompanied by a deposit of either a good and sufficient bond to the agency for the benefit of the agency, with corporate surety authorized to do business in this State, the form of the bond and the surety to be approved by the agency, or a security of the bidder assigned to the agency, for a sum equal to at least 10% of the bid plus all add alternates, or in lieu of the bid bond a security deposit in the form of a certified check, bank treasurer's check, cashier's check, money order, or other prior approved secured deposit assigned to the State. The bid bond need not be for a specific sum, but may be stated to be for a sum equal to 10% of the bid plus all add alternates to which it relates and not to exceed a certain stated sum, if said sum is equal to at least 10% of the bid. The Bid Bond form used shall be the standard OMB form (attached).

- 4.2.2 The Agency has the right to retain the bid security of Bidders to whom an award is being considered until either a formal contract has been executed and bonds have been furnished or the specified time has elapsed so the Bids may be withdrawn or all Bids have been rejected.
- 4.2.3 In the event of any successful Bidder refusing or neglecting to execute a formal contract and bond within 20 days of the awarding of the contract, the bid bond or security deposited by the successful bidder shall be forfeited.
- 4.3 SUBCONTRACTOR LIST
- 4.3.1 In accordance with Title 29, Chapter 69, Section 6962(d)(10)b of the Delaware Code, each Bidder shall submit with their Bid a completed List of Sub-Contractors included with the Bid Form. NAME ONLY ONE SUBCONTRACTOR FOR EACH TRADE. The bidder must list **in each category** the full name and address (City & State) of the subcontractor that the Bidder will be using to perform the work and provide material for that subcontractor category. Should the Bidder's listed subcontractor intend to provide any of their subcontractor category of work through a third-tier contractor, the Bidder shall list that third-tier contractor's full name and address (City & State). **If the Bidder intends to perform any category of work itself, it must list its full name and address.** For clarification, if the Bidder intends to perform the work themselves, the Bidder **may not** insert "not applicable", "N/A", "self" or anything other than its own full name and address (City & State). To do so shall cause the bid to be rejected. In addition, the failure to produce a completed subcontractor list with the bid submittal shall cause the bid to be rejected. If you have more than three (3) third-tier contractors to report in any subcontractor category, print out additional page(s) containing the appropriate category, complete the rest of your list of third-tier contractors for that category, notate the addition in parentheses as (CONTINUATION) next to the subcontractor category and an asterisk (*) next to any additional third-tier contractors, and submit it with your bid.
- 4.3.2 It is the responsibility of the Contractor to ensure that their Subcontractors are in compliance with the provisions of this law. Also, if a Contractor elects to list themselves as a Subcontractor for any category, they must specifically name themselves on the Bid Form and be able to document their capability to act as Subcontractor in that category in accordance with this law.
- 4.4 AFFIDAVIT OF CONTRACTOR QUALIFICATIONS
- 4.4.1 In accordance with Title 29, Chapter 69, Section 6962(d)(10)b.3 of the Delaware Code, each Bidder shall submit with their Bid the Affidavit of Contractor Qualifications certifying that the Bidder will abide by the contractor's qualifications outlined in the construction bid specifications for the duration of the contract term. After a contract has been awarded the successful bidder shall not substitute another subcontractor whose name was submitted on the Subcontractor Form except for the reasons in the statute and not without written consent from the awarding agency. Failure to utilize the subcontractors on the list will subject the successful bidder to penalties as outlined in the General Requirements Section 5.2 of the contract.
- 4.5 AFFIDAVIT OF CRAFT TRAINING COMPLIANCE

4.5.1 In accordance with Title 29, Chapter 69, Section 6962(d)(13) of the Delaware Code, contractors and subcontractors must provide craft training for journeyman and apprentice levels if all of the following apply:

- A. A project meets the prevailing wage requirement under Title 29, Chapter 69, Section 6960 of the Delaware Code.
- B. The contractor employs 10 or more total employees.
- C. The project is not a federal highway project

Failure to provide required craft training on the project may subject the successful contractor and/or subcontractor(s) to penalties as outlined in Title 29, Chapter 69, Section 6962(d)(13) of the Delaware Code.

Bidders shall submit the Affidavit of Craft Training Compliance prior to contract execution.

4.6 EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS

4.6.1 During the performance of this contract, the contractor agrees as follows:

- A. The Contractor will not discriminate against any employee or applicant for employment because of race, creed, sex, color, sexual orientation, gender identity or national origin. The Contractor will take affirmative action to ensure the applicants are employed, and that employees are treated during employment, without regard to their race, creed, sex, color, sexual orientation, gender identity or national origin. Such action shall include, but not be limited to, the following: Employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.
- B. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, sex, color, sexual orientation, gender identity or national origin."

4.7 PREVAILING WAGE REQUIREMENT

4.7.1 Wage Provisions: For renovation and new construction projects whose costs exceed the thresholds contained in Delaware Code, Title 29, Section 6960, the minimum wage rates for various classes of laborers and mechanics shall be as determined by the Department of Labor, Division of Industrial Affairs of the State of Delaware.

4.7.2 The employer shall pay all mechanics and labors employed directly upon the site of work, unconditionally and not less often than once a week and without subsequent deduction or rebate on any account, the full amounts accrued at time of payment, computed at wage rates not less than those stated in the specifications, regardless of any contractual relationship which may be alleged to exist between the employer and such laborers and mechanics.

- 4.7.3 The scale of the wages to be paid shall be posted by the employer in a prominent and easily accessible place at the site of the work.
- 4.7.4 Every contract based upon these specifications shall contain a stipulation that sworn payroll information, as required by the Department of Labor, be furnished weekly. The Department of Labor shall keep and maintain the sworn payroll information for a period of 6 months from the last day of the work week covered by the payroll.
- 4.8 SUBMISSION OF BIDS
- 4.8.1 Enclose the Bid, the Bid Security, and any other documents required to be submitted with the Bid in a sealed opaque envelope. Address the envelope to the party receiving the Bids. Identify with the project name, project number, and the Bidder's name and address. If the Bid is sent by mail, enclose the sealed envelope in a separate mailing envelope with the notation "BID ENCLOSED" on the face thereof. The State is not responsible for the opening of bids prior to bid opening date and time that are not properly marked.
- 4.8.2 Deposit Bids at the designated location prior to the time and date for receipt of bids indicated in the Advertisement for Bids. Bids received after the time and date for receipt of bids will be marked "LATE BID" and returned.
- 4.8.3 Bidder assumes full responsibility for timely delivery at location designated for receipt of bids.
- 4.8.4 Oral, telephonic or telegraphic bids are invalid and will not receive consideration.
- 4.8.5 Withdrawn Bids may be resubmitted up to the date and time designated for the receipt of Bids, provided that they are then fully in compliance with these Instructions to Bidders.
- 4.9 MODIFICATION OR WITHDRAW OF BIDS
- 4.9.1 Prior to the closing date for receipt of Bids, a Bidder may withdraw a Bid by personal request and by showing proper identification to the Architect. A request for withdraw by letter or fax, if the Architect is notified in writing prior to receipt of fax, is acceptable. A fax directing a modification in the bid price will render the Bid informal, causing it to be ineligible for consideration of award. Telephone directives for modification of the bid price shall not be permitted and will have no bearing on the submitted proposal in any manner.
- 4.9.2 Bidders submitting Bids that are late shall be notified as soon as practicable and the bid shall be returned.
- 4.9.3 A Bid may not be modified, withdrawn or canceled by the Bidder during a thirty (30) day period following the time and date designated for the receipt and opening of Bids, and Bidder so agrees in submitting their Bid. Bids shall be binding for 30 days after the date of the Bid opening.

ARTICLE 5: CONSIDERATION OF BIDS

5.1 OPENING/REJECTION OF BIDS

- 5.1.1 Unless otherwise stated, Bids received on time will be publicly opened and will be read aloud. An abstract of the Bids will be made available to Bidders.
- 5.1.2 The Agency shall have the right to reject any and all Bids. A Bid not accompanied by a required Bid Security or by other data required by the Bidding Documents, or a Bid which is in any way incomplete or irregular is subject to rejection.
- 5.1.3 If the Bids are rejected, it will be done within thirty (30) calendar day of the Bid opening.
- 5.2 COMPARISON OF BIDS
- 5.2.1 After the Bids have been opened and read, the bid prices will be compared and the result of such comparisons will be made available to the public. Comparisons of the Bids may be based on the Base Bid plus desired Alternates. The Agency shall have the right to accept Alternates in any order or combination.
- 5.2.2 The Agency reserves the right to waive technicalities, to reject any or all Bids, or any portion thereof, to advertise for new Bids, to proceed to do the Work otherwise, or to abandon the Work, if in the judgment of the Agency or its agent(s), it is in the best interest of the State.
- 5.2.3 An increase or decrease in the quantity for any item is not sufficient grounds for an increase or decrease in the Unit Price.
- 5.2.4 The prices quoted are to be those for which the material will be furnished F.O.B. Job Site and include all charges that may be imposed during the period of the Contract.
- 5.2.5 No qualifying letter or statements in or attached to the Bid, or separate discounts will be considered in determining the low Bid except as may be otherwise herein noted. Cash or separate discounts should be computed and incorporated into Unit Bid Price(s).
- 5.3 DISQUALIFICATION OF BIDDERS
- 5.3.1 An agency shall determine that each Bidder on any Public Works Contract is responsible before awarding the Contract. Factors to be considered in determining the responsibility of a Bidder include:
- A. The Bidder's financial, physical, personnel or other resources including Subcontracts;
 - B. The Bidder's record of performance on past public or private construction projects, including, but not limited to, defaults and/or final adjudication or admission of violations of the Prevailing Wage Laws in Delaware or any other state;
 - C. The Bidder's written safety plan;
 - D. Whether the Bidder is qualified legally to contract with the State;
 - E. Whether the Bidder supplied all necessary information concerning its responsibility; and,

F. Any other specific criteria for a particular procurement, which an agency may establish; provided however, that, the criteria be set forth in the Invitation to Bid and is otherwise in conformity with State and/or Federal law.

5.3.2 If an agency determines that a Bidder is nonresponsive and/or nonresponsible, the determination shall be in writing and set forth the basis for the determination. A copy of the determination shall be sent to the affected Bidder within five (5) working days of said determination.

5.3.3 In addition, any one or more of the following causes may be considered as sufficient for the disqualification of a Bidder and the rejection of their Bid or Bids.

5.3.3.1 More than one Bid for the same Contract from an individual, firm or corporation under the same or different names.

5.3.3.2 Evidence of collusion among Bidders.

5.3.3.3 Unsatisfactory performance record as evidenced by past experience.

5.3.3.4 If the Unit Prices are obviously unbalanced either in excess or below reasonable cost analysis values.

5.3.3.5 If there are any unauthorized additions, interlineation, conditional or alternate bids or irregularities of any kind which may tend to make the Bid incomplete, indefinite or ambiguous as to its meaning.

5.3.3.6 If the Bid is not accompanied by the required Bid Security and other data required by the Bidding Documents.

5.3.3.7 If any exceptions or qualifications of the Bid are noted on the Bid Form.

5.4 ACCEPTANCE OF BID AND AWARD OF CONTRACT

5.4.1 A formal Contract shall be executed with the successful Bidder within twenty (20) calendar days after the award of the Contract.

5.4.2 Per Section 6962(d)(13) a., Title 29, Delaware Code, "The contracting agency shall award any public works contract within thirty (30) days of the bid opening to the lowest responsive and responsible Bidder, unless the Agency elects to award on the basis of best value, in which case the election to award on the basis of best value shall be stated in the Invitation To Bid."

5.4.3 Each Bid on any Public Works Contract must be deemed responsive by the Agency to be considered for award. A responsive Bid shall conform in all material respects to the requirements and criteria set forth in the Contract Documents and specifications.

5.4.4 The Agency shall have the right to accept Alternates in any order or combination, and to determine the low Bidder on the basis of the sum of the Base Bid, plus accepted Alternates.

5.4.5 The successful Bidder shall execute a formal contract, submit the required Insurance Certificate, and furnish good and sufficient bonds, unless specifically waived in the General

Requirements, in accordance with the General Requirement, within twenty (20) days of official notice of contract award. The successful Bidder shall provide, at least two business days prior to contract execution, copies of the Employee Drug Testing Program for the Bidder and all listed Subcontractors. Bonds shall be for the benefit of the Agency with surety in the amount of 100% of the total contract award. Said Bonds shall be conditioned upon the faithful performance of the contract. Bonds shall remain in affect for period of one year after the date of substantial completion.

5.4.6 If the successful Bidder fails to execute the required Contract, Bond and all required information, as aforesaid, within twenty (20) calendar days after the date of official Notice of the Award of the Contract, their Bid guaranty shall immediately be taken and become the property of the State for the benefit of the Agency as liquidated damages, and not as a forfeiture or as a penalty. Award will then be made to the next lowest qualified Bidder of the Work or readvertised, as the Agency may decide.

5.4.7 Each bidder shall supply with its bid its taxpayer identification number (i.e., federal employer identification number or social security number) and a copy of its Delaware business license, and should the vendor be awarded a contract, such vendor shall provide to the agency the taxpayer identification license numbers of such subcontractors. Such numbers shall be provided on the later of the date on which such subcontractor is required to be identified or the time the contract is executed. The successful Bidder shall provide to the agency to which it is contracting, within 30 days of entering into such public works contract, copies of all Delaware Business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the Bidder entered the public works contract the Delaware Business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.

5.4.8 The Bid Security shall be returned to the successful Bidder upon the execution of the formal contract. The Bid Securities of unsuccessful bidders shall be returned within thirty (30) calendar days after the opening of the Bids.

ARTICLE 6: POST-BID INFORMATION

6.1 CONTRACTOR'S QUALIFICATION STATEMENT

6.1.1 Bidders to whom an award of a Contract is under consideration shall, if requested by the Agency, submit a properly executed AIA Document A305, Contractor's Qualification Statement, unless such a statement has been previously required and submitted.

6.2 BUSINESS DESIGNATION FORM

6.2.1 Successful bidder shall be required to accurately complete an Office of Management and Budget Business Designation Form for Subcontractors.

6.3 Bidders to whom an award of a Contract has been made must produce their Delaware Business License before the Contract can be executed.

ARTICLE 7: PERFORMANCE BOND AND PAYMENT BOND

7.1 BOND REQUIREMENTS

7.1.1 The cost of furnishing the required Bonds, that are stipulated in the Bidding Documents, shall be included in the Bid.

7.1.2 If the Bidder is required by the Agency to secure a bond from other than the Bidder's usual sources, changes in cost will be adjusted as provide in the Contract Documents.

7.1.3 The Performance and Payment Bond forms used shall be the standard OMB forms (attached).

7.2 TIME OF DELIVERY AND FORM OF BONDS

7.2.1 The bonds shall be dated on or after the date of the Contract.

7.2.2 The Bidder shall require the attorney-in-fact who executes the required bonds on behalf of the surety to affix a certified and current copy of the power of attorney.

ARTICLE 8: FORM OF AGREEMENT BETWEEN AGENCY AND CONTRACTOR

8.1 Unless otherwise required in the Bidding Documents, the Agreement for the Work will be written on AIA Document A101, Standard Form of Agreement Between Owner and Contractor Where the Basis of Payment is a Stipulated Sum.

END OF INSTRUCTIONS TO BIDDERS

HEAT OF REJECTION EQUIPMENT REPLACEMENT (IRD25036-HVAC)

CONTRACT NO.: IRD25036-HVAC

For Bids Due: October 22, 2025

Name of Bidder: _____

Delaware Business License No.: _____ **Taxpayer ID No.:** _____

(Other License Nos.): _____

Phone No.: () _____ - _____ **Fax No.:** () _____ - _____

\$ _____
(\$ _____)

Bidder shall include allowance amount in Base Bid.

Allowances conform to applicable project specification section. Refer to the specifications for a complete description of the following Allowance:

Allowance No. 1: For general contingencies and repairs, the remaining balance of which is to be returned to owner by credit change order at project conclusion.

Alternate prices conform to applicable project specification section. Refer to specifications for a complete description of the following Alternates. An “ADD” or “DEDUCT” amount is indicated by the crossed out part that does not apply.

ALTERNATE No. 1: Selbyville Middle School Cooling Tower System

Add: _____
(\$ _____)

INDIAN RIVER SCHOOL DISTRICT – HEAT OF REJECTION EQUIPMENT REPLACEMENT FOR GEORGE WASHINGTON
CARVER EDUCATIONAL CENTER AND SELBYVILLE MIDDLE SCHOOL – SUSSEX COUNTY, DE

CONTRACT NO.: IRD25036-HVAC

BID FORM

I/We acknowledge Addendums numbered _____ and the price(s) submitted include any cost/schedule impact they may have.

This bid shall remain valid and cannot be withdrawn for sixty (60) days from the date of opening of bids (60 days for School Districts and Department of Education), and the undersigned shall abide by the Bid Security forfeiture provisions. Bid Security is attached to this Bid.

The Owner shall have the right to reject any or all bids, and to waive any informality or irregularity in any bid received.

This bid is based upon work being accomplished by the Sub-Contractors named on the list attached to this bid.

Should I/We be awarded this contract, I/We pledge to achieve substantial completion of all the work within _____ calendar days of the Notice to Proceed.

The undersigned represents and warrants that he has complied and shall comply with all requirements of local, state, and national laws; that no legal requirement has been or shall be violated in making or accepting this bid, in awarding the contract to him or in the prosecution of the work required; that the bid is legal and firm; that he has not, directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken action in restraint of free competitive bidding.

Upon receipt of written notice of the acceptance of this Bid, the Bidder shall, within twenty (20) calendar days, execute the agreement in the required form and deliver the Contract Bonds, and Insurance Certificates, required by the Contract Documents.

I am / We are an Individual / a Partnership / a Corporation

By _____ Trading as _____
(Individual's / General Partner's / Corporate Name)

(State of Corporation)

Business Address: _____

Witness: _____ By: _____
(SEAL) (Authorized Signature)

(Title)
Date: _____

ATTACHMENTS

Sub-Contractor List
Non-Collusion Statement
Affidavit of Employee Drug Testing Program
Affidavit of Contractor Qualifications
Bid Security
(Others as Required by Project Manuals)

INDIAN RIVER SCHOOL DISTRICT – HEAT OF REJECTION EQUIPMENT REPLACEMENT FOR GEORGE WASHINGTON CARVER EDUCATIONAL CENTER AND
SELBYVILLE MIDDLE SCHOOL – SUSSEX COUNTY, DE

CONTRACT NO.: IRD25036-HVAC

BID FORM

SUBCONTRACTOR LIST

In accordance with Title 29, Chapter 69, Section 6962(d)(10)b of the Delaware Code, the following subcontractor listing must accompany any bid submittal. The bidder must list **in each category** the full name and address (City & State) of the sub-contractor that the bidder will be using to perform the work and provide material for that subcontractor category. Should the bidder’s listed subcontractor intend to provide any of their subcontractor category of work through a third-tier contractor, the bidder shall list that third-tier contractor’s full name and address (City & State). **If the bidder intends to perform any category of work itself, it must list its full name and address.** For clarification, if the bidder intends to perform the work themselves, the bidder **may not** insert “not applicable”, “N/A”, “self” or anything other than its own full name and address (City & State). To do so shall cause the bid to be rejected. In addition, the failure to produce a completed subcontractor list with the bid submittal shall cause the bid to be rejected. If you have more than three (3) third-tier contractors to report in any subcontractor category, print out additional page(s) containing the appropriate category, complete the rest of your list of third-tier contractors for that category, notate the addition in parentheses as (CONTINUATION) next to the subcontractor category and an asterisk (*) next to any additional third-tier contractors, and submit it with your bid.

<u>Subcontractor Category</u>	<u>Subcontractor</u>	<u>Address (City & State)</u>	<u>Subcontractors tax-payer ID # or Delaware Business license #</u>
1. Electrical	_____	_____	_____
2. Insulation	_____	_____	_____
3. Cooling Tower Manufacturer	_____	_____	_____
4. Closed Circuit Evaporative Fluid Cooler Manufacturer	_____	_____	_____
5. HVAC Piping	_____	_____	_____
6. ATC Controls	_____	_____	_____
7. Concrete & Masonry	_____	_____	_____
8. Testing & Balancing	_____	_____	_____
9. Water Treatment Vendor	_____	_____	_____

INDIAN RIVER SCHOOL DISTRICT – HEAT OF REJECTION EQUIPMENT REPLACEMENT FOR GEORGE WASHINGTON
CARVER EDUCATIONAL CENTER AND SELBYVILLE MIDDLE SCHOOL – SUSSEX COUNTY, DE

CONTRACT NO.: IRD25036-HVAC

BID FORM

NON-COLLUSION STATEMENT

This is to certify that the undersigned bidder has neither directly nor indirectly, entered into any agreement, participated in any collusion or otherwise taken any action in restraint of free competitive bidding in connection with this proposal submitted this date (*to the Office of Management and Budget, Division of Facilities Management*).

All the terms and conditions of (*Project or Contract Number*) have been thoroughly examined and are understood.

NAME OF BIDDER:

**AUTHORIZED REPRESENTATIVE
(TYPED):**

**AUTHORIZED REPRESENTATIVE
(SIGNATURE):**

TITLE:

ADDRESS OF BIDDER:

E-MAIL:

PHONE NUMBER:

Sworn to and Subscribed before me this _____ day of _____ 20____.

My Commission expires _____. NOTARY PUBLIC _____.

THIS PAGE MUST BE SIGNED AND NOTARIZED FOR YOUR BID TO BE CONSIDERED.

INDIAN RIVER SCHOOL DISTRICT – HEAT OF REJECTION EQUIPMENT REPLACEMENT FOR GEORGE WASHINGTON
CARVER EDUCATIONAL CENTER AND SELBYVILLE MIDDLE SCHOOL – SUSSEX COUNTY, DE

CONTRACT NO.: IRD25036-HVAC

**AFFIDAVIT
OF
EMPLOYEE DRUG TESTING PROGRAM**

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects requires that Contractors and Subcontractors implement a program of mandatory drug testing for Employees who work on Large Public Works Contracts funded all or in part with public funds.

We hereby certify that we have in place or will implement during the entire term of the contract a Mandatory Drug Testing Program for our employees on the jobsite, including subcontractors, that complies with this regulation:

Contractor/Subcontractor Name: _____

Contractor/Subcontractor Address: _____

Authorized Representative (typed or printed): _____

Authorized Representative (signature): _____

Title: _____

Sworn to and Subscribed before me this _____ day of _____ 20____.

My Commission expires _____. NOTARY PUBLIC _____.

THIS PAGE MUST BE SIGNED AND NOTARIZED FOR YOUR BID TO BE CONSIDERED.

INDIAN RIVER SCHOOL DISTRICT – HEAT OF REJECTION EQUIPMENT REPLACEMENT FOR GEORGE WASHINGTON
CARVER EDUCATIONAL CENTER AND SELBYVILLE MIDDLE SCHOOL – SUSSEX COUNTY, DE

CONTRACT NO.: IRD25036-HVAC

**AFFIDAVIT
OF
CONTRACTOR QUALIFICATIONS**

We hereby certify that we will abide by the contractor's qualifications outlined in the construction bid specifications for the duration of the contract term.

In accordance with Title 29, Chapter 69, Section 6962(d)(10)b.3 of the Delaware Code, after a contract has been awarded the successful bidder shall not substitute another subcontractor whose name was submitted on the Subcontractor Form except for the reasons in the statute and not without written consent from the awarding agency. Failure to utilize the subcontractors on the list will subject the successful bidder to penalties as outlined in the General Requirements Section 5.2 of the contract.

Contractor Name:

Contractor Address:

Authorized Representative (typed or printed):

Authorized Representative (signature):

Title:

Sworn to and Subscribed before me this _____ day of _____ 20____.

My Commission expires _____. NOTARY PUBLIC _____.

THIS PAGE MUST BE SIGNED AND NOTARIZED FOR YOUR BID TO BE CONSIDERED.

BID BOND

Bid Bond attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

STATE OF DELAWARE - OFFICE OF MANAGEMENT AND BUDGET

BID BOND

TO ACCOMPANY PROPOSAL
(Not necessary if security is used)

KNOW ALL MEN BY THESE PRESENTS That: _____
_____ of _____ in the County of _____
_____ and State of _____ as **Principal**, and _____
_____ of _____ in the County of _____
and State of _____ as **Surety**, legally authorized to do business in the State of Delaware
("State"), are held and firmly unto the **State** in the sum of _____
_____ Dollars (\$ _____), or _____ percent not to exceed _____
_____ Dollars (\$ _____)
of amount of bid on Contract No. _____, to be paid to the **State** for the use and
benefit of Indian River School District (IRD25036-HVAC) for which payment well and truly to be made, we
do bind ourselves, our and each of our heirs, executors, administrators, and successors, jointly and severally
for and in the whole firmly by these presents.

NOW THE CONDITION OF THIS OBLIGATION IS SUCH That if the above bonded **Principal**
who has submitted to the Indian River School District (IRD25036-HVAC) a certain proposal to enter into
this contract for the furnishing of certain material and/or services within the **State**, shall be awarded this
Contract, and if said **Principal** shall well and truly enter into and execute this Contract as may be required by
the terms of this Contract and approved by the Indian River School District (IRD25036-HVAC) this Contract
to be entered into within twenty days after the date of official notice of the award thereof in accordance with
the terms of said proposal, then this obligation shall be void or else to be and remain in full force and virtue.

Sealed with _____ seal and dated this _____ day of _____ in the year of our Lord two
thousand and _____ (20____).

SEALED, AND DELIVERED IN THE
Presence of

Name of Bidder (Organization)

Corporate
Seal

By:

Authorized Signature

Attest _____

Title

Name of Surety

Witness: _____

By:

THIS PAGE LEFT INTENTIONALLY BLANK

STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR A101-2017

The contract to be utilized on this project shall be the “Standard Form of Agreement Between Owner and Contractor” AIA Document A101-2017.

THIS PAGE LEFT INTENTIONALLY BLANK

AIA[®] Document A101[™] – 2017

Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum

AGREEMENT made as of the day of in the year
(In words, indicate day, month and year.)

BETWEEN the Owner:
(Name, legal status, address and other information)

and the Contractor:
(Name, legal status, address and other information)

for the following Project:
(Name, location and detailed description)

The Architect:
(Name, legal status, address and other information)

The Owner and Contractor agree as follows.

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

The parties should complete A101[™]–2017, Exhibit A, Insurance and Bonds, contemporaneously with this Agreement. AIA Document A201[™]–2017, General Conditions of the Contract for Construction, is adopted in this document by reference. Do not use with other general conditions unless this document is modified.

TABLE OF ARTICLES

- 1 THE CONTRACT DOCUMENTS
- 2 THE WORK OF THIS CONTRACT
- 3 DATE OF COMMENCEMENT AND SUBSTANTIAL COMPLETION
- 4 CONTRACT SUM
- 5 PAYMENTS
- 6 DISPUTE RESOLUTION
- 7 TERMINATION OR SUSPENSION
- 8 MISCELLANEOUS PROVISIONS
- 9 ENUMERATION OF CONTRACT DOCUMENTS

EXHIBIT A INSURANCE AND BONDS

ARTICLE 1 THE CONTRACT DOCUMENTS

The Contract Documents consist of this Agreement, Conditions of the Contract (General, Supplementary, and other Conditions), Drawings, Specifications, Addenda issued prior to execution of this Agreement, other documents listed in this Agreement, and Modifications issued after execution of this Agreement, all of which form the Contract, and are as fully a part of the Contract as if attached to this Agreement or repeated herein. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations, or agreements, either written or oral. An enumeration of the Contract Documents, other than a Modification, appears in Article 9.

ARTICLE 2 THE WORK OF THIS CONTRACT

The Contractor shall fully execute the Work described in the Contract Documents, except as specifically indicated in the Contract Documents to be the responsibility of others.

ARTICLE 3 DATE OF COMMENCEMENT AND SUBSTANTIAL COMPLETION

§ 3.1 The date of commencement of the Work shall be:

(Check one of the following boxes.)

☐ The date of this Agreement.

☐ A date set forth in a notice to proceed issued by the Owner.

☐ Established as follows:

(Insert a date or a means to determine the date of commencement of the Work.)

If a date of commencement of the Work is not selected, then the date of commencement shall be the date of this Agreement.

§ 3.2 The Contract Time shall be measured from the date of commencement of the Work.

§ 3.3 Substantial Completion

§ 3.3.1 Subject to adjustments of the Contract Time as provided in the Contract Documents, the Contractor shall achieve Substantial Completion of the entire Work:

Init.

(Check one of the following boxes and complete the necessary information.)

☐ Not later than () calendar days from the date of commencement of the Work.

☐ By the following date:

§ 3.3.2 Subject to adjustments of the Contract Time as provided in the Contract Documents, if portions of the Work are to be completed prior to Substantial Completion of the entire Work, the Contractor shall achieve Substantial Completion of such portions by the following dates:

Portion of Work

Substantial Completion Date

§ 3.3.3 If the Contractor fails to achieve Substantial Completion as provided in this Section 3.3, liquidated damages, if any, shall be assessed as set forth in Section 4.5.

ARTICLE 4 CONTRACT SUM

§ 4.1 The Owner shall pay the Contractor the Contract Sum in current funds for the Contractor's performance of the Contract. The Contract Sum shall be (\$), subject to additions and deductions as provided in the Contract Documents.

§ 4.2 Alternates

§ 4.2.1 Alternates, if any, included in the Contract Sum:

Item

Price

§ 4.2.2 Subject to the conditions noted below, the following alternates may be accepted by the Owner following execution of this Agreement. Upon acceptance, the Owner shall issue a Modification to this Agreement.
(Insert below each alternate and the conditions that must be met for the Owner to accept the alternate.)

Item

Price

Conditions for Acceptance

§ 4.3 Allowances, if any, included in the Contract Sum:
(Identify each allowance.)

Item

Price

§ 4.4 Unit prices, if any:

(Identify the item and state the unit price and quantity limitations, if any, to which the unit price will be applicable.)

Item

Units and Limitations

Price per Unit (\$0.00)

§ 4.5 Liquidated damages, if any:

(Insert terms and conditions for liquidated damages, if any.)

§ 4.6 Other:

(Insert provisions for bonus or other incentives, if any, that might result in a change to the Contract Sum.)

ARTICLE 5 PAYMENTS

§ 5.1 Progress Payments

§ 5.1.1 Based upon Applications for Payment submitted to the Architect by the Contractor and Certificates for Payment issued by the Architect, the Owner shall make progress payments on account of the Contract Sum to the Contractor as provided below and elsewhere in the Contract Documents.

§ 5.1.2 The period covered by each Application for Payment shall be one calendar month ending on the last day of the month, or as follows:

§ 5.1.3 Provided that an Application for Payment is received by the Architect not later than the day of a month, the Owner shall make payment of the amount certified to the Contractor not later than the day of the month. If an Application for Payment is received by the Architect after the application date fixed above, payment of the amount certified shall be made by the Owner not later than () days after the Architect receives the Application for Payment.

(Federal, state or local laws may require payment within a certain period of time.)

§ 5.1.4 Each Application for Payment shall be based on the most recent schedule of values submitted by the Contractor in accordance with the Contract Documents. The schedule of values shall allocate the entire Contract Sum among the various portions of the Work. The schedule of values shall be prepared in such form, and supported by such data to substantiate its accuracy, as the Architect may require. This schedule of values shall be used as a basis for reviewing the Contractor's Applications for Payment.

§ 5.1.5 Applications for Payment shall show the percentage of completion of each portion of the Work as of the end of the period covered by the Application for Payment.

§ 5.1.6 In accordance with AIA Document A201™-2017, General Conditions of the Contract for Construction, and subject to other provisions of the Contract Documents, the amount of each progress payment shall be computed as follows:

§ 5.1.6.1 The amount of each progress payment shall first include:

- .1 That portion of the Contract Sum properly allocable to completed Work;
- .2 That portion of the Contract Sum properly allocable to materials and equipment delivered and suitably stored at the site for subsequent incorporation in the completed construction, or, if approved in advance by the Owner, suitably stored off the site at a location agreed upon in writing; and
- .3 That portion of Construction Change Directives that the Architect determines, in the Architect's professional judgment, to be reasonably justified.

§ 5.1.6.2 The amount of each progress payment shall then be reduced by:

- .1 The aggregate of any amounts previously paid by the Owner;
- .2 The amount, if any, for Work that remains uncorrected and for which the Architect has previously withheld a Certificate for Payment as provided in Article 9 of AIA Document A201-2017;
- .3 Any amount for which the Contractor does not intend to pay a Subcontractor or material supplier, unless the Work has been performed by others the Contractor intends to pay;
- .4 For Work performed or defects discovered since the last payment application, any amount for which the Architect may withhold payment, or nullify a Certificate of Payment in whole or in part, as provided in Article 9 of AIA Document A201-2017; and
- .5 Retainage withheld pursuant to Section 5.1.7.

§ 5.1.7 Retainage

§ 5.1.7.1 For each progress payment made prior to Substantial Completion of the Work, the Owner may withhold the following amount, as retainage, from the payment otherwise due:

(Insert a percentage or amount to be withheld as retainage from each Application for Payment. The amount of retainage may be limited by governing law.)

§ 5.1.7.1.1 The following items are not subject to retainage:

(Insert any items not subject to the withholding of retainage, such as general conditions, insurance, etc.)

§ 5.1.7.2 Reduction or limitation of retainage, if any, shall be as follows:

(If the retainage established in Section 5.1.7.1 is to be modified prior to Substantial Completion of the entire Work, including modifications for Substantial Completion of portions of the Work as provided in Section 3.3.2, insert provisions for such modifications.)

§ 5.1.7.3 Except as set forth in this Section 5.1.7.3, upon Substantial Completion of the Work, the Contractor may submit an Application for Payment that includes the retainage withheld from prior Applications for Payment pursuant to this Section 5.1.7. The Application for Payment submitted at Substantial Completion shall not include retainage as follows:

(Insert any other conditions for release of retainage upon Substantial Completion.)

§ 5.1.8 If final completion of the Work is materially delayed through no fault of the Contractor, the Owner shall pay the Contractor any additional amounts in accordance with Article 9 of AIA Document A201–2017.

§ 5.1.9 Except with the Owner's prior approval, the Contractor shall not make advance payments to suppliers for materials or equipment which have not been delivered and stored at the site.

§ 5.2 Final Payment

§ 5.2.1 Final payment, constituting the entire unpaid balance of the Contract Sum, shall be made by the Owner to the Contractor when

- .1 the Contractor has fully performed the Contract except for the Contractor's responsibility to correct Work as provided in Article 12 of AIA Document A201–2017, and to satisfy other requirements, if any, which extend beyond final payment; and
- .2 a final Certificate for Payment has been issued by the Architect.

§ 5.2.2 The Owner's final payment to the Contractor shall be made no later than 30 days after the issuance of the Architect's final Certificate for Payment, or as follows:

§ 5.3 Interest

Payments due and unpaid under the Contract shall bear interest from the date payment is due at the rate stated below, or in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located.

(Insert rate of interest agreed upon, if any.)

%

ARTICLE 6 DISPUTE RESOLUTION

§ 6.1 Initial Decision Maker

The Architect will serve as the Initial Decision Maker pursuant to Article 15 of AIA Document A201–2017, unless the parties appoint below another individual, not a party to this Agreement, to serve as the Initial Decision Maker. *(If the parties mutually agree, insert the name, address and other contact information of the Initial Decision Maker, if other than the Architect.)*

§ 6.2 Binding Dispute Resolution

For any Claim subject to, but not resolved by, mediation pursuant to Article 15 of AIA Document A201–2017, the method of binding dispute resolution shall be as follows:

(Check the appropriate box.)

☐ Arbitration pursuant to Section 15.4 of AIA Document A201–2017

☐ Litigation in a court of competent jurisdiction

☐ Other *(Specify)*

If the Owner and Contractor do not select a method of binding dispute resolution, or do not subsequently agree in writing to a binding dispute resolution method other than litigation, Claims will be resolved by litigation in a court of competent jurisdiction.

ARTICLE 7 TERMINATION OR SUSPENSION

§ 7.1 The Contract may be terminated by the Owner or the Contractor as provided in Article 14 of AIA Document A201–2017.

§ 7.1.1 If the Contract is terminated for the Owner's convenience in accordance with Article 14 of AIA Document A201–2017, then the Owner shall pay the Contractor a termination fee as follows:

(Insert the amount of, or method for determining, the fee, if any, payable to the Contractor following a termination for the Owner's convenience.)

§ 7.2 The Work may be suspended by the Owner as provided in Article 14 of AIA Document A201–2017.

ARTICLE 8 MISCELLANEOUS PROVISIONS

§ 8.1 Where reference is made in this Agreement to a provision of AIA Document A201–2017 or another Contract Document, the reference refers to that provision as amended or supplemented by other provisions of the Contract Documents.

§ 8.2 The Owner's representative:

(Name, address, email address, and other information)

§ 8.3 The Contractor's representative:

(Name, address, email address, and other information)

§ 8.4 Neither the Owner's nor the Contractor's representative shall be changed without ten days' prior notice to the other party.

§ 8.5 Insurance and Bonds

§ 8.5.1 The Owner and the Contractor shall purchase and maintain insurance as set forth in AIA Document A101™-2017, Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum, Exhibit A, Insurance and Bonds, and elsewhere in the Contract Documents.

§ 8.5.2 The Contractor shall provide bonds as set forth in AIA Document A101™-2017 Exhibit A, and elsewhere in the Contract Documents.

§ 8.6 Notice in electronic format, pursuant to Article 1 of AIA Document A201-2017, may be given in accordance with AIA Document E203™-2013, Building Information Modeling and Digital Data Exhibit, if completed, or as otherwise set forth below:

(If other than in accordance with AIA Document E203-2013, insert requirements for delivering notice in electronic format such as name, title, and email address of the recipient and whether and how the system will be required to generate a read receipt for the transmission.)

§ 8.7 Other provisions:

ARTICLE 9 ENUMERATION OF CONTRACT DOCUMENTS

§ 9.1 This Agreement is comprised of the following documents:

- .1 AIA Document A101™-2017, Standard Form of Agreement Between Owner and Contractor
- .2 AIA Document A101™-2017, Exhibit A, Insurance and Bonds
- .3 AIA Document A201™-2017, General Conditions of the Contract for Construction
- .4 AIA Document E203™-2013, Building Information Modeling and Digital Data Exhibit, dated as indicated below:
(Insert the date of the E203-2013 incorporated into this Agreement.)

.5 Drawings

Number	Title	Date

.6 Specifications

Section	Title	Date	Pages

.7 Addenda, if any:

Number	Date	Pages

Portions of Addenda relating to bidding or proposal requirements are not part of the Contract Documents unless the bidding or proposal requirements are also enumerated in this Article 9.

.8 Other Exhibits:

(Check all boxes that apply and include appropriate information identifying the exhibit where required.)

Init.

☐ AIA Document E204™–2017, Sustainable Projects Exhibit, dated as indicated below:
(Insert the date of the E204-2017 incorporated into this Agreement.)

☐ The Sustainability Plan:

Title	Date	Pages

☐ Supplementary and other Conditions of the Contract:

Document	Title	Date	Pages

.9 Other documents, if any, listed below:

(List here any additional documents that are intended to form part of the Contract Documents. AIA Document A201™–2017 provides that the advertisement or invitation to bid, Instructions to Bidders, sample forms, the Contractor's bid or proposal, portions of Addenda relating to bidding or proposal requirements, and other information furnished by the Owner in anticipation of receiving bids or proposals, are not part of the Contract Documents unless enumerated in this Agreement. Any such documents should be listed here only if intended to be part of the Contract Documents.)

This Agreement entered into as of the day and year first written above.

OWNER (Signature)

CONTRACTOR (Signature)

(Printed name and title)

(Printed name and title)

Additions and Deletions Report for **AIA® Document A101™ – 2017**

This Additions and Deletions Report, as defined on page 1 of the associated document, reproduces below all text the author has added to the standard form AIA document in order to complete it, as well as any text the author may have added to or deleted from the original AIA text. Added text is shown underlined. Deleted text is indicated with a horizontal line through the original AIA text.

Note: This Additions and Deletions Report is provided for information purposes only and is not incorporated into or constitute any part of the associated AIA document. This Additions and Deletions Report and its associated document were generated simultaneously by AIA software at 15:35:54 ET on 05/31/2019.

Certification of Document's Authenticity

AIA® Document D401™ – 2003

I, , hereby certify, to the best of my knowledge, information and belief, that I created the attached final document simultaneously with its associated Additions and Deletions Report and this certification at 15:35:54 ET on 05/31/2019 under Order No. 1840604654 from AIA Contract Documents software and that in preparing the attached final document I made no changes to the original text of AIA® Document A101™ - 2017, Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum, as published by the AIA in its software, other than those additions and deletions shown in the associated Additions and Deletions Report.

(Signed)

(Title)

(Dated)

AIA® Document A101™ – 2017 Exhibit A

Insurance and Bonds

This Insurance and Bonds Exhibit is part of the Agreement, between the Owner and the Contractor, dated the day of in the year
(In words, indicate day, month and year.)

for the following **PROJECT**:
(Name and location or address)

THE OWNER:
(Name, legal status and address)

THE CONTRACTOR:
(Name, legal status and address)

TABLE OF ARTICLES

A.1 GENERAL

A.2 OWNER'S INSURANCE

A.3 CONTRACTOR'S INSURANCE AND BONDS

A.4 SPECIAL TERMS AND CONDITIONS

ARTICLE A.1 GENERAL

The Owner and Contractor shall purchase and maintain insurance, and provide bonds, as set forth in this Exhibit. As used in this Exhibit, the term General Conditions refers to AIA Document A201™–2017, General Conditions of the Contract for Construction.

ARTICLE A.2 OWNER'S INSURANCE

§ A.2.1 General

Prior to commencement of the Work, the Owner shall secure the insurance, and provide evidence of the coverage, required under this Article A.2 and, upon the Contractor's request, provide a copy of the property insurance policy or policies required by Section A.2.3. The copy of the policy or policies provided shall contain all applicable conditions, definitions, exclusions, and endorsements.

§ A.2.2 Liability Insurance

The Owner shall be responsible for purchasing and maintaining the Owner's usual general liability insurance.

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

This document is intended to be used in conjunction with AIA Document A201™–2017, General Conditions of the Contract for Construction. Article 11 of A201™–2017 contains additional insurance provisions.

§ A.2.3 Required Property Insurance

§ A.2.3.1 Unless this obligation is placed on the Contractor pursuant to Section A.3.3.2.1, the Owner shall purchase and maintain, from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located, property insurance written on a builder's risk "all-risks" completed value or equivalent policy form and sufficient to cover the total value of the entire Project on a replacement cost basis. The Owner's property insurance coverage shall be no less than the amount of the initial Contract Sum, plus the value of subsequent Modifications and labor performed and materials or equipment supplied by others. The property insurance shall be maintained until Substantial Completion and thereafter as provided in Section A.2.3.1.3, unless otherwise provided in the Contract Documents or otherwise agreed in writing by the parties to this Agreement. This insurance shall include the interests of the Owner, Contractor, Subcontractors, and Sub-subcontractors in the Project as insureds. This insurance shall include the interests of mortgagees as loss payees.

§ A.2.3.1.1 **Causes of Loss.** The insurance required by this Section A.2.3.1 shall provide coverage for direct physical loss or damage, and shall not exclude the risks of fire, explosion, theft, vandalism, malicious mischief, collapse, earthquake, flood, or windstorm. The insurance shall also provide coverage for ensuing loss or resulting damage from error, omission, or deficiency in construction methods, design, specifications, workmanship, or materials. Sub-limits, if any, are as follows:

(Indicate below the cause of loss and any applicable sub-limit.)

Causes of Loss

Sub-Limit

§ A.2.3.1.2 **Specific Required Coverages.** The insurance required by this Section A.2.3.1 shall provide coverage for loss or damage to falsework and other temporary structures, and to building systems from testing and startup. The insurance shall also cover debris removal, including demolition occasioned by enforcement of any applicable legal requirements, and reasonable compensation for the Architect's and Contractor's services and expenses required as a result of such insured loss, including claim preparation expenses. Sub-limits, if any, are as follows:

(Indicate below type of coverage and any applicable sub-limit for specific required coverages.)

Coverage

Sub-Limit

§ A.2.3.1.3 Unless the parties agree otherwise, upon Substantial Completion, the Owner shall continue the insurance required by Section A.2.3.1 or, if necessary, replace the insurance policy required under Section A.2.3.1 with property insurance written for the total value of the Project that shall remain in effect until expiration of the period for correction of the Work set forth in Section 12.2.2 of the General Conditions.

§ A.2.3.1.4 **Deductibles and Self-Insured Retentions.** If the insurance required by this Section A.2.3 is subject to deductibles or self-insured retentions, the Owner shall be responsible for all loss not covered because of such deductibles or retentions.

§ A.2.3.2 **Occupancy or Use Prior to Substantial Completion.** The Owner's occupancy or use of any completed or partially completed portion of the Work prior to Substantial Completion shall not commence until the insurance company or companies providing the insurance under Section A.2.3.1 have consented in writing to the continuance of coverage. The Owner and the Contractor shall take no action with respect to partial occupancy or use that would cause cancellation, lapse, or reduction of insurance, unless they agree otherwise in writing.

§ A.2.3.3 Insurance for Existing Structures

If the Work involves remodeling an existing structure or constructing an addition to an existing structure, the Owner shall purchase and maintain, until the expiration of the period for correction of Work as set forth in Section 12.2.2 of the General Conditions, "all-risks" property insurance, on a replacement cost basis, protecting the existing structure against direct physical loss or damage from the causes of loss identified in Section A.2.3.1, notwithstanding the undertaking of the Work. The Owner shall be responsible for all co-insurance penalties.

§ A.2.4 Optional Extended Property Insurance.

The Owner shall purchase and maintain the insurance selected and described below.

(Select the types of insurance the Owner is required to purchase and maintain by placing an X in the box(es) next to

Init.

the description(s) of selected insurance. For each type of insurance selected, indicate applicable limits of coverage or other conditions in the fill point below the selected item.)

- ☐ § A.2.4.1 **Loss of Use, Business Interruption, and Delay in Completion Insurance**, to reimburse the Owner for loss of use of the Owner's property, or the inability to conduct normal operations due to a covered cause of loss.
- ☐ § A.2.4.2 **Ordinance or Law Insurance**, for the reasonable and necessary costs to satisfy the minimum requirements of the enforcement of any law or ordinance regulating the demolition, construction, repair, replacement or use of the Project.
- ☐ § A.2.4.3 **Expediting Cost Insurance**, for the reasonable and necessary costs for the temporary repair of damage to insured property, and to expedite the permanent repair or replacement of the damaged property.
- ☐ § A.2.4.4 **Extra Expense Insurance**, to provide reimbursement of the reasonable and necessary excess costs incurred during the period of restoration or repair of the damaged property that are over and above the total costs that would normally have been incurred during the same period of time had no loss or damage occurred.
- ☐ § A.2.4.5 **Civil Authority Insurance**, for losses or costs arising from an order of a civil authority prohibiting access to the Project, provided such order is the direct result of physical damage covered under the required property insurance.
- ☐ § A.2.4.6 **Ingress/Egress Insurance**, for loss due to the necessary interruption of the insured's business due to physical prevention of ingress to, or egress from, the Project as a direct result of physical damage.
- ☐ § A.2.4.7 **Soft Costs Insurance**, to reimburse the Owner for costs due to the delay of completion of the Work, arising out of physical loss or damage covered by the required property insurance: including construction loan fees; leasing and marketing expenses; additional fees, including those of architects, engineers, consultants, attorneys and accountants, needed for the completion of the construction, repairs, or reconstruction; and carrying costs such as property taxes, building permits, additional interest on loans, realty taxes, and insurance premiums over and above normal expenses.

§ A.2.5 Other Optional Insurance.

The Owner shall purchase and maintain the insurance selected below.

(Select the types of insurance the Owner is required to purchase and maintain by placing an X in the box(es) next to the description(s) of selected insurance.)

- ☐ § A.2.5.1 **Cyber Security Insurance** for loss to the Owner due to data security and privacy breach, including costs of investigating a potential or actual breach of confidential or private information.
(Indicate applicable limits of coverage or other conditions in the fill point below.)

[] § A.2.5.2 Other Insurance

(List below any other insurance coverage to be provided by the Owner and any applicable limits.)

Coverage

Limits

ARTICLE A.3 CONTRACTOR'S INSURANCE AND BONDS

§ A.3.1 General

§ A.3.1.1 Certificates of Insurance. The Contractor shall provide certificates of insurance acceptable to the Owner evidencing compliance with the requirements in this Article A.3 at the following times: (1) prior to commencement of the Work; (2) upon renewal or replacement of each required policy of insurance; and (3) upon the Owner's written request. An additional certificate evidencing continuation of commercial liability coverage, including coverage for completed operations, shall be submitted with the final Application for Payment and thereafter upon renewal or replacement of such coverage until the expiration of the periods required by Section A.3.2.1 and Section A.3.3.1. The certificates will show the Owner as an additional insured on the Contractor's Commercial General Liability and excess or umbrella liability policy or policies.

§ A.3.1.2 Deductibles and Self-Insured Retentions. The Contractor shall disclose to the Owner any deductible or self-insured retentions applicable to any insurance required to be provided by the Contractor.

§ A.3.1.3 Additional Insured Obligations. To the fullest extent permitted by law, the Contractor shall cause the commercial general liability coverage to include (1) the Owner, the Architect, and the Architect's consultants as additional insureds for claims caused in whole or in part by the Contractor's negligent acts or omissions during the Contractor's operations; and (2) the Owner as an additional insured for claims caused in whole or in part by the Contractor's negligent acts or omissions for which loss occurs during completed operations. The additional insured coverage shall be primary and non-contributory to any of the Owner's general liability insurance policies and shall apply to both ongoing and completed operations. To the extent commercially available, the additional insured coverage shall be no less than that provided by Insurance Services Office, Inc. (ISO) forms CG 20 10 07 04, CG 20 37 07 04, and, with respect to the Architect and the Architect's consultants, CG 20 32 07 04.

§ A.3.2 Contractor's Required Insurance Coverage

§ A.3.2.1 The Contractor shall purchase and maintain the following types and limits of insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located. The Contractor shall maintain the required insurance until the expiration of the period for correction of Work as set forth in Section 12.2.2 of the General Conditions, unless a different duration is stated below:
(If the Contractor is required to maintain insurance for a duration other than the expiration of the period for correction of Work, state the duration.)

§ A.3.2.2 Commercial General Liability

§ A.3.2.2.1 Commercial General Liability insurance for the Project written on an occurrence form with policy limits of not less than (\$) each occurrence, (\$) general aggregate, and (\$) aggregate for products-completed operations hazard, providing coverage for claims including

- .1 damages because of bodily injury, sickness or disease, including occupational sickness or disease, and death of any person;
- .2 personal injury and advertising injury;
- .3 damages because of physical damage to or destruction of tangible property, including the loss of use of such property;
- .4 bodily injury or property damage arising out of completed operations; and
- .5 the Contractor's indemnity obligations under Section 3.18 of the General Conditions.

§ A.3.2.2.2 The Contractor's Commercial General Liability policy under this Section A.3.2.2 shall not contain an exclusion or restriction of coverage for the following:

- .1 Claims by one insured against another insured, if the exclusion or restriction is based solely on the fact that the claimant is an insured, and there would otherwise be coverage for the claim.
- .2 Claims for property damage to the Contractor's Work arising out of the products-completed operations hazard where the damaged Work or the Work out of which the damage arises was performed by a Subcontractor.
- .3 Claims for bodily injury other than to employees of the insured.
- .4 Claims for indemnity under Section 3.18 of the General Conditions arising out of injury to employees of the insured.
- .5 Claims or loss excluded under a prior work endorsement or other similar exclusionary language.
- .6 Claims or loss due to physical damage under a prior injury endorsement or similar exclusionary language.
- .7 Claims related to residential, multi-family, or other habitational projects, if the Work is to be performed on such a project.
- .8 Claims related to roofing, if the Work involves roofing.
- .9 Claims related to exterior insulation finish systems (EIFS), synthetic stucco or similar exterior coatings or surfaces, if the Work involves such coatings or surfaces.
- .10 Claims related to earth subsidence or movement, where the Work involves such hazards.
- .11 Claims related to explosion, collapse and underground hazards, where the Work involves such hazards.

§ A.3.2.3 Automobile Liability covering vehicles owned, and non-owned vehicles used, by the Contractor, with policy limits of not less than (\$) per accident, for bodily injury, death of any person, and property damage arising out of the ownership, maintenance and use of those motor vehicles along with any other statutorily required automobile coverage.

§ A.3.2.4 The Contractor may achieve the required limits and coverage for Commercial General Liability and Automobile Liability through a combination of primary and excess or umbrella liability insurance, provided such primary and excess or umbrella insurance policies result in the same or greater coverage as the coverages required under Section A.3.2.2 and A.3.2.3, and in no event shall any excess or umbrella liability insurance provide narrower coverage than the primary policy. The excess policy shall not require the exhaustion of the underlying limits only through the actual payment by the underlying insurers.

§ A.3.2.5 Workers' Compensation at statutory limits.

§ A.3.2.6 Employers' Liability with policy limits not less than (\$) each accident, (\$) each employee, and (\$) policy limit.

§ A.3.2.7 Jones Act, and the Longshore & Harbor Workers' Compensation Act, as required, if the Work involves hazards arising from work on or near navigable waterways, including vessels and docks

§ A.3.2.8 If the Contractor is required to furnish professional services as part of the Work, the Contractor shall procure Professional Liability insurance covering performance of the professional services, with policy limits of not less than (\$) per claim and (\$) in the aggregate.

§ A.3.2.9 If the Work involves the transport, dissemination, use, or release of pollutants, the Contractor shall procure Pollution Liability insurance, with policy limits of not less than (\$) per claim and (\$) in the aggregate.

§ A.3.2.10 Coverage under Sections A.3.2.8 and A.3.2.9 may be procured through a Combined Professional Liability and Pollution Liability insurance policy, with combined policy limits of not less than (\$) per claim and (\$) in the aggregate.

§ A.3.2.11 Insurance for maritime liability risks associated with the operation of a vessel, if the Work requires such activities, with policy limits of not less than (\$) per claim and (\$) in the aggregate.

§ A.3.2.12 Insurance for the use or operation of manned or unmanned aircraft, if the Work requires such activities, with policy limits of not less than (\$) per claim and (\$) in the aggregate.

§ A.3.3 Contractor's Other Insurance Coverage

§ A.3.3.1 Insurance selected and described in this Section A.3.3 shall be purchased from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located. The Contractor shall maintain the required insurance until the expiration of the period for correction of Work as set forth in Section 12.2.2 of the General Conditions, unless a different duration is stated below:

(If the Contractor is required to maintain any of the types of insurance selected below for a duration other than the expiration of the period for correction of Work, state the duration.)

§ A.3.3.2 The Contractor shall purchase and maintain the following types and limits of insurance in accordance with Section A.3.3.1.

(Select the types of insurance the Contractor is required to purchase and maintain by placing an X in the box(es) next to the description(s) of selected insurance. Where policy limits are provided, include the policy limit in the appropriate fill point.)

- ☐ § A.3.3.2.1 Property insurance of the same type and scope satisfying the requirements identified in Section A.2.3, which, if selected in this section A.3.3.2.1, relieves the Owner of the responsibility to purchase and maintain such insurance except insurance required by Section A.2.3.1.3 and Section A.2.3.3. The Contractor shall comply with all obligations of the Owner under Section A.2.3 except to the extent provided below. The Contractor shall disclose to the Owner the amount of any deductible, and the Owner shall be responsible for losses within the deductible. Upon request, the Contractor shall provide the Owner with a copy of the property insurance policy or policies required. The Owner shall adjust and settle the loss with the insurer and be the trustee of the proceeds of the property insurance in accordance with Article 11 of the General Conditions unless otherwise set forth below:
(Where the Contractor's obligation to provide property insurance differs from the Owner's obligations as described under Section A.2.3, indicate such differences in the space below. Additionally, if a party other than the Owner will be responsible for adjusting and settling a loss with the insurer and acting as the trustee of the proceeds of property insurance in accordance with Article 11 of the General Conditions, indicate the responsible party below.)

- ☐ § A.3.3.2.2 Railroad Protective Liability Insurance, with policy limits of not less than (\$) per claim and (\$) in the aggregate, for Work within fifty (50) feet of railroad property.

- ☐ § A.3.3.2.3 Asbestos Abatement Liability Insurance, with policy limits of not less than (\$) per claim and (\$) in the aggregate, for liability arising from the encapsulation, removal, handling, storage, transportation, and disposal of asbestos-containing materials.

- ☐ § A.3.3.2.4 Insurance for physical damage to property while it is in storage and in transit to the construction site on an "all-risks" completed value form.

- ☐ § A.3.3.2.5 Property insurance on an "all-risks" completed value form, covering property owned by the Contractor and used on the Project, including scaffolding and other equipment.

- ☐ § A.3.3.2.6 Other Insurance
(List below any other insurance coverage to be provided by the Contractor and any applicable limits.)

Coverage

Limits

§ A.3.4 Performance Bond and Payment Bond

The Contractor shall provide surety bonds, from a company or companies lawfully authorized to issue surety bonds in the jurisdiction where the Project is located, as follows:

(Specify type and penal sum of bonds.)

Type**Penal Sum (\$0.00)**

Payment Bond

Performance Bond

Payment and Performance Bonds shall be AIA Document A312™, Payment Bond and Performance Bond, or contain provisions identical to AIA Document A312™, current as of the date of this Agreement.

ARTICLE A.4 SPECIAL TERMS AND CONDITIONS

Special terms and conditions that modify this Insurance and Bonds Exhibit, if any, are as follows:

Init.

/

Additions and Deletions Report for AIA® Document A101™ – 2017 Exhibit A

This Additions and Deletions Report, as defined on page 1 of the associated document, reproduces below all text the author has added to the standard form AIA document in order to complete it, as well as any text the author may have added to or deleted from the original AIA text. Added text is shown underlined. Deleted text is indicated with a horizontal line through the original AIA text.

Note: This Additions and Deletions Report is provided for information purposes only and is not incorporated into or constitute any part of the associated AIA document. This Additions and Deletions Report and its associated document were generated simultaneously by AIA software at 10:14:56 ET on 06/04/2019.

The following supplements modify the “Standard Form of Agreement Between Owner and Contractor,” AIA Document A101-2017. Where a portion of the Standard Form of Agreement is modified or deleted by the following, the unaltered portions of the Standard Form of Agreement shall remain in effect.

“Provided that a valid Application for Payment is received by the Engineer that meets all requirements of the Contract, payment shall be made by the Owner not later than 30 days after the Owner receives the valid Application for Payment.”

6.2 BINDING DISPUTE RESOLUTION

Check Other – and add the following sentence:

"Any remedies available in law or in equity."

8.2 Insert the following:

"Payments are due 30 days after receipt of a valid Application for Payment. After that 30 day period, interest may be charged at the rate of 1% per month not to exceed 12% per annum."

8.5 Delete paragraph 8.5 in its entirety and replace with the following:

“The Contractor’s representative shall not be changed without ten days written notice to the Owner.”

END OF SUPPLEMENT TO AGREEMENT BETWEEN OWNER AND CONTRACTOR

THIS PAGE LEFT INTENTIONALLY BLANK

PERFORMANCE BOND

Performance Bond attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

PERFORMANCE BOND

STATE OF DELAWARE OFFICE OF MANAGEMENT AND BUDGET

Bond Number: _____

KNOW ALL PERSONS BY THESE PRESENTS, that we, _____, as principal (**"Principal"**), and _____, a _____ corporation, legally authorized to do business in the State of Delaware, as surety (**"Surety"**), are held and firmly bound unto the Indian River School District (IRD25036-HVAC) (**"Owner"**), in the amount of _____ (\$_____), to be paid to **Owner**, for which payment well and truly to be made, we do bind ourselves, our and each and every of our heirs, executors, administrations, successors and assigns, jointly and severally, for and in the whole, firmly by these presents.

Sealed with our seals and dated this _____ day of _____, 20__.

NOW THE CONDITION OF THIS OBLIGATION IS SUCH, that if **Principal**, who has been awarded by **Owner** that certain contract known as Contract No. _____ dated the _____ day of _____, 20__ (the "Contract"), which Contract is incorporated herein by reference, shall well and truly provide and furnish all materials, appliances and tools and perform all the work required under and pursuant to the terms and conditions of the Contract and the Contract Documents (as defined in the Contract) or any changes or modifications thereto made as therein provided, shall make good and reimburse **Owner** sufficient funds to pay the costs of completing the Contract that **Owner** may sustain by reason of any failure or default on the part of **Principal**, and shall also indemnify and save harmless **Owner** from all costs, damages and expenses arising out of or by reason of the performance of the Contract and for as long as provided by the Contract; then this obligation shall be void, otherwise to be and remain in full force and effect.

Surety, for value received, hereby stipulates and agrees, if requested to do so by **Owner**, to fully perform and complete the work to be performed under the Contract pursuant to the terms, conditions and covenants thereof, if for any cause **Principal** fails or neglects to so fully perform and complete such work.

Surety, for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of **Surety** and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition or change in or to the Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any work to be performed or any monies due or to become due thereunder; and **Surety** hereby waives notice of any and all such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to **Surety** as though done or omitted to be done by or in relation to **Principal**.

Surety hereby stipulates and agrees that no modifications, omissions or additions in or to the terms of the Contract shall in any way whatsoever affect the obligation of **Surety** and its bond.

Any proceeding, legal or equitable, under this Bond may be brought in any court of competent jurisdiction in the State of Delaware. Notices to **Surety** or Contractor may be mailed or delivered to them at their respective addresses shown below.

IN WITNESS WHEREOF, **Principal** and **Surety** have hereunto set their hand and seals, and such of them as are corporations have caused their corporate seal to be hereto affixed and these presents to be signed by their duly authorized officers, the day and year first above written.

PRINCIPAL

Name: _____

Witness or Attest: Address: _____

_____ Name: (Corporate Seal)	By: _____ (SEAL) Name: Title:

SURETY

Name: _____

Witness or Attest: Address: _____

_____ Name: (Corporate Seal)	By: _____ (SEAL) Name: Title:

PAYMENT BOND

Payment Bond attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

PAYMENT BOND

STATE OF DELAWARE OFFICE OF MANAGEMENT AND BUDGET

Bond Number: _____

KNOW ALL PERSONS BY THESE PRESENTS, that we, _____, as principal (“**Principal**”), and _____, a _____ corporation, legally authorized to do business in the State of Delaware, as surety (“**Surety**”), are held and firmly bound unto the Indian River School District (IRD25036-HVAC) (“**Owner**”), in the amount of _____ (\$ _____), to be paid to **Owner**, for which payment well and truly to be made, we do bind ourselves, our and each and every of our heirs, executors, administrations, successors and assigns, jointly and severally, for and in the whole firmly by these presents.

Sealed with our seals and dated this _____ day of _____, 20__.

NOW THE CONDITION OF THIS OBLIGATION IS SUCH, that if **Principal**, who has been awarded by **Owner** that certain contract known as Contract No. _____ dated the _____ day of _____, 20__ (the “Contract”), which Contract is incorporated herein by reference, shall well and truly pay all and every person furnishing materials or performing labor or service in and about the performance of the work under the Contract, all and every sums of money due him, her, them or any of them, for all such materials, labor and service for which **Principal** is liable, shall make good and reimburse **Owner** sufficient funds to pay such costs in the completion of the Contract as **Owner** may sustain by reason of any failure or default on the part of **Principal**, and shall also indemnify and save harmless **Owner** from all costs, damages and expenses arising out of or by reason of the performance of the Contract and for as long as provided by the Contract; then this obligation shall be void, otherwise to be and remain in full force and effect.

Surety, for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of **Surety** and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition or change in or to the Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any work to be performed or any monies due or to become due thereunder; and **Surety** hereby waives notice of any and all such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to **Surety** as though done or omitted to be done by or in relation to **Principal**.

Surety hereby stipulates and agrees that no modifications, omission or additions in or to the terms of the Contract shall in any way whatsoever affect the obligation of **Surety** and its bond.

Any proceeding, legal or equitable, under this Bond may be brought in any court of competent jurisdiction in the State of Delaware. Notices to **Surety** or Contractor may be mailed or delivered to them at their respective addresses shown below.

IN WITNESS WHEREOF, **Principal** and **Surety** have hereunto set their hand and seals, and such of them as are corporations have caused their corporate seal to be hereto affixed and these presents to be signed by their duly authorized officers, the day and year first above written.

PRINCIPAL

Name: _____

Witness or Attest: Address: _____

Name:

(Corporate Seal)

By: _____(SEAL)
Name:
Title:

SURETY

Name: _____

Witness or Attest: Address: _____

Name:

(Corporate Seal)

By: _____(SEAL)
Name:
Title:

SUBMITTAL TRANSMITTAL FORM – CSI FORM 12.1A

Submittal Transmittal Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK



SUBMITTAL TRANSMITTAL

Project: _____ Date: _____
A/E Project Number: _____

TRANSMITTAL To (Contractor): _____ Date: _____ Submittal No. _____
A From (Subcontractor): _____ By: _____ ☐ Resubmission

Qty.	Reference / Number	Title / Description / Manufacturer	Spec. Section Title and Paragraph / Drawing Detail Reference

- ☐ Submitted for review and approval
☐ Resubmitted for review and approval
☐ Complies with contract requirements
☐ Will be available to meet construction schedule
☐ A/E review time included in construction schedule

- ☐ Substitution involved - Substitution request attached
☐ If substitution involved, submission includes point-by-point comparative data or preliminary details
☐ Items included in submission will be ordered immediately upon receipt of approval

Other remarks on above submission: _____

☐ One copy retained by sender

TRANSMITTAL To (A/E): _____ Attn: _____ Date Rec'd by Contractor: _____
B From (Contractor): _____ By: _____ Date Trnsmt'd by Contractor: _____

- ☐ Approved
☐ Approved as noted

- ☐ Revise / Resubmit
☐ Rejected / Resubmit

Other remarks on above submission: _____

☐ One copy retained by sender

TRANSMITTAL To (Contractor): _____ Attn: _____ Date Rec'd by A/E: _____
C From (A/E): _____ ☐ Other By: _____ Date Trnsmt'd by A/E: _____

- ☐ Approved
☐ Approved as noted
☐ Not subject to review
☐ No action required
☐ Revise / Resubmit
☐ Rejected / Resubmit
☐ Approved as noted / Resubmit

- ☐ Provide file copy with corrections identified
☐ Sepia copies only returned
☐ Point-by-point comparative data required to complete approval process
☐ Submission Incomplete / Resubmit

Other remarks on above submission: _____

☐ One copy retained by sender

TRANSMITTAL To (Subcontractor): _____ Attn: _____ Date Rec'd by Contractor: _____
D From (Contractor): _____ By: _____ Date Trnsmt'd by Contractor: _____

Copies: ☐ Owner ☐ Consultants ☐ _____ ☐ _____ ☐ _____ ☐ One copy retained by sender

THIS PAGE LEFT INTENTIONALLY BLANK

SCHEDULE OF VALUES FORM – AIA DOCUMENT G703-1992

Schedules of Values Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK



AIA Document G703™ – 1992

Continuation Sheet

AIA Document, G702™-1992, Application and Certification for Payment, or G736™-2009, Project Application and Project Certificate for Payment, Construction Manager as Adviser Edition, containing Contractor's signed certification is attached.

In tabulations below, amounts are in US dollars.

Use Column I on Contracts where variable retainage for line items may apply.

APPLICATION NO:

APPLICATION DATE:

PERIOD TO:

ARCHITECT'S PROJECT NO.:

001

[illegible]

AIA Document G703™ – 1992. Copyright © 1963, 1965, 1966, 1967, 1970, 1978, 1983 and 1992 by The American Institute of Architects. All rights reserved. **WARNING:** This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 15:42:36 ET on 05/31/2019 under Order No. 1840604654 which expires on 01/31/2020, and is not for sale.

THIS PAGE LEFT INTENTIONALLY BLANK

APPLICATION AND CERTIFICATE FOR PAYMENT FORM – AIA DOCUMENT G702-1992

Application and Certificate for Payment Form attached herein shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

Application and Certificate for Payment

TO OWNER:		PROJECT:		APPLICATION NO: 001	Distribution to:
				PERIOD TO:	OWNER: ☐
				CONTRACT FOR: General Construction	ARCHITECT: ☐
				CONTRACT DATE:	CONTRACTOR: ☐
				PROJECT NOS: / /	FIELD: ☐
					OTHER: ☐

CONTRACTOR'S APPLICATION FOR PAYMENT

Application is made for payment, as shown below, in connection with the Contract. Continuation Sheet, AIA Document G703, is attached.

1. ORIGINAL CONTRACT SUM \$0.00
2. NET CHANGE BY CHANGE ORDERS \$0.00
3. CONTRACT SUM TO DATE (Line 1 + 2) \$0.00
4. TOTAL COMPLETED & STORED TO DATE (Column G on G703) \$0.00
5. RETAINAGE:
 - a. 0 % of Completed Work (Column D + E on G703) \$0.00
 - b. 0 % of Stored Material (Column F on G703) \$0.00

Total Retainage (Lines 5a + 5b or Total in Column I of G703) \$0.00

6. TOTAL EARNED LESS RETAINAGE \$0.00
(Line 4 Less Line 5 Total)

7. LESS PREVIOUS CERTIFICATES FOR PAYMENT \$0.00
(Line 6 from prior Certificate)

8. CURRENT PAYMENT DUE \$0.00

9. BALANCE TO FINISH, INCLUDING RETAINAGE \$0.00
(Line 3 less Line 6)

CHANGE ORDER SUMMARY	ADDITIONS	DEDUCTIONS
Total changes approved in previous months by Owner	\$0.00	\$0.00
Total approved this Month	\$0.00	\$0.00
TOTALS	\$0.00	\$0.00
NET CHANGES by Change Order		\$0.00

The undersigned Contractor certifies that to the best of the Contractor's knowledge, information and belief the Work covered by this Application for Payment has been completed in accordance with the Contract Documents, that all amounts have been paid by the Contractor for Work for which previous Certificates for Payment were issued and payments received from the Owner, and that current payment shown herein is now due.

CONTRACTOR: _____
By: _____ Date: _____
State of: _____

County of: _____
Subscribed and sworn to before me this _____ day of _____

Notary Public: _____
My Commission expires: _____

ARCHITECT'S CERTIFICATE FOR PAYMENT

In accordance with the Contract Documents, based on on-site observations and the data comprising this application, the Architect certifies to the Owner that to the best of the Architect's knowledge, information and belief the Work has progressed as indicated, the quality of the Work is in accordance with the Contract Documents, and the Contractor is entitled to payment of the AMOUNT CERTIFIED.

AMOUNT CERTIFIED \$0.00
(Attach explanation if amount certified differs from the amount applied. Initial all figures on this Application and on the Continuation Sheet that are changed to conform with the amount certified.)

ARCHITECT: _____
By: _____ Date: _____

This Certificate is not negotiable. The AMOUNT CERTIFIED is payable only to the Contractor named herein. Issuance, payment and acceptance of payment are without prejudice to any rights of the Owner or Contractor under this Contract.

THIS PAGE LEFT INTENTIONALLY BLANK

CAD FILE RELEASE FORM

CAD File Release Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK



Gipe Associates, Inc.
CONSULTING ENGINEERS

RELEASE OF ELECTRONIC MEDIA (DRAWINGS, SPECIFICATIONS, ETC.)

PROJECT: _____ DATE: _____

PROJECT NO: _____ RECORD DOCUMENT DATE _____

In accepting and utilizing any drawings or other data on any form of electronic media generated and provided by Gipe Associates, Inc., the Owner, its agents, other design professionals, or contractors covenants and agrees that all such drawings and data are instruments of service of Gipe Associates, Inc., and its Consultants (hereinafter referred to as the Engineer), who shall be deemed the author of the drawings and data, and shall retain all common law, statutory law and other rights, including copyrights.

For documentation purposes, the original electronic media (disks) will be retained by the Engineer, and both parties acknowledge that the referenced, dated Record Document is the actual contract deliverable. The Owner shall be permitted to retain copies of Drawings and Specifications prepared in electronic form for the Owner's convenience in connection with the specific project for which this information was prepared. Due to the potential that the information set forth on the electronic media can be modified, unintentionally or otherwise, the Engineer reserves the right to remove all indicia of its ownership and/or involvement from each document on the electronic media.

No warranty is made or implied as to the suitability of these files or the information they contain for such purpose. In all cases, the Contract Drawings and Specifications shall define all requirements. The Contractor is responsible for verification of Drawings and field conditions and/or recognizing the impermanence and changeability of electronic files, assumes all responsibility for their use and alteration.

The Owner, its Agents or other design professionals further agree not to use these drawings and data, in whole or in part, for any purpose or project other than the project which is the subject of this Agreement. The Owner, its Agents, other design professionals, or contractors agree to waive all claims against the Engineer, and to the fullest extent permitted by law, to indemnify and hold the Engineer harmless from any damage, liability or cost, including reasonable attorneys' fees and cost of defense, arising from any changes or use of the Drawings and data made by anyone other than the Engineer without the prior written consent of the Engineer. Any such unauthorized use or reuse will be at the Owner's sole risk and without liability or legal exposure to the Engineer.

Under no circumstances shall transfer of the Drawings and other instruments of service on electronic media for use by the Owner, its Agents or other design professionals be deemed a sale by the Engineer, and the Engineer makes no warranties, either express or implied, of merchantability and fitness for any particular purpose.

Accepted - Owner or Owner's Representative

Printed Name and Title

Date

THIS PAGE LEFT INTENTIONALLY BLANK

REQUEST FOR INTERPRETATION FORM – CSI FORM 13.2A

Request for Interpretation Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK



Advancement
of Construction
Technology

REQUEST FOR INTERPRETATION

Project: _____

R.F.I. Number: _____

From: _____

To: _____

Date: _____

A/E Project Number: _____

Re: _____

Contract For: _____

Specification Section: _____

Paragraph: _____

Drawing Reference: _____

Detail: _____

Request:

Signed by: _____

Date: _____

Response:

☐ Attachments

Response From: _____

To: _____

Date Rec'd: _____

Date Ret'd: _____

Signed by: _____

Date: _____

Copies: ☐ Owner ☐ Consultants ☐ _____ ☐ _____ ☐ _____ ☐ _____ ☐ File

THIS PAGE LEFT INTENTIONALLY BLANK

REQUEST FOR INTERPRETATION LOG – CSI LOG FORM 13.2B

Request for Interpretation Log attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK



Owner: _____ Contractor: _____

July 1994
CSI Log Form 13.2B

THIS PAGE LEFT INTENTIONALLY BLANK

SUBSTITUTION REQUEST FORM (DURING CONSTRUCTION) – CSI FORM 13.1A

Substitution Request Form CSI Form 13.1A attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK



SUBSTITUTION REQUEST (After the Bidding Phase)

Project: _____ Substitution Request Number: _____

From: _____
To: _____ Date: _____

A/E Project Number: _____
Re: _____ Contract For: _____

Specification Title: _____ Description: _____
Section: _____ Page: _____ Article/Paragraph: _____

Proposed Substitution: _____
Manufacturer: _____ Address: _____ Phone: _____
Trade Name: _____ Model No.: _____
Installer: _____ Address: _____ Phone: _____
History: ☐ New product ☐ 2-5 years old ☐ 5-10 yrs old ☐ More than 10 years old

Differences between proposed substitution and specified product: _____

☐ Point-by-point comparative data attached - REQUIRED BY A/E

Reason for not providing specified item: _____

Similar Installation:

Project: _____ Architect: _____
Address: _____ Owner: _____
_____ Date Installed: _____

Proposed substitution affects other parts of Work: ☐ No ☐ Yes; explain _____

Savings to Owner for accepting substitution: _____ (\$ _____).

Proposed substitution changes Contract Time: ☐ No ☐ Yes [Add] [Deduct] _____ days.

Supporting Data Attached: ☐ Drawings ☐ Product Data ☐ Samples ☐ Tests ☐ Reports ☐ _____

SUBSTITUTION REQUEST (Continued)

The Undersigned certifies:

- Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.
- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule.
- Cost data as stated above is complete. Claims for additional costs related to accepted substitution which may subsequently become apparent are to be waived.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.
- Coordination, installation, and changes in the Work as necessary for accepted substitution will be complete in all respects.

Submitted by: _____

Signed by: _____

Firm: _____

Address: _____

Telephone: _____

Attachments: _____

A/E's REVIEW AND ACTION

- ☐ Substitution approved - Make submittals in accordance with Specification Section 01330.
☐ Substitution approved as noted - Make submittals in accordance with Specification Section 01330.
☐ Substitution rejected - Use specified materials.
☐ Substitution Request received too late - Use specified materials.

Signed by: _____

Date: _____

Additional Comments: ☐ Contractor ☐ Subcontractor ☐ Supplier ☐ Manufacturer ☐ A/E ☐ _____

ARCHITECT'S SUPPLEMENTAL INSTRUCTIONS FORM – AIA DOCUMENT G710-2017

AIA Document G710-2017 Supplemental Instructions attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

AIA[®] Document G710[™] – 2017

Architect's Supplemental Instructions

PROJECT: *(name and address)*

CONTRACT INFORMATION:

Contract For: General Construction

Date:

ASI INFORMATION:

ASI Number: 001

Date:

OWNER: *(name and address)*

ARCHITECT: *(name and address)*

CONTRACTOR: *(name and address)*

The Contractor shall carry out the Work in accordance with the following supplemental instructions without change in Contract Sum or Contract Time. Proceeding with the Work in accordance with these instructions indicates your acknowledgment that there will be no change in the Contract Sum or Contract Time.

(Insert a detailed description of the Architect's supplemental instructions and, if applicable, attach or reference specific exhibits.)

ISSUED BY THE ARCHITECT:

ARCHITECT *(Firm name)*

SIGNATURE

PRINTED NAME AND TITLE

DATE

THIS PAGE LEFT INTENTIONALLY BLANK

CONSTRUCTION CHANGE DIRECTIVE FORM – AIA DOCUMENT G714-2017

AIA Document G714-2017 Construction Change Directive attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

AIA® Document G714™ – 2017

Construction Change Directive

PROJECT: (name and address)

CONTRACT INFORMATION:
Contract For: General Construction
Date:

CCD INFORMATION:
Directive Number: 001
Date:

OWNER: (name and address)

ARCHITECT: (name and address)

CONTRACTOR: (name and address)

The Contractor is hereby directed to make the following change(s) in this Contract:
(Insert a detailed description of the change and, if applicable, attach or reference specific exhibits.)

PROPOSED ADJUSTMENTS

1. The proposed basis of adjustment to the Contract Sum or Guaranteed Maximum Price is:

- ☒ Lump Sum decrease of \$0.00
- ☐ Unit Price of \$ per
- ☐ Cost, as defined below, plus the following fee:
(Insert a definition of, or method for determining, cost)

☐ As follows:

2. The Contract Time is proposed to remain unchanged. The proposed adjustment, if any, is (0 days).

NOTE: The Owner, Architect and Contractor should execute a Change Order to supersede this Construction Change Directive to the extent they agree upon adjustments to the Contract Sum, Contract Time, or Guaranteed Maximum price for the change(s) described herein.

When signed by the Owner and Architect and received by the Contractor, this document becomes effective IMMEDIATELY as a Construction Change Directive (CCD), and the Contractor shall proceed with the change(s) described above.

Contractor signature indicates agreement with the proposed adjustments in Contract Sum and Contract Time set forth in this CCD.

ARCHITECT (Firm name)

OWNER (Firm name)

CONTRACTOR (Firm name)

SIGNATURE

SIGNATURE

SIGNATURE

PRINTED NAME AND TITLE

PRINTED NAME AND TITLE

PRINTED NAME AND TITLE

DATE

DATE

DATE

THIS PAGE LEFT INTENTIONALLY BLANK

PROPOSAL REQUEST FORM – AIA DOCUMENT G709-2018

AIA Document G709 Proposal Request attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

AIA[®] Document G709[™] – 2018

Proposal Request

PROJECT: *(name and address)*
TEST

CONTRACT INFORMATION:
Contract For: General Construction
Date:

Architect's Project Number:
Proposal Request Number: 001
Proposal Request Date:

OWNER: *(name and address)*

ARCHITECT: *(name and address)*

CONTRACTOR: *(name and address)*

The Owner requests an itemized proposal for changes to the Contract Sum and Contract Time for proposed modifications to the Contract Documents described herein. The Contractor shall submit this proposal within Zero (0) days or notify the Architect in writing of the anticipated date of submission.

(Insert a detailed description of the proposed modifications to the Contract Documents and, if applicable, attach or reference specific exhibits.)

THIS IS NOT A CHANGE ORDER, A CONSTRUCTION CHANGE DIRECTIVE, OR A DIRECTION TO PROCEED WITH THE WORK DESCRIBED IN THE PROPOSED MODIFICATIONS.

REQUESTED BY THE ARCHITECT:

PRINTED NAME AND TITLE

THIS PAGE LEFT INTENTIONALLY BLANK

CHANGE ORDER FORM – AIA DOCUMENT G701-2017

AIA Document G701 - Change Order attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK



Document G701™ – 2017

Change Order

PROJECT: *(Name and address)*

CONTRACT INFORMATION:

Contract For: General Construction

Date:

CHANGE ORDER INFORMATION:

Change Order Number: 001

Date:

OWNER: *(Name and address)*

ARCHITECT: *(Name and address)*

CONTRACTOR: *(Name and address)*

THE CONTRACT IS CHANGED AS FOLLOWS:

(Insert a detailed description of the change and, if applicable, attach or reference specific exhibits. Also include agreed upon adjustments attributable to executed Construction Change Directives.)

The original Contract Sum was	\$	0.00
The net change by previously authorized Change Orders	\$	0.00
The Contract Sum prior to this Change Order was	\$	0.00
The Contract Sum will be increased by this Change Order in the amount of	\$	0.00
The new Contract Sum including this Change Order will be	\$	0.00
The Contract Time will be increased by Zero (0) days.		
The new date of Substantial Completion will be		

NOTE: This Change Order does not include adjustments to the Contract Sum or Guaranteed Maximum Price, or the Contract Time, that have been authorized by Construction Change Directive until the cost and time have been agreed upon by both the Owner and Contractor, in which case a Change Order is executed to supersede the Construction Change Directive.

NOT VALID UNTIL SIGNED BY THE ARCHITECT, CONTRACTOR AND OWNER.

ARCHITECT *(Firm name)*

CONTRACTOR *(Firm name)*

OWNER *(Firm name)*

SIGNATURE

SIGNATURE

SIGNATURE

PRINTED NAME AND TITLE

PRINTED NAME AND TITLE

PRINTED NAME AND TITLE

DATE

DATE

DATE

THIS PAGE LEFT INTENTIONALLY BLANK

ALLOWANCE AUTHORIZATION FORM

Allowance Authorization Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

ALLOWANCE AUTHORIZATION

Project:

Engineer:

Project No.:

Contractor:

AAA No.:

Initiation Date:

The Allowance is allocated as follows:

Total original Contract Allowance was:	\$
Amount of Contract Allowance Access previously authorized:	\$
Adjusted Contract Allowance prior to this authorization is:	\$
The amount of available allowance will decrease by this Access Authorization:	\$
The remaining Contract Allowance, after this Access Authorization will be:	\$

Recommended by:
Engineer

By (Signature): _____

Date: _____

Accepted by:
Contractor

Approved by:
Owner

By (Signature): _____ By (Signature): _____

Date: _____ Date: _____

THIS PAGE LEFT INTENTIONALLY BLANK

CERTIFICATE OF SUBSTANTIAL COMPLETION FORM – AIA DOCUMENT G704-2017

AIA Document G704-2017 Certificate of Substantial Completion Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

AIA[®] Document G704[™] – 2017

Certificate of Substantial Completion

PROJECT: *(name and address)*

CONTRACT INFORMATION:

Contract For: General Construction

Date:

CERTIFICATE INFORMATION:

Certificate Number: 001

Date:

OWNER: *(name and address)*

ARCHITECT: *(name and address)*

CONTRACTOR: *(name and address)*

The Work identified below has been reviewed and found, to the Architect's best knowledge, information, and belief, to be substantially complete. Substantial Completion is the stage in the progress of the Work when the Work or designated portion is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use. The date of Substantial Completion of the Project or portion designated below is the date established by this Certificate.
(Identify the Work, or portion thereof, that is substantially complete.)

ARCHITECT *(Firm Name)*

SIGNATURE

PRINTED NAME AND TITLE

DATE OF SUBSTANTIAL COMPLETION

WARRANTIES

The date of Substantial Completion of the Project or portion designated above is also the date of commencement of applicable warranties required by the Contract Documents, except as stated below:

(Identify warranties that do not commence on the date of Substantial Completion, if any, and indicate their date of commencement.)

WORK TO BE COMPLETED OR CORRECTED

A list of items to be completed or corrected is attached hereto, or transmitted as agreed upon by the parties, and identified as follows:

(Identify the list of Work to be completed or corrected.)

The failure to include any items on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents. Unless otherwise agreed to in writing, the date of commencement of warranties for items on the attached list will be the date of issuance of the final Certificate of Payment or the date of final payment, whichever occurs first. The Contractor will complete or correct the Work on the list of items attached hereto within () days from the above date of Substantial Completion.

Cost estimate of Work to be completed or corrected: \$

The responsibilities of the Owner and Contractor for security, maintenance, heat, utilities, damage to the Work, insurance, and other items identified below shall be as follows:

(Note: Owner's and Contractor's legal and insurance counsel should review insurance requirements and coverage.)

The Owner and Contractor hereby accept the responsibilities assigned to them in this Certificate of Substantial Completion:

CONTRACTOR *(Firm Name)*

SIGNATURE

PRINTED NAME AND TITLE

DATE

OWNER *(Firm Name)*

SIGNATURE

PRINTED NAME AND TITLE

DATE

THIS PAGE LEFT INTENTIONALLY BLANK

AFFIDAVIT OF PAYMENT OF DEBTS AND CLAIMS FORM – AIA DOCUMENT G706-1994

AIA Document G706 Affidavit of Payment of Debts and Claims Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

AIA[®] Document G706[™] – 1994

Contractor's Affidavit of Payment of Debts and Claims

PROJECT: <i>(Name and address)</i>	ARCHITECT'S PROJECT NUMBER:	OWNER: ☐
		ARCHITECT: ☐
TO OWNER: <i>(Name and address)</i>	CONTRACT FOR: General Construction	CONTRACTOR: ☐
	CONTRACT DATED:	SURETY: ☐
		OTHER: ☐

STATE OF:
COUNTY OF:

The undersigned hereby certifies that, except as listed below, payment has been made in full and all obligations have otherwise been satisfied for all materials and equipment furnished, for all work, labor, and services performed, and for all known indebtedness and claims against the Contractor for damages arising in any manner in connection with the performance of the Contract referenced above for which the Owner or Owner's property might in any way be held responsible or encumbered.

EXCEPTIONS:

SUPPORTING DOCUMENTS ATTACHED HERETO:

1. Consent of Surety to Final Payment. Whenever Surety is involved, Consent of Surety is required. AIA Document G707, Consent of Surety, may be used for this purpose

Indicate Attachment ☐ Yes ☒ No

CONTRACTOR: *(Name and address)*

BY:

(Signature of authorized representative)

(Printed name and title)

The following supporting documents should be attached hereto if required by the Owner:

1. Contractor's Release or Waiver of Liens, conditional upon receipt of final payment.
2. Separate Releases or Waivers of Liens from Subcontractors and material and equipment suppliers, to the extent required by the Owner, accompanied by a list thereof.
3. Contractor's Affidavit of Release of Liens (AIA Document G706A).

Subscribed and sworn to before me on this date:

Notary Public:
My Commission Expires:

THIS PAGE LEFT INTENTIONALLY BLANK

AFFIDAVIT OF RELEASE OF LIENS FORM – AIA DOCUMENT G706A-1994

AIA Document G706A-1994 - Affidavit of Release of Liens Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK

AIA[®] Document G706A[™] – 1994

Contractor's Affidavit of Release of Liens

PROJECT: <i>(Name and address)</i> TEST	ARCHITECT'S PROJECT NUMBER:	OWNER: ☐
	CONTRACT FOR: General Construction	ARCHITECT: ☐
TO OWNER: <i>(Name and address)</i>	CONTRACT DATED:	CONTRACTOR: ☐
		SURETY: ☐
		OTHER: ☐

STATE OF:
COUNTY OF:

The undersigned hereby certifies that to the best of the undersigned's knowledge, information and belief, except as listed below, the Releases or Waivers of Lien attached hereto include the Contractor, all Subcontractors, all suppliers of materials and equipment, and all performers of Work, labor or services who have or may have liens or encumbrances or the right to assert liens or encumbrances against any property of the Owner arising in any manner out of the performance of the Contract referenced above.

EXCEPTIONS:

SUPPORTING DOCUMENTS ATTACHED HERETO:

1. Contractor's Release or Waiver of Liens, conditional upon receipt of final payment.
2. Separate Releases or Waivers of Liens from Subcontractors and material and equipment suppliers, to the extent required by the Owner, accompanied by a list thereof.

CONTRACTOR: *(Name and address)*

BY:

*(Signature of authorized
representative)*

(Printed name and title)

Subscribed and sworn to before me on this date:

Notary Public:

My Commission Expires:

THIS PAGE LEFT INTENTIONALLY BLANK

CONSENT OF SURETY TO FINAL PAYMENT FORM – AIA DOCUMENT G707-1994

AIA Document G707-1994 - Consent of Surety to Final Payment Form attached shall be utilized on this project.

THIS PAGE LEFT INTENTIONALLY BLANK



AIA[®] Document G707[™] – 1994

Consent Of Surety to Final Payment

PROJECT: <i>(Name and address)</i> TEST	ARCHITECT'S PROJECT NUMBER:	OWNER: ☐
	CONTRACT FOR: General Construction	ARCHITECT: ☐
TO OWNER: <i>(Name and address)</i>	CONTRACT DATED:	CONTRACTOR: ☐
		SURETY: ☐
		OTHER: ☐

In accordance with the provisions of the Contract between the Owner and the Contractor as indicated above, the
(Insert name and address of Surety)

on bond of
(Insert name and address of Contractor)

, SURETY,

hereby approves of the final payment to the Contractor, and agrees that final payment to the Contractor shall
not relieve the Surety of any of its obligations to
(Insert name and address of Owner)

, CONTRACTOR,

as set forth in said Surety's bond.

, OWNER,

IN WITNESS WHEREOF, the Surety has hereunto set its hand on this date:
(Insert in writing the month followed by the numeric date and year.)

(Surety)

(Signature of authorized representative)

(Printed name and title)

Attest:
(Seal):

THIS PAGE LEFT INTENTIONALLY BLANK

**GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION – AIA DOCUMENT
A201-2017**

The General Conditions of this Contract are as stated in the American Institute of Architects Document AIA A201 (2017 Edition) entitled General Conditions of the Contract for Construction and is part of this project manual as if herein written in full.

THIS PAGE LEFT INTENTIONALLY BLANK

AIA® Document A201™ – 2017

General Conditions of the Contract for Construction

for the following PROJECT:
(Name and location or address)

THE OWNER:
(Name, legal status and address)

THE ARCHITECT:
(Name, legal status and address)

TABLE OF ARTICLES

- 1 GENERAL PROVISIONS**
- 2 OWNER**
- 3 CONTRACTOR**
- 4 ARCHITECT**
- 5 SUBCONTRACTORS**
- 6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS**
- 7 CHANGES IN THE WORK**
- 8 TIME**
- 9 PAYMENTS AND COMPLETION**
- 10 PROTECTION OF PERSONS AND PROPERTY**
- 11 INSURANCE AND BONDS**
- 12 UNCOVERING AND CORRECTION OF WORK**
- 13 MISCELLANEOUS PROVISIONS**
- 14 TERMINATION OR SUSPENSION OF THE CONTRACT**
- 15 CLAIMS AND DISPUTES**

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

For guidance in modifying this document to include supplementary conditions, see AIA Document A503™, Guide for Supplementary Conditions.

INDEX

(Topics and numbers in bold are Section headings.)

Acceptance of Nonconforming Work

9.6.6, 9.9.3, 12.3

Acceptance of Work

9.6.6, 9.8.2, 9.9.3, 9.10.1, 9.10.3, 12.3

Access to Work

3.16, 6.2.1, 12.1

Accident Prevention

10

Acts and Omissions

3.2, 3.3.2, 3.12.8, 3.18, 4.2.3, 8.3.1, 9.5.1, 10.2.5,
10.2.8, 13.3.2, 14.1, 15.1.2, 15.2

Addenda

1.1.1

Additional Costs, Claims for

3.7.4, 3.7.5, 10.3.2, 15.1.5

Additional Inspections and Testing

9.4.2, 9.8.3, 12.2.1, 13.4

Additional Time, Claims for

3.2.4, 3.7.4, 3.7.5, 3.10.2, 8.3.2, 15.1.6

Administration of the Contract

3.1.3, 4.2, 9.4, 9.5

Advertisement or Invitation to Bid

1.1.1

Aesthetic Effect

4.2.13

Allowances

3.8

Applications for Payment

4.2.5, 7.3.9, 9.2, 9.3, 9.4, 9.5.1, 9.5.4, 9.6.3, 9.7, 9.10

Approvals

2.1.1, 2.3.1, 2.5, 3.1.3, 3.10.2, 3.12.8, 3.12.9,
3.12.10.1, 4.2.7, 9.3.2, 13.4.1

Arbitration

8.3.1, 15.3.2, 15.4

ARCHITECT

4

Architect, Definition of

4.1.1

Architect, Extent of Authority

2.5, 3.12.7, 4.1.2, 4.2, 5.2, 6.3, 7.1.2, 7.3.4, 7.4, 9.2,
9.3.1, 9.4, 9.5, 9.6.3, 9.8, 9.10.1, 9.10.3, 12.1, 12.2.1,
13.4.1, 13.4.2, 14.2.2, 14.2.4, 15.1.4, 15.2.1

Architect, Limitations of Authority and Responsibility

2.1.1, 3.12.4, 3.12.8, 3.12.10, 4.1.2, 4.2.1, 4.2.2,
4.2.3, 4.2.6, 4.2.7, 4.2.10, 4.2.12, 4.2.13, 5.2.1, 7.4,
9.4.2, 9.5.4, 9.6.4, 15.1.4, 15.2

Architect's Additional Services and Expenses

2.5, 12.2.1, 13.4.2, 13.4.3, 14.2.4

Architect's Administration of the Contract

3.1.3, 3.7.4, 15.2, 9.4.1, 9.5

Architect's Approvals

2.5, 3.1.3, 3.5, 3.10.2, 4.2.7

Architect's Authority to Reject Work

3.5, 4.2.6, 12.1.2, 12.2.1

Architect's Copyright

1.1.7, 1.5

Architect's Decisions

3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 4.2.14, 6.3,
7.3.4, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4.1, 9.5, 9.8.4, 9.9.1,
13.4.2, 15.2

Architect's Inspections

3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 13.4

Architect's Instructions

3.2.4, 3.3.1, 4.2.6, 4.2.7, 13.4.2

Architect's Interpretations

4.2.11, 4.2.12

Architect's Project Representative

4.2.10

Architect's Relationship with Contractor

1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2,
3.5, 3.7.4, 3.7.5, 3.9.2, 3.9.3, 3.10, 3.11, 3.12, 3.16,
3.18, 4.1.2, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5,
9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3, 12, 13.3.2, 13.4, 15.2

Architect's Relationship with Subcontractors

1.1.2, 4.2.3, 4.2.4, 4.2.6, 9.6.3, 9.6.4, 11.3

Architect's Representations

9.4.2, 9.5.1, 9.10.1

Architect's Site Visits

3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4

Asbestos

10.3.1

Attorneys' Fees

3.18.1, 9.6.8, 9.10.2, 10.3.3

Award of Separate Contracts

6.1.1, 6.1.2

Award of Subcontracts and Other Contracts for Portions of the Work

5.2

Basic Definitions

1.1

Bidding Requirements

1.1.1

Binding Dispute Resolution

8.3.1, 9.7, 11.5, 13.1, 15.1.2, 15.1.3, 15.2.1, 15.2.5,
15.2.6.1, 15.3.1, 15.3.2, 15.3.3, 15.4.1

Bonds, Lien

7.3.4.4, 9.6.8, 9.10.2, 9.10.3

Bonds, Performance, and Payment

7.3.4.4, 9.6.7, 9.10.3, 11.1.2, 11.1.3, 11.5

Building Information Models Use and Reliance

1.8

Building Permit

3.7.1

Capitalization

1.3

Certificate of Substantial Completion

9.8.3, 9.8.4, 9.8.5

Init.

Certificates for Payment
4.2.1, 4.2.5, 4.2.9, 9.3.3, 9.4, 9.5, 9.6.1, 9.6.6, 9.7,
9.10.1, 9.10.3, 14.1.1.3, 14.2.4, 15.1.4
Certificates of Inspection, Testing or Approval
13.4.4
Certificates of Insurance
9.10.2
Change Orders
1.1.1, 3.4.2, 3.7.4, 3.8.2.3, 3.11, 3.12.8, 4.2.8, 5.2.3,
7.1.2, 7.1.3, 7.2, 7.3.2, 7.3.7, 7.3.9, 7.3.10, 8.3.1,
9.3.1.1, 9.10.3, 10.3.2, 11.2, 11.5, 12.1.2
Change Orders, Definition of
7.2.1
CHANGES IN THE WORK
2.2.2, 3.11, 4.2.8, 7, 7.2.1, 7.3.1, 7.4, 8.3.1, 9.3.1.1,
11.5
Claims, Definition of
15.1.1
Claims, Notice of
1.6.2, 15.1.3
CLAIMS AND DISPUTES
3.2.4, 6.1.1, 6.3, 7.3.9, 9.3.3, 9.10.4, 10.3.3, 15, 15.4
Claims and Timely Assertion of Claims
15.4.1
Claims for Additional Cost
3.2.4, 3.3.1, 3.7.4, 7.3.9, 9.5.2, 10.2.5, 10.3.2, 15.1.5
Claims for Additional Time
3.2.4, 3.3.1, 3.7.4, 6.1.1, 8.3.2, 9.5.2, 10.3.2, 15.1.6
Concealed or Unknown Conditions, Claims for
3.7.4
Claims for Damages
3.2.4, 3.18, 8.3.3, 9.5.1, 9.6.7, 10.2.5, 10.3.3, 11.3,
11.3.2, 14.2.4, 15.1.7
Claims Subject to Arbitration
15.4.1
Cleaning Up
3.15, 6.3
Commencement of the Work, Conditions Relating to
2.2.1, 3.2.2, 3.4.1, 3.7.1, 3.10.1, 3.12.6, 5.2.1, 5.2.3,
6.2.2, 8.1.2, 8.2.2, 8.3.1, 11.1, 11.2, 15.1.5
Commencement of the Work, Definition of
8.1.2
Communications
3.9.1, 4.2.4
Completion, Conditions Relating to
3.4.1, 3.11, 3.15, 4.2.2, 4.2.9, 8.2, 9.4.2, 9.8, 9.9.1,
9.10, 12.2, 14.1.2, 15.1.2
COMPLETION, PAYMENTS AND
9
Completion, Substantial
3.10.1, 4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, 9.8, 9.9.1,
9.10.3, 12.2, 15.1.2
Compliance with Laws
2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 10.2.2,
13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14.1.1, 14.2.1.3,
15.2.8, 15.4.2, 15.4.3
Concealed or Unknown Conditions

3.7.4, 4.2.8, 8.3.1, 10.3
Conditions of the Contract
1.1.1, 6.1.1, 6.1.4
Consent, Written
3.4.2, 3.14.2, 4.1.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3, 13.2,
15.4.4.2
Consolidation or Joinder
15.4.4
CONSTRUCTION BY OWNER OR BY
SEPARATE CONTRACTORS
1.1.4, 6
Construction Change Directive, Definition of
7.3.1
Construction Change Directives
1.1.1, 3.4.2, 3.11, 3.12.8, 4.2.8, 7.1.1, 7.1.2, 7.1.3,
7.3, 9.3.1.1
Construction Schedules, Contractor's
3.10, 3.11, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2
Contingent Assignment of Subcontracts
5.4, 14.2.2.2
Continuing Contract Performance
15.1.4
Contract, Definition of
1.1.2
CONTRACT, TERMINATION OR SUSPENSION
OF THE
5.4.1.1, 5.4.2, 11.5, 14
Contract Administration
3.1.3, 4, 9.4, 9.5
Contract Award and Execution, Conditions Relating
to
3.7.1, 3.10, 5.2, 6.1
Contract Documents, Copies Furnished and Use of
1.5.2, 2.3.6, 5.3
Contract Documents, Definition of
1.1.1
Contract Sum
2.2.2, 2.2.4, 3.7.4, 3.7.5, 3.8, 3.10.2, 5.2.3, 7.3, 7.4,
9.1, 9.2, 9.4.2, 9.5.1.4, 9.6.7, 9.7, 10.3.2, 11.5, 12.1.2,
12.3, 14.2.4, 14.3.2, 15.1.4.2, 15.1.5, 15.2.5
Contract Sum, Definition of
9.1
Contract Time
1.1.4, 2.2.1, 2.2.2, 3.7.4, 3.7.5, 3.10.2, 5.2.3, 6.1.5,
7.2.1.3, 7.3.1, 7.3.5, 7.3.6, 7, 7, 7.3.10, 7.4, 8.1.1,
8.2.1, 8.2.3, 8.3.1, 9.5.1, 9.7, 10.3.2, 12.1.1, 12.1.2,
14.3.2, 15.1.4.2, 15.1.6.1, 15.2.5
Contract Time, Definition of
8.1.1
CONTRACTOR
3
Contractor, Definition of
3.1, 6.1.2
Contractor's Construction and Submittal Schedules
3.10, 3.12.1, 3.12.2, 4.2.3, 6.1.3, 15.1.6.2
Contractor's Employees

2.2.4, 3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6,
10.2, 10.3, 11.3, 14.1, 14.2.1.1
Contractor's Liability Insurance
11.1
Contractor's Relationship with Separate Contractors
and Owner's Forces
3.12.5, 3.14.2, 4.2.4, 6, 11.3, 12.2.4
Contractor's Relationship with Subcontractors
1.2.2, 2.2.4, 3.3.2, 3.18.1, 3.18.2, 4.2.4, 5, 9.6.2,
9.6.7, 9.10.2, 11.2, 11.3, 11.4
Contractor's Relationship with the Architect
1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2,
3.5.1, 3.7.4, 3.10, 3.11, 3.12, 3.16, 3.18, 4.2, 5.2,
6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6,
10.3, 11.3, 12, 13.4, 15.1.3, 15.2.1
Contractor's Representations
3.2.1, 3.2.2, 3.5, 3.12.6, 6.2.2, 8.2.1, 9.3.3, 9.8.2
Contractor's Responsibility for Those Performing the
Work
3.3.2, 3.18, 5.3, 6.1.3, 6.2, 9.5.1, 10.2.8
Contractor's Review of Contract Documents
3.2
Contractor's Right to Stop the Work
2.2.2, 9.7
Contractor's Right to Terminate the Contract
14.1
Contractor's Submittals
3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 9.2, 9.3, 9.8.2,
9.8.3, 9.9.1, 9.10.2, 9.10.3
Contractor's Superintendent
3.9, 10.2.6
Contractor's Supervision and Construction
Procedures
1.2.2, 3.3, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4,
7.1.3, 7.3.4, 7.3.6, 8.2, 10, 12, 14, 15.1.4
Coordination and Correlation
1.2, 3.2.1, 3.3.1, 3.10, 3.12.6, 6.1.3, 6.2.1
Copies Furnished of Drawings and Specifications
1.5, 2.3.6, 3.11
Copyrights
1.5, 3.17
Correction of Work
2.5, 3.7.3, 9.4.2, 9.8.2, 9.8.3, 9.9.1, 12.1.2, 12.2, 12.3,
15.1.3.1, 15.1.3.2, 15.2.1
Correlation and Intent of the Contract Documents
1.2
Cost, Definition of
7.3.4
Costs
2.5, 3.2.4, 3.7.3, 3.8.2, 3.15.2, 5.4.2, 6.1.1, 6.2.3,
7.3.3.3, 7.3.4, 7.3.8, 7.3.9, 9.10.2, 10.3.2, 10.3.6,
11.2, 12.1.2, 12.2.1, 12.2.4, 13.4, 14
Cutting and Patching
3.14, 6.2.5
Damage to Construction of Owner or Separate
Contractors
3.14.2, 6.2.4, 10.2.1.2, 10.2.5, 10.4, 12.2.4

Damage to the Work
3.14.2, 9.9.1, 10.2.1.2, 10.2.5, 10.4, 12.2.4
Damages, Claims for
3.2.4, 3.18, 6.1.1, 8.3.3, 9.5.1, 9.6.7, 10.3.3, 11.3.2,
11.3, 14.2.4, 15.1.7
Damages for Delay
6.2.3, 8.3.3, 9.5.1.6, 9.7, 10.3.2, 14.3.2
Date of Commencement of the Work, Definition of
8.1.2
Date of Substantial Completion, Definition of
8.1.3
Day, Definition of
8.1.4
Decisions of the Architect
3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 6.3, 7.3.4,
7.3.9, 8.1.3, 8.3.1, 9.2, 9.4, 9.5.1, 9.8.4, 9.9.1, 13.4.2,
14.2.2, 14.2.4, 15.1, 15.2
Decisions to Withhold Certification
9.4.1, 9.5, 9.7, 14.1.1.3
Defective or Nonconforming Work, Acceptance,
Rejection and Correction of
2.5, 3.5, 4.2.6, 6.2.3, 9.5.1, 9.5.3, 9.6.6, 9.8.2, 9.9.3,
9.10.4, 12.2.1
Definitions
1.1, 2.1.1, 3.1.1, 3.5, 3.12.1, 3.12.2, 3.12.3, 4.1.1, 5.1,
6.1.2, 7.2.1, 7.3.1, 8.1, 9.1, 9.8.1, 15.1.1
Delays and Extensions of Time
3.2, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, 8.3, 9.5.1, 9.7,
10.3.2, 10.4, 14.3.2, 15.1.6, 15.2.5
Digital Data Use and Transmission
1.7
Disputes
6.3, 7.3.9, 15.1, 15.2
Documents and Samples at the Site
3.11
Drawings, Definition of
1.1.5
Drawings and Specifications, Use and Ownership of
3.11
Effective Date of Insurance
8.2.2
Emergencies
10.4, 14.1.1.2, 15.1.5
Employees, Contractor's
3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2,
10.3.3, 11.3, 14.1, 14.2.1.1
Equipment, Labor, or Materials
1.1.3, 1.1.6, 3.4, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1,
4.2.6, 4.2.7, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3,
9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2
Execution and Progress of the Work
1.1.3, 1.2.1, 1.2.2, 2.3.4, 2.3.6, 3.1, 3.3.1, 3.4.1, 3.7.1,
3.10.1, 3.12, 3.14, 4.2, 6.2.2, 7.1.3, 7.3.6, 8.2, 9.5.1,
9.9.1, 10.2, 10.3, 12.1, 12.2, 14.2, 14.3.1, 15.1.4
Extensions of Time
3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3, 7.4, 9.5.1, 9.7, 10.3.2,
10.4, 14.3, 15.1.6, 15.2.5

Failure of Payment
 9.5.1.3, 9.7, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2
 Faulty Work
 (See Defective or Nonconforming Work)
 Final Completion and Final Payment
 4.2.1, 4.2.9, 9.8.2, 9.10, 12.3, 14.2.4, 14.4.3
 Financial Arrangements, Owner's
 2.2.1, 13.2.2, 14.1.1.4
GENERAL PROVISIONS
1
 Governing Law
 13.1
 Guarantees (See Warranty)
 Hazardous Materials and Substances
 10.2.4, 10.3
 Identification of Subcontractors and Suppliers
 5.2.1
 Indemnification
 3.17, 3.18, 9.6.8, 9.10.2, 10.3.3, 11.3
 Information and Services Required of the Owner
 2.1.2, 2.2, 2.3, 3.2.2, 3.12.10.1, 6.1.3, 6.1.4, 6.2.5,
 9.6.1, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2,
 14.1.1.4, 14.1.4, 15.1.4
 Initial Decision
 15.2
 Initial Decision Maker, Definition of
 1.1.8
 Initial Decision Maker, Decisions
 14.2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5
 Initial Decision Maker, Extent of Authority
 14.2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5
 Injury or Damage to Person or Property
 10.2.8, 10.4
 Inspections
 3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3,
 9.9.2, 9.10.1, 12.2.1, 13.4
 Instructions to Bidders
 1.1.1
 Instructions to the Contractor
 3.2.4, 3.3.1, 3.8.1, 5.2.1, 7, 8.2.2, 12, 13.4.2
 Instruments of Service, Definition of
 1.1.7
 Insurance
 6.1.1, 7.3.4, 8.2.2, 9.3.2, 9.8.4, 9.9.1, 9.10.2, 10.2.5,
 11
Insurance, Notice of Cancellation or Expiration
11.1.4, 11.2.3
 Insurance, Contractor's Liability
 11.1
 Insurance, Effective Date of
 8.2.2, 14.4.2
 Insurance, Owner's Liability
 11.2
 Insurance, Property
 10.2.5, 11.2, 11.4, 11.5
 Insurance, Stored Materials
 9.3.2

INSURANCE AND BONDS
11
 Insurance Companies, Consent to Partial Occupancy
 9.9.1
 Insured loss, Adjustment and Settlement of
 11.5
 Intent of the Contract Documents
 1.2.1, 4.2.7, 4.2.12, 4.2.13
 Interest
 13.5
 Interpretation
 1.1.8, 1.2.3, 1.4, 4.1.1, 5.1, 6.1.2, 15.1.1
 Interpretations, Written
 4.2.11, 4.2.12
 Judgment on Final Award
 15.4.2
 Labor and Materials, Equipment
 1.1.3, 1.1.6, 3.4, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1,
 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1,
 10.2.4, 14.2.1.1, 14.2.1.2
 Labor Disputes
 8.3.1
 Laws and Regulations
 1.5, 2.3.2, 3.2.3, 3.2.4, 3.6, 3.7, 3.12.10, 3.13, 9.6.4,
 9.9.1, 10.2.2, 13.1, 13.3.1, 13.4.2, 13.5, 14, 15.2.8,
 15.4
 Liens
 2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8
 Limitations, Statutes of
 12.2.5, 15.1.2, 15.4.1.1
 Limitations of Liability
 3.2.2, 3.5, 3.12.10, 3.12.10.1, 3.17, 3.18.1, 4.2.6,
 4.2.7, 6.2.2, 9.4.2, 9.6.4, 9.6.7, 9.6.8, 10.2.5, 10.3.3,
 11.3, 12.2.5, 13.3.1
 Limitations of Time
 2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2.7,
 5.2, 5.3, 5.4.1, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3,
 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, 15,
 15.1.2, 15.1.3, 15.1.5
 Materials, Hazardous
 10.2.4, 10.3
 Materials, Labor, Equipment and
 1.1.3, 1.1.6, 3.4.1, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1,
 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2,
 10.2.1.2, 10.2.4, 14.2.1.1, 14.2.1.2
 Means, Methods, Techniques, Sequences and
 Procedures of Construction
 3.3.1, 3.12.10, 4.2.2, 4.2.7, 9.4.2
 Mechanic's Lien
 2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8
 Mediation
 8.3.1, 15.1.3.2, 15.2.1, 15.2.5, 15.2.6, 15.3, 15.4.1,
 15.4.1.1
 Minor Changes in the Work
 1.1.1, 3.4.2, 3.12.8, 4.2.8, 7.1, 7.4
MISCELLANEOUS PROVISIONS
13

Modifications, Definition of
1.1.1
Modifications to the Contract
1.1.1, 1.1.2, 2.5, 3.11, 4.1.2, 4.2.1, 5.2.3, 7, 8.3.1, 9.7,
10.3.2
Mutual Responsibility
6.2
Nonconforming Work, Acceptance of
9.6.6, 9.9.3, 12.3
Nonconforming Work, Rejection and Correction of
2.4, 2.5, 3.5, 4.2.6, 6.2.4, 9.5.1, 9.8.2, 9.9.3, 9.10.4,
12.2
Notice
1.6, 1.6.1, 1.6.2, 2.1.2, 2.2.2., 2.2.3, 2.2.4, 2.5, 3.2.4,
3.3.1, 3.7.4, 3.7.5, 3.9.2, 3.12.9, 3.12.10, 5.2.1, 7.4,
8.2.2, 9.6.8, 9.7, 9.10.1, 10.2.8, 10.3.2, 11.5, 12.2.2.1,
13.4.1, 13.4.2, 14.1, 14.2.2, 14.4.2, 15.1.3, 15.1.5,
15.1.6, 15.4.1
Notice of Cancellation or Expiration of Insurance
11.1.4, 11.2.3
Notice of Claims
1.6.2, 2.1.2, 3.7.4, 9.6.8, 10.2.8, 15.1.3, 15.1.5,
15.1.6, 15.2.8, 15.3.2, 15.4.1
Notice of Testing and Inspections
13.4.1, 13.4.2
Observations, Contractor's
3.2, 3.7.4
Occupancy
2.3.1, 9.6.6, 9.8
Orders, Written
1.1.1, 2.4, 3.9.2, 7, 8.2.2, 11.5, 12.1, 12.2.2.1, 13.4.2,
14.3.1
OWNER
2
Owner, Definition of
2.1.1
Owner, Evidence of Financial Arrangements
2.2, 13.2.2, 14.1.1.4
Owner, Information and Services Required of the
2.1.2, 2.2, 2.3, 3.2.2, 3.12.10, 6.1.3, 6.1.4, 6.2.5,
9.3.2, 9.6.1, 9.6.4, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1,
13.4.2, 14.1.1.4, 14.1.4, 15.1.4
Owner's Authority
1.5, 2.1.1, 2.3.32.4, 2.5, 3.4.2, 3.8.1, 3.12.10, 3.14.2,
4.1.2, 4.2.4, 4.2.9, 5.2.1, 5.2.4, 5.4.1, 6.1, 6.3, 7.2.1,
7.3.1, 8.2.2, 8.3.1, 9.3.2, 9.5.1, 9.6.4, 9.9.1, 9.10.2,
10.3.2, 11.4, 11.5, 12.2.2, 12.3, 13.2.2, 14.3, 14.4,
15.2.7
Owner's Insurance
11.2
Owner's Relationship with Subcontractors
1.1.2, 5.2, 5.3, 5.4, 9.6.4, 9.10.2, 14.2.2
Owner's Right to Carry Out the Work
2.5, 14.2.2
Owner's Right to Clean Up
6.3
Owner's Right to Perform Construction and to Award

Separate Contracts
6.1
Owner's Right to Stop the Work
2.4
Owner's Right to Suspend the Work
14.3
Owner's Right to Terminate the Contract
14.2, 14.4
Ownership and Use of Drawings, Specifications and
Other Instruments of Service
1.1.1, 1.1.6, 1.1.7, 1.5, 2.3.6, 3.2.2, 3.11, 3.17, 4.2.12,
5.3
Partial Occupancy or Use
9.6.6, 9.9
Patching, Cutting and
3.14, 6.2.5
Patents
3.17
Payment, Applications for
4.2.5, 7.3.9, 9.2, 9.3, 9.4, 9.5, 9.6.3, 9.7, 9.8.5, 9.10.1,
14.2.3, 14.2.4, 14.4.3
Payment, Certificates for
4.2.5, 4.2.9, 9.3.3, 9.4, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1,
9.10.3, 14.1.1.3, 14.2.4
Payment, Failure of
9.5.1.3, 9.7, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2
Payment, Final
4.2.1, 4.2.9, 9.10, 12.3, 14.2.4, 14.4.3
Payment Bond, Performance Bond and
7.3.4.4, 9.6.7, 9.10.3, 11.1.2
Payments, Progress
9.3, 9.6, 9.8.5, 9.10.3, 14.2.3, 15.1.4
PAYMENTS AND COMPLETION
9
Payments to Subcontractors
5.4.2, 9.5.1.3, 9.6.2, 9.6.3, 9.6.4, 9.6.7, 14.2.1.2
PCB
10.3.1
Performance Bond and Payment Bond
7.3.4.4, 9.6.7, 9.10.3, 11.1.2
Permits, Fees, Notices and Compliance with Laws
2.3.1, 3.7, 3.13, 7.3.4.4, 10.2.2
PERSONS AND PROPERTY, PROTECTION OF
10
Polychlorinated Biphenyl
10.3.1
Product Data, Definition of
3.12.2
Product Data and Samples, Shop Drawings
3.11, 3.12, 4.2.7
Progress and Completion
4.2.2, 8.2, 9.8, 9.9.1, 14.1.4, 15.1.4
Progress Payments
9.3, 9.6, 9.8.5, 9.10.3, 14.2.3, 15.1.4
Project, Definition of
1.1.4
Project Representatives

4.2.10
 Property Insurance
 10.2.5, 11.2
 Proposal Requirements
 1.1.1
 PROTECTION OF PERSONS AND PROPERTY
 10
 Regulations and Laws
 1.5, 2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 9.9.1,
 10.2.2, 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14, 15.2.8,
 15.4
 Rejection of Work
 4.2.6, 12.2.1
 Releases and Waivers of Liens
 9.3.1, 9.10.2
 Representations
 3.2.1, 3.5, 3.12.6, 8.2.1, 9.3.3, 9.4.2, 9.5.1, 9.10.1
 Representatives
 2.1.1, 3.1.1, 3.9, 4.1.1, 4.2.10, 13.2.1
 Responsibility for Those Performing the Work
 3.3.2, 3.18, 4.2.2, 4.2.3, 5.3, 6.1.3, 6.2, 6.3, 9.5.1, 10
 Retainage
 9.3.1, 9.6.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3
 Review of Contract Documents and Field Conditions
 by Contractor
 3.2, 3.12.7, 6.1.3
 Review of Contractor's Submittals by Owner and
 Architect
 3.10.1, 3.10.2, 3.11, 3.12, 4.2, 5.2, 6.1.3, 9.2, 9.8.2
 Review of Shop Drawings, Product Data and
 Samples by Contractor
 3.12
 Rights and Remedies
 1.1.2, 2.4, 2.5, 3.5, 3.7.4, 3.15.2, 4.2.6, 5.3, 5.4, 6.1,
 6.3, 7.3.1, 8.3, 9.5.1, 9.7, 10.2.5, 10.3, 12.2.1, 12.2.2,
 12.2.4, 13.3, 14, 15.4
 Royalties, Patents and Copyrights
 3.17
 Rules and Notices for Arbitration
 15.4.1
 Safety of Persons and Property
 10.2, 10.4
 Safety Precautions and Programs
 3.3.1, 4.2.2, 4.2.7, 5.3, 10.1, 10.2, 10.4
 Samples, Definition of
 3.12.3
 Samples, Shop Drawings, Product Data and
 3.11, 3.12, 4.2.7
 Samples at the Site, Documents and
 3.11
 Schedule of Values
 9.2, 9.3.1
 Schedules, Construction
 3.10, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2
 Separate Contracts and Contractors
 1.1.4, 3.12.5, 3.14.2, 4.2.4, 4.2.7, 6, 8.3.1, 12.1.2
 Separate Contractors, Definition of

6.1.1
 Shop Drawings, Definition of
 3.12.1
 Shop Drawings, Product Data and Samples
 3.11, 3.12, 4.2.7
 Site, Use of
 3.13, 6.1.1, 6.2.1
 Site Inspections
 3.2.2, 3.3.3, 3.7.1, 3.7.4, 4.2, 9.9.2, 9.4.2, 9.10.1, 13.4
 Site Visits, Architect's
 3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4
 Special Inspections and Testing
 4.2.6, 12.2.1, 13.4
 Specifications, Definition of
 1.1.6
 Specifications
 1.1.1, 1.1.6, 1.2.2, 1.5, 3.12.10, 3.17, 4.2.14
 Statute of Limitations
 15.1.2, 15.4.1.1
 Stopping the Work
 2.2.2, 2.4, 9.7, 10.3, 14.1
 Stored Materials
 6.2.1, 9.3.2, 10.2.1.2, 10.2.4
 Subcontractor, Definition of
 5.1.1
 SUBCONTRACTORS
 5
 Subcontractors, Work by
 1.2.2, 3.3.2, 3.12.1, 3.18, 4.2.3, 5.2.3, 5.3, 5.4,
 9.3.1.2, 9.6.7
 Subcontractual Relations
 5.3, 5.4, 9.3.1.2, 9.6, 9.10, 10.2.1, 14.1, 14.2.1
 Submittals
 3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 7.3.4, 9.2, 9.3,
 9.8, 9.9.1, 9.10.2, 9.10.3
 Submittal Schedule
 3.10.2, 3.12.5, 4.2.7
 Subrogation, Waivers of
 6.1.1, 11.3
 Substances, Hazardous
 10.3
 Substantial Completion
 4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, 9.8, 9.9.1, 9.10.3,
 12.2, 15.1.2
 Substantial Completion, Definition of
 9.8.1
 Substitution of Subcontractors
 5.2.3, 5.2.4
 Substitution of Architect
 2.3.3
 Substitutions of Materials
 3.4.2, 3.5, 7.3.8
 Sub-subcontractor, Definition of
 5.1.2
 Subsurface Conditions
 3.7.4
 Successors and Assigns

13.2
 Superintendent
 3.9, 10.2.6
 Supervision and Construction Procedures
 1.2.2, 3.3, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4,
 7.1.3, 7.3.4, 8.2, 8.3.1, 9.4.2, 10, 12, 14, 15.1.4
 Suppliers
 1.5, 3.12.1, 4.2.4, 4.2.6, 5.2.1, 9.3, 9.4.2, 9.5.4, 9.6,
 9.10.5, 14.2.1
 Surety
 5.4.1.2, 9.6.8, 9.8.5, 9.10.2, 9.10.3, 11.1.2, 14.2.2,
 15.2.7
 Surety, Consent of
 9.8.5, 9.10.2, 9.10.3
 Surveys
 1.1.7, 2.3.4
 Suspension by the Owner for Convenience
 14.3
 Suspension of the Work
 3.7.5, 5.4.2, 14.3
 Suspension or Termination of the Contract
 5.4.1.1, 14
 Taxes
 3.6, 3.8.2.1, 7.3.4.4
 Termination by the Contractor
 14.1, 15.1.7
 Termination by the Owner for Cause
 5.4.1.1, 14.2, 15.1.7
 Termination by the Owner for Convenience
 14.4
 Termination of the Architect
 2.3.3
 Termination of the Contractor Employment
 14.2.2

TERMINATION OR SUSPENSION OF THE CONTRACT

14
 Tests and Inspections
 3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3,
 9.9.2, 9.10.1, 10.3.2, 12.2.1, 13.4
 TIME
 8
 Time, Delays and Extensions of
 3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, 8.3, 9.5.1, 9.7,
 10.3.2, 10.4, 14.3.2, 15.1.6, 15.2.5
 Time Limits

2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2,
 5.2, 5.3, 5.4, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3,
 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14,
 15.1.2, 15.1.3, 15.4
 Time Limits on Claims
 3.7.4, 10.2.8, 15.1.2, 15.1.3
 Title to Work
 9.3.2, 9.3.3
 UNCOVERING AND CORRECTION OF WORK
 12
 Uncovering of Work
 12.1
 Unforeseen Conditions, Concealed or Unknown
 3.7.4, 8.3.1, 10.3
 Unit Prices
 7.3.3.2, 9.1.2
 Use of Documents
 1.1.1, 1.5, 2.3.6, 3.12.6, 5.3
 Use of Site
 3.13, 6.1.1, 6.2.1
 Values, Schedule of
 9.2, 9.3.1
 Waiver of Claims by the Architect
 13.3.2
 Waiver of Claims by the Contractor
 9.10.5, 13.3.2, 15.1.7
 Waiver of Claims by the Owner
 9.9.3, 9.10.3, 9.10.4, 12.2.2.1, 13.3.2, 14.2.4, 15.1.7
 Waiver of Consequential Damages
 14.2.4, 15.1.7
 Waiver of Liens
 9.3, 9.10.2, 9.10.4
 Waivers of Subrogation
 6.1.1, 11.3
 Warranty
 3.5, 4.2.9, 9.3.3, 9.8.4, 9.9.1, 9.10.2, 9.10.4, 12.2.2,
 15.1.2
 Weather Delays
 8.3, 15.1.6.2
 Work, Definition of
 1.1.3
 Written Consent
 1.5.2, 3.4.2, 3.7.4, 3.12.8, 3.14.2, 4.1.2, 9.3.2, 9.10.3,
 13.2, 13.3.2, 15.4.4.2
 Written Interpretations
 4.2.11, 4.2.12
 Written Orders
 1.1.1, 2.4, 3.9, 7, 8.2.2, 12.1, 12.2, 13.4.2, 14.3.1

ARTICLE 1 GENERAL PROVISIONS

§ 1.1 Basic Definitions

§ 1.1.1 The Contract Documents

The Contract Documents are enumerated in the Agreement between the Owner and Contractor (hereinafter the Agreement) and consist of the Agreement, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, Addenda issued prior to execution of the Contract, other documents listed in the Agreement, and Modifications issued after execution of the Contract. A Modification is (1) a written amendment to the Contract signed by both parties, (2) a Change Order, (3) a Construction Change Directive, or (4) a written order for a minor change in the Work issued by the Architect. Unless specifically enumerated in the Agreement, the Contract Documents do not include the advertisement or invitation to bid, Instructions to Bidders, sample forms, other information furnished by the Owner in anticipation of receiving bids or proposals, the Contractor's bid or proposal, or portions of Addenda relating to bidding or proposal requirements.

§ 1.1.2 The Contract

The Contract Documents form the Contract for Construction. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations, or agreements, either written or oral. The Contract may be amended or modified only by a Modification. The Contract Documents shall not be construed to create a contractual relationship of any kind (1) between the Contractor and the Architect or the Architect's consultants, (2) between the Owner and a Subcontractor or a Sub-subcontractor, (3) between the Owner and the Architect or the Architect's consultants, or (4) between any persons or entities other than the Owner and the Contractor. The Architect shall, however, be entitled to performance and enforcement of obligations under the Contract intended to facilitate performance of the Architect's duties.

§ 1.1.3 The Work

The term "Work" means the construction and services required by the Contract Documents, whether completed or partially completed, and includes all other labor, materials, equipment, and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The Work may constitute the whole or a part of the Project.

§ 1.1.4 The Project

The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part and which may include construction by the Owner and by Separate Contractors.

§ 1.1.5 The Drawings

The Drawings are the graphic and pictorial portions of the Contract Documents showing the design, location and dimensions of the Work, generally including plans, elevations, sections, details, schedules, and diagrams.

§ 1.1.6 The Specifications

The Specifications are that portion of the Contract Documents consisting of the written requirements for materials, equipment, systems, standards and workmanship for the Work, and performance of related services.

§ 1.1.7 Instruments of Service

Instruments of Service are representations, in any medium of expression now known or later developed, of the tangible and intangible creative work performed by the Architect and the Architect's consultants under their respective professional services agreements. Instruments of Service may include, without limitation, studies, surveys, models, sketches, drawings, specifications, and other similar materials.

§ 1.1.8 Initial Decision Maker

The Initial Decision Maker is the person identified in the Agreement to render initial decisions on Claims in accordance with Section 15.2. The Initial Decision Maker shall not show partiality to the Owner or Contractor and shall not be liable for results of interpretations or decisions rendered in good faith.

§ 1.2 Correlation and Intent of the Contract Documents

§ 1.2.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all; performance by the Contractor shall be required only to the extent

consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results.

§ 1.2.1.1 The invalidity of any provision of the Contract Documents shall not invalidate the Contract or its remaining provisions. If it is determined that any provision of the Contract Documents violates any law, or is otherwise invalid or unenforceable, then that provision shall be revised to the extent necessary to make that provision legal and enforceable. In such case the Contract Documents shall be construed, to the fullest extent permitted by law, to give effect to the parties' intentions and purposes in executing the Contract.

§ 1.2.2 Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade.

§ 1.2.3 Unless otherwise stated in the Contract Documents, words that have well-known technical or construction industry meanings are used in the Contract Documents in accordance with such recognized meanings.

§ 1.3 Capitalization

Terms capitalized in these General Conditions include those that are (1) specifically defined, (2) the titles of numbered articles, or (3) the titles of other documents published by the American Institute of Architects.

§ 1.4 Interpretation

In the interest of brevity the Contract Documents frequently omit modifying words such as "all" and "any" and articles such as "the" and "an," but the fact that a modifier or an article is absent from one statement and appears in another is not intended to affect the interpretation of either statement.

§ 1.5 Ownership and Use of Drawings, Specifications, and Other Instruments of Service

§ 1.5.1 The Architect and the Architect's consultants shall be deemed the authors and owners of their respective Instruments of Service, including the Drawings and Specifications, and retain all common law, statutory, and other reserved rights in their Instruments of Service, including copyrights. The Contractor, Subcontractors, Sub-subcontractors, and suppliers shall not own or claim a copyright in the Instruments of Service. Submittal or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of the Architect's or Architect's consultants' reserved rights.

§ 1.5.2 The Contractor, Subcontractors, Sub-subcontractors, and suppliers are authorized to use and reproduce the Instruments of Service provided to them, subject to any protocols established pursuant to Sections 1.7 and 1.8, solely and exclusively for execution of the Work. All copies made under this authorization shall bear the copyright notice, if any, shown on the Instruments of Service. The Contractor, Subcontractors, Sub-subcontractors, and suppliers may not use the Instruments of Service on other projects or for additions to the Project outside the scope of the Work without the specific written consent of the Owner, Architect, and the Architect's consultants.

§ 1.6 Notice

§ 1.6.1 Except as otherwise provided in Section 1.6.2, where the Contract Documents require one party to notify or give notice to the other party, such notice shall be provided in writing to the designated representative of the party to whom the notice is addressed and shall be deemed to have been duly served if delivered in person, by mail, by courier, or by electronic transmission if a method for electronic transmission is set forth in the Agreement.

§ 1.6.2 Notice of Claims as provided in Section 15.1.3 shall be provided in writing and shall be deemed to have been duly served only if delivered to the designated representative of the party to whom the notice is addressed by certified or registered mail, or by courier providing proof of delivery.

§ 1.7 Digital Data Use and Transmission

The parties shall agree upon protocols governing the transmission and use of Instruments of Service or any other information or documentation in digital form. The parties will use AIA Document E203™-2013, Building Information Modeling and Digital Data Exhibit, to establish the protocols for the development, use, transmission, and exchange of digital data.

§ 1.8 Building Information Models Use and Reliance

Any use of, or reliance on, all or a portion of a building information model without agreement to protocols governing the use of, and reliance on, the information contained in the model and without having those protocols set forth in AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, and the requisite AIA Document G202™–2013, Project Building Information Modeling Protocol Form, shall be at the using or relying party's sole risk and without liability to the other party and its contractors or consultants, the authors of, or contributors to, the building information model, and each of their agents and employees.

ARTICLE 2 OWNER

§ 2.1 General

§ 2.1.1 The Owner is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Owner shall designate in writing a representative who shall have express authority to bind the Owner with respect to all matters requiring the Owner's approval or authorization. Except as otherwise provided in Section 4.2.1, the Architect does not have such authority. The term "Owner" means the Owner or the Owner's authorized representative.

§ 2.1.2 The Owner shall furnish to the Contractor, within fifteen days after receipt of a written request, information necessary and relevant for the Contractor to evaluate, give notice of, or enforce mechanic's lien rights. Such information shall include a correct statement of the record legal title to the property on which the Project is located, usually referred to as the site, and the Owner's interest therein.

§ 2.2 Evidence of the Owner's Financial Arrangements

§ 2.2.1 Prior to commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract. The Contractor shall have no obligation to commence the Work until the Owner provides such evidence. If commencement of the Work is delayed under this Section 2.2.1, the Contract Time shall be extended appropriately.

§ 2.2.2 Following commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract only if (1) the Owner fails to make payments to the Contractor as the Contract Documents require; (2) the Contractor identifies in writing a reasonable concern regarding the Owner's ability to make payment when due; or (3) a change in the Work materially changes the Contract Sum. If the Owner fails to provide such evidence, as required, within fourteen days of the Contractor's request, the Contractor may immediately stop the Work and, in that event, shall notify the Owner that the Work has stopped. However, if the request is made because a change in the Work materially changes the Contract Sum under (3) above, the Contractor may immediately stop only that portion of the Work affected by the change until reasonable evidence is provided. If the Work is stopped under this Section 2.2.2, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided in the Contract Documents.

§ 2.2.3 After the Owner furnishes evidence of financial arrangements under this Section 2.2, the Owner shall not materially vary such financial arrangements without prior notice to the Contractor.

§ 2.2.4 Where the Owner has designated information furnished under this Section 2.2 as "confidential," the Contractor shall keep the information confidential and shall not disclose it to any other person. However, the Contractor may disclose "confidential" information, after seven (7) days' notice to the Owner, where disclosure is required by law, including a subpoena or other form of compulsory legal process issued by a court or governmental entity, or by court or arbitrator(s) order. The Contractor may also disclose "confidential" information to its employees, consultants, sureties, Subcontractors and their employees, Sub-subcontractors, and others who need to know the content of such information solely and exclusively for the Project and who agree to maintain the confidentiality of such information.

§ 2.3 Information and Services Required of the Owner

§ 2.3.1 Except for permits and fees that are the responsibility of the Contractor under the Contract Documents, including those required under Section 3.7.1, the Owner shall secure and pay for necessary approvals, easements,

assessments and charges required for construction, use or occupancy of permanent structures or for permanent changes in existing facilities.

§ 2.3.2 The Owner shall retain an architect lawfully licensed to practice architecture, or an entity lawfully practicing architecture, in the jurisdiction where the Project is located. That person or entity is identified as the Architect in the Agreement and is referred to throughout the Contract Documents as if singular in number.

§ 2.3.3 If the employment of the Architect terminates, the Owner shall employ a successor to whom the Contractor has no reasonable objection and whose status under the Contract Documents shall be that of the Architect.

§ 2.3.4 The Owner shall furnish surveys describing physical characteristics, legal limitations and utility locations for the site of the Project, and a legal description of the site. The Contractor shall be entitled to rely on the accuracy of information furnished by the Owner but shall exercise proper precautions relating to the safe performance of the Work.

§ 2.3.5 The Owner shall furnish information or services required of the Owner by the Contract Documents with reasonable promptness. The Owner shall also furnish any other information or services under the Owner's control and relevant to the Contractor's performance of the Work with reasonable promptness after receiving the Contractor's written request for such information or services.

§ 2.3.6 Unless otherwise provided in the Contract Documents, the Owner shall furnish to the Contractor one copy of the Contract Documents for purposes of making reproductions pursuant to Section 1.5.2.

§ 2.4 Owner's Right to Stop the Work

If the Contractor fails to correct Work that is not in accordance with the requirements of the Contract Documents as required by Section 12.2 or repeatedly fails to carry out Work in accordance with the Contract Documents, the Owner may issue a written order to the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, the right of the Owner to stop the Work shall not give rise to a duty on the part of the Owner to exercise this right for the benefit of the Contractor or any other person or entity, except to the extent required by Section 6.1.3.

§ 2.5 Owner's Right to Carry Out the Work

If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a ten-day period after receipt of notice from the Owner to commence and continue correction of such default or neglect with diligence and promptness, the Owner may, without prejudice to other remedies the Owner may have, correct such default or neglect. Such action by the Owner and amounts charged to the Contractor are both subject to prior approval of the Architect and the Architect may, pursuant to Section 9.5.1, withhold or nullify a Certificate for Payment in whole or in part, to the extent reasonably necessary to reimburse the Owner for the reasonable cost of correcting such deficiencies, including Owner's expenses and compensation for the Architect's additional services made necessary by such default, neglect, or failure. If current and future payments are not sufficient to cover such amounts, the Contractor shall pay the difference to the Owner. If the Contractor disagrees with the actions of the Owner or the Architect, or the amounts claimed as costs to the Owner, the Contractor may file a Claim pursuant to Article 15.

ARTICLE 3 CONTRACTOR

§ 3.1 General

§ 3.1.1 The Contractor is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Contractor shall be lawfully licensed, if required in the jurisdiction where the Project is located. The Contractor shall designate in writing a representative who shall have express authority to bind the Contractor with respect to all matters under this Contract. The term "Contractor" means the Contractor or the Contractor's authorized representative.

§ 3.1.2 The Contractor shall perform the Work in accordance with the Contract Documents.

§ 3.1.3 The Contractor shall not be relieved of its obligations to perform the Work in accordance with the Contract Documents either by activities or duties of the Architect in the Architect's administration of the Contract, or by tests, inspections or approvals required or performed by persons or entities other than the Contractor.

§ 3.2 Review of Contract Documents and Field Conditions by Contractor

§ 3.2.1 Execution of the Contract by the Contractor is a representation that the Contractor has visited the site, become generally familiar with local conditions under which the Work is to be performed, and correlated personal observations with requirements of the Contract Documents.

§ 3.2.2 Because the Contract Documents are complementary, the Contractor shall, before starting each portion of the Work, carefully study and compare the various Contract Documents relative to that portion of the Work, as well as the information furnished by the Owner pursuant to Section 2.3.4, shall take field measurements of any existing conditions related to that portion of the Work, and shall observe any conditions at the site affecting it. These obligations are for the purpose of facilitating coordination and construction by the Contractor and are not for the purpose of discovering errors, omissions, or inconsistencies in the Contract Documents; however, the Contractor shall promptly report to the Architect any errors, inconsistencies or omissions discovered by or made known to the Contractor as a request for information in such form as the Architect may require. It is recognized that the Contractor's review is made in the Contractor's capacity as a contractor and not as a licensed design professional, unless otherwise specifically provided in the Contract Documents.

§ 3.2.3 The Contractor is not required to ascertain that the Contract Documents are in accordance with applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, but the Contractor shall promptly report to the Architect any nonconformity discovered by or made known to the Contractor as a request for information in such form as the Architect may require.

§ 3.2.4 If the Contractor believes that additional cost or time is involved because of clarifications or instructions the Architect issues in response to the Contractor's notices or requests for information pursuant to Sections 3.2.2 or 3.2.3, the Contractor shall submit Claims as provided in Article 15. If the Contractor fails to perform the obligations of Sections 3.2.2 or 3.2.3, the Contractor shall pay such costs and damages to the Owner, subject to Section 15.1.7, as would have been avoided if the Contractor had performed such obligations. If the Contractor performs those obligations, the Contractor shall not be liable to the Owner or Architect for damages resulting from errors, inconsistencies or omissions in the Contract Documents, for differences between field measurements or conditions and the Contract Documents, or for nonconformities of the Contract Documents to applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities.

§ 3.3 Supervision and Construction Procedures

§ 3.3.1 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for, and have control over, construction means, methods, techniques, sequences, and procedures, and for coordinating all portions of the Work under the Contract. If the Contract Documents give specific instructions concerning construction means, methods, techniques, sequences, or procedures, the Contractor shall evaluate the jobsite safety thereof and shall be solely responsible for the jobsite safety of such means, methods, techniques, sequences, or procedures. If the Contractor determines that such means, methods, techniques, sequences or procedures may not be safe, the Contractor shall give timely notice to the Owner and Architect, and shall propose alternative means, methods, techniques, sequences, or procedures. The Architect shall evaluate the proposed alternative solely for conformance with the design intent for the completed construction. Unless the Architect objects to the Contractor's proposed alternative, the Contractor shall perform the Work using its alternative means, methods, techniques, sequences, or procedures.

§ 3.3.2 The Contractor shall be responsible to the Owner for acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons or entities performing portions of the Work for, or on behalf of, the Contractor or any of its Subcontractors.

§ 3.3.3 The Contractor shall be responsible for inspection of portions of Work already performed to determine that such portions are in proper condition to receive subsequent Work.

§ 3.4 Labor and Materials

§ 3.4.1 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for proper execution and completion of the Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.

§ 3.4.2 Except in the case of minor changes in the Work approved by the Architect in accordance with Section 3.12.8 or ordered by the Architect in accordance with Section 7.4, the Contractor may make substitutions only with the consent of the Owner, after evaluation by the Architect and in accordance with a Change Order or Construction Change Directive.

§ 3.4.3 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Work. The Contractor shall not permit employment of unfit persons or persons not properly skilled in tasks assigned to them.

§ 3.5 Warranty

§ 3.5.1 The Contractor warrants to the Owner and Architect that materials and equipment furnished under the Contract will be of good quality and new unless the Contract Documents require or permit otherwise. The Contractor further warrants that the Work will conform to the requirements of the Contract Documents and will be free from defects, except for those inherent in the quality of the Work the Contract Documents require or permit. Work, materials, or equipment not conforming to these requirements may be considered defective. The Contractor's warranty excludes remedy for damage or defect caused by abuse, alterations to the Work not executed by the Contractor, improper or insufficient maintenance, improper operation, or normal wear and tear and normal usage. If required by the Architect, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

§ 3.5.2 All material, equipment, or other special warranties required by the Contract Documents shall be issued in the name of the Owner, or shall be transferable to the Owner, and shall commence in accordance with Section 9.8.4.

§ 3.6 Taxes

The Contractor shall pay sales, consumer, use and similar taxes for the Work provided by the Contractor that are legally enacted when bids are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect.

§ 3.7 Permits, Fees, Notices and Compliance with Laws

§ 3.7.1 Unless otherwise provided in the Contract Documents, the Contractor shall secure and pay for the building permit as well as for other permits, fees, licenses, and inspections by government agencies necessary for proper execution and completion of the Work that are customarily secured after execution of the Contract and legally required at the time bids are received or negotiations concluded.

§ 3.7.2 The Contractor shall comply with and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities applicable to performance of the Work.

§ 3.7.3 If the Contractor performs Work knowing it to be contrary to applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, the Contractor shall assume appropriate responsibility for such Work and shall bear the costs attributable to correction.

§ 3.7.4 Concealed or Unknown Conditions

If the Contractor encounters conditions at the site that are (1) subsurface or otherwise concealed physical conditions that differ materially from those indicated in the Contract Documents or (2) unknown physical conditions of an unusual nature that differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, the Contractor shall promptly provide notice to the Owner and the Architect before conditions are disturbed and in no event later than 14 days after first observance of the conditions. The Architect will promptly investigate such conditions and, if the Architect determines that they differ materially and cause an increase or decrease in the Contractor's cost of, or time required for, performance of any part of the Work, will recommend that an equitable adjustment be made in the Contract Sum or Contract Time, or both. If the Architect determines that the conditions at the site are not materially different from those indicated in the Contract Documents and that no change in the terms of the Contract is justified, the Architect shall promptly notify the Owner and Contractor, stating the reasons. If either party disputes the Architect's determination or recommendation, that party may submit a Claim as provided in Article 15.

§ 3.7.5 If, in the course of the Work, the Contractor encounters human remains or recognizes the existence of burial markers, archaeological sites or wetlands not indicated in the Contract Documents, the Contractor shall immediately suspend any operations that would affect them and shall notify the Owner and Architect. Upon receipt of such notice, the Owner shall promptly take any action necessary to obtain governmental authorization required to resume the operations. The Contractor shall continue to suspend such operations until otherwise instructed by the Owner but shall continue with all other operations that do not affect those remains or features. Requests for adjustments in the Contract Sum and Contract Time arising from the existence of such remains or features may be made as provided in Article 15.

§ 3.8 Allowances

§ 3.8.1 The Contractor shall include in the Contract Sum all allowances stated in the Contract Documents. Items covered by allowances shall be supplied for such amounts and by such persons or entities as the Owner may direct, but the Contractor shall not be required to employ persons or entities to whom the Contractor has reasonable objection.

§ 3.8.2 Unless otherwise provided in the Contract Documents,

- .1 allowances shall cover the cost to the Contractor of materials and equipment delivered at the site and all required taxes, less applicable trade discounts;
- .2 Contractor's costs for unloading and handling at the site, labor, installation costs, overhead, profit, and other expenses contemplated for stated allowance amounts shall be included in the Contract Sum but not in the allowances; and
- .3 whenever costs are more than or less than allowances, the Contract Sum shall be adjusted accordingly by Change Order. The amount of the Change Order shall reflect (1) the difference between actual costs and the allowances under Section 3.8.2.1 and (2) changes in Contractor's costs under Section 3.8.2.2.

§ 3.8.3 Materials and equipment under an allowance shall be selected by the Owner with reasonable promptness.

§ 3.9 Superintendent

§ 3.9.1 The Contractor shall employ a competent superintendent and necessary assistants who shall be in attendance at the Project site during performance of the Work. The superintendent shall represent the Contractor, and communications given to the superintendent shall be as binding as if given to the Contractor.

§ 3.9.2 The Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the name and qualifications of a proposed superintendent. Within 14 days of receipt of the information, the Architect may notify the Contractor, stating whether the Owner or the Architect (1) has reasonable objection to the proposed superintendent or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 3.9.3 The Contractor shall not employ a proposed superintendent to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not change the superintendent without the Owner's consent, which shall not unreasonably be withheld or delayed.

§ 3.10 Contractor's Construction and Submittal Schedules

§ 3.10.1 The Contractor, promptly after being awarded the Contract, shall submit for the Owner's and Architect's information a Contractor's construction schedule for the Work. The schedule shall contain detail appropriate for the Project, including (1) the date of commencement of the Work, interim schedule milestone dates, and the date of Substantial Completion; (2) an apportionment of the Work by construction activity; and (3) the time required for completion of each portion of the Work. The schedule shall provide for the orderly progression of the Work to completion and shall not exceed time limits current under the Contract Documents. The schedule shall be revised at appropriate intervals as required by the conditions of the Work and Project.

§ 3.10.2 The Contractor, promptly after being awarded the Contract and thereafter as necessary to maintain a current submittal schedule, shall submit a submittal schedule for the Architect's approval. The Architect's approval shall not be unreasonably delayed or withheld. The submittal schedule shall (1) be coordinated with the Contractor's construction schedule, and (2) allow the Architect reasonable time to review submittals. If the Contractor fails to submit a submittal schedule, or fails to provide submittals in accordance with the approved submittal schedule, the

Contractor shall not be entitled to any increase in Contract Sum or extension of Contract Time based on the time required for review of submittals.

§ 3.10.3 The Contractor shall perform the Work in general accordance with the most recent schedules submitted to the Owner and Architect.

§ 3.11 Documents and Samples at the Site

The Contractor shall make available, at the Project site, the Contract Documents, including Change Orders, Construction Change Directives, and other Modifications, in good order and marked currently to indicate field changes and selections made during construction, and the approved Shop Drawings, Product Data, Samples, and similar required submittals. These shall be in electronic form or paper copy, available to the Architect and Owner, and delivered to the Architect for submittal to the Owner upon completion of the Work as a record of the Work as constructed.

§ 3.12 Shop Drawings, Product Data and Samples

§ 3.12.1 Shop Drawings are drawings, diagrams, schedules, and other data specially prepared for the Work by the Contractor or a Subcontractor, Sub-subcontractor, manufacturer, supplier, or distributor to illustrate some portion of the Work.

§ 3.12.2 Product Data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams, and other information furnished by the Contractor to illustrate materials or equipment for some portion of the Work.

§ 3.12.3 Samples are physical examples that illustrate materials, equipment, or workmanship, and establish standards by which the Work will be judged.

§ 3.12.4 Shop Drawings, Product Data, Samples, and similar submittals are not Contract Documents. Their purpose is to demonstrate how the Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents for those portions of the Work for which the Contract Documents require submittals. Review by the Architect is subject to the limitations of Section 4.2.7. Informational submittals upon which the Architect is not expected to take responsive action may be so identified in the Contract Documents. Submittals that are not required by the Contract Documents may be returned by the Architect without action.

§ 3.12.5 The Contractor shall review for compliance with the Contract Documents, approve, and submit to the Architect, Shop Drawings, Product Data, Samples, and similar submittals required by the Contract Documents, in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness and in such sequence as to cause no delay in the Work or in the activities of the Owner or of Separate Contractors.

§ 3.12.6 By submitting Shop Drawings, Product Data, Samples, and similar submittals, the Contractor represents to the Owner and Architect that the Contractor has (1) reviewed and approved them, (2) determined and verified materials, field measurements and field construction criteria related thereto, or will do so, and (3) checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.

§ 3.12.7 The Contractor shall perform no portion of the Work for which the Contract Documents require submittal and review of Shop Drawings, Product Data, Samples, or similar submittals, until the respective submittal has been approved by the Architect.

§ 3.12.8 The Work shall be in accordance with approved submittals except that the Contractor shall not be relieved of responsibility for deviations from the requirements of the Contract Documents by the Architect's approval of Shop Drawings, Product Data, Samples, or similar submittals, unless the Contractor has specifically notified the Architect of such deviation at the time of submittal and (1) the Architect has given written approval to the specific deviation as a minor change in the Work, or (2) a Change Order or Construction Change Directive has been issued authorizing the deviation. The Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples, or similar submittals, by the Architect's approval thereof.

§ 3.12.9 The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples, or similar submittals, to revisions other than those requested by the Architect on previous submittals. In the absence of such notice, the Architect's approval of a resubmission shall not apply to such revisions.

§ 3.12.10 The Contractor shall not be required to provide professional services that constitute the practice of architecture or engineering unless such services are specifically required by the Contract Documents for a portion of the Work or unless the Contractor needs to provide such services in order to carry out the Contractor's responsibilities for construction means, methods, techniques, sequences, and procedures. The Contractor shall not be required to provide professional services in violation of applicable law.

§ 3.12.10.1 If professional design services or certifications by a design professional related to systems, materials, or equipment are specifically required of the Contractor by the Contract Documents, the Owner and the Architect will specify all performance and design criteria that such services must satisfy. The Contractor shall be entitled to rely upon the adequacy and accuracy of the performance and design criteria provided in the Contract Documents. The Contractor shall cause such services or certifications to be provided by an appropriately licensed design professional, whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings, and other submittals prepared by such professional. Shop Drawings, and other submittals related to the Work, designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to the Architect. The Owner and the Architect shall be entitled to rely upon the adequacy and accuracy of the services, certifications, and approvals performed or provided by such design professionals, provided the Owner and Architect have specified to the Contractor the performance and design criteria that such services must satisfy. Pursuant to this Section 3.12.10, the Architect will review and approve or take other appropriate action on submittals only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents.

§ 3.12.10.2 If the Contract Documents require the Contractor's design professional to certify that the Work has been performed in accordance with the design criteria, the Contractor shall furnish such certifications to the Architect at the time and in the form specified by the Architect.

§ 3.13 Use of Site

The Contractor shall confine operations at the site to areas permitted by applicable laws, statutes, ordinances, codes, rules and regulations, lawful orders of public authorities, and the Contract Documents and shall not unreasonably encumber the site with materials or equipment.

§ 3.14 Cutting and Patching

§ 3.14.1 The Contractor shall be responsible for cutting, fitting, or patching required to complete the Work or to make its parts fit together properly. All areas requiring cutting, fitting, or patching shall be restored to the condition existing prior to the cutting, fitting, or patching, unless otherwise required by the Contract Documents.

§ 3.14.2 The Contractor shall not damage or endanger a portion of the Work or fully or partially completed construction of the Owner or Separate Contractors by cutting, patching, or otherwise altering such construction, or by excavation. The Contractor shall not cut or otherwise alter construction by the Owner or a Separate Contractor except with written consent of the Owner and of the Separate Contractor. Consent shall not be unreasonably withheld. The Contractor shall not unreasonably withhold, from the Owner or a Separate Contractor, its consent to cutting or otherwise altering the Work.

§ 3.15 Cleaning Up

§ 3.15.1 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials and rubbish caused by operations under the Contract. At completion of the Work, the Contractor shall remove waste materials, rubbish, the Contractor's tools, construction equipment, machinery, and surplus materials from and about the Project.

§ 3.15.2 If the Contractor fails to clean up as provided in the Contract Documents, the Owner may do so and the Owner shall be entitled to reimbursement from the Contractor.

§ 3.16 Access to Work

The Contractor shall provide the Owner and Architect with access to the Work in preparation and progress wherever located.

§ 3.17 Royalties, Patents and Copyrights

The Contractor shall pay all royalties and license fees. The Contractor shall defend suits or claims for infringement of copyrights and patent rights and shall hold the Owner and Architect harmless from loss on account thereof, but shall not be responsible for defense or loss when a particular design, process, or product of a particular manufacturer or manufacturers is required by the Contract Documents, or where the copyright violations are contained in Drawings, Specifications, or other documents prepared by the Owner or Architect. However, if an infringement of a copyright or patent is discovered by, or made known to, the Contractor, the Contractor shall be responsible for the loss unless the information is promptly furnished to the Architect.

§ 3.18 Indemnification

§ 3.18.1 To the fullest extent permitted by law, the Contractor shall indemnify and hold harmless the Owner, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), but only to the extent caused by the negligent acts or omissions of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss, or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity that would otherwise exist as to a party or person described in this Section 3.18.

§ 3.18.2 In claims against any person or entity indemnified under this Section 3.18 by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, the indemnification obligation under Section 3.18.1 shall not be limited by a limitation on amount or type of damages, compensation, or benefits payable by or for the Contractor or a Subcontractor under workers' compensation acts, disability benefit acts, or other employee benefit acts.

ARTICLE 4 ARCHITECT

§ 4.1 General

§ 4.1.1 The Architect is the person or entity retained by the Owner pursuant to Section 2.3.2 and identified as such in the Agreement.

§ 4.1.2 Duties, responsibilities, and limitations of authority of the Architect as set forth in the Contract Documents shall not be restricted, modified, or extended without written consent of the Owner, Contractor, and Architect. Consent shall not be unreasonably withheld.

§ 4.2 Administration of the Contract

§ 4.2.1 The Architect will provide administration of the Contract as described in the Contract Documents and will be an Owner's representative during construction until the date the Architect issues the final Certificate for Payment. The Architect will have authority to act on behalf of the Owner only to the extent provided in the Contract Documents.

§ 4.2.2 The Architect will visit the site at intervals appropriate to the stage of construction, or as otherwise agreed with the Owner, to become generally familiar with the progress and quality of the portion of the Work completed, and to determine in general if the Work observed is being performed in a manner indicating that the Work, when fully completed, will be in accordance with the Contract Documents. However, the Architect will not be required to make exhaustive or continuous on-site inspections to check the quality or quantity of the Work. The Architect will not have control over, charge of, or responsibility for the construction means, methods, techniques, sequences or procedures, or for the safety precautions and programs in connection with the Work, since these are solely the Contractor's rights and responsibilities under the Contract Documents.

§ 4.2.3 On the basis of the site visits, the Architect will keep the Owner reasonably informed about the progress and quality of the portion of the Work completed, and promptly report to the Owner (1) known deviations from the

Contract Documents, (2) known deviations from the most recent construction schedule submitted by the Contractor, and (3) defects and deficiencies observed in the Work. The Architect will not be responsible for the Contractor's failure to perform the Work in accordance with the requirements of the Contract Documents. The Architect will not have control over or charge of, and will not be responsible for acts or omissions of, the Contractor, Subcontractors, or their agents or employees, or any other persons or entities performing portions of the Work.

§ 4.2.4 Communications

The Owner and Contractor shall include the Architect in all communications that relate to or affect the Architect's services or professional responsibilities. The Owner shall promptly notify the Architect of the substance of any direct communications between the Owner and the Contractor otherwise relating to the Project. Communications by and with the Architect's consultants shall be through the Architect. Communications by and with Subcontractors and suppliers shall be through the Contractor. Communications by and with Separate Contractors shall be through the Owner. The Contract Documents may specify other communication protocols.

§ 4.2.5 Based on the Architect's evaluations of the Contractor's Applications for Payment, the Architect will review and certify the amounts due the Contractor and will issue Certificates for Payment in such amounts.

§ 4.2.6 The Architect has authority to reject Work that does not conform to the Contract Documents. Whenever the Architect considers it necessary or advisable, the Architect will have authority to require inspection or testing of the Work in accordance with Sections 13.4.2 and 13.4.3, whether or not the Work is fabricated, installed or completed. However, neither this authority of the Architect nor a decision made in good faith either to exercise or not to exercise such authority shall give rise to a duty or responsibility of the Architect to the Contractor, Subcontractors, suppliers, their agents or employees, or other persons or entities performing portions of the Work.

§ 4.2.7 The Architect will review and approve, or take other appropriate action upon, the Contractor's submittals such as Shop Drawings, Product Data, and Samples, but only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents. The Architect's action will be taken in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness while allowing sufficient time in the Architect's professional judgment to permit adequate review. Review of such submittals is not conducted for the purpose of determining the accuracy and completeness of other details such as dimensions and quantities, or for substantiating instructions for installation or performance of equipment or systems, all of which remain the responsibility of the Contractor as required by the Contract Documents. The Architect's review of the Contractor's submittals shall not relieve the Contractor of the obligations under Sections 3.3, 3.5, and 3.12. The Architect's review shall not constitute approval of safety precautions or of any construction means, methods, techniques, sequences, or procedures. The Architect's approval of a specific item shall not indicate approval of an assembly of which the item is a component.

§ 4.2.8 The Architect will prepare Change Orders and Construction Change Directives, and may order minor changes in the Work as provided in Section 7.4. The Architect will investigate and make determinations and recommendations regarding concealed and unknown conditions as provided in Section 3.7.4.

§ 4.2.9 The Architect will conduct inspections to determine the date or dates of Substantial Completion and the date of final completion; issue Certificates of Substantial Completion pursuant to Section 9.8; receive and forward to the Owner, for the Owner's review and records, written warranties and related documents required by the Contract and assembled by the Contractor pursuant to Section 9.10; and issue a final Certificate for Payment pursuant to Section 9.10.

§ 4.2.10 If the Owner and Architect agree, the Architect will provide one or more Project representatives to assist in carrying out the Architect's responsibilities at the site. The Owner shall notify the Contractor of any change in the duties, responsibilities and limitations of authority of the Project representatives.

§ 4.2.11 The Architect will interpret and decide matters concerning performance under, and requirements of, the Contract Documents on written request of either the Owner or Contractor. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness.

§ 4.2.12 Interpretations and decisions of the Architect will be consistent with the intent of, and reasonably inferable from, the Contract Documents and will be in writing or in the form of drawings. When making such interpretations

and decisions, the Architect will endeavor to secure faithful performance by both Owner and Contractor, will not show partiality to either, and will not be liable for results of interpretations or decisions rendered in good faith.

§ 4.2.13 The Architect's decisions on matters relating to aesthetic effect will be final if consistent with the intent expressed in the Contract Documents.

§ 4.2.14 The Architect will review and respond to requests for information about the Contract Documents. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness. If appropriate, the Architect will prepare and issue supplemental Drawings and Specifications in response to the requests for information.

ARTICLE 5 SUBCONTRACTORS

§ 5.1 Definitions

§ 5.1.1 A Subcontractor is a person or entity who has a direct contract with the Contractor to perform a portion of the Work at the site. The term "Subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Subcontractor or an authorized representative of the Subcontractor. The term "Subcontractor" does not include a Separate Contractor or the subcontractors of a Separate Contractor.

§ 5.1.2 A Sub-subcontractor is a person or entity who has a direct or indirect contract with a Subcontractor to perform a portion of the Work at the site. The term "Sub-subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Sub-subcontractor or an authorized representative of the Sub-subcontractor.

§ 5.2 Award of Subcontracts and Other Contracts for Portions of the Work

§ 5.2.1 Unless otherwise stated in the Contract Documents, the Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the persons or entities proposed for each principal portion of the Work, including those who are to furnish materials or equipment fabricated to a special design. Within 14 days of receipt of the information, the Architect may notify the Contractor whether the Owner or the Architect (1) has reasonable objection to any such proposed person or entity or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 5.2.2 The Contractor shall not contract with a proposed person or entity to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not be required to contract with anyone to whom the Contractor has made reasonable objection.

§ 5.2.3 If the Owner or Architect has reasonable objection to a person or entity proposed by the Contractor, the Contractor shall propose another to whom the Owner or Architect has no reasonable objection. If the proposed but rejected Subcontractor was reasonably capable of performing the Work, the Contract Sum and Contract Time shall be increased or decreased by the difference, if any, occasioned by such change, and an appropriate Change Order shall be issued before commencement of the substitute Subcontractor's Work. However, no increase in the Contract Sum or Contract Time shall be allowed for such change unless the Contractor has acted promptly and responsively in submitting names as required.

§ 5.2.4 The Contractor shall not substitute a Subcontractor, person, or entity for one previously selected if the Owner or Architect makes reasonable objection to such substitution.

§ 5.3 Subcontractual Relations

By appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities, including the responsibility for safety of the Subcontractor's Work that the Contractor, by these Contract Documents, assumes toward the Owner and Architect. Each subcontract agreement shall preserve and protect the rights of the Owner and Architect under the Contract Documents with respect to the Work to be performed by the Subcontractor so that subcontracting thereof will not prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise in the subcontract agreement, the benefit of all rights, remedies, and redress against the Contractor that the Contractor, by the Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor,

prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor will be bound, and, upon written request of the Subcontractor, identify to the Subcontractor terms and conditions of the proposed subcontract agreement that may be at variance with the Contract Documents. Subcontractors will similarly make copies of applicable portions of such documents available to their respective proposed Sub-subcontractors.

§ 5.4 Contingent Assignment of Subcontracts

§ 5.4.1 Each subcontract agreement for a portion of the Work is assigned by the Contractor to the Owner, provided that

- .1 assignment is effective only after termination of the Contract by the Owner for cause pursuant to Section 14.2 and only for those subcontract agreements that the Owner accepts by notifying the Subcontractor and Contractor; and
- .2 assignment is subject to the prior rights of the surety, if any, obligated under bond relating to the Contract.

When the Owner accepts the assignment of a subcontract agreement, the Owner assumes the Contractor's rights and obligations under the subcontract.

§ 5.4.2 Upon such assignment, if the Work has been suspended for more than 30 days, the Subcontractor's compensation shall be equitably adjusted for increases in cost resulting from the suspension.

§ 5.4.3 Upon assignment to the Owner under this Section 5.4, the Owner may further assign the subcontract to a successor contractor or other entity. If the Owner assigns the subcontract to a successor contractor or other entity, the Owner shall nevertheless remain legally responsible for all of the successor contractor's obligations under the subcontract.

ARTICLE 6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

§ 6.1 Owner's Right to Perform Construction and to Award Separate Contracts

§ 6.1.1 The term "Separate Contractor(s)" shall mean other contractors retained by the Owner under separate agreements. The Owner reserves the right to perform construction or operations related to the Project with the Owner's own forces, and with Separate Contractors retained under Conditions of the Contract substantially similar to those of this Contract, including those provisions of the Conditions of the Contract related to insurance and waiver of subrogation.

§ 6.1.2 When separate contracts are awarded for different portions of the Project or other construction or operations on the site, the term "Contractor" in the Contract Documents in each case shall mean the Contractor who executes each separate Owner-Contractor Agreement.

§ 6.1.3 The Owner shall provide for coordination of the activities of the Owner's own forces and of each Separate Contractor with the Work of the Contractor, who shall cooperate with them. The Contractor shall participate with any Separate Contractors and the Owner in reviewing their construction schedules. The Contractor shall make any revisions to its construction schedule deemed necessary after a joint review and mutual agreement. The construction schedules shall then constitute the schedules to be used by the Contractor, Separate Contractors, and the Owner until subsequently revised.

§ 6.1.4 Unless otherwise provided in the Contract Documents, when the Owner performs construction or operations related to the Project with the Owner's own forces or with Separate Contractors, the Owner or its Separate Contractors shall have the same obligations and rights that the Contractor has under the Conditions of the Contract, including, without excluding others, those stated in Article 3, this Article 6, and Articles 10, 11, and 12.

§ 6.2 Mutual Responsibility

§ 6.2.1 The Contractor shall afford the Owner and Separate Contractors reasonable opportunity for introduction and storage of their materials and equipment and performance of their activities, and shall connect and coordinate the Contractor's construction and operations with theirs as required by the Contract Documents.

§ 6.2.2 If part of the Contractor's Work depends for proper execution or results upon construction or operations by the Owner or a Separate Contractor, the Contractor shall, prior to proceeding with that portion of the Work,

promptly notify the Architect of apparent discrepancies or defects in the construction or operations by the Owner or Separate Contractor that would render it unsuitable for proper execution and results of the Contractor's Work. Failure of the Contractor to notify the Architect of apparent discrepancies or defects prior to proceeding with the Work shall constitute an acknowledgment that the Owner's or Separate Contractor's completed or partially completed construction is fit and proper to receive the Contractor's Work. The Contractor shall not be responsible for discrepancies or defects in the construction or operations by the Owner or Separate Contractor that are not apparent.

§ 6.2.3 The Contractor shall reimburse the Owner for costs the Owner incurs that are payable to a Separate Contractor because of the Contractor's delays, improperly timed activities or defective construction. The Owner shall be responsible to the Contractor for costs the Contractor incurs because of a Separate Contractor's delays, improperly timed activities, damage to the Work or defective construction.

§ 6.2.4 The Contractor shall promptly remedy damage that the Contractor wrongfully causes to completed or partially completed construction or to property of the Owner or Separate Contractor as provided in Section 10.2.5.

§ 6.2.5 The Owner and each Separate Contractor shall have the same responsibilities for cutting and patching as are described for the Contractor in Section 3.14.

§ 6.3 Owner's Right to Clean Up

If a dispute arises among the Contractor, Separate Contractors, and the Owner as to the responsibility under their respective contracts for maintaining the premises and surrounding area free from waste materials and rubbish, the Owner may clean up and the Architect will allocate the cost among those responsible.

ARTICLE 7 CHANGES IN THE WORK

§ 7.1 General

§ 7.1.1 Changes in the Work may be accomplished after execution of the Contract, and without invalidating the Contract, by Change Order, Construction Change Directive or order for a minor change in the Work, subject to the limitations stated in this Article 7 and elsewhere in the Contract Documents.

§ 7.1.2 A Change Order shall be based upon agreement among the Owner, Contractor, and Architect. A Construction Change Directive requires agreement by the Owner and Architect and may or may not be agreed to by the Contractor. An order for a minor change in the Work may be issued by the Architect alone.

§ 7.1.3 Changes in the Work shall be performed under applicable provisions of the Contract Documents. The Contractor shall proceed promptly with changes in the Work, unless otherwise provided in the Change Order, Construction Change Directive, or order for a minor change in the Work.

§ 7.2 Change Orders

§ 7.2.1 A Change Order is a written instrument prepared by the Architect and signed by the Owner, Contractor, and Architect stating their agreement upon all of the following:

- .1 The change in the Work;
- .2 The amount of the adjustment, if any, in the Contract Sum; and
- .3 The extent of the adjustment, if any, in the Contract Time.

§ 7.3 Construction Change Directives

§ 7.3.1 A Construction Change Directive is a written order prepared by the Architect and signed by the Owner and Architect, directing a change in the Work prior to agreement on adjustment, if any, in the Contract Sum or Contract Time, or both. The Owner may by Construction Change Directive, without invalidating the Contract, order changes in the Work within the general scope of the Contract consisting of additions, deletions, or other revisions, the Contract Sum and Contract Time being adjusted accordingly.

§ 7.3.2 A Construction Change Directive shall be used in the absence of total agreement on the terms of a Change Order.

§ 7.3.3 If the Construction Change Directive provides for an adjustment to the Contract Sum, the adjustment shall be based on one of the following methods:

- .1 Mutual acceptance of a lump sum properly itemized and supported by sufficient substantiating data to permit evaluation;
- .2 Unit prices stated in the Contract Documents or subsequently agreed upon;
- .3 Cost to be determined in a manner agreed upon by the parties and a mutually acceptable fixed or percentage fee; or
- .4 As provided in Section 7.3.4.

§ 7.3.4 If the Contractor does not respond promptly or disagrees with the method for adjustment in the Contract Sum, the Architect shall determine the adjustment on the basis of reasonable expenditures and savings of those performing the Work attributable to the change, including, in case of an increase in the Contract Sum, an amount for overhead and profit as set forth in the Agreement, or if no such amount is set forth in the Agreement, a reasonable amount. In such case, and also under Section 7.3.3.3, the Contractor shall keep and present, in such form as the Architect may prescribe, an itemized accounting together with appropriate supporting data. Unless otherwise provided in the Contract Documents, costs for the purposes of this Section 7.3.4 shall be limited to the following:

- .1 Costs of labor, including applicable payroll taxes, fringe benefits required by agreement or custom, workers' compensation insurance, and other employee costs approved by the Architect;
- .2 Costs of materials, supplies, and equipment, including cost of transportation, whether incorporated or consumed;
- .3 Rental costs of machinery and equipment, exclusive of hand tools, whether rented from the Contractor or others;
- .4 Costs of premiums for all bonds and insurance, permit fees, and sales, use, or similar taxes, directly related to the change; and
- .5 Costs of supervision and field office personnel directly attributable to the change.

§ 7.3.5 If the Contractor disagrees with the adjustment in the Contract Time, the Contractor may make a Claim in accordance with applicable provisions of Article 15.

§ 7.3.6 Upon receipt of a Construction Change Directive, the Contractor shall promptly proceed with the change in the Work involved and advise the Architect of the Contractor's agreement or disagreement with the method, if any, provided in the Construction Change Directive for determining the proposed adjustment in the Contract Sum or Contract Time.

§ 7.3.7 A Construction Change Directive signed by the Contractor indicates the Contractor's agreement therewith, including adjustment in Contract Sum and Contract Time or the method for determining them. Such agreement shall be effective immediately and shall be recorded as a Change Order.

§ 7.3.8 The amount of credit to be allowed by the Contractor to the Owner for a deletion or change that results in a net decrease in the Contract Sum shall be actual net cost as confirmed by the Architect. When both additions and credits covering related Work or substitutions are involved in a change, the allowance for overhead and profit shall be figured on the basis of net increase, if any, with respect to that change.

§ 7.3.9 Pending final determination of the total cost of a Construction Change Directive to the Owner, the Contractor may request payment for Work completed under the Construction Change Directive in Applications for Payment. The Architect will make an interim determination for purposes of monthly certification for payment for those costs and certify for payment the amount that the Architect determines, in the Architect's professional judgment, to be reasonably justified. The Architect's interim determination of cost shall adjust the Contract Sum on the same basis as a Change Order, subject to the right of either party to disagree and assert a Claim in accordance with Article 15.

§ 7.3.10 When the Owner and Contractor agree with a determination made by the Architect concerning the adjustments in the Contract Sum and Contract Time, or otherwise reach agreement upon the adjustments, such agreement shall be effective immediately and the Architect will prepare a Change Order. Change Orders may be issued for all or any part of a Construction Change Directive.

§ 7.4 Minor Changes in the Work

The Architect may order minor changes in the Work that are consistent with the intent of the Contract Documents and do not involve an adjustment in the Contract Sum or an extension of the Contract Time. The Architect's order for minor changes shall be in writing. If the Contractor believes that the proposed minor change in the Work will

affect the Contract Sum or Contract Time, the Contractor shall notify the Architect and shall not proceed to implement the change in the Work. If the Contractor performs the Work set forth in the Architect's order for a minor change without prior notice to the Architect that such change will affect the Contract Sum or Contract Time, the Contractor waives any adjustment to the Contract Sum or extension of the Contract Time.

ARTICLE 8 TIME

§ 8.1 Definitions

§ 8.1.1 Unless otherwise provided, Contract Time is the period of time, including authorized adjustments, allotted in the Contract Documents for Substantial Completion of the Work.

§ 8.1.2 The date of commencement of the Work is the date established in the Agreement.

§ 8.1.3 The date of Substantial Completion is the date certified by the Architect in accordance with Section 9.8.

§ 8.1.4 The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.

§ 8.2 Progress and Completion

§ 8.2.1 Time limits stated in the Contract Documents are of the essence of the Contract. By executing the Agreement, the Contractor confirms that the Contract Time is a reasonable period for performing the Work.

§ 8.2.2 The Contractor shall not knowingly, except by agreement or instruction of the Owner in writing, commence the Work prior to the effective date of insurance required to be furnished by the Contractor and Owner.

§ 8.2.3 The Contractor shall proceed expeditiously with adequate forces and shall achieve Substantial Completion within the Contract Time.

§ 8.3 Delays and Extensions of Time

§ 8.3.1 If the Contractor is delayed at any time in the commencement or progress of the Work by (1) an act or neglect of the Owner or Architect, of an employee of either, or of a Separate Contractor; (2) by changes ordered in the Work; (3) by labor disputes, fire, unusual delay in deliveries, unavoidable casualties, adverse weather conditions documented in accordance with Section 15.1.6.2, or other causes beyond the Contractor's control; (4) by delay authorized by the Owner pending mediation and binding dispute resolution; or (5) by other causes that the Contractor asserts, and the Architect determines, justify delay, then the Contract Time shall be extended for such reasonable time as the Architect may determine.

§ 8.3.2 Claims relating to time shall be made in accordance with applicable provisions of Article 15.

§ 8.3.3 This Section 8.3 does not preclude recovery of damages for delay by either party under other provisions of the Contract Documents.

ARTICLE 9 PAYMENTS AND COMPLETION

§ 9.1 Contract Sum

§ 9.1.1 The Contract Sum is stated in the Agreement and, including authorized adjustments, is the total amount payable by the Owner to the Contractor for performance of the Work under the Contract Documents.

§ 9.1.2 If unit prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are materially changed so that application of such unit prices to the actual quantities causes substantial inequity to the Owner or Contractor, the applicable unit prices shall be equitably adjusted.

§ 9.2 Schedule of Values

Where the Contract is based on a stipulated sum or Guaranteed Maximum Price, the Contractor shall submit a schedule of values to the Architect before the first Application for Payment, allocating the entire Contract Sum to the various portions of the Work. The schedule of values shall be prepared in the form, and supported by the data to substantiate its accuracy, required by the Architect. This schedule, unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's Applications for Payment. Any changes to the schedule of values shall be submitted to the Architect and supported by such data to substantiate its accuracy as the Architect may require, and

unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's subsequent Applications for Payment.

§ 9.3 Applications for Payment

§ 9.3.1 At least ten days before the date established for each progress payment, the Contractor shall submit to the Architect an itemized Application for Payment prepared in accordance with the schedule of values, if required under Section 9.2, for completed portions of the Work. The application shall be notarized, if required, and supported by all data substantiating the Contractor's right to payment that the Owner or Architect require, such as copies of requisitions, and releases and waivers of liens from Subcontractors and suppliers, and shall reflect retainage if provided for in the Contract Documents.

§ 9.3.1.1 As provided in Section 7.3.9, such applications may include requests for payment on account of changes in the Work that have been properly authorized by Construction Change Directives, or by interim determinations of the Architect, but not yet included in Change Orders.

§ 9.3.1.2 Applications for Payment shall not include requests for payment for portions of the Work for which the Contractor does not intend to pay a Subcontractor or supplier, unless such Work has been performed by others whom the Contractor intends to pay.

§ 9.3.2 Unless otherwise provided in the Contract Documents, payments shall be made on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. If approved in advance by the Owner, payment may similarly be made for materials and equipment suitably stored off the site at a location agreed upon in writing. Payment for materials and equipment stored on or off the site shall be conditioned upon compliance by the Contractor with procedures satisfactory to the Owner to establish the Owner's title to such materials and equipment or otherwise protect the Owner's interest, and shall include the costs of applicable insurance, storage, and transportation to the site, for such materials and equipment stored off the site.

§ 9.3.3 The Contractor warrants that title to all Work covered by an Application for Payment will pass to the Owner no later than the time of payment. The Contractor further warrants that upon submittal of an Application for Payment all Work for which Certificates for Payment have been previously issued and payments received from the Owner shall, to the best of the Contractor's knowledge, information, and belief, be free and clear of liens, claims, security interests, or encumbrances, in favor of the Contractor, Subcontractors, suppliers, or other persons or entities that provided labor, materials, and equipment relating to the Work.

§ 9.4 Certificates for Payment

§ 9.4.1 The Architect will, within seven days after receipt of the Contractor's Application for Payment, either (1) issue to the Owner a Certificate for Payment in the full amount of the Application for Payment, with a copy to the Contractor; or (2) issue to the Owner a Certificate for Payment for such amount as the Architect determines is properly due, and notify the Contractor and Owner of the Architect's reasons for withholding certification in part as provided in Section 9.5.1; or (3) withhold certification of the entire Application for Payment, and notify the Contractor and Owner of the Architect's reason for withholding certification in whole as provided in Section 9.5.1.

§ 9.4.2 The issuance of a Certificate for Payment will constitute a representation by the Architect to the Owner, based on the Architect's evaluation of the Work and the data in the Application for Payment, that, to the best of the Architect's knowledge, information, and belief, the Work has progressed to the point indicated, the quality of the Work is in accordance with the Contract Documents, and that the Contractor is entitled to payment in the amount certified. The foregoing representations are subject to an evaluation of the Work for conformance with the Contract Documents upon Substantial Completion, to results of subsequent tests and inspections, to correction of minor deviations from the Contract Documents prior to completion, and to specific qualifications expressed by the Architect. However, the issuance of a Certificate for Payment will not be a representation that the Architect has (1) made exhaustive or continuous on-site inspections to check the quality or quantity of the Work; (2) reviewed construction means, methods, techniques, sequences, or procedures; (3) reviewed copies of requisitions received from Subcontractors and suppliers and other data requested by the Owner to substantiate the Contractor's right to payment; or (4) made examination to ascertain how or for what purpose the Contractor has used money previously paid on account of the Contract Sum.

§ 9.5 Decisions to Withhold Certification

§ 9.5.1 The Architect may withhold a Certificate for Payment in whole or in part, to the extent reasonably necessary to protect the Owner, if in the Architect's opinion the representations to the Owner required by Section 9.4.2 cannot be made. If the Architect is unable to certify payment in the amount of the Application, the Architect will notify the Contractor and Owner as provided in Section 9.4.1. If the Contractor and Architect cannot agree on a revised amount, the Architect will promptly issue a Certificate for Payment for the amount for which the Architect is able to make such representations to the Owner. The Architect may also withhold a Certificate for Payment or, because of subsequently discovered evidence, may nullify the whole or a part of a Certificate for Payment previously issued, to such extent as may be necessary in the Architect's opinion to protect the Owner from loss for which the Contractor is responsible, including loss resulting from acts and omissions described in Section 3.3.2, because of

- .1 defective Work not remedied;
- .2 third party claims filed or reasonable evidence indicating probable filing of such claims, unless security acceptable to the Owner is provided by the Contractor;
- .3 failure of the Contractor to make payments properly to Subcontractors or suppliers for labor, materials or equipment;
- .4 reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum;
- .5 damage to the Owner or a Separate Contractor;
- .6 reasonable evidence that the Work will not be completed within the Contract Time, and that the unpaid balance would not be adequate to cover actual or liquidated damages for the anticipated delay; or
- .7 repeated failure to carry out the Work in accordance with the Contract Documents.

§ 9.5.2 When either party disputes the Architect's decision regarding a Certificate for Payment under Section 9.5.1, in whole or in part, that party may submit a Claim in accordance with Article 15.

§ 9.5.3 When the reasons for withholding certification are removed, certification will be made for amounts previously withheld.

§ 9.5.4 If the Architect withholds certification for payment under Section 9.5.1.3, the Owner may, at its sole option, issue joint checks to the Contractor and to any Subcontractor or supplier to whom the Contractor failed to make payment for Work properly performed or material or equipment suitably delivered. If the Owner makes payments by joint check, the Owner shall notify the Architect and the Contractor shall reflect such payment on its next Application for Payment.

§ 9.6 Progress Payments

§ 9.6.1 After the Architect has issued a Certificate for Payment, the Owner shall make payment in the manner and within the time provided in the Contract Documents, and shall so notify the Architect.

§ 9.6.2 The Contractor shall pay each Subcontractor, no later than seven days after receipt of payment from the Owner, the amount to which the Subcontractor is entitled, reflecting percentages actually retained from payments to the Contractor on account of the Subcontractor's portion of the Work. The Contractor shall, by appropriate agreement with each Subcontractor, require each Subcontractor to make payments to Sub-subcontractors in a similar manner.

§ 9.6.3 The Architect will, on request, furnish to a Subcontractor, if practicable, information regarding percentages of completion or amounts applied for by the Contractor and action taken thereon by the Architect and Owner on account of portions of the Work done by such Subcontractor.

§ 9.6.4 The Owner has the right to request written evidence from the Contractor that the Contractor has properly paid Subcontractors and suppliers amounts paid by the Owner to the Contractor for subcontracted Work. If the Contractor fails to furnish such evidence within seven days, the Owner shall have the right to contact Subcontractors and suppliers to ascertain whether they have been properly paid. Neither the Owner nor Architect shall have an obligation to pay, or to see to the payment of money to, a Subcontractor or supplier, except as may otherwise be required by law.

§ 9.6.5 The Contractor's payments to suppliers shall be treated in a manner similar to that provided in Sections 9.6.2, 9.6.3 and 9.6.4.

§ 9.6.6 A Certificate for Payment, a progress payment, or partial or entire use or occupancy of the Project by the Owner shall not constitute acceptance of Work not in accordance with the Contract Documents.

§ 9.6.7 Unless the Contractor provides the Owner with a payment bond in the full penal sum of the Contract Sum, payments received by the Contractor for Work properly performed by Subcontractors or provided by suppliers shall be held by the Contractor for those Subcontractors or suppliers who performed Work or furnished materials, or both, under contract with the Contractor for which payment was made by the Owner. Nothing contained herein shall require money to be placed in a separate account and not commingled with money of the Contractor, create any fiduciary liability or tort liability on the part of the Contractor for breach of trust, or entitle any person or entity to an award of punitive damages against the Contractor for breach of the requirements of this provision.

§ 9.6.8 Provided the Owner has fulfilled its payment obligations under the Contract Documents, the Contractor shall defend and indemnify the Owner from all loss, liability, damage or expense, including reasonable attorney's fees and litigation expenses, arising out of any lien claim or other claim for payment by any Subcontractor or supplier of any tier. Upon receipt of notice of a lien claim or other claim for payment, the Owner shall notify the Contractor. If approved by the applicable court, when required, the Contractor may substitute a surety bond for the property against which the lien or other claim for payment has been asserted.

§ 9.7 Failure of Payment

If the Architect does not issue a Certificate for Payment, through no fault of the Contractor, within seven days after receipt of the Contractor's Application for Payment, or if the Owner does not pay the Contractor within seven days after the date established in the Contract Documents, the amount certified by the Architect or awarded by binding dispute resolution, then the Contractor may, upon seven additional days' notice to the Owner and Architect, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided for in the Contract Documents.

§ 9.8 Substantial Completion

§ 9.8.1 Substantial Completion is the stage in the progress of the Work when the Work or designated portion thereof is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use.

§ 9.8.2 When the Contractor considers that the Work, or a portion thereof which the Owner agrees to accept separately, is substantially complete, the Contractor shall prepare and submit to the Architect a comprehensive list of items to be completed or corrected prior to final payment. Failure to include an item on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents.

§ 9.8.3 Upon receipt of the Contractor's list, the Architect will make an inspection to determine whether the Work or designated portion thereof is substantially complete. If the Architect's inspection discloses any item, whether or not included on the Contractor's list, which is not sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work or designated portion thereof for its intended use, the Contractor shall, before issuance of the Certificate of Substantial Completion, complete or correct such item upon notification by the Architect. In such case, the Contractor shall then submit a request for another inspection by the Architect to determine Substantial Completion.

§ 9.8.4 When the Work or designated portion thereof is substantially complete, the Architect will prepare a Certificate of Substantial Completion that shall establish the date of Substantial Completion; establish responsibilities of the Owner and Contractor for security, maintenance, heat, utilities, damage to the Work and insurance; and fix the time within which the Contractor shall finish all items on the list accompanying the Certificate. Warranties required by the Contract Documents shall commence on the date of Substantial Completion of the Work or designated portion thereof unless otherwise provided in the Certificate of Substantial Completion.

§ 9.8.5 The Certificate of Substantial Completion shall be submitted to the Owner and Contractor for their written acceptance of responsibilities assigned to them in the Certificate. Upon such acceptance, and consent of surety if any, the Owner shall make payment of retainage applying to the Work or designated portion thereof. Such payment shall be adjusted for Work that is incomplete or not in accordance with the requirements of the Contract Documents.

§ 9.9 Partial Occupancy or Use

§ 9.9.1 The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor, provided such occupancy or use is consented to by the insurer and authorized by public authorities having jurisdiction over the Project. Such partial occupancy or use may commence whether or not the portion is substantially complete, provided the Owner and Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage, if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of warranties required by the Contract Documents. When the Contractor considers a portion substantially complete, the Contractor shall prepare and submit a list to the Architect as provided under Section 9.8.2. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld. The stage of the progress of the Work shall be determined by written agreement between the Owner and Contractor or, if no agreement is reached, by decision of the Architect.

§ 9.9.2 Immediately prior to such partial occupancy or use, the Owner, Contractor, and Architect shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work.

§ 9.9.3 Unless otherwise agreed upon, partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

§ 9.10 Final Completion and Final Payment

§ 9.10.1 Upon receipt of the Contractor's notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Architect will promptly make such inspection. When the Architect finds the Work acceptable under the Contract Documents and the Contract fully performed, the Architect will promptly issue a final Certificate for Payment stating that to the best of the Architect's knowledge, information and belief, and on the basis of the Architect's on-site visits and inspections, the Work has been completed in accordance with the Contract Documents and that the entire balance found to be due the Contractor and noted in the final Certificate is due and payable. The Architect's final Certificate for Payment will constitute a further representation that conditions listed in Section 9.10.2 as precedent to the Contractor's being entitled to final payment have been fulfilled.

§ 9.10.2 Neither final payment nor any remaining retained percentage shall become due until the Contractor submits to the Architect (1) an affidavit that payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or the Owner's property might be responsible or encumbered (less amounts withheld by Owner) have been paid or otherwise satisfied, (2) a certificate evidencing that insurance required by the Contract Documents to remain in force after final payment is currently in effect, (3) a written statement that the Contractor knows of no reason that the insurance will not be renewable to cover the period required by the Contract Documents, (4) consent of surety, if any, to final payment, (5) documentation of any special warranties, such as manufacturers' warranties or specific Subcontractor warranties, and (6) if required by the Owner, other data establishing payment or satisfaction of obligations, such as receipts and releases and waivers of liens, claims, security interests, or encumbrances arising out of the Contract, to the extent and in such form as may be designated by the Owner. If a Subcontractor refuses to furnish a release or waiver required by the Owner, the Contractor may furnish a bond satisfactory to the Owner to indemnify the Owner against such lien, claim, security interest, or encumbrance. If a lien, claim, security interest, or encumbrance remains unsatisfied after payments are made, the Contractor shall refund to the Owner all money that the Owner may be compelled to pay in discharging the lien, claim, security interest, or encumbrance, including all costs and reasonable attorneys' fees.

§ 9.10.3 If, after Substantial Completion of the Work, final completion thereof is materially delayed through no fault of the Contractor or by issuance of Change Orders affecting final completion, and the Architect so confirms, the Owner shall, upon application by the Contractor and certification by the Architect, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed, corrected, and accepted. If the remaining balance for Work not fully completed or corrected is less than retainage stipulated in the Contract Documents, and if bonds have been furnished, the written consent of the surety to payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by the Contractor to the Architect prior to certification of such payment. Such payment shall be made under terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

§ 9.10.4 The making of final payment shall constitute a waiver of Claims by the Owner except those arising from

- .1 liens, Claims, security interests, or encumbrances arising out of the Contract and unsettled;
- .2 failure of the Work to comply with the requirements of the Contract Documents;
- .3 terms of special warranties required by the Contract Documents; or
- .4 audits performed by the Owner, if permitted by the Contract Documents, after final payment.

§ 9.10.5 Acceptance of final payment by the Contractor, a Subcontractor, or a supplier, shall constitute a waiver of claims by that payee except those previously made in writing and identified by that payee as unsettled at the time of final Application for Payment.

ARTICLE 10 PROTECTION OF PERSONS AND PROPERTY

§ 10.1 Safety Precautions and Programs

The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract.

§ 10.2 Safety of Persons and Property

§ 10.2.1 The Contractor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury, or loss to

- .1 employees on the Work and other persons who may be affected thereby;
- .2 the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody, or control of the Contractor, a Subcontractor, or a Sub-subcontractor; and
- .3 other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures, and utilities not designated for removal, relocation, or replacement in the course of construction.

§ 10.2.2 The Contractor shall comply with, and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities, bearing on safety of persons or property or their protection from damage, injury, or loss.

§ 10.2.3 The Contractor shall implement, erect, and maintain, as required by existing conditions and performance of the Contract, reasonable safeguards for safety and protection, including posting danger signs and other warnings against hazards; promulgating safety regulations; and notifying the owners and users of adjacent sites and utilities of the safeguards.

§ 10.2.4 When use or storage of explosives or other hazardous materials or equipment, or unusual methods are necessary for execution of the Work, the Contractor shall exercise utmost care and carry on such activities under supervision of properly qualified personnel.

§ 10.2.5 The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property insurance required by the Contract Documents) to property referred to in Sections 10.2.1.2 and 10.2.1.3 caused in whole or in part by the Contractor, a Subcontractor, a Sub-subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable and for which the Contractor is responsible under Sections 10.2.1.2 and 10.2.1.3. The Contractor may make a Claim for the cost to remedy the damage or loss to the extent such damage or loss is attributable to acts or omissions of the Owner or Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's obligations under Section 3.18.

§ 10.2.6 The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner and Architect.

§ 10.2.7 The Contractor shall not permit any part of the construction or site to be loaded so as to cause damage or create an unsafe condition.

§ 10.2.8 Injury or Damage to Person or Property

If either party suffers injury or damage to person or property because of an act or omission of the other party, or of others for whose acts such party is legally responsible, notice of the injury or damage, whether or not insured, shall be given to the other party within a reasonable time not exceeding 21 days after discovery. The notice shall provide sufficient detail to enable the other party to investigate the matter.

§ 10.3 Hazardous Materials and Substances

§ 10.3.1 The Contractor is responsible for compliance with any requirements included in the Contract Documents regarding hazardous materials or substances. If the Contractor encounters a hazardous material or substance not addressed in the Contract Documents and if reasonable precautions will be inadequate to prevent foreseeable bodily injury or death to persons resulting from a material or substance, including but not limited to asbestos or polychlorinated biphenyl (PCB), encountered on the site by the Contractor, the Contractor shall, upon recognizing the condition, immediately stop Work in the affected area and notify the Owner and Architect of the condition.

§ 10.3.2 Upon receipt of the Contractor's notice, the Owner shall obtain the services of a licensed laboratory to verify the presence or absence of the material or substance reported by the Contractor and, in the event such material or substance is found to be present, to cause it to be rendered harmless. Unless otherwise required by the Contract Documents, the Owner shall furnish in writing to the Contractor and Architect the names and qualifications of persons or entities who are to perform tests verifying the presence or absence of the material or substance or who are to perform the task of removal or safe containment of the material or substance. The Contractor and the Architect will promptly reply to the Owner in writing stating whether or not either has reasonable objection to the persons or entities proposed by the Owner. If either the Contractor or Architect has an objection to a person or entity proposed by the Owner, the Owner shall propose another to whom the Contractor and the Architect have no reasonable objection. When the material or substance has been rendered harmless, Work in the affected area shall resume upon written agreement of the Owner and Contractor. By Change Order, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable additional costs of shutdown, delay, and start-up.

§ 10.3.3 To the fullest extent permitted by law, the Owner shall indemnify and hold harmless the Contractor, Subcontractors, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work in the affected area if in fact the material or substance presents the risk of bodily injury or death as described in Section 10.3.1 and has not been rendered harmless, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), except to the extent that such damage, loss, or expense is due to the fault or negligence of the party seeking indemnity.

§ 10.3.4 The Owner shall not be responsible under this Section 10.3 for hazardous materials or substances the Contractor brings to the site unless such materials or substances are required by the Contract Documents. The Owner shall be responsible for hazardous materials or substances required by the Contract Documents, except to the extent of the Contractor's fault or negligence in the use and handling of such materials or substances.

§ 10.3.5 The Contractor shall reimburse the Owner for the cost and expense the Owner incurs (1) for remediation of hazardous materials or substances the Contractor brings to the site and negligently handles, or (2) where the Contractor fails to perform its obligations under Section 10.3.1, except to the extent that the cost and expense are due to the Owner's fault or negligence.

§ 10.3.6 If, without negligence on the part of the Contractor, the Contractor is held liable by a government agency for the cost of remediation of a hazardous material or substance solely by reason of performing Work as required by the Contract Documents, the Owner shall reimburse the Contractor for all cost and expense thereby incurred.

§ 10.4 Emergencies

In an emergency affecting safety of persons or property, the Contractor shall act, at the Contractor's discretion, to prevent threatened damage, injury, or loss. Additional compensation or extension of time claimed by the Contractor on account of an emergency shall be determined as provided in Article 15 and Article 7.

ARTICLE 11 INSURANCE AND BONDS

§ 11.1 Contractor's Insurance and Bonds

§ 11.1.1 The Contractor shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Contractor shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located. The Owner, Architect, and Architect's consultants shall be named as additional insureds under the Contractor's commercial general liability policy or as otherwise described in the Contract Documents.

§ 11.1.2 The Contractor shall provide surety bonds of the types, for such penal sums, and subject to such terms and conditions as required by the Contract Documents. The Contractor shall purchase and maintain the required bonds from a company or companies lawfully authorized to issue surety bonds in the jurisdiction where the Project is located.

§ 11.1.3 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.

§ 11.1.4 **Notice of Cancellation or Expiration of Contractor's Required Insurance.** Within three (3) business days of the date the Contractor becomes aware of an impending or actual cancellation or expiration of any insurance required by the Contract Documents, the Contractor shall provide notice to the Owner of such impending or actual cancellation or expiration. Upon receipt of notice from the Contractor, the Owner shall, unless the lapse in coverage arises from an act or omission of the Owner, have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by the Contractor. The furnishing of notice by the Contractor shall not relieve the Contractor of any contractual obligation to provide any required coverage.

§ 11.2 Owner's Insurance

§ 11.2.1 The Owner shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Owner shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located.

§ 11.2.2 **Failure to Purchase Required Property Insurance.** If the Owner fails to purchase and maintain the required property insurance, with all of the coverages and in the amounts described in the Agreement or elsewhere in the Contract Documents, the Owner shall inform the Contractor in writing prior to commencement of the Work. Upon receipt of notice from the Owner, the Contractor may delay commencement of the Work and may obtain insurance that will protect the interests of the Contractor, Subcontractors, and Sub-Subcontractors in the Work. When the failure to provide coverage has been cured or resolved, the Contract Sum and Contract Time shall be equitably adjusted. In the event the Owner fails to procure coverage, the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent the loss to the Owner would have been covered by the insurance to have been procured by the Owner. The cost of the insurance shall be charged to the Owner by a Change Order. If the Owner does not provide written notice, and the Contractor is damaged by the failure or neglect of the Owner to purchase or maintain the required insurance, the Owner shall reimburse the Contractor for all reasonable costs and damages attributable thereto.

§ 11.2.3 **Notice of Cancellation or Expiration of Owner's Required Property Insurance.** Within three (3) business days of the date the Owner becomes aware of an impending or actual cancellation or expiration of any property insurance required by the Contract Documents, the Owner shall provide notice to the Contractor of such impending or actual cancellation or expiration. Unless the lapse in coverage arises from an act or omission of the Contractor: (1) the Contractor, upon receipt of notice from the Owner, shall have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by either the Owner or the Contractor; (2) the Contract Time and Contract Sum shall be equitably adjusted; and (3) the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent any loss to the Owner would have been covered by the insurance had it not expired or been cancelled. If the Contractor purchases replacement coverage, the cost of the insurance shall be charged to the Owner by an appropriate Change Order. The furnishing of notice by the Owner shall not relieve the Owner of any contractual obligation to provide required insurance.

§ 11.3 Waivers of Subrogation

§ 11.3.1 The Owner and Contractor waive all rights against (1) each other and any of their subcontractors, sub-subcontractors, agents, and employees, each of the other; (2) the Architect and Architect's consultants; and (3) Separate Contractors, if any, and any of their subcontractors, sub-subcontractors, agents, and employees, for damages caused by fire, or other causes of loss, to the extent those losses are covered by property insurance required by the Agreement or other property insurance applicable to the Project, except such rights as they have to proceeds of such insurance. The Owner or Contractor, as appropriate, shall require similar written waivers in favor of the individuals and entities identified above from the Architect, Architect's consultants, Separate Contractors, subcontractors, and sub-subcontractors. The policies of insurance purchased and maintained by each person or entity agreeing to waive claims pursuant to this section 11.3.1 shall not prohibit this waiver of subrogation. This waiver of subrogation shall be effective as to a person or entity (1) even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, (2) even though that person or entity did not pay the insurance premium directly or indirectly, or (3) whether or not the person or entity had an insurable interest in the damaged property.

§ 11.3.2 If during the Project construction period the Owner insures properties, real or personal or both, at or adjacent to the site by property insurance under policies separate from those insuring the Project, or if after final payment property insurance is to be provided on the completed Project through a policy or policies other than those insuring the Project during the construction period, to the extent permissible by such policies, the Owner waives all rights in accordance with the terms of Section 11.3.1 for damages caused by fire or other causes of loss covered by this separate property insurance.

§ 11.4 Loss of Use, Business Interruption, and Delay in Completion Insurance

The Owner, at the Owner's option, may purchase and maintain insurance that will protect the Owner against loss of use of the Owner's property, or the inability to conduct normal operations, due to fire or other causes of loss. The Owner waives all rights of action against the Contractor and Architect for loss of use of the Owner's property, due to fire or other hazards however caused.

§ 11.5 Adjustment and Settlement of Insured Loss

§ 11.5.1 A loss insured under the property insurance required by the Agreement shall be adjusted by the Owner as fiduciary and made payable to the Owner as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause and of Section 11.5.2. The Owner shall pay the Architect and Contractor their just shares of insurance proceeds received by the Owner, and by appropriate agreements the Architect and Contractor shall make payments to their consultants and Subcontractors in similar manner.

§ 11.5.2 Prior to settlement of an insured loss, the Owner shall notify the Contractor of the terms of the proposed settlement as well as the proposed allocation of the insurance proceeds. The Contractor shall have 14 days from receipt of notice to object to the proposed settlement or allocation of the proceeds. If the Contractor does not object, the Owner shall settle the loss and the Contractor shall be bound by the settlement and allocation. Upon receipt, the Owner shall deposit the insurance proceeds in a separate account and make the appropriate distributions. Thereafter, if no other agreement is made or the Owner does not terminate the Contract for convenience, the Owner and Contractor shall execute a Change Order for reconstruction of the damaged or destroyed Work in the amount allocated for that purpose. If the Contractor timely objects to either the terms of the proposed settlement or the allocation of the proceeds, the Owner may proceed to settle the insured loss, and any dispute between the Owner and Contractor arising out of the settlement or allocation of the proceeds shall be resolved pursuant to Article 15. Pending resolution of any dispute, the Owner may issue a Construction Change Directive for the reconstruction of the damaged or destroyed Work.

ARTICLE 12 UNCOVERING AND CORRECTION OF WORK

§ 12.1 Uncovering of Work

§ 12.1.1 If a portion of the Work is covered contrary to the Architect's request or to requirements specifically expressed in the Contract Documents, it must, if requested in writing by the Architect, be uncovered for the Architect's examination and be replaced at the Contractor's expense without change in the Contract Time.

§ 12.1.2 If a portion of the Work has been covered that the Architect has not specifically requested to examine prior to its being covered, the Architect may request to see such Work and it shall be uncovered by the Contractor. If such Work is in accordance with the Contract Documents, the Contractor shall be entitled to an equitable adjustment to

the Contract Sum and Contract Time as may be appropriate. If such Work is not in accordance with the Contract Documents, the costs of uncovering the Work, and the cost of correction, shall be at the Contractor's expense.

§ 12.2 Correction of Work

§ 12.2.1 Before Substantial Completion

The Contractor shall promptly correct Work rejected by the Architect or failing to conform to the requirements of the Contract Documents, discovered before Substantial Completion and whether or not fabricated, installed or completed. Costs of correcting such rejected Work, including additional testing and inspections, the cost of uncovering and replacement, and compensation for the Architect's services and expenses made necessary thereby, shall be at the Contractor's expense.

§ 12.2.2 After Substantial Completion

§ 12.2.2.1 In addition to the Contractor's obligations under Section 3.5, if, within one year after the date of Substantial Completion of the Work or designated portion thereof or after the date for commencement of warranties established under Section 9.9.1, or by terms of any applicable special warranty required by the Contract Documents, any of the Work is found to be not in accordance with the requirements of the Contract Documents, the Contractor shall correct it promptly after receipt of notice from the Owner to do so, unless the Owner has previously given the Contractor a written acceptance of such condition. The Owner shall give such notice promptly after discovery of the condition. During the one-year period for correction of Work, if the Owner fails to notify the Contractor and give the Contractor an opportunity to make the correction, the Owner waives the rights to require correction by the Contractor and to make a claim for breach of warranty. If the Contractor fails to correct nonconforming Work within a reasonable time during that period after receipt of notice from the Owner or Architect, the Owner may correct it in accordance with Section 2.5.

§ 12.2.2.2 The one-year period for correction of Work shall be extended with respect to portions of Work first performed after Substantial Completion by the period of time between Substantial Completion and the actual completion of that portion of the Work.

§ 12.2.2.3 The one-year period for correction of Work shall not be extended by corrective Work performed by the Contractor pursuant to this Section 12.2.

§ 12.2.3 The Contractor shall remove from the site portions of the Work that are not in accordance with the requirements of the Contract Documents and are neither corrected by the Contractor nor accepted by the Owner.

§ 12.2.4 The Contractor shall bear the cost of correcting destroyed or damaged construction of the Owner or Separate Contractors, whether completed or partially completed, caused by the Contractor's correction or removal of Work that is not in accordance with the requirements of the Contract Documents.

§ 12.2.5 Nothing contained in this Section 12.2 shall be construed to establish a period of limitation with respect to other obligations the Contractor has under the Contract Documents. Establishment of the one-year period for correction of Work as described in Section 12.2.2 relates only to the specific obligation of the Contractor to correct the Work, and has no relationship to the time within which the obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish the Contractor's liability with respect to the Contractor's obligations other than specifically to correct the Work.

§ 12.3 Acceptance of Nonconforming Work

If the Owner prefers to accept Work that is not in accordance with the requirements of the Contract Documents, the Owner may do so instead of requiring its removal and correction, in which case the Contract Sum will be reduced as appropriate and equitable. Such adjustment shall be effected whether or not final payment has been made.

ARTICLE 13 MISCELLANEOUS PROVISIONS

§ 13.1 Governing Law

The Contract shall be governed by the law of the place where the Project is located, excluding that jurisdiction's choice of law rules. If the parties have selected arbitration as the method of binding dispute resolution, the Federal Arbitration Act shall govern Section 15.4.

§ 13.2 Successors and Assigns

§ 13.2.1 The Owner and Contractor respectively bind themselves, their partners, successors, assigns, and legal representatives to covenants, agreements, and obligations contained in the Contract Documents. Except as provided in Section 13.2.2, neither party to the Contract shall assign the Contract as a whole without written consent of the other. If either party attempts to make an assignment without such consent, that party shall nevertheless remain legally responsible for all obligations under the Contract.

§ 13.2.2 The Owner may, without consent of the Contractor, assign the Contract to a lender providing construction financing for the Project, if the lender assumes the Owner's rights and obligations under the Contract Documents. The Contractor shall execute all consents reasonably required to facilitate the assignment.

§ 13.3 Rights and Remedies

§ 13.3.1 Duties and obligations imposed by the Contract Documents and rights and remedies available thereunder shall be in addition to and not a limitation of duties, obligations, rights, and remedies otherwise imposed or available by law.

§ 13.3.2 No action or failure to act by the Owner, Architect, or Contractor shall constitute a waiver of a right or duty afforded them under the Contract, nor shall such action or failure to act constitute approval of or acquiescence in a breach thereunder, except as may be specifically agreed upon in writing.

§ 13.4 Tests and Inspections

§ 13.4.1 Tests, inspections, and approvals of portions of the Work shall be made as required by the Contract Documents and by applicable laws, statutes, ordinances, codes, rules, and regulations or lawful orders of public authorities. Unless otherwise provided, the Contractor shall make arrangements for such tests, inspections, and approvals with an independent testing laboratory or entity acceptable to the Owner, or with the appropriate public authority, and shall bear all related costs of tests, inspections, and approvals. The Contractor shall give the Architect timely notice of when and where tests and inspections are to be made so that the Architect may be present for such procedures. The Owner shall bear costs of tests, inspections, or approvals that do not become requirements until after bids are received or negotiations concluded. The Owner shall directly arrange and pay for tests, inspections, or approvals where building codes or applicable laws or regulations so require.

§ 13.4.2 If the Architect, Owner, or public authorities having jurisdiction determine that portions of the Work require additional testing, inspection, or approval not included under Section 13.4.1, the Architect will, upon written authorization from the Owner, instruct the Contractor to make arrangements for such additional testing, inspection, or approval, by an entity acceptable to the Owner, and the Contractor shall give timely notice to the Architect of when and where tests and inspections are to be made so that the Architect may be present for such procedures. Such costs, except as provided in Section 13.4.3, shall be at the Owner's expense.

§ 13.4.3 If procedures for testing, inspection, or approval under Sections 13.4.1 and 13.4.2 reveal failure of the portions of the Work to comply with requirements established by the Contract Documents, all costs made necessary by such failure, including those of repeated procedures and compensation for the Architect's services and expenses, shall be at the Contractor's expense.

§ 13.4.4 Required certificates of testing, inspection, or approval shall, unless otherwise required by the Contract Documents, be secured by the Contractor and promptly delivered to the Architect.

§ 13.4.5 If the Architect is to observe tests, inspections, or approvals required by the Contract Documents, the Architect will do so promptly and, where practicable, at the normal place of testing.

§ 13.4.6 Tests or inspections conducted pursuant to the Contract Documents shall be made promptly to avoid unreasonable delay in the Work.

§ 13.5 Interest

Payments due and unpaid under the Contract Documents shall bear interest from the date payment is due at the rate the parties agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located.

ARTICLE 14 TERMINATION OR SUSPENSION OF THE CONTRACT

§ 14.1 Termination by the Contractor

§ 14.1.1 The Contractor may terminate the Contract if the Work is stopped for a period of 30 consecutive days through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, for any of the following reasons:

- .1 Issuance of an order of a court or other public authority having jurisdiction that requires all Work to be stopped;
- .2 An act of government, such as a declaration of national emergency, that requires all Work to be stopped;
- .3 Because the Architect has not issued a Certificate for Payment and has not notified the Contractor of the reason for withholding certification as provided in Section 9.4.1, or because the Owner has not made payment on a Certificate for Payment within the time stated in the Contract Documents; or
- .4 The Owner has failed to furnish to the Contractor reasonable evidence as required by Section 2.2.

§ 14.1.2 The Contractor may terminate the Contract if, through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, repeated suspensions, delays, or interruptions of the entire Work by the Owner as described in Section 14.3, constitute in the aggregate more than 100 percent of the total number of days scheduled for completion, or 120 days in any 365-day period, whichever is less.

§ 14.1.3 If one of the reasons described in Section 14.1.1 or 14.1.2 exists, the Contractor may, upon seven days' notice to the Owner and Architect, terminate the Contract and recover from the Owner payment for Work executed, as well as reasonable overhead and profit on Work not executed, and costs incurred by reason of such termination.

§ 14.1.4 If the Work is stopped for a period of 60 consecutive days through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, or their agents or employees or any other persons or entities performing portions of the Work because the Owner has repeatedly failed to fulfill the Owner's obligations under the Contract Documents with respect to matters important to the progress of the Work, the Contractor may, upon seven additional days' notice to the Owner and the Architect, terminate the Contract and recover from the Owner as provided in Section 14.1.3.

§ 14.2 Termination by the Owner for Cause

§ 14.2.1 The Owner may terminate the Contract if the Contractor

- .1 repeatedly refuses or fails to supply enough properly skilled workers or proper materials;
- .2 fails to make payment to Subcontractors or suppliers in accordance with the respective agreements between the Contractor and the Subcontractors or suppliers;
- .3 repeatedly disregards applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of a public authority; or
- .4 otherwise is guilty of substantial breach of a provision of the Contract Documents.

§ 14.2.2 When any of the reasons described in Section 14.2.1 exist, and upon certification by the Architect that sufficient cause exists to justify such action, the Owner may, without prejudice to any other rights or remedies of the Owner and after giving the Contractor and the Contractor's surety, if any, seven days' notice, terminate employment of the Contractor and may, subject to any prior rights of the surety:

- .1 Exclude the Contractor from the site and take possession of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor;
- .2 Accept assignment of subcontracts pursuant to Section 5.4; and
- .3 Finish the Work by whatever reasonable method the Owner may deem expedient. Upon written request of the Contractor, the Owner shall furnish to the Contractor a detailed accounting of the costs incurred by the Owner in finishing the Work.

§ 14.2.3 When the Owner terminates the Contract for one of the reasons stated in Section 14.2.1, the Contractor shall not be entitled to receive further payment until the Work is finished.

§ 14.2.4 If the unpaid balance of the Contract Sum exceeds costs of finishing the Work, including compensation for the Architect's services and expenses made necessary thereby, and other damages incurred by the Owner and not expressly waived, such excess shall be paid to the Contractor. If such costs and damages exceed the unpaid balance,

the Contractor shall pay the difference to the Owner. The amount to be paid to the Contractor or Owner, as the case may be, shall be certified by the Initial Decision Maker, upon application, and this obligation for payment shall survive termination of the Contract.

§ 14.3 Suspension by the Owner for Convenience

§ 14.3.1 The Owner may, without cause, order the Contractor in writing to suspend, delay or interrupt the Work, in whole or in part for such period of time as the Owner may determine.

§ 14.3.2 The Contract Sum and Contract Time shall be adjusted for increases in the cost and time caused by suspension, delay, or interruption under Section 14.3.1. Adjustment of the Contract Sum shall include profit. No adjustment shall be made to the extent

- .1 that performance is, was, or would have been, so suspended, delayed, or interrupted, by another cause for which the Contractor is responsible; or
- .2 that an equitable adjustment is made or denied under another provision of the Contract.

§ 14.4 Termination by the Owner for Convenience

§ 14.4.1 The Owner may, at any time, terminate the Contract for the Owner's convenience and without cause.

§ 14.4.2 Upon receipt of notice from the Owner of such termination for the Owner's convenience, the Contractor shall

- .1 cease operations as directed by the Owner in the notice;
- .2 take actions necessary, or that the Owner may direct, for the protection and preservation of the Work; and
- .3 except for Work directed to be performed prior to the effective date of termination stated in the notice, terminate all existing subcontracts and purchase orders and enter into no further subcontracts and purchase orders.

§ 14.4.3 In case of such termination for the Owner's convenience, the Owner shall pay the Contractor for Work properly executed; costs incurred by reason of the termination, including costs attributable to termination of Subcontracts; and the termination fee, if any, set forth in the Agreement.

ARTICLE 15 CLAIMS AND DISPUTES

§ 15.1 Claims

§ 15.1.1 Definition

A Claim is a demand or assertion by one of the parties seeking, as a matter of right, payment of money, a change in the Contract Time, or other relief with respect to the terms of the Contract. The term "Claim" also includes other disputes and matters in question between the Owner and Contractor arising out of or relating to the Contract. The responsibility to substantiate Claims shall rest with the party making the Claim. This Section 15.1.1 does not require the Owner to file a Claim in order to impose liquidated damages in accordance with the Contract Documents.

§ 15.1.2 Time Limits on Claims

The Owner and Contractor shall commence all Claims and causes of action against the other and arising out of or related to the Contract, whether in contract, tort, breach of warranty or otherwise, in accordance with the requirements of the binding dispute resolution method selected in the Agreement and within the period specified by applicable law, but in any case not more than 10 years after the date of Substantial Completion of the Work. The Owner and Contractor waive all Claims and causes of action not commenced in accordance with this Section 15.1.2.

§ 15.1.3 Notice of Claims

§ 15.1.3.1 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered prior to expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party and to the Initial Decision Maker with a copy sent to the Architect, if the Architect is not serving as the Initial Decision Maker. Claims by either party under this Section 15.1.3.1 shall be initiated within 21 days after occurrence of the event giving rise to such Claim or within 21 days after the claimant first recognizes the condition giving rise to the Claim, whichever is later.

§ 15.1.3.2 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party. In such event, no decision by the Initial Decision Maker is required.

§ 15.1.4 Continuing Contract Performance

§ 15.1.4.1 Pending final resolution of a Claim, except as otherwise agreed in writing or as provided in Section 9.7 and Article 14, the Contractor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments in accordance with the Contract Documents.

§ 15.1.4.2 The Contract Sum and Contract Time shall be adjusted in accordance with the Initial Decision Maker's decision, subject to the right of either party to proceed in accordance with this Article 15. The Architect will issue Certificates for Payment in accordance with the decision of the Initial Decision Maker.

§ 15.1.5 Claims for Additional Cost

If the Contractor wishes to make a Claim for an increase in the Contract Sum, notice as provided in Section 15.1.3 shall be given before proceeding to execute the portion of the Work that is the subject of the Claim. Prior notice is not required for Claims relating to an emergency endangering life or property arising under Section 10.4.

§ 15.1.6 Claims for Additional Time

§ 15.1.6.1 If the Contractor wishes to make a Claim for an increase in the Contract Time, notice as provided in Section 15.1.3 shall be given. The Contractor's Claim shall include an estimate of cost and of probable effect of delay on progress of the Work. In the case of a continuing delay, only one Claim is necessary.

§ 15.1.6.2 If adverse weather conditions are the basis for a Claim for additional time, such Claim shall be documented by data substantiating that weather conditions were abnormal for the period of time, could not have been reasonably anticipated, and had an adverse effect on the scheduled construction.

§ 15.1.7 Waiver of Claims for Consequential Damages

The Contractor and Owner waive Claims against each other for consequential damages arising out of or relating to this Contract. This mutual waiver includes

- .1 damages incurred by the Owner for rental expenses, for losses of use, income, profit, financing, business and reputation, and for loss of management or employee productivity or of the services of such persons; and
- .2 damages incurred by the Contractor for principal office expenses including the compensation of personnel stationed there, for losses of financing, business and reputation, and for loss of profit, except anticipated profit arising directly from the Work.

This mutual waiver is applicable, without limitation, to all consequential damages due to either party's termination in accordance with Article 14. Nothing contained in this Section 15.1.7 shall be deemed to preclude assessment of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents.

§ 15.2 Initial Decision

§ 15.2.1 Claims, excluding those where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2 or arising under Sections 10.3, 10.4, and 11.5, shall be referred to the Initial Decision Maker for initial decision. The Architect will serve as the Initial Decision Maker, unless otherwise indicated in the Agreement. Except for those Claims excluded by this Section 15.2.1, an initial decision shall be required as a condition precedent to mediation of any Claim. If an initial decision has not been rendered within 30 days after the Claim has been referred to the Initial Decision Maker, the party asserting the Claim may demand mediation and binding dispute resolution without a decision having been rendered. Unless the Initial Decision Maker and all affected parties agree, the Initial Decision Maker will not decide disputes between the Contractor and persons or entities other than the Owner.

§ 15.2.2 The Initial Decision Maker will review Claims and within ten days of the receipt of a Claim take one or more of the following actions: (1) request additional supporting data from the claimant or a response with supporting data from the other party, (2) reject the Claim in whole or in part, (3) approve the Claim, (4) suggest a compromise, or (5) advise the parties that the Initial Decision Maker is unable to resolve the Claim if the Initial Decision Maker lacks sufficient information to evaluate the merits of the Claim or if the Initial Decision Maker concludes that, in the

Initial Decision Maker's sole discretion, it would be inappropriate for the Initial Decision Maker to resolve the Claim.

§ 15.2.3 In evaluating Claims, the Initial Decision Maker may, but shall not be obligated to, consult with or seek information from either party or from persons with special knowledge or expertise who may assist the Initial Decision Maker in rendering a decision. The Initial Decision Maker may request the Owner to authorize retention of such persons at the Owner's expense.

§ 15.2.4 If the Initial Decision Maker requests a party to provide a response to a Claim or to furnish additional supporting data, such party shall respond, within ten days after receipt of the request, and shall either (1) provide a response on the requested supporting data, (2) advise the Initial Decision Maker when the response or supporting data will be furnished, or (3) advise the Initial Decision Maker that no supporting data will be furnished. Upon receipt of the response or supporting data, if any, the Initial Decision Maker will either reject or approve the Claim in whole or in part.

§ 15.2.5 The Initial Decision Maker will render an initial decision approving or rejecting the Claim, or indicating that the Initial Decision Maker is unable to resolve the Claim. This initial decision shall (1) be in writing; (2) state the reasons therefor; and (3) notify the parties and the Architect, if the Architect is not serving as the Initial Decision Maker, of any change in the Contract Sum or Contract Time or both. The initial decision shall be final and binding on the parties but subject to mediation and, if the parties fail to resolve their dispute through mediation, to binding dispute resolution.

§ 15.2.6 Either party may file for mediation of an initial decision at any time, subject to the terms of Section 15.2.6.1.

§ 15.2.6.1 Either party may, within 30 days from the date of receipt of an initial decision, demand in writing that the other party file for mediation. If such a demand is made and the party receiving the demand fails to file for mediation within 30 days after receipt thereof, then both parties waive their rights to mediate or pursue binding dispute resolution proceedings with respect to the initial decision.

§ 15.2.7 In the event of a Claim against the Contractor, the Owner may, but is not obligated to, notify the surety, if any, of the nature and amount of the Claim. If the Claim relates to a possibility of a Contractor's default, the Owner may, but is not obligated to, notify the surety and request the surety's assistance in resolving the controversy.

§ 15.2.8 If a Claim relates to or is the subject of a mechanic's lien, the party asserting such Claim may proceed in accordance with applicable law to comply with the lien notice or filing deadlines.

§ 15.3 Mediation

§ 15.3.1 Claims, disputes, or other matters in controversy arising out of or related to the Contract, except those waived as provided for in Sections 9.10.4, 9.10.5, and 15.1.7, shall be subject to mediation as a condition precedent to binding dispute resolution.

§ 15.3.2 The parties shall endeavor to resolve their Claims by mediation which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Mediation Procedures in effect on the date of the Agreement. A request for mediation shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the mediation. The request may be made concurrently with the filing of binding dispute resolution proceedings but, in such event, mediation shall proceed in advance of binding dispute resolution proceedings, which shall be stayed pending mediation for a period of 60 days from the date of filing, unless stayed for a longer period by agreement of the parties or court order. If an arbitration is stayed pursuant to this Section 15.3.2, the parties may nonetheless proceed to the selection of the arbitrator(s) and agree upon a schedule for later proceedings.

§ 15.3.3 Either party may, within 30 days from the date that mediation has been concluded without resolution of the dispute or 60 days after mediation has been demanded without resolution of the dispute, demand in writing that the other party file for binding dispute resolution. If such a demand is made and the party receiving the demand fails to file for binding dispute resolution within 60 days after receipt thereof, then both parties waive their rights to binding dispute resolution proceedings with respect to the initial decision.

§ 15.3.4 The parties shall share the mediator's fee and any filing fees equally. The mediation shall be held in the place where the Project is located, unless another location is mutually agreed upon. Agreements reached in mediation shall be enforceable as settlement agreements in any court having jurisdiction thereof.

§ 15.4 Arbitration

§ 15.4.1 If the parties have selected arbitration as the method for binding dispute resolution in the Agreement, any Claim subject to, but not resolved by, mediation shall be subject to arbitration which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Arbitration Rules in effect on the date of the Agreement. The Arbitration shall be conducted in the place where the Project is located, unless another location is mutually agreed upon. A demand for arbitration shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the arbitration. The party filing a notice of demand for arbitration must assert in the demand all Claims then known to that party on which arbitration is permitted to be demanded.

§ 15.4.1.1 A demand for arbitration shall be made no earlier than concurrently with the filing of a request for mediation, but in no event shall it be made after the date when the institution of legal or equitable proceedings based on the Claim would be barred by the applicable statute of limitations. For statute of limitations purposes, receipt of a written demand for arbitration by the person or entity administering the arbitration shall constitute the institution of legal or equitable proceedings based on the Claim.

§ 15.4.2 The award rendered by the arbitrator or arbitrators shall be final, and judgment may be entered upon it in accordance with applicable law in any court having jurisdiction thereof.

§ 15.4.3 The foregoing agreement to arbitrate and other agreements to arbitrate with an additional person or entity duly consented to by parties to the Agreement, shall be specifically enforceable under applicable law in any court having jurisdiction thereof.

§ 15.4.4 Consolidation or Joinder

§ 15.4.4.1 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may consolidate an arbitration conducted under this Agreement with any other arbitration to which it is a party provided that (1) the arbitration agreement governing the other arbitration permits consolidation, (2) the arbitrations to be consolidated substantially involve common questions of law or fact, and (3) the arbitrations employ materially similar procedural rules and methods for selecting arbitrator(s).

§ 15.4.4.2 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may include by joinder persons or entities substantially involved in a common question of law or fact whose presence is required if complete relief is to be accorded in arbitration, provided that the party sought to be joined consents in writing to such joinder. Consent to arbitration involving an additional person or entity shall not constitute consent to arbitration of any claim, dispute or other matter in question not described in the written consent.

§ 15.4.4.3 The Owner and Contractor grant to any person or entity made a party to an arbitration conducted under this Section 15.4, whether by joinder or consolidation, the same rights of joinder and consolidation as those of the Owner and Contractor under this Agreement.

Additions and Deletions Report for AIA® Document A201™ – 2017

This Additions and Deletions Report, as defined on page 1 of the associated document, reproduces below all text the author has added to the standard form AIA document in order to complete it, as well as any text the author may have added to or deleted from the original AIA text. Added text is shown underlined. Deleted text is indicated with a horizontal line through the original AIA text.

Note: This Additions and Deletions Report is provided for information purposes only and is not incorporated into or constitute any part of the associated AIA document. This Additions and Deletions Report and its associated document were generated simultaneously by AIA software at 15:44:45 ET on 05/31/2019.

[Faint, illegible text, likely a watermark or bleed-through from the reverse side of the page.]

Certification of Document's Authenticity

AIA® Document D401™ – 2003

I, , hereby certify, to the best of my knowledge, information and belief, that I created the attached final document simultaneously with its associated Additions and Deletions Report and this certification at 15:44:45 ET on 05/31/2019 under Order No. 1840604654 from AIA Contract Documents software and that in preparing the attached final document I made no changes to the original text of AIA® Document A201™ - 2017, General Conditions of the Contract for Construction, as published by the AIA in its software, other than those additions and deletions shown in the associated Additions and Deletions Report.

(Signed)

(Title)

(Dated)

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 00 73 13: SUPPLEMENTARY GENERAL CONDITIONS

PART 1 GENERAL

1.1 DESCRIPTION

- A. Copy of the Supplementary General Conditions is bound herein.

PART 2 PRODUCTS

NOT USED

PART 3 EXECUTION

NOT USED

END OF SECTION

SECTION 00 73 13: SUPPLEMENTARY GENERAL CONDITIONS

The following supplementary conditions modify "General Conditions of the Contract for Construction, AIA Document A201, 2017 Edition. When a portion of the General Conditions is modified or deleted by these Supplementary Conditions, the unaltered portions of the General Conditions shall remain in effect.

ARTICLE 1 - GENERAL PROVISIONS

1.1 BASIC DEFINITIONS

Add the following to the end of subparagraph 1.1.1 The Contract Documents:

"The Contract Documents executed in accordance with subparagraph 1.5.1 shall prevail in case of an inconsistency with subsequent versions made through manipulable electronic operations involving computers."

Add the following to the General Conditions 1.1 Basic Definitions:

- 1.1.9 The words - 'as directed,' 'as permitted,' 'as required,' or words of like effect, shall mean that the direction, permission or requirement of the Engineer is intended; and similarly, the words 'approved,' 'acceptable,' 'satisfactory,' or words of like import, shall mean approved by, or acceptable or satisfactory to the Engineer unless otherwise provided herein. The words 'necessary', 'suitable', 'equal', or words of the like import, shall mean necessary or equal in the opinion of the Engineer.

1.2 CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

- 1.2.1 At the end of the last sentence in last line delete "indicated" and insert "intended".

Add the following subparagraphs:

- 1.2.4 "Whenever a material, article or piece of equipment is referred to in the singular number in the Contract Documents, it shall be the same as referring to it in the plural. As manufactured, such materials, articles, or pieces of equipment shall be provided as required to complete the Work."
- 1.2.5 "Should the Drawings, Specifications or schedules disagree in themselves or with either or both of the others, the better quality or greater quantity of work or materials shall be estimated upon and unless otherwise directed in writing by the Engineer shall be performed and provided."
- 1.2.6 "In case of disagreement, discrepancies or contradiction between any parts of the Contract Documents or within any part of the Contract Documents, only the Engineer may interpret the intent and requirements of the Documents and decision shall be final and no additional cost will be allowed in the account if the matter is brought to the Engineer attention after 7 days prior to the receipt of the Bids, the matter will be clarified by Bulletin Addenda."

- 1.2.7 "Where documents duplicate the same Work or materials under more than one contract or subcontract, such duplication shall be settled by the Engineer in writing upon request of a Contractor concerned BEFORE proposals are submitted. Any such duplications which may exist in Documents after proposals are submitted will be interpreted by the Engineer as having duplicate values in the several contract or subcontracts and proper credit to the Owner, therefore shall be made by the Contractors as the Engineer shall designate."
- 1.2.8 "Where reference is made to a text, standard, federal specification, manufacturer's directions, or to other publication, the latest publication published prior to the date of issuance of the Drawings shall apply, unless identified in the specification by a specific publication date."
- 1.2.9 "Locations, sizes, and depth of existing services (i.e., manholes, utilities, etc.) as indicated are based on records made available by the utility companies and field surveys and/or the authorities having jurisdiction. Under the work of each applicable section, examine the premises and verify visible, existing conditions prior to proposal submission and the starting of work."
- 1.2.10 "Drawing indication of items are generally diagrammatic. Connection and anchorage of materials, interconnection of equipment and accessories necessary to any system operation not otherwise detailed or specified shall be selected under the work of each section, subject to Engineer's approval, to suit the requirements of the items."
- 1.2.11 "Adhere to dimensions which may differ from scale measurements. In the absence of dimensions, or in case of doubt as to the proper measurement, consult the Engineer. Actual field dimensions where applicable shall be verified in the field prior to proceeding."
- 1.2.12 "Wherever in the Specifications there appears a reference to a "contractor" or the "Subcontractor", or a reference to a Contractor, installer or supplier of a particular trade, or for a particular type of Work, such reference, regardless of the language thereof, shall be deemed a reference to the Contractor. It shall not be construed as relieving the Contractor from the duty to perform all of the Work and other obligations provided for under this Contract."
- 1.2.13 "Sections of Division 01 - Common Work Results" govern by execution of the work of all sections of the specifications.

ARTICLE 2 - OWNER

2.3 INFORMATION AND SERVICES REQUIRED OF THE OWNER

Add the following after subparagraph 2.3.1

"The Contractor shall verify the location of all utilities before starting work, which shall include contacting "Miss Utility of Delmarva" and local utility companies, 1-800-441-

8355."

Delete subparagraph 2.3.6 and substitute the following:

- 2.3.6 The Contractor will be furnished, free of charge three (3) copies of Contract Drawings and Project Manuals. Additional sets will be furnished at the cost of reproduction, postage, and handling.

ARTICLE 3 - CONTRACTOR

3.5 WARRANTY

Add the following:

- 3.5.3 The warranty provided in paragraph 3.5 shall be concurrent with and shall not be limited of any other warranty required by the Contract Documents. The Contractor shall repair or replace those products found not to be in compliance with the warranty terms during the period of two (2) years after the date of substantial completion.

3.7 PERMITS, FEES, NOTICES, AND COMPLIANCE WITH LAWS

Add the following:

- 3.7.1.1. " The Owner shall secure and pay for the building permit. The Contractor shall secure and pay for all other permits including but not limited to HVAC and electrical permits. Costs of all permits shall be included in the Base Bid."

3.9 SUPERINTENDENT

After subparagraph 3.9.3 add the following:

- 3.9.4 "The Superintendent shall be satisfactory to the Engineer and Owner and upon request shall furnish them within seven (7) days his/her qualifications to supervise the project. The Superintendent shall not be changed except with the consent of the Owner, unless he proves to be unsatisfactory to the contractor and ceases to be in his employment."

3.13 USE OF SITE

Add the following:

- 3.13.1 The Contractor shall coordinate phasing of the project with the Owner to allow continuous use of the building and site during the construction period. Final phasing plans to be developed by the Contractor, are subject to approval by the Engineer/Owner.

Add the following:

- 3.13.2 The Contractor shall be responsible for the security of all parts of the work not accepted by the Owner, until such time as the Owner accepts said parts of the

work.

3.15 CLEANING UP

Add the following to subparagraph 3.15.1:

- 3.15.1 The Contractor shall, on a daily basis, police and clean the site and surrounding areas of the project of his materials, rubbish, tools, construction equipment, machinery or any materials to be stored thereon, either temporarily or permanently.

ARTICLE 7 - CHANGES IN THE WORK

7.1 GENERAL

Add the following subparagraph 7.1.4:

- 7.1.4 "The allowance for the combined overhead and profit included in the total cost to the Owner for changes in the work shall be based on the following schedule:

1. For the Contractor, for Work performed by the Contractor's own forces, the combined overhead and profit shall be based on the following schedule:

<u>Value of Work</u>	<u>Combined Overhead & Profit</u>
\$ 0 - \$ 1,000	15 percent
\$ 1,001 - \$ 5,000	15 percent
\$ 5,001 - \$10,000	15 percent
\$10,001 - \$25,000	12 percent

2. For the Contractor, for Work performed by the Contractor's Subcontractor, the overhead and profit allowance shall be 8 (eight) percent of the amount due the Subcontractor.
3. For each Subcontractor involved, for Work performed by that Subcontractor's own forces, the combined overhead and profit allowance shall be based on the same schedule indicated in 7.1.4.
4. Cost to which overhead and profit is to be applied shall be determined in accordance with Subparagraph 7.1.4.
5. In order to facilitate checking quotations for extras or credits, all proposals, except those so minor that their propriety can be seen by inspection, shall be accompanied by a complete itemization of costs, including labor, materials and Subcontractors. Labor and materials shall be itemized in the manner described above. Where major cost items are Subcontractors, they shall be itemized also. In no case will a change be approved without such itemization."

6. When preparing a Construction Change Directive, please use AIA G714 Construction Change Directive (Form AIA G714 is enclosed at end of Division 01, Section *Contract Modification Procedures*).

ARTICLE 8- TIME

8.2 PROGRESS AND COMPLETION

Add the following Subparagraph to 8.2

- 8.2.4 "Should the progress of the Work be delayed by fault, neglect, act, or omission of the Contractor or by person or firm employed by him, the Contractor shall, at his own cost and expense, work such overtime as may be necessary to make up for time lost and to avoid delay in completion of the Work. If, in the opinion of the Engineer and Owner, the progress of the Work is unsatisfactory, overtime Work will be demanded and the Contractor shall institute overtime Work to meet the Construction Schedule at no additional cost to the Owner."

ARTICLE 9 - PAYMENTS AND COMPLETION

9.2 SCHEDULE OF VALUES

Add the following subparagraph to 9.2

- 9.2.1 The Contractor's Schedule of Values data shall be submitted within fourteen (14) days after the award of Contract.

9.3 APPLICATIONS FOR PAYMENT

After subparagraph 9.3.3., add the following:

- 9.3.4 "On or about the thirtieth (30th) day after receipt of the Contractor's monthly request for payment from the Engineer, the Owner shall make payment on account of the contract as follows: Ninety-five (95%) of the value of the work completed up to the first (1st) day of that month, based upon the Contractor's estimate of labor and materials or equipment delivered and suitably stored at the site thereof up to the first (1st) day of that month, as approved by the Project Engineer and the Owner's Representative less the aggregate of any previous payments."
- 9.3.5 "Each request for payment shall be prepared on AIA Documents G702 and G703, 1992 edition, by the Contractor (copy enclosed). Present the original and three (3) copies (total of four) for joint review and action by the Engineer. The Engineer will deliver the original and two (2) copies to the Owner for processing. Owner will process payment upon approval by The Indian River School District. Contractor to allow up to thirty (30) days after the The Indian River School District approval for issuance of payment." (A copy of G702 and G703 are enclosed at the end of Division 01, Section *Payment Procedures*.)

- 9.3.6 "At the time the General contractor is preparing each monthly requisition, it will be required that, upon completion of his rough pencil draft covering payment request, and prior to preparation the final draft, the rough draft will be reviewed by the Engineer and the General Contractor. Agreement shall be reached among these prior to the final draft of the requisition being forwarded to the Engineer for subsequent transmittal to the Owner for payment. It shall carry the notarized signature of the General Contractor and the Signature of the Engineer. Notarization is required by a notary public commissioned in the State of Maryland."
- 9.3.7 "When the "Application for Payment" includes material or equipment stored off-site, the application shall be accompanied with a certified statement including:
- a) Description of item.
 - b) Bills of sale.
 - c) Location of storage and security thereof.
 - d) Indication that the item is currently covered by all contractual requirements, including Liability and Fire Insurance made out in the name of the Owner.
 - e) Indication that the material or equipment or any part thereof will not be installed in any other project construction other than work under this contract.
 - f) All items must be clearly marked, labeled or tagged for identification.
 - g) Available to the Owner and Engineer for inspection."
- 9.3.8 "When the "Application for Payment" includes materials or equipment delivered and suitably stored at the site but not incorporated in the work, the Engineer may require the Contractor to submit bills of sale to establish the Owner's title to such material and adequately protect the Owner's interest. Payments for stored materials should not exceed seventy-five (75%) percent of actual value."
- 9.3.9 "All requisitions shall have Contractor's Certification on the Application for Payment form modified to read, "I certify that the above is a true statement of the status of the work and of the accounts; that work and material conform with the Contract and duly authorized charges; that all just and lawful bills against the undersigned and his Subcontractors for labor, materials and equipment required by the Contract have been paid in full through prior certificates." This certification is required to be duly notarized."
- 9.3.10 "When the Engineer and Owner agree that the project is substantially complete, is on schedule and it appears that there are not complicating problems in completing the job, the retainage may be reduced to three percent (3%) at the Owner's discretion."
- 9.3.11 "The Owner will require a release of liens from each Subcontractor and supplier covering work for which each progress payment is made."
- 9.3.12 "Upon request, when the Engineer and Owner agree that the building is ready for final inspection (preparation of the final punch list), and at the Owner's discretion, retainage may be further reduced or adjusted to the value of the remaining work, whichever is greater, if the project retainage has not already

been reduced."

9.10 FINAL COMPLETION AND FINAL PAYMENT

After paragraph 9.10.5, add the following:

- 9.10.6 "The final payment to the Contractor does not become due until all requirements covered under Division 01, Project Closeout, have been certified by the Engineer."
- 9.10.7 "Release of liens shall be required of the Contractor, each Subcontractor and each material supplier prior to the final payment of any part of the retained percentage becoming due. Execute and forward with all releases of liens on the "Contractor's Affidavit of Release of Liens and Payment of Debts and Claims, AIA Form G-706, in duplicate. Forward with release of liens, two copies of AIA Form G-707, "Consent of Surety Company to Final Payment' properly executed and attested." (Forms AIA Form G-706 and G-707 are enclosed at the end of Division 01, Section *Payment Procedures*.)
- 9.10.8 "The Contractor's guarantee responsibility period commences upon the date of issuance of the Engineer's Certificate of Substantial Completion."
- 9.10.9 "The Owner shall deduct from the General Contractor's contract all hourly billings made by the Engineer for services required after the date of Substantial Completion to Determine Final Completion other than for two on-site punch list reviews."
- 9.10.10 "The final accounting of any unused allowances shall be documented in a change order prior to final payment."

ARTICLE 10 - PROTECTION OF PERSONS AND PROPERTY

10.2 SAFETY OF PERSONS AND PROPERTY

Add the following to subparagraph 10.2.6:

"This person, or approved alternate person, shall be on-site at all times while personnel for whom they are responsible are on-site. This person will be fully responsible for implementing and enforcing a program amongst his company's employees, that ensure their safety and the safety of other affected by their work, and that is in full compliance with the governing agencies including the Occupational Safety and Health Administration."

ARTICLE 11 -INSURANCE AND BONDS

After paragraph 11.1.3 add the following:

- 11.1.3.1 The Contractor shall obtain and continue in force, during the term of the contract, all insurance specified below. Each insurance policy shall not be canceled or changed without sixty (60) days' prior written notice by registered mail, given by

the insurance carrier to The Indian River School District. The Contractor shall deposit with The Indian River School District certificates evidencing the insurance it is to provide as follows:

.1 Contractor's Contractual Liability Insurance, Minimum coverage to be:

Bodily Injury	\$ 500,000	for each person
	\$1,000,000	for each occurrence
	\$1,000,000	aggregate

Property Damage	\$ 500,000	for each occurrence
	\$1,000,000	aggregate

.2 Contractor's Protective Liability Insurance, Minimum coverage to be:

Bodily Injury	\$ 500,000	for each person
	\$1,000,000	for each occurrence
	\$1,000,000	aggregate

Property Damage	\$ 500,000	for each occurrence
	\$ 500,000	aggregate

.3 Automotive Liability Insurance, Minimum coverage to be:

Bodily Injury	\$1,000,000	for each person
	\$1,000,000	for each occurrence
Property Damage	\$ 500,000	per accident

.4 Builder's Risk Insurance for the value of the project.

11.1.3.2 The Contractor shall cause the aforesaid insurance policies to be duly and properly endorsed by insurance underwriters as follows:

- .1 To provide that The Indian River School District is endorsed as an additional insured to the Contractor on liability coverage for work performed by the Contractor.
- .2 To provide that said insurance shall be primary in all instances with respect to work performed by the Contractor for The Indian River School District.
- .3 To provide contractual liability coverage for liability assumed under the terms of the contract.
- .4 To provide sixty (60) days' prior written notice of cancellation or change in coverage.

11.1.3.3 A copy of the Performance Bond and Payment Bond are enclosed in Section 00 61 13.13, "Performance Bond" and Section 00 61 13.16, "Payment Bond".

- 11.1.3.4 "The Contractor shall furnish bonds covering faithful performance of the Contract and payment of obligations arising thereunder. Bonds may be obtained through the Contractors usual source and the cost thereof shall be included in the Contract Sum. The amount of each bond shall be equal to 100 percent of the Contract Sum."
- 11.1.3.5 "The Contractor shall deliver the required bonds to the Owner concurrently with date the Agreement is entered into, or if the Work is to be commenced prior thereto in response to a letter of intent, the Contractor shall, prior to the commencement of the Work, submit evidence satisfactory to the Owner that such bonds will be furnished."
- 11.1.3.36 "The Contractor shall require the attorney-in-fact, who executes the required bonds on behalf of the surety, to affix a certified and current copy of the power of attorney to each of the bonds."

ARTICLE 15 - CLAIMS AND DISPUTES

15.1.6 Claims for Additional Time

At the end of subparagraph 15.1.6.2 add the following:

"In no case shall any weather claims for contract time extension be honored and neither shall they be construed to add changes for Contractor's overhead and project administration. Approved contract time extension for weather, based upon National Weather Service data for extreme weather beyond a five (5) year normal, will be acknowledged and may be accounted for in reducing liquidated damages only."

15.3 MEDIATION

Delete Article 15.3 MEDIATION in its entirety.

15.4 ARBITRATION

Delete Article 15.4 ARBITRATION in its entirety.

Add the following ARTICLE 16 - LIQUIDATED DAMAGES:

ARTICLE 16 - LIQUIDATED DAMAGES

- 16.1 "It is expressly understood and agreed by and between the Contractor and the Owner that the Contract time stipulated in the bid form is a reasonable time for completion of the work, taking into consideration the average climatic range and the usual conditions prevailing in the locality of the project. Time is an essential element of the contract and it is important that the work be vigorously prosecuted and conform to the scheduled start

and finish dates of the Construction Documents."

- 16.2 "The Contractor agrees that he can and will substantially complete the total projects work in accordance with the Contract Documents within the stated Contract Time."
- 16.3 "The Owner and Contractor agree that due to the uniqueness of this contract and the fact that the Owner is a private agency and the relevant factors, damages resulting from failure of the Contractor to perform the contract within the time specified therefore will result in damages to the Owner which shall be difficult, if not impossible, to ascertain; therefore, the provision for damages herein specified shall be applied in the event of such a default. The Owner and the Contractor, both of whom are, by their own admissions, sophisticated business entities with prior experience in dealing with construction contracts, stipulate that damages shall be the sum of \$300.00 for each day that the work shall remain uncompleted beyond the time(s) specified elsewhere in the contract, provided, however, that due account shall be taken of any adjustment of specified completion time(s) for completion of work as granted by approved change orders."
- 16.4 "The Contractor, by the execution of the contract document, does hereby irrevocably constitute, designate and appoint the Owner to be his agent for the limited but express purpose of deducting on a daily basis the liquidated damages as above determined from the balance of the contract funds in the hands of the Owner and due to the Contractor, and the failure of the Owner to deduct such sum for any day or any combination of days, whether consecutive or not, shall not operate as a waiver of such liquidated damages for that period, and such damages for such day or days shall be cumulative and may be subsequently deducted by the Owner from such sums as may be due the Contractor, but work performed. In the event that the amounts due the Contractor are less than the amount of such damages, the Contractor, shall be liable to the Owner for the difference."
- 16.5 "The power granted by the Contractor to the Owner above is a power coupled with an interest and is irrevocable."

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

WAGE RATE REQUIREMENTS AND WAGE RATE DETERMINATION SCHEDULES

Attached herein are the State of Delaware Wage Rate Requirements and the Davis-Bacon Act Wage Rates, which shall both apply to this project. For each trade on the project, the higher of the two wage requirements shall prevail.

THIS PAGE LEFT INTENTIONALLY BLANK



State of Delaware
Department of labor
Office of Construction Industry Enforcement
655 South Bay Road
Suite 2h
Dover, DE 19901

Via Electronic and Regular Mail

July 30, 2025

Mr. R. Adam Kegan
Gipe Associates, Inc.
8719 Brooks Drive
Easton, MD 21601

Re: IRD-25036 GW CARVER ACADEMY AND SELBYVILLE HVAC REPLACEMENT, Sussex County, DE

Dear Mr. Kegan:

I am responding to your request for a category determination for the IRD-25036 GW CARVER ACADEMY AND SELBYVILLE HVAC REPLACEMENT, which is a state funded construction project located in Sussex County, DE. The work consists of replacement of existing cooling towers, closed circuit evaporate fluid coolers and pumps. You estimate the total cost of construction for this project to be \$1,999,243.00.

Based upon the information you provided the Department of Labor has determined that this project is a Building Construction project.

Delaware's Prevailing Wage Regulations provide that the rates applicable to a project are the rates in effect on the date of publication of the specifications for that project. I have enclosed a certified copy of the March 14, 2025, prevailing wage rates for Building Construction to be included in your bid specification. However, please be advised that, in the event that a contract for a project is not executed within one hundred and twenty (120) days from the earliest date the specifications were published, the rates in effect at the time of the execution of the contract shall be the applicable rates for the project.

This determination is directed solely to the parties identified herein. It is based on the unique facts relevant to this matter. It does not constitute precedent and should not be cited as such by future parties.


Pursuant to 19 Del. Chapter 36, all contractors must obtain their Contractor Registration Certificate prior to performing construction services or maintenance work throughout Delaware. Contractors can submit an application by visiting the Delaware One Stop https://onestop.delaware.gov/Operate_Contractors.

Additionally, effective January 1, 2025, SSI for SB307 amends Delaware's Prevailing Law 29 Del.C.6960(b) now requires these applicable prevailing wage rates to be paid to all workers who perform custom fabrication work regardless of where the work is performed. For further information regarding custom fabrication see 29 Del.C.6902(8).

Lastly, please see the enclosed debarment list. Entities/individuals listed shall not be permitted to bid on, be awarded or work on Delaware State funded construction projects, in the timeframe specified, as provided for under 29 Del.C.6960 or other applicable State statutes.

If you have any questions or I can provide any additional assistance, please do not hesitate to contact me at: 302-430-7717

Sincerely,

A handwritten signature in black ink, appearing to read "Keith Tanis". The signature is fluid and cursive, with the first name "Keith" and last name "Tanis" clearly distinguishable.

KEITH TANIS
KEITH.TANIS@DELAWARE.GOV

Enclosures

STATE OF DELAWARE
DEPARTMENT OF LABOR
DIVISION OF INDUSTRIAL AFFAIRS
OFFICE OF LABOR LAW ENFORCEMENT
PHONE: (302) 318-2769

Mailing Address:
252 Chapman Road
Suite 210
Newark, DE 19702

Located at:
252 Chapman Road
Suite 210
Newark, DE 19702

PREVAILING WAGES FOR BUILDING CONSTRUCTION EFFECTIVE MARCH 14, 2025

CLASSIFICATION	NEW CASTLE	KENT	SUSSEX
ASBESTOS WORKERS	29.89	36.79	53.56
BOILERMAKERS	89.46	45.39	66.72
BRICKLAYERS	66.79	66.79	66.79
CARPENTERS	62.56	62.56	50.80
CEMENT FINISHERS	94.36	67.11	52.04
ELECTRICAL LINE WORKERS	59.42	50.96	38.85
ELECTRICIANS	83.92	83.92	83.92
ELEVATOR CONSTRUCTORS	117.63	84.30	100.06
GLAZIERS	85.50	85.50	74.04
INSULATORS	69.12	69.12	69.12
IRON WORKERS	77.73	77.73	77.73
LABORERS	57.65	57.65	57.65
MILLWRIGHTS	88.35	88.35	70.97
PAINTERS	59.63	59.63	59.63
PILEDRIERS	91.12	51.44	41.60
PLASTERERS	39.01	39.01	28.91
PLUMBERS/PIPEFITTERS/STEAMFITTERS	79.55	82.95	73.71
POWER EQUIPMENT OPERATORS	83.29	83.29	83.29
ROOFERS-COMPOSITION	32.40	30.53	32.76
ROOFERS-SHINGLE/SLATE/TILE	24.03	28.59	22.47
SHEET METAL WORKERS	86.84	86.84	86.84
SOFT FLOOR LAYERS	61.68	61.68	47.74
SPRINKLER FITTERS	73.13	73.13	73.13
TERRAZZO/MARBLE/TILE FNRS	70.79	70.79	81.89
TERRAZZO/MARBLE/TILE STRS	78.73	78.73	90.82
TRUCK DRIVERS	86.88	35.86	27.91

CERTIFIED: 7/30/2025

BY: [Signature] / For Fran Chudzik
ADMINISTRATOR, OFFICE OF LABOR LAW ENFORCEMENT

NOTE: THESE RATES ARE PROMULGATED AND ENFORCED PURSUANT TO THE PREVAILING WAGE REGULATIONS ADOPTED BY THE DEPARTMENT OF LABOR ON APRIL 3, 1992.

CLASSIFICATIONS OF WORKERS ARE DETERMINED BY THE DEPARTMENT OF LABOR. FOR ASSISTANCE IN CLASSIFYING WORKERS, OR FOR A COPY OF THE REGULATIONS OR CLASSIFICATIONS, PHONE (302) 318-2769.

NON-REGISTERED APPRENTICES MUST BE PAID THE MECHANIC'S RATE.

PROJECT: IRD-25036 GW CARVER ACADEMY AND SELBYVILLE HVAC REPLACEMENT, S



PREVAILING WAGE DEBARMENT LIST

The following contractors have been debarred for violations of the prevailing wage law 29Del.C. §6960 or other applicable State statutes.

Therefore, no public construction contract in this State shall be bid on, awarded to, or received by contractors and individuals on this list for a period of (3) three years from the date of the judgment or as deemed by a court of competent jurisdiction.

Contractor	Address	Date of Debarment
Mullen Brothers, Inc. and Daniel Mullen, individually	3375 Garnett Road, Boothwyn, PA 19060	Indefinite/ Civil Contempt
State Contractors Corporation, and Jose Oscar Rivera, individually	13004 Hathaway Drive Silver Spring, MD 20906	Indefinite/ 19 <u>Del.C. 2374(f)</u>
Green Granite and Jason Green, individually	604 Heatherbrooke Court Avondale, PA 19311	Indefinite/ Civil Contempt
Pro Image Landscaping, Inc. and Owner(s) individually	23 Commerce Street Wilmington, DE 19801 and/or 2 Cameo Road Claymont, DE 19703	Indefinite/19 <u>Del.C. §108 & 10 Del.C. 542(c)</u>
Liberty Mechanical, LLC and Owner(s), individually	2032 Duncan Road Wilmington, DE 19801	Indefinite/ 19 <u>Del.C. 2374(f)</u>
Integrated Mechanical and Fire Systems Inc. and Allison Sheldon, individually	4601 Governor Printz Boulevard Wilmington, DE 19809	Indefinite/19 <u>Del.C. §108 & 10 Del.C. 542(c)</u>
ACH 1, INC.	873 Salem Church Road Newark, DE 19702	Indefinite/19 <u>Del.C.6960</u>

Updated: July 6, 2022

GENERAL REQUIREMENTS

TABLE OF ARTICLES

1. GENERAL PROVISIONS
2. OWNER
3. CONTRACTOR
4. ADMINISTRATION OF THE CONTRACT
5. SUBCONTRACTORS
6. CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS
7. CHANGES IN THE WORK
8. TIME
9. PAYMENTS AND COMPLETION
10. PROTECTION OF PERSONS AND PROPERTY
11. INSURANCE AND BONDS
12. UNCOVERING AND CORRECTION OF WORK
13. MISCELLANEOUS PROVISIONS
14. TERMINATION OR SUSPENSION OF THE CONTRACT

ARTICLE 1: GENERAL

1.1 CONTRACT DOCUMENTS

1.1.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary and what is required by one shall be as binding as if required by all. Performance by the Contractor shall be required to an extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the intended results.

1.1.2 Work including material purchases shall not begin until the Contractor is in receipt of a bonafide State of Delaware Purchase Order. Any work performed or material purchases prior to the issuance of the Purchase Order is done at the Contractor's own risk and cost.

1.2 EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS

1.2.1 For Public Works Projects financed in whole or in part by state appropriation the Contractor agrees that during the performance of this contract:

1. The Contractor will not discriminate against any employee or applicant for employment because of race, creed, sex, color, sexual orientation, gender identity or national origin. The Contractor will take positive steps to ensure that applicants are employed and that employees are treated during employment without regard to their race, creed, sex, color, sexual orientation, gender identity or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.
2. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, sex, color, sexual orientation, gender identity or national origin."

ARTICLE 2: OWNER

(NO ADDITIONAL GENERAL REQUIREMENTS – SEE SUPPLEMENTARY GENERAL CONDITIONS)

ARTICLE 3: CONTRACTOR

3.1 Schedule of Values: The successful Bidder shall within twenty (20) days after receiving notice to proceed with the work, furnish to the Owner a complete schedule of values on the various items comprising the work.

- 3.2 Subcontracts: Upon approval of Subcontractors, the Contractor shall award their Subcontracts as soon as possible after the signing of their own contract and see that all material, their own and those of their Subcontractors, are promptly ordered so that the work will not be delayed by failure of materials to arrive on time.
- 3.3 Before commencing any work or construction, the General Contractor is to consult with the Owner as to matters in connection with access to the site and the allocation of Ground Areas for the various features of hauling, storage, etc.
- 3.4 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for and have control over construction means, methods, techniques, sequences and procedures and for coordinating all portions of the Work under the Contract, unless the Contract Documents give other specific instructions.
- 3.5 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Contract. The Contractor shall not permit employment of unfit persons or persons not skilled in tasks assigned to them.
- 3.6 The Contractor warrants to the Owner that materials and equipment furnished will be new and of good quality, unless otherwise permitted, and that the work will be free from defects and in conformance with the Contract Documents. Work not conforming to these requirements, including substitutions not properly approved, may be considered defective. If required by the Owner, the Contractor shall furnish evidence as to the kind and quality of materials and equipment provided.
- 3.7 Unless otherwise provided, the Contractor shall pay all sales, consumer, use and other similar taxes, and shall secure and pay for required permits, fees, licenses, and inspections necessary for proper execution of the Work.
- 3.8 The Contractor shall comply with and give notices required by laws, ordinances, rules, regulations, and lawful orders of public authorities bearing on performance of the Work. The Contractor shall promptly notify the Owner if the Drawings and Specifications are observed to be at variance therewith.
- 3.9 The Contractor shall be responsible to the Owner for the acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons performing portions of the Work under contract with the Contractor.
- 3.10 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under the Contract. At completion of the Work the Contractor shall remove from and about the Project all waste materials, rubbish, the Contractor's tools, construction equipment, machinery and surplus materials. The Contractor shall be responsible for returning all damaged areas to their original conditions.
- 3.11 STATE LICENSE AND TAX REQUIREMENTS
- 3.11.1 Each Contractor and Subcontractor shall be licensed to do business in the State of Delaware and shall pay all fees and taxes due under State laws. In conformance with Section 2503, Chapter 25, Title 30, Delaware Code, "the Contractor shall furnish the Delaware Department of Finance within ten (10) days after entering into any contract with a contractor or subcontractor not a resident of this State, a statement of total value of

such contract or contracts together with the names and addresses of the contracting parties.”

3.12 The Contractor shall comply with all requirements set forth in Section 6962, Chapter 69, Title 29 of the Delaware Code.

3.13 During the contract Work, the Contractor and each Subcontractor, shall implement an Employee Drug Testing Program in accordance with OMB Regulation 4104 - “Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on “Large Public Works Projects”. “Large Public Works” is based upon the current threshold required for bidding Public Works as set by the Purchasing and Contracting Advisory Council.

ARTICLE 4: ADMINISTRATION OF THE CONTRACT

4.1 CONTRACT SURETY

4.1.1 PERFORMANCE BOND AND LABOR AND MATERIAL PAYMENT BOND

4.1.2 All bonds will be required as follows unless specifically waived elsewhere in the Bidding Documents.

4.1.3 Contents of Performance Bonds – The bond shall be in the form approved by the Office of Management and Budget. The bond shall be conditioned upon the faithful compliance and performance by the successful bidder of each and every term and condition of the contract and the proposal, plans, specifications, and bid documents thereof. Each term and condition shall be met at the time and in the manner prescribed by the Contract, Bid documents and the specifications, including the payment in full to every person furnishing materiel or performing labor in the performance of the Contract, of all sums of money due the person for such labor and materiel. (The bond shall also contain the successful bidder’s guarantee to indemnify and save harmless the State and the agency from all costs, damages and expenses growing out of or by reason of the Contract in accordance with the Contract.)

4.1.4 Invoking a Performance Bond – The agency may, when it considers that the interest of the State so require, cause judgement to be confessed upon the bond.

4.1.5 Within twenty (20) days after the date of notice of award of contract, the Bidder to whom the award is made shall furnish a Performance Bond and Labor and Material Payment Bond, each equal to the full amount of the Contract price to guarantee the faithful performance of all terms, covenants and conditions of the same. The bonds are to be issued by an acceptable Bonding Company licensed to do business in the State of Delaware and shall be issued in duplicate.

4.1.6 Performance and Payment Bonds shall be maintained in full force (warranty bond) for a period of two (2) years after the date of the Certificate for Final Payment. The Performance Bond shall guarantee the satisfactory completion of the Project and that the Contractor will make good any faults or defects in his work which may develop during the period of said guarantees as a result of improper or defective workmanship, material or apparatus, whether furnished by themselves or their Sub-Contractors. The Payment Bond shall guarantee that the Contractor shall pay in full all persons, firms or corporations who furnish labor or

material or both labor and material for, or on account of, the work included herein. The bonds shall be paid for by this Contractor. The Owner shall have the right to demand that the proof parties signing the bonds are duly authorized to do so.

4.2 FAILURE TO COMPLY WITH CONTRACT

- 4.2.1 If any firm entering into a contract with the State, or Agency that neglects or refuses to perform or fails to comply with the terms thereof, the Agency which signed the Contract may terminate the Contract and proceed to award a new contract in accordance with this Chapter 69, Title 29 of the Delaware Code or may require the Surety on the Performance Bond to complete the Contract in accordance with the terms of the Performance Bond. Nothing herein shall preclude the Agency from pursuing additional remedies as otherwise provided by law.

4.3 CONTRACT INSURANCE AND CONTRACT LIABILITY

- 4.3.1 In addition to the bond requirements stated in the Bid Documents, each successful Bidder shall purchase adequate insurance for the performance of the Contract and, by submission of a Bid, agrees to indemnify and save harmless and to defend all legal or equitable actions brought against the State, any Agency, officer and/or employee of the State, for and from all claims of liability which is or may be the result of the successful Bidder's actions during the performance of the Contract.

- 4.3.2 The purchase or nonpurchase of such insurance or the involvement of the successful Bidder in any legal or equitable defense of any action brought against the successful Bidder based upon work performed pursuant to the Contract will not waive any defense which the State, its agencies and their respective officers, employees and agents might otherwise have against such claims, specifically including the defense of sovereign immunity, where applicable, and by the terms of this section, the State and all agencies, officers and employees thereof shall not be financially responsible for the consequences of work performed, pursuant to said contract.

4.4 RIGHT TO AUDIT RECORDS

- 4.4.1 The Owner shall have the right to audit the books and records of a Contractor or any Subcontractor under any Contract or Subcontract to the extent that the books and records relate to the performance of the Contract or Subcontract.
- 4.4.2 Said books and records shall be maintained by the Contractor for a period of seven (7) years from the date of final payment under the Prime Contract and by the Subcontractor for a period of seven (7) years from the date of final payment under the Subcontract.

ARTICLE 5: SUBCONTRACTORS

5.1 SUBCONTRACTING REQUIREMENTS

- 5.1.1 All contracts for the construction, reconstruction, alteration or repair of any public building (not a road, street or highway) shall be subject to the following provisions:
1. A contract shall be awarded only to a Bidder whose Bid is accompanied by a statement containing, for each Subcontractor category, the name and address

(city or town and State only – street number and P.O. Box addresses not required) of the subcontractor whose services the Bidder intends to use in performing the Work and providing the material for such Subcontractor category.

2. A Bid will not be accepted nor will an award of any Contract be made to any Bidder which, as the Prime Contractor, has listed itself as the Subcontractor for any Subcontractor unless:
 - A. It has been established to the satisfaction of the awarding Agency that the Bidder has customarily performed the specialty work of such Subcontractor category by artisans regularly employed by the Bidder's firm;
 - B. That the Bidder is duly licensed by the State to engage in such specialty work, if the State requires licenses; and
 - C. That the Bidder is recognized in the industry as a bona fide Subcontractor or Contractor in such specialty work and Subcontractor category.

5.1.2 The decision of the awarding Agency as to whether a Bidder who list itself as the Subcontractor for a Subcontractor category shall be final and binding upon all Bidders, and no action of any nature shall lie against any awarding agency or its employees or officers because of its decision in this regard.

5.1.3 After such a Contract has been awarded, the successful Bidder shall not substitute another Subcontractor for any Subcontractor whose name was set forth in the statement which accompanied the Bid without the written consent of the awarding Agency.

5.1.4 No Agency shall consent to any substitution of Subcontractors unless the Agency is satisfied that the Subcontractor whose name is on the Bidders accompanying statement:

- A. Is unqualified to perform the work required;
- B. Has failed to execute a timely reasonable Subcontract;
- C. Has defaulted in the performance on the portion of the work covered by the Subcontract; or
- D. Is no longer engaged in such business.

5.1.5 Should a Bidder be awarded a contract, such successful Bidder shall provide to the agency the taxpayer identification license numbers of such subcontractors. Such numbers shall be provided on the later of the date on which such subcontractor is required to be identified or the time the contract is executed. The successful Bidder shall provide to the agency to which it is contracting, within 30 days of entering into such public works contract, copies of all Delaware Business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the Bidder entered the public works contract the Delaware Business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.

5.1.6 The Contractor may employ additional Subcontractors on the jobsite only after submitting a copy of the Subcontractor's Employee Drug Testing Program to the Owner for approval. A Contractor or Subcontractor shall not commence work until the Owner has concluded its review and determined that the submitted Employee Drug Testing Program complies with OMB Regulation 4104.

5.2 PENALTY FOR SUBSTITUTION OF SUBCONTRACTORS

5.2.1 Should the Contractor fail to utilize any or all of the Subcontractors in the Contractor's Bid statement in the performance of the Work on the public bidding, the Contractor shall be penalized in the amount of (project specific amount*). The Agency may determine to deduct payments of the penalty from the Contractor or have the amount paid directly to the Agency. Any penalty amount assessed against the Contractor may be remitted or refunded, in whole or in part, by the Agency awarding the Contract, only if it is established to the satisfaction of the Agency that the Subcontractor in question has defaulted or is no longer engaged in such business. No claim for the remission or refund of any penalty shall be granted unless an application is filed within one year after the liability of the successful Bidder accrues. All penalty amounts assessed and not refunded or remitted to the contractor shall be reverted to the State.

*one (1) percent of contract amount not to exceed \$10,000

5.3 ASBESTOS ABATEMENT

5.3.1 The selection of any Contractor to perform asbestos abatement for State-funded projects shall be approved by the Office of Management and Budget, Division of Facilities Management pursuant to Chapter 78 of Title 16.

5.4 STANDARDS OF CONSTRUCTION FOR THE PROTECTION OF THE PHYSICALLY HANDICAPPED

5.4.1 All Contracts shall conform with the standard established by the Delaware Architectural Accessibility Board unless otherwise exempted by the Board.

5.5 CONTRACT PERFORMANCE

5.5.1 Any firm entering into a Public Works Contract that neglects or refuses to perform or fails to comply with its terms, the Agency may terminate the Contract and proceed to award a new Contract or may require the Surety on the Performance Bond to complete the Contract in accordance with the terms of the Performance Bond.

ARTICLE 6: CONSTRUCTION BY OWNER OR SEPARATE CONTRACTORS

6.1 The Owner reserves the right to simultaneously perform other construction or operations related to the Project with the Owner's own forces, and to award separate contracts in connection with other portions of the Project or other Projects at the same site.

6.2 The Contractor shall afford the Owner and other Contractors reasonable opportunity for access and storage of materials and equipment, and for the performance of their activities,

and shall connect and coordinate their activities with other forces as required by the Contract Documents.

ARTICLE 7: CHANGES IN THE WORK

- 7.1 The Owner, without invalidating the Contract, may order changes in the Work consisting of Additions, Deletions, Modifications or Substitutions, with the Contract Sum and Contract completion date being adjusted accordingly. Such changes in the Work shall be authorized by written Change Order signed by the Professional, as the duly authorized agent, the Contractor and the Owner.
- 7.2 The Contract Sum and Contract Completion Date shall be adjusted only by a fully executed Change Order.
- 7.3 The additional cost, or credit to the Owner resulting from a change in the Work shall be by mutual agreement of the Owner, Contractor and the Engineer. In all cases, this cost or credit shall be based on the 'DPE' wages required and the "invoice price" of the materials/equipment needed.
- 7.3.1 "DPE" shall be defined to mean "direct personnel expense". Direct payroll expense includes prevailing wage rates plus a maximum multiplier of 1.35 times DPE. For example, if the prevailing wage rate is \$50/hour, the DPE would be \$67.50/hour (50 x 1.35).
- 7.3.2 "Invoice price" of materials/equipment shall be defined to mean the actual cost of materials and/or equipment that is paid by the Contractor, (or subcontractor), to a material distributor, direct factory vendor, store, material provider, or equipment leasing entity. Rates for equipment that is leased and/or owned by the Contractor or subcontractor(s) shall not exceed those listed in the latest version of the "Means Building Construction Cost Data" publication.
- 7.3.3 In addition to the above, the General Contractor is allowed a fifteen percent (15%) markup for overhead and profit for additional work performed by the General Contractor's own forces. For additional subcontractor work, the Subcontractor is allowed a fifteen (15) percent overhead and profit on change order work above and beyond the direct costs stated previously. To this amount, the General Contractor will be allowed a mark-up not exceeding seven and one half percent (7.5%) on the subcontractors work. These mark-ups shall include all costs including, but not limited to: overhead, profit, bonds, insurance, supervision, etc. No markup is permitted on the work of the subcontractors subcontractor. No additional costs shall be allowed for changes related to the Contractor's onsite superintendent/staff, or project manager, unless a change in the work changes the project duration and is identified by the CPM schedule. There will be no other costs associated with the change order.

ARTICLE 8: TIME

- 8.1 Time limits, if any, are as stated in the Project Manual. By executing the Agreement, the Contractor confirms that the stipulated limits are reasonable, and that the Work will be completed within the anticipated time frame.
- 8.2 If progress of the Work is delayed at any time by changes ordered by the Owner, by labor disputes, fire, unusual delay in deliveries, abnormal adverse weather conditions, unavoidable

casualties or other causes beyond the Contractor's control, the Contract Time shall be extended for such reasonable time as the Owner may determine.

- 8.3 Any extension of time beyond the date fixed for completion of the construction and acceptance of any part of the Work called for by the Contract, or the occupancy of the building by the Owner, in whole or in part, previous to the completion shall not be deemed a waiver by the Owner of his right to annul or terminate the Contract for abandonment or delay in the matter provided for, nor relieve the Contractor of full responsibility.

8.4 SUSPENSION AND DEBARMENT

- 8.4.1 Per Section 6962(d)(14), Title 29, Delaware Code, "Any Contractor who fails to perform a public works contract or complete a public works project within the time schedule established by the Agency in the Invitation To Bid, may be subject to Suspension or Debarment for one or more of the following reasons: a) failure to supply the adequate labor supply ratio for the project; b) inadequate financial resources; or, c) poor performance on the Project."

- 8.4.2 "Upon such failure for any of the above stated reasons, the Agency that contracted for the public works project may petition the Director of the Office of Management and Budget for Suspension or Debarment of the Contractor. The Agency shall send a copy of the petition to the Contractor within three (3) working days of filing with the Director. If the Director concludes that the petition has merit, the Director shall schedule and hold a hearing to determine whether to suspend the Contractor, debar the Contractor or deny the petition. The Agency shall have the burden of proving, by a preponderance of the evidence, that the Contractor failed to perform or complete the public works project within the time schedule established by the Agency and failed to do so for one or more of the following reasons: a) failure to supply the adequate labor supply ratio for the project; b) inadequate financial resources; or, c) poor performance on the project. Upon a finding in favor of the Agency, the Director may suspend a Contractor from Bidding on any project funded, in whole or in part, with public funds for up to 1 year for a first offense, up to 3 years for a second offense and permanently debar the Contractor for a third offense. The Director shall issue a written decision and shall send a copy to the Contractor and the Agency. Such decision may be appealed to the Superior Court within thirty (30) days for a review on the record."

8.5 RETAINAGE

- 8.5.1 Per Section 6962(d)(5) a.3, Title 29, Delaware Code: The Agency may at the beginning of each public works project establish a time schedule for the completion of the project. If the project is delayed beyond the completion date due to the Contractor's failure to meet their responsibilities, the Agency may forfeit, at its discretion, all or part of the Contractor's retainage.

- 8.5.2 This forfeiture of retainage also applies to the timely completion of the punchlist. A punchlist will only be prepared upon the mutual agreement of the Owner, Engineer and Contractor. Once the punchlist is prepared, all three parties will by mutual agreement, establish a schedule for its completion. Should completion of the punchlist be delayed beyond the established date due to the Contractor's failure to meet their responsibilities, the Agency may hold permanently, at its discretion, all or part of the Contractor's retainage.

ARTICLE 9: PAYMENTS AND COMPLETION

9.1 APPLICATION FOR PAYMENT

- 9.1.1 Applications for payment shall be made upon AIA Document G702. There will be a five percent (5%) retainage on all Contractor's monthly invoices until completion of the project. This retainage may become payable upon receipt of all required closeout documentation, provided all other requirements of the Contract Documents have been met.
- 9.1.2 A date will be fixed for the taking of the monthly account of work done. Upon receipt of Contractor's itemized application for payment, such application will be audited, modified, if found necessary, and approved for the amount. Statement shall be submitted to the Owner.
- 9.1.3 Section 6516, Title 29 of the Delaware Code annualized interest is not to exceed 12% per annum beginning thirty (30) days after the "presentment" (as opposed to the date) of the invoice.

9.2 PARTIAL PAYMENTS

- 9.2.1 Any public works Contract executed by any Agency may provide for partial payments at the option of the Owner with respect to materials placed along or upon the sites or stored at secured locations, which are suitable for use in the performance of the contract.
- 9.2.2 When approved by the agency, partial payment may include the values of tested and acceptable materials of a nonperishable or noncontaminative nature which have been produced or furnished for incorporation as a permanent part of the work yet to be completed, provided acceptable provisions have been made for storage.
- 9.2.2.1 Any allowance made for materials on hand will not exceed the delivered cost of the materials as verified by invoices furnished by the Contractor, nor will it exceed the contract bid price for the material complete in place.
- 9.2.3 If requested by the Agency, receipted bills from all Contractors, Subcontractors, and material, men, etc., for the previous payment must accompany each application for payment. Following such a request, no payment will be made until these receipted bills have been received by the Owner.

9.3 SUBSTANTIAL COMPLETION

- 9.3.1 When the building has been made suitable for occupancy and met the requirements of substantial completion, but still requires small items of miscellaneous work, the Engineer will determine the date when the project has been substantially completed.
- 9.3.2 If, after the Work has been substantially completed, full completion thereof is materially delayed through no fault of the Contractor, and without terminating the Contract, the Owner may make payment of the balance due for the portion of the Work fully completed and accepted. Such payment shall be made under the terms and conditions governing final payment that it shall not constitute a waiver of claims.

- 9.3.3 On projects where commissioning is included, the commissioning work as defined in the specifications must be complete prior to the issuance of substantial completion.
- 9.4 FINAL PAYMENT
- 9.4.1 Final payment, including the five percent (5%) retainage if determined appropriate, shall be made within thirty (30) days after the Work is fully completed and the Contract fully performed and provided that the Contractor has submitted the following closeout documentation (in addition to any other documentation required elsewhere in the Contract Documents):
- 9.4.1.1 Evidence satisfactory to the Owner that all payrolls, material bills, and other indebtedness connected with the work have been paid,
- 9.4.1.2 An acceptable RELEASE OF LIENS,
- 9.4.1.3 Copies of all applicable warranties,
- 9.4.1.4 As-built drawings,
- 9.4.1.5 Operations and Maintenance Manuals,
- 9.4.1.6 Instruction Manuals,
- 9.4.1.7 Consent of Surety to final payment.
- 9.4.1.8 The Owner reserves the right to retain payments, or parts thereof, for its protection until the foregoing conditions have been complied with, defective work corrected and all unsatisfactory conditions remedied.

ARTICLE 10: PROTECTION OF PERSONS AND PROPERTY

- 10.1 The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract. The Contractor shall take all reasonable precautions to prevent damage, injury or loss to: workers, persons nearby who may be affected, the Work, materials and equipment to be incorporated, and existing property at the site or adjacent thereto. The Contractor shall give notices and comply with applicable laws ordinances, rules regulations, and lawful orders of public authorities bearing on the safety of persons and property and their protection from injury, damage, or loss. The Contractor shall promptly remedy damage and loss to property at the site caused in whole or in part by the Contractor, a Subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable.
- 10.2 The Contractor shall notify the Owner in the event any existing hazardous material such as lead, PCBs, asbestos, etc. is encountered on the project. The Owner will arrange with a qualified specialist for the identification, testing, removal, handling and protection against exposure or environmental pollution, to comply with applicable regulation laws and ordinances. The Contractor and Engineer will not be required to participate in or to perform this operation. Upon completion of this work, the Owner will notify the Contractor and Engineer in writing the area has been cleared and approved by the authorities in order for the

work to proceed. The Contractor shall attach documentation from the authorities of said approval.

- 10.3 As required in the Hazardous Chemical Information Act of June 1984, all vendors supplying any materials that may be defined as hazardous, must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it has a warning caution on the label relating to a potential physical or health hazard, if it is known to be present in the work place, and if employees may be exposed under normal conditions or in any foreseeable emergency situation. Material Safety Data Sheets must be provided directly to the Owner along with the shipping slips that include those products.
- 10.4 The Contractor shall certify to the Owner that materials incorporated into the Work are free of all asbestos. This certification may be in the form of Material Safety Data Sheet (MSDS) provided by the product manufacturer for the materials used in construction, as specified or as provided by the Contractor.

ARTICLE 11: INSURANCE AND BONDS

- 11.1 The Contractor shall carry all insurance required by law, such as Unemployment Insurance, etc. The Contractor shall carry such insurance coverage as they desire on their own property such as a field office, storage sheds or other structures erected upon the project site that belong to them and for their own use. The Subcontractors involved with this project shall carry whatever insurance protection they consider necessary to cover the loss of any of their personal property, etc.
- 11.2 Upon being awarded the Contract, the Contractor shall obtain a minimum of two (2) copies of all required insurance certificates called for herein, and submit one (1) copy of each certificate, to the Owner, within 20 days of contract award.
- 11.3 Bodily Injury Liability and Property Damage Liability Insurance shall, in addition to the coverage included herein, include coverage for injury to or destruction of any property arising out of the collapse of or structural injury to any building or structure due to demolition work and evidence of these coverages shall be filed with and approved by the Owner.
- 11.4 The Contractor's Property Damage Liability Insurance shall, in addition to the coverage noted herein, include coverage on all real and personal property in their care, custody and control damaged in any way by the Contractor or their Subcontractors during the entire construction period on this project.
- 11.5 Builders Risk (including Standard Extended Coverage Insurance) on the existing building during the entire construction period, shall not be provided by the Contractor under this contract. The Owner shall insure the existing building and all of its contents and all this new alteration work under this contract during entire construction period for the full insurable value of the entire work at the site. Note, however, that the Contractor and their Subcontractors shall be responsible for insuring building materials (installed and stored) and their tools and equipment whenever in use on the project, against fire damage, theft, vandalism, etc.

11.6 Certificates of the insurance company or companies stating the amount and type of coverage, terms of policies, etc., shall be furnished to the Owner, within 20 days of contract award.

11.7 The Contractor shall, at their own expense, (in addition to the above) carry the following forms of insurance:

11.7.1 Contractor's Contractual Liability Insurance

Minimum coverage to be:

Bodily Injury	\$500,000	for each person
	\$1,000,000	for each occurrence
	\$1,000,000	aggregate
Property Damage	\$500,000	for each occurrence
	\$1,000,000	aggregate

11.7.2 Contractor's Protective Liability Insurance

Minimum coverage to be:

Bodily Injury	\$500,000	for each person
	\$1,000,000	for each occurrence
	\$1,000,000	aggregate
Property Damage	\$500,000	for each occurrence
	\$500,000	aggregate

11.7.3 Automobile Liability Insurance

Minimum coverage to be:

Bodily Injury	\$1,000,000	for each person
	\$1,000,000	for each occurrence
Property Damage	\$500,000	per accident

11.7.4 Prime Contractor's and Subcontractors' policies shall include contingent and contractual liability coverage in the same minimum amounts as 11.7.1 above.

11.7.5 Workmen's Compensation (including Employer's Liability):

11.7.5.1 Minimum Limit on employer's liability to be as required by law.

11.7.5.2 Minimum Limit for all employees working at one site.

11.7.6 Certificates of Insurance must be filed with the Owner guaranteeing fifteen (15) days prior notice of cancellation, non-renewal, or any change in coverages and limits of liability shown as included on certificates.

11.7.7 Social Security Liability

11.7.7.1 With respect to all persons at any time employed by or on the payroll of the Contractor or performing any work for or on their behalf, or in connection with or arising out of the Contractor's business, the Contractor shall accept full and exclusive liability for the payment of any and all contributions or taxes or unemployment insurance, or old age retirement benefits, pensions or annuities now or hereafter imposed by the Government of the United States and the State or political subdivision thereof, whether the same be measured by wages, salaries or other remuneration paid to such persons or otherwise.

11.7.7.2 Upon request, the Contractor shall furnish Owner such information on payrolls or employment records as may be necessary to enable it to fully comply with the law imposing the aforesaid contributions or taxes.

11.7.7.3 If the Owner is required by law to and does pay any and/or all of the aforesaid contributions or taxes, the Contractor shall forthwith reimburse the Owner for the entire amount so paid by the Owner.

ARTICLE 12: UNCOVERING AND CORRECTION OF WORK

12.1 The Contractor shall promptly correct Work rejected by the Owner or failing to conform to the requirements of the Contract Documents, whether observed before or after Substantial Completion and whether or not fabricated, installed or completed, and shall correct any Work found to be not in accordance with the requirements of the Contract Documents within a period of two years from the date of Substantial Completion, or by terms of an applicable special warranty required by the Contract Documents. The provisions of this Article apply to work done by Subcontractors as well as to Work done by direct employees of the Contractor.

12.2 At any time during the progress of the work, or in any case where the nature of the defects shall be such that it is not expedient to have them corrected, the Owner, at their option, shall have the right to deduct such sum, or sums, of money from the amount of the contract as they consider justified to adjust the difference in value between the defective work and that required under contract including any damage to the structure.

ARTICLE 13: MISCELLANEOUS PROVISIONS

13.1 CUTTING AND PATCHING

13.1.1 The Contractor shall be responsible for all cutting and patching. The Contractor shall coordinate the work of the various trades involved.

13.2 DIMENSIONS

13.2.1 All dimensions shown shall be verified by the Contractor by actual measurements at the project site. Any discrepancies between the drawings and specifications and the existing conditions shall be referred to the Owner for adjustment before any work affected thereby has been performed.

13.3 LABORATORY TESTS

- 13.3.1 Any specified laboratory tests of material and finished articles to be incorporated in the work shall be made by bureaus, laboratories or agencies approved by the Owner and reports of such tests shall be submitted to the Owner. The cost of the testing shall be paid for by the Contractor.
- 13.3.2 The Contractor shall furnish all sample materials required for these tests and shall deliver same without charge to the testing laboratory or other designated agency when and where directed by the Owner.
- 13.4 ARCHAEOLOGICAL EVIDENCE
- 13.4.1 Whenever, in the course of construction, any archaeological evidence is encountered on the surface or below the surface of the ground, the Contractor shall notify the authorities of the State Historic Preservation Office and suspend work in the immediate area for a reasonable time to permit those authorities, or persons designated by them, to examine the area and ensure the proper removal of the archaeological evidence for suitable preservation by the Division of Historical and Cultural Affairs.
- 13.5 GLASS REPLACEMENT AND CLEANING
- 13.5.1 The General Contractor shall replace without expense to the Owner all glass broken during the construction of the project. If job conditions warrant, at completion of the job the General Contractor shall have all glass cleaned and polished.
- 13.6 WARRANTY
- 13.6.1 For a period of two (2) years from the date of substantial completion, as evidenced by the date of final acceptance of the work, the contractor warrants that work performed under this contract conforms to the contract requirements and is free of any defect of equipment, material or workmanship performed by the contractor or any of his subcontractors or suppliers. However, manufacturer's warranties and guarantees, if for a period longer than two (2) years, shall take precedence over the above warranties. The contractor shall remedy, at his own expense, any such failure to conform or any such defect. The protection of this warranty shall be included in the Contractor's Performance Bond.

ARTICLE 14: TERMINATION OF CONTRACT

- 14.1 If the Contractor defaults or persistently fails or neglects to carry out the Work in accordance with the Contract Documents or fails to perform a provision of the Contract, the Owner, after seven days written notice to the Contractor, may make good such deficiencies and may deduct the cost thereof from the payment then or thereafter due the Contractor. Alternatively, at the Owner's option, and the Owner may terminate the Contract and take possession of the site and of all materials, equipment, tools, and machinery thereon owned by the Contractor and may finish the Work by whatever method the Owner may deem expedient. If the costs of finishing the Work exceed any unpaid compensation due the Contractor, the Contractor shall pay the difference to the Owner.
- 14.2 "If the continuation of this Agreement is contingent upon the appropriation of adequate state, or federal funds, this Agreement may be terminated on the date beginning on the first fiscal year for which funds are not appropriated or at the exhaustion of the

appropriation. The Owner may terminate this Agreement by providing written notice to the parties of such non-appropriation. All payment obligations of the Owner will cease upon the date of termination. Notwithstanding the foregoing, the Owner agrees that it will use its best efforts to obtain approval of necessary funds to continue the Agreement by taking appropriate action to request adequate funds to continue the Agreement.”

END OF GENERAL REQUIREMENTS

EMPLOYEE DRUG TESTING REPORT FORM

Period Ending:_____

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects requires that Contractors and Subcontractors who work on Large Public Works Contracts funded all or in part with public funds maintain testing data that includes but is not limited to the data elements below.

Project Number: _____

Project Name: _____

Contractor/Subcontractor Name: _____

Contractor/Subcontractor Address: _____

Number of employees who worked on the jobsite during the report period:_____

Number of employees subject to random testing during the report period:_____

Number of Negative Results _____ Number of Positive Results _____

Action taken on employee(s) in response to a failed or positive random test:

Date: _____

This form is not required to be submitted to the Owner. Included as a reference to show information required to be maintained by the Contractor. The Owner shall have the right to periodically audit all Contractor and Subcontractor test results at the Contractor's or Subcontractor's offices (or by other means to make the data available for inspection by the Owner).

**EMPLOYEE DRUG TESTING
REPORT OF POSITIVE RESULTS**

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects requires that Contractors and Subcontractors who work on Large Public Works Contracts funded all or in part with public funds to notify the Owner in writing of a positive random drug test.

Project Number: _____

Project Name: _____

Contractor/Subcontractor Name: _____

Contractor/Subcontractor Address: _____

Name of employee with positive test result: _____

Last 4 digits of employee SSN: _____

Date test results received: _____

Action taken on employee in response to a positive test result:

Authorized Representative of Contractor/Subcontractor: _____
(typed or printed)

Authorized Representative of Contractor/Subcontractor: _____
(signature)

Date: _____

This form shall be sent by mail to the Owner within 24 hours of receipt of test results.

Enclose this test results form in a sealed envelope with the notation "Drug Testing Form – DO NOT OPEN" on the face thereof and place in a separate mailing envelope.

Regulations Menu

Administrative Code > Title 19 Labor

Authenticated PDF Version 

Search Administrative Code 

4000 Office of Management and Budget

4100 Division of Facilities Management

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects

1.0 Purpose

The Office of Management and Budget (“Office”), has developed these regulations that require contractors and subcontractors to implement a program of mandatory drug testing for employees who work on large public works contracts funded all or in part with public funds pursuant to 29 **Del.C.** §6908(a)(6). The regulations establish the mechanism, standards and requirements of a Mandatory Drug Testing Program that will be incorporated by reference into all large public works contracts awarded pursuant to 29 **Del.C.** §6962.

2.0 Definitions

“Consortium”/“third party administrator” or “(C/TPA)” means a service agent that provides or coordinates the provision of a variety of drug and alcohol testing services to employers. C/TPAs typically perform administrative tasks concerning the operation of the employers' drug and alcohol testing programs. This term includes, but is not limited to, groups of employers who join together to administer, as a single entity, the drug and alcohol testing programs of its members.

“Contractor” means an entity such as, but not limited to, an individual, firm, partnership or corporation that has a contractual obligation to perform work for contracts awarded pursuant to 29 **Del.C.** §6962.

“Division of Facilities Management” and “DFM” means the Division of Facilities Management within the Office of Management and Budget.

“Drug testing firm” is an entity engaged in the business of providing drug testing services for businesses, individuals, governments or any entity that requires drug testing of employees, applicants, licensees, etc., in compliance with these requirements.

“Employee” means an individual employed by a contractor or subcontractor who works on the jobsite of a large public works contract but does not fulfill a clerical or administrative function. For the purpose of this definition, clerical or administrative functions shall refer to job responsibilities that do not generally require an employee to work outside of the contractor's jobsite office, home office or other employer-provided office. For the purposes of this regulation, the term “employee” shall also include supervisors and foremen working on the jobsite. The term “employee” shall also include employees of a contractor or subcontractor working on or delivering materials and equipment to and from a jobsite.

“Impairment” or **“impaired”** means symptoms that an employee while working may be under the influence of drugs or alcohol that may decrease or lessen the employee's performance of the duties or tasks of the employee's job position, including symptoms of the employee's speech, walking, standing, physical dexterity, agility, coordination, actions, movement, demeanor, appearance, clothing, odor, irrational or unusual behavior, negligence or carelessness in operating equipment, machinery or production or manufacturing processes, disregard for the safety of the employee or others, or other symptoms causing a reasonable suspicion of the use of drugs or alcohol.

“Jobsite” means the site or area directly or indirectly owned, operated or controlled by the owner in which the contractor or subcontractor performs work or delivers services to the owner. For the purpose of this definition, “jobsite” does not mean a remote work site not under the direct or indirect control of the owner in which work is performed to fulfill the contractor's or subcontractor's obligations.

“Large public works contract” means a contract for a public works construction awarded pursuant to 29 **Del.C.** §6962.

“Mandatory drug testing program” and **“program”** means a defined set of basic procedures, requirements and rules that must be used by a contractor or subcontractor to test employees for drugs in compliance with these requirements.

“Owner” is the state agency, school district or entity that awards a large public works contract to a contractor pursuant to 29 **Del.C.** §6962.

“Positive test result” and **“fail a drug test”** means the result reported by a Health and Human Services certified laboratory when a specimen contains a drug or drug metabolite equal to or greater than the cutoff concentration. For purposes of these regulations, an employee shall not be considered to have a positive test result nor shall an employee be considered to “fail a drug test”, unless the employee was impaired by marijuana at the jobsite if:

- The employee is a registered qualifying patient and;
- The drug detected was marijuana, a component of marijuana, or marijuana metabolites.

“Random drug testing” means that an employee is chosen at random for testing without advance notice, from a pool of employees or as a member of a consortium. Specific requirements for random drug testing conducted under these regulations are described in Section 5.0.

“Registered qualifying patient” means a person (1) validly issued and in possession of an unexpired registry identification card as defined by 16 **Del.C.** §4902A (14), and (2) subject to confirmation through a “verification system” as set forth at 16 **Del.C.** §4902A(17).

“Subcontractor” means an entity such as, but not limited to, an individual, firm, partnership or corporation that has a contractual obligation to perform work for, or supply services to a contractor as defined in Section 2.0.

21 DE Reg. 503 (12/01/17)

3.0 Employee Drug Testing Documentation Requirements

3.1 The following documentation requirements apply:

3.1.1 At bid submission. A solicitation for a large public works contract must require each contractor that submits a bid for the work to submit with the bid a signed affidavit certifying that the contractor and subcontractor(s) has in place or will implement during the entire term of the contract a mandatory drug testing program that complies with this regulation.

3.1.2 At least 2 business days prior to contract execution. The awarded contractor shall provide to the owner copies of the employee drug testing program for the contractor and for all listed subcontractors.

3.1.3 During contract execution. Contractors that employ additional subcontractors on the jobsite may do so only after submitting a copy of the subcontractor's employee drug testing program. A contractor or subcontractor shall

not commence work until the owner has concluded the employee drug testing program complies with this regulation as per subsection 3.2.

3.1.4 In the event of an emergency a contractor may employ additional subcontractors on the jobsite prior to submitting the subcontractor's employee drug testing program provided that said program is submitted to the owner as soon as practicable.

3.2 A contractor or subcontractor shall be treated as having a mandatory drug testing program that complies with this regulation if the program includes the following:

3.2.1 The program meets the minimum standards in Section 4.0 of this regulation.

3.2.2 The program provides for the frequency of testing of employees as per Section 5.0 of this regulation:

3.2.3 The program imposes disciplinary measures on an employee who fails a drug test as per Section 6.0 of this regulation.

3.3 Prequalified contractors and subcontractors. A contractor or subcontractor may meet the provisions of subsection 3.1 if they are prequalified through the DFM prequalification and if the DFM prequalification includes provisions requiring an employee mandatory drug testing program that meet the requirements of Sections 4.0, 5.0 and 6.0 of this regulation

3.4 The State shall not be obligated to pay, and the contractor or subcontractor shall expressly agree that, any portion of work performed by a contractor or subcontractor commenced before that contractor or subcontractor has complied with subsections 3.1 and 3.2, provided however that emergency work as referenced in subsection 3.1.4 may not be subject to this provision.

21 DE Reg. 503 (12/01/17)

4.0 Minimum Standards for a Mandatory Drug Testing Program

4.1 Testing for the presence of drugs in an employee's system and the handling of test specimens shall be conducted in accordance with guidelines for the collection, chain-of-custody procedures, laboratory testing, and Medical Officer Review procedures contained within the Mandatory Guidelines for Federal Workplace Drug Testing Programs published by the Substance Abuse and Mental Health Services Administration (SAMHSA). (49 CFR Part 40).

All tests must be processed by a federal Health and Human Services certified laboratory. Contractors must provide documentation detailing the procedures used in the collection, testing and reporting of drug tests sufficient to show conformance with SAMHSA guidelines.

4.2 Contractors and subcontractors subject to these regulations may procure the services of an appropriate drug testing firm to administer their program. A contractor or subcontractor may also participate in a consortium. A contractor or subcontractor may also implement a mandatory drug testing program using in-house personnel and resources.

4.3 Employees subject to drug testing shall be tested using at a minimum a seven-panel protocol testing plus alcohol screening for the following:

Initial test analyte	Initial test cutoff concentration	Confirmatory test analyte	Confirmatory test cutoff concentration
Marijuana metabolites	50 ng/mL	THCA	15 ng/mL
Cocaine metabolites	150 ng/mL	Benzoyllecgonine	100 ng/mL
Opiate metabolites			
Codeine/Morphine	2000 ng/mL	Codeine	2000 ng/mL
		Morphine	2000 ng/mL
6-Acetylmorphine	10 ng/mL	6-Acetylmorphine	10 ng/mL
Phencyclidine	25 ng/mL	Phencyclidine	25 ng/mL
Amphetamines			
AMP/MAMP	500 ng/mL	Amphetamine	250 ng/mL
		Methamphetamine	250 ng/mL
MDMA	500 ng/mL	MDMA	250 ng/mL
		MDA	250 ng/mL
		MDEA	250 ng/mL
Alcohol	0.04%		

4.4 The frequency of random drug testing and the methodology for selecting employees to be screened are defined in Section 5.0 and shall be incorporated into contractor and subcontractor mandatory testing procedures. A contractor or subcontractor may incorporate rules or requirements that exceed the requirements defined herein.

21 DE Reg. 503 (12/01/17)

5.0 Drug Testing Requirements – Frequency for the Testing of Employees

5.1 Initial drug testing. Employees commencing work on a jobsite must be tested with the exception that an employee who has passed a random or scheduled drug test within the past 180 days from the date of commencing work or an employee who passed a pre-employment drug test administered pursuant to a contractor's or subcontractor's program, or who possesses a certification no more than 6 months old under the then current New Castle County ordinance 2.05.305 - Alcohol and Drug Testing of Employees of Contractors Working on Public Works Projects and Jobsites, and is subject to testing as part of a contractor's or subcontractor's ongoing program or as part of a consortium shall be permitted to work at the jobsite without further testing; however, the employee is still subject to random testing.

5.2 Random drug testing. During the course of a project, each contractor and subcontractor with employees on the jobsite shall maintain a program that meets or exceeds the following requirements.

5.2.1 All employees will be subject to random, unannounced testing.

5.2.2 The selection of employees shall be made by a scientifically valid method of randomly generating an employee identifier from a contractor or subcontractor's entire pool of employees, through those employees working on a public works jobsite or through the contractor or subcontractor's participation in a consortium.

5.2.3 A contractor or subcontractor's program shall provide that no less than 5% of a contractor's or subcontractor's employees shall be randomly selected each month for drug testing and no less than 2.5% of a contractor or subcontractor's employees be randomly selected for alcohol testing. Contractors or subcontractors may participate in a consortium provided that no less than 5% of the consortium's pool shall be subject to drug testing each month and no less than 2.5% of the consortium's pool shall be subject to alcohol testing each month. Contractors or subcontractors with less than 10 employees that do not participate in a consortium shall test at least 1 of their employees, selected randomly per month. Each employee shall have an equal chance of selection each time the selection is made. Because the selection process is random, some employees may not be tested within a year, while others may be tested more than once. Nothing in this regulation shall require an employee of a contractor or subcontractor not working or assigned to a public works jobsite to be subject to random alcohol testing.

5.2.4 Employees notified that they have been selected must report within 4 hours for testing to a site specified. Employees so notified must have been given such notification at least 4 hours before the scheduled closing time of the testing facility. Any failure to report for random testing, or to cooperate with the testing procedure shall be considered a positive result.

5.2.5 Purposely impeding or delaying an employee's fulfillment of the testing requirements herein by a contractor or subcontractor may subject the contractor or subcontractor to sanctions listed in Section 8.0.

5.3 Reasonable suspicion testing. An employee will be required to take a drug and/or alcohol test at any time his or her employing contractor, subcontractor or the owner reasonably believes that he or she has an impairment caused by drugs and/or alcohol. Further, an employee may be required to take a drug and/or alcohol test at any time his or her employing contractor, subcontractor or the owner finds drug paraphernalia and/or open alcohol containers on the jobsite.

5.4 Return to duty testing. As required in Section 6.0.

5.5 Accident triggered testing. An employee will be required to take a drug test and may be subject to an alcohol breathalyzer test at any time there is a jobsite accident involving loss or significant property damage, injury or death to an employee of the contractor, subcontractor, or owner or member of the public.

5.5.1 As soon as practicable following an accident, the contractor will notify the employee(s) whose performance could have contributed to the accident of the need for the test.

5.5.2 The appropriate contractor shall ensure that an employee, required to be tested under this section, report to a testing center as soon as practicable, but no longer than 4 hours after the accident. Employees so notified must have been given such notification at least 4 hours before the scheduled closing time of the testing facility. If the drug test is not conducted within 4 hours, attempts to conduct the test must cease and the reasons for the failure to test documented.

5.5.3 An employee who is subject to post-accident testing who fails to remain readily available for such testing, including notifying a supervisor of his or her location if he or she leaves the scene of the accident prior to submission to such test, may be deemed to have refused to submit to testing.

5.5.4 If an employee fails or refuses to be tested, he/she must be removed from the jobsite and shall be subject to consequences in Section 6.0.

5.5.5 Nothing in this section shall be construed to require the delay of necessary medical attention for the injured following an accident, or to prohibit an employee from leaving the scene of an accident for the period necessary to obtain assistance in responding to the accident, or to obtain necessary emergency medical care.

5.6 All testing required by this section shall be administered according to the standards outlined in Section 4.0.

21 DE Reg. 503 (12/01/17)

28 DE Reg. 228 (09/01/24)

6.0 Consequences of a Positive Test Result

6.1 The disciplinary measures contained within a contractor's or subcontractor's program for an employee who tests positive to a mandatory drug test must include at a minimum, all of the following:

6.1.1 The employee is subject to an immediate suspension from any public works jobsite.

6.1.2 The employee is not eligible for reinstatement by the contractor or subcontractor to any public works jobsite until 30 days after the employee tests negative on a seven drug panel plus alcohol test certified by a medical review officer.

6.1.3 The employee is subject to unscheduled monthly random testing as per subsection 5.2.

6.1.4 An employee who has tested positive for more than 1 drug test within a 3-year period shall be permanently banned from working at public works jobsites.

6.1.5 An employee who has tested positive for marijuana, a component of marijuana, or marijuana metabolites and is a registered qualifying patient shall be exempted from the disciplinary actions contained in this section unless:

6.1.5.1 The employee was impaired by marijuana at the jobsite.

6.1.5.2 Employment of the registered qualifying patient would cause the owner to lose monetary or licensing-related benefits under Federal law.

6.2 A contractor or subcontractor shall report the positive test result to the employee's professional licensing board, if applicable.

21 DE Reg. 503 (12/01/17)

7.0 Contractor and Subcontractor Certification of Compliance with Regulations

7.1 During the term of the contract:

7.1.1 During the term of the contract, contractors and subcontractors on the jobsite for more than 30 days shall maintain testing data that includes but is not limited to the data elements contained in subsection 7.1.2:

7.1.1.1 A contractor or subcontractor that is employed on the jobsite for less than 30 days shall not be subject to the reporting requirements contained in subsection 7.1.2 of this regulation, unless the owner specifies that such reporting is required in the invitation to bid or specifications relating to the work to be performed.

7.1.2 The data shall at a minimum contain the following elements:

7.1.2.1 The number of employees who worked on the jobsite during the previous month or quarter.

7.1.2.2 The number of employees subjected to random testing during the previous month or quarter.

7.1.2.3 The number of negative results and the number of positive results.

7.1.2.4 Action taken by the contractor or subcontractor on an employee who failed or tested positive to a random test.

7.1.3 Test results must be kept by a contractor or subcontractor for a minimum of 1 year subsequent to the date of close out of the public works project.

7.1.4 Any positive test result of an employee working on a public works jobsite including the employee name and action taken in response by a contractor or subcontractor must be reported by the contractor or subcontractor to the owner in writing within 24 hours of the contractor or subcontractor receiving the test results.

7.1.5 The owner shall have the right to periodically audit all contractor and subcontractor test results at the contractor or subcontractor's offices or by other means to make the data available for inspection by the owner.

7.1.6 The failure to comply with these reporting requirements may be considered a material breach of any agreement relating to the performance of work by the contractor or subcontractor.

21 DE Reg. 503 (12/01/17)

8.0 Penalties

8.1 A contractor or subcontractor on a large public works contract that fails to implement a mandatory drug testing program in accordance with this regulation or falsifies testing results shall be subject to the following sanctions:

8.1.1 Written warning (1st offense).

8.1.2 Prohibition from bidding on new public works jobs for a period not to exceed 3 months (2nd offense) and 1 year (3rd offense).

8.1.3 For subsequent offenses, debarment or bond revocation.

8.2 Notwithstanding any other provision of this regulation, if any failure to comply with the requirements of this regulation are particularly flagrant or egregious, the owner may seek a termination for cause, a temporary suspension, a determination that the contractor or subcontractor is not responsible, debarment or bond revocation, and any other statutory, common law, or equitable remedy.

19 DE Reg. 207 (09/01/15)

21 DE Reg. 503 (12/01/17)

21 DE Reg. 645 (02/01/18)

28 DE Reg. 228 (09/01/24)

28 DE Reg. 326 (10/01/24)

Agency Information

Contact Information

Register of Regulations

Administrative Code

Delaware Code

Laws of Delaware

City & Town Charters

Delaware General Assembly

Style Manual

Cumulative Table

Citizen Participation

FOIA Request Form



THIS PAGE LEFT INTENTIONALLY BLANK

HEAT OF REJECTION EQUIPMENT REPLACEMENT FOR
GEORGE WASHINGTON CARVER EDUCATIONAL CENTER AND SELBYVILLE MIDDLE SCHOOL
INDIAN RIVER SCHOOL DISTRICT
CONTRACT #IRD25036-HVAC

**AFFIDAVIT OF
CRAFT TRAINING COMPLIANCE**

We, the contractor, hereby certify that we and all applicable subcontractors will abide by the contractor and subcontractor craft training requirements outlined below for the duration of the contract. Craft training must be provided by a contractor and/or subcontractor for each craft on a project for which there are Delaware Department of Labor approved and registered training programs or, if the contractor and/or subcontractor meets the requirements under Title 29, Chapter 69, Section 6960A.(b)(1)c.1.-3., payment may be made in accordance with Title 29, Chapter 69, Section 6960A.(b)(1)d. A list of crafts for which there are approved and registered training programs is maintained by the Delaware Department of Labor and can be found at:

<https://laborfiles.delaware.gov/main/det/apprenticeship/DE%20Craft%20Training%20Occupation%20List%20Effective%20March%201%202022.pdf>. If you have questions regarding craft training programs, please submit all questions in writing to the Delaware Department of Labor at: apprenticeship@delaware.gov. ***This Affidavit of Craft Training Compliance must be submitted prior to contract execution.***

In accordance with Title 29, Chapter 69, Section 6960A.(a)(1), a contract relating to a public works project under § 6962 of Title 29 must include a craft training program for each craft in the project if at the time the contractor executes a public works contract, all of the following apply:

- a. A project meets the prevailing wage requirement under Section 6960 of Title 29.
- b. The contractor employs 10 or more total employees.
- c. The project is not a federal highway project, except for the project under Section 6962(c)(11) of Title 29.
- d. There is an apprenticeship program for a craft in the project on the list of crafts under Section 204(b)(2) of Title 19.

Pursuant to Title 29, Chapter 69, Section 6960A.(a)(2), ***a contractor must commit that all subcontractors provide craft training*** if paragraph (a)(1) of this section applies to the subcontractor. Failure to provide required craft training or payment on the project may subject the successful contractor and/or subcontractor(s) to penalties as outlined in Title 29, Chapter 69, Section 6960A.(d)(1)-(3).

Craft(s):

Contractor Name:

Contractor Address:

Contractor Program

Registration Number(s)

On this line also indicate whether DE, Other State (identify) or US Registration Number

Or

☐ A payment has been made in the amount established under Section 204(b)(2)b.2. of Title 19, for the craft into the Delaware Department of Labor’s Apprenticeship and Training Fund.

Or

☐ Craft Training requirements are not applicable because:

Authorized Representative (typed or printed): _____

Authorized Representative (signature): _____

Title: _____

State of Delaware)
County of _____) ss:

Before me, a notary public, in and for said county and state, personally appeared, _____, who acknowledged to me that she/he did execute the foregoing instrument on behalf of _____.

IN TESTIMONY WHEREOF, I have subscribed my name and affixed my official seal this _____ day of _____ 20____.

Notary Public
Commission Expires _____

THIS PAGE MUST BE SIGNED AND NOTARIZED TO BE CONSIDERED.

**SECTION 01 11 00
SUMMARY OF WORK
TABLE OF CONTENTS**

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 PROJECT INFORMATION
- 1.4 WORK COVERED BY CONTRACT DOCUMENTS
- 1.5 ACCESS TO SITE
- 1.6 COORDINATION WITH OCCUPANTS
- 1.7 WORK RESTRICTIONS
- 1.8 SPECIFICATION AND DRAWING CONVENTIONS

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 11 00
SUMMARY OF WORK

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes:

- 1. Project information.
- 2. Work covered by Contract Documents.
- 3. Work by Owner.
- 4. Access to site.
- 5. Coordination with occupants.
- 6. Work restrictions.
- 7. Specification and drawing conventions.

- B. Related Section:

- 1. Division 01 Section 01 50 00 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

1.3 PROJECT INFORMATION

- A. Project Identification: Indian River School District – Heat of Rejection Equipment Replacement.

- 1. Project Locations:

- a. George Washington Carver Educational Center, 30207 Frankford School Rd, Frankford, DE 19945
- b. Selbyville Middle School, 80 Bethany Road, Selbyville, DE 19975

- B. Owner: Indian River School District, 31 Hosier Street, Selbyville, Delaware 19975.

- 1. Owner's Representative: William (Joe) Dooley, Supervisor of Buildings and Grounds, 302-436-1000, william.dooley@irsd.k12.de.us

- C. M/E/P Engineer: Gipe Associates, Inc., 8719 Brooks Drive, Easton, MD 21601.

- 1. Engineer's Representative: David R. Hoffman, P.E. President, 410-822-8688; dhoffman@gipe.net

1.4 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Work of the Project is defined by the Contract Documents and consists of the following:
 - 1. The heat of rejection equipment replacements at two (2) schools. Project shall include, but not be limited to heat of rejection equipment replacement, closed circuit evaporative fluid cooler replacement, controls, insulation, piping, pumps, testing and balancing, chemical water treatment, commissioning, housekeeping pads, vibration isolation, and power connections. Refer to project alternates defined under Specification Section 01 23 00, "Alternates". The base bid shall consist of the work at one (1) school and alternate shall reflect the work at the second school.
- B. Type of Contract
 - 1. Project will be constructed under a single prime contract.

1.5 ACCESS TO SITE

- A. General: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section.
- B. Use of Site: Limit use of Project site to areas within the Contract limits indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
 - 1. Limits: Confine construction operations to the specific spaces indicated in all three (3) schools.
 - 2. Driveways, Walkways and Entrances: Keep driveways and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- C. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.

1.6 COORDINATION WITH OCCUPANTS

- A. Owner Limited Occupancy of Completed Areas of Construction: Owner reserves the right to occupy and to place and install equipment in completed portions of the Work, prior to Substantial Completion of the Work, provided such occupancy does not interfere with completion of the Work. Such placement of equipment and limited occupancy shall not constitute acceptance of the total Work.
 - 1. Engineer will prepare a Certificate of Substantial Completion for each specific portion of the Work to be occupied prior to Owner acceptance of the completed Work.

2. Obtain a Certificate of Occupancy from authorities having jurisdiction before limited Owner occupancy.
3. Before limited Owner occupancy, mechanical and electrical systems shall be fully operational, and required tests and inspections shall be successfully completed. On occupancy, Owner will operate and maintain mechanical and electrical systems serving occupied portions of Work.
4. On occupancy, Owner will assume responsibility for maintenance and custodial service for occupied portions of Work.

1.7 WORK RESTRICTIONS

- A. Work Restrictions, General: Comply with restrictions on construction operations.
 1. Comply with limitations on use of public streets and other requirements of authorities having jurisdiction.
- B. All finishes and floor must be protected as indicated on Contract Drawing.
- C. On-Site Work Hours: Limit work in the existing building to normal business working hours of 7:00 a.m. to 4:30 p.m., Monday through Friday, except as otherwise indicated.
 1. Weekend Hours: (As approved by the Owner)
 2. Early Morning Hours: (As approved by the Owner)
 3. Hours for Utility Shutdowns: (As approved by the Owner)
 4. Hours for Core Drilling and Other noisy activity: (As approved by the Owner)
 5. Lifting, crane operations, and overhead work shall not occur while staff are in the facility.
- D. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:
 1. Notify Owner not less than fourteen (14) days in advance of proposed utility interruptions.
 2. Obtain Owner's written permission before proceeding with utility interruptions.
- E. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner occupancy with Owner.
 1. Notify Owner not less than fourteen (14) days in advance of proposed disruptive operations.
 2. Obtain Owner's written permission before proceeding with disruptive operations.
- F. Nonsmoking Building: Smoking is not permitted within the building or within 25 feet (8 m) of entrances, operable windows, or outdoor air intakes.
- G. Controlled Substances: Use of tobacco products and other controlled substances within the existing building and on the Project site is not permitted.

- H. Employee Identification: Provide identification tags for Contractor personnel working on the Project site. Require personnel to utilize identification tags at all times. Contractor must provide required information to the Owner to allow proper background checks.
- I. Employee Screening: Comply with Owner's requirements regarding drug and background screening of Contractor personnel working on the Project site.
 - 1. Maintain list of approved screened personnel with Owner's Representative.

1.8 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
 - 1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
 - 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on the Drawings are described in detail in the Specifications. One or more of the following are used on the Drawings to identify materials and products:
 - 1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
 - 2. Abbreviations: Materials and products are identified by abbreviations.
 - 3. Keynoting: Materials and products are identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 01 14 00
WORK RESTRICTIONS
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 USE OF PREMISES
- 1.3 OCCUPANCY REQUIREMENTS

PART 2 PRODUCTS

NOT USED

PART 3 EXECUTION

NOT USED

THIS PAGE LEFT INTENTIONALLY BLANK

**SECTION 01 14 00
WORK RESTRICTIONS**

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 USE OF PREMISES

- A. Use of Site: Limit use of premises to work in areas indicated. Do not disturb portions of site beyond areas in which the Work is indicated.
 - 1. Limits: Confine constructions operations to the specific areas indicated in all three (3) schools.
 - 2. Owner Occupancy: Allow for Owner occupancy of site.
 - 3. Driveways and Entrances: Keep driveways and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- B. Use of Existing Building: Maintain existing buildings in a weathertight condition throughout construction period. Repair damage caused by construction operations. Protect buildings and occupants during construction period.
- C. Background Checks: All workers who perform work on the site shall be subject to a full background check.
- D. Any crane/rigging work shall be completed when schools are unoccupied during weekends or days when students are not on site.
- E. Electrical shutdowns shall occur during weekends, holidays, and "off-hours" when the schools are not in use.

1.3 OCCUPANCY REQUIREMENTS

- A. Full Owner Occupancy: Owner will occupy sites and existing buildings during entire construction period. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's operations.

HEAT OF REJECTION EQUIPMENT REPLACEMENT
(IRD25036-HVAC)

INDIAN RIVER SCHOOL DISTRICT
CARVER EC & SELBYVILLE MS

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

**SECTION 01 21 00
ALLOWANCES
TABLE OF CONTENTS**

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 SELECTIONS AND PURCHASE
- 1.4 SUBMITTALS
- 1.5 COORDINATION
- 1.6 CONTINGENCY ALLOWANCES
- 1.7 ADJUSTMENT OF ALLOWANCES

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

- 3.1 EXAMINATION
- 3.2 PREPARATION
- 3.3 SCHEDULE OF ALLOWANCES

**SECTION 01 21 00
ALLOWANCES**

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements governing allowances.
 - 1. Certain items are specified in the Contract Documents by allowances. Allowances have been established in lieu of additional requirements and to defer selection of actual materials and equipment to a later date when direction will be provided to the Contractor. If necessary, additional requirements will be issued by Change Order.
- B. Types of allowances include the following:
 - 1. Contingency allowances.
- C. Related Sections:
 - 1. Division 01 Section "Quality Requirements" for procedures governing the use of allowances for testing and inspecting.
 - 2. Divisions 02 through 28 Sections for items of Work covered by allowances.

1.3 SELECTION AND PURCHASE

- A. At the earliest practical date after award of the Contract, advise Engineer of the date when final selection and purchase of each product or system described by an allowance must be completed to avoid delaying the Work.
- B. At Engineer's request, obtain proposals for each allowance for use in making final selections. Include recommendations that are relevant to performing the Work.
- C. Purchase products and systems selected by Engineer from the designated supplier.

1.4 SUBMITTALS

- A. Submit proposals for purchase of products or systems included in allowances, in the form specified for Change Orders.
- B. Submit invoices or delivery slips to show actual quantities of materials delivered to the site for use in fulfillment of each allowance.

- C. Submit time sheets and other documentation to show labor time and cost for installation of allowance items that include installation as part of the allowance.
- D. Coordinate and process submittals for allowance items in same manner as for other portions of the Work.

1.5 COORDINATION

- A. Coordinate allowance items with other portions of the Work. Furnish templates as required to coordinate installation.

1.6 CONTINGENCY ALLOWANCES

- A. Use the contingency allowance only as directed by Engineer for Owner's purposes and only by Change Orders that indicate amounts to be charged to the allowance.
- B. Contractor's overhead, profit, and related costs for products and equipment ordered by Owner under the contingency allowance are included in the allowance and are not part of the Contract Sum. These costs include delivery, installation, insurance, equipment rental, and similar costs.
- C. Allowances authorizing use of funds from the contingency allowance will include Contractor's related costs and reasonable overhead and profit margins.
- D. At Project closeout, credit unused amounts remaining in the contingency allowance to Owner by Change Order.

1.7 ADJUSTMENT OF ALLOWANCES

- A. Allowance Adjustment: To adjust allowance amounts, prepare a Change Order proposal based on the difference between purchase amount and the allowance, multiplied by final measurement of work-in-place where applicable. If applicable, include reasonable allowances for cutting losses, tolerances, mixing wastes, normal product imperfections, and similar margins.
 - 1. Include installation costs in purchase amount only where indicated as part of the allowance.
 - 2. If requested, prepare explanation and documentation to substantiate distribution of overhead costs and other margins claimed.
 - 3. Submit substantiation of a change in scope of work, if any, claimed in Change Orders related to unit-cost allowances.
 - 4. Owner reserves the right to establish the quantity of work-in-place by independent quantity survey, measure, or count.
- B. Submit claims for increased costs because of a change in scope or nature of the allowance described in the Contract Documents, whether for the purchase order amount or Contractor's handling, labor, installation, overhead, and profit.
 - 1. Do not include Contractor's or subcontractor's indirect expense in the Change Order cost amount unless it is clearly shown that the nature or extent of work has changed from what could have been foreseen from information in the Contract Documents.

2. No change to Contractor's indirect expense is permitted for selection of higher- or lower-priced materials or systems of the same scope and nature as originally indicated.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine products covered by an allowance promptly on delivery for damage or defects. Return damaged or defective products to manufacturer for replacement.

3.2 PREPARATION

- A. Coordinate materials and their installation for each allowance with related materials and installations to ensure that each allowance item is completely integrated and interfaced with related work.

3.3 SCHEDULE OF ALLOWANCES

- A. Allowance No. 1: Contingency Allowance: Include a contingency allowance of \$15,000.00 for use according to Owner's instructions.

END OF SECTION

**SECTION 01 23 00
ALTERNATES
TABLE OF CONTENTS**

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 PROCEDURES

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

- 3.1 SCHEDULE OF ALTERNATES

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 23 00
ALTERNATES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for alternates.

1.3 DEFINITIONS

- A. Alternate: An amount proposed by bidders and stated on the Bid Form for certain work defined in the Bidding Requirements that may be added to or deducted from the base bid amount if Owner decides to accept a corresponding change either in the amount of construction to be completed or in the products, materials, equipment, systems, or installation methods described in the Contract Documents.
 - 1. Alternates described in this Section are part of the Work only if enumerated in the Agreement.
 - 2. The cost or credit for each alternate is the net addition to or deduction from the Contract Sum to incorporate alternate into the Work. No other adjustments are made to the Contract Sum.
 - 3. The costs for alternates shall include additional Bonds and Insurance costs as a results of project value increasing if alternate is accepted.

1.4 PROCEDURES

- A. Coordination: Modify or adjust affected adjacent work as necessary to completely integrate work of the alternate into Project.
 - 1. Include as part of each alternate, miscellaneous devices, accessory objects, and similar items incidental to or required for a complete installation whether or not indicated as part of alternate.
- B. Notification: Immediately following award of the Contract, notify each party involved, in writing, of the status of each alternate. Indicate if alternates have been accepted, rejected, or deferred for later consideration. Include a complete description of negotiated modifications to alternates.
- C. Execute accepted alternates under the same conditions as other work of the Contract.

- D. Schedule: A schedule of alternates is included at the end of this Section. Specification Sections referenced in schedule contain requirements for materials necessary to achieve the work described under each alternate.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF ALTERNATES

A. Alternate #1 – Selbyville Middle School

1. Base Bid: Provide all work associated with replacing the closed circuit evaporative fluid cooler system serving George Washington Carver Educational Center.
2. Alternate: Provide additional cost to perform all work associated with replacing the cooling tower system serving Selbyville Middle School.

END OF SECTION

SECTION 01 25 00
SUBSTITUTION PROCEDURES
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 SUBMITTALS
- 1.5 QUALITY ASSURANCE
- 1.6 PROCEDURES

PART 2 PRODUCTS

- 2.1 SUBSTITUTIONS

PART 3 EXECUTION (Not Used)

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 25 00
SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Sections:
 - 1. Division 01 Section 01 23 00 "Alternates" for products selected under an alternate.
 - 2. Division 01 Section 01 60 00 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.
 - 3. Divisions 02 through 28 Sections for specific requirements and limitations for substitutions.

1.3 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
 - 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
 - 2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required in order to meet other Project requirements but may offer advantage to Contractor or Owner.

1.4 SUBMITTALS

- A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use CSI Form 13.1A.
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.

- b. Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable specification section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. Certificates and qualification data, where applicable or requested.
 - g. List of similar installations for completed projects with project names and addresses and names and addresses of engineers, architects, and owners.
 - h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - i. Research reports evidencing compliance with building code in effect for Project.
 - j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
 - k. Cost information, including a proposal of change, if any, in the Contract Sum.
 - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
 - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
3. Engineer's Action: If necessary, Engineer will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Engineer will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
- a. Forms of Acceptance: Change Order, Construction Change Directive, or Engineer's Supplemental Instructions for minor changes in the Work.
 - b. Use product specified if Engineer does not issue a decision on use of a proposed substitution within time allocated.

1.5 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage qualified testing agency to perform compatibility tests recommended by manufacturers.

1.6 PROCEDURES

- A. Coordination: Modify or adjust affected work as necessary to integrate work of the approved substitutions.

PART 2 - PRODUCTS

2.1 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately upon discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
 - 1. Conditions: Engineer will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Engineer will return requests without action, except to record noncompliance with these requirements:
 - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Substitution request is fully documented and properly submitted.
 - c. Requested substitution will not adversely affect Contractor's construction schedule.
 - d. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - e. Requested substitution is compatible with other portions of the Work.
 - f. Requested substitution has been coordinated with other portions of the Work.
 - g. Requested substitution provides specified warranty.
 - h. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Not allowed, unless otherwise indicated.

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK



SUBSTITUTION REQUEST (After the Bidding Phase)

Project: _____ Substitution Request Number: _____

From: _____
To: _____ Date: _____

A/E Project Number: _____
Re: _____ Contract For: _____

Specification Title: _____ Description: _____
Section: _____ Page: _____ Article/Paragraph: _____

Proposed Substitution: _____
Manufacturer: _____ Address: _____ Phone: _____
Trade Name: _____ Model No.: _____
Installer: _____ Address: _____ Phone: _____
History: ☐ New product ☐ 2-5 years old ☐ 5-10 yrs old ☐ More than 10 years old

Differences between proposed substitution and specified product: _____

☐ Point-by-point comparative data attached - REQUIRED BY A/E

Reason for not providing specified item: _____

Similar Installation:

Project: _____ Architect: _____
Address: _____ Owner: _____
_____ Date Installed: _____

Proposed substitution affects other parts of Work: ☐ No ☐ Yes; explain _____

Savings to Owner for accepting substitution: _____ (\$ _____).

Proposed substitution changes Contract Time: ☐ No ☐ Yes [Add] [Deduct] _____ days.

Supporting Data Attached: ☐ Drawings ☐ Product Data ☐ Samples ☐ Tests ☐ Reports ☐ _____

SUBSTITUTION REQUEST (Continued)

The Undersigned certifies:

- Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.
- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay progress schedule.
- Cost data as stated above is complete. Claims for additional costs related to accepted substitution which may subsequently become apparent are to be waived.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.
- Coordination, installation, and changes in the Work as necessary for accepted substitution will be complete in all respects.

Submitted by: _____

Signed by: _____

Firm: _____

Address: _____

Telephone: _____

Attachments: _____

A/E's REVIEW AND ACTION

- ☐ Substitution approved - Make submittals in accordance with Specification Section 01330.
☐ Substitution approved as noted - Make submittals in accordance with Specification Section 01330.
☐ Substitution rejected - Use specified materials.
☐ Substitution Request received too late - Use specified materials.

Signed by: _____

Date: _____

Additional Comments: ☐ Contractor ☐ Subcontractor ☐ Supplier ☐ Manufacturer ☐ A/E ☐ _____

SECTION 01 26 00
CONTRACT MODIFICATION PROCEDURES
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 MINOR CHANGES IN THE WORK
- 1.4 PROPOSAL REQUESTS
- 1.5 ADMINISTRATIVE CHANGE ORDERS
- 1.6 CHANGE ORDER PROCEDURES
- 1.7 CONSTRUCTION CHANGE DIRECTIVE

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

THIS PAGE LEFT INTENTIONALLY BLANK

**SECTION 01 26 00
CONTRACT MODIFICATION PROCEDURES**

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements for handling and processing Contract modifications.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 60 00 "Product Requirements" for administrative procedures for handling requests for substitutions made after Contract award.

1.3 MINOR CHANGES IN THE WORK

- A. Engineer will issue supplemental instructions authorizing Minor Changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Engineer will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Proposal Requests issued by Engineer are for information only. Do not consider them instructions either to stop work in progress or to execute the proposed change.
 - 2. Within (7) seven days after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and additional supervision directly attributable to the change.

- d. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- B. Contractor-Initiated Proposals: If latent or unforeseen conditions require modifications to the Contract, Contractor may propose changes by submitting a request for a change to Engineer.
 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 4. Include costs of labor and supervision directly attributable to the change.
 5. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 6. Comply with requirements in Division 01 Section 01 60 00 "Product Requirements" if the proposed change requires substitution of one product or system for product or system specified.
- C. The Proposal Request shall include the Allowable Overhead and Profit Mark-Up scheduled in the General Conditions.

1.5 ADMINISTRATIVE CHANGE ORDERS

- A. Allowance Adjustment: Refer to Division 01 Section 01 21 16 "Contingency Allowances" for administrative procedures for preparation of Change Order Proposal for adjusting the Contract Sum to reflect actual costs of allowances.

1.6 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Proposal Request, the Engineer will issue a Change Order for signatures of Owner, Contractor and Engineer.

1.7 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Engineer may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.

- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 29 00
PAYMENT PROCEDURES
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 SCHEDULE OF VALUES
- 1.5 APPLICATIONS FOR PAYMENT

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 29 00
PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 26 00 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
 - 2. Division 01 Section 01 32 00 "Construction Progress Documentation" for administrative requirements governing preparation and submittal of Contractor's Construction Schedule and Submittals Schedule.
 - 3. Division 01 Section 01 33 00 "Submittal Procedures" for administrative requirements governing the preparation and submittal of submittal schedule.

1.3 DEFINITIONS

- A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the Schedule of Values with preparation of Contractor's Construction Schedule.
 - 1. Correlate line items in the Schedule of Values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with Continuation Sheets.
 - b. Submittals Schedule.
 - c. Contractor's Construction Schedule.
 - 2. Submit the Schedule of Values to Engineer at earliest possible date but no later than the Work Initiation Conference.
 - 3. Subschedules: Where the Work is separated into phases requiring separately phased payments, provide subschedules showing values correlated with each phase of payment.

- B. Format and Content: Use the Project Manual table of contents as a guide to establish line items for the Schedule of Values. Provide at least one line item for each Specification Section.
1. Identification: Include the following Project identification on the Schedule of Values:
 - a. Project name and location.
 - b. Name of Engineer.
 - c. Engineer's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 2. Submit draft of AIA Document G703 Continuation Sheets.
 3. Arrange the Schedule of Values in tabular form with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value.
 - 1) Percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
 4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project Manual table of contents. Provide several line items for principal subcontract amounts, where appropriate.
 5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
 6. Provide a separate line item in the Schedule of Values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site. If specified, include evidence of insurance or bonded warehousing.
 7. Provide separate line items in the Schedule of Values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
 8. Allowances: Provide a separate line item in the schedule of values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.

9. Purchase Contracts: Provide a separate line item in the schedule of values for each purchase contract. Show line-item value of purchase contract. Indicate owner payments or deposits, if any, and balance to be paid by Contractor.
10. Each item in the Schedule of Values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
 - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the Schedule of Values or distributed as general overhead expense, at Contractor's option.
11. Schedule Updating: Update and resubmit the Schedule of Values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Engineer and paid for by Owner.
 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction Work covered by each Application for Payment is the period indicated in the Agreement.
- C. Payment Application Forms: Use AIA Document G702 and AIA Document G703 Continuation Sheets as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Engineer will return incomplete applications without action.
 1. Entries shall match data on the Schedule of Values and Contractor's Construction Schedule. Use updated schedules if revisions were made.
 2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
- E. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.
 1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment, for stored materials.
 2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
 3. Provide summary documentation for stored materials indicating the following:

- a. Materials previously stored and included in previous Applications for Payment.
 - b. Work completed for this Application utilizing previously stored materials.
 - c. Additional materials stored with this Application.
 - d. Total materials remaining stored, including materials with this Application.
- F. Transmittal: Submit 3 signed and notarized original copies of each Application for Payment to Engineer by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's liens from subcontractors, sub-subcontractors, and suppliers for construction period covered by the previous application.
1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
 2. When an application shows completion of an item, submit conditional final or full waivers.
 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 4. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
- H. Waiver Forms: Submit waivers of lien on forms, executed in a manner acceptable to Owner.
- I. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
1. List of subcontractors.
 2. Schedule of Values.
 3. Contractor's Construction Schedule (preliminary if not final).
 4. Products list.
 5. Submittals Schedule (preliminary if not final).
 6. List of Contractor's staff assignments.
 7. List of Contractor's principal consultants.
 8. Copies of building permits.
 9. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 10. Initial progress report.
 11. Report of preconstruction conference.
 12. Certificates of insurance and insurance policies.
 13. Performance and payment bonds.
 14. Data needed to acquire Owner's insurance.
- J. Application for Payment at Substantial Completion and in accordance with the applicable sections in the Owner's General Terms and Conditions: After issuing the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.

1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- K. Final Payment Application and in accordance with the applicable sections in the Owner's General Terms and Conditions: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements.
 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 3. Updated final statement, accounting for final changes to the Contract Sum.
 4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
 5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
 6. AIA Document G707, "Consent of Surety to Final Payment."
 7. Evidence that claims have been settled.
 8. Final, liquidated damages settlement statement.
 9. Final credit for unused allowance amount.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 31 00
PROJECT MANAGEMENT AND COORDINATION
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 COORDINATION
- 1.5 KEY PERSONNEL
- 1.6 REQUESTS FOR INFORMATION (RFIs)
- 1.7 PROJECT MEETINGS
- 1.8 SUBMITTALS
- 1.9 ADMINISTRATIVE AND SUPERVISORY PERSONNEL

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 31 00
PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
1. General project coordination procedures.
 2. Administrative and supervisory personnel.
 3. Requests for Information (RFIs).
 4. Project meetings.
- B. Each contractor shall participate in coordination requirements. Certain areas of responsibility will be assigned to a specific contractor.
- C. Related Sections include the following:
1. Division 01 Section 01 32 00 "Construction Progress Documentation" for preparing and submitting Contractor's Construction Schedule (Accepted Baseline and Monthly Updates).
 2. Division 01 Section 01 73 00 "Execution Requirements" for procedures for coordinating general installation and field-engineering services.
 3. Division 01 Section 01 77 00 "Closeout Procedures" for coordinating Contract closeout.

1.3 DEFINITIONS

- A. RFI: Request from Owner, Engineer, or Contractor seeking information from each other during construction.

1.4 COORDINATION

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections that depend on each other for proper installation, connection, and operation.
1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.

2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. Coordination: Each contractor shall coordinate its construction operations with those of other contractors and entities to ensure efficient and orderly installation of each part of the Work. Each contractor shall coordinate its operations with operations, included in different Sections that depend on each other for proper installation, connection, and operation.
1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 2. Coordinate installation of different components with other contractors to ensure maximum accessibility for required maintenance, service, and repair.
 3. Make adequate provisions to accommodate items scheduled for later installation.
 4. Where availability of space is limited, coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair of all components, including mechanical and electrical.
- C. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- D. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
1. Preparation of Contractor's Construction Schedule (Accepted Baseline and Monthly Updates).
 2. Preparation of the Schedule of Values.
 3. Installation and removal of temporary facilities and controls.
 4. Delivery and processing of submittals.
 5. Progress meetings.
 6. Pre-installation conferences.
 7. Project closeout activities.
 8. Startup and adjustment of systems.
- E. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials.
1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. Refer to other Sections for disposition of salvaged materials that are designated as Owner's property.

1.5 KEY PERSONNEL

- A. Key Personnel Names: Within 15 days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home, office, and cellular telephone numbers and email addresses. Provide names, addresses, and telephone numbers of individuals assigned as standbys in the absence of individuals assigned to Project.
1. Post copies of list in project meeting room, in temporary field office, and by each temporary telephone. Keep list current at all times.

1.6 REQUESTS FOR INFORMATION (RFIs)

- A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
1. Engineer will return RFIs submitted to Engineer by other entities controlled by Contractor with no response.
 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
1. Project name.
 2. Project number.
 3. Date.
 4. Name of Contractor.
 5. Name of Engineer.
 6. RFI number, numbered sequentially.
 7. RFI subject.
 8. Specification Section number and title and related paragraphs, as appropriate.
 9. Drawing number and detail references, as appropriate.
 10. Field dimensions and conditions, as appropriate.
 11. Contractor's suggested resolution. If Contractor's solution(s) impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 12. Contractor's signature.
 13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
 - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- C. RFI Forms: CSI Form 13.2A.
- D. Engineer's Action: Engineer will review each RFI, determine action required, and respond. Allow seven working days for Engineer's response for each RFI. RFIs received by Engineer after 1:00 p.m. will be considered as received the following working day.

1. The following RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.
 - c. Requests for coordination information already indicated in the Contract Documents.
 - d. Requests for adjustments in the Contract Time or the Contract Sum.
 - e. Requests for interpretation of Engineer's actions on submittals.
 - f. Incomplete RFIs or inaccurately prepared RFIs.
2. Engineer's action may include a request for additional information, in which case Engineer's time for response will date from time of receipt of additional information.
3. Engineer's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Division 01 Section 01 26 00 "Contract Modification Procedures."
 - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Engineer in writing within 10 days of receipt of the RFI response.
- E. On receipt of Engineer's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Engineer within seven days if Contractor disagrees with response.
- F. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Use CSI Log Form 13.2B. Include the following:
 1. Project name.
 2. Name and address of Contractor.
 3. Name and address of Engineer.
 4. RFI number including RFIs that were dropped and not submitted.
 5. RFI description.
 6. Date the RFI was submitted.
 7. Date Engineer's response was received.
 8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
 9. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

1.7 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site, unless otherwise indicated.
 1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Engineer of scheduled meeting dates and times.
 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.

3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Engineer, within three days of the meeting.
- B. Preconstruction Conference: Engineer will schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Engineer, but no later than 15 days after execution of the Agreement.
1. Conduct the conference to review responsibilities and personnel assignments.
 2. Attendees: Authorized representatives of Owner, Engineer, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 3. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Tentative construction schedule.
 - b. Phasing.
 - c. Critical work sequencing and long-lead items.
 - d. Designation of key personnel and their duties.
 - e. Lines of communications.
 - f. Procedures for processing field decisions and Change Orders.
 - g. Procedures for RFIs.
 - h. Procedures for testing and inspecting.
 - i. Procedures for processing Applications for Payment.
 - j. Distribution of the Contract Documents.
 - k. Submittal procedures.
 - l. Preparation of record documents.
 - m. Use of the premises and existing building.
 - n. Work restrictions.
 - o. Working hours.
 - p. Owner's occupancy requirements.
 - q. Responsibility for temporary facilities and controls.
 - r. Procedures for moisture and mold control.
 - s. Procedures for disruptions and shutdowns.
 - t. Construction waste management and recycling.
 - u. Parking availability.
 - v. Office, work, and storage areas.
 - w. Equipment deliveries and priorities.
 - x. First aid.
 - y. Security.
 - z. Progress cleaning.
 4. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and

- installations that have preceded or will follow, shall attend the meeting. Advise Engineer of scheduled meeting dates.
2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
 - a. Contract Documents.
 - b. Options.
 - c. Related RFIs.
 - d. Related Change Orders.
 - e. Purchases.
 - f. Deliveries.
 - g. Submittals.
 - h. Review of mockups.
 - i. Possible conflicts.
 - j. Compatibility problems.
 - k. Time schedules.
 - l. Weather limitations.
 - m. Manufacturer's written recommendations.
 - n. Warranty requirements.
 - o. Compatibility of materials.
 - p. Acceptability of substrates.
 - q. Temporary facilities and controls.
 - r. Space and access limitations.
 - s. Regulations of authorities having jurisdiction.
 - t. Testing and inspecting requirements.
 - u. Installation procedures.
 - v. Coordination with other work.
 - w. Required performance results.
 - x. Protection of adjacent work.
 - y. Protection of construction and personnel.
 3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
 4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
 5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Project Closeout Conference: Schedule and conduct a Project closeout conference, at a time convenient to Owner and Engineer, but no later than 30 days prior to the scheduled date of Substantial Completion.
1. Conduct the conference to review requirements and responsibilities related to Project closeout.
 2. Attendees: Authorized representatives of Owner, Engineer, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the meeting. Participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
 3. Agenda: Discuss items of significance that could affect or delay Project closeout, including the following:

- a. Preparation of record documents.
 - b. Procedures required prior to inspection for Substantial Completion and for final inspection for acceptance.
 - c. Submittal of written warranties.
 - d. Requirements for preparing sustainable design documentation.
 - e. Requirements for preparing operations and maintenance data.
 - f. Requirements for demonstration and training.
 - g. Preparation of Contractor's punch list.
 - h. Procedures for processing Applications for Payment at Substantial Completion and for final payment.
 - i. Submittal procedures.
 - j. Coordination of separate contracts.
 - k. Owner's partial occupancy requirements.
 - l. Installation of Owner's furniture, fixtures, and equipment.
 - m. Responsibility for removing temporary facilities and controls.
 4. Minutes: Entity conducting meeting will record and distribute meeting minutes.
- E. Progress Meetings: Conduct progress meetings at regular intervals.
1. Coordinate dates of meetings with preparation of payment requests.
 2. Attendees: In addition to representatives of Owner and Engineer, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
 3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - 1) Review schedule for next period.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.
 - 6) Access.
 - 7) Site utilization.
 - 8) Temporary facilities and controls.
 - 9) Progress cleaning.
 - 10) Quality and work standards.

- 11) Status of correction of deficient items.
 - 12) Field observations.
 - 13) Status of RFIs.
 - 14) Status of proposal requests.
 - 15) Pending changes.
 - 16) Status of Change Orders.
 - 17) Pending claims and disputes.
 - 18) Documentation of information for payment requests.
4. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
 - a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.
- F. Coordination Meetings: Conduct Project coordination meetings at regular intervals. Project coordination meetings are in addition to specific meetings held for other purposes, such as progress meetings and preinstallation conferences.
1. Attendees: In addition to representatives of Owner and Engineer, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meetings shall be familiar with Project and authorized to conclude matters relating to the Work.
 2. Agenda: Review and correct or approve minutes of the previous coordination meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Combined Contractor's Construction Schedule: Review progress since the last coordination meeting. Determine whether each contract is on time, ahead of schedule, or behind schedule, in relation to combined Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - b. Schedule Updating: Revise combined Contractor's construction schedule after each coordination meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with report of each meeting.
 - c. Review present and future needs of each contractor present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.
 - 6) Access.
 - 7) Site utilization.
 - 8) Temporary facilities and controls.
 - 9) Work hours.

- 10) Hazards and risks.
 - 11) Progress cleaning.
 - 12) Quality and work standards.
 - 13) Change Orders.
3. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.

1.8 SUBMITTALS

A. Contractor Deliverables:

B. Monthly Progress Report Deliverables: Prepare and submit Monthly Deliverables as described below:

1. Project Narrative providing executive summary, any schedule deviations, and current issues.
2. Update Schedule providing status of individual Activity Time and Cost Progress projected to end of month.
3. Safety Log providing to-date summary lists of incidents or illnesses.
4. Submittal Log.
5. RFI Log.
6. Change Order Log.
7. Quality Assurance/Quality Control Log, with summary statement.

C. Coordination Drawings: Prepare Coordination Drawings.

1. Content: Project-specific information, drawn accurately to scale. Do not base Coordination Drawings on reproductions of the Contract Documents or standard printed data. Include the following information, as applicable:
 - a. Indicate functional and spatial relationships of components of Civil, mechanical, and electrical systems.
 - b. Indicate required installation sequences.
 - c. Indicate dimensions shown on the Contract Drawings and make specific note of dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternate sketches to Engineer for resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.
2. Sheet Size: At least 8-1/2 by 11 inches (215 by 280 mm) but no larger than 30 by 40 inches (750 by 1000 mm).
3. Number of Copies: Submit two opaque copies of each submittal. Engineer will return one copy.
 - a. Submit five copies where Coordination Drawings are required for operation and maintenance manuals. Engineer will retain two copies; remainder will be returned.
4. Refer to individual Sections for Coordination Drawing requirements for Work in those Sections.

- D. Key Personnel Names: Within 15 days of receiving Notice To Proceed, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home and office telephone numbers. Provide names, addresses, and telephone numbers of individuals assigned as standbys in the absence of individuals assigned to Project.
1. Post copies of list in Project meeting room, in temporary field office, and by each temporary telephone. Keep list current at all times.

1.9 ADMINISTRATIVE AND SUPERVISORY PERSONNEL

- A. General: In addition to Project superintendent, provide other administrative and supervisory personnel as required for proper performance of the Work.
1. Include special personnel required for coordination of operations with other contractors.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 01 32 00
CONSTRUCTION PROGRESS DOCUMENTATION
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 INFORMATIONAL SUBMITTALS
- 1.5 SUBMITTALS
- 1.6 QUALITY ASSURANCE
- 1.7 COORDINATION

PART 2 PRODUCTS

- 2.1 SUBMITTALS SCHEDULE
- 2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL
- 2.3 REPORTS

PART 3 EXECUTION

- 3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 32 00
CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:

- 1. Baseline Construction Schedule.
- 2. Update Construction Schedule.
- 3. Submittals Schedule.
- 4. Daily construction reports.
- 5. Material location reports.
- 6. Field condition reports.
- 7. Special reports.

- B. Related Sections include the following:

- 1. Division 01 Section 01 29 00 "Payment Procedures" for submitting the Schedule of Values.
- 2. Division 01 Section 01 31 00 "Project Management and Coordination" for submitting and distributing meeting and conference minutes.
- 3. Division 01 Section 01 33 00 "Submittal Procedures" for submitting schedules and reports.
- 4. Division 01 Section 01 40 00 "Quality Requirements" for submitting a schedule of tests and inspections.

1.3 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.

- 1. Critical activities are activities on the critical path. They must start and finish on the planned early start and finish times.
- 2. Predecessor Activity: An activity that precedes another activity in the network.
- 3. Successor Activity: An activity that follows another activity in the network.

- B. Cost Loading: The allocation of the Schedule of Values for the completion of an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum, unless otherwise approved by Engineer.
- C. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.
- D. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- E. Days: Unit of time duration in calendar days, unless specifically indicated to be work days.
- F. Event: The starting or ending point of an activity.
- G. Float: The measure of leeway in starting and completing an activity.
 - 1. Float time belongs to Owner.
 - 2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
 - 3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.
- H. Fragment: A partial or fragmentary network that breaks down activities into smaller activities for greater detail.
- I. Major Area: A story of construction, a separate building, or a similar significant construction element.
- J. Milestone: A key or critical point in time for reference or measurement.

1.4 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
 - 1. PDF electronic file.
- B. Start-up construction schedule.
 - 1. Approval of cost-loaded start-up construction schedule will not constitute approval of schedule of values for cost-loaded activities.
- C. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
 - 1. Submit a working electronic copy of schedule, using software indicated, and labeled to comply with requirements for submittals. Include type of schedule (initial or updated) and date on label.
- D. CPM Reports: Concurrent with CPM schedule, submit each of the following reports. Format for each activity in reports shall contain activity number, activity description, cost and resource

loading, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float in calendar days.

1. Activity Report: List of all activities sorted by activity number and then early start date, or actual start date if known.
 2. Logic Report: List of preceding and succeeding activities for all activities, sorted in ascending order by activity number and then early start date, or actual start date if known.
 3. Total Float Report: List of all activities sorted in ascending order of total float.
- E. Field Condition Reports: Submit at time of discovery of differing conditions.
- F. Special Reports: Submit at time of unusual event.
- G. Qualification Data: For scheduling consultant.

1.5 SUBMITTALS

- A. Submittals Schedule: Submit three copies of schedule. Arrange the following information in a tabular format:
1. Scheduled date for first submittal.
 2. Specification Section number and title.
 3. Submittal category (action or informational).
 4. Name of subcontractor.
 5. Description of the Work covered.
 6. Scheduled date for Engineer's final release or approval.
- B. Baseline Construction Schedule: Submit two opaque copies.
1. Approval of cost-loaded Baseline Construction Schedule will not constitute approval of Schedule of Values for cost-loaded activities.
- C. Update Construction Schedule: Submit two opaque copies of Update Construction Schedule, large enough to show entire schedule for entire construction period.
1. Submit an electronic copy of schedule, using software indicated, on CD-R, and labeled to comply with requirements for submittals. Include type of schedule (Initial or Updated) and date on label.
- D. Daily Construction Reports: Submit two copies at monthly intervals.
- E. Material Location Reports: Submit two copies at monthly intervals.
- F. Field Condition Reports: Submit two copies at time of discovery of differing conditions.

1.6 QUALITY ASSURANCE

- A. Scheduling Consultant Qualifications: An experienced specialist in CPM scheduling and reporting, with capability of producing CPM reports and diagrams within 24 hours of Engineer's request.

- B. Prescheduling Conference: Conduct conference at Project site to comply with requirements in Division 01 Section 01 31 00 "Project Management and Coordination." Review methods and procedures related to the preliminary construction schedule and Contractor's construction schedule, including, but not limited to, the following:
1. Review software limitations and content and format for reports.
 2. Verify availability of qualified personnel needed to develop and update schedule.
 3. Review delivery dates for Owner-furnished products.
 4. Review schedule for work of Owner's separate contracts.
 5. Review time required for review of submittals and resubmittals.
 6. Review requirements for tests and inspections by independent testing and inspecting agencies.
 7. Review time required for completion and startup procedures.
 8. Review and finalize list of construction activities to be included in schedule.
 9. Review submittal requirements and procedures.
 10. Review procedures for updating schedule.

1.7 COORDINATION

- A. Coordinate preparation and processing of schedules and reports with performance of construction activities and with scheduling and reporting of separate contractors.
- B. Coordinate Contractor's Baseline and Update Construction Schedules with the Schedule of Values, list of subcontracts, Submittals Schedule, progress reports, payment requests, and other required schedules and reports.
1. Secure time commitments for performing critical elements of the Work from parties involved.
 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 SUBMITTALS SCHEDULE

- A. Preparation: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, resubmittal, ordering, manufacturing, fabrication, and delivery when establishing dates.
1. Coordinate Submittals Schedule with list of subcontracts, the Schedule of Values, and Contractor's Baseline and Update Construction Schedule.
 2. Initial Submittal: Submit concurrently with preliminary bar-chart schedule. Include submittals required during the first 60 days of construction. List those required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
 - a. At Contractor's option, show submittals on the Baseline Construction Schedule, instead of tabulating them separately.

3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's Baseline Construction Schedule.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Procedures: Comply with procedures contained in AGC's "Construction Planning & Scheduling."
- B. Contractor's Construction Schedule Acceptance is represented in two forms: 1) Accepted Baseline Schedule, and 2) Accepted Monthly Update Schedule.
- C. Time Frame: Extend schedule from date established for the Notice to Proceed to date of Substantial Completion.
 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- D. Activities: Treat each story or separate area as a separate numbered activity for each principal element of the Work. Comply with the following:
 1. Activity Duration: Define activities so no activity is longer than 30 days, unless specifically allowed by Engineer.
 2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 30 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
 - a. Cooling Towers/Closed Circuit Evaporative Fluid Coolers
 - b. Electrical Gear
 - c. ATC Controls
 - d. Pumps
 - e. Variable Frequency Drives
 3. Submittal Review Time: Include review and re-submittal times indicated in Division 01 Section 01 33 00 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with Submittals Schedule.
 4. Startup and Testing Time: Include not less than 14 days for startup and testing.
 5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Engineer's administrative procedures necessary for certification of Substantial Completion.
 6. Punch List and Final Completion: Include not more than 30 days for punch list and final completion.
- E. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
 1. Phasing: Arrange list of activities on schedule by phase.
 2. Work under More Than One Contract: Include a separate activity for each contract.
 3. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.

4. Work Restrictions: Show the effect of the following items on the schedule:
 - a. Coordination with existing construction.
 - b. Limitations of continued occupancies.
 - c. Uninterruptible services.
 - d. Partial occupancy before Substantial Completion.
 - e. Use of premises restrictions.
 - f. Provisions for future construction.
 - g. Seasonal variations.
 - h. Environmental control.
 5. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:
 - a. Subcontract awards.
 - b. Submittals.
 - c. Purchases.
 - d. Mockups.
 - e. Fabrication.
 - f. Sample testing.
 - g. Deliveries.
 - h. Installation.
 - i. Tests and inspections.
 - j. Adjusting.
 - k. Curing.
 - l. Startup and placement into final use and operation.
 6. Construction Areas: Identify each major area of construction for each major portion of the Work. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities to provide for the following:
 - a. Refurbishment Completion.
 - b. Permanent space enclosure.
 - c. Completion of mechanical installation.
 - d. Completion of ductwork.
 - e. Completion of electrical installation.
 - f. Completion of testing/balancing.
 - g. Substantial Completion.
- F. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Equipment Deliveries Complete, Equipment in Place, Systems Ready for Test, Substantial Completion, and Final Completion
- G. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using fragments to demonstrate the effect of the proposed change on the overall project schedule.
- H. Cost Correlation: At the head of schedule, provide a cost correlation line, indicating planned and actual costs. On the line, show dollar volume of the Work performed as of dates used for preparation of payment requests.

1. Refer to Division 01 Section 01 29 00 "Payment Procedures" for cost reporting and payment procedures.
- I. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
 1. Unresolved issues.
 2. Unanswered RFIs.
 3. Rejected or unreturned submittals.
 4. Notations on returned submittals.
- J. Recovery Schedule: When periodic update indicates the Work is fourteen (14) or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule. Indicate changes to working hours, working days, crew sizes, and equipment required to achieve compliance, and date by which recovery will be accomplished.
- K. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.
 1. Utilize Microsoft Project, Primavera, or Prolog, for Windows XP operating system.

2.3 REPORTS

- A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:
 1. List of subcontractors at Project site.
 2. List of separate contractors at Project site.
 3. Approximate count of personnel at Project site.
 4. Equipment at Project site.
 5. Material deliveries.
 6. High and low temperatures and general weather conditions.
 7. Accidents.
 8. Meetings and significant decisions.
 9. Unusual events (refer to special reports).
 10. Stoppages, delays, shortages, and losses.
 11. Emergency procedures.
 12. Orders and requests of authorities having jurisdiction.
 13. Change Orders received and implemented.
 14. Construction Change Directives received and implemented.
 15. Services connected and disconnected.
 16. Equipment or system tests and startups.
 17. Substantial Completions authorized.
- B. Material Location Reports: At monthly intervals, prepare and submit a comprehensive list of materials delivered to and stored at Project site. List shall be cumulative, showing materials previously reported plus items recently delivered. Include with list a statement of progress on and delivery dates for materials or items of equipment fabricated or stored away from Project site.

- C. Field Condition Reports: Immediately on discovery of a difference between field conditions and the Contract Documents, prepare and submit a detailed report. Submit with a request for interpretation on CSI Form 13.2A. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.
 - 1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
 - 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
 - 3. As the Work progresses, indicate Actual Completion percentage for each activity.
- B. Distribution: Distribute copies of approved schedule to Engineer, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
 - 1. Post copies in Project meeting rooms and temporary field offices.
 - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION

**SECTION 01 33 00
SUBMITTAL PROCEDURES
TABLE OF CONTENTS**

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 SUBMITTAL PROCEDURES
- 1.5 CONTRACTOR'S USE OF ENGINEER'S CAD FILES

PART 2 PRODUCTS

- 2.1 ACTION SUBMITTALS
- 2.2 INFORMATIONAL SUBMITTALS

PART 3 EXECUTION

- 3.1 CONTRACTOR'S REVIEW

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 33 00
SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 29 00 "Payment Procedures" for submitting Applications for Payment and the Schedule of Values.
 - 2. Division 01 Section 01 31 00 "Project Management and Coordination" for submitting and distributing meeting and conference minutes and for submitting Coordination Drawings.
 - 3. Division 01 Section 01 32 00 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's Construction Schedule and the Submittals Schedule.
 - 4. Division 01 Section 01 77 00 "Closeout Procedures" for submitting warranties.
 - 5. Division 01 Section 01 78 39 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
 - 6. Division 01 Section 01 78 23 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
 - 7. Division 01 Section 01 79 00 "Demonstration and Training" for training of Owner's personnel.
 - 8. Divisions 02 through 26 Sections for specific requirements for submittals in those Sections.

1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information that requires Engineer's responsive action.
- B. Informational Submittals: Written information that does not require Engineer's responsive action. Submittals may be rejected for not complying with requirements.
- C. File Transfer Protocol (FTP): Communications protocol that enables transfer of files to and from another computer over a network and that serves as the basis for standard Internet protocols. An FTP site is a portion of a network located outside of network firewalls within which internal and external users are able to access files.

- D. Portable Document Format (PDF): An open standard file format licensed by Adobe Systems used for representing documents in a device-independent and display resolution-independent fixed-layout document format.

1.4 SUBMITTAL PROCEDURES

- A. General: Electronic copies of CAD Drawings of the Contract Drawings will be provided by Engineer for Contractor's use in preparing submittals at the cost identified in Paragraph 1.5.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Engineer reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Submittals Schedule: Comply with requirements in Division 01 Section 01 32 00 "Construction Progress Documentation" for list of submittals and time requirements for scheduled performance of related construction activities.
- D. Processing Time: Allow enough time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Engineer's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - 1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Engineer will advise Contractor when a submittal being processed must be delayed for coordination.
 - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 - 3. Resubmittal Review: Allow 15 days for review of each resubmittal.
 - 4. Concurrent Consultant Review: Where the Contract Documents indicate that submittals may be transmitted simultaneously to Engineer and to Engineer's consultants, allow 15 days for review of each submittal. Submittal will be returned to Engineer before being returned to Contractor.
- E. Identification: Place a permanent label or title block on each submittal for identification.
 - 1. Indicate name of firm or entity that prepared each submittal on label or title block.
 - 2. Provide a space approximately 6 by 8 inches (150 by 200 mm) on label or beside title block to record Contractor's review and approval markings and action taken by Engineer.
 - 3. Include the following information on label for processing and recording action taken:
 - a. Project name.
 - b. Date.

- c. Name and address of Engineer.
 - d. Name and address of Contractor.
 - e. Name and address of subcontractor.
 - f. Name and address of supplier.
 - g. Name of manufacturer.
 - h. Submittal number or other unique identifier, including revision identifier.
 - 1) Submittal number shall use Specification Section number followed by a decimal point and then a sequential number (e.g., 06100.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., 06100.01.A).
 - i. Number and title of appropriate Specification Section.
 - j. Drawing number and detail references, as appropriate.
 - k. Location(s) where product is to be installed, as appropriate.
 - l. Other necessary identification.
- F. Deviations: Highlight, encircle, or otherwise specifically identify deviations from the Contract Documents on submittals.
- G. Additional Copies: Unless additional copies are required for final submittal, and unless Engineer observes noncompliance with provisions in the Contract Documents, initial submittal may serve as final submittal.
- 1. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Engineer.
 - 2. Additional copies submitted for maintenance manuals will be marked with action taken and will be returned.
- H. Transmittal: Package each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Engineer will return submittals, without review, received from sources other than Contractor.
- 1. Transmittal Form: Use CSI Form 12.1A found in Section 00 62 11 "Submittal Transmittal Form".
 - 2. Transmittal Form: Provide locations on form for the following information:
 - a. Project name.
 - b. Date.
 - c. Destination (To:).
 - d. Source (From:).
 - e. Names of subcontractor, manufacturer, and supplier.
 - f. Category and type of submittal.
 - g. Submittal purpose and description.
 - h. Specification Section number and title.
 - i. Drawing number and detail references, as appropriate.
 - j. Transmittal number.
 - k. Submittal and transmittal distribution record.
 - l. Remarks.
 - m. Signature of transmitter.

3. On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Engineer on previous submittals, and deviations from requirements in the Contract Documents, including minor variations and limitations. Include same label information as related submittal.
- I. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
 1. Note date and content of previous submittal.
 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 3. Resubmit submittals until they are marked "Approved" or "Approved as Noted."
 4. For any submittal requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.
 - J. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
 - K. Use for Construction: Use only final submittals with mark indicating "Approved" taken by Engineer
- 1.5 CONTRACTOR'S USE OF ENGINEER'S CAD FILES
- A. General: At Contractor's written request, copies of Engineer's CAD files will be provided to Contractor for Contractor's use in connection with Project, subject to the following conditions:
 - B. General: Electronic copies of CAD Drawings of the Contract Drawings may be provided by Engineer for Contractor's use in preparing submittals.
 1. The Documents for this project were prepared using commercial software on computers.
 2. Drawing files (in AutoCAD V2018) are available to the Contractor.
 3. These digital files will only be released with original signature on the "Digital Information Electronic Release Agreement Form found in Section 00 62 90 "CAD File Release".

PART 2 - PRODUCTS

2.1 ACTION SUBMITTALS

- A. General: Prepare and submit Action Submittals required by individual Specification Sections.
 1. Submit electronic submittals via email as PDF electronic files.
 - a. Engineer will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.

- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
1. If information must be specially prepared for submittal because standard printed data are not suitable for use, submit as Shop Drawings, not as Product Data.
 2. Mark each copy of each submittal to show which products and options are applicable.
 3. Include the following information, as applicable:
 - a. Manufacturer's written recommendations.
 - b. Manufacturer's product specifications.
 - c. Manufacturer's installation instructions.
 - d. Standard color charts.
 - e. Manufacturer's catalog cuts.
 - f. Wiring diagrams showing factory-installed wiring.
 - g. Printed performance curves.
 - h. Operational range diagrams.
 - i. Standard product operation and maintenance manuals.
 - j. Compliance with specified referenced standards.
 - k. Testing by recognized testing agency.
 - l. Application of testing agency labels and seals.
 - m. Notation of coordination requirements.
 4. Submit Product Data before or concurrent with Samples.
 5. Number of Copies: Submit one PDF electronic file. Engineer will return one electronic copy with comment page. Mark up and retain one returned copy as a Project Record Document.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data, unless submittal of Engineer's CAD Drawings are otherwise permitted.
1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Dimensions.
 - b. Identification of products.
 - c. Fabrication and installation drawings.
 - d. Roughing-in and setting diagrams.
 - e. Wiring diagrams showing field-installed wiring, including power, signal, and control wiring.
 - f. Shopwork manufacturing instructions.
 - g. Templates and patterns.
 - h. Schedules.
 - i. Design calculations.
 - j. Compliance with specified standards.
 - k. Notation of coordination requirements.
 - l. Notation of dimensions established by field measurement.
 - m. Relationship to adjoining construction clearly indicated.
 - n. Seal and signature of professional engineer if specified.
 - o. Wiring Diagrams: Differentiate between manufacturer-installed and field-installed wiring.

2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches (215 by 280 mm) but no larger than 30 by 40 inches (750 by 1000 mm).
 3. Number of Copies: Submit two opaque (bond) copies of each submittal. Engineer will return one copy.
 4. Number of Copies: Submit three opaque copies of each submittal, unless copies are required for operation and maintenance manuals. Submit five copies where copies are required for operation and maintenance manuals. Engineer will retain two copies; remainder will be returned.
 5. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
 - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
- D. Contractor's Construction Schedule: Comply with requirements specified in Division 01 Section 01 32 00 "Construction Progress Documentation" for Construction Manager's action.
- E. Submittals Schedule: Comply with requirements specified in Division 01 Section 01 32 00 "Construction Progress Documentation."
- F. Application for Payment: Comply with requirements specified in Division 01 Section 01 29 00 "Payment Procedures."
- G. Schedule of Values: Comply with requirements specified in Division 01 Section 01 29 00 "Payment Procedures."
- H. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Use CSI Form 1.5A. Include the following information in tabular form:
1. Name, address, and telephone number of entity performing subcontract or supplying products.
 2. Number and title of related Specification Section(s) covered by subcontract.
 3. Drawing number and detail references, as appropriate, covered by subcontract.
 4. Number of Copies: Submit three copies of subcontractor list, unless otherwise indicated. Engineer will return two copies.
 - a. Mark up and retain one returned copy as a Project Record Document.

2.2 INFORMATIONAL SUBMITTALS

- A. General: Prepare and submit Informational Submittals required by other Specification Sections.

1. Number of Copies: Submit two copies of each submittal, unless otherwise indicated. Engineer will not return copies.
 2. Certificates and Certifications: Provide a notarized statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
 3. Test and Inspection Reports: Comply with requirements specified in Division 01 Section 01 40 00 "Quality Requirements."
- B. Coordination Drawings: Comply with requirements specified in Division 01 Section 01 31 00 "Project Management and Coordination."
- C. Contractor's Construction Schedule: Comply with requirements specified in Division 01 Section 01 32 00 "Construction Progress Documentation."
- D. Schedule of Tests and Inspections: Comply with requirements specified in Division 01 Section 01 40 00 "Quality Requirements."
- E. Preconstruction Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- F. Field Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- G. Maintenance Data: Prepare written and graphic instructions and procedures for operation and normal maintenance of products and equipment. Comply with requirements specified in Division 01 Section 01 78 23 "Operation and Maintenance Data."
- H. Manufacturer's Instructions: Prepare written or published information that documents manufacturer's recommendations, guidelines, and procedures for installing or operating a product or equipment. Include name of product and name, address, and telephone number of manufacturer. Include the following, as applicable:
1. Preparation of substrates.
 2. Required substrate tolerances.
 3. Sequence of installation or erection.
 4. Required installation tolerances.
 5. Required adjustments.
 6. Recommendations for cleaning and protection.
- I. Manufacturer's Field Reports: Prepare written information documenting factory-authorized service representative's tests and inspections. Include the following, as applicable:
1. Name, address, and telephone number of factory-authorized service representative making report.
 2. Statement on condition of substrates and their acceptability for installation of product.
 3. Statement that products at Project site comply with requirements.

4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 6. Statement whether conditions, products, and installation will affect warranty.
 7. Other required items indicated in individual Specification Sections.
- J. Insurance Certificates and Bonds: Prepare written information indicating current status of insurance or bonding coverage. Include name of entity covered by insurance or bond, limits of coverage, amounts of deductibles, if any, and term of the coverage.
- K. Material Safety Data Sheets (MSDSs): Submit information directly to Owner; do not submit to Engineer.
1. Engineer will not review submittals that include MSDSs and will return the entire submittal for resubmittal.
- L. Coordination Drawings: Comply with requirements specified in Division 01 Section 01 31 00 "Project Management and Coordination."
- M. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of engineers and owners, and other information specified.
- N. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
- O. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
- P. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
- Q. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
- R. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
- S. Product Test Reports: Submit written reports indicating current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- T. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:

1. Name of evaluation organization.
 2. Date of evaluation.
 3. Time period when report is in effect.
 4. Product and manufacturers' names.
 5. Description of product.
 6. Test procedures and results.
 7. Limitations of use.
- U. Schedule of Tests and Inspections: Comply with requirements specified in Division 01 Section 01 40 00 "Quality Requirements."
- V. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- W. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- X. Field Test Reports: Submit reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- Y. Maintenance Data: Comply with requirements specified in Division 01 Section 01 78 23 "Operation and Maintenance Data."
- Z. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Engineer.
- B. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ENGINEER'S / ACTION

- A. General: Engineer will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Engineer will review each submittal, make marks to indicate corrections or modifications required, and return it. Engineer will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action taken, as follows:
 - 1. Reviewed: Approved.
 - 2. Reviewed: Submittals which require no corrections.
 - 3. Rejected: Not Approved. Constricting to requirement of the Contract Documents. Do not perform work illustrated.
 - 4. Resubmit as specified: Item required major correction, future clarification and/or completion. Do not perform work illustrated.
 - 5. For Information only/Not Reviewed: Submittals that are not required by Contract Documents to be reviewed by Engineer.
 - 6. Comments Noted: Make corrections noted.
 - 7. Revise & Resubmit: To be corrected and returned for approval. Do not perform work as illustrated.
 - 8. Resubmit for Record Only: Proceed with work and re-submit information submitted for Engineers records.
- C. Informational Submittals: Engineer will review each submittal and will not return it, or will return it if it does not comply with requirements. Engineer will forward each submittal to appropriate party.
- D. Partial submittals are not acceptable, will be considered nonresponsive, and will be returned without review.
- E. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

END OF SECTION

SECTION 01 40 00
QUALITY REQUIREMENTS
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 CONFLICTING REQUIREMENTS
- 1.5 ACTION SUBMITTALS
- 1.6 INFORMATIONAL SUBMITTALS
- 1.7 REPORTS AND DOCUMENTS
- 1.8 QUALITY ASSURANCE
- 1.9 QUALITY CONTROL

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

- 3.1 TEST AND INSPECTION LOG
- 3.2 REPAIR AND PROTECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 40 00
QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-assurance and -control services required by Engineer, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
- C. Related Sections:
 - 1. Division 01 Section 01 32 00 "Construction Progress Documentation" for developing a schedule of required tests and inspections.
 - 2. Divisions 02 through 28 Sections for specific test and inspection requirements.

1.3 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Engineer.

- C. Preconstruction Testing: Tests and inspections performed specifically for the Project before products and materials are incorporated into the Work to verify performance or compliance with specified criteria.
- D. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- E. Source Quality-Control Testing: Tests and inspections that are performed at the source, i.e., plant, mill, factory, or shop.
- F. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- G. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- H. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
 - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade or trades.
- I. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1.4 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Engineer for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Engineer for a decision before proceeding.

1.5 ACTION SUBMITTALS

- A. Shop Drawings: For ductwork, provide plans, sections, and elevations, indicating materials and size of mockup construction.

1. Indicate manufacturer and model number of individual components.
2. Provide axonometric drawings for conditions difficult to illustrate in two dimensions.

1.6 INFORMATIONAL SUBMITTALS

- A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- B. Contractor's Quality-Control Manager Qualifications: For supervisory personnel.
- C. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility sent to authorities having jurisdiction before starting work on the following systems.
 1. Seismic-force resisting system, designated seismic system, or component listed in the designated seismic system quality assurance plan prepared by the Engineer.
 2. Main wind-force resisting system or a wind-resisting component listed in the wind-force-resisting system quality assurance plan prepared by the Engineer.
- D. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- E. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
 1. Specification Section number and title.
 2. Entity responsible for performing tests and inspections.
 3. Description of test and inspection.
 4. Identification of applicable standards.
 5. Identification of test and inspection methods.
 6. Number of tests and inspections required.
 7. Time schedule or time span for tests and inspections.
 8. Requirements for obtaining samples.
 9. Unique characteristics of each quality-control service.

1.7 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
 1. Date of issue.
 2. Project title and number.
 3. Name, address, and telephone number of testing agency.
 4. Dates and locations of samples and tests or inspections.
 5. Names of individuals making tests and inspections.
 6. Description of the Work and test and inspection method.
 7. Identification of product and Specification Section.
 8. Complete test or inspection data.
 9. Test and inspection results and an interpretation of test results.

10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 12. Name and signature of laboratory inspector.
 13. Recommendations on retesting and reinspection.
- B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
1. Name, address, and telephone number of technical representatives making report.
 2. Statement on condition of substrates and their acceptability for installation of product.
 3. Statement that products at Project site comply with requirements.
 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 6. Statement whether conditions, products, and installation will affect warranty.
 7. Other required items indicated in individual Specification Sections.
- C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
1. Name, address, and telephone number of factory-authorized service representative making report.
 2. Statement that equipment complies with requirements.
 3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 4. Statement whether conditions, products, and installation will affect warranty.
 5. Other required items indicated in individual Specification Sections.
- D. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.
- 1.8 QUALITY ASSURANCE
- A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

- D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar to those indicated for this Project in material, design, and extent.
- F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.
 - 1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.
- G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and where required by authorities having jurisdiction, that is acceptable to authorities.
 - 1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
 - 2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.
- H. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- J. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
 - 1. Contractor responsibilities include the following:
 - a. Provide test specimens representative of proposed products and construction.
 - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
 - c. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
 - d. Build site-assembled test assemblies and mockups using installers who will perform same tasks for Project.

- e. Build laboratory mockups at testing facility using personnel, products, and methods of construction indicated for the completed Work.
 - f. When testing is complete, remove test specimens, assemblies, mockups; do not reuse products on Project.
2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Engineer, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.

1.9 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
- 1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
 - 2. Payment for these services will be made from testing and inspecting allowances, as authorized by Change Orders.
 - 3. Costs for retesting and reinspection construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.
- 1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
 - 2. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
 - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
 - 3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
 - 4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
 - 5. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
 - 6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Division 01 Section 01 33 00 "Submittal Procedures."

- D. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.
- E. Retesting/Reinspection: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspection, for construction that replaced Work that failed to comply with the Contract Documents.
- F. Testing Agency Responsibilities: Cooperate with Engineer and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
 - 1. Notify Engineer and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 - 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
 - 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
 - 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 - 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
 - 6. Do not perform any duties of Contractor.
- G. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
 - 1. Access to the Work.
 - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 - 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 - 4. Facilities for storage and field curing of test samples.
 - 5. Delivery of samples to testing agencies.
 - 6. Security and protection for samples and for testing and inspecting equipment at Project site.
- H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
 - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
- I. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents. Coordinate and submit concurrently with Contractor's construction schedule. Update as the Work progresses.
 - 1. Distribution: Distribute schedule to Owner, Engineer, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

- A. Prepare a record of tests and inspections. Include the following:
 - 1. Date test or inspection was conducted.
 - 2. Description of the Work tested or inspected.
 - 3. Date test or inspection results were transmitted to Engineer.
 - 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and modifications as they occur. Provide access to test and inspection log for Engineer's reference during normal working hours.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
 - 1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Division 01 Section 01 73 00 "Execution Requirements."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION

SECTION 01 50 00
TEMPORARY FACILITIES AND CONTROLS
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 USE CHARGES
- 1.4 SUBMITTALS
- 1.5 QUALITY ASSURANCE
- 1.6 PROJECT CONDITIONS

PART 2 PRODUCTS

- 2.1 TEMPORARY FACILITIES
- 2.2 EQUIPMENT

PART 3 EXECUTION

- 3.1 INSTALLATION, GENERAL
- 3.2 TEMPORARY UTILITY INSTALLATION
- 3.3 SUPPORT FACILITIES INSTALLATION
- 3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION
- 3.5 OPERATION, TERMINATION, AND REMOVAL

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 50 00
TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes requirements for temporary utilities, support facilities, and security and protection facilities.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 11 00 "Summary" for limitations on utility interruptions and other work restrictions.
 - 2. Division 01 Section 01 33 00 "Submittal Procedures" for procedures for submitting copies of implementation and termination schedule and utility reports.
 - 3. Division 01 Section 01 73 00 "Execution Requirements" for progress cleaning requirements.

1.3 USE CHARGES

- A. General: Utility usage shall not be metered. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Engineer, testing agencies, and authorities having jurisdiction.
- B. Sewer Service: Owner will pay sewer service use charges for sewer usage by all entities for construction operations.
- C. Water Service: Owner will pay water service use charges for water used by all entities for construction operations.
- D. Electric Power Service: Utility usage shall not be metered. Provide connections and extensions of services as required for construction operations.
- E. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.
- F. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

1.4 SUBMITTALS

- A. Site Plan: Show temporary facilities, staging areas, crane mobilization area, and parking areas for construction personnel.
- B. Moisture-Protection Plan: Describe procedures and controls for protecting materials and construction from water absorption and damage, including delivery, handling, and storage provisions for materials subject to water absorption or water damage, discarding water-damaged materials, protocols for mitigating water intrusion into completed Work, and replacing water damaged Work.

1.5 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

1.6 PROJECT CONDITIONS

- A. Temporary Use of Permanent Facilities: Installer of each permanent service shall assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 TEMPORARY FACILITIES

- A. Field Offices, General: Space within building shall be utilized as field offices.

2.2 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.

1. Locate facilities to limit site disturbance as specified in Division 01 Section 01 11 00 "Summary."
- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
 1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
- B. Water Service: Use of Owner's existing water service facilities will be permitted, as long as facilities are cleaned and maintained in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.
 1. Where installations below an outlet might be damaged by spillage or leakage, provide a drip pan of suitable size to minimize water damage. Drain accumulated water promptly from pans.
- C. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities. Owner will not allow use of onsite sanitary facilities.
- D. Electric Power Service: Use of Owner's existing electric power service will be permitted, as long as equipment is maintained in a condition acceptable to Owner.
- E. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
 1. Provide construction for temporary offices, shops, and sheds located within construction area or within 30 feet (9 m) of building lines that is noncombustible according to ASTM E 136. Comply with NFPA 241.
 2. Maintain support facilities until Engineer schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.
- B. Parking: Use designated areas of Owner's existing parking areas for construction personnel.

- C. Project Identification and Temporary Signs: Provide Project identification and other signs. Install signs where indicated to inform public and individuals seeking entrance to Project. Unauthorized signs are not permitted.
 - 1. Provide temporary, directional signs for construction personnel and visitors.
 - 2. Maintain and touchup signs so they are legible at all times.
- D. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.
 - 1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.
- E. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with Division 01 Section 01 73 00 "Execution Requirements" for progress cleaning requirements.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction in ways and by methods that comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
 - 1. Comply with work restrictions specified in Division 01 Section 01 11 00 "Summary of Work."
- B. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each work day.
- C. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities.
- D. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241.
 - 1. Prohibit smoking in construction areas.
 - 2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition according to requirements of authorities having jurisdiction.
 - 3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.

3.5 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal.
 - 1. Maintain operation of temporary enclosures, heating, cooling, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
- C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.
- D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
 - 1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
 - 2. Remove temporary paving not intended for or acceptable for integration into permanent paving. Where area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at temporary entrances, as required by authorities having jurisdiction.
 - 3. At Substantial Completion, clean and renovate permanent facilities used during construction period. Comply with final cleaning requirements specified in Division 01 Section 01 77 00 "Closeout Procedures."

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 60 00
PRODUCT REQUIREMENTS
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 ACTION SUBMITTALS
- 1.5 QUALITY ASSURANCE
- 1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING
- 1.7 PRODUCT WARRANTIES

PART 2 PRODUCTS

- 2.1 PRODUCT SELECTION PROCEDURES
- 2.2 PRODUCT SUBSTITUTIONS
- 2.3 COMPARABLE PRODUCTS

PART 3 EXECUTION (Not Used)

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 60 00
PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; product substitutions; and comparable products.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 77 00 "Closeout Procedures" for submitting warranties for Contract closeout.
 - 2. Division 01 Section 01 23 00 "Alternates" for products selected under an alternate.
 - 3. Division 01 Section 01 25 00 "Substitution Procedures" for requests for substitutions.
 - 4. Divisions 02 through 26 Sections for specific requirements for warranties on products and installations specified to be warranted.

1.3 DEFINITIONS

- A. Products: Items purchased for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved through submittal process, or where indicated as a product substitution, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.

- B. Basis-of-Design Product Specification: Where a specific manufacturer's product is named and accompanied by the words "basis of design," including make or model number, or first named product, or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of other named manufacturers.

1.4 SUBMITTALS

- A. Product List: Submit a list, in tabular form, showing specified products. Include generic names of products required. Include manufacturer's name and proprietary product names for each product.
1. Coordinate product list with Contractor's Construction Schedule and the Submittals Schedule.
 2. Form: Tabulate information for each product under the following column headings:
 - a. Specification Section number and title.
 - b. Generic name used in the Contract Documents.
 - c. Proprietary name, model number, and similar designations.
 - d. Manufacturer's name and address.
 - e. Supplier's name and address.
 - f. Installer's name and address.
 - g. Projected delivery date or time span of delivery period.
 - h. Identification of items that require early submittal approval for scheduled delivery date.
 3. Initial Submittal: Within 30 days after date of commencement of the Work, submit 3 copies of initial product list. Include a written explanation for omissions of data and for variations from Contract requirements.
 - a. At Contractor's option, initial submittal may be limited to product selections and designations that must be established early in Contract period.
 4. Completed List: Within 60 days after date of commencement of the Work, submit 3 copies of completed product list. Include a written explanation for omissions of data and for variations from Contract requirements.
 5. Engineer's Action: Engineer will respond in writing to Contractor within 15 days of receipt of completed product list. Engineer's response will include a list of unacceptable product selections and a brief explanation of reasons for this action. Engineer's response, or lack of response, does not constitute a waiver of requirement to comply with the Contract Documents.
- B. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
1. Substitution Request Form: Use CSI Form 13.1A found in Section 00 63 25.
 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:

- a. Statement indicating why specified material or product cannot be provided.
 - b. Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. List of similar installations for completed projects with project names and addresses and names and addresses of Engineers and owners.
 - g. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - h. Research/evaluation reports evidencing compliance with building code in effect for Project, from a model code organization acceptable to authorities having jurisdiction.
 - i. Detailed comparison of Contractor's Construction Schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating lack of availability or delays in delivery.
 - j. Cost information, including a proposal of change, if any, in the Contract Sum.
 - k. Contractor's certification that proposed substitution complies with requirements in the Contract Documents and is appropriate for applications indicated.
 - l. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
3. Engineer's Action: If necessary, Engineer will request additional information or documentation for evaluation within 7 days of receipt of a request for substitution. Engineer will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or 7 days of receipt of additional information or documentation, whichever is later.
 - a. Form of Acceptance: Change Order.
 - b. Use product specified if Engineer cannot make a decision on use of a proposed substitution within time allocated.
- C. Comparable Product Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 1. Engineer's Action: If necessary, Engineer will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Engineer will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or 7 days of receipt of additional information or documentation, whichever is later.

- a. Form of Approval: As specified in Division 01 Section 01 33 00 "Submittal Procedures."
 - b. Use product specified if Engineer cannot make a decision on use of a comparable product request within time allocated.
- D. Basis-of-Design Product Specification Submittal: Comply with requirements in Division 01 Section 01 33 00 "Submittal Procedures." Show compliance with requirements.

1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, product selected shall be compatible with products previously selected, even if previously selected products were also options.
- 1. Each contractor is responsible for providing products and construction methods compatible with products and construction methods of other contractors.
 - 2. If a dispute arises between contractors over concurrently selectable but incompatible products, Engineer will determine which products shall be used.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft. Comply with manufacturer's written instructions.
- B. Delivery and Handling:
- 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
 - 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
 - 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
 - 4. Inspect products on delivery to ensure compliance with the Contract Documents and to ensure that products are undamaged and properly protected.
- C. Storage:
- 1. Store products to allow for inspection and measurement of quantity or counting of units.
 - 2. Store materials in a manner that will not endanger Project structure.
 - 3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
 - 4. Store cementitious products and materials on elevated platforms.
 - 5. Store foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
 - 6. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
 - 7. Protect stored products from damage and liquids from freezing.

8. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
 1. Manufacturer's Warranty: Preprinted written warranty published by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
 2. Special Warranty: Written warranty required by or incorporated into the Contract Documents, either to extend time limit provided by manufacturer's warranty or to provide more rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution. Submit a draft for approval before final execution.
 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 2. Specified Form: When specified forms are included with the Specifications, prepare a written document using appropriate form properly executed.
 3. Refer to Divisions 02 through 26 Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Division 01 Section 01 77 00 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, that are undamaged and, unless otherwise indicated, that are new at time of installation.
 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
 4. Where products are accompanied by the term "as selected," Engineer will make selection.
 5. Where products are accompanied by the term "match sample," sample to be matched is Engineer's.

6. Descriptive, performance, and reference standard requirements in the Specifications establish "salient characteristics" of products.
7. Or Equal: Where products are specified by name and accompanied by the term "or equal" or "or approved equal" or "or approved," comply with provisions in Part 2 "Comparable Products" Article to obtain approval for use of an unnamed product.

B. Product Selection Procedures:

1. Product: Where Specifications name a single product and manufacturer, provide the named product that complies with requirements.
2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements.
3. Products: Where Specifications include a list of names of both products and manufacturers, provide one of the products listed that complies with requirements.
4. Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements.
5. Available Products: Where Specifications include a list of names of both products and manufacturers, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with provisions in Part 2 "Comparable Products" Article for consideration of an unnamed product.
6. Available Manufacturers: Where Specifications include a list of manufacturers, provide a product by one of the manufacturers listed, or an unnamed manufacturer, that complies with requirements. Comply with provisions in Part 2 "Comparable Products" Article for consideration of an unnamed product.
7. Product Options: Where Specifications indicate that sizes, profiles, and dimensional requirements on Drawings are based on a specific product or system, provide the specified product or system. Comply with provisions in Part 2 "Product Substitutions" Article for consideration of an unnamed product or system.
8. Basis-of-Design Product: Where Specifications name a product and include a list of manufacturers, provide the specified product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with provisions in Part 2 "Comparable Products" Article for consideration of an unnamed product by the other named manufacturers.
9. Visual Matching Specification: Where Specifications require matching an established Sample, select a product that complies with requirements and matches Engineer's sample. Engineer's decision will be final on whether a proposed product matches.
 - a. If no product available within specified category matches and complies with other specified requirements, comply with provisions in Part 2 "Product Substitutions" Article for proposal of product.
10. Visual Selection Specification: Where Specifications include the phrase "as selected from manufacturer's colors, patterns, textures" or a similar phrase, select a product that complies with other specified requirements.
 - a. Standard Range: Where Specifications include the phrase "standard range of colors, patterns, textures" or similar phrase, Engineer will select color, pattern, density, or texture from manufacturer's product line that does not include premium items.

- b. Full Range: Where Specifications include the phrase "full range of colors, patterns, textures" or similar phrase, Engineer will select color, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 PRODUCT SUBSTITUTIONS

- A. Timing: Engineer will consider requests for substitution if received within 15 days after the Notice to Proceed. Requests received after that time may be considered or rejected at discretion of Engineer.
- B. Conditions: Engineer will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Engineer will return requests without action, except to record noncompliance with these requirements:
 - 1. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Engineer for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 - 2. Requested substitution does not require extensive revisions to the Contract Documents.
 - 3. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - 4. Substitution request is fully documented and properly submitted.
 - 5. Requested substitution will not adversely affect Contractor's Construction Schedule.
 - 6. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - 7. Requested substitution is compatible with other portions of the Work.
 - 8. Requested substitution has been coordinated with other portions of the Work.
 - 9. Requested substitution provides specified warranty.
 - 10. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

2.3 COMPARABLE PRODUCTS

- A. Conditions: Engineer will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Engineer will return requests without action, except to record noncompliance with these requirements:
 - 1. Evidence that the proposed product does not require extensive revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
 - 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 - 3. Evidence that proposed product provides specified warranty.
 - 4. List of similar installations for completed projects with project names and addresses and names and addresses of Engineers and owners, if requested.

5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION

**SECTION 01 73 00
EXECUTION
TABLE OF CONTENTS**

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 INFORMATIONAL SUBMITTALS
- 1.5 QUALITY ASSURANCE
- 1.6 WARRANTY

PART 2 PRODUCTS

- 2.1 MATERIALS

PART 3 EXECUTION

- 3.1 EXAMINATION
- 3.2 PREPARATION
- 3.3 INSTALLATION
- 3.4 CUTTING AND PATCHING
- 3.5 OWNER-INSTALLED PRODUCTS
- 3.6 PROGRESS CLEANING
- 3.7 STARTING AND ADJUSTING
- 3.8 PROTECTION OF INSTALLED CONSTRUCTION
- 3.9 CORRECTION OF THE WORK

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 73 00
EXECUTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes general procedural requirements governing execution of the Work including, but not limited to, the following:
 - 1. Construction layout.
 - 2. Field engineering and surveying.
 - 3. General installation of products.
 - 4. Coordination of Owner-installed products.
 - 5. Progress cleaning.
 - 6. Starting and adjusting.
 - 7. Protection of installed construction.
 - 8. Correction of the Work.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 31 00 "Project Management and Coordination" for procedures for coordinating field engineering with other construction activities.
 - 2. Division 01 Section 01 33 00 "Submittal Procedures" for submitting surveys.
 - 3. Division 01 Section 01 73 29 "Cutting and Patching" for procedural requirements for cutting and patching necessary for the installation or performance of other components of the Work.
 - 4. Division 01 Section 01 77 00 "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, and final cleaning.

1.3 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of other work.
- B. Patching: Fitting and repair work required to restore construction to original conditions after installation of other work.

1.4 INFORMATIONAL SUBMITTALS

- A. Cutting and Patching Plan: Submit plan describing procedures at least 10 days prior to the time cutting and patching will be performed. Include the following information:
1. Extent: Describe reason for and extent of each occurrence of cutting and patching.
 2. Changes to In-Place Construction: Describe anticipated results. Include changes to structural elements and operating components as well as changes in building appearance and other significant visual elements.
 3. Products: List products to be used for patching and firms or entities that will perform patching work.
 4. Dates: Indicate when cutting and patching will be performed.
 5. Utilities and Mechanical and Electrical Systems: List services and systems that cutting and patching procedures will disturb or affect. List services and systems that will be relocated and those that will be temporarily out of service. Indicate how long services and systems will be disrupted.
- B. Landfill Receipts: Submit copy of receipts issued by a landfill facility, licensed to accept hazardous materials, for hazardous waste disposal.

1.5 QUALITY ASSURANCE

- A. Land Surveyor Qualifications: A professional land surveyor who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing land-surveying services of the kind indicated.
- B. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
1. Structural Elements: When cutting and patching structural elements, notify Engineer of locations and details of cutting and await directions from the Engineer before proceeding. Shore, brace, and support structural element during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection
 2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety. Operational elements include the following:
 - a. Primary operational systems and equipment.
 - b. Fire separation assemblies.
 - c. Air or smoke barriers.
 - d. Fire-suppression systems.
 - e. Mechanical systems piping and ducts.
 - f. Control systems.
 - g. Communication systems.
 - h. Conveying systems.
 - i. Electrical wiring systems.

3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety. Other construction elements include but are not limited to the following:
 - a. Water, moisture, or vapor barriers.
 - b. Membranes and flashings.
 - c. Equipment supports.
 - d. Piping, ductwork, vessels, and equipment.
 - e. Noise- and vibration-control elements and systems.
 4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Engineer's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- C. Cutting and Patching Conference: Before proceeding, meet at Project site with parties involved in cutting and patching, including mechanical and electrical trades. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.
- D. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of products and equipment.

1.6 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
- B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to the Engineer for the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Existing Conditions: The existence and location of site improvements, utilities, and other construction indicated as existing are not guaranteed. Before beginning work, investigate and verify the existence and location of mechanical and electrical systems and other construction affecting the Work.
 - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; underground electrical services, and other utilities.
- B. Acceptance of Conditions: Examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 - 1. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
 - a. Description of the Work.
 - b. List of detrimental conditions, including substrates.
 - c. List of unacceptable installation tolerances.
 - d. Recommended corrections.
 - 2. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
 - 3. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
 - 4. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
 - 5. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents, submit a request for information to Engineer. Include a detailed description of problem encountered, together with recommendations for changing the

Contract Documents. Submit requests on CSI Form 13.2A, "Request for Interpretation", form enclosed in Division 01 Section 01 32 00 "Construction Progress Documentation."

- D. Surface and Substrate Preparation: Comply with manufacturer's recommendations for preparation of substrates to receive subsequent work.

3.3 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
1. Make vertical work plumb and make horizontal work level.
 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
 3. Conceal pipes, ducts, and wiring in finished areas, unless otherwise indicated.
 4. Maintain minimum headroom clearance of 96 inches (2440 mm) in occupied spaces and 90 inches (2300 mm) in unoccupied spaces.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- F. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- G. Anchors and Fasteners: Provide anchors and fasteners as required to anchor each component securely in place, accurately located and aligned with other portions of the Work.
1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Engineer.
 2. Allow for piping, building movement, including thermal expansion and contraction.
 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- H. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- I. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

3.4 CUTTING AND PATCHING

- A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 - 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Temporary Support: Provide temporary support of work to be cut.
- C. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- D. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
 - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 - 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
 - 3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 - 4. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 - 5. Proceed with patching after construction operations requiring cutting are complete.
- E. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.
 - 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
 - 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.
 - a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
 - b. Restore damaged pipe covering to its original condition.
 - 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.

- a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.
4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance.
5. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition.
- F. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.5 OWNER-INSTALLED PRODUCTS

- A. Site Access: Provide access to Project site for Owner's construction personnel.
- B. Coordination: Coordinate construction and operations of the Work with work performed by Owner's construction personnel.
 1. Construction Schedule: Inform Owner of Contractor's preferred construction schedule for Owner's portion of the Work. Adjust construction schedule based on a mutually agreeable timetable. Notify Owner if changes to schedule are required due to differences in actual construction progress.
 2. Preinstallation Conferences: Include Owner's construction personnel at preinstallation conferences covering portions of the Work that are to receive Owner's work. Attend preinstallation conferences conducted by Owner's construction personnel if portions of the Work depend on Owner's construction.

3.6 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Coordinate progress cleaning for joint-use areas where more than one installer has worked. Enforce requirements strictly. Dispose of materials lawfully.
 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
 2. Do not hold materials more than 7 days during normal weather or 3 days if the temperature is expected to rise above 80 deg F (27 deg C).
 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
 1. Remove liquid spills promptly.

- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- F. Waste Disposal: Burying or burning waste materials on-site will not be permitted. Washing waste materials down sewers or into waterways will not be permitted.
- G. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- H. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- I. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.7 STARTING AND ADJUSTING

- A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- B. Adjust operating components for proper operation without binding. Adjust equipment for proper operation.
- C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Manufacturer's Field Service: If a factory-authorized service representative is required to inspect field-assembled components and equipment installation, comply with qualification requirements in Division 01 Section 01 40 00 "Quality Requirements."

3.8 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

3.9 CORRECTION OF THE WORK

- A. Repair or remove and replace defective construction. Restore damaged substrates and finishes. Comply with requirements in Division 01 Section 01 73 29 "Cutting and Patching."

1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- B. Restore permanent facilities used during construction to their specified condition.
- C. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.
- D. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.
- E. Remove and replace chipped, scratched, and broken glass or reflective surfaces.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 73 29
CUTTING AND PATCHING
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 SUBMITTALS
- 1.5 QUALITY ASSURANCE
- 1.6 WARRANTY

PART 2 PRODUCTS

- 2.1 MATERIALS

PART 3 EXECUTION

- 3.1 EXAMINATION
- 3.2 PREPARATION
- 3.3 PERFORMANCE

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 73 29
CUTTING AND PATCHING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes procedural requirements for cutting and patching.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 73 20 "Selective Demolition" for demolition of selected portions.
 - 2. Divisions 02 through 28 Sections for specific requirements and limitations applicable to cutting and patching individual parts of the Work.

1.3 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of other Work.
- B. Patching: Fitting and repair work required to restore surfaces to original conditions after installation of other Work.

1.4 SUBMITTALS

- A. Cutting and Patching Proposal: Submit a proposal describing procedures at least 10 days before the time cutting and patching will be performed, requesting approval to proceed. Include the following information:
 - 1. Extent: Describe cutting and patching, show how they will be performed, and indicate why they cannot be avoided.
 - 2. Changes to In-Place Construction: Describe anticipated results. Include changes to structural elements and operating components as well as changes in building's appearance and other significant visual elements.
 - 3. Products: List products to be used and firms or entities that will perform the Work.
 - 4. Dates: Indicate when cutting and patching will be performed.
 - 5. Utility Services and Mechanical/Electrical Systems: List services/systems that cutting and patching procedures will disturb or affect. List services/systems that will be relocated and those that will be temporarily out of service. Indicate how long services/systems will be disrupted.

6. Structural Elements: Where cutting and patching involve adding reinforcement to structural elements, submit details and engineering calculations showing integration of reinforcement with original structure.
7. Engineer's Approval: Obtain approval of cutting and patching proposal before cutting and patching. Approval does not waive right to later require removal and replacement of unsatisfactory work.

1.5 QUALITY ASSURANCE

- A. Structural Elements: Do not cut and patch structural elements in a manner that could change their load-carrying capacity or load-deflection ratio.
- B. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety. Operating elements include the following:
 1. Primary operational systems and equipment.
 2. Air or smoke barriers.
 3. Fire-suppression systems.
 4. Mechanical systems piping and ducts.
 5. Control systems.
 6. Communication systems.
 7. Electrical wiring systems.
- C. Miscellaneous Elements: Do not cut and patch miscellaneous elements or related components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety. Miscellaneous elements include the following:
 1. Water, moisture, or vapor barriers.
 2. Membranes and flashings.
 3. Exterior curtain-wall construction.
 4. Equipment supports.
 5. Piping, ductwork, vessels, and equipment.
 6. Noise- and vibration-control elements and systems.
- D. Visual Requirements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch construction exposed on the exterior or in occupied spaces in a manner that would, in Engineer's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- E. Cutting and Patching Conference: Before proceeding, meet at Project site with parties involved in cutting and patching, including mechanical and electrical trades. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.

1.6 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during cutting and patching operations, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
- B. In-Place Materials: Use materials identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
 - 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will match the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine surfaces to be cut and patched and conditions under which cutting and patching are to be performed.
 - 1. Compatibility: Before patching, verify compatibility with and suitability of substrates, including compatibility with in-place finishes or primers.
 - 2. Proceed with installation only after unsafe or unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Temporary Support: Provide temporary support of Work to be cut.
- B. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- C. Adjoining Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.
- D. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to minimize interruption to occupied areas.

3.3 PERFORMANCE

- A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 - 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
 - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots as small as possible, neatly to size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 - 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
 - 3. Concrete: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 - 4. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 - 5. Proceed with patching after construction operations requiring cutting are complete.
- C. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as possible. Provide materials and comply with installation requirements specified in other Sections.
 - 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate integrity of installation.
 - 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.
 - a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
 - b. Restore damaged pipe covering to its original condition.
 - 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance.
 - a. Where patching occurs in a painted surface, apply primer and intermediate paint coats over the patch and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.
 - 4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance. Where ceiling tiles are removed and are damaged, the

- same shall be replaced with new ceiling tiles to match existing. Where ceiling grid is damaged replace with new ceiling grid to match existing.
5. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition.
 6. Patch and repair masonry work to match exiting adjacent construction.
- D. Cleaning: Clean areas and spaces where cutting and patching are performed. Completely remove paint, mortar, oils, putty, and similar materials.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 74 19
CONSTRUCTION WASTE MANAGEMENT
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 SUMMARY
- 1.2 DEFINITIONS
- 1.3 SUBMITTALS
- 1.4 PERFORMANCE REQUIREMENTS
- 1.5 QUALITY ASSURANCE
- 1.6 WASTE MANAGEMENT PLAN

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

- 3.1 CONSTRUCTION WASTE MANAGEMENT, GENERAL
- 3.2 SOURCE SEPARATION
- 3.3 CO-MINGLED RECYCLING
- 3.4 REMOVAL OF CONSTRUCTION WASTE MATERIALS
- 3.5 UNIVERSAL WASTE DIVERSION

THIS PAGE LEFT INTENTIONALLY BLANK

PART 1 – GENERAL

1.1 SUMMARY

- A. Section includes: Administrative and procedural requirements for construction waste management activities.

1.2 DEFINITIONS

- A. Construction, Demolition, and Land clearing (CDL) Waste: Includes all non-hazardous solid wastes resulting from construction, remodeling, alterations, repair, demolition and land clearing. Includes material that is recycled, reused, salvaged or disposed as garbage.
- B. Salvage: Recovery of materials for on-site reuse, sale or donation to a third party.
- C. Reuse: Making use of a material without altering its form. Materials can be reused on-site or reused on other projects off-site. Examples include, but are not limited to the following: Crushing or grinding of concrete for use as sub-base material. Chipping of land clearing debris for use as mulch.
- D. Recycling: The process of sorting, cleaning, treating, and reconstituting materials for the purpose of using the material in the manufacture of a new product.
- E. Source-Separated CDL Recycling: The process of separating recyclable materials in separate containers as they are generated on the job-site. The separated materials are hauled directly to a recycling facility or transfer station.
- F. Co-mingled CDL Recycling: The process of collecting mixed recyclable materials in one container on-site. The container is taken to a material recovery facility where materials are separated for recycling.
- G. Approved Recycling Facility: Any of the following:
 - 1. A facility that can legally accept CDL waste materials for the purpose of processing the materials into an altered form for the manufacture of a new product.
 - 2. Material Recovery Facility: A general term used to describe a waste-sorting facility. Mechanical, hand-separation, or a combination of both procedures, are used to recover recyclable materials.
- H. Universal waste components (UWC) are as follows: electric motors, PCB ballasts, non PCB ballasts, capacitors, contactors, circuit breakers, elemental and liquid mercury containing articles, transformers, lead acid batteries, fluorescent light bulbs, and all HID light bulbs.

1.3 SUBMITTALS

- A. Contractor shall develop a Waste Management Plan: Submit 3 copies of plan within 14 days of date established for the Notice to Proceed.
- B. Contractor shall provide Waste Management Report: Concurrent with each Application for Payment, submit 3 copies of report.

1.4 PERFORMANCE REQUIREMENTS

- A. General: Divert a minimum of **75%** CDL waste, by weight, from the landfill by one, or a combination of the following activities:
 - 1. Salvage
 - 2. Reuse
 - 3. Source-Separated CDL Recycling
 - 4. Co-mingled CDL Recycling
- B. CDL waste materials that can be salvaged, reused or recycled include, but are not limited to, the following:
 - 1. Acoustical ceiling tiles
 - 2. Asphalt
 - 3. Asphalt shingles
 - 4. Cardboard packaging
 - 5. Carpet and carpet pad
 - 6. Concrete
 - 7. Drywall
 - 8. Fluorescent lights and ballasts
 - 9. Land clearing debris (vegetation, stumpage, dirt)
 - 10. Metals
 - 11. Paint (through hazardous waste outlets)
 - 12. Wood
 - 13. Plastic film (sheeting, shrink wrap, packaging)
 - 14. Window glass
 - 15. Wood
 - 16. Field office waste, including office paper, aluminum cans, glass, plastic, and office cardboard.

1.5 QUALITY ASSURANCE

- A. Waste Management Coordinator Qualifications: Experienced firm, with a record of successful waste management coordination of projects with similar requirements, that employs a LEED Accredited Professional, certified by the USGBC as waste management coordinator.
- B. Refrigerant Recovery Technician Qualifications: Certified by EPA-approved certification program.
- C. Regulatory Requirements: Conduct construction waste management activities in accordance with hauling and disposal regulations of all authorities having jurisdiction and all other applicable laws and ordinances.
- D. Preconstruction Conference: Schedule and conduct meeting at Project site prior to construction activities.
 - 1. Attendees: Inform the following individuals, whose presence is required, of date and time of meeting.

- a. Owner

- b. Architect
 - c. Contractor's superintendent
 - d. Major subcontractors
 - e. Waste Management Coordinator
 - f. Other concerned parties.
2. Agenda Items: Review methods and procedures related to waste management including, but not limited to, the following:
 - a. Review and discuss waste management plan including responsibilities of Waste Management Coordinator.
 - b. Review requirements for documenting quantities of each type of waste and its disposition.
 - c. Review and finalize procedures for materials separation and verify availability of containers and bins needed to avoid delays.
 - d. Review procedures for periodic waste collection and transportation to recycling and disposal facilities.
 - e. Review waste management requirements for each trade.
3. Minutes: Record discussion. Distribute meeting minutes to all participants.
Note: If there is a Project Architect, they will perform this role.

1.6 WASTE MANAGEMENT PLAN – Contactor shall develop and document the following:

- A. Develop a plan to meet the requirements listed in this section at a minimum. Plan shall consist of waste identification, waste reduction plan and cost/revenue analysis. Distinguish between demolition and construction waste. Indicate quantities by weight throughout the plan.
- B. Indicate anticipated types and quantities of demolition, site-cleaning and construction waste generated by the project. List all assumptions made for the quantities estimates.
- C. List each type of waste and whether it will be salvaged, recycled, or disposed of in an landfill. The plan should included the following information:
 1. Types and estimated quantities, by weight, of CDL waste expected to be generated during demolition and construction.
 2. Proposed methods for CDL waste salvage, reuse, recycling and disposal during demolition including, but not limited to, one or more of the following:
 - a. Contracting with a deconstruction specialist to salvage materials generated,
 - b. Selective salvage as part of demolition contractor's work,
 - c. Reuse of materials on-site or sale or donation to a third party.
 3. Proposed methods for salvage, reuse, recycling and disposal during construction including, but not limited to, one or more of the following:
 - a. Requiring subcontractors to take their CDL waste to a recycling facility;
 - b. Contracting with a recycling hauler to haul recyclable CDL waste to an approved recycling or material recovery facility;
 - c. Processing and reusing materials on-site;

- d. Self-hauling to a recycling or material recovery facility.
4. Name of recycling or material recovery facility receiving the CDL wastes.
5. Handling and Transportation Procedures: Include method that will be used for separating recyclable waste including sizes of containers, container labeling, and designated location on project site where materials separation will be located.
- D. Cost/Revenue Analysis: Indicate total cost of waste disposal as if there was no waste management plan and net additional cost or net savings resulting from implementing waste management plan. Include the following:
 1. Total quantity of waste.
 2. Estimated cost of disposal (cost per unit). Include hauling and tipping fees and cost of collection containers for each type of waste.
 3. Total cost of disposal (with no waste management).
 4. Revenue from salvaged materials.
 5. Revenue from recycled materials.
 6. Savings in hauling and tipping fees by donating materials.
 7. Savings in hauling and tipping fees that are avoided.
 8. Handling and transportation costs. Including cost of collection containers for each type of waste.
 9. Net additional cost or net savings from waste management plan.

PART 2 - PRODUCTS (Not Used)

PART 3 – EXECUTION

3.1 CONSTRUCTION WASTE MANAGEMENT, GENERAL

- A. Provide containers for CDL waste that is to be recycled clearly labeled as such with a list of acceptable and unacceptable materials. The list of acceptable materials must be the same as the materials recycled at the receiving material recovery facility or recycling processor.
- B. The collection containers for recyclable CDL waste must contain no more than 10% non-recyclable material, by volume.
- C. Provide containers for CDL waste that is disposed in a landfill clearly labeled as such.
- D. Use detailed material estimates to reduce risk of unplanned and potentially wasteful cuts.
- E. To the greatest extent possible, include in material purchasing agreements a waste reduction provision requesting that materials and equipment be delivered in packaging made of recyclable material, that they reduce the amount of packaging, that packaging be taken back for reuse or recycling, and to take back all unused product. Insure that subcontractors require the same provisions in their purchase agreements.
- F. Conduct regular visual inspections of dumpsters and recycling bins to remove contaminants.

3.2 SOURCE SEPARATION

- A. General: Contractor shall separate recyclable materials from CDL waste to the maximum extent possible.

Separate recyclable materials by type.

1. Provide containers, clearly labeled, by type of separated materials or provide other storage method for managing recyclable materials until they are removed from Project site.
2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water and to minimize pest attraction. Cover to prevent windblown dust.
3. Stockpile materials away from demolition area. Do not store within drip line of remaining trees.
4. Store components off the ground and protect from weather.

3.3 CO-MINGLED RECYCLING

- A. General: Do not put CDL waste that will be disposed in a landfill into a co-mingled CDL waste recycling container.

3.4 REMOVAL OF CONSTRUCTION WASTE MATERIALS

- A. Remove CDL waste materials from project site on a regular basis. Do not allow CDL waste to accumulate on-site.
- B. Transport CDL waste materials off Owner's property and legally dispose of them.
- C. Burning of CDL waste is not permitted.

3.5 UNIVERSAL WASTE DIVERSION

- A. Remove all universal waste from fixtures, panels, and related devices for proper diversion and reclamation.
- B. Store all universal waste in containers provided by contact person within facilities operations.
- C. Store all universal waste in a secured location and request periodic removal from assigned contact person.
- D. Exemption: electric motors, circuit breakers, transformers and lighting contactors are exempt from this provision provided the contractor chooses to salvage or reuse the components.
- E. No identified universal waste will be discarded into the waste stream.

END OF SECTION

WASTE MANAGEMENT PROGRESS REPORT				
MATERIAL CATEGORY	DISPOSED IN MUNICIPAL SOLID WASTE LANDFILL	DIVERTED FROM LANDFILL BY RECYCLING, SALVAGE OR REUSE		
		Recycled	Salvaged	Reused
1. Acoustical Ceiling Tiles				
2. Asphalt				
3. Asphalt Shingles				
4. Cardboard Packaging				
5. Carpet and Carpet Pad				
6. Concrete				
7. Drywall				
8. Fluorescent Lights and Ballasts				
9. Land Clearing Debris (vegetation, stumpage, dirt)				
10. Metals				
11. Paint (through hazardous waste outlets)				
12. Wood				
13. Plastic Film (sheeting, shrink wrap, packaging)				
14. Window Glass				
15. Field Office Waste (office paper, aluminum cans, glass, plastic, and coffee cardboard)				
16. Other (insert description)				
17. Other (insert description)				
Total (In Weight)		(TOTAL OF ALL ABOVE VALUES – IN WEIGHT)		
		Percentage of Waste Diverted	(TOTAL WASTE DIVIDED BY TOTAL DIVERTED)	

SECTION 01 77 00
CLOSE-OUT PROCEDURES
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 SUBSTANTIAL COMPLETION
- 1.4 FINAL COMPLETION
- 1.5 LIST OF INCOMPLETE ITEMS (PUNCH LIST)
- 1.6 WARRANTIES

PART 2 PRODUCTS

- 2.1 MATERIALS

PART 3 EXECUTION

- 3.1 FINAL CLEANING

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 77 00

CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Inspection procedures.
 - 2. Substantial Completion procedures.
 - 3. Final completion procedures.
 - 4. Warranties.
 - 5. Final cleaning.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 29 00 "Payment Procedures" for requirements for Applications for Payment for Substantial and Final Completion.
 - 2. Division 01 Section 01 73 00 "Execution" for progress cleaning of Project site.
 - 3. Division 01 Section 01 78 39 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
 - 4. Division 01 Section 01 78 23 "Operation and Maintenance Data" for operation and maintenance manual requirements.
 - 5. Division 01 Section 01 79 00 "Demonstration and Training" for requirements for instructing Owner's personnel.
 - 6. Divisions 02 through 26 Sections for specific closeout and special cleaning requirements for the Work in those Sections.

1.3 SUBSTANTIAL COMPLETION

- A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request.
 - 1. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
 - 2. Advise Owner of pending insurance changeover requirements.
 - 3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 - 4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.

5. Prepare and submit Project Record Documents, operation and maintenance manuals, damage or settlement surveys, property surveys, and similar final record information.
6. Deliver tools, spare parts, extra materials, and similar items to location designated by Owner. Label with manufacturer's name and model number where applicable.
7. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
8. Complete startup testing of systems.
9. Submit test/adjust/balance records.
10. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
11. Advise Owner of changeover in heat and other utilities.
12. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
13. Complete final cleaning requirements, including touchup painting.
14. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.

B. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. Engineer will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Engineer, that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for Final Completion.

1.4 FINAL COMPLETION

A. Preliminary Procedures: Before requesting final inspection for determining date of Final Completion, complete the following:

1. Submit a final Application for Payment according to Division 01 Section 01 29 00 "Payment Procedures."
2. Submit certified copy of Engineer's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Engineer. The certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
3. Submit evidence of final, continuing insurance coverage complying with insurance requirements.
4. Submit pest-control final inspection report and warranty.
5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training videotapes.

B. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. Engineer will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.5 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Preparation: Submit three copies of list. Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
 1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor.
 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Engineer.
 - d. Name of Contractor.
 - e. Page number.

1.6 WARRANTIES

- A. Submittal Time: Submit written warranties on request of Engineer for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated.
- B. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
 1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch (215-by-280-mm) paper.
 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
 3. Identify each binder on the front and spine with the typed or printed title "INDIAN RIVER SCHOOL DISTRICT - (The appropriate name of the school where the manual will be stored) – HEAT OF REJECTION EQUIPMENT REPLACEMENT," Project name, and name of Contractor.
 4. Scan warranties and bonds and assemble complete warranty and bond submittal package into a single indexed electronic PDF file with links enabling navigation to each item. Provide table of contents at beginning of document.
- C. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Provide final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers for final cleaning. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
 - c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
 - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
 - e. Remove snow and ice to provide safe access to building.
 - f. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
 - g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
 - h. Sweep concrete floors broom clean in unoccupied spaces.
 - i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; shampoo if visible soil or stains remain.
 - j. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
 - k. Remove labels that are not permanent.

- l. Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.
 - 1) Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates.
 - m. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
 - n. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
 - o. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
 - p. Clean ducts and make-up air units if units were operated without filters during construction or that display contamination with particulate matter upon inspection.
 - q. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burned-out bulbs, and those noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.
 - r. Leave Project clean and ready for occupancy.
- C. Comply with safety standards for cleaning. Do not burn waste materials. Do not bury debris or excess materials on Owner's property. Do not discharge volatile, harmful, or dangerous materials into drainage systems. Remove waste materials from Project site and dispose of lawfully.
- D. Construction Waste Disposal: Comply with waste disposal requirements in Division 01 Section 01 50 00 "Temporary Facilities and Controls."

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 78 23
OPERATION AND MAINTENANCE DATA
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 CLOSE OUT SUBMITTALS
- 1.5 COORDINATION

PART 2 PRODUCTS

- 2.1 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY
- 2.2 MANUALS, GENERAL
- 2.3 OPERATION MANUALS
- 2.4 PRODUCT MAINTENANCE MANUALS

PART 3 EXECUTION

- 3.1 MANUAL PREPARATION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 78 23
OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - 1. Operation and maintenance documentation directory.
 - 2. Emergency manuals.
 - 3. Operation manuals for systems, subsystems, and equipment.
 - 4. Maintenance manuals for the care and maintenance of systems and equipment.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 33 00 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.
 - 2. Division 01 Section 01 77 00 "Closeout Procedures" for submitting operation and maintenance manuals.
 - 3. Division 01 Section 01 78 39 "Project Record Documents" for preparing Record Drawings for operation and maintenance manuals.
 - 4. Divisions 02 through 26 Sections for specific operation and maintenance manual requirements for the Work in those Sections.
- C. For each school, three (3) separate Operations and Maintenance Manuals shall be provided.

1.3 DEFINITIONS

- A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.
- B. Subsystem: A portion of a system with characteristics similar to a system.

1.4 SUBMITTALS

- A. Initial Submittal: Submit 2 draft copies of each manual at least 15 days before requesting inspection for Substantial Completion. Include a complete operation and maintenance directory. Engineer will return both copy of draft and mark whether general scope and content of manual are acceptable.

- B. Final Submittal: Submit one copy of each manual in final form at least 15 days before final inspection. Engineer will return copy with comments within 15 days after final inspection.
 - 1. Correct or modify each manual to comply with Engineer's comments. Submit three (3) copies of each corrected manual within 15 days of receipt of Engineer's comments and one (1) copy electronically.

1.5 COORDINATION

- A. Where operation and maintenance documentation includes information on installations by more than one factory-authorized service representative, assemble and coordinate information furnished by representatives and prepare manuals.

PART 2 - PRODUCTS

2.1 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY

- A. Organization: Include a section in the directory for each of the following:
 - 1. List of documents.
 - 2. List of equipment.
 - 3. Table of contents.
- B. List of Systems and Subsystems: List systems alphabetically. Include references to operation and maintenance manuals that contain information about each system.
- C. List of Equipment: List equipment for each system, organized alphabetically by system. For pieces of equipment not part of system, list alphabetically in separate list.
- D. Tables of Contents: Include a table of contents for each emergency, operation, and maintenance manual.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

2.2 MANUALS, GENERAL

- A. Organization: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:
 - 1. Title page.
 - 2. Table of contents.
 - 3. Manual contents.

B. Title Page: Enclose title page in transparent plastic sleeve. Include the following information:

1. Subject matter included in manual.
2. Name and address of Project.
3. Name and address of Owner.
4. Date of submittal.
5. Name, address, and telephone number of Contractor.
6. Name and address of Engineer.
7. Cross-reference to related systems in other operation and maintenance manuals.

C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.

1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.

D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.

1. Binders: Heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch (215-by-280-mm) paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.
 - a. If two or more binders are necessary to accommodate data of a system, organize data in each binder into groupings by subsystem and related components. Cross-reference other binders if necessary to provide essential information for proper operation or maintenance of equipment or system.
 - b. At least three (3) manuals shall be created for each of the six (6) schools included in this project.
 - c. Identify each binder on front and spine, with printed title "INDIAN RIVER SCHOOL DISTRICT- (The appropriate name of the school where the manual will be stored) – HEAT OF REJECTION EQUIPMENT REPLACEMENT" and subject matter of contents. Indicate volume number for multiple-volume sets.
2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software diskettes for computerized electronic equipment.
4. Supplementary Text: Prepared on 8-1/2-by-11-inch (215-by-280-mm) white bond paper.
5. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.
 - a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
 - b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in

manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

2.3 OPERATION MANUALS

- A. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
1. System, subsystem, and equipment descriptions.
 2. Performance and design criteria if Contractor is delegated design responsibility.
 3. Operating standards.
 4. Operating procedures.
 5. Operating logs.
 6. Wiring diagrams.
 7. Control diagrams.
 8. Piped system diagrams.
 9. Precautions against improper use.
 10. License requirements including inspection and renewal dates.
- B. Descriptions: Include the following:
1. Product name and model number.
 2. Manufacturer's name.
 3. Equipment identification with serial number of each component.
 4. Equipment function.
 5. Operating characteristics.
 6. Limiting conditions.
 7. Performance curves.
 8. Engineering data and tests.
 9. Complete nomenclature and number of replacement parts.
- C. Operating Procedures: Include the following, as applicable:
1. Startup procedures.
 2. Equipment or system break-in procedures.
 3. Routine and normal operating instructions.
 4. Regulation and control procedures.
 5. Instructions on stopping.
 6. Normal shutdown instructions.
 7. Seasonal and weekend operating instructions.
 8. Required sequences for electric or electronic systems.
 9. Special operating instructions and procedures.
- D. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.

2.4 PRODUCT MAINTENANCE MANUAL

- A. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- B. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual.
- C. Product Information: Include the following, as applicable:
 - 1. Product name and model number.
 - 2. Manufacturer's name.
 - 3. Color, pattern, and texture.
 - 4. Material and chemical composition.
 - 5. Reordering information for specially manufactured products.
- D. Maintenance Procedures: Include manufacturer's written recommendations and the following:
 - 1. Inspection procedures.
 - 2. Types of cleaning agents to be used and methods of cleaning.
 - 3. List of cleaning agents and methods of cleaning detrimental to product.
 - 4. Schedule for routine cleaning and maintenance.
 - 5. Repair instructions.
- E. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- F. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.

PART 3 - EXECUTION

3.1 MANUAL PREPARATION

- A. Operation and Maintenance Documentation Directory: Prepare a separate manual that provides an organized reference to emergency, operation, and maintenance manuals.
- B. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.
- C. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.

- D. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.
 - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
 - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- E. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
 - 1. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
- F. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in Record Drawings to ensure correct illustration of completed installation.
 - 1. Do not use original Project Record Documents as part of operation and maintenance manuals.
 - 2. Comply with requirements of newly prepared Record Drawings in Division 01 Section 01 78 39 "Project Record Documents."
- G. Comply with Division 01 Section 01 77 00 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

END OF SECTION

SECTION 01 78 39
PROJECT RECORD DOCUMENTS
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 SUBMITTALS

PART 2 PRODUCTS

- 2.1 RECORD DRAWINGS
- 2.2 RECORD SPECIFICATIONS
- 2.3 RECORD PRODUCT DATA
- 2.4 MISCELLANEOUS RECORD SUBMITTALS

PART 3 EXECUTION

- 3.1 RECORDING AND MAINTENANCE

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 78 39
PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for Project Record Documents, including the following:
 - 1. Record Drawings.
 - 2. Record Specifications.
 - 3. Record Product Data.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 73 00 "Execution Requirements" for final property survey.
 - 2. Division 01 Section 01 77 00 "Closeout Procedures" for general closeout procedures.
 - 3. Division 01 Section 01 78 23 "Operation and Maintenance Data" for operation and maintenance manual requirements.
 - 4. Divisions 02 through 28 Sections for specific requirements for project record documents of the Work in those Sections
- C. Separate project record documents shall be provided for each school.

1.3 SUBMITTALS

- A. Record Drawings: Comply with the following:
 - 1. Number of Copies: Submit one set(s) of marked-up Record Prints.
- B. Record Specifications: Submit one copy of Project's Specifications, including addenda and contract modifications.
- C. Record Product Data: Submit one copy of each Product Data submittal.
 - 1. Where Record Product Data is required as part of operation and maintenance manuals, submit marked-up Product Data as an insert in manual instead of submittal as Record Product Data.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of blue- or black-line white prints of the Contract Drawings and Shop Drawings.
1. Preparation: Mark Record Prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to prepare the marked-up Record Prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Accurately record information in an understandable drawing technique.
 - c. Record data as soon as possible after obtaining it. Record and check the markup before enclosing concealed installations.
 2. Content: Types of items requiring marking include, but are not limited to, the following:
 - a. Dimensional changes to Drawings.
 - b. Revisions to details shown on Drawings.
 - c. Revisions to routing of piping and conduits.
 - d. Revisions to electrical circuitry.
 - e. Actual equipment locations.
 - f. Locations of concealed internal utilities.
 - g. Changes made by Change Order or Construction Change Directive.
 - h. Changes made following Engineer's written orders.
 - i. Details not on the original Contract Drawings.
 - j. Field records for variable and concealed conditions.
 - k. Record information on the Work that is shown only schematically.
 3. Mark the Contract Drawings or Shop Drawings, whichever is most capable of showing actual physical conditions, completely and accurately. If Shop Drawings are marked, show cross-reference on the Contract Drawings.
 4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
 6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.
- B. Record Transparencies: Immediately before inspection for Certificate of Substantial Completion, review marked-up Record Prints with Engineer. When authorized, prepare a full set of corrected transparencies of the Contract Drawings and Shop Drawings.
1. Incorporate changes and additional information previously marked on Record Prints. Erase, redraw, and add details and notations where applicable.
 2. Refer instances of uncertainty to Engineer for resolution.

3. Owner will furnish Contractor one set of transparencies of the Contract Drawings for use in recording information.
 4. Print the Contract Drawings and Shop Drawings for use as Record Transparencies. Engineer will make the Contract Drawings available to Contractor's print shop.
- C. Format: At least one (1) set of record drawings shall be created for each of the six (6) schools included in this project. Identify and date each Record Drawing; include the designation "INDIAN RIVER SCHOOL DISTRICT – (The Appropriate Name of the School where The Drawings will be Stored) – HEAT OF REJECTION EQUIPMENT REPLACEMENT - PROJECT RECORD DRAWING" in a prominent location.
1. Record Prints: Organize Record Prints and newly prepared Record Drawings into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
 2. Record Transparencies: Organize into unbound sets matching Record Prints. Place transparencies in durable tube-type drawing containers with end caps. Mark end cap of each container with identification. If container does not include a complete set, identify Drawings included.
 3. Identification: As follows:
 - a. Project name.
 - b. Date.
 - c. Designation "INDIAN RIVER SCHOOL DISTRICT – (The Appropriate Name of the School where The Drawings Will Be Stored) – HEAT OF REJECTION EQUIPMENT REPLACEMENT - PROJECT RECORD DRAWINGS"
 - d. Name of Engineer.
 - e. Name of Contractor.

2.2 RECORD SPECIFICATIONS

- A. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
 4. For each principal product, indicate whether Record Product Data has been submitted in operation and maintenance manuals instead of submitted as Record Product Data.
 5. Note related Change Orders, Record Product Data, and Record Drawings where applicable.

2.3 RECORD PRODUCT DATA

- A. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
3. Note related Change Orders, Record Specifications, and Record Drawings where applicable.

2.4 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

- A. Recording: Maintain one copy of each submittal during the construction period for Project Record Document purposes. Post changes and modifications to Project Record Documents as they occur; do not wait until the end of Project.
- B. Maintenance of Record Documents and Samples: Store Record Documents and Samples in the field office apart from the Contract Documents used for construction. Do not use Project Record Documents for construction purposes. Maintain Record Documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to Project Record Documents for Engineer's reference during normal working hours.

END OF SECTION

SECTION 01 79 00
DEMONSTRATION AND TRAINING
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 SUBMITTALS
- 1.4 CLOSE OUT SUBMITTALS
- 1.5 QUALITY ASSURANCE
- 1.6 COORDINATION

PART 2 PRODUCTS

- 2.1 INSTRUCTION PROGRAM

PART 3 EXECUTION

- 3.1 PREPARATION
- 3.2 INSTRUCTION

THIS PAGE LEFT INTENTIONALLY LEFT BLANK

SECTION 01 79 00
DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
 - 1. Demonstration of operation of systems, subsystems, and equipment.
 - 2. Training in operation and maintenance of systems, subsystems, and equipment.
 - 3. Demonstration and training video recordings.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 31 00 "Project Management and Coordination" for requirements for pre-instruction conferences.
 - 2. Divisions 02 through 26 Sections for specific requirements for demonstration and training for products in those Sections.
- C. Demonstration and training shall occur at the site of each school and a separate video recording of the same shall be provided for each school.

1.3 SUBMITTALS

- A. Instruction Program: Submit two copies of outline of instructional program for demonstration and training, including a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.
 - 1. At completion of training, submit one complete training manual(s) for Owner's use.
- B. Qualification Data: For instructor.
- C. Attendance Record: For each training module, submit list of participants and length of instruction time.
- D. Evaluations: For each participant and for each training module, submit results and documentation of performance-based test.

1.4 CLOSEOUT SUBMITTALS

- A. Demonstration and Training Video Recordings: Submit two copies within seven days of end of each training module.
 - 1. Identification: On each copy, provide an applied label with the following information:
 - a. Name of Project.
 - b. Name of Engineer.
 - c. Name of Contractor.
 - d. Date of video recording.
 - 2. Transcript: Prepared on 8-1/2-by-11-inch (215-by-280-mm) paper, punched and bound in heavy-duty, three-ring, vinyl-covered binders. Mark appropriate identification on front and spine of each binder. Include a cover sheet with same label information as the corresponding video recording. Include name of Project and date of video recording on each page.
 - 3. At completion of training, submit complete training manual(s) for Owner's use.

1.5 QUALITY ASSURANCE

- A. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.
- B. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Division 01 Section 01 40 00 "Quality Requirements," experienced in operation and maintenance procedures and training.
- C. Preinstruction Conference: Conduct conference at Project site to comply with requirements in Division 01 Section 01 31 00 "Project Management and Coordination." Review methods and procedures related to demonstration and training including, but not limited to, the following:
 - 1. Inspect and discuss locations and other facilities required for instruction.
 - 2. Review and finalize instruction schedule and verify availability of educational materials, instructors' personnel, audiovisual equipment, and facilities needed to avoid delays.
 - 3. Review required content of instruction.
 - 4. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.

1.6 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.

- C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data has been reviewed and approved by Engineer.

PART 2 - PRODUCTS

2.1 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and equipment not part of a system, as required by individual Specification Sections, and as follows:
 - 1. Electrical components
 - 2. ATC System
 - 3. Cooling Tower
 - 4. Water Treatment Systems
 - 5. Closed Circuit Evaporated Fluid Cooler
 - 6. Pumps
 - 7. Variable Frequency Drives
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following:
 - 1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
 - a. System, subsystem, and equipment descriptions.
 - b. Performance and design criteria if Contractor is delegated design responsibility.
 - c. Operating standards.
 - d. Regulatory requirements.
 - e. Equipment function.
 - f. Operating characteristics.
 - g. Limiting conditions.
 - h. Performance curves.
 - 2. Documentation: Review the following items in detail:
 - a. Operations manuals.
 - b. Maintenance manuals.
 - c. Project Record Documents.
 - d. Identification systems.
 - e. Warranties and bonds.
 - f. Maintenance service agreements and similar continuing commitments.
 - 3. Emergencies: Include the following, as applicable:
 - a. Instructions on meaning of warnings, trouble indications, and error messages.
 - b. Instructions on stopping.
 - c. Shutdown instructions for each type of emergency.
 - d. Operating instructions for conditions outside of normal operating limits.
 - e. Sequences for electric or electronic systems.

- f. Special operating instructions and procedures.
- 4. Operations: Include the following, as applicable:
 - a. Startup procedures.
 - b. Equipment or system break-in procedures.
 - c. Routine and normal operating instructions.
 - d. Regulation and control procedures.
 - e. Control sequences.
 - f. Safety procedures.
 - g. Instructions on stopping.
 - h. Normal shutdown instructions.
 - i. Operating procedures for emergencies.
 - j. Operating procedures for system, subsystem, or equipment failure.
 - k. Seasonal and weekend operating instructions.
 - l. Required sequences for electric or electronic systems.
 - m. Special operating instructions and procedures.
- 5. Adjustments: Include the following:
 - a. Alignments.
 - b. Checking adjustments.
 - c. Noise and vibration adjustments.
 - d. Economy and efficiency adjustments.
- 6. Troubleshooting: Include the following:
 - a. Diagnostic instructions.
 - b. Test and inspection procedures.
- 7. Maintenance: Include the following:
 - a. Inspection procedures.
 - b. Types of cleaning agents to be used and methods of cleaning.
 - c. List of cleaning agents and methods of cleaning detrimental to product.
 - d. Procedures for routine cleaning
 - e. Procedures for preventive maintenance.
 - f. Procedures for routine maintenance.
 - g. Instruction on use of special tools.
- 8. Repairs: Include the following:
 - a. Diagnosis instructions.
 - b. Repair instructions.
 - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - d. Instructions for identifying parts and components.
 - e. Review of spare parts needed for operation and maintenance.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a combined training manual organized in coordination with requirements in Division 01 Section 01 78 23 "Operations and Maintenance Data."
- B. Set up instructional equipment at instruction location.

3.2 INSTRUCTION

- A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.
- B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
 - 1. Engineer will furnish an instructor to describe basis of system design, operational requirements, criteria, and regulatory requirements.
 - 2. Owner will furnish an instructor to describe Owner's operational philosophy.
 - 3. Owner will furnish Contractor with names and positions of participants.
- C. Scheduling: Provide instruction at mutually agreed on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.
 - 1. Schedule training with Owner, through Engineer, with at least seven days' advance notice.
- D. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 01 SECTION 01 91 13
GENERAL COMMISSIONING REQUIREMENTS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS	3
1.2. SUMMARY	3
1.3. DEFINITIONS	3
1.4. COMMISSIONING TEAM	3
1.5. OWNER'S RESPONSIBILITIES	4
1.6. CONTRACTOR'S RESPONSIBILITIES	4
1.7. CxA'S RESPONSIBILITIES	5
1.8. COMMISSIONING DOCUMENTATION	6
1.9. SUBMITTALS	10
1.10. QUALITY ASSURANCE	10
1.11. COORDINATION	10
1.12. ALTERNATES	11
PART 2. PRODUCTS (NOT USED)	11
PART 3. EXECUTION	11
3.1. OPERATION AND MAINTENANCE TRAINING REQUIREMENTS	11
END OF SECTION	11

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 91 13 – GENERAL COMMISSIONING REQUIREMENTS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2. SUMMARY

- A. This Section includes general requirements that apply to implementation of commissioning without regard to systems, subsystems, and equipment being commissioned.
- B. Related Sections include the following:
 - 1. Division 01 Section "HVAC Commissioning Requirements" for specific requirements for commissioning HVAC systems.
 - 2. Division 01 Section "Plumbing Commissioning Requirements" for specific requirements for commissioning Plumbing systems.
 - 3. Division 01 Section "Closeout Procedures" for specific requirements for closeout at substantial and final completion.
 - 4. Division 01 Section "Closeout Procedures" for Specific Requirements for training and demonstration of systems to Owner.
 - 5. Division 01 Section "Closeout Procedures" for Specific Requirements related to the Preparation of systems operation and maintenance manuals.

1.3. DEFINITIONS

- A. CxA: Commissioning Authority.
- B. OPR: Owner's Project Requirements.
- C. Systems, Subsystems, and Equipment: Where these terms are used together or separately, they shall mean "as-built" systems, subsystems, and equipment.
- D. TAB: Testing, Adjusting, and Balancing.

1.4. COMMISSIONING TEAM

- A. Members Appointed by Contractor(s): Individuals, each having authority to act on behalf of the entity he or she represents, explicitly organized to implement the commissioning process through coordinated actions. The commissioning team shall consist of, but not be limited to, representatives of Contractor, including Project superintendent and subcontractors, installers, suppliers, and specialists deemed appropriate by the CxA.
- B. Members Appointed by Owner:

1. CxA: The designated person, company, or entity that plans, schedules, and coordinates the commissioning team to implement the commissioning process. Owner will engage the CxA under a separate contract.
2. All contractor commissioning requirements and costs associated with commissioning the project shall be included in the base bid.
3. Representatives of the facility user and operation and maintenance personnel.
4. Engineering design professionals.

1.5. OWNER'S RESPONSIBILITIES

- A. Assign operation and maintenance personnel and schedule them to participate in commissioning team activities including, but not limited to, the following:
 1. Coordination meetings.
 2. Training in operation and maintenance of systems, subsystems, and equipment.
 3. Testing meetings.
 4. Demonstration of operation of systems, subsystems, and equipment.

1.6. CONTRACTOR'S RESPONSIBILITIES

- A. Provide utility services required for the commissioning process.
- B. Contractor shall assign representatives with expertise and authority to act on behalf of the Contractor and schedule them to participate in and perform commissioning team activities including, but not limited to, the following:
 1. Participate in commissioning and construction-phase coordination meetings.
 2. Participate in maintenance orientation and inspection.
 3. Participate in operation and maintenance training sessions.
 4. Participate in final review at acceptance meeting.
 5. Certify that Work is complete and systems are operational according to the Contract Documents, including calibration of instrumentation and controls.
 6. Evaluate performance deficiencies identified in test reports and, in collaboration with entity responsible for system and equipment installation, recommend corrective action.
 7. Review and approve final commissioning documentation.
 8. Certify that all pre-test work and pre-testing of functional performance tests are complete and operational prior to scheduling performed testing by CxA. Submit completed functional performance test forms with data from pre-testing.

9. During functional performance testing, a representative from the mechanical contractor, controls contractor, and test/balance engineer must be present and participate in testing.
- C. Subcontractors shall assign representatives with expertise and authority to act on behalf of subcontractors and schedule them to participate in and perform commissioning team activities including, but not limited to, the following:
1. Pre-test all systems/equipment prior to engaging CxA for Functional Performance Testing.
 2. Participate in commissioning and construction-phase coordination meetings.
 3. Participate in maintenance orientation and inspection.
 4. Participate in procedures meeting for testing.
 5. Participate in final review at acceptance meeting.
 6. Provide schedule for operation and maintenance data submittals, equipment startup, and testing to CxA for incorporation into the commissioning plan. Update schedule on a weekly basis throughout the construction period.
 7. Provide information to the CxA for developing construction-phase commissioning plan.
 8. Participate in training sessions for Owner's operation and maintenance personnel.
 9. Provide updated Project Record Documents to the CxA on a daily basis.
 10. Gather and submit operation and maintenance data for systems, subsystems, and equipment to the CxA, as specified in Division 01 Section "Operation and Maintenance Data."
 11. Provide technicians who are familiar with the construction and operation of installed systems and who shall develop specific test procedures and participate in testing of installed systems, subsystems, and equipment.
 12. The test/balance subcontractor, mechanical contractor, and automatic temperature controls subcontractor must be on-site and provide assistance during all functional performance testing.
- D. Contractors and subcontractors must pre-inspect and pre-test all equipment and systems prior to requesting functional performance testing by the CxA. All pre-start/start-up checklists and functional performance test forms must be completed and submitted to Engineer prior to scheduling formal functional performance testing.

1.7. CXA'S RESPONSIBILITIES

- A. Organize and lead the commissioning team.
- B. Prepare a construction-phase commissioning plan. Collaborate with Contractor and with

subcontractors to develop test and inspection procedures. Include design changes and scheduled commissioning activities coordinated with overall Project schedule. Identify commissioning team member responsibilities, by name, firm, and trade specialty, for performance of each commissioning task.

- C. Convene commissioning team meetings for the purpose of coordination, communication, and conflict resolution; discuss progress of the commissioning processes. Responsibilities include arranging for facilities, preparing agenda and attendance lists, and notifying participants. The CxA shall prepare and distribute minutes to commissioning team members and attendees within five workdays of the commissioning meeting.
- D. At a mutually agreed upon time, conduct an initial construction-phase coordination meeting for the purpose of reviewing the commissioning activities and establishing tentative schedules for operation and maintenance submittals; operation and maintenance training sessions; TAB Work; and Project completion.
- E. Observe and inspect construction and report progress and deficiencies. In addition to compliance with the Contract Documents, inspect systems and equipment installation for adequate accessibility for maintenance and component replacement or repair.
- F. Prepare Project-specific test and inspection procedures and checklists.
- G. Schedule, direct, witness, and document tests, inspections, and systems startup.
- H. Compile test data, inspection reports, and certificates and include them in the systems manual and commissioning report.
- I. Certify date of acceptance and startup for each item of equipment for start of warranty periods.
- J. Review Project Record Documents for accuracy. Request revisions from Contractor to achieve accuracy. Project Record Documents requirements are specified in Division 01 Section "Project Record Documents."
- K. Review and comment on operation and maintenance documentation and systems manual outline for compliance with the Contract Documents. Operation and maintenance documentation requirements are specified in Division 01 Section "Operation and Maintenance Data."
- L. Assemble the final commissioning documentation, including the commissioning report and Project Record Documents.

1.8. COMMISSIONING DOCUMENTATION

- A. Commissioning Plan: A document, prepared by CxA, that outlines the schedule, allocation of resources, and documentation requirements of the commissioning process, and shall include, but is not limited to the following:
 - 1. Plan for delivery and review of submittals, systems manuals, and other documents and reports. Identification of the relationship of these documents to other functions and a detailed description of submittals that are required to support the

- commissioning processes. Submittal dates shall include the latest date approved submittals must be received without adversely affecting commissioning plan.
2. Description of the organization, layout, and content of commissioning documentation (including systems manual) and a detailed description of documents to be provided along with identification of responsible parties.
 3. Identification of systems and equipment to be commissioned.
 4. Description of schedules for testing procedures along with identification of parties involved in performing and verifying tests.
 5. Identification of items that must be completed before the next operation can proceed.
 6. Description of responsibilities of commissioning team members.
 7. Description of observations to be made.
 8. Description of requirements for operation and maintenance training, including required training materials.
 9. Description of expected performance for systems, subsystems, equipment, and controls.
 10. Schedule for commissioning activities with specific dates coordinated with overall construction schedule.
 11. Identification of installed systems, subsystems, and equipment, including design changes that occurred during the construction phase.
 12. Process and schedule for documenting changes on a continuous basis to appear in Project Record Documents.
 13. Process and schedule for completing prestart and startup checklists for systems, subsystems, and equipment to be verified and tested.
 14. Step-by-step procedures for testing systems, subsystems, and equipment with descriptions for methods of verifying relevant data, recording the results obtained, and listing parties involved in performing and verifying tests.
- B. Test Checklists: CxA, with assistance of Contractor and Subcontractors, shall develop test checklists for each system, subsystem, or equipment including interfaces and interlocks, and include a separate entry, with space for comments, for each item to be tested. Prepare separate checklists for each mode of operation and provide space to indicate whether the mode under test responded as required. Provide space for testing personnel to sign off on each checklist. Specific checklist content requirements are specified in Division 01 Sections "HVAC Commissioning Requirements" and "Plumbing System Commissioning Requirements". Test checklists will be jointly developed as the project progresses. Each checklist, regardless of system, subsystem, or equipment being tested, shall include, but not be limited to, the following:

1. Name and identification code of tested item.
 2. Test number.
 3. Time and date of test.
 4. Indication of whether the record is for a first test or retest following correction of a problem or issue.
 5. Dated signatures of the person performing test and of the witness, if applicable.
 6. Individuals present for test.
 7. Deficiencies.
 8. Issue number, if any, generated as the result of test.
- C. Certificate of Readiness: Certificate of Readiness shall be signed by Contractor, Subcontractor(s), Installer(s), and CxA certifying that systems, subsystems, equipment, and associated controls are ready for testing. Completed test checklists signed by the responsible parties shall accompany this certificate.
- D. Test and Inspection Reports: CxA shall record test data, observations, and measurements on test checklists. Photographs, forms, and other means appropriate for the application shall be included with data. CxA shall compile test and inspection reports and test and inspection certificates and include them in systems manual and commissioning report.
- E. Corrective Action Documents: CxA shall document corrective action taken for systems and equipment that fail tests. Include required modifications to systems and equipment and revisions to test procedures, if any. Retest systems and equipment requiring corrective action and document retest results.
- F. Issues Log: CxA shall prepare and maintain an issues log that describes design, installation, and performance issues that are at variance with the Contract Documents. Identify and track issues as they are encountered, documenting the status of unresolved and resolved issues.
1. Creating an Issues Log Entry:
 - a. Identify the issue with unique numeric or alphanumeric identifier by which the issue may be tracked.
 - b. Assign a descriptive title of the issue.
 - c. Identify date and time of the issue.
 - d. Identify test number of test being performed at the time of the observation, if applicable, for cross-reference.
 - e. Identify system, subsystem, and equipment to which the issue applies.
 - f. Identify location of system, subsystem, and equipment.
 - g. Include information that may be helpful in diagnosing or evaluating the issue.
 - h. Note recommended corrective action.
 - i. Identify commissioning team member responsible for corrective action.

- j. Identify expected date of correction.
 - k. Identify person documenting the issue.
2. Documenting Issue Resolution:
- a. Log date correction is completed or the issue is resolved.
 - b. Describe corrective action or resolution taken. Include description of diagnostic steps taken to determine root cause of the issue, if any.
 - c. Identify changes to the Contract Documents that may require action.
 - d. State that correction was completed and system, subsystem, and equipment is ready for retest, if applicable.
 - e. Identify person(s) who corrected or resolved the issue.
 - f. Identify person(s) documenting the issue resolution.
3. Issues Log Report: On a periodic basis, but not less than for each commissioning team meeting, CxA shall prepare a written narrative for review of outstanding issues and a status update of the issues log. As a minimum, CxA shall include the following information in the issues log and expand it in the narrative:
- a. Issue number and title.
 - b. Date of the identification of the issue.
 - c. Name of the commissioning team member assigned responsibility for resolution.
 - d. Expected date of correction.
- G. Commissioning Report: CxA shall document results of the commissioning process including unresolved issues and performance of systems, subsystems, and equipment. The commissioning report shall indicate whether systems, subsystems, and equipment have been completed and are performing according to the Contract Documents. The commissioning report shall include, but is not limited to, the following:
- 1. Lists and explanations of substitutions; compromises; variances in the Contract Documents; record of conditions; and, if appropriate, recommendations for resolution. This report shall be used to evaluate systems, subsystems, and equipment and shall serve as a future reference document during Owner occupancy and operation. It shall describe components and performance that exceed requirements of the Contract Documents and those that do not meet requirements of the Contract Documents. It may also include a recommendation for accepting or rejecting systems, subsystems, and equipment.
 - 2. Commissioning plan.
 - 3. Testing plans and reports.
 - 4. Corrective modification documentation.
 - 5. Issues log.
 - 6. Completed test checklists.
 - 7. Punch Lists.

8. Test/Balance Reports.
 9. Listing of off-season test(s) not performed and a schedule for their completion.
 10. All commissioning documents must be submitted to the building Owner within 90 days of the date of receipt of the Certificate of Occupancy.
- H. Systems Manual: CxA shall gather required information and compile systems manual. Systems manual shall include, but is not limited to, the following:
1. Project Record Documents as specified in Division 01 Section "Project Record Documents."
 2. Final commissioning plan.
 3. Commissioning report.
 4. Operation and maintenance data as specified in Division 01 Section "Operation and Maintenance Data."

1.9. SUBMITTALS

- A. Test Checklists and Report Forms: CxA shall submit sample checklists and forms to Contractor quality-control manager and subcontractors for review and comment. Submit two copies of each checklist and report form.
- B. Test and Inspection Reports: CxA shall submit test and inspection reports.
- C. Corrective Action Documents: CxA shall submit corrective action documents.

1.10. QUALITY ASSURANCE

- A. Instructor Qualifications: Factory-authorized service representatives, experienced in training, operation, and maintenance procedures for installed systems, subsystems, and equipment.
- B. Test Equipment Calibration: Comply with test equipment manufacturer's calibration procedures and intervals. Recalibrate test instruments immediately whenever instruments have been repaired following damage or dropping. Affix calibration tags to test instruments. Instruments shall have been calibrated within six months prior to use.

1.11. COORDINATION

- A. Coordinating Meetings: CxA shall conduct coordination meetings of the commissioning team to review progress on the commissioning plan, to discuss scheduling conflicts, and to discuss upcoming commissioning process activities.
- B. Pretesting Meetings: CxA shall conduct pretest meetings of the commissioning team to review startup reports, pretest inspection results, testing procedures, testing personnel and instrumentation requirements, and manufacturers' authorized service representative services for each system, subsystem, equipment, and component to be tested.

- C. Testing Coordination: CxA shall coordinate sequence of testing activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
 - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
- D. Manufacturers' Field Services: CxA and Contractor shall coordinate services of manufacturers' field services.

1.12. ALTERNATES

- A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION

3.1. OPERATION AND MAINTENANCE TRAINING REQUIREMENTS

- A. Training Preparation Conference: Before operation and maintenance training, CxA shall convene a training preparation conference to include Owner's operation and maintenance personnel, Contractor, and subcontractors. In addition to requirements specified in Division 01 Section "Demonstration and Training," perform the following:
 - 1. Review installed systems, subsystems, and equipment.
 - 2. Review instructor qualifications.
 - 3. Review instructional methods and procedures.
 - 4. Review training module outlines and contents.
 - 5. Review course materials (including operation and maintenance manuals).
 - 6. Inspect and discuss locations and other facilities required for instruction.
 - 7. Review and finalize training schedule and verify availability of educational materials, instructors, audiovisual equipment, and facilities needed to avoid delays.
 - 8. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.
- B. Training Modules: Develop an instruction program that includes individual training modules for each system, subsystem, and equipment as specified in Division 01 Section "Demonstration and Training."

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 01 SECTION 01 91 14
PLUMBING COMMISSIONING REQUIREMENTS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SUMMARY	3
1.3. DEFINITIONS.....	3
1.4. CONTRACTOR'S RESPONSIBILITIES.....	3
1.5. COMMISSIONING DOCUMENTATION	5
1.6. SUBMITTALS	5
1.7. ALTERNATES.....	6
PART 2. PRODUCTS (NOT USED)	6
PART 3. EXECUTION.....	6
3.1. TESTING PREPARATION.....	6
3.2. TAB VERIFICATION	7
3.3. TESTING	8
END OF SECTION	10

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 91 14- PLUMBING COMMISSIONING REQUIREMENTS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2. SUMMARY

- A. This Section includes requirements for commissioning the plumbing system and its subsystems and equipment. This Section supplements the general requirements specified in Division 01 Section "General Commissioning Requirements."
- B. Related Sections include the following:
 - 1. Division 01 Section "General Commissioning Requirements" for general requirements for commissioning processes that apply to this Section.
- C. The following systems and/or equipment shall be commissioned:
 - 1. Bleed Water motorized ball valves.
 - 2. Backflow preventers.
 - 3. Closed circuit evaporative fluid cooler/cooling tower water meters.
 - 4. Domestic water meters (including interlock to ATC system and water treatment system).
 - 5. Make-up water motorized ball valves.

1.3. DEFINITIONS

- A. Architect: Includes Architect identified in the Contract for Construction between Owner and Contractor, plus consultant/design professionals responsible for design of plumbing systems, electrical, communications, controls for plumbing systems, and other related systems.
- B. CxA: Commissioning Authority.
- C. Systems, Subsystems, and Equipment: Where these terms are used together or separately, they shall mean "as-built" systems, subsystems, and equipment.
- D. TAB: Testing, Adjusting, and Balancing.

1.4. CONTRACTOR'S RESPONSIBILITIES

- A. The following responsibilities are in addition to those specified in Division 01 Section "General Commissioning Requirements."

B. Contractor:

1. Attend procedures meeting for TAB Work.
2. Certify that TAB Work is complete.
3. Assist performing functional performance tests.

C. Mechanical Contractor:

1. Attend TAB verification testing.
2. Provide measuring instruments and logging devices to record test data, and data acquisition equipment to record data for the complete range of testing for the required test period.
3. Assist performing functional performance tests.

D. HVAC Instrumentation and Control Contractor: With the CxA, review control designs for compliance with the Contract Documents, controllability with respect to actual equipment to be installed, and recommend adjustments to control designs and sequence of operation descriptions.

E. TAB Subcontractor:

1. Contract Documents Review: With the CxA, review the Contract Documents before developing TAB procedures.
 - a. Verify the following:
 - i. Accessibility of equipment and components required for TAB Work.
 - ii. Adequate number and placement of balancing valves to allow proper balancing and recording of water flow.
 - iii. Adequate number and placement of test ports and test instrumentation to allow reading and compilation of system and equipment performance data needed to conduct both TAB and commissioning testing.
 - b. Identify discontinuities and omissions in the Contract Documents.
 - c. This review of the Contract Documents by the TAB Subcontractor satisfies requirements for a design review report as specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."
 - d. Assist performing functional performance tests.
2. Additional Responsibilities: Participate in tests specified in Division 23 Sections "Instrumentation & Controls of HVAC & Plumbing Systems."

F. Electrical Contractor:

1. With the Mechanical Contractor, coordinate installations and connections between and among electrical and plumbing systems, subsystems, and equipment.

2. Attend TAB verification testing.

1.5. COMMISSIONING DOCUMENTATION

- A. The following are in addition to documentation specified in Division 01 Section "General Commissioning Requirements."
- B. Test Checklists: CxA with assistance of Contractor shall develop test checklists for plumbing systems, subsystems, and equipment, including interfaces and interlocks with other systems. CxA shall prepare separate checklists for each mode of operation and provide space to indicate whether the mode under test responded as required. In addition to the requirements specified in Division 01 Section "General Commissioning Requirements," checklists shall include, but not be limited to, the following:
 1. Calibration of sensors and sensor function.
 2. Testing conditions under which test was conducted, including (as applicable) ambient conditions, set points, override conditions, and status and operating conditions that impact the results of test.
 3. Control sequences for plumbing systems and equipment.
 4. Strength of control signal for each set point at specified conditions.
 5. Responses to control signals at specified conditions.
 6. Sequence of response(s) to control signals at specified conditions.
 7. Electrical demand or power input at specified conditions.
 8. Power quality and related measurements.
 9. Expected performance of systems, subsystems, and equipment at each step of test.
 10. Narrative description of observed performance of systems, subsystems, and equipment. Notation to indicate whether the observed performance at each step meets the expected results.
 11. Interaction of auxiliary equipment.
 12. Issues log.

1.6. SUBMITTALS

- A. The following submittals are in addition to those specified in Division 01 Section "General Commissioning Requirements."
- B. Testing Procedures: CxA shall submit detailed testing plan, procedures, and checklists for each series of tests. Submittals shall include samples of data reporting sheets that will be part of the reports.

- C. Certificate of Readiness: CxA shall compile certificates of readiness from Contractor certifying that systems, subsystems, equipment, and associated controls are ready for testing.
- D. Certificate of Completion of Installation, Prestart, and Startup: CxA shall certify that installation, prestart, and startup activities have been completed. Certification shall include completed checklists provided by TAB Subcontractor as specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."
- E. Certified Pipe Cleaning and Flushing Report: CxA shall certify that pipe cleaning, flushing, hydrostatic testing, and chemical treating have been completed.
- F. Test and Inspection Reports: CxA shall compile and submit test and inspection reports and certificates, and shall include them in systems manual and commissioning report.
- G. Corrective Action Documents: CxA shall submit corrective action documents.
- H. Certified TAB Reports: CxA shall submit verified, certified TAB reports.

1.7. ALTERNATES

- A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION

3.1. TESTING PREPARATION

- A. Prerequisites for Testing:
 - 1. Certify that plumbing systems, subsystems, and equipment have been completed, calibrated, and started; are operating according to the Contract Documents; and that Certificates of Readiness are signed and submitted.
 - 2. Certify that plumbing instrumentation and control systems have been completed and calibrated; are operating according to the Contract Documents; and that pretest set points have been recorded.
 - 3. Certify that plumbing procedures have been completed, and that TAB reports have been submitted, discrepancies corrected, and corrective work approved.
 - 4. Test systems and intersystem performance after approval of test checklists for systems, subsystems, and equipment.
 - 5. Set systems, subsystems, and equipment into operating mode to be tested (e.g., normal shut down, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).
 - 6. Verify each operating cycle after it has been running for a specified period and is operating in a steady-state condition.

7. Inspect and verify the position of each device and interlock identified on checklists. Sign off each item as acceptable, or failed. Repeat this test for each operating cycle that applies to system being tested.
 8. Annotate checklist or data sheet when a deficiency is observed.
 9. Verify equipment interface with monitoring and control system and TAB criteria; include the following:
 - a. Backflow preventer cross connection tests.
 - b. Make-up water motorized ball valves and control.
 - c. Chemical treatment bleed motorized ball valves.
 - d. Water meter flow rates and calibration.
 10. Verify proper responses of monitoring and control system controllers and sensors to include the following:
 - a. For each controller or sensor, record the indicated monitoring and control system reading and the test instrument reading. If initial test indicates that the test reading is outside of the control range of the installed device, check calibration of the installed device and adjust as required. Retest malfunctioning devices and record results on checklist or data sheet.
 - b. Report deficiencies and prepare an issues log entry.
 11. Verify that plumbing equipment field quality-control testing has been completed and approved. CxA shall direct, witness, and document field quality-control tests, inspections, and startup specified in individual Division 22 Sections.
 12. Verify the operation and flow rates of all plumbing fixtures.
- B. Testing Instrumentation: Install measuring instruments and logging devices to record test data for the required test period. Instrumentation shall monitor and record full range of operating conditions and shall allow for calculation of total capacity of system for each mode of operation. Operational modes include the following:
1. Occupied and unoccupied.
 2. Life-safety and safety systems.
 3. Temporary upset of system operation.
 4. Partial occupancy conditions.
 5. Special cycles.
 6. Alarm conditions.
 7. Lead/lag operation where redundant equipment is indicated.
 8. All alarms.

3.2. TAB VERIFICATION

- A. TAB Subcontractor shall coordinate with CxA for work required in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing." TAB Subcontractor shall copy CxA with required reports, sample forms, checklists, and certificates.
- B. Contractor, Plumbing Contractor, and CxA shall witness TAB Work.
- C. TAB Preparation:
 - 1. TAB Subcontractor shall provide CxA with data required for "Pre-Field TAB Engineering Reports" specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."
 - a. CxA shall use this data to certify that prestart and startup activities have been completed for systems, subsystems, and equipment installation.
- D. Verification of Final TAB Report:
 - 1. CxA shall select, at random, 10 percent of report for field verification.
 - 2. CxA shall notify TAB Subcontractor 10 days in advance of the date of field verification; however, notice shall not include data points to be verified. The TAB Subcontractor shall use the same instruments (by model and serial number) that were used when original data were collected.
 - 3. Failure of an item is defined as follows:
 - a. A deviation of more than 10 percent.
 - 4. Failure of more than 10 percent of selected items shall result in rejection of final TAB report.
- E. If deficiencies are identified during verification testing, CxA shall notify the HVAC Contractor and Engineer and shall take action to remedy the deficiency. Engineer shall review final tabulated checklists and data sheets to determine if verification is complete and that system is operating according to the Contract Documents.
- F. CxA shall certify that TAB Work has been successfully completed.

3.3. TESTING

- A. Test systems and intersystem performance after test checklists for systems, subsystems, and equipment have been approved.
- B. Perform tests using design conditions whenever possible.
 - 1. Simulate conditions by imposing an artificial load when it is not practical to test under design conditions and when written approval for simulated conditions is received from CxA. Before simulating conditions, calibrate testing instruments. Set and document simulated conditions and methods of simulation. After tests, return settings to normal operating conditions.
 - 2. Alter set points when simulating conditions is not practical and when written

approval is received from CxA.

3. Alter sensor values with a signal generator when design or simulating conditions and altering set points are not practical. Do not use sensor to act as signal generator to simulate conditions or override values.

C. Scope of Plumbing Contractor Testing:

1. Test all operating modes, interlocks, control responses, responses to abnormal or emergency conditions, and verify proper response of building automation system controllers and sensors.
2. Verify that all backflow preventers have been tested. Document in writing.
3. Test operation and interlock of all make-up water and bleed water motorized ball valves.
4. Test water meters and interlock with ATC system.
5. Test the operation of all motorized ball valves, including interlocks to water level controllers and water treatment system.

D. Detailed Testing Procedures: CxA, with Plumbing Contractor, TAB Subcontractor, and Plumbing Instrumentation and Control Contractor, shall prepare detailed testing plans, procedures, and checklists for plumbing systems, subsystems, and equipment.

E. HVAC Instrumentation and Control System Testing:

1. Field testing plans and testing requirements are specified in Division 23 Section "Instrumentation & Controls of HVAC & Plumbing Systems." The CxA, Plumbing Contractor, and the HVAC Instrumentation and Control Contractor shall collaborate to prepare testing plans.
2. CxA shall convene a meeting of appropriate entities to review test report of HVAC instrumentation and control systems.

F. Plumbing System Testing: Plumbing Contractor shall prepare a testing plan to verify performance of backflow preventers, domestic water meters, and motorized ball valves. Plan shall include the following:

1. Sequence of testing and testing procedures for each item of equipment and section of pipe to be tested, identified by identification marker. Markers shall be keyed to Drawings for each pipe sector showing the physical location of each item of equipment and pipe test section. Drawings shall be formatted to allow each item of equipment and section of piping to be physically located and identified when referred to in the system testing plan.
2. Tracking checklist for managing and ensuring that all pipe sections have been tested.
3. Design and actual measurements for all equipment.

G. Deferred Testing:

1. If tests cannot be completed because of a deficiency outside the scope of the plumbing system, the deficiency shall be documented and reported to Owner. Deficiencies shall be resolved and corrected by appropriate parties and test rescheduled.
2. If the testing plan indicates specific seasonal testing, appropriate initial performance tests shall be completed and documented and additional tests scheduled.

H. Testing Reports:

1. Reports shall include measured data, data sheets, and a comprehensive summary describing the operation of systems at the time of testing.
2. Include data sheets for each controller to verify proper operation of the control system, the system it serves, the service it provides, and its location. For each controller, provide space for recording its readout, the reading at the controller's sensor(s), plus comments. Provide space for testing personnel to sign off on each data sheet.
3. Prepare a preliminary test report. Deficiencies will be evaluated by Engineer to determine corrective action. Deficiencies shall be corrected and test repeated.

END OF SECTION

DIVISION 01 SECTION 01 91 15
HVAC COMMISSIONING REQUIREMENTS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SUMMARY	3
1.3. DEFINITIONS.....	4
1.4. CONTRACTOR'S RESPONSIBILITIES.....	4
1.5. COMMISSIONING DOCUMENTATION	5
1.6. SUBMITTALS	6
1.7. ALTERNATES.....	7
PART 2. PRODUCTS (NOT USED)	7
PART 3. EXECUTION.....	7
3.1. TESTING PREPARATION.....	7
3.2. TAB VERIFICATION.....	9
3.3. TESTING.....	10
END OF SECTION	12

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 91 15 - HVAC COMMISSIONING REQUIREMENTS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2. SUMMARY

- A. This Section includes requirements for commissioning the HVAC system and its subsystems and equipment. This Section supplements the general requirements specified in Division 01 Section "General Commissioning Requirements."
- B. Related Sections include the following:
 - 1. Division 01 Section "General Commissioning Requirements" for general requirements for commissioning processes that apply to this Section.
- C. The following systems and/or equipment shall be commissioned:
 - 1. Automatic Temperature Control System.
 - 2. Basin Heaters.
 - 3. Closed Circuit Evaporative Fluid Cooler Units and Fans.
 - 4. Cooling Tower Pumps.
 - 5. Chemical Water Treatment Control Panels/Pumps.
 - 6. Cooling Towers. (Including Strainers and Fans)
 - 7. Dampers
 - 8. Differential Pressure Bypass Valves.
 - 9. Electric Basin Heaters.
 - 10. Electric Heat Trace.
 - 11. Expansion Tanks.
 - 12. Existing Boiler.
 - 13. Flow Measuring Stations.
 - 14. Flow Switches.
 - 15. High and Low Temperature Alarms.

16. HVAC Controls And Sequences Of Operation.
17. Low Water Cut-Offs.
18. Makeup Water Meter Flow Rates And Alarms.
19. Pumps.
20. Pressure Independent Control Valves.
21. Refurbished Heat Exchanger (Selbyville).
22. Existing Heat Exchangers.
23. Makeup Water Meter/ATC Interface.
24. Variable Frequency Drives.
25. Water Meter/ATC Interface/Chemical Water Treatment Interfaces.

1.3. DEFINITIONS

- A. Architect: Includes Architect identified in the Contract for Construction between Owner and Contractor, plus consultant/design professionals responsible for design of HVAC, electrical, communications, controls for HVAC systems, and other related systems.
- B. CxA: Commissioning Authority.
- C. Systems, Subsystems, and Equipment: Where these terms are used together or separately, they shall mean "as-built" systems, subsystems, and equipment.
- D. TAB: Testing, Adjusting, and Balancing.

1.4. CONTRACTOR'S RESPONSIBILITIES

- A. The following responsibilities are in addition to those specified in Division 01 Section "General Commissioning Requirements."
- B. Contractor:
 1. Attend procedures meeting for TAB Work.
 2. Certify that TAB Work is complete.
 3. Assist performing functional performance tests.
- C. Mechanical Contractor:
 1. Attend TAB verification testing.
 2. Provide measuring instruments and logging devices to record test data, and data acquisition equipment to record data for the complete range of testing for the

required test period.

3. Assist performing functional performance tests.
- D. HVAC Instrumentation and Control Contractor: With the CxA, review control designs for compliance with the Contract Documents, controllability with respect to actual equipment to be installed, and recommend adjustments to control designs and sequence of operation descriptions. Assist with performing functional performance tests.
- E. TAB Subcontractor:
1. Contract Documents Review: With the CxA, review the Contract Documents before developing TAB procedures.
 - a. Verify the following:
 - i. Accessibility of equipment and components required for TAB Work.
 - ii. Adequate number and placement of duct balancing dampers to allow proper balancing while minimizing sound levels in occupied spaces.
 - iii. Adequate number and placement of balancing valves to allow proper balancing and recording of water flow.
 - iv. Adequate number and placement of test ports and test instrumentation to allow reading and compilation of system and equipment performance data needed to conduct both TAB and commissioning testing.
 - v. Air and water flow rates have been specified and compared to central equipment output capacities.
 - b. Identify discontinuities and omissions in the Contract Documents.
 - c. This review of the Contract Documents by the TAB Subcontractor satisfies requirements for a design review report as specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."
 - d. Assist performing functional performance tests.
 2. Additional Responsibilities: Participate in tests specified in Division 23 Sections "Instrumentation & Controls of HVAC & Plumbing Systems."
- F. Electrical Contractor:
1. With the Mechanical Contractor, coordinate installations and connections between and among electrical and HVAC systems, subsystems, and equipment.
 2. Attend TAB verification testing.

1.5. COMMISSIONING DOCUMENTATION

- A. The following are in addition to documentation specified in Division 01 Section "General Commissioning Requirements."
- B. Test Checklists: CxA with assistance of Contractor shall develop test checklists for HVAC systems, subsystems, and equipment, including interfaces and interlocks with other

systems. CxA shall prepare separate checklists for each mode of operation and provide space to indicate whether the mode under test responded as required. In addition to the requirements specified in Division 01 Section "General Commissioning Requirements," checklists shall include, but not be limited to, the following:

1. Calibration of sensors and sensor function.
2. Testing conditions under which test was conducted, including (as applicable) ambient conditions, set points, override conditions, and status and operating conditions that impact the results of test.
3. Control sequences for HVAC systems.
4. Strength of control signal for each set point at specified conditions.
5. Responses to control signals at specified conditions.
6. Sequence of response(s) to control signals at specified conditions.
7. Electrical demand or power input at specified conditions.
8. Power quality and related measurements.
9. Expected performance of systems, subsystems, and equipment at each step of test.
10. Narrative description of observed performance of systems, subsystems, and equipment. Notation to indicate whether the observed performance at each step meets the expected results.
11. Interaction of auxiliary equipment.
12. Issues log.

1.6. SUBMITTALS

- A. The following submittals are in addition to those specified in Division 01 Section "General Commissioning Requirements."
- B. Testing Procedures: CxA shall submit detailed testing plan, procedures, and checklists for each series of tests. Submittals shall include samples of data reporting sheets that will be part of the reports.
- C. Certificate of Readiness: CxA shall compile certificates of readiness from Contractor certifying that systems, subsystems, equipment, and associated controls are ready for testing.
- D. Certificate of Completion of Installation, Prestart, and Startup: CxA shall certify that installation, prestart, and startup activities have been completed. Certification shall include completed checklists provided by TAB Subcontractor as specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."
- E. Test and Inspection Reports: CxA shall compile and submit test and inspection reports and

certificates, and shall include them in systems manual and commissioning report.

F. Corrective Action Documents: CxA shall submit corrective action documents.

G. Certified TAB Reports: CxA shall submit verified, certified TAB reports.

1.7. ALTERNATES

A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

PART 2. PRODUCTS (NOT USED)

PART 3. EXECUTION

3.1. TESTING PREPARATION

A. Prerequisites for Testing:

1. Certify that HVAC systems, subsystems, and equipment have been completed, calibrated, and started; are operating according to the Contract Documents; and that Certificates of Readiness are signed and submitted.
2. Certify that HVAC instrumentation and control systems have been completed and calibrated; are operating according to the Contract Documents; and that pretest set points have been recorded.
3. Certify that TAB procedures have been completed, and that TAB reports have been submitted, discrepancies corrected, and corrective work approved.
4. Test systems and intersystem performance after approval of test checklists for systems, subsystems, and equipment.
5. Set systems, subsystems, and equipment into operating mode to be tested (e.g., normal shut down, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).
6. Verify each operating cycle after it has been running for a specified period and is operating in a steady-state condition.
7. Inspect and verify the position of each device and interlock identified on checklists. Sign off each item as acceptable, or failed. Repeat this test for each operating cycle that applies to system being tested.
8. Check safety cutouts, alarms, and interlocks with and life-safety systems during each mode of operation.
9. Annotate checklist or data sheet when a deficiency is observed.
10. Verify equipment interface with monitoring and control system and TAB criteria; include the following:

- a. All pump status alarms, pump operation, flow rates, and controls.
 - b. All temperature alarms.
 - c. Cooling Tower/closed circuit evaporative fluid cooler flow rates, pressures, temperatures, set points, and safeties.
 - d. Test all minimum flow bypass valves and controls.
 - e. Differential bypass valves and transmitters.
 - f. Electric basin heating equipment and heat tracing volts, amps, temperature and temperature rise.
 - g. Existing boiler flow rates, temperatures, and pressure drops.
 - h. Fluid flow rates and temperature for all equipment.
 - i. Existing heat exchanger flow rates and temperature pressures.
 - j. Existing indirect fluid storage tank flow rates, temperatures, and pressures.
 - k. Operation/Accuracy of fluid flow measuring stations at various flow rates.
 - l. Pump flow rates, pressure and amperage at each operating mode.
 - m. Sequences of operation of all HVAC equipment.
 - n. Set point and operation of "high temperature" alarms.
 - o. Test all flow switches including operation and alarms.
 - p. Variable speed drive parameters at each operated mode.
 - q. Chemical water treatment interlocks, controls and operation.
 11. Verify proper responses of monitoring and control system controllers and sensors to include the following:
 - a. For each controller or sensor, record the indicated monitoring and control system reading and the test instrument reading. If initial test indicates that the test reading is outside of the control range of the installed device, check calibration of the installed device and adjust as required. Retest malfunctioning devices and record results on checklist or data sheet.
 - b. Report deficiencies and prepare an issues log entry.
 12. Verify that HVAC equipment field quality-control testing has been completed and approved. CxA shall direct, witness, and document field quality-control tests, inspections, and startup specified in individual Division 23 Sections.
- B. Testing Instrumentation: Install measuring instruments and logging devices to record test data for the required test period. Instrumentation shall monitor and record full range of operating conditions and shall allow for calculation of total capacity of system for each mode of operation. Operational modes include the following:
1. Heating/Cooling Mode.
 2. Occupied and unoccupied.
 3. Warm up and cool down.
 4. Fluid flow rates and temperatures for all water cooled equipment.
 5. Life-safety and safety systems.
 6. Fire safety.

7. Temporary upset of system operation.
8. Partial occupancy conditions.
9. Special cycles.
10. Test all cooling towers/closed circuit evaporative fluid cooler modes of operation.
11. Lead/standby modes of operation where redundant equipment is indicated.
12. All alarms.
13. Flow switch shut-down and alarm.
14. Existing boilers and heat exchangers operation, setpoint, flow rates and safeties.
15. Test operation and accuracy of fluid flow measuring stations.
16. Test all flow switches and differential pressure sensors.

3.2. TAB VERIFICATION

- A. TAB Subcontractor shall coordinate with CxA for work required in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing." TAB Subcontractor shall copy CxA with required reports, sample forms, checklists, and certificates.
- B. Contractor, HVAC Contractor, and CxA shall witness TAB Work.
- C. TAB Preparation:
 1. TAB Subcontractor shall provide CxA with data required for "Pre-Field TAB Engineering Reports" specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."
 - a. CxA shall use this data to certify that prestart and startup activities have been completed for systems, subsystems, and equipment installation.
- D. Verification of Final TAB Report:
 1. CxA shall select, at random, 10 percent of report for field verification.
 2. CxA shall notify TAB Subcontractor 10 days in advance of the date of field verification; however, notice shall not include data points to be verified. The TAB Subcontractor shall use the same instruments (by model and serial number) that were used when original data were collected.
 3. Failure of an item is defined as follows:
 - a. For all readings a deviation of more than 10 percent.
 4. Failure of more than 10 percent of selected items shall result in rejection of final TAB report.

- E. If deficiencies are identified during verification testing, CxA shall notify the HVAC Contractor and Engineer, and shall take action to remedy the deficiency. Architect shall review final tabulated checklists and data sheets to determine if verification is complete and that system is operating according to the Contract Documents.
- F. CxA shall certify that TAB Work has been successfully completed.

3.3. TESTING

- A. Test systems and intersystem performance after test checklists for systems, subsystems, and equipment have been approved.
- B. Contractors and subcontractors must pre-inspect and pre-test all equipment and systems prior to requesting functional performance testing by the CxA. All pre-start/start-up checklists and functional performance test forms must be completed and submitted to Engineer prior to scheduling formal functional performance testing.
- C. Perform tests using design conditions whenever possible.
 - 1. Simulate conditions by imposing an artificial load when it is not practical to test under design conditions and when written approval for simulated conditions is received from CxA. Before simulating conditions, calibrate testing instruments. Set and document simulated conditions and methods of simulation. After tests, return settings to normal operating conditions.
 - 2. Alter set points when simulating conditions is not practical and when written approval is received from CxA.
 - 3. Alter sensor values with a signal generator when design or simulating conditions and altering set points are not practical. Do not use sensor to act as signal generator to simulate conditions or override values.
- D. Scope of HVAC Contractor Testing:
 - 1. Testing scope shall include entire HVAC installation, from central equipment for heat generation and refrigeration through distribution systems to each conditioned space. It shall include measuring capacities and effectiveness of operational and control functions.
 - 2. Test all operating modes, interlocks, control responses, responses to abnormal or emergency conditions, and verify proper response of building automation system controllers and sensors.
- E. Detailed Testing Procedures: CxA, with HVAC Contractor, TAB Subcontractor, and HVAC Instrumentation and Control Contractor, shall prepare detailed testing plans, procedures, and checklists for HVAC systems, subsystems, and equipment.
- F. HVAC Instrumentation and Control System Testing:
 - 1. Field testing plans and testing requirements are specified in Division 23 Section "Instrumentation & Controls of HVAC & Plumbing Systems". The CxA, HVAC

- Contractor, Equipment Provider/Manufacturer and the HVAC Instrumentation and Control Contractor shall collaborate to prepare testing plans.
2. CxA shall convene a meeting of appropriate entities to review test report of HVAC instrumentation and control systems.
- G. Heat-Generation System Testing: HVAC Contractor shall prepare a testing plan to verify performance of heat exchangers, existing boilers, and existing indirect fluid storage tanks. Plan shall include the following:
1. Sequence of testing and testing procedures for each item of equipment and section of pipe to be tested, identified by identification marker. Markers shall be keyed to Drawings for each pipe sector showing the physical location of each item of equipment and pipe test section. Drawings shall be formatted to allow each item of equipment and section of piping to be physically located and identified when referred to in the system testing plan.
 2. Tracking checklist for managing and ensuring that all pipe sections have been tested.
- H. Refrigeration Heat Rejection System Testing: HVAC Contractor shall prepare a testing plan to verify performance of existing heat exchangers, closed circuit evaporative fluid cooler units, and cooling towers. Plan shall include the following:
1. Sequence of testing and testing procedures for each item of equipment and section of pipe to be tested, identified by identification marker. Markers shall be keyed to Drawings showing the physical location of each item of equipment and pipe test section. Drawings shall be formatted to allow each item of equipment and section of piping to be physically located and identified when referred to in the system testing plan.
 2. Tracking checklist for managing and ensuring that all pipe sections have been tested.
- I. HVAC Distribution System Testing: HVAC Contractor shall prepare a testing plan to verify performance of air and hydronic distribution systems, closed circuit evaporative fluid coolers and cooling towers and other distribution systems. Include HVAC terminal equipment and unitary equipment. Plan shall include the following:
1. Sequence of testing and testing procedures for each item of equipment and section of pipe to be tested, identified by identification marker. Markers shall be keyed to Drawings showing the physical location of each item of equipment and pipe test section. Drawings shall be formatted to allow each item of equipment and section of piping to be physically located and identified when referred to in the system testing plan.
 2. Tracking checklist for managing and ensuring that all pipe sections have been tested.
 3. Equipment, air flow rates, air temperatures, fluid flow rates, and safeties.

J. Deferred Testing:

1. If tests cannot be completed because of a deficiency outside the scope of the HVAC system, the deficiency shall be documented and reported to Owner. Deficiencies shall be resolved and corrected by appropriate parties and test rescheduled.
2. If the testing plan indicates specific seasonal testing, appropriate initial performance tests shall be completed and documented and additional tests scheduled.

K. Testing Reports:

1. Reports shall include measured data, data sheets, and a comprehensive summary describing the operation of systems at the time of testing.
2. Include data sheets for each controller to verify proper operation of the control system, the system it serves, the service it provides, and its location. For each controller, provide space for recording its readout, the reading at the controller's sensor(s), plus comments. Provide space for testing personnel to sign off on each data sheet.
3. Prepare a preliminary test report. Deficiencies will be evaluated by Engineer to determine corrective action. Deficiencies shall be corrected and test repeated.

END OF SECTION

SECTION 02 41 19
SELECTIVE DEMOLITION
TABLE OF CONTENTS

PART 1 GENERAL

- 1.1 RELATED DOCUMENTS
- 1.2 SUMMARY
- 1.3 DEFINITIONS
- 1.4 MATERIALS OWNERSHIP
- 1.5 SUBMITTALS
- 1.6 QUALITY ASSURANCE
- 1.7 PROJECT CONDITIONS
- 1.8 WARRANTY

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION

- 3.1 EXAMINATION
- 3.2 UTILITY SERVICE AND MECHANICAL/ELECTRICAL SYSTEMS
- 3.3 PREPARATION
- 3.4 SELECTIVE DEMOLITION, GENERAL
- 3.5 DISPOSAL OF DEMOLISHED MATERIALS
- 3.6 CLEANING

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 02 41 19
SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Demolition and removal of selected portions of building or structure.
 - 2. Demolition and removal of selected site elements.
 - 3. Salvage of existing items to be reused or recycled.
- B. Related Sections include the following:
 - 1. Division 01 Section 01 11 00 "Summary of Work" for use of premises and Owner-occupancy requirements.
 - 2. Division 01 Section 01 50 00 "Temporary Facilities and Controls" for temporary construction and environmental-protection measures for selective demolition operations.
 - 3. Division 01 Section 01 73 29 "Cutting and Patching" for cutting and patching procedures.

1.3 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site, unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Detach items from existing construction and deliver them to Owner.
- C. Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and re-install them where indicated.
- D. Existing to Remain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.4 MATERIALS OWNERSHIP

- A. Items of interest or value to Owner that may be encountered during selective demolition remain Owner's property. Carefully remove each item or object in a manner to prevent damage and deliver promptly to Owner.

1.5 SUBMITTALS

- A. Schedule of Selective Demolition Activities: Indicate the following:
1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's building manager's on-site operations are uninterrupted.
 2. Interruption of utility services. Indicate how long utility services will be interrupted.
 3. Coordination for shutoff, capping, and continuation of utility services.
 4. Use of elevator and stairs.
 5. Locations of proposed dust- and noise-control temporary partitions and means of egress.
 6. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.
 7. Means of protection for items to remain and items in path of waste removal from building.
- B. Inventory: After selective demolition is complete, submit a list of items that have been removed and salvaged.
- C. Predemolition Videotapes: Show existing conditions of adjoining construction, including finish surfaces that might be misconstrued as damage caused by selective demolition operations.
- D. Landfill Records: Indicate receipt and acceptance of hazardous wastes by a landfill facility licensed to accept hazardous wastes.

1.6 QUALITY ASSURANCE

- A. Demolition Firm Qualifications: An experienced firm that has specialized in demolition work similar in material and extent to that indicated for this Project.
- B. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- C. Standards: Comply with ANSI A10.6 and NFPA 241.
- D. Predemolition Conference: Conduct conference at Project site to comply with requirements in Division 01 Section 01 31 00 "Project Management and Coordination." Review methods and procedures related to selective demolition including, but not limited to, the following:
1. Inspect and discuss condition of construction to be selectively demolished.
 2. Review structural load limitations of existing structure.
 3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
 4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
 5. Review areas where existing construction is to remain and requires protection.

1.7 PROJECT CONDITIONS

- A. Owner will occupy portions of building and site immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.
 - 1. Comply with requirements specified in Division 01 Section 01 11 00 "Summary of Work."
- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- C. Notify Engineer of discrepancies between existing conditions and Drawings before proceeding with selective demolition. Video tape all existing areas prior to selective demolition work.
- D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
 - 1. Hazardous materials will be removed by Owner before start of the Work.
 - 2. If materials suspected of containing hazardous materials are encountered, do not disturb; immediately notify Engineer and Owner. Owner will remove hazardous materials under a separate contract.
- E. Hazardous Materials: Hazardous materials are present in construction to be selectively demolished. A report on the presence of hazardous materials is on file for review and use. Examine report to become aware of locations where hazardous materials are present.
 - 1. Hazardous material remediation is specified elsewhere in the Contract Documents.
 - 2. Do not disturb hazardous materials or items suspected of containing hazardous materials except under procedures specified elsewhere in the Contract Documents.
- F. Storage or sale of removed items or materials on-site is not permitted.
- G. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
 - 1. Maintain existing site fire-protection facilities in service during selective demolition operations.
- H. Create a video recording of all existing conditions where work will occur at each school prior to the start of demolition.
- I. Where indicated, pre-test fluid flow rates utilizing an ultrasonic flow meter prior to the start of demolition work.

1.8 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged.
- D. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Engineer.
- E. Engage a professional engineer to survey condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective demolition operations.
- F. Survey of Existing Conditions: Record existing conditions by use of measured drawings and preconstruction digital videotapes.
 - 1. Before selective demolition or removal of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems: Maintain services/systems indicated to remain and protect them against damage during selective demolition operations.
 - 1. Comply with requirements for existing services/systems interruptions specified in Division 01 Section 01 11 00 "Summary of Work."
- B. Service/System Requirements: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.
 - 1. Owner will arrange to shut off indicated services/systems when requested by Contractor.
 - 2. Arrange to shut off indicated utilities with utility companies.
 - 3. If services/systems are required to be removed, relocated, or abandoned, before proceeding with selective demolition provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
 - 4. Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit after bypassing.
 - a. Where entire wall is to be removed, existing services/systems may be removed with removal of the wall.

3.3 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Comply with requirements for access and protection specified in Division 01 Section 01 50 00 "Temporary Facilities and Controls."
- B. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
 - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
 - 2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
 - 3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
 - 4. Cover and protect furniture, furnishings, and equipment that have not been removed.
 - 5. Comply with requirements for temporary enclosures, dust control, heating, and cooling specified in Division 01 Section 01 50 00 "Temporary Facilities and Controls."
- C. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
 - 1. Strengthen or add new supports when required during progress of selective demolition.

3.4 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
 - 1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
 - 2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
 - 3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 - 4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain fire watch and portable fire-suppression devices during flame-cutting operations.

5. Maintain adequate ventilation when using cutting torches.
6. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
7. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
8. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
9. Dispose of demolished items and materials promptly.

B. Removed and Salvaged Items:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Store items in a secure area until delivery to Owner.
4. Transport items to Owner's storage area on-campus.
5. Protect items from damage during transport and storage.

C. Removed and Reinstalled Items:

1. Clean and repair items to functional condition adequate for intended reuse. Paint equipment to match new equipment.
2. Pack or crate items after cleaning and repairing. Identify contents of containers.
3. Protect items from damage during transport and storage.
4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

D. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Engineer, items may be removed to a suitable, protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete.

E. Air-Conditioning Equipment: Remove equipment without releasing refrigerants.

3.5 DISPOSAL OF DEMOLISHED MATERIALS

A. General: Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Project site and legally dispose of them in an EPA-approved landfill.

1. Do not allow demolished materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.

B. Burning: Do not burn demolished materials.

C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

3.6 CLEANING

- A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 07 SECTION 07 84 13
HVAC & PLUMBING PENETRATION FIRESTOPPING
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. SUMMARY	3
1.2. REFERENCES	3
1.3. DEFINITIONS	3
1.4. SYSTEM DESCRIPTION	3
1.5. SUBMITTALS	4
1.6. QUALITY ASSURANCE	4
1.7. DELIVERY, STORAGE, AND HANDLING	5
1.8. PROJECT CONDITIONS	5
1.9. WARRANTY	5
PART 2. PRODUCTS	5
2.1. THROUGH-PENETRATION FIRESTOPPING OF FIRE-RATED CONSTRUCTION	5
2.2. SMOKE-STOPPING AT SMOKE PARTITIONS	6
2.3. ACCESSORIES	6
PART 3. EXECUTION	6
3.1. EXAMINATION	6
3.2. PREPARATION	6
3.3. INSTALLATION	7
3.4. FIELD QUALITY CONTROL	7
3.5. ADJUSTING AND CLEANING	7
3.6. SYSTEMS AND APPLICATION SCHEDULES*	7
END OF SECTION	9

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 07 84 13 - HVAC & PLUMBING PENETRATION FIRESTOPPING

PART 1. GENERAL

1.1. SUMMARY

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Section includes:
 - 1. Through-penetration firestopping in fire rated construction.
 - 2. Through-penetration smoke-stopping in smoke partitions.

1.2. REFERENCES

- A. Underwriters Laboratories
 - 1. UL Fire Resistance Directory
 - a. Through-penetration firestop devices (XHCR)
 - b. Fire resistance rating (BXUV)
 - c. Through-penetration firestop systems (XHEZ)
 - d. Fill, void, or cavity material (XHHW)
- B. American Society for Testing and Materials Standards:
- C. ASTM E 814-88: Standard Test Method for Fire Tests of Through-Penetration Firestops.

1.3. DEFINITIONS

- A. Assembly: Particular arrangement of materials specific to given type of construction described or detailed in referenced documents.
- B. Barriers: Time-rated fire walls, smoke barrier walls, time-rated ceiling/floor assemblies and structural floors.
- C. Firestopping: Methods and materials applied in penetrations and unprotected openings to limit spread of heat, fire, gasses and smoke.
- D. Penetration: Opening or foreign material passing through or into barrier or structural floor such that full thickness of rated materials is not obtained.
- E. System: Specific products and applications, classified and numbered by Underwriters Laboratories, Inc. to close specific barrier penetrations.
- F. Sleeve: Metal fabrication or pipe section extended through thickness of barrier and used to permanently guard penetration. Sleeves are described as part of penetrating system in other sections and may or may not be required.

1.4. SYSTEM DESCRIPTION

A. Design Requirements

1. Fire-rated construction: Maintain barrier and structural floor fire resistance ratings including resistance to cold smoke at all penetrations.
2. Smoke barrier construction: Maintain barrier and structural floor resistance to cold smoke at all penetrations.

1.5. SUBMITTALS

- A. Submit in accordance with Division 01 Section Submittal Procedures, unless otherwise indicated.
- B. Product data: Manufacturer's specifications and technical data including the following:
1. Detailed specification of construction and fabrication.
 2. Manufacturer's installation instructions.
- C. Shop drawings: Indicate dimensions, description of materials and finishes, general construction, specific modifications, component connections, anchorage methods, hardware, and installation procedures, plus the following specific requirements.
1. Details of each proposed assembly identifying intended products and applicable UL system number, or UL classified devices.
 2. Manufacturer or manufacturer's representative shall provide qualified engineering judgment and drawings relating to non-standard applications as needed.
- D. Quality control submittals:
1. Statement of qualifications.
- E. Applicators' qualifications statement:
1. List past projects indicating required experience.

1.6. QUALITY ASSURANCE

- A. Installer's qualifications: Fire experienced in installation or application of systems similar in complexity to those required for this project, plus the following:
1. Acceptable to or licensed by manufacturer, State or local authority where applicable.
 2. At least 2 years experience with systems.
 3. Successfully completed at least 5 comparable scale projects using this system.
- B. Local and State regulatory requirements: Submit forms or acceptance for proposed assemblies not conforming to specific UL Firestop System numbers, or UL classified devices.

- C. Materials shall have been tested to provide fire rating at least equal to that of the construction.

1.7. DELIVERY, STORAGE, AND HANDLING

- A. Packing and shipping:
 - 1. Deliver products in original unopened packaging with legible manufacturer's identification.
 - 2. Coordinate delivery with scheduled installation date, allow minimum storage at site.
- B. Storage and protection: Store materials in a clean, dry, ventilated location. Protect from soiling, abuse, moisture and freezing when required. Follow manufacturer's instructions.

1.8. PROJECT CONDITIONS

- A. Existing condition:
 - 1. Verify existing conditions and substrates before starting work. Correct unsatisfactory conditions before proceeding.
 - 2. Proceed with installation only after penetrations of the substrate and supporting brackets have been installed.
- B. Environmental requirements:
 - 1. Furnish adequate ventilation if using solvent.
 - 2. Furnish forced air ventilation during installation if required by manufacturer.
 - 3. Keep flammable materials away from sparks or flame.
 - 4. Provide masking and drop cloths to prevent contamination of adjacent surfaces by firestopping materials.

1.9. WARRANTY

- A. Submit copies of written warranty agreeing to repair or replace joint sealers which fail in joint adhesion, extrusion resistance, migration resistance, or general durability or appear to deteriorate in any other manner not clearly specified by submitted manufacturer's data as an inherent quality of the material for the exposure indicated. The warranty period shall be two (2) years from date of substantial completion unless otherwise noted.

PART 2. PRODUCTS

2.1. THROUGH-PENETRATION FIRESTOPPING OF FIRE-RATED CONSTRUCTION

- A. Systems of devices listed in the UL Fire Resistance Directory under categories XHCR and XHEZ may be used, providing that it conforms to the construction type, penetrant type, annular space requirements and fire rating involved in each separate instance, and that the

system be symmetrical for wall applications. Systems or devices must be asbestos-free.

1. Additional requirements: Withstand the passage of cold smoke either as an inherent property of the system, or by the use of a separate product included as a part of the UL system or device, and designed to perform this function.
2. Acceptable manufacturers and products.
 - a. Those listed in the UL Fire Resistance directory for the UL System involved and as further defined in the System and Applications Schedule in Part 3.6 of this section.
3. All firestopping products must be from a single manufacturer. All trades shall use products from the same manufacturer unless otherwise noted.

2.2. SMOKE-STOPPING AT SMOKE PARTITIONS

- A. Through-penetration smoke-stopping: Any system complying with the requirements for through-penetration firestopping in fire-rated construction, as specified in The Systems and Applications Schedule in Part 3.6 of this section, is acceptable, provided that the system includes the specified smoke seal or will provide a smoke seal. The length of time of the fire resistance may be disregarded.

2.3. ACCESSORIES

- A. Fill, void or cavity materials: As classified under category XHHW in the UL Fire Resistance Directory.
- B. Forming materials: As classified under category XHKU in the UL Fire Resistance Directory.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
 1. Verify barrier penetrations are properly sized and in suitable condition for application of materials.
 2. Do not proceed until unsatisfactory conditions have been corrected.
- B. Coordinate an inspection of all Mechanical Firestopping systems with the Fire Marshal prior to installation of ceilings, walls, etc.

3.2. PREPARATION

- A. Clean surfaces to be in contact with penetration seal materials of dirt, grease, oil, loose materials, rust, or other substances that may affect proper fitting, adhesion, or the required fire resistance.

3.3. INSTALLATION

- A. Install penetration seal materials in accordance with printed instructions of the UL Fire Resistance Directory and in accordance with manufacturer's instruction.
- B. Seal holes or voids made by penetrations to ensure an effective smoke barrier.
- C. Protect materials from damage on surfaces subject to traffic.
- D. When large openings are created in walls or floors to permit installation of pipes, ducts, or other items, close unused portions of opening with firestopping materials tested for the application. See UL Fire Resistance Directory or Section 3.6 of this document.
 - 1. Install smoke stopping as specified for firestopping.

3.4. FIELD QUALITY CONTROL

- A. Examine penetration sealed areas to ensure proper installation before concealing or enclosing areas.
- B. Keep areas of work accessible until inspection by applicable code authorities.
- C. Perform under this section patching and repairing of firestopping caused by cutting or penetration by other trades.

3.5. ADJUSTING AND CLEANING

- A. Clean up spills of liquid components.
- B. Neatly cut and trim materials as required.
- C. Remove equipment, materials and debris, leaving area in undamaged, clean condition.

3.6. SYSTEMS AND APPLICATION SCHEDULES*

HEAT OF REJECTION EQUIPMENT REPLACEMENT
(IRD25036-HVAC)

INDIAN RIVER SCHOOL DISTRICT
CARVER EC & SELBYVILLE MS

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/CEILING
Metal Pipe	CAJ1001 CP25S/L, CP25N/S CAJ1006 CS-195+, FS-195+ CAJ1007 FS-195+, 1-inch& 2-inch Wide CAJ1009 2000, 2000+, 2003 CAJ1010 2000, 2000+, 2003 CAJ1012 2000, 2000+, 2003 CAJ1013 2000, 2000+, 2003 CAJ1014 2000, 2000+, 2003 CAJ1015 2000, 2000+, 2003 CAJ1017 FD 150 CAJ1021 FD 150 CAJ1027 MPS-2+ CAJ1044 CP 25WB+ CAJ1052 CP 25S/L, CP 25N/S CAJ1058 2000, 2000+, 2003 CAJ1060 2000, 2000+, 2003 CAJ1063 2000, 2000+, 2003 CAJ1066 CP 25N/S, CP 25S/L, CP 25WB+ CAJ1091 CP 25N/S, CP 25S/L, CP 25WB+ CAJ1092 CP 25WB+ CAJ1112 FS-195+ CAJ1160 CP 25S/L, CP 25N/S CAJ1175 CP 25WB+ CAJ1176 CP 25WB+ CAJ1188 2000+ CBJ1020 CS-195+, FS-195+ CBJ1021 CS-195+, MPS-2+ CBJ1031 2001 CBJ1032 2001 FA1002 CP 25WB+ WJ1010 CP25WB+ WJ1023 2001	WL1001 CP 25 WL1002 FS-195+ WL1003 CP 25WB+, CP 25N/S WL1008 2000+ WL1009 2000+ WL1010 2000+ WL1016 CP 25WB+ WL1017 CP 25WB+, CP 25N/S WL1032 CP 25WB+, CP 25N/S WL1036 FD 150 WL1037 CS-195+, FS-195+ WL1067 CP 25N/S WL1073 CP 25WB+ WL1080 MPS2+ WL1082 2000+	FC1002 CP 25 FC1003 2000, 2000+, 20003 FC1006 CP 25WB+
Non-Metallic	CAJ2001 FS-195+, 1-inch& 2-inch WIDE, PPD'S CAJ2002 FS-195+ CAJ2003 CS-195+, FS-195+ CAJ2005 FS-195 CAJ2006 FS-195+ CAJ2013 FS-195+ CAJ2019 2000, 2000+, 2003 CAJ2027 FS-195+, CP 25N/S, CP 25S/L, CP 25WB+ CAJ2028 FS-195, MPS-2+ CAJ2029 FS-195+, PPD'S CAJ2030 CS-195+, FS-195+ CAJ2040 FS-195+, CP 25WB+ CAJ2044 FS-195+, CP 25N/S, CP 25S/L CP 25 WB+ CAJ2090 FS-195+ CAJ2177 FS-195+, PPD'S FA2001 FS-195+, PPD'S FS2002 CS-195+, FS-195+, MPS-2+, PPD'S FA2011 FS-195+ WJ2012 FS-195+ 1-inch WIDE	WL2002 FS-195+, PPD'S WL2003 FS-195+ WL2004 FS-195+ WL2005 FS-195+ 4' WIDE WL2006 FS-195+ WL2013 FS-195+ WL2031 CS-195+, FS-195+ WL2032 CS-195+, FS-195+ WL2033 FS-195+ WL2073 FS-195+ 1-inch WIDE	FC2002 FS-195+, PPD'S FC2007 FS-195+, PPD'S FC2008 FS-195+ FC2009 FS-195+, PPD'S FC2024 FS-195 FC2026 FS-195+ FC2028 FS-195, 1' & 2-inch WIDE, PPD'S

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/CEILING
Insulated Metallic Pipe	CAJ5001 CP 25N/S, CP 25S/L, CP 25WB+ CAJ5002 FS-195+ CAJ5003 FS-195+ CAJ5005 MPS-2+ CAJ5009 2000+, 2003 CAJ5017 FS-195+, CP 25 CAJ5022 FS-195+ CAJ5024 FS-195+ CAJ5030 CS-195+, FS-195+ CAJ5041 2000, 2000+, 2003 CAJ5060 CP 25WB+ CAJ5074 2000+ CBJ5002 CP 25 CBJ5003 FS-195+ FA5001 FS-195+, CP 25WB+	WL5001 FS-195+ WL5002 FS-195+ WL5009 FS-195+ WL5010 FS-195+ WL5011 CP 25WB+ WL5032 2000+ WL5038 CP 25WB+ WL5039 CP 25WB+ WL5040 CP 25WB+ WL5045 CP 25WB+ WL5053 2000+	FC5002 FS-195+ FC5008 FS-195+
Miscellaneous Mechanical HVAC Ducts	CAJ7001 CP 25N/S CP 25S/L CAJ7003 CP 25WB+ CAJ7009 DUCT WRAP, BULK PUTTY		FC7001 CP 25S/L, CP 25N/S
Mixed Penetrating Items Combos	CAJ8001 CS-195+ FS-195 CAJ8003 2000, 2000+, 20003 CAJ8004 2000, 2000+, 20003 CAJ8006 2001 CAJ8013 FS-195+, CP 25 CBJ8004 CS-195, FS-195+ CBJ8005 CS-195+, MPS-2+ CBJ8008 2001 FA8001 FS-195+, CP 25WB+	WL8002 CS-195+, FS-195+	

*Underwriter's Laboratories, Inc., Fire Resistance Directory.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 22 SECTION 22 05 00
COMMON WORK RESULTS FOR PLUMBING
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. SUMMARY	3
1.2. PERMITS AND FEES	3
1.3. EXAMINATION OF SITE	3
1.4. CONTRACTOR QUALIFICATION	4
1.5. MATERIALS AND EQUIPMENT	4
1.6. FIRE SAFE MATERIALS	5
1.7. REFERENCED STANDARDS, CODES AND SPECIFICATIONS	5
1.8. SUBMITTALS, REVIEW AND ACCEPTANCE	5
1.9. SHOP DRAWINGS	6
1.10. SUPERVISION AND COORDINATION	8
1.11. CUTTING AND PATCHING	9
1.12. PENETRATION OF WATERPROOF CONSTRUCTION	9
1.13. CONCRETE AND MASONRY WORK	9
1.14. CONNECTIONS AND ALTERATIONS TO EXISTING WORK	9
1.15. DEMOLITION	10
1.16. VIBRATION ISOLATION	11
1.17. ALTERNATES	11
1.18. DEFINITIONS	11
1.19. MINIMUM EFFICIENCY REQUIREMENTS	12
1.20. SYSTEM INTEGRATION	12
1.21. LEAD FREE REQUIREMENTS	13
1.22. COORDINATION WITH INDIAN RIVER SCHOOL DISTRICT I.T. DEPARTMENT	13
1.23. EXTRA MATERIALS	13
PART 2. ELECTRICAL REQUIREMENTS	13
2.1. GENERAL MOTOR AND ELECTRICAL REQUIREMENTS	13
2.2. MOTORS AND CONTROLS	14
2.3. MOTOR INSTALLATION	17
2.4. WIRING DIAGRAMS	17
2.5. ENCLOSURES	17
PART 3. EXECUTION	17
3.1. EQUIPMENT INSTALLATION - COMMON REQUIREMENTS	17
3.2. SUPPORTS, HANGERS AND FOUNDATIONS	18
3.3. DEMONSTRATION AND TRAINING VIDEO RECORDINGS	18
3.4. PROVISIONS FOR ACCESS	18
3.5. PAINTING AND FINISHES	19
3.6. CLEANING OF SYSTEMS	20
3.7. COLOR SELECTION	20
3.8. PROTECTION OF WORK	20
3.9. OPERATION OF EQUIPMENT	21
3.10. IDENTIFICATIONS, FLOW DIAGRAMS, ELECTRICAL DIAGRAMS AND OPERATING INSTRUCTIONS	21
3.11. WALL AND FLOOR PENETRATION	22
3.12. RECORD DRAWINGS	22

3.13. WARRANTY	23
3.14. OPERATIONS AND MAINTENANCE MANUALS.....	23
3.15. INSTALLATION AND COORDINATION DRAWINGS	25
3.16. PIPING SYSTEMS TESTING	25
3.17. WINTERIZATION OF ALL WATER CONTAINING PIPING SYSTEMS	25
END OF SECTION	26

SECTION 22 05 00 - COMMON WORK RESULTS FOR PLUMBING

PART 1. GENERAL

1.1. SUMMARY

- A. All work under Division 22 is subject to the Division 01, General Requirements, the General Conditions and Supplementary Conditions.
- B. Provide all labor, materials, equipment, and services necessary for and incidental to the complete installation and operation of all plumbing work.
- C. Unless otherwise specified, all submissions shall be made to, and acceptances and approvals made by the Engineer.
- D. Contract Drawings are generally diagrammatic and all offsets, fittings, transitions and accessories are not necessarily shown. Furnish and install all such items as may be required to fit the work to the conditions encountered. Arrange piping, equipment, and other work generally as shown on the contract drawings, providing proper clearance and access. Where departures are proposed because of field conditions or other causes, prepare and submit detailed shop drawings for approval in accordance with Submittals specified below. The right is reserved to make reasonable changes in location of equipment, piping, up to the time of rough-in or fabrication.
- E. Conform to the requirements of all rules, regulations and codes of local, state and federal authorities having jurisdiction.
- F. Coordinate the work under Division 22 with the work of all other construction trades.
- G. Be responsible for all construction means, methods, techniques, procedures, and phasing sequences used in the work. Furnish all tools, equipment and materials necessary to properly perform the work in first class, substantial, and workmanlike manner, in accordance with the full intent and meaning of the contract documents.

1.2. PERMITS AND FEES

- A. Obtain all permits and pay taxes, fees and other costs in connection with the work. File necessary plans, prepare documents, give proper notices and obtain necessary approvals. Deliver inspection and approval certificates to Owner prior to final acceptance of the work.
- B. Permits and fees shall comply with the Division 01, General Requirements of the specification.

1.3. EXAMINATION OF SITE

- A. Examine the site, determine all conditions and circumstances under which the work must be done, and make all necessary allowances for same. No additional cost to the Owner will be permitted for contractor's failure to do so.
- B. Examine and verify specific conditions described in individual specifications sections.
- C. Verify that utility services are available, of the correct characteristics, and in the correct

locations.

1.4. CONTRACTOR QUALIFICATION

- A. Any Contractor or Subcontractor performing work under Division 22 shall be fully qualified and acceptable to the Engineer and Owner. Submit the following evidence when requested:
 - 1. A list of not less than five comparable projects which the Contractor completed.
 - 2. Letter of reference from not less than three registered professional engineers, general contractors or building owners.
 - 3. Local and/or State License, where required.
 - 4. Membership in trade or professional organizations where required.
- B. A Contractor is any individual, partnership, or corporation, performing work by contract or subcontract on this project.
- C. Acceptance of a Contractor or Subcontractor will not relieve the Contractor or subcontractor of any contractual requirements or his responsibility to supervise and coordinate the work, of various trades.

1.5. MATERIALS AND EQUIPMENT

- A. Materials and equipment installed as a permanent part of the project shall be new, unless otherwise indicated or specified, and of the specified type and quality. Existing items of equipment are being relocated under another Division of these specifications. The Contractor shall be responsible for connecting all utilities as shown on the drawings, to equipment identified as existing.
- B. Where material or equipment is identified by proprietary name, model number and/or manufacturer, furnish named item, or its equal, subject to approval by Engineer. Substituted items shall be equal or better in quality and performance and must be suitable for available space, required arrangement, and application. Submit all data necessary to determine suitability of substituted items, for approval.
- C. The suitability of named item only has been verified. Where more than one item is named, only the first named item has been verified as suitable. Substituted items, including items other than first named shall be equal or better in quality and performance to that of specified items, and must be suitable for available space, required arrangement and application. Contractor, by providing other than the first named manufacturer, assumes responsibility for all necessary adjustments and modifications necessary for a satisfactory installation. Adjustments and modifications shall include but not be limited to electrical, structural, support, and architectural work.
- D. Substitution will not be permitted for specified items of material or equipment where noted.
- E. All items of equipment furnished shall have a service record of at least five (5) years.

1.6. FIRE SAFE MATERIALS

- A. Unless otherwise indicated, materials and equipment shall conform to UL, NFPA and ASTM standards for fire safety with smoke and fire hazard rating not exceeding flame spread of 25 and smoke developed of 50.

1.7. REFERENCED STANDARDS, CODES AND SPECIFICATIONS

- A. Specifications, Codes and Standards listed below are included as part of this specification, latest edition.
- B. ASHRAE - American Society of Heating, Refrigerating and Air Conditioning Engineers
- C. ASME - American Society of Mechanical Engineers
- D. ASPE - American Society of Plumbing Engineers
- E. ASTM - American Society for Testing and Materials
- F. CS - Commercial Standard
- G. CSD - Control and Safety Devices
- H. FM - Factory Mutual
- I. IBC - International Building Code
- J. IEEE - Institute of Electrical and Electronics Engineers
- K. MSSP - Manufacturers Standards Society of the Valve and Fittings Industry
- L. NEC - National Electrical Code
- M. NEMA - National Electrical Manufacturers Association
- N. NSF - National Sanitation Foundation
- O. UL - Underwriters' Laboratories
- P. All plumbing equipment and materials shall comply with the codes and standards listed in the latest edition of ASHRAE HVAC Applications Handbook, Chapter entitled Codes and Standards.

1.8. SUBMITTALS, REVIEW AND ACCEPTANCE

- A. Equipment, materials, installation, workmanship and arrangement of work are subject to review and acceptance. No substitution will be permitted after acceptance of equipment or materials except where such substitution is considered by the Engineer to be in best interest of Owner.

- B. After acceptance of Material and Equipment List, submit three (3) copies or more as required under General Conditions of complete descriptive data for all items. Data shall consist of specifications, data sheets, samples, capacity ratings, performance curves, operating characteristics, catalog cuts, dimensional drawings, wiring diagrams, installation instructions, and any other information necessary to indicate complete compliance with Contract Documents. Edit submittal data specifically for application to this project.
- C. Thoroughly review and stamp all submittals to indicate compliance with contract requirements prior to submission. Coordinate installation requirements and any electrical requirements for equipment submitted. Contractor shall be responsible for correctness of all submittals.
- D. Submittals will be reviewed for general compliance with design concept in accordance with contract documents, but dimensions, quantities, or other details will not be verified.
- E. Identify submittals, indicating intended application, location and service of submitted items. Refer to specification sections or paragraphs and drawings where applicable. Clearly indicate exact type, model number, style, size and special features of proposed item. Submittals of a general nature will not be acceptable. For substituted items, clearly list on the first page of the submittal all differences between the specified item and the proposed item. The contractor shall be responsible for corrective action and maintaining the specification requirements if differences have not been clearly indicated in the submittal.
- F. Submit actual operating conditions or characteristics for all equipment where required capacities are indicated. Factory order forms showing only required capacities will not be acceptable. Call attention, in writing, to deviation from contract requirements.
- G. Acceptance will not constitute waiver of contract requirements unless deviations are specifically indicated and clearly noted. Use only final or corrected submittals and data prior to fabrication and/or installation.
- H. For any submittal requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.
- I. For resubmissions, the Contractor must address in writing all of the Engineer's comments on the original submission to verify compliance.

1.9. SHOP DRAWINGS

- A. Prepare and submit shop drawings for all plumbing equipment, specially fabricated items, modifications to standard items, specially designed systems where detailed design is not shown on the contract drawings, or where the proposed installation differs from that shown on contract drawings.
- B. Submit data and shop drawings including but not limited to the list below, in addition to provisions of the paragraph above. Identify all shop drawings by the name of the item and system and the applicable specification paragraph number and drawing number.

- C. Every submittal including, but not limited to the list below, shall be forwarded with its own transmittal as a separate, distinct shop drawing. Grouping of items/systems that are not related shall be unacceptable.
- D. Items and Systems
 - 1. Access Doors/Panels including layout and location
 - 2. Automatic Temperature Control System and Equipment as it relates to plumbing system
 - 3. Backflow Preventers
 - 4. Coordinated Drawings
 - 5. Domestic Water Motorized Ball Valves
 - 6. Drain Valves
 - 7. Drip Pans
 - 8. Equipment Rails
 - 9. Exterior Equipment/Piping Supports
 - 10. Exterior Pipe Roller Support
 - 11. Fire Stopping - Methods and Materials
 - 12. Wall Hydrants
 - 13. Identification System
 - 14. Make-up Water Meters
 - 15. Material and Equipment List
 - 16. Motorized Ball Valves
 - 17. Operations and Maintenance Manuals
 - 18. Pipe Enclosures
 - 19. Pipe Guides and Anchors.
 - 20. Pipe Materials Including Itemized Schedule
 - 21. Preliminary Testing and Balancing Report
 - 22. Pressure/Temperature Relief Valves
 - 23. Pressure Regulating Valves

24. Screenshots of ATC System Graphics
 25. Shock Absorbers
 26. Strainers
 27. Test Certificates
 28. Thermal Insulation Materials Include Table Summary
 29. Thermometers and Gauges
 30. Vacuum Breakers
 31. Valves
 32. Vibration Isolation Materials
 33. Water Meters
 34. Weatherproof Assembly Components
 35. Wiring Diagrams, Flow Diagrams and Operating Instructions
- E. Contractor, additionally, shall submit for review any other shop drawings as required by the Engineer. No item shall be delivered to the site, or installed, until the Contractor has received a submittal from the Engineer marked Reviewed or Comments Noted. After the proposed materials have been reviewed, no substitution will be permitted except where approved by the Engineer.

1.10. SUPERVISION AND COORDINATION

- A. Provide complete supervision, direction, scheduling, and coordination of all work under the Contract, including that of subcontractors.
- B. Coordinate rough-in of all work and installation of sleeves, anchors, and supports for piping, equipment, and other work performed under Division 22.
- C. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction to allow for mechanical installations.
- D. Coordinate electrical work required under Division 22 with that under Division 26. Coordinate all work under Division 22 with work under all other Divisions.
- E. Supply services of an experienced (10 years minimum) and competent Project Manager to be in constant charge of work at site.
- F. Where a discrepancy exists within the specifications or drawings or between the specifications and drawings, the more stringent (or costly) requirement shall apply until clarification can be obtained from the Engineer. Failure to clarify such discrepancies with the Engineer will not relieve the Contractor of the responsibility of conforming to the requirements of the Contract.

- G. Failure of contractor to obtain a full and complete set of contract documents (either before or after bidding) will not relieve the contractor of the responsibility of complying with the intent of the contract documents.

1.11. CUTTING AND PATCHING

- A. Accomplish all cutting and patching necessary for the installation of work under Division 22. Damage resulting from this work to other work already in place, shall be repaired at Contractor's expense. Where cutting is required, perform work in neat and workmanlike manner. Restore disturbed work to match and blend with existing construction and finish, using materials compatible with the original. Use mechanics skilled in the particular trades required.
- B. Do not cut structural members without approval from the Engineer.

1.12. PENETRATION OF WATERPROOF CONSTRUCTION

- A. Coordinate the work to minimize penetration of waterproof construction, including roofs, exterior walls, and interior waterproof construction. Where such penetrations are necessary, furnish and install all necessary curbs, sleeves, flashings, fittings and caulking to make penetrations absolutely watertight.
- B. Furnish and install pitch pockets or weather tight curb assemblies where required.

1.13. CONCRETE AND MASONRY WORK

- A. Furnish and install concrete and masonry work for equipment foundations, supports, pads, and other items required under Division 22. Perform work in accordance with requirements of other applicable Divisions of these specifications.
- B. Concrete shall test not less than 3,000 psi compressive strength after 28 days.
- C. Grout shall be non-shrink, high strength mortar, free of iron or chlorides and suitable for use in contact with all metals, without caps or other protective finishes. Apply in accordance with manufacturer's instructions and standard grouting practices.

1.14. CONNECTIONS AND ALTERATIONS TO EXISTING WORK

- A. Unless otherwise noted on the drawings, where existing plumbing work is removed all pipes, valves, etc., shall be removed, including hangers, to a point below finished floors or behind finished walls and capped. Such point shall be far enough behind finished surfaces to allow for installation of normal thickness of required finish material.
- B. Where work specified in Division 22 connects to existing equipment, piping, etc., Contractor shall perform all necessary alterations, cuttings, fittings, etc., of existing work as may be necessary to make satisfactory connections between new and existing work, and to leave completed work in a finished and workmanlike condition.
- C. Where the work specified under Division 22, or under other Divisions, requires relocation of existing equipment, piping, etc., Contractor shall perform all work and make necessary changes to existing work as may be required to leave completed work in a finished and

workmanlike condition. Where existing insulation is disturbed, replace insulation where removed or damaged equal to existing, in type, thickness, density, finish and thermal resistance (R-value) value.

- D. Where the relocation of existing equipment is required for access or the installation of new equipment, the contractor shall temporarily remove and/or relocate and re-install as required to leave the existing and new work in a finished and workman like condition.

1.15. DEMOLITION

- A. Unless otherwise noted all existing equipment, piping, etc., shall remain.
- B. Where existing equipment is indicated to be removed, all associated piping, conduit, power, controls, control panels, sensors, tubing, insulation, hangers, supports and housekeeping pads, etc., patch, paint and repair walls/roof/floor to match existing and/or new finishes.
- C. Provide necessary piping, valves, traps, temporary feeds, etc., as required. Drain and refill piping systems as often as necessary to accommodate phasing and to minimize time lengths of outages.
- D. The Contractor shall be responsible for visiting the site and determining the existing conditions in which the work is to be performed.
- E. Where any abandoned pipes in existing floors, walls, pipe tunnels, ceilings, etc., conflict with new work, remove abandoned pipes as necessary to accommodate new work.
- F. The location of all existing equipment, piping, etc., indicated is approximate only and shall be checked and verified. Install all new plumbing work to connect to or clear existing work as applicable.
- G. Maintain egress at all times. Coordinate egress requirements with the State Fire Marshal, the Owner and the authorities having jurisdiction.
- H. When applicable, make provisions and include in bid all costs associated with confined entry/space requirements in crawl spaces, tunnels and all other applicable OSHA regulations.
- I. Where required to maintain the existing systems in operation, temporarily backfeed existing systems from new equipment. Contractor shall temporarily extend existing piping systems to new piping systems with the appropriate shut-off valves.
- J. At completion of project all temporary piping, valves, controls, etc., shall be removed in their entirety.
- K. Existing piping, equipment, materials, etc., not required for re-use or re-installation in this project, shall be removed from the project site.
- L. Deliver to the Owner, on the premises where directed, existing equipment and materials which are removed and which are desired by the Owner or are indicated to remain the property of the Owner.

- M. All other materials and equipment which are removed shall become property of the Contractor and shall be promptly removed, from the premises, and disposed of by the Contractor, in an approved manner.
- N. Where piping is removed, remove all pipe hangers which were supporting the removed piping. Patch the remaining penetration voids with like materials and paint to match existing construction.
- O. Where required, provide and coordinate removal and re-installation of existing equipment. Take care to protect materials and equipment indicated for reuse. Contractor shall repair or replace items which are damaged. Contractor shall have Owner's representative present to confirm condition of equipment prior to demolition.
- P. Before demolition begins, and in the presence of the Owners representative, test and note all deficiencies in all existing systems affected by demolition but not completely removed by demolition. Provide a copy of the list of system deficiencies to the Owner and the Engineer. Videotape existing conditions in each space prior to beginning demolition work.
- Q. The Owner shall have the first right of refusal for all plumbing fixtures, devices and equipment removed by the Contractor.
- R. All existing equipment refused by the Owner shall become the property of the Contractor and shall be removed from the site by the Contractor in a timely manner and disposed of in a legal manner.
- S. Work Abandoned in Place: cut and remove underground pipe a minimum of 2 inches beyond face of adjacent construction. Cap and patch surface to match existing finish.
- T. Temporary Disconnection: Remove, store, clean, reinstall, reconnect, and make operational equipment indicated for relocation.
- U. Terminate services and utilities in accordance with local laws, ordinances, rules and regulations.

1.16. VIBRATION ISOLATION

- A. Furnish and install vibration isolators, flexible connections, supports, anchors and/or foundations required to prevent transmission of vibration from equipment, or piping to building structure. See Division 23 Section, Vibration Controls for HVAC and Plumbing Equipment.

1.17. ALTERNATES

- A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

1.18. DEFINITIONS

- A. Approve - to permit use of material, equipment or methods conditional upon compliance with contract documents requirements.

- B. Furnish and install or provide means to supply, erect, install, and connect to complete for readiness for regular operation, the particular work referred to.
- C. Contractor means the mechanical contractor and any of his subcontractors, vendors, suppliers, or fabricators.
- D. Piping includes pipe, all fittings, valves, hangers, insulation, identification, and other accessories relative to such piping.
- E. Concealed means hidden from sight in chases, formed spaces, shafts, hung ceilings, or embedded in construction.
- F. Exposed means not installed underground or concealed as defined above.
- G. Invert Elevation means the elevation of the inside bottom of pipe.
- H. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceiling, and unexcavated spaces.
- I. Review - limited observation or checking to ascertain general conformance with design concept of the work and with information given in contract documents. Such action does not constitute a waiver or alteration of the contract requirements.
- J. Building Line: Exterior wall of building.

1.19. MINIMUM EFFICIENCY REQUIREMENTS

- A. All plumbing equipment shall be manufactured to provide the minimum efficiency requirements as specified in ASHRAE Standard 90.1, latest edition.
- B. All piping and equipment insulation shall comply with ASHRAE Standard 90.1, latest edition.
- C. All plumbing devices, controls, accessories, and components shall be manufactured to provide the minimum efficiency requirements as specified in ASHRAE Standard 90.1, latest edition.
- D. Department of Energy (DOE) compliance: Pump manufacturers shall comply with US Department of Energy (DOE) energy conservation standard for "clean water pumps" 1-200 horse power, less than 459 feet of head and greater than 25 gpm. These pumps shall be evaluated using the Pump Energy Index (PEI) of equal to or lesser than 1.0. The PEI number shall appear on the pump name plate and available for the record at <http://er.pumps.org>.

1.20. SYSTEM INTEGRATION

- A. For all plumbing equipment specified to be provided with packaged controls and interfaced with the automatic temperature control system, provide system integration between the equipment manufacturer and the automatic temperature control subcontractor.
- B. Plumbing equipment submittals requiring system integration as defined above must

identify all required system integration points.

- C. Plumbing equipment manufacturers must coordinate with ATC subcontractor regarding system integration prior to submitting on the equipment.
- D. A system integration meeting must be arranged by the Mechanical Contractor and include, but not be limited to the systems integrator for the plumbing equipment manufacturer and the ATC Subcontractor. This portion of systems integration must occur prior to plumbing equipment being delivered to the project.
- E. Once the plumbing equipment is on site, a second systems integration meeting must be arranged by the Mechanical Contractor to coordinate the packaged controls with the ATC system. The plumbing equipment manufacturer's representative familiar with system integration and the ATC subcontractor familiar with programming must be present.
- F. A final system integrations meeting shall occur once all equipment is in place and ready for operation. The Mechanical Contractor, the plumbing equipment systems' integrator, and the ATC Subcontractor shall meet on site to jointly program, schedule, verify points, interlock devices, and fully set up all systems integration components.
- G. All systems integration coordination, programming, and graphics must be completed prior to requesting commissioning and/or inspections by the Engineer of Record.

1.21. LEAD FREE REQUIREMENTS

- A. All plumbing fixtures, equipment, and devices that contact potable water must be lead free per the State requirements. Potable water systems shall also comply with NSF 61 – Annex G and NSF-372.

1.22. COORDINATION WITH INDIAN RIVER SCHOOL DISTRICT I.T. DEPARTMENT

- A. All equipment that interfaces with the internet shall be coordinated with the Indian River School District I.T. Department to verify that the same is suitable for use on the School IT infrastructure. Coordinate with the Indian River School District I.T. Department regarding the allowable frequency bands to avoid interference with each school's I.T. infrastructure.

1.23. EXTRA MATERIALS

- A. Provide one set of seals for each type and model of pump provided on the project at each school.

PART 2. ELECTRICAL REQUIREMENTS

2.1. GENERAL MOTOR AND ELECTRICAL REQUIREMENTS

- A. Furnish and install control and interlock wiring for the equipment furnished. In general, power wiring and motor starting equipment will be provided under Division 26. Carefully review the contract documents to coordinate the electrical work under Division 22 with the work under Division 26. Where the electrical requirements of the equipment furnished differ from the provisions made under Division 26, make the necessary allowances under Division 22. Where no electrical provisions are made under Division 26, include all

necessary electrical work under Division 22.

- B. All electrical work performed under Division 22 shall conform to the applicable requirements of Division 26 and conforming to the National Electrical Code. All wiring, conduit, etc., installed in ceiling plenums must be plenum rated per NFPA & International Building Code.
- C. Provide wiring diagrams with electrical characteristics and connection requirements.
- D. Test Reports: Indicate test results verifying nominal efficiency and power factor for three phase motors larger than five (5) horsepower.
- E. Protect motors stored on site from weather and moisture by maintaining factory covers and suitable weatherproof covering. For extended outdoor storage, remove motors from equipment and store separately.
- F. All motors shall be furnished with visible nameplate indicating motor horsepower, voltage, phase, cycles, RPM, full load amps, locked rotor amps, frame size, manufacturer's name and model number, service factor, power factor and efficiency.
- G. Motors located in exterior locations, wet air streams and outdoors shall be totally enclosed weatherproof epoxy-treated type.
- H. Nominal efficiency and power factor shall be as scheduled at full load and rated voltage when tested in accordance with IEEE 112.
- I. Brake horsepower load requirement at specified duty shall not exceed 85 percent of nameplate horsepower times NEMA service factor for motors with 1.0 and 1.15 service factors.
- J. All single phase motors shall be provided with thermal protection: Internal protection shall automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature ratings of motor insulation. Thermal protection device shall automatically reset when motor temperature returns to normal range, unless otherwise indicated.
- K. Where a motor disconnect is indicated downstream of a variable frequency drive (VFD) provide interlock wiring from the auxiliary contacts on the disconnect to the VFD to de-energize when the disconnect is turned "off".
- L. Where equipment under this Division is specified with integral disconnecting means, the same shall be a single disconnecting means for disconnecting all ungrounded main power supply conductors that is capable of being locked in the open ("off") position in accordance with the National Electrical Code and the local electrical inspector.

2.2. MOTORS AND CONTROLS

- A. Motors and controls shall conform to the latest requirements of IEEE, NEMA, NFPA-70 and shall be UL listed. Motor sizes are specified with the driven equipment. Motor starting and control equipment is specified either with the motor which is controlled or in an electrical specification section. The Contractor is advised to consult all specification

sections to determine responsibility for motors and controls.

- B. Motors shall be designed, built and tested in accordance with the latest revision of NEMA Standard MG 1.
- C. Motors used with variable-frequency controllers shall have ratings, characteristics, and features coordinated with and approved by the variable frequency controller (drive) manufacturer. As a minimum the following shall apply to variable frequency controlled motors:
 - 1. Motors shall be manufactured to withstand peak voltages of 1600 volts with .1 microsecond rise time per NEMA MG-1.
 - 2. Critical vibration frequencies of motor shall not be within operating range of variable frequency controller output.
 - 3. Temperature rise: Match rating for Class B insulation.
 - 4. Insulation: Class F.
 - 5. Thermal Protection: Conform to MG1 requirements for thermally protected motors.
- D. Motors shall be suitable for use under the conditions and with the equipment to which applied, and designed for operation on the electrical systems specified or indicated.
 - 1. Motor capacities shall be such that the horsepower rating and the rated full-load current will not be exceeded while operating under the specified operating conditions. Under no condition shall the motor current exceed that indicated on the nameplates.
 - 2. Motor sizes noted in the individual equipment specifications are minimum requirements only. It is the responsibility of the equipment manufacturers and of the Contractor to furnish motors, electrical circuits and equipment of ample capacity to operate the equipment without overloading, exceeding the rated full-load current, or overheating at full-load capacity under the most severe operating service of this equipment. Motors shall have sufficient torque to accelerate the total WR2 of the driven equipment to operating speed.
 - 3. Motors shall be continuous duty type and shall operate quietly at all speeds and loads.
 - 4. Motors shall be designed for operation on 60 hertz power service. Unless otherwise specified or shown, motors less than ½ horsepower shall be single phase, and motors ½ horsepower and larger shall be 3 phase unless otherwise noted.
 - 5. Motors shall be mounted so that the motor can be removed without removing the entire driven unit.
- E. Single phase motors, smaller than 1/20 horsepower shall be ball or sleeve bearing; drip-proof, totally enclosed or explosion proof, as specified; 120 volts; permanent-split

capacitor or shaded pole type. These motors shall not be used for general power purposes, and shall only be provided as built-in components of plumbing equipment. When approved by the Engineer, deviations from the specifications will be permitted as follows:

1. Open motors may be installed as part of an assembly where enclosure within a cabinet provides protection against moisture.
 2. Motors used in conjunction with low voltage control systems may have a voltage rating less than 115 volts.
- F. Single phase motors, greater than 1/20 horsepower and less than ½ horsepower shall be ball bearing; drip-proof, totally enclosed or explosion proof, as specified, with Class A or B insulation, as standard with the motor manufacturer; 115 or 120/208/240 volts as required; capacitor start-induction run, permanent split capacitor, or repulsion start-induction run type with minimum efficiency of 70 percent and a minimum full load power of 77 percent.
- G. Except as otherwise specified in the various specification sections, 3 phase motors 60 horsepower and smaller shall be NEMA design B squirrel cage induction type meeting the requirements of this paragraph. Motors shall be drip-proof, totally enclosed or explosion proof, as specified or indicated. Insulation shall be Class B or F, at 40 degrees C ambient temperature. Drip-proof motors shall have a 1.15 service factor and totally enclosed and explosion proof motors shall have a service factor of 1.00 or higher. Motors specified for operation at 480, 240, and 208 volts shall be nameplated 460, 230, 200 volts, respectively. Efficiencies and percent power factor at full load for three phase motors shall be not less than the values listed below for premium efficiency motors:

MOTOR NAMEPLATE	MINIMUM PERCENT EFFICIENCY AT NOMINAL SPEED AND RATED LOAD	MINIMUM PERCENT POWER FACTOR
1HP and above to	85.5 percent	84 percent
1-½ HP	86.5 percent	85 percent
2HP	86.5 percent	85 percent

- H. Three phase motors ½ HP or greater shall be the Duty Master XE by Reliance Electric Company, Super-E Premium Efficiency of Baldor Motor and Drives, E-plus Efficient Standard Duty Motor of the Electric Motor Division of Gould, Inc., the MAC II High Efficiency motor of Westinghouse Electric Corp., the equivalent product of General Electric, or approved equal.
- I. Motor frames shall be NEMA Standard T-Frames of steel, aluminum, or cast iron with end brackets of cast-iron or aluminum with steel inserts.
- J. Control of each motor shall be manual or automatic as specified for each in the various mechanical sections. In general, and unless otherwise specified for a particular item in the various mechanical sections of the specifications, motor starters and controls shall be specified and provided under the various electrical sections of these specifications.

2.3. MOTOR INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install securely on firm foundation. Mount ball bearing motors to support shaft regardless of shaft position.
- C. Check line voltage and phase and ensure agreement with nameplate. Check that proper thermal overloads have been installed prior to operating motors.

2.4. WIRING DIAGRAMS

- A. The Contractor is responsible for obtaining and submitting wiring diagrams for all major items of equipment.
- B. Wiring diagrams shall be provided with shop drawings for all equipment requiring electric power.
- C. Provide wiring diagrams for all major plumbing items of equipment to electrical contractor and ATC subcontractor for coordination.

2.5. ENCLOSURES

- A. Electrical enclosures including factory provided enclosures, field provided and installed enclosures, and automatic temperature control system enclosures shall be as follows:
 - 1. Dry Interior Locations: NEMA 1.
 - 2. Damp/Wet Locations, Including Exterior Locations: NEMA 3R.

PART 3. EXECUTION

3.1. EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- A. Install equipment to provide maximum possible headroom, if mounting heights are not indicated.
- B. Install equipment according to approved submittal data. Portions of the work are shown only in diagrammatic form. Refer conflicts to the Engineer.
- C. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.
- D. Install plumbing equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
- E. Install equipment giving right of way to piping installed at required slope.
- F. Install flexible connectors on equipment side of shutoff valves, horizontally and parallel to equipment shafts if possible.

- G. Do not install equipment or piping over electrical gear, electrical panels, motor controllers, and similar electrical equipment. Install equipment and piping to maintain clear space above and in front of all electrical components per the National Electric Code.

3.2. SUPPORTS, HANGERS AND FOUNDATIONS

- A. Provide supports, hangers, braces, attachments and foundations required for the work. Support and set the work in a thoroughly substantial and workmanlike manner without placing strains on materials, equipment, or building structure, submit shop drawings for approval. Coordinate all work with the requirements of the structural division.
- B. Supports, hangers, braces, and attachments shall be standard manufactured items or fabricated structural steel shapes. All interior hangers shall be galvanized or steel with rust inhibiting paint. For un-insulated copper piping provide copper hanger to prevent contact of dissimilar metals. All exterior hangers shall be constructed of stainless steel utilizing stainless steel rods, nuts, washers, bolts, etc.
- C. Concrete housekeeping pads and foundations shall be not less than 4 inches high and shall extend a minimum of 6 inches beyond equipment bases. Provide wire-mesh reinforcement; chamfer exposed edges and corners; and finish exposed surfaces smooth.
- D. Where new concrete housekeeping pads are placed on existing concrete, saw cut the existing concrete to the perimeter dimension of the new pad to a depth of ½ inch. Break out the top ½ inch area of the existing concrete. Add stubs of #4 rebar angled into the existing concrete at a depth of approximately 50 percent of the existing slab thickness. The top portion of the rebar stub shall extend into the new pad by approximately 50 percent of its thickness. Furnish one rebar stub per every two square feet of new pad. Chemically bond the new concrete to the existing concrete.

3.3. DEMONSTRATION AND TRAINING VIDEO RECORDINGS

- A. General: Record demonstration and training video recordings. Record each training module separately.
 - 1. At beginning of each training module, record each chart containing learning objective and lesson outline.
- B. Video Recording Format: Provide high-quality color video recordings with menu navigation in format acceptable to Engineer
- C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to show area of demonstration and training. Display continuous running time.
- D. Narration: Describe scenes on video recording by audio narration by microphone while video recording is recorded. Include description of items being viewed.
- E. Transcript: Provide a transcript of the narration. Display images and running time captured from videotape opposite the corresponding narration segment.

3.4. PROVISIONS FOR ACCESS

- A. The contractor shall provide access panels and doors for all concealed equipment, valves, strainers, dampers, filters, controls, control devices, cleanouts, traps, and other devices requiring maintenance, service, adjustment, balancing or manual operation.
- B. Where access doors are necessary, furnish and install manufactured painted steel door assemblies consisting of hinged door, key locks, and frame designed for the particular wall or ceiling construction. Properly locate each door. Door sizes shall be a minimum of 12 inches x 12 inches for hand access, 18 inches x 18 inches for shoulder access and 20 inches x 30 inches for full body access where required. Review locations and sizes with Engineer prior to fabrication. Provide U.L. approved and labeled access doors where installed in fire rated walls or ceilings. Doors shall be Milcor Metal Access Doors as manufactured by Inland-Ryerson, Mifab, or approved equal.
 - 1. Acoustical or Cement Plaster: Style B
 - 2. Hard Finish Plaster: Style K or L
 - 3. Masonry or Dry Wall: Style M
- C. Where access is by means of liftout ceiling tiles or panels, mark each ceiling grid using small color-coded and numbered tabs. Provide a chart or index for identification. Place markers within ceiling grid not on ceiling tiles.
- D. Access panels, doors, etc. described herein shall be furnished under the section of specifications providing the particular service and to be turned over to the pertinent trade for installation. Coordinate installation with installing contractor. All access doors shall be painted in baked enamel finish to match ceiling or wall finish.
- E. Submit shop drawings indicating the proposed location of all access panels/doors. Access doors in finished spaces shall be coordinated with air devices, lighting and sprinklers to provide a neat and symmetrical appearance.

3.5. PAINTING AND FINISHES

- A. Provide protective finishes on all materials and equipment. Use coated or corrosion-resistant materials, hardware and fittings throughout the work. Paint bare, untreated ferrous surfaces with rust-inhibiting paint. All exterior components including supports, hangers, nuts, bolts, washers, vibration isolators, etc. shall be stainless steel.
- B. Clean surfaces prior to application of insulation, adhesives, coatings, paint, or other finishes.
- C. Provide factory-applied finishes where specified. Unless otherwise indicated factory-applied paints shall be baked enamel with proper pretreatment.
- D. Protect all finishes and restore any finishes damaged as a result of work under Division 22 to their original condition.
- E. The preceding requirements apply to all work, whether exposed or concealed.
- F. Remove all construction marking and writing from exposed equipment, piping and

building surfaces. Do not paint manufacturer's labels or tags.

- G. All exposed piping, equipment, etc. shall be painted. Colors shall be as stated in this division or as selected by the Owner and conform to ANSI Standards.
- H. All exterior roof mounted equipment, piping and vents shall be painted to match roof in color as selected by Owner.
- I. All exposed piping, equipment, etc. in finished spaces shall be painted. Colors shall be as selected by the Owner and conform to ANSI Standards.
- J. All exposed piping, equipment, etc., in Mechanical Rooms, Fire Pump Rooms, Mezzanines, and Storage where PVC jacketed shall not require painting. Label and identify and color code as specified.

3.6. CLEANING OF SYSTEMS

- A. Thoroughly clean systems after satisfactory completion of pressure tests and before permanently connecting fixtures, equipment, traps, strainers, and other accessory items. Blow out and flush piping until interior surfaces are free of foreign matter.
- B. Flush piping in re-circulating water systems to remove cutting oil, excess pipe joint compound, solder slag and other foreign materials. Do not use system pumps until after cleaning and flushing has been accomplished to the satisfaction of the Engineer. Employ chemical cleaners, including a non-foaming detergent, not harmful to system components. After cleaning operation, final flushing and refilling, the residual alkalinity shall not exceed 300 parts per million. Submit a certificate of completion to Engineer stating name of service company used.
- C. Maintain strainers and dirt pockets in clean condition.
- D. Pay for labor and materials required to locate and remove obstructions from systems that are clogged with construction refuse after acceptance. Replace and repair work disturbed during removal of obstructions.
- E. Leave systems clean, and in complete running order.

3.7. COLOR SELECTION

- A. Color of finishes shall be as selected by the Owner.
- B. Submit color of factory-finished equipment for acceptance prior to ordering.

3.8. PROTECTION OF WORK

- A. Protect work, material and equipment from weather and construction operations before and after installation. Properly store and handle all materials and equipment.
- B. Cover temporary openings in piping and equipment to prevent the entrance of water, dirt, debris, or other foreign matter. Deliver pipes and tubes with factory applied end caps.
- C. Cover or otherwise protect all finishes.

- D. Replace damaged materials, devices, finishes and equipment.
- E. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, where stored inside.

3.9. OPERATION OF EQUIPMENT

- A. Clean all systems and equipment prior to initial operation for testing, balancing, or other purposes. Lubricate, adjust, and test all equipment in accordance with manufacturer's instructions. Do not operate equipment unless all proper safety devices or controls are operational. Provide all maintenance and service for equipment that is authorized for operation during construction.
- B. Where specified, or otherwise required, provide the services of the manufacturer's factory-trained servicemen or technicians to start up the equipment. Where factory start-up of equipment is not specified, provide field start-up by qualified technician.
- C. Submit factory start-up sheets or field start-ups sheets for all equipment prior to the commencement of testing and balancing work. Testing and balancing work shall not commence until start-up reports have been completed, reviewed by Engineer and forwarded to Testing and Balancing Agency.
- D. Do not use plumbing systems for temporary services or temporary conditioning during construction. Refer to Division 01 section "Temporary Facilities and Controls" for temporary plumbing during construction.
- E. Upon completion of work, clean and restore all equipment to new conditions; replace expendable items such as filters.

3.10. IDENTIFICATIONS, FLOW DIAGRAMS, ELECTRICAL DIAGRAMS AND OPERATING INSTRUCTIONS

- A. Contractor shall submit for approval schematic piping diagrams of each piping system installed in the building. Diagrams shall indicate the location and the identification number of each valve in the particular system. Following approval by all authorities, the diagrams shall be framed, mounted under safety glass and hung in each Mechanical Room where directed. Contractor shall deliver the tracing or sepia from which the diagrams were reproduced to the Owner.
- B. All valves shall be plainly tagged. For any bypass valves, install sign indicating valve position as "Normally Open" or "Normally Closed" as required.
- C. All items of equipment, including motor starters and disconnects shall be furnished with white on black plastic permanent identification cards. Lettering shall be a minimum of 1/4 inch high. Identification plates shall be secured, affixed to each piece of equipment, starters, disconnects, panels by screw or adhesive (tuff bond #TB2 or as approved equal). Equipment identification and room name or area served shall be on each panel.
- D. Provide six (6) copies of operating and maintenance instructions for all principal items of equipment furnished. This material shall be bound as a volume of the Operations and Maintenance Manuals as hereinafter specified.

- E. All lines piping installed under this contract shall be stenciled with direction of flow arrows and with stenciled letters naming each pipe and service. Refer to Division 22 Section, Plumbing Piping, Fittings, Valves, Etc. Color code all direction of flow arrows and labels. In finished spaces omit labeling and direction of flow arrows. Paint in color as selected by Owner.
- F. Submit list of wording, symbols, letter size, and color coding for plumbing identification. Submit samples of equipment identification cards, piping labels, labels, and valve tags to Engineer for review prior to installation.
- G. Provide at least 24 hours of straight time instruction to the operating personnel. Time of instruction shall be designated by the Owner. Additional instruction time for the automatic temperature control (ATC) system is specified in Division 23 Section, Instrumentation and Controls of HVAC and Plumbing Systems.
- H. Contractor shall demonstrate Sequences of Operation of all plumbing equipment in presence of Owner's representative, Engineer, and ATC subcontractor.

3.11. WALL AND FLOOR PENETRATION

- A. All penetrations of partitions, ceilings, roofs and floors by piping or conduit under Division 22 shall be sleeved, sealed, and caulked airtight for sound and air transfer control. Penetrations of mechanical room partitions, ceilings, and floors shall be as specified in Division 07 Section, "HVAC and Plumbing Penetration Firestopping".
- B. All penetration of fire rated assemblies shall be sleeved, sealed, caulked and protected to maintain the rating of the wall, roof, or floor. Fire Marshal approved U.L. assemblies shall be utilized. See Division 07 Section, "HVAC and Plumbing Penetration Firestopping".
- C. Where piping extends through exterior walls or below grade, provide waterproof pipe penetration seals, as specified in another division of these specifications.
- D. Provide pipe escutcheons for sleeved pipes in finished areas.
- E. Piping sleeves:
 - 1. Galvanized steel pipe, standard weight where pipes are exposed and roofs and concrete and masonry walls. On exterior walls provide anchor flange welded to perimeter.
 - 2. Twenty-two (22) gauge galvanized steel elsewhere.
- F. Extend all floor sleeves through floor at least 2-inches above finished floor, caulk sleeve the entire depth and furnish and install floor plate.
- G. For renovation projects where new pipes penetrate existing floors, furnish ground penetrating radar to properly map out acceptable locations for pipe penetrations. Review penetrations with Structural Engineer.

3.12. RECORD DRAWINGS

- A. Upon completion of the mechanical installations, the Contractor shall deliver to the Engineer one complete set of prints of the mechanical contract drawings which shall be legibly marked in red pencil to show all changes and departures of the installation as compared with the original design. They shall be suitable for use in preparation of Record Drawings.
- B. Contractor shall incorporate all sketches, addendums, value engineering, change orders, etc., into record drawings prior to delivering to Engineer.

3.13. WARRANTY

- A. Contractor's attention is directed to warranty obligations contained in the General Conditions and Supplementary Conditions.
- B. The above shall not in any way void or abrogate equipment manufacturer's guarantee or warranty. Certificates of equipment manufacturer's warranties shall be included in the operations and maintenance manuals.
- C. The contractor guarantees for a two (2) year period from the time of final acceptance by the Owner.
 - 1. That the work contains no faulty or imperfect material or equipment or any imperfect, careless, or unskilled workmanship.
 - 2. That all work, equipment, machines, devices, etc. shall be adequate for the use to which they are intended, and shall operate with ordinary care and attention in a satisfactory and efficient manner.
 - 3. That the contractor will re-execute, correct, repair, or remove and replace with proper work, without cost to the Owner, any work found to be deficient. The contractor shall also make good all damages caused to their work or materials in the process of complying with this section.
 - 4. That the entire work shall be water-tight and leak-proof.

3.14. OPERATIONS AND MAINTENANCE MANUALS

- A. The Contractor shall have prepared three (3) hardcopies and one (1) electronic copy of the Operations and Maintenance Manuals for each of the six (6) schools on the project and deliver these copies of the manuals to the Owner. The manuals shall be as specified herein. The manuals must be approved and will not be accepted as final until so stamped.
- B. The manuals shall be bound in a three ring loose-leaf binder similar to National No. 3881 with the following title lettered on the front: Operations and Maintenance Manual - Indian River School District – (The appropriate name of the school where the manual will be stored) - Heat of Rejection Equipment Replacement – Plumbing Systems. No sheets larger than 8-1/2 inches x 11 inches shall be used, except sheets that are neatly folded to 8-1/2 inches x 11 inches and used as a pull-out. Provide divider tabs and table of contents for organizing and separating information.
- C. Electronic copies of the manual shall be saved on USB flash drives, and shall be in

searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of Volume 1 (if applicable) of hard copies of the manual.

D. Provide the following data in the booklet:

1. As first entry, an approved letter indicating the starting/ending time of Contractor's warranty period.
2. Catalog data on each piece of plumbing equipment furnished.
3. Maintenance operation and lubrication instructions on each piece of plumbing equipment furnished.
4. Complete catalog data on each piece of plumbing equipment furnished including approved shop drawing.
5. Manufacturer's extended limited warranties on equipment.
6. Chart form indicating frequency and type of routine maintenance for all plumbing equipment. The chart shall also indicate model number of equipment, location and service.
7. Provide sales and authorized service representatives names, address, and phone numbers of all equipment and subcontractors.
8. Provide supplier and subcontractor's names, address, and phone number.
9. Catalog data of all equipment, valves, etc. shall include wiring diagrams, parts list and assembly drawing.
10. Provide and install in locations as directed by the Owner, valve charts including valve tag number, valve type, valve model number, valve manufacturer, style, service and location. Each valve chart shall be enclosed in a durable polymer based frame with a cover safety glass. .
11. Copy of the approved balancing report for plumbing equipment/system.
12. Access panel charts with index illustrating the location and purpose of access panels.
13. Approved HVAC, Plumbing, and Electrical Certificates.
14. Start-up reports for equipment.
15. Insert color graphic with embedded parameters for ATC system into Record and Information Booklet.
16. Cooling Tower/Closed Circuit Evaporative Fluid Cooler Winterization Instructions

E. Submit Operations and Maintenance Manuals prior to the anticipated date of substantial

completion for Engineer review and approval. Substantial completion requires that Operations and Maintenance Manuals are reviewed and approved.

3.15. INSTALLATION AND COORDINATION DRAWINGS

- A. Prepare, submit, and use composite installation and coordination drawings to assure proper coordination and installation of work. Drawings shall include, but not be limited, to the following:
 - 1. Complete Plumbing, Sprinkler and HVAC Piping Drawings showing coordination with lights, electrical equipment, HVAC equipment and structural amenities.
- B. Draw plans to a scale not less than 3/8-inch equals one foot. Include plans, sections, and elevations of proposed work, showing all equipment, and piping in areas involved. Fully dimension all work including lighting fixtures, conduits, pullboxes, panelboards, and other electrical work, walls, doors, ceilings, columns, beams, joists and other architectural and structural work.
- C. Identify all equipment and devices on wiring diagrams and schematics. Where field connections are shown to factory-wired terminals, include manufacturer's literature showing internal wiring.

3.16. PIPING SYSTEMS TESTING

- A. The entire new plumbing piping systems shall be tested hydrostatically before insulation covering is applied and proven tight under the following gauge pressures for a duration of twenty-four (24) hours. Testing to be witnessed by Owner's representative and documented in writing.

SYSTEM	TEST PRESSURE
Domestic Water Piping	100 psi
Chemical Treatment Water Piping	50 psig

- B. Upon completion of roughing-in and before setting equipment and fixtures, the entire new water piping system shall be tested at a hydrostatic pressure of not less than one hundred (100) pounds per square inch gauge and proven tight at this pressure. Where a portion of the water piping system is to be concealed before completion, this portion shall be tested separately in a manner described for the entire system.
- C. Testing and acceptance thereof shall be in accordance with local requirements and shall meet approval of authority having jurisdiction. Submit certificates and approved permits and insert one (1) copy in the Operations and Maintenance Manuals.

3.17. WINTERIZATION OF ALL WATER CONTAINING PIPING SYSTEMS

- A. The cooling towers/closed circuit evaporative fluid coolers will be provided with provisions to be winterized every winter. Contractor to install all drain valves, plugs, and Schrader valves to allow proper winterization.
- B. Contractor to include in scope and bid all costs, material, and labor for winterizing the

cooling towers/closed circuit evaporative fluid coolers in preparation for the first winter.

- C. A detailed plan with instructions for winterizing the cooling towers/closed circuit evaporative fluid coolers shall be provided by the Contractor and inserted in the operation and maintenance manuals.

END OF SECTION

OUTAGE REQUEST

DATE APPLIED: _____ BY: _____

DATE FOR OUTAGE: _____ FIRM: _____

START OUTAGE-TIME: _____ DATE: _____

END OUTAGE -- TIME: _____ DATE: _____

AREAS AND ROOMS: _____

FLOOR(S): _____

AREA(S): _____

ROOM(S): _____

WORK TO BE PERFORMED: _____

SYSTEM(S): _____

REQUEST APPROVED BY: _____

(FOREMAN OR OTHER PERSON IN CHARGE)

(FOR OWNER'S USE ONLY):

APPROVED: _____

YES ____ NO ____ BY: _____ DATE: _____

DATE/TIME-AS REQUESTED: _____ OTHER : _____

OWNER'S PRESENCE REQUIRED: _____

YES: ____ NO: ____ NAME: _____

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 22 SECTION 22 05 05
PLUMBING PIPING, FITTINGS & VALVES
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. SUMMARY	3
1.2. SYSTEM DESCRIPTION CONDITIONS	3
1.3. QUALITY ASSURANCE	3
1.4. DELIVERY, STORAGE AND HANDLING	4
1.5. ENVIRONMENTAL REQUIREMENTS	4
1.6. ALTERNATES	4
1.7. LEAD FREE REQUIREMENTS	4
1.8. PLASTIC PIPE PENETRATIONS	4
PART 2. PRODUCTS	4
2.1. PIPE MATERIALS	4
2.2. PIPE HANGERS, ROLLER SUPPORTS, ANCHORS, GUIDES, AND SADDLES	7
2.3. VALVES	9
2.4. STRAINERS	9
2.5. UNIONS, FLANGES, AND COUPLINGS	9
2.6. MANUAL AIR VENTS	9
2.7. THERMOMETERS	10
2.8. PRESSURE GAUGES	10
2.9. PIPING SPECIALTIES	10
2.10. ESCUTCHEONS	11
2.11. DIELECTRIC CONNECTIONS:	11
2.12. SLEEVES	11
2.13. PRESSURE REDUCING VALVES	12
2.14. WATER PROOF PIPE PENETRATION SEALS	12
2.15. TRANSITION FITTINGS	12
PART 3. EXECUTION	13
3.1. GENERAL PIPING INSTALLATION REQUIREMENTS	13
3.2. THERMOMETER AND PRESSURE GAGE INSTALLATION REQUIREMENTS	14
3.3. VALVE INSTALLATION REQUIREMENTS	15
3.4. PIPE JOINTS INSTALLATION REQUIREMENTS	16
3.5. HANGERS AND SUPPORTS INSTALLATION REQUIREMENTS	17
3.6. AIR VENTING INSTALLATION REQUIREMENTS	18
3.7. EXPANSION LOOPS AND SWING CONNECTION INSTALLATION REQUIREMENTS	18
3.8. PIPING IDENTIFICATION REQUIREMENTS	18
3.9. VALVE IDENTIFICATION REQUIREMENTS	19
3.10. CLEANING PIPING AND EQUIPMENT REQUIREMENTS	19
3.11. PRESSURE SEAL FITTING INSTALLATION REQUIREMENTS	19
END OF SECTION	20

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 22 05 05 - PLUMBING PIPING, FITTINGS AND VALVES

PART 1. GENERAL

1.1. SUMMARY

- A. The conditions of the contract and other general requirements apply to the work specified in this section. All work under this section shall also be subject to the requirements of Division 22 Section, Common Work Results for Plumbing and Division 01, General Requirements.
- B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SYSTEM DESCRIPTION CONDITIONS

- A. Provide all labor and materials necessary to furnish and install all piping systems on this project as herein specified and/or shown on the drawings. Final connections to equipment furnished in other sections of the specifications shall be included under this section.
- B. All piping and insulation installed in ceiling plenums must be plenum rated and comply with NFPA and International Building Code (IBC).
- C. Where more than one piping system material is specified, ensure system components are compatible and joined to ensure the integrity of the system is not jeopardized. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.
- D. Use unions, flanges, and couplings downstream of valves and at equipment or apparatus connections. Do not use direct welded or threaded connections to valves, equipment or other apparatus.
- E. Use non-conducting dielectric connections whenever jointing dissimilar metals in open systems.
- F. Provide pipe hangers and supports in accordance with ASTM B31.9 and MSS SP69 unless indicated otherwise.
- G. Use spring loaded "silent" check valves on discharge of all pumps.
- H. Use 3/4 inch (20 mm) ball valves with cap and chain for drains at main shut-off valves, low points of piping, bases of vertical risers, and at equipment. Pipe to nearest floor drain.
- I. At all runout piping serving equipment, use swing joints with elbows to prevent excessive movement of piping due to expansion.

1.3. QUALITY ASSURANCE

- A. Valves: Manufacturer's name and pressure rating marked on valve body.
- B. All grooved joint couplings, fittings, valves, and specialties shall be the products of a single manufacturer. Grooving tools shall be of the same manufacturer as the grooved

components.

- C. All castings used for coupling housings, fittings, and valve bodies shall be date stamped for quality assurance and traceability.
- D. Maintain one copy of each document on site.

1.4. DELIVERY, STORAGE AND HANDLING

- A. Deliver, store, protect and handle products to site under as hereinbefore specified.
- B. Accept valves on site in shipping containers with labeling in place. Inspect for damage.
- C. Provide temporary protective coating on cast iron and steel valves.
- D. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.
- E. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed systems.

1.5. ENVIRONMENTAL REQUIREMENTS

- A. Do not install underground piping when bedding is wet or frozen.

1.6. ALTERNATES

- A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

1.7. LEAD FREE REQUIREMENTS

- A. All plumbing fixtures, equipment, and devices that contact potable water must be lead free per the State requirements.

1.8. PLASTIC PIPE PENETRATIONS

- A. Install UL listed collars, sealing methods, and firestopping at all plastic pipe penetrations of smoke walls and fire rated walls per NFPA.

PART 2. PRODUCTS

2.1. PIPE MATERIALS

- A. All materials, unless otherwise specified, shall be new and of the best quality of their respective kinds, and shall conform to the requirements and ordinances of local, state and insurance authorities having jurisdiction.

- 1. Indirect Waste Piping:

- a. Pipe & Fittings: Hard drawn Type L copper tubing with cast brass drainage fittings. ASTM B88-78 and ANSI B16.1877. All exposed

indirect waste piping shall be chrome plated or primed and painted with silver paint.

2. Domestic Cold Water Piping Inside Buildings, Above Grade:

- a. Pipe or Tubing: 2 inches & smaller, all water lines soft temper Type K copper tubing below ground, hard temper Type L copper tubing above ground, ASTM B88, or Type 304/304L, Schedule 10S, stainless steel to ASTM A312.
2-1/2 inches & larger, hot dipped galvanized steel A120, ASTM A53, Grade B, Schedule 40 steel, or hard copper tube, Type L with copper-tube dimensioned grooved ends; copper ground - end fittings; copper tubing, keyed couplings; and grooved joints. (Flaring of tube or fitting ends to accommodate alternate sized couplings is not permitted.)
Provide dielectric fittings between steel and copper. Victaulic Style 47 or approved equal.
- b. Fittings & Joints: Copper tubing fittings and joints shall be solder type wrought copper - 95-5 silver solder or braze (lead and antimony based solders are prohibited). Galvanized steel pipe fittings and joints shall be ANSI B16.12 hot dipped galvanized threaded ends and 125 lb. galvanized cast iron fittings or 150 lb. galvanized malleable iron.
 - i. Stainless steel fittings shall be Vic-Press or approved equal for Schedule 10S pipe. Fittings shall be precision, cold drawn, stainless steel with EPDM O-ring seals. (Seals shall be UL classified in accordance with ANSI/NSF61 for Potable Water service.) Fittings rated for working pressures to 500-psi.
 - ii. Grooved joint couplings shall consist of two ductile iron housing segments cast with offsetting angle pattern bolt pads, FlushSeal elastomer gasket, and ASTM A449 electroplated steel bolts and nuts. (Gasket shall be UL classified in accordance with ANSI/NSF61 for Potable Water service, and shall meet the lead content requirements of NSF-372.) Installation-Ready, for direct stab installation without field disassembly. Victaulic Style 807N or approved equal. Couplings shall be coated blue enamel.
 - iii. Installation-Ready™ fittings for grooved end copper tubing shall be manufactured to copper-tube dimensions. Fittings shall be ductile iron conforming to ASTM A-536, Grade 65-45-12, with Installation-Ready™ ends, complete with PVDF (Poly Vinylidene Fluoride) and Grade "EHP" EPDM-HP (Grade 'T' Nitrile) gasket; and ASTM A449 electroplated steel bolts and nuts. System shall be rated to 300 psi (2065 kPa) with Type K or L Copper Tubing.
 - 1) UL classified in accordance with NSF-61 for potable water service. The system shall meet the low-lead requirements of NSF-372.
 - iv. For copper pipe the gasket shall be potable water grade P compound with a red and blue stripe color code for operating temperatures from 0°F to 180°F.
 - 1) Reference shall always be made to the latest published Victaulic selection guide for gaskets for proper gasket selection for the intended purpose.

- c. Gate Valves: 2-1/2 inches & larger - OS&Y, IBBM flanged, 125 lb. standard solid wedge.
 - i. 2 inches & smaller - bronze solder end, bronze body, solid wedge, rising stem, 200 lb. w.o.g. non-shock. However, use brass valves only on all copper pipe.
- d. Butterfly Valves: Cast brass body to UNS C87850, elastomer pressure responsive seat, aluminum-bronze disc with stainless steel stem. Stem shall be offset from the disc centerline to provide complete 360-degree circumferential seating. Copper-tube dimensioned grooved ends, suitable for working pressures to 300-psig CWP Victaulic Style 608N or approved equal.
- e. Ball Valves: Shut-off valves 2-inches and smaller shall be ball valves. Ball valves shall be 150 lbs, brass or bronze body, standard port, 2 piece body, TFE seats with bronze trim. Ball valves shall be threaded end or solder end, or Vic-Press end as required to accommodate piping. Ball valves shall be as manufactured by Victaulic, Conbraco, Crane, Apollo, Nibco, Watts or engineer approved equal.
- f. Unions: 2-1/2 inches & larger - 150 lb. brass companion flanges.
 - i. 2 inches & smaller - wrought copper, ground joint solder ends; threaded hexagonal stainless steel union with Vic-Press ends, Victaulic P589 or approved equal.
- g. Check Valves: 2-1/2 inches & larger - IBBM, 125 lb. std. flanged bronze swing check, with metal disc; 2-inches and smaller - 125 lb. std. screwed or solder ends.
- h. Globe Valves: 2 inches and smaller, bronze body, bronze trim, rising stem, hand wheel, inside screw, renewable composition disc, solder ends, 150 lb, with back seating capacity.
 - i. 2 inches & larger: IBBM, 150 lb, bronze trim, rising stem, handwheel OS&Y, plug type disc, flanged ends, renewable seat and disc.
 - ii. Globe valves shall be Conbraco, Crane, Nibco, Milwaukee, Watts or approved equal.
- i. Extended Valve Stems: Provide and install round collar type extended valve stems on all valves installed in insulated piping. Valve stem and collar shall be selected to suit insulation thickness and maintain valve handles outside of insulation.
- j. (Alternate): At contractor's option, Viega ProPress pressure seal mechanical fittings may be utilized.
 - i. Viega ProPress, Mueller Streamline PRS or approved equal, Pressure Seal Fittings: Bronze, or copper shall conform to ASME B16.51, ICC LC 1002, IAPMO PS 117, NSF 61, and NSF 61-G or NSF 372. Pressure Seal fittings 1/2-inch thru 4-inch for use with ASTM B88 copper tube type L and 1/2-inch up to 1-1/4-inch annealed copper tube. Pressure Seal fittings shall have an EPDM sealing element grip ring, PBT separator ring, EPDM sealing element and Smart Connect (SC) or Sure PS Leak Detection.

B. Copper pipe shall be Revere, Anaconda or Chase with approved solder fittings.

2.2. PIPE HANGERS, ROLLER SUPPORTS, ANCHORS, GUIDES, AND SADDLES

- A. All hangers for metallic piping shall be adjustable, wrought clevis type, or adjustable malleable split ring swivel type, having rods with machine threads. Hangers shall be Grinnell Company's Figure 260, Carpenter and Patterson, or approved equal for pipe $\frac{3}{4}$ -inch and larger, and Figure 65 for pipe 2-inches and smaller, or approved equal. Adjustable pipe stanchion with U-bolt shall be Grinnell Company's Figure 191. Pipe roller supports shall be Grinnell's Figure 181 or Figure 271. Exterior pipe hangers shall be galvanized or stainless steel construction. For copper piping in direct contact with the hanger, hanger construction shall be copper coated to prevent contact of dissimilar metals similar to Grinnell's Figure CT-65. Hanger spacing and rod sizes for steel and copper pipe shall not be less than the following:

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
$\frac{3}{4}$ & 1	6	5	$\frac{3}{8}$
1 - $\frac{1}{2}$	6	8	$\frac{3}{8}$
2	8	8	$\frac{3}{8}$
2 - $\frac{1}{2}$	10	9	$\frac{1}{2}$
3	12	10	$\frac{1}{2}$
4	14	12	$\frac{5}{8}$
5	14	12	$\frac{5}{8}$

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
6	16	14	3/4

- B. Anchors, guides, and roller supports shall be installed in accordance with the contract drawings and manufacturer's recommendations to provide pipe support and control pipe movement for all piping systems. Anchors and guides shall be securely attached to the pipe support structure. Submit shop drawing for proposed pipe support structure for guides and anchors for approval of the Structural Engineer. Pipe alignment guides shall be Fig. 255 Grinnell, or as approved equal. Guides shall be sized to accommodate the pipe with insulation. Guides shall be steel factory, fabricated, with bolted two section outer cylinder and base for alignment of piping and two section guiding spider for bolting to pipe.
- C. Hangers for pipe sizes ½ to 1 ½ inch (13 to 38 mm): Carbon steel, adjustable swivel, split ring.
- D. Hangers for cold pipe sizes 2 inches (50 mm) and over: Carbon steel, adjustable, clevis.
- E. Hangers for cold pipe sizes 2 to 4 inches (50 to 100 mm): Carbon steel, adjustable, clevis.
- F. Multiple or Trapeze hangers: Steel channels with welded spacers and hanger rods.
- G. Multiple or Trapeze hangers for hot pipe sizes 6 inches (150 mm) and over: Steel channels with welded spacers and hanger rod, cast iron roll.
- H. Wall support for pipe sizes to 3 inches (76 mm): cast iron hook
- I. Wall support for pipe sizes 4 inches (100 mm) and over: Welded steel bracket and wrought steel clamp.
- J. Vertical Support: Steel riser clamp.
- K. Floor support for cold pipe: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
- L. Floor support for hot pipe sizes to 4 inches (100 mm): Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
- M. Copper pipe support: Carbon steel ring, adjustable, copper plated.
- N. Hanger rods: Mild steel threaded both ends, threaded one end, or continuous threaded.
- O. Inserts: Malleable iron case of galvanized steel shell and expander plug for threaded

connection with lateral adjustment, top slot for reinforcing rods, lugs for attaching to forms; size inserts to suit threaded hanger rods.

2.3. VALVES

- A. Provide parts list and assembly drawings (exploded view) for all valves in shop drawing submittals. Provide valves of the same type by the same manufacturer.

2.4. STRAINERS

- A. Strainers shall be of the basket or "Y" type and shall be heavy and durable, constructed of best grade gray iron with the bottoms drilled and plugged. Bodies shall have arrows clearly cast on the sides to show flow direction. Strainers shall be equipped with easily removable covers and brass sediment baskets made of brass not less than #22 gauge in thickness. Total area of basket perforations shall be not less than four times the cross section of the entering pipe. Flow shall be into basket, and then out through the perforations. Strainers shall be suitable for water or the intended fluid. Strainers 2 inches and smaller shall have threaded or solder ends, 2 inches and larger shall have flanged ends.
- B. Strainer screens shall be stainless steel with perforations and shall be 1/16-inch for pipe sizes 5 inches and less, 1/8-inch (40 percent open area) perforations for pipe sizes 6-inch and greater.
- C. Provide valved and capped (with chain) blowdowns in each strainer. Blowdown valves shall be Appolo 78-100/200 series or as approved equal.
- D. Strainers shall be manufactured by Watts, Mueller, Armstrong, Yarway, Spirax/Sarco or as approved equal.

2.5. UNIONS, FLANGES, AND COUPLINGS

- A. Unions in steel pipe 2-inches and smaller shall be malleable iron with brass inserted seats designed for a working pressure of 150 psig.
- B. Unions in copper pipe 2-inches and smaller shall be sweat fittings with bronze seats designed for a working pressure of 125 psig.
- C. Flanges for steel pipe over 2 inches shall be 150 psig, forged steel, and slip on type. Gaskets shall be 1/16 inch thick pre-formed neoprene.
- D. Flanges for copper pipe over 2 inches shall be bronze. Gaskets shall be 1/16 inch thick preformed neoprene.

2.6. MANUAL AIR VENTS

- A. Manual air vents shall be similar to the hereinafter specified gauge valves. Provide 1/4-inch size on 3/4-inch pipe and smaller, 1/2 -inch size on 1-inch pipe and larger. Install at all high points of piping. Valves shall be Crane No. 88, Honeywell or as approved equal, with threaded ends, bronze body, bronze or brass bonnet and bronze stem.

2.7. THERMOMETERS

- A. Unless otherwise indicated, thermometers shall be ASTM E1, in a glass type, organic filled, 9-inch scale size, corrosion-resistant metal case, with "any-angle" mounting with positive locking device. Terice Industrial Thermometers, Weksler Instruments, Ernst Gage Co., Miljoco, or approved equal. Insertion stem length shall suite the pipe size and configuration. Thermometer wells shall be brass with brass union hubs in copper and in ferrous piping. Where piping is insulated or otherwise covered, use wells with lagging extension. Where wells are installed in pipe tees at turns, increase pipe size so that well does not restrict flow. Accuracy shall be 2 percent.
- B. Unless otherwise indicated, thermometer ranges shall be as follows:
 - 1. Domestic cold water: 0 degrees F to 100 degrees F, 1 degrees F Division.
- C. Provide heat conducting compound in wells.

2.8. PRESSURE GAUGES

- A. Unless otherwise indicated, pressure gauges shall be the bronze bourdon tube type, 4-1/2-inch dial, stem mounting, cast aluminum adjustable pointer, 1 percent accuracy over middle half of scale range, 1-1/2 percent over balance: Terice Model 600C; Weksler Instruments, Ernst Gage Co., Miljoco, or as approved equal.
- B. Gauges shall have pressure, vacuum, compound, or retard ranges as required, select ranges so that the normal readings are at the approximate midpoint and maximum system pressures do not exceed full scale.
- C. Furnish and install a gauge valve at each pressure gauge. Gauge valves shall be Crane Model No. 88, Needle Valve, Ernst Gage Co. FLG 200, Wexler Instrument Corp. Type BBV4, or approved equal, rated for pressure intended.
- D. Gauge connections for pressure gauges, thermometers, or control instruments shall be made using tee fittings, except that gauge connections up to 1-inch size in steel may be using threaded extra heavy pipe couplings welded directly to the main, provided that the main is at least 2-inch size for 2-inch connections, 3-inch size for 3/4-inch connections, and 4-inch size for 1-inch connections. Minimum gauge connection shall be 2-inch ips.
- E. Provide snubbers on all gauges. Snubbers shall be No. 872 by Terice, RS1/RS6 by Wexler Instruments, Miljoco or as approved equal.

2.9. PIPING SPECIALTIES

- A. Furnish and install flexible pipe connections, as specified and/or shown on the drawings at all vibrating equipment and elsewhere as shown. Refer to Division 23 Section, Vibration Control for HVAC and Plumbing Equipment for specifications.
- B. Pressure relief valves shall be provided in the number and sizes required to relieve 110 percent of the full input to the systems. Valves shall be rated; and installed in accordance with ASME, and CSD-1 including all amendments. Pipe discharge full size to floor drain, (with union) and support discharge pipe to prevent exerting any strain on relief valve body,

piping to be Type-L copper. Water safety relief valves shall be Watts Series 740, Conbraco, Series 154A, Bell and Gossett, or approved equal. Provide pressure gauge adjacent to all safety relief valves.

2.10. ESCUTCHEONS

- A. Provide chromium plated escutcheons properly fitted and secured with set screws on all exposed piping which passes through walls, floors or ceilings of finished spaces.
- B. All escutcheon plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface. Plastic escutcheon plates will not be accepted.

2.11. DIELECTRIC CONNECTIONS:

- A. Furnish and install electrically insulated dielectric unions, waterway fittings, or flanges, as manufactured by Victaulic Company, EPCO Sales, Inc., at the following locations:
 - 1. Where steel piping systems join copper piping.
 - 2. Where copper tube connects to domestic water storage tanks, water heaters, heat exchangers, expansion tanks, and other steel vessels.
 - 3. Avoid the installation of steel nipples, cast iron or steel valves and specialties, or other ferrous components in predominately copper piping systems. Where such installation is necessary, isolate the component with dielectric connections. Do not mix steel pipe and copper tube in the same run of pipe or in the same section of a piping system.
 - 4. Dielectric Waterway: Copper silicon casting conforming to UNS C87850 with grooved and/or threaded ends. UL classified in accordance with NSF-61 for potable water service, and shall meet the low lead requirements of NSF-372. Basis of Design: Victaulic Series 647.

2.12. SLEEVES

- A. Sleeves shall be provided around all pipes through walls, floors, ceilings, partitions, roof structure members or other building parts. Sleeves shall be standard weight galvanized iron pipe two sizes larger than the pipe or insulation so that pipe or insulation shall pass through masonry or concrete walls or floors. Provide 20 gauge galvanized steel sheet or galvanized pipe sleeves for all piping passing through frame walls.
- B. Sleeves through floors shall be flush with the floor except for sleeves passing through Equipment Rooms which shall extend ¾-inch above the floor. Refer to Division 23 Section, Vibration Controls for HVAC and Plumbing Equipment for mechanical equipment room penetrations additional requirements. Space between the pipe and sleeve shall be caulked. Escutcheon plates shall be constructed to conceal the ends of sleeves. Each trade shall be responsible for drilling existing floors and walls for necessary sleeve holes. Drilling methods and tools shall be as hereinbefore specified.
- C. Sleeves through walls and floors shall be sealed with a waterproof caulking compound.

- D. Firestop at sleeves that penetrate smoke barriers smoke partitions and/or rated walls/floors.

2.13. PRESSURE REDUCING VALVES

- A. Provide pressure reducing valves as indicated, of size and capacity selected by the installer to maintain operating pressure on the system. Body shall be cast-iron or bronze construction, renewable stainless steel seat, non-corrosive disc, water tight cage assembly, adjustable pressure ranges and inlet strainer Watts Regulator Model 223-S, Armstrong, Bell and Gossett or as approved equal.
- B. Provide pressure gauge adjacent to all pressure reducing valves to verify proper set point.

2.14. WATER PROOF PIPE PENETRATION SEALS

- A. Provide and install waterproof pipe penetration seals at all pipes that enter the building below grade or through exterior wall.
- B. Link seals are to be Metraflex Metraseals, Model MS, Linkseal, or approved equal, black EPDM seal material, glass reinforced plastic pressure plates, zinc plated nuts and bolts, seals are to be resistant to sunlight and ozone, pressure rated to make a hydrostatic seal of up to 20 psig and up to 40 feet of head, temperature rated from -40 degrees F to 250 degrees F.

2.15. TRANSITION FITTINGS

- A. General Requirements:
 - 1. Same size as pipes to be joined.
 - 2. Pressure rating at least equal to pipes to be joined.
 - 3. End connections compatible with pipes to be joined.
- B. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.
- C. Plastic-to-Metal Transition Fittings:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Charlotte Pipe and Foundry Company.
 - b. Harvel Plastics, Inc.
 - c. Spears Manufacturing Company.
 - 2. Description: PVC or CPVC one-piece fitting with manufacturer's Schedule 80 equivalent dimensions; one end with threaded brass insert and one solvent-cement-socket end.
- D. Plastic-to-Metal Transition Unions:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one

of the following:

- a. Colonial Engineering, Inc.
 - b. NIBCO INC.
 - c. Spears Manufacturing Company.
2. Description: PVC or CPVC four-part union. Include brass threaded end, solvent-cement-joint plastic end, rubber O-ring, and union nut.

PART 3. EXECUTION

3.1. GENERAL PIPING INSTALLATION REQUIREMENTS

- A. All pipes shall be cut accurately to measurements established at the building, and shall be worked into place without springing or forcing, properly clearing all windows, doors and other openings. Excessive cutting or other weakening of the building structure to facilitate piping installation will not be permitted. All pipes shall be so installed as to permit free expansion and contraction without causing damage. All open ends of pipe lines, equipment, etc., shall be properly capped or plugged during installation to keep dirt or other foreign material out of the system. All pipes shall be run parallel with the lines of the building and as close to walls, columns and ceilings as may be practical, with proper pitch. All piping shall be arranged so as not to interfere with removal of other equipment on devices not to block access to doors, windows, manholes, or other access openings. Flanges or unions, as applicable for the type of piping specified, shall be provided in the piping at connections to all items of equipment, coils, etc., and installed so that there will be no interference with the installation of the equipment, ducts, etc. All valves and specialties shall be placed to permit easy operation and access and all valves shall be regulated, packed and glands adjusted at the completion of the work before final acceptance. All piping shall be installed so as to avoid air or liquid pockets throughout the work. Ends of pipe shall be reamed so as to remove all burrs.
- B. All piping shall be graded to convey entrained air to high points where automatic air vents shall be provided. The size of supply and return pipes for each piece of equipment shall in no case be smaller than the outlets in the equipment.
- C. All piping shall be run to provide a minimum clearance of 2-inches between finished covering on such piping and all adjacent work. Group piping wherever practical at common elevations.
- D. All valves, strainers, caps, and other fittings shall be readily accessible.
- E. Rough-in and final connections are required to all equipment provided under this Contract.
- F. Drain valves with hose connections shall be provided at low points for drainage of piping systems. Blow down valves shall be provided at the ends of all mains and branches so as to properly clean by blowing down the lines throughout in the direction of normal flow.
- G. Discharge lines from all relief valves shall be piped to within 4-inches of floor and extend to floor drains wherever floors are not pitched to drains. Pitch the relief valve piping away from the relief valve to issue that no fluid can be trapped in valve discharge. Support all relief valve piping to prevent exerting strain on the relief valve body. The end of the relief

valve discharge piping shall not be threaded to prevent capping or plugging.

- H. All branches from water mains shall be taken from the top of the supply mains at an angle of forty-five (45) degrees above the horizontal, unless otherwise directed. Branches feeding down shall be taken from the side or bottom of the main on water mains only. All connections shall be carefully made to insure unrestricted circulation, eliminate air pockets or trapped condensate, and permit the complete drainage of the system.
- I. Cutoff valves shall be provided on each branch line from the mains on all plumbing lines.
- J. Shut-off valves shall be installed at the inlet and outlet of each piece of equipment to permit isolation for maintenance and repair.
- K. Unions shall be installed on all bypasses, at all connections to equipment, where shown on drawings or where required to facilitate removal of equipment whether shown or not.
- L. Spring clamp plates (escutcheons) shall be provided where pipes are exposed in the building and run through walls, floors, or ceilings. Plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface.
- M. If the size of any piping is not clearly evident in the drawings, the Contractor shall request instructions for the Engineer as to the proper sizing. Any changes resulting from the Contractor's failure to request clarification shall be at his expense. Where pipe size discrepancies or conflicts exist in the drawings, the larger pipe size shall govern.
- N. Install all valves with stem upright or horizontal, not inverted.
- O. Where pipe support members are welded to structural building framing, scrape, brush clean, weld and apply one coat of zinc rich primer.
- P. Provide clearance for installation of insulation and access to valves and fittings.
- Q. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed system.
- R. All water containing pipes shall be routed clear of combustion air dampers and louvers to prevent freezing condition when dampers are open.
- S. Provide manual air vents at top of piping systems.
- T. Install Schrader valves with ball valves to allow all domestic water to be blown out with compressed air for wintertime freeze protection.
- U. Where access doors are required, install piping so that valves can be grouped together to minimize the quantity of access doors.

3.2. THERMOMETER AND PRESSURE GAGE INSTALLATION REQUIREMENTS.

- A. Install thermometers and adjust vertical and tilted positions.
- B. Install separable sockets in vertical position in piping tees where fixed thermometers are indicated.

1. Install with socket extending to one-third diameter of pipe.
2. Fill sockets with oil or graphite and secure caps.
- C. Install pressure gages in piping tees with pressure-gage valve located on a pipe at most readable location.
- D. Adjust faces of thermometer and gages to proper angle for best visibility.
- E. Clean windows of thermometer and gauges and clean factory-finished surfaces. Replace cracked and broken window, and repair scratched and marred surfaces with manufacturer's touch up paint.

3.3. VALVE INSTALLATION REQUIREMENTS

- A. Examine piping system for compliance with requirements for installation tolerances and other conditions affecting performance of valves. Do not proceed with installation until unsatisfactory conditions have been corrected.
- B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- C. Operate valves from fully open to fully closed positions. Examine guides and seats made accessible by such operation.
- D. Examine threads on valve and mating pipe for form and cleanliness.
- E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Check gasket material for proper size, material composition suitable for service, and freedom from defects and damage.
- F. Examine grooved ends for form and cleanliness. Grooved ends shall be clean and free from indentations, projections, and roll marks in the area from pipe end to groove.
- G. Do not attempt to repair defective valves; replace with new valves.
- H. Install valves as indicated, according to manufacturer's written instructions.
- I. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate the general arrangement of piping, fittings, and specialties.
- J. Install valves with unions or flanges at each piece of equipment arranged to allow servicing, maintenance, and equipment removal without system shutdown.
- K. Locate valves for easy access and provide separate support where necessary.
- L. Install valves in horizontal piping with stem at or above the center of the pipe.
- M. Install valves in a position to allow full stem movement.
- N. Adjust or replace packing after piping systems have been tested and put into service, but

before final adjusting and balancing. Replace valves if leak persists.

3.4. PIPE JOINTS INSTALLATION REQUIREMENTS

- A. Grooved Joints: Grooved joint shall be installed in accordance with the manufacturer's written recommendations. Grooved ends shall be clean and free from indentations, projections, or roll marks. The gasket shall be molded and produced by the coupling manufacturer of an elastomer suitable for the intended service. The coupling manufacturer's factory trained representative shall provide on-site training for the contractor's field personnel in the use of grooving tools and installation of product. The representative shall periodically visit the job site to ensure best practices in grooved product installation are being followed. (A distributor's representative is not considered qualified to conduct the training.)
- B. Screwed Joints: All screwed joints shall be made with tapered threads properly cut. Screwed joints shall be made perfectly tight with a stiff mixture of graphite and oil, applied with a brush to the male threads on the fittings.
- C. Soldered Joints and Copper Piping: Joints in copper piping shall conform to the following minimum standards.
 - 1. The pipes shall be cut to a length making certain that the ends are square, using a fins hacksaw blade or tube cutter. The ends of all pipes shall be reamed and all burrs removed.
 - 2. The outside end of the pipe and the cut end of the fitting shall be cleaned with steel wool, sand cloth, or steel wire brush. All dark spots shall be removed.
 - 3. The flux shall be applied evenly and sparingly to the outside end of the pipe and the inside of the outer end of the fitting until all surfaces to be jointed are completely covered. The piping and fitting shall be slipped together and reworked several times to insure an even distribution of the flux.
 - 4. The correct amount of solder per joint for each size pipe shall be used in accordance with the manufacturer's recommendations.
 - 5. Solder joints shall be made by using a direct flame from a torch.
 - 6. On pipe sizes larger than 1/4-inch, the fittings and valves in the pipe shall be moved or tapped with a hammer when the solder starts to melt to insure an even distribution of the solder.
 - 7. The excess solder shall be removed while it is still in the plastic state leaving a fillet around the cup of the fitting.
 - 8. Solder joints shall be suitable for working pressure of 100 psig and for working temperature of not less than 250 degrees F. The type of solder and flux used will be submitted for approval. Type 95-5 shall be the minimum standard.
 - 9. Lead and antimony-based solders shall not be used for potable water systems. Brazing and silver solders are acceptable.

- D. Where copper piping joins steel piping, approved bronze adapters shall be used.
- E. Prohibited Connections: No direct weld, soldered, or brazed connections, without unions or flanges, shall be made to valves, strainers, apparatus, or related equipment. Right and left couplings, long threads, or caulking of pipe threads or gasket joints will not be permitted.
- F. Plastic piping solvent cement joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:
 - 1. Comply with ASTM F 402 for safe handling practice of cleaners, primers, and solvent cements. Apply primer.
 - 2. PVC Piping: Join according to ASTM D2855.

3.5. HANGERS AND SUPPORTS INSTALLATION REQUIREMENTS

- A. General: All hangers shall be of an approved type arranged to maintain the required grading and pitching of lines to prevent vibration and to provide for expansion and contraction. Provide protection saddles between hangers and insulation on heating water insulated pipe. Saddles shall be Victaulic, Grinnells Figure 173/273, Sure-Joint, or approved equal. Provide approved spacers between saddles and pipe where flexible insulation is specified. Provide insulation protection shields for insulated piping without saddles. Shields shall be Carpenter Patterson, Grinnell Figure 167 or as approved equal.
- B. Spacing: Regardless of spacing, hangers shall be provided at or near all changes in direction, both vertical and horizontal, for all piping. For cast iron soil pipe, one hanger shall be placed at each hub or bell.
- C. Vertical Lines: Shall be supported at their bases, using either a suitable hanger placed in a horizontal line near the riser, or a base type fitting set on a pedestal, foundation or support. All vertical lines extending through more than one floor level shall be supported at each floor with a riser clamp. Riser clamp shall be Carpenter Patterson, Grinnell Co.'s Figure 261, or approved equal. All vertical drops to pump suction elbows shall be supported by floor posts.
- D. Racks and Brackets: All horizontal piping on vertical walls shall be properly supported by suitable racks securely anchored into the wall construction. Where not practical to obtain ceiling anchorage, all piping near walls shall be supported by approved brackets securely anchored into the wall construction. Washer plates (Fib. 60, 60L) and other miscellaneous attachments, fasteners, etc., shall be Carpenter Patterson, Grinnell or as approved equal. All exterior hanger and bracket systems in their entirety shall be galvanized.
- E. Pipe Hangers and supports shall be attached to the panel point at the top chord of bar joist or at a location approved by the engineer.
- F. Select hangers and components for loads imposed. Secure rods with double nuts.
- G. Support of horizontal piping shall allow for vertical adjustment after installation of piping.
- H. Support overhead piping with clevis hangers.

- I. Do not support all parallel piping from the same joist. Stagger all supports in accordance with the engineer's recommendations.

3.6. AIR VENTING INSTALLATION REQUIREMENTS

- A. The top of each plumbing piping system and other points as indicated or where necessary for the removal of air from the system or equipment, shall be vented using an approved type of manual air vent.
- B. In addition to manual air vents at high points of system, each item of water heat transfer equipment shall be manually vented using an approved type manual air vent. All air vents shall be accessible.

3.7. EXPANSION LOOPS AND SWING CONNECTION INSTALLATION REQUIREMENTS

- A. Connect risers and branch connections to mains with at least five pipe fittings, including tee in main.
- B. Connect risers and branch connections to plumbing equipment with at least four pipe fittings, including tee in riser.
- C. Connect mains and branch connections to plumbing equipment with at least four pipe fittings, including tee in main.

3.8. PIPING IDENTIFICATION REQUIREMENTS

- A. All piping shall be identified with painted background marked with the name of the service with arrows to indicate flow direction. Color code and system identification shall comply with ANSI Standards and piping identification system shall comply with ASME A13.1-81., scheme for the identification of piping systems and ASHRAE Fundamentals Handbook, latest edition.
- B. Markings shall be plain block letters, stenciled on pipes, and shall be located near each branch connection, near each valve, and at least every 10 feet on straight runs of pipe. Where pipes are adjacent to each other, markings shall be neatly lined up. All markings shall be located in such manner as to be easily legible from the floor. Pipe identification schedule shall be as follows:

OUTSIDE DIAMETER OF PIPE OR COVERING (INCHES)	LENGTH OF COLOR FIELD (INCHES)	SIZE OF LETTERS (INCHES)
$\frac{1}{2}$ to 1 $\frac{1}{4}$	8	$\frac{1}{2}$
1- $\frac{1}{2}$ to 2	8	$\frac{3}{4}$
2 $\frac{1}{2}$ to 6	12	1 $\frac{1}{4}$
8 to 10	24	2 $\frac{1}{2}$

Over 10	32	3 ½

3.9. VALVE IDENTIFICATION REQUIREMENTS

- A. All valves shall be tagged with a numbered tag.
- B. The tags shall be made of 1-inch diameter brass tags fastened to the valve by means of brass chains. Numbers shall agree with valve numbers on diagrammatic herein before specified.
- C. Provide a minimum of three (3) valve charts with valve numbers indicating valve type, size, manufacturer and service.
- D. Additional valve charts shall be mounted behind glazed wooden frames and be hung in each mechanical equipment room including each air handling unit mechanical equipment room. Additional copies shall be provided in each copy of the O&M manuals.

3.10. CLEANING PIPING AND EQUIPMENT REQUIREMENTS

- A. All water and plumbing piping systems shall be cleaned by filling with a solution of one (1) pound of trisodium phosphate to each 50 gallons of water and circulating this solution for a period of six (6) hours during which time the system shall reach operating temperature. The systems shall then be flushed with fresh water and refilled with fresh water purged of all air.
- B. All water piping system shall be flushed clean with fresh water. See Division 22 Sections, Plumbing Fixture and Plumbing Equipment for domestic potable water cleaning and sterilization.

3.11. PRESSURE SEAL FITTING INSTALLATION REQUIREMENTS

- A. Viega, ProPress Pressure Seal bronze, Mueller Streamline, or approved equal or copper fittings: Sealing element shall be verified for the intended use. Tube ends shall be cut on a right angle (square) to the tube. Tube ends shall be reamed and chamfered, all grease oil or dirt shall be removed from the tube end with a clean rag. Visually examine the fitting sealing element to ensure there is no damage, and it is properly seated into the fitting. Utilizing a Viega Insertion Depth Inspection Gauge mark the tube wall, with a felt tip pen, at the appropriate location, or insert the tube fully into the fitting and mark the tube wall at the face of the fitting. Always examine the tube to ensure it is fully inserted into the fitting prior to pressing the joint. ProPress fittings shall be installed according to the most current edition of the Viega installation guidelines. Installers shall attend a Viega ProPress installation training class.
- B. After ProPress, Mueller Streamline, or approved equal. Pressure seal fittings have been installed a "two step test" shall be followed. Pressurize the system with application appropriate test medium, water between 15 and 85 psi, or air/dry nitrogen between .5 and 45 psi. Check the pressure gauge for pressure loss. If the system does not hold pressure, walk the system and check for un-pressed fittings. Should you identify an un-pressed ensure the tube is fully inserted into the fitting and properly marked, prior to pressing the joint. After appropriate repairs have been made, retest the system per local code, or

specification requirements, not to exceed 600 psi with water or 200 psi when using air.

END OF SECTION

DIVISION 22 SECTION 22 07 01
PLUMBING INSULATION
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. REFERENCE	3
1.2. DESCRIPTION	3
1.3. SCOPE.....	3
1.4. STANDARDS	3
1.5. SYSTEM PERFORMANCE	4
1.6. QUALITY ASSURANCE	4
1.7. DELIVERY AND STORAGE OF MATERIALS	4
1.8. ALTERNATES	5
PART 2. PRODUCTS.....	5
2.1. GENERAL.....	5
2.2. PIPE INSULATION MATERIALS	5
2.3. PIPING INSULATION THICKNESSES SCHEDULE	8
2.4. EQUIPMENT INSULATION MATERIALS AND THICKNESSES.....	8
2.5. ACCESSORY MATERIALS	9
2.6. FIELD-APPLIED JACKET	9
PART 3. EXECUTION.....	10
3.1. WORKMANSHIP	10
3.2. SITE INSPECTION.....	10
3.3. PREPARATION.....	11
3.4. INSTALLATION	11
3.5. FIELD QUALITY ASSURANCE.....	13
3.6. PROTECTION	13
3.7. SAFETY PRECAUTIONS.....	13
3.8. INSULATION COVERING.....	13
END OF SECTION	14

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 22 07 01 - PLUMBING INSULATION

PART 1. GENERAL

1.1. REFERENCE

- A. The Conditions of the Contract and other General Requirements apply to the work specified in this Section. All work under this Section shall be subject to the requirements of Division 22 Section, Common Work Results for Plumbing.
- B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section

1.2. DESCRIPTION

- A. All piping and equipment installed under this Contract shall be covered as specified.

1.3. SCOPE

- A. The work covered by this specification consists of furnishing all labor, equipment, materials and accessories, and performing all operations required, for the correct fabrication and installation of thermal insulation applied to all piping, equipment, and systems, in accordance with applicable project specifications and drawings, subject to the terms and conditions of the contract.

1.4. STANDARDS

- A. Thermal insulation materials shall meet the property requirements of one or more of the following specifications as applicable to the specific product or use:
 - 1. American Society for Testing of Materials Specifications:
 - a. ASTM C 547, "Standard Specification for Mineral Fiber Preformed Pipe Insulation".
 - b. ASTM C 533, "Standard Specification for Calcium Silicate Pipe & Block Insulation".
 - c. ASTM C 55, "Standard Specification for Mineral Fiber Blanket and Felt Insulation".
 - d. ASTM E 96, "Standard Test Methods for Water Vapor Transmission of Materials".
 - e. ASTM C 585, "Recommended Practice for Inner and Outer Diameters of Rigid Pipe Insulation for Nominal Sizes of Pipe and Tubing (NPS System)".
 - f. ASTM C 612, "Standard Specification for Mineral Fiber Block and Board Thermal Insulation".
 - g. ASTM C 1136, "Standard Specification for Barrier Material, Vapor, "Type 1 or 2 (Jacket only)".
 - h. ASHRAE 90.1 "Energy efficient design of new buildings except low-rise residential buildings", latest edition.
- B. Insulation materials, including all weather and vapor barrier materials, closures, hangers,

supports, fitting covers, and other accessories, shall be furnished and installed in strict accordance with project drawings, plans, and specifications.

1.5. SYSTEM PERFORMANCE

- A. Insulation materials furnished and installed hereunder should meet the minimum economic insulation thickness requirements of the North American Insulation Manufacturers' Association (NAIMA) (formerly known as TIMA), to ensure cost-effective energy conservation performance. Alternatively, materials should meet the minimum thickness requirements of National Voluntary Consensus Standard 90.1, (latest edition) and "Energy Efficient Design of New Buildings," of the American Society of Heating, Refrigeration, and Air-Conditioning Engineers (ASHRAE), latest edition. However, if other factors such as condensation control or personnel protection are to be considered, the selection of the thickness of insulation should satisfy the controlling factor. As minimum, all insulation thicknesses shall be as hereinafter specified.
- B. Insulation materials furnished and installed hereunder shall meet the fire hazard requirements of any one of the following specifications:
 - 1. American Society for Testing of Materials ASTM E 84
 - 2. Underwriters' Laboratories, Inc. UL 723
 - 3. National Fire Protection Association NFPA 255
- C. Calcium silicate products shall include a visual identification system to permit positive field determination of their asbestos-free characteristics.

1.6. QUALITY ASSURANCE

- A. Insulation materials and accessories furnished and installed hereunder shall, where required, be accompanied by manufacturers' current submittal or data sheets showing compliance with applicable specifications listed in Section 1.4 above.
- B. Insulation materials and accessories shall be installed in a workmanlike manner by skilled and experienced workers who are regularly engaged in commercial insulation work.

1.7. DELIVERY AND STORAGE OF MATERIALS

- A. All of the insulation materials and accessories covered by this specification shall be delivered to the job site and stored in a safe, dry place with appropriate labels and/or other product identification.
- B. The Contractor shall use whatever means are necessary to protect the insulation materials and accessories before, during, and after installation. No insulation material shall be installed that has become damaged in any way. The Contractor shall also use all means necessary to protect work and materials installed by other trades.
- C. If any insulation material has become wet because of transit or job site exposure to moisture or water, the Contractor shall not install such material, and shall remove it from the job site. An exception may be allowed in cases where the Contractor is able to demonstrate

that wet insulation when fully dried out (either before installation, or afterward following exposure to system operating temperatures) will provide installed performance that is equivalent in all respects to new, completely dry insulation. In such cases, consult the insulation manufacturer in writing for technical assistance.

- D. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cements. Protect all insulation from water, construction traffic, dirt, chemical and mechanical damage.

1.8. ALTERNATES

- A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

PART 2. PRODUCTS

2.1. GENERAL

- A. All materials to be insulated shall be thoroughly cleaned, after completion of successful tests, and shall be covered as specified below. Fiberglass insulation shall be Owens-Corning, Manville, Armstrong, or P.P.G, or as approved equal.

2.2. PIPE INSULATION MATERIALS

- A. Unless otherwise noted, insulation shall be one piece or half sectional molded fibrous glass with "K" rating of .23 at 75 degrees F mean temperature, for service temperatures between -60 degrees F and +450 degrees F with all service poly-encapsulated jacket. Pipe insulation shall be fiberglass ASJmax SSL II with double closure system as manufactured by Owens Corning, Johns Manville, Knauf or approved equal.
- B. Unless otherwise noted, pipe insulation jacket shall be factory-applied vinyl coated, embossed and reinforced vapor barrier laminate, with a perm rating of not more than 0.02 perms. All hot and cold, concealed, and exposed butt strips shall be of the same material as the jacket. Jacket and butt strips shall be sealed with field-applied Foster 85-20/85-50 or Childers CP-82 (5 gallon cans only) adhesive. Jacket and butt strips shall be off-white color and shall be equivalent to Owens-Corning Fiberglass 25-ASJ, Johns Manville, Knauf, or approved equal.
- C. For fittings on all piping, valves, and flanges, apply fiberglass molded or segmented insulation equal in thickness to the adjoining insulation and securely fasten in place using wire. Cold piping: Apply a tack coat of vapor barrier coating and reinforcing mesh. After ½ hour, apply second coat of same vapor barrier coating, UL labeled, Type C, for cold water piping. Hot piping, Type H for hot water piping: Apply tack of breather mastic. Wrap fitting with fiberglass reinforcing cloth overlapping adjoining sections of pipe insulation by 2-inches. Apply a second coat of breather mastic over the reinforcing cloth, working it to a smooth finish. As an option to the above hot fittings, a polyvinyl chloride fitting cover may be supplied.
- D. All pipe insulation, jackets, or facings, and adhesives used to adhere jacket or facing to the insulation, including fittings and butt strips, shall have non-combustible fire and smoke hazard system rating and label as tested by ASTM E-84, NFPA 225, and UL 73, not

exceeding Flame Spread 25, Fuel Contributed 50, Smoke Developed 50. Accessories such as adhesives, mastic cements, tapes and cloth for fittings shall have the same ratings as listed above. All products or their shipping cartons shall bear the Underwriter's label indicating that flame and smoke ratings do not exceed the above criteria.

- E. For piping having a vapor barrier insulation and for all insulated piping requiring supports, hangers and supports shall be installed outside the insulation. Wherever hangers and supports are installed outside the insulation, pipe insulation protecting shields shall be provided. Where insulation is a load bearing material, of sufficient strength to support the weight of the piping, pipe shields one-third the circumference of the insulation and of a length not less than three times the diameter of the insulation (maximum length 24-inches) shall be provided. Insulation of 7-1/4 pound or greater density will be considered as load bearing for pipe sizes up to and including 2-inches. Where insulation is not of sufficient strength to support the weight of the piping, a half section of high density fiberglass or foam inserts, shall be provided. Vapor barrier and finish shall be applied as required to match adjoining insulation. In addition, shields shall be furnished as specified above.
- F. For piping located outside of the building, a corrugated aluminum weatherproof jacketing system shall be provided. This system shall be Micro-Lot ML as manufactured by Manville, Polyweld by Pabco Metals Corp., Childers, or as approved equal, and installed per the manufacturer's recommendations. Where outdoor piping is receiving electric heat tape, the insulation shall be oversized so that the heat tape is not compressed tightly to the pipe. Pipe jacketing shall be corrugated (3/16-inch) deep aluminum, .016-inch thickness of H-14 temper with aluminum strapping of .75-inch width and .020 inch thickness with moisture barrier. Aluminum jacketing elbows shall be smooth, .016-inch thickness and 1100 alloy. All jacketing shall have an integrally bonded moisture barrier over the entire surface in contact with the insulation. Longitudinal joints shall be applied so they will shed water and shall be sealed completely and shall be sealed completely with metal jacketing sealant. Sealant shall be Foster 95-44 or Childers CP-76. Circumferential joints shall be closed using preformed butt strips following manufacturer's recommendations for securement. Jacket seams shall be located on the bottom side of the horizontal piping.
- G. All disturbed piping insulation in existing areas shall be re-insulated with insulation type, density, and thickness as specified for new piping. Insulation damaged due to new work and demolition only shall be replaced unless otherwise noted.
- H. On cold systems such as domestic cold water, vapor barrier performance is extremely important. All penetrations and seams of the ASJ and exposed ends of insulation must be sealed with vapor barrier coating. The ASJ must be protected with either a vapor barrier coating or a suitable vapor retarding outer jacket. Vapor seals at butt joints shall be applied at every fourth pipe section joint and at each fitting to provide isolation of water incursion. Vapor Barrier Coating: Foster 30-65; Childers CP-34 or Vimasco 749. Permeance shall be 0.03 perms or less at 45 mils dry at test by ASTM E96.
- I. Fittings and valves shall be insulated with pre-formed fiberglass fittings, fabricated sections of Fiberglass pipe insulation, Fiberglass pipe and tank insulation, Fiberglass blanket insulation, or insulating cement. Thickness shall be equal to adjacent pipe insulation. Finish shall be with pre-formed PVC fitting covers or as otherwise specified on contract drawings. Where applicable, grooved joint PVC fitting valve and coupling covers shall be utilized. Grooved joint PVC covers shall be installed with matching pipe insulation jacketing material, vinyl tape, solvent weld adhesive and appropriate fasteners.

1. Flanges, couplings and valve bonnets shall be covered with an oversized pipe insulation section sized to provide the same insulation thickness as on the main pipe section. An oversized insulation section shall be used to form a collar between the two insulation sections with low density blanket insulation being used to fill gaps. Jacketing shall match that used on straight pipe sections. Rough cut ends shall be coated with a suitable weather or vapor-resistant mastic as dictated by the system location and service. Finish valve installation with a Tyvac jacket with ends that secure to adjacent piping.
 2. On hot systems where fittings are to be left exposed, insulation ends should be beveled away from bolts for easy access.
 3. On cold systems, particular care must be given to vapor sealing the fitting cover or finish to the pipe insulation vapor barrier. All valve stems must be sealed with caulking which allows free movement of the stem but provides a seal against moisture incursion. All gauge and thermometer penetrations and extensions shall be correctly sealed and insulated to prevent surface condensation.
- J. All piping shall be supported in such a manner that neither the insulation or the vapor/weather barrier is compromised by the hanger or the effects of the hanger. In all cases, hanger spacing must be such that the circumferential joint may be made outside the hanger. On cold systems, vapor barrier must be continuous, including material covered by the hanger saddle.
1. Piping systems 3-inches (7.5cm) in diameter or less, insulated with Fiberglass insulation, may be supported by placing saddles of the proper length and spacing, as designated in Owens-Corning Pub. 1-IN-12534, under the insulation. Hangers saddles shall be minimum 16 gauge with a saddle arc of 120 degrees minimum.
 2. For hot or cold piping systems larger than 3-inches (7.5 cm) in diameter, operating at temperatures less than +200 degrees F (93 degrees C) and insulated with fiber glass, high density inserts such as foam with sufficient compressive strength shall be used to support the weight of the piping system. At temperatures exceeding + 200 degrees F (93 degrees C), Owens-Corning Pink or IIG, Calcium Silicate pipe insulation shall be used for high density inserts.
 3. Owens-Corning Pink Calcium Silicate pipe insulation may be used to support the entire weight of the piping system provided the hanger saddle is designed so the maximum compressive load does not exceed 100 psi (7kg/cm).
 4. Where pipe shoes and roller supports are required, insulation shall be inserted in the pipe shoe to minimize pipe heat loss. Where possible, the pipe shoe shall be sized to be flush with the outer pipe insulation diameter.
 5. Thermal expansion and contraction of the piping and insulation system shall generally be taken care of by utilizing double layers of insulation and staggering both longitudinal and circumferential joints. Where long runs are encountered, expansion joints may be required where single layers of insulation are being used and should be so noted on the contract drawings.
 6. On vertical runs, insulation support rings shall be used.

2.3. PIPING INSULATION THICKNESSES SCHEDULE

- A. All piping shall be insulated with pipe insulation of the thicknesses indicated below:

PIPING INSULATION THICKNESS SCHEDULE SERVICES	THICKNESS
All Domestic Cold Water Piping	1-inch thickness
Exterior Chemical Treatment Piping	1-inch thickness

2.4. EQUIPMENT INSULATION MATERIALS AND THICKNESSES

- A. The following equipment shall be insulated with Fiberglass Rigid Board Insulation or Foam Plastic Insulation:
1. All Pump Volute and Strainers.
 2. Backflow Preventer Valve Bodies.
 3. Exterior Chemical Feed Tanks.
 4. Domestic Water Meters.
 5. Make-up Water Valve Bodies.
 6. Make-Up Water Meters.
 7. Motorized Ball Valve Bodies.
 8. Plumbing Pumps.
 9. Cooling tower/closed circuit evaporative fluid cooler makeup water meter and motorized ball valves.
- B. Insulation for cold surfaces shall be 1-1/2-inch thickness, 6 lb. density, 705 FRK with a "K" rating of .23 at 75 degrees F mean temperature. Insulation for hot surfaces except as otherwise noted shall be 1-1/2-inch thickness, 6 lb. density, 705 with a "K" rating of .23 at 75 degrees F mean temperature. Insulation shall be applied with staggered joints firmly butted and joined. The insulation shall be held in place by steel bands. Bands shall be 1-inch by 25 gauge galvanized steel spaced on not over 12-inch centers. All joints and voids shall be filled with Owens-Corning #110 cement, well troweled into openings. For 705 FRK insulation, all joints and voids shall be FRK taped and vapor sealed. There shall be applied over the insulation surface 1-inch galvanized wire netting laced together at all edges and wired to the steel bands with 16 gauge soft annealed wire. Over this shall be applied 2-inch thick layer of Owens-Corning #110 cement applied in two layers. Install metal corner beads at all corners and edges in order to provide a permanent installation. Onto the dry cement surface apply a brush coat of Foster Sealfas 30-36 or Childers CP-50AMV1 lagging adhesive at the rate of 60-70 square feet per gallon. Cleanouts, nameplates, and manholes shall not be insulated, and the insulation on surrounding surfaces shall be neatly beveled off at such openings.

C. Insulation Installation on Pumps:

1. Fabricate metal boxes lined with insulation. Fit boxes around pumps and coincide box joints with splits in pump casings. Fabricate joints with outward bolted flanges. Bolt flanges on 6-inch (150-mm) centers, starting at corners. Install 3/8-inch- (10-mm-) diameter fasteners with wing nuts. Alternatively, secure the box sections together using a latching mechanism.
2. Fabricate boxes from aluminum at least 0.040 inch (1.0 mm) thick.
3. For below ambient services, install a vapor barrier coating at seams, joints, and penetrations. Seal between flanges with replaceable gasket material to form a vapor barrier.

D. Mechanical fasteners shall be utilized to hold insulation to surface with bands as required to hold the curvature of the material.

E. Support rings shall be provided to support the top head insulation where required.

F. Outdoor installations require a weather barrier mastic for protection of the insulation jacketing.

G. Insulation types materials shall be suitable for temperatures encountered by each item of equipment.

H. Install removable insulation sections at all cleanouts, test ports, and items that must be periodically tested.

2.5. ACCESSORY MATERIALS

A. Accessory materials installed as part of insulation work under this section shall include, but not be limited to:

1. Closure Materials - Butt strips, bands, wires, staples, mastics, adhesives; pressure-sensitive tapes.
2. Field-applied jacketing materials - sheet metal, plastic, canvas, fiber glass cloth, insulating cement; PVC fitting covers, PVC jacketing.
3. Support Materials - Hanger straps, hanger rods, saddles.
4. Fasteners, weld pins/studs, speed clips, insulation washers.
5. Metal mesh or expanded metal lagging.

B. All accessory materials shall be installed in accordance with project drawings and specifications, manufacturer's instructions, and/or in conformance with the current edition of the Midwest Insulation Contractors Association (MICA) "Commercial & Industrial Insulation Standards."

2.6. FIELD-APPLIED JACKET

- A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.
- B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
 - 1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Johns Manville; Zeston.
 - b. P.I.C. Plastics, Inc.; FG Series.
 - c. Proto PVC Corporation; LoSmoke.
 - d. Speedline Corporation; SmokeSafe.
 - 2. Adhesive: As recommended by jacket material manufacturer. VOC content not to exceed 250 g/L.
 - 3. Color: High Gloss White
 - 4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
 - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, and mechanical joints.
 - 5. Factory-fabricated tank heads and tank side panels.

PART 3. EXECUTION

3.1. WORKMANSHIP

- A. The Contractor shall take special care to prevent soiling equipment below or adjacent to areas being insulated. He shall be completely responsible for removing insulation cement splashes and smears and all surfaces that he mars or otherwise soils or defaces, and he will be totally responsible for restoring these damaged surfaces to their like-new condition when delivered to the site.

3.2. SITE INSPECTION

- A. Before starting work under this section, carefully inspect the site and installed work of other trades and verify that such work is complete to the point where installation of materials and accessories under this section can begin.
- B. Verify that all materials and accessories can be installed in accordance with project drawings and specifications and material manufacturers' recommendations.
- C. Verify, by inspecting product labeling, submittal data, and/or certifications which may accompany the shipments, that all materials and accessories to be installed on the project comply with applicable specifications and standards and meet specified thermal and physical properties.

3.3. PREPARATION

- A. Ensure that all pipe and equipment surfaces over which insulation is to be installed are clean and dry.
- B. Ensure that insulation is clean, dry, and in good mechanical condition with all factory-applied vapor or weather barriers intact and undamaged. Wet, dirty, or damaged insulation shall not be acceptable for installation.
- C. Ensure that pressure testing of piping systems has been completed prior to installing insulation.

3.4. INSTALLATION

A. Piping Systems

1. General:

- a. Install all insulation materials and accessories in accordance with manufacturer's published instructions and recognized industry practices to ensure that it will serve its intended purpose.
- b. Install insulation on piping subsequent to installation of heat tracing, painting, testing, and acceptance tests.
- c. Install insulation materials with smooth and even surfaces. Insulate each continuous run of piping with full-length units of insulation, with single cut piece to complete run. Do not use cut pieces or scraps abutting each other. Butt insulation joints firmly to ensure complete, tight fit over all piping surfaces.
- d. Maintain the integrity of factory-applied vapor barrier jacketing on all pipe insulation, protecting it against puncture, tear or other damage. Seal all tears, punctures and other penetrations of the pipe insulation vapor barrier coating.
- e. On exposed piping, locate insulation and cover seams in least visible location.

2. Fittings: Cover valves, fittings, unions, flanges, strainers, flexible connections, expansion joints, pump bodies, strainers, blowdowns, backflow preventers, autoflow valves and similar items in each piping system using one of the following:

- a. Mitered sections of insulation equivalent in thickness and composition to that installed on straight pipe runs.
- b. Insulation cement equal in thickness to the adjoining insulation.
- c. PVC fitting covers insulated with material equal in thickness and composition to adjoining insulation.

3. Penetrations: Extend piping insulation without interruption through walls, floors, and similar piping penetrations, except where otherwise specified.

4. Joints:

- a. Butt pipe insulation against hanger inserts. For hot pipes, apply 3-inch

(7.5cm) wide vapor barrier tape or bank over butt joints. For cold piping, apply wet coat of vapor barrier lap cement on butt joints, and seal joints with 3-inch (7.5cm) wide vapor barrier tape or band.

b. All pipe insulation ends shall be tapered and sealed, regardless of service.

5. For heat traced piping, insulate fittings, joints, and valves with insulation of like material, thickness and finish as adjoining pipe. Size insulation large enough to enclose pipe and heat tracer. Cover with aluminum jacket with seams located on bottom side of horizontal piping.

B. Equipment Insulation:

1. General:

- a. Install insulation in accordance with manufacturer's published instructions and recognized industry practices to ensure that it will serve its intended purpose.
- b. Install insulation on equipment after installation of heat tracing, painting, testing, and acceptance tests.
- c. Install insulation materials with smooth, even surfaces. Rework poorly fitted joints. Do not use joint sealer or mastic as filler for joint gaps and excessive voids resulting from poor workmanship. Apply insulation using staggered joint method for both single and double layer installation, applying each layer of insulation separately.
- d. Coat insulated surfaces where specified on contract drawings with layer of insulating cement, troweled in a workmanlike manner, leaving a smooth and continuous surface. Fill in seams, broken edges, and depressions. Cover over wire mesh and joints with cement sufficiently thick to remove surface irregularities.
- e. Maintain the integrity of factory-applied vapor barrier jacketing on all insulation, protecting it against puncture, tears or other damage. Seal all tears, punctures and other penetrations of equipment insulation facing.
- f. Where specification calls for field-applied all-service vapor barrier jacketing, it shall be neatly fitted and tightly secured. Lap seams 2-inches (5cm) (min.). Seal all joints with adhesive. Tape with 3-inches (7.5cm) matching pressure-sensitive tape or 3-inch (7.5cm) glass fabric and vapor barrier coating.
- g. On exposed equipment, locate insulation and cover seams in least visible location.

2. Removable Insulation: Provide removable insulation sections to cover parts of equipment which must be opened periodically for maintenance, such as vessel covers, fasteners, flanges, frames accessories, manholes, handholes, cleanouts ASME stamp, and manufacturer nameplates.

3. Areas Left Uninsulated: Items such as manholes, handholes, clean-outs, ASME stamp, and manufacturers' nameplates should be left uninsulated unless omitting insulation would cause a condensation problem. When such is the case, provide removable insulation and appropriate tagging to identify the presence of these items. Provide neatly beveled edges at interruptions of insulation.

4. Equipment Exposed to Weather: Protect outdoor insulation from weather by installation of weather barrier mastic protective finish or jacketing as recommended by the jacketing manufacturer.

3.5. FIELD QUALITY ASSURANCE

- A. Upon completion of all insulation work covered by this specification, visually inspect the work and verify that it has been correctly installed. This may be done while work is in progress, to assure compliance with requirements herein to cover and protect insulation materials during installation.

3.6. PROTECTION

- A. Replace damaged insulation which cannot be satisfactorily repaired, including insulation with vapor barrier damage and moisture-saturated insulation.
- B. The insulation contractor shall advise the general and/or the mechanical contractor as to requirements for protection of the insulation work during the remainder of the construction period, to avoid damage and deterioration of the finished insulation work.

3.7. SAFETY PRECAUTIONS

- A. Insulation contractor's employees shall be properly protected during installation of all insulation. Protection shall include proper attire when handling and applying insulation materials, and shall include (but not be limited to) disposable dust respirators, gloves, hard hats, and eye protection.
- B. The insulation contractor shall conduct all job site operations in compliance with applicable provisions of the Occupational Safety and Health Act, as well as with all state and/or local safety and health codes and regulations that may apply to the work.

3.8. INSULATION COVERING

- A. Unless otherwise noted, all exposed equipment insulation shall have a field applied PVC jacket cover neatly cut and pasted over equipment insulation. PVC shall be high gloss white and shall be 20 mils thick. Exposed areas include, but are not limited to, all mechanical equipment rooms/fan rooms, mezzanines, penthouses, boiler rooms, janitor's closets, kitchens, electric rooms, and piping and ductwork exposed in an occupied space.
- B. Unless otherwise noted, all exposed pipe insulation required to be insulated shall be jacketed with a PVC Jacketing with fitting covers. PVC jacket shall be color fade resistant, white high gloss, U.S.D.A. authorized as manufactured by Proto Corporation or approved equal. PVC jacketing shall be high impact, ultraviolet resistant PVC. Minimum thickness shall be 20 mils, roll stock ready for shop or field cutting and forming.
- C. Where PVC jackets are indicated, install with 1 inch overlap at longitudinal seams and end joints, for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturers recommended adhesive.
 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

HEAT OF REJECTION EQUIPMENT REPLACEMENT
(IRD25036-HVAC)

INDIAN RIVER SCHOOL DISTRICT
CARVER EC & SELBYVILLE MS

END OF SECTION

DIVISION 22 SECTION 22 40 05
PLUMBING EQUIPMENT
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. GENERAL.....	3
1.2. REFERENCES	3
1.3. DELIVERY, STORAGE, AND HANDLING	4
1.4. FIELD MEASUREMENTS	4
1.5. ALTERNATES	4
PART 2. PRODUCTS.....	4
2.1. SHOCK ABSORBERS	4
2.2. VACUUM BREAKERS/HOSE CONNECTION BACKFLOW PREVENTERS.....	4
2.3. BACKFLOW PREVENTER (REDUCED PRESSURE PRINCIPAL TYPE)	5
2.4. WALL HYDRANT (EXTERIOR).....	5
PART 3. EXECUTION.....	5
3.1. GENERAL INSTALLATION REQUIREMENTS.....	5
3.2. PLUMBING SPECIALTY INSTALLATION REQUIREMENTS	6
3.3. TESTING.....	7
3.4. CLEANING AND STERILIZATION	7
3.5. EXAMINATION.....	8
3.6. CLEANING.....	8
END OF SECTION	8

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 22 40 05 - PLUMBING EQUIPMENT

PART 1. GENERAL

1.1. GENERAL

- A. For General Mechanical Requirements, see Division 22 Section, Common Work Results for Plumbing & Division 01, General Requirements.
- B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 specifications apply to this Section.
- C. All exposed bolts, screws, etc., shall be vandal proof.
- D. All plumbing materials and equipment shall be new and of best grade, free of defects and complete with all required appurtenances and accessories.
- E. Piping and insulation are specified under other sections.
- F. Provide all materials, equipment and perform all labor required to install plumbing system complete as specified, as drawings indicated and as required by the State of Delaware, National Standard Plumbing Code, International Plumbing Code, City that each school is located in Code, the local code, and all other authorities have jurisdiction.
- G. Provide stops for all plumbing equipment. Stops are to be accessible.
- H. Ensure products and installation of specified products are in conformance with recommendations and requirements of the following organizations:
 - 1. National Sanitation Foundation (NSF).
 - 2. American Society of Mechanical Engineers (ASME).
 - 3. National Electrical Manufacturers' Association (NEMA).
 - 4. Underwriters Laboratories (UL).

1.2. REFERENCES

- A. ANSI/ASSE 1011 - Hose Connection Vacuum Breakers.
- B. ANSI/ASSE 1013 - Backflow Preventers, Reduced Pressure Principle.
- C. ANSI/ASE 1019 - Wall Hydrants, Frost Proof Automatic Draining Anti-Backflow Types.
- D. ANSI A112.26.1 - Water Hammer Arrestors.
- E. PDI WH-201 Water Hammer Arresters.
- F. ANSI/ASHRAE 90A - Energy Conservation in New Building Design.
- G. ASME Section VIII D - Pressure Vessels; Boiler and Pressure Vessel Codes.

H. ANSI/NFPA 70 - National Electrical Code.

I. IBC - International Building Code

1.3. DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, protect and handle products to site under provisions of General Requirements.
- B. Accept equipment on site in factory packaging. Inspect for damage.
- C. Protect installed equipment from damage by securing areas and by leaving factory packaging in place to protect equipment and prevent use.

1.4. FIELD MEASUREMENTS

- A. Verify that field measurements are as indicated on shop drawings and per the manufacturer.

1.5. ALTERNATES

- A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

PART 2. PRODUCTS

2.1. SHOCK ABSORBERS

- A. Provide shock absorbers equal to Josam Shokstops at all fast closing valves, at the top of all cold water risers, at each flush valve or battery of flush valves, and where indicated. Sizes and locations shall be in accordance with PDI Standard WH 201.
- B. Shock absorbers shall conform to ANSI A112.26.1, precharged suitable for operation in temperature range -100 to 300 degrees F and maximum 250 psig working pressure.
- C. Approved Manufacturers: Josam, Wade, Zurn, J.R. Smith, Sioux Chief, Watts, or approved equal.

2.2. VACUUM BREAKERS/HOSE CONNECTION BACKFLOW PREVENTERS

- A. Provide vacuum breakers on water connections to fixtures and equipment where minimum air gaps required by Plumbing Code are not possible and on hose bibbs and other outlets to which hoses can be attached.
- B. Vacuum breakers not subject to back pressure, Watts No. 288A; vacuum breakers subject to back pressure, Watts Series 9D or for hose threads, Watts Series 8A.
- C. Hose connection backflow preventers shall be ASSE 1052, suitable for at least 5 gpm flow and applications with up to 10 foot head back pressure. Include two (2) check valves, intermediate atmospheric vent, and non-removable, ASME B1.20.7 garden-hose thread on outlet.
- D. Hose connection vacuum breakers shall be ASSE 1011, nickel plated, with nonremovable

and manual drain features, and ASME B1.20.7 garden-hose threads on outlet. Units attached to rough-bronze finish hose connections may be rough bronze.

- E. Approved manufacturers: Watts, Beeco, B&K Industries, Zurn, Sparco, Conbraco or approved equal.

2.3. BACKFLOW PREVENTER (REDUCED PRESSURE PRINCIPAL TYPE)

- A. Furnish and install reduced pressure principal backflow preventers at all cold water make-up connections to HVAC water systems, cooling towers, closed circuit evaporative fluid coolers, and where indicated on contract drawings.
- B. Backflow preventers shall be of bronze body construction, inlet and discharge OS&Y gate valves, stainless steel check and relief valve seats, stainless steel relief valve shafts and flange bolts. Ball valve test cocks shall be bronze body.
- C. Pressure ratings shall be up to 175 psi and temperature ratings shall be up to 210 degrees F continuous.
- D. Install unit per local code requirements and authorities having jurisdiction. Unless otherwise noted, install backflow preventers between 12 inches and 60 inches above finished floor.
- E. Units shall be approved by ASSE 1013, UPC, UL, and shall be No. 909 with air gap fitting and inlet/outlet gate valves as manufactured by Watts Regulator, Conbraco, Wilkens, or as approved equal. Pipe discharge to nearest floor drain/floor sink. Provide minimum 18-inch clearance for servicing and testing.
- F. Pipe discharge of backflow preventer full size to closest floor drain utilizing type "L" copper.

2.4. WALL HYDRANT (EXTERIOR)

- A. HYD-1 Wall Hydrant (Exterior)
 - 1. Provide and install recessed anti-siphon wall hydrant, 3/4-inch non-freeze, key operated wall hydrant with hinged locking cover, polished bronze box and cover and bronze casing and integral vacuum breaker. Non-Freeze, exterior wall hydrants shall be Zurn Model Z-1320-XL, Josam, Wade, J.R. Smith, Mifab, Watts or approved equal.
 - 2. Seat and disc shall be removable from front of the hydrant. Wall thickness; see architectural drawings. Wall hydrants shall conform to ANSI/ASSE 1019 with wall plate, lock shield and removable key. Install 18 – 24 inches above finished grade.

PART 3. EXECUTION

3.1. GENERAL INSTALLATION REQUIREMENTS

- A. Install all equipment in accordance with manufacturer's instructions.

- B. Install components plumb and level.
- C. Unless otherwise noted, all plumbing piping shall be routed as high as possible between bottom of roof joists and above ceiling to allow proper installation of ductwork, fire protection piping, conduits, etc.
- D. All openings in ceilings and plenum walls for plumbing shall be sealed air tight and protected with fire stop.
- E. See site plan for extent of all piping leaving and entering building.
- F. See flow diagrams for location of valves, shock absorbers, etc.
- G. Make proper CW and drain connections to all equipment even though all branch main, elbows and connections are not shown.
- H. Unless otherwise noted, all domestic water piping shall be installed on heated side of ceiling insulation.
- I. All piping and installation shall comply with all local and national plumbing codes. Test piping as required by plumbing code and authority having jurisdiction.

3.2. PLUMBING SPECIALTY INSTALLATION REQUIREMENTS

- A. General: Install plumbing specialty components, connections, and devices according to manufacturer's written instructions.
- B. Install backflow preventers of type, size, and capacity indicated, at each water supply connection to mechanical equipment and systems, and to other equipment and water systems as indicated. Comply with authorities having jurisdiction. Locate backflow preventers in same room as connected equipment. Install air gap fitting on units with atmospheric vent connection and pipe relief outlet drain to nearest floor drain. Do not install bypass around backflow preventer. Label all piping downstream of backflow preventers as "non-potable" water.
- C. Field test all backflow preventers and submit test reports to Engineer. Furnish test kits as required for field testing.
- D. Install pressure regulators with inlet and outlet shutoff valves and balance valve bypass. Install pressure gages on inlet and outlet.
- E. Install strainers on supply side of each control valve, pressure regulator, and solenoid valve, and where indicated.
- F. Install wall hydrants with integral or field installed vacuum breaker.
- G. All wall hydrants shall be mounted 24" above finished grade unless otherwise specified.
- H. Fasten recessed, wall mounting plumbing specialties to reinforcement built into walls.
- I. Secure supplies to supports or substrate.

- J. Install individual stop valve in each water supply to plumbing specialties. Use ball, gate, or globe valve if specific valve as appropriate is not indicated.
- K. Install water supply stop valves in accessible locations.
- L. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep pattern escutcheons if required to conceal protruding pipe fittings.
- M. Include wood blocking reinforcement for recessed and wall mounting plumbing specialties.
- N. Install ball valves at all shock absorbers to allow removal for service/replacement.

3.3. TESTING

- A. After the building has been occupied and the various equipment is in actual use, the Contractor shall make an operating test of all equipment at a time directed by the Engineer to determine that all contract requirements are met.

3.4. CLEANING AND STERILIZATION

- A. After final testing for leaks, all potable water lines shall be thoroughly flushed, by plumbing contractor, to remove foreign material. Before placing the systems in service, sterilize the new water lines in accordance with local health department codes and at a minimum according to the following procedure:
 - 1. Through a 3/4-inch hose connection in each branch main and building main, pump in sufficient sodium hypochlorite to produce a free available chlorine residual of not less than 200 ppm. Plumbing Contractor shall provide plumbing connections and power for pumping chlorine into system.
 - 2. Proceed upstream from the point of chlorine application opening all faucets and taps until chlorine is detected. Close faucets and taps when chlorine is evident.
 - 3. When chlorinated water has been brought to every faucet and tap with a minimum concentration of 200 ppm chlorine, retain this water in the system for at least three (3) hours.
 - 4. CAUTION: Over-concentration of chlorine and more than three (3) hours of retention may result in damage to piping system. It is not necessary to retain chlorine in any system for twenty-four hours to achieve sterilization. AWWA states that 200 ppm chlorine for three hours is sufficient.
 - 5. At the end of the retention period, no less than 100 ppm of chlorine shall be present at the extreme end of the system.
 - 6. Proceed to open all faucets and taps and thoroughly flush all new lines until the chlorine residual in the water is less than 1.0 ppm.
 - 7. Obtain representative water sample from the system for analysis by an independent

and recognized bacteriological laboratory.

8. If the sample tested for coliform organisms is negative, a letter and laboratory report shall be submitted by the service organization to the Contractor, certifying successful completion of the sterilization. Additionally, this report shall be forwarded to the Owner as well as be included in the O&M Manual.
9. If any samples tested indicate the presence of coliform organisms, the entire sterilization procedure shall be repeated.
10. Take precautions to avoid use of plumbing fixtures and domestic water systems during sterilization period. Place signs on all plumbing fixtures and outlets during sterilization period.

3.5. EXAMINATION

- A. Verify that walls and floor finishes are prepared and ready for installation of fixtures.
- B. Verify that electric power is available and of the correct characteristics.

3.6. CLEANING

- A. At completion, clean plumbing equipment.

END OF SECTION

DIVISION 23 SECTION 23 05 00
COMMON WORK RESULTS FOR HVAC
TABLE OF CONTENTS

PART 1.	GENERAL	3
1.1.	SUMMARY.....	3
1.2.	PERMITS AND FEES.....	3
1.3.	EXAMINATION OF SITE.....	3
1.4.	CONTRACTOR QUALIFICATION	4
1.5.	MATERIALS AND EQUIPMENT	4
1.6.	FIRE SAFE MATERIALS	5
1.7.	REFERENCED STANDARDS, CODES AND SPECIFICATIONS	5
1.8.	SUBMITTALS, REVIEW AND ACCEPTANCE	6
1.9.	SHOP DRAWINGS.....	6
1.10.	SUPERVISION AND COORDINATION	9
1.11.	CUTTING AND PATCHING	9
1.12.	PENETRATION OF WATERPROOF CONSTRUCTION	9
1.13.	CONCRETE AND MASONRY WORK.....	10
1.14.	CONNECTIONS AND ALTERATIONS TO EXISTING WORK.....	10
1.15.	DEMOLITION	10
1.16.	DRIVE GUARDS.....	12
1.17.	VIBRATION ISOLATION	12
1.18.	ALTERNATES	13
1.19.	DEFINITIONS	13
1.20.	MINIMUM EFFICIENCY REQUIREMENTS.....	13
1.21.	SYSTEM INTEGRATION.....	14
1.22.	COORDINATION WITH INDIAN RIVER SCHOOL DISTRICT I.T. DEPARTMENT	14
1.23.	VFD BYPASSES.....	14
PART 2.	ELECTRICAL REQUIREMENTS	15
2.1.	GENERAL MOTOR AND ELECTRICAL REQUIREMENTS	15
2.2.	MOTORS AND CONTROLS	16
2.3.	MOTOR INSTALLATION.....	18
2.4.	WIRING DIAGRAMS	19
2.5.	VARIABLE FREQUENCY DRIVE MOTOR BEARING PROTECTIVE RINGS:	19
2.6.	ENCLOSURES	19
PART 3.	EXECUTION.....	19
3.1.	EQUIPMENT INSTALLATION - COMMON REQUIREMENTS	19
3.2.	SUPPORTS, HANGERS AND FOUNDATIONS	20
3.3.	PROVISIONS FOR ACCESS	20
3.4.	PAINTING AND FINISHES.....	21
3.5.	CLEANING OF SYSTEMS	22
3.6.	COLOR SELECTION	22
3.7.	PROTECTION OF WORK	22
3.8.	OPERATION OF EQUIPMENT.....	23
3.9.	DEMONSTRATION AND TRAINING VIDEO RECORDINGS.....	23
3.10.	IDENTIFICATIONS, FLOW DIAGRAMS, ELECTRICAL DIAGRAMS AND OPERATING INSTRUCTIONS	24
3.11.	WALL AND FLOOR PENETRATION	24
3.12.	RECORD DRAWINGS.....	25

3.13.	WARRANTY	25
3.14.	LUBRICATION	26
3.15.	OPERATIONS AND MAINTENANCE MANUALS	26
3.16.	INSTALLATION AND COORDINATION DRAWINGS	27
3.17.	PIPING SYSTEMS TESTING	28
3.18.	EQUIPMENT BY OTHERS	28
3.19.	STRAINER CLEANING	28
3.20.	OUTAGES.....	29
	END OF SECTION.....	29

SECTION 23 05 00 COMMON WORK RESULTS FOR HVAC

PART 1. GENERAL

1.1. SUMMARY

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Provide all labor, materials, equipment, and services necessary for and incidental to the complete installation and operation of all mechanical work.
- C. Unless otherwise specified, all submissions shall be made to, and acceptances and approvals made by the Engineer.
- D. Contract Drawings are generally diagrammatic and all offsets, fittings, transitions and accessories are not necessarily shown. Furnish and install all such items as may be required to fit the work to the conditions encountered. Arrange piping, ductwork, equipment, and other work generally as shown on the contract drawings, providing proper clearance and access. Where departures are proposed because of field conditions or other causes, prepare and submit detailed shop drawings for approval in accordance with Submittals specified below. The right is reserved to make reasonable changes in location of equipment, piping, and ductwork, up to the time of rough-in or fabrication.
- E. Conform to the requirements of all rules, regulations and codes of local, state and federal authorities having jurisdiction.
- F. Coordinate the work under Division 23 with the work of all other construction trades.
- G. Be responsible for all construction means, methods, techniques, procedures, and phasing sequences used in the work. Furnish all tools, equipment and materials necessary to properly perform the work in first class, substantial, and workmanlike manner, in accordance with the full intent and meaning of the contract documents.

1.2. PERMITS AND FEES

- A. Obtain all permits and pay taxes, fees and other costs in connection with the work. File necessary plans, prepare documents, give proper notices and obtain necessary approvals. Deliver inspection and approval certificates to Owner prior to final acceptance of the work.
- B. Permits and fees shall comply with the Division 01, General Requirements of the specification.

1.3. EXAMINATION OF SITE

- A. Examine the site, determine all conditions and circumstances under which the work must be done, and make all necessary allowances for same. No additional cost to the Owner will be permitted for contractors' failure to do so.
- B. Examine and verify specific conditions described in individual specifications sections.
- C. Verify that utility services are available, of the correct characteristics, and in the correct

locations.

1.4. CONTRACTOR QUALIFICATION

- A. Any Contractor or Subcontractor performing work under Division 23 shall be fully qualified and acceptable to the Engineer and Owner. Submit the following evidence when requested:
 - 1. A list of not less than five comparable projects which the Contractor completed.
 - 2. Letter of reference from not less than three registered professional engineers, general contractors or building owners.
 - 3. Local and/or State License, where required.
 - 4. Membership in trade or professional organizations where required.
- B. A Contractor is any individual, partnership, or corporation, performing work by contract or subcontract on this project.
- C. Acceptance of a Contractor or Subcontractor will not relieve the Contractor or subcontractor of any contractual requirements or his responsibility to supervise and coordinate the work, of various trades.

1.5. MATERIALS AND EQUIPMENT

- A. Materials and equipment installed as a permanent part of the project shall be new, unless otherwise indicated or specified, and of the specified type and quality. Existing items of equipment are being relocated under another Division of these specifications. The Contractor shall be responsible for connecting all utilities as shown on the drawings, to equipment identified as existing.
- B. Where material or equipment is identified by proprietary name, model number and/or manufacturer, furnish named item, or its equal, subject to approval by Engineer. Substituted items shall be equal or better in quality and performance and must be suitable for available space, required arrangement, and application. Submit all data necessary to determine suitability of substituted items, for approval.
- C. The suitability of named item only has been verified. Where more than one item is named, only the first named item has been verified as suitable. Substituted items, including items other than first named shall be equal or better in quality and performance to that of specified items, and must be suitable for available space, required arrangement and application. Contractor, by providing other than the first named manufacturer, assumes responsibility for all necessary adjustments and modifications necessary for a satisfactory installation. Adjustments and modifications shall include but not be limited to electrical, structural, support, and architectural work.
- D. Substitution will not be permitted for specified items of material or equipment where noted.
- E. All items of equipment furnished shall have a service record of at least five (5) years.

1.6. FIRE SAFE MATERIALS

- A. Unless otherwise indicated, materials and equipment shall conform to UL, NFPA and ASTM standards for fire safety with smoke and fire hazard rating not exceeding flame spread of 25 and smoke developed of 50.

1.7. REFERENCED STANDARDS, CODES AND SPECIFICATIONS

- A. Specifications, Codes and Standards listed below are included as part of this specification, latest edition.
- B. AABC Associated Air Balance Council
- C. ACCA - Air Conditioning Contractors of America
- D. AMCA Air Movement and Control Association
- E. ANSI - American National Standards Institute
- F. ASHRAE - American Society of Heating, Refrigerating and Air Conditioning Engineers
- G. ASME - American Society of Mechanical Engineers
- H. ASPE - American Society of Plumbing Engineers
- I. ASTM - American Society for Testing and Materials
- J. CS - Commercial Standard
- K. CTI - Cooling Tower Institute
- L. FM - Factory Mutual
- M. IEEE - Institute of Electrical and Electronics Engineers
- N. MSSP - Manufacturers Standards Society of the Valve and Fittings Industry
- O. NEC - National Electrical Code
- P. NEMA - National Electrical Manufacturers Association
- Q. NFPA - National Fire Protection Association
- R. UL - Underwriters' Laboratories
- S. State of Delaware Fire Protection Regulations.
- T. All mechanical equipment and materials shall comply with the codes and standards listed in the latest edition of ASHRAE HVAC Applications Handbook, Chapter entitled Codes and Standards.

1.8. SUBMITTALS, REVIEW AND ACCEPTANCE

- A. Equipment, materials, installation, workmanship and arrangement of work are subject to review and acceptance. No substitution will be permitted after acceptance of equipment or materials except where such substitution is considered by the Engineer to be in best interest of Owner.
- B. After acceptance of Material and Equipment List, submit three (3) copies or more as required under General Conditions of complete descriptive data for all items. Data shall consist of specifications, data sheets, samples, capacity ratings, performance curves, operating characteristics, catalog cuts, dimensional drawings, wiring diagrams, installation instructions, and any other information necessary to indicate complete compliance with Contract Documents. Edit submittal data specifically for application to this project.
- C. Thoroughly review and stamp all submittals to indicate compliance with contract requirements prior to submission. Coordinate installation requirements and any electrical requirements for equipment submitted. Contractor shall be responsible for correctness of all submittals.
- D. Submittals will be reviewed for general compliance with design concept in accordance with contract documents, but dimensions, quantities, or other details will not be verified.
- E. Identify submittals, indicating intended application, location and service of submitted items. Refer to specification sections or paragraphs and drawings where applicable. Clearly indicate exact type, model number, style, size and special features of proposed item. Submittals of a general nature will not be acceptable. For substituted items, clearly list on the first page of the submittal all differences between the specified item and the proposed item. The contractor shall be responsible for corrective action and maintaining the specification requirements if differences have not been clearly indicated in the submittal.
- F. Submit actual operating conditions or characteristics for all equipment where required capacities are indicated. Factory order forms showing only required capacities will not be acceptable. Call attention, in writing, to deviation from contract requirements.
- G. Acceptance will not constitute waiver of contract requirements unless deviations are specifically indicated and clearly noted. Use only final or corrected submittals and data prior to fabrication and/or installation.
- H. For any submittal requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.
- I. For resubmissions, the Contractor must address in writing all of the Engineer's comments on the original submission to verify compliance.

1.9. SHOP DRAWINGS

- A. Prepare and submit shop drawings for all mechanical equipment, specially fabricated items, modifications to standard items, specially designed systems where detailed design is not

shown on the contract drawings, or where the proposed installation differs from that shown on contract drawings.

- B. Submit data and shop drawings including but not limited to the list below, in addition to provisions of the paragraph above. Identify all shop drawings by the name of the item and system and the applicable specification paragraph number and drawing number.
- C. Every submittal including, but not limited to the list below, shall be forwarded with its own transmittal as a separate, distinct shop drawing. Grouping of items/systems that are not related shall be unacceptable.
- D. Items and Systems
 - 1. Access Doors/Panels including layouts and locations
 - 2. Automatic Air Vents
 - 3. Automatic Temperature Control Systems and Equipment
 - 4. Central Control and Monitoring Systems (CCMS) and Equipment
 - 5. Chemical Feed Systems
 - 6. Closed Circuit Evaporative Fluid Cooler/Cooling Tower Piping and Accessories
 - 7. Cooling Towers/Closed Circuit Evaporative Fluid Coolers
 - 8. Coordinated Drawings
 - 9. Differential Bypass Valves, Transmitters
 - 10. Drip Pans
 - 11. Equipment Rails
 - 12. Expansion Tanks and Accessories
 - 13. Exterior Equipment/Piping Supports
 - 14. Exterior Pipe Roller Supports
 - 15. Fire Stopping - Methods and Materials
 - 16. Flow Measuring Stations
 - 17. Flowmeter and Primary Elements (Flow Fittings)
 - 18. Identification Systems
 - 19. Material and Equipment Lists
 - 20. Motorized Make-Up Water Ball Valves.

21. Motorized Bleed Water Ball Valves.
22. Operations and Maintenance Manuals
23. Pete's Plugs
24. Pipe Enclosures
25. Pipe Guides and Anchors
26. Pipe Materials Including Itemized Schedules
27. Plate/Frame Heat Exchanger Plates for Refurbishment of Selbyville Heat Exchanger
28. Preliminary Testing and Balancing Reports
29. Pressure Relief Valves
30. Pressure Regulating Valves
31. Pressure Independent Control Valves (Minimum Flow Bypass Valves)
32. Pumps
33. Screen shots of ATC System Graphics
34. Strainers
35. Test Certificates
36. Thermal Insulation Materials Include Table Summaries
37. Thermometers and Gauges
38. Variable Frequency Drive Motor Bearing Protective Rings
39. Variable Speed Drives
40. Vibration Isolation Materials
41. Water Treatment Services
42. Weatherproof Assembly Components
43. Wiring Diagrams, Flow Diagrams and Operating Instructions

- E. Contractor, additionally, shall submit for review any other shop drawings as required by the Engineer. No item shall be delivered to the site, or installed, until the Contractor has received a submittal from the Engineer marked Reviewed or Comments Noted. After the proposed materials have been reviewed, no substitution will be permitted except where approved by the Engineer.

- F. For any shop drawing requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.

1.10. SUPERVISION AND COORDINATION

- A. Provide complete supervision, direction, scheduling, and coordination of all work under the Contract, including that of subcontractors.
- B. Coordinate rough-in of all work and installation of sleeves, anchors, and supports for piping, ductwork, equipment, and other work performed under Division 23.
- C. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction to allow for mechanical installations.
- D. Coordinate electrical work required under Division 23 with that under Division 26. Coordinate all work under Division 23 with work under all other Divisions.
- E. Supply services of an experienced (10 year minimum) and competent Project Manager to be in constant charge of work at site.
- F. Where a discrepancy exists within the specifications or drawings or between the specifications and drawings, the more stringent (or costly) requirement shall apply until clarification can be obtained from the Engineer. Failure to clarify such discrepancies with the Engineer will not relieve the Contractor of the responsibility of conforming to the requirements of the Contract.
- G. Failure of contractor to obtain a full and complete set of contract documents (either before or after bidding) will not relieve the contractor of the responsibility of complying with the intent of the contract documents.

1.11. CUTTING AND PATCHING

- A. Accomplish all cutting and patching necessary for the installation of work under Division 23. Damage resulting from this work to other work already in place, shall be repaired at Contractor's expense. Where cutting is required, perform work in neat and work-manlike manner. Restore disturbed work to match and blend with existing construction and finish, using materials compatible with the original. Use mechanics skilled in the particular trades required.
- B. Do not cut structural members without approval from the Engineer.

1.12. PENETRATION OF WATERPROOF CONSTRUCTION

- A. Coordinate the work to minimize penetration of waterproof construction, including roofs, exterior walls, and interior waterproof construction. Where such penetrations are necessary, furnish and install all necessary curbs, sleeves, flashings, fittings and caulking to make penetrations absolutely watertight.
- B. Where pipes penetrate roofs, flash pipe with Stoneman Stormtite, Pate or approved equal,

roof flashing assemblies with skirt and caulked counter flashing sleeve.

- C. Furnish and install pitch pockets or weather tight curb assemblies where required.
- D. Furnish and install roof drains, curbs, vent assemblies, and duct sleeves specifically designed for application to the particular roof construction, and install in accordance with the manufacturer's instructions. The Contractor shall be responsible for sleeve sizes and locations. All roof penetrations shall be installed in accordance with manufacturer's instructions, the National Roofing Contractors Association, SMACNA, and as required by other divisions of these specifications.

1.13. CONCRETE AND MASONRY WORK

- A. Furnish and install concrete and masonry work for equipment foundations, supports, pads, and other items required under Division 23. Perform work in accordance with requirements of other applicable Divisions of these specifications.
- B. Concrete shall test not less than 3,000 psi compressive strength after 28 days.
- C. Grout shall be non-shrink, high strength mortar, free of iron of chlorides and suitable for use in contact with all metals, without caps or other protective finishes. Apply in accordance with manufacturer's instructions and standard grouting practices.

1.14. CONNECTIONS AND ALTERATIONS TO EXISTING WORK

- A. Unless otherwise noted on the drawings, where existing mechanical work is removed, pipes, valves, ductwork, etc., shall be removed, including hangers, to a point below finished floors or behind finished walls and capped. Such point shall be far enough behind finished surfaces to allow for installation of normal thickness of required finish material.
- B. Where work specified in Division 23 connects to existing equipment, piping, ductwork, etc., Contractor shall perform all necessary alterations, cuttings, fittings, etc., of existing work as may be necessary to make satisfactory connections between new and existing work, and to leave completed work in a finished and workmanlike condition.
- C. Where the work specified under Division 23, or under other Divisions, requires relocation of existing equipment, piping, ductwork, etc., Contractor shall perform all work and make necessary changes to existing work as may be required to leave completed work in a finished and workmanlike condition. Where existing insulation is disturbed, replace insulation where removed or damaged equal to existing, in type, thickness, density, finish and thermal resistance (R-value) value.
- D. Where the relocation of existing equipment is required for access or the installation of new equipment, the contractor shall temporarily remove and/or relocate and re-install as required to leave the existing and new work in a finished and workman like condition.

1.15. DEMOLITION

- A. Unless otherwise noted all existing equipment, piping, ductwork, etc., shall remain.
- B. Where existing equipment is indicated to be removed, all associated piping, conduit,

- power, controls, control panels, sensors, tubing, insulation, hangers, ductwork, supports and housekeeping pads, etc., patch, paint and repair walls/roof/floor to match existing and/or new finishes.
- C. Provide necessary piping, valves, traps, temporary feeds, drips, etc., as required. Drain and refill piping systems as often as necessary to accommodate phasing and to minimize time lengths of outages.
 - D. The Contractor shall be responsible for visiting the site and determining the existing conditions in which the work is to be performed.
 - E. Where any abandoned pipes in existing floors, walls, pipe tunnels, ceilings, etc., conflict with new work, remove abandoned pipes as necessary to accommodate new work.
 - F. The location of all existing equipment, piping, ductwork, etc., indicated is approximate only and shall be checked and verified. Install all new mechanical/plumbing/fire protection work to connect to or clear existing work as applicable.
 - G. Maintain egress at all times. Coordinate egress requirements with the State Fire Marshal, the Owner and the authorities having jurisdiction.
 - H. Make provisions and include in bid all costs associated with confined entry/space requirements in crawl spaces and all other applicable OSHA regulations.
 - I. Where required to maintain the existing systems in operation, temporarily backfeed existing systems from new equipment. Contractor shall temporarily extend existing piping systems to new piping systems with the appropriate shut-off valves.
 - J. At completion of project all temporary piping, valves, controls, etc., shall be removed in their entirety.
 - K. Existing piping, equipment, ductwork, materials, etc., not required for re-use or re-installation in this project, shall be removed from the project site.
 - L. Deliver to the Owner, on the premises where directed, existing equipment and materials which are removed and which are desired by the Owner or are indicated to remain the property of the Owner.
 - M. All other materials and equipment which are removed shall become property of the Contractor and shall be promptly removed, from the premises, and disposed of by the Contractor, in an approved manner.
 - N. Where piping and/or ductwork is removed, remove all pipe or ductwork hangers which were supporting the removed piping or ductwork. Patch the remaining penetration voids with like materials and paint to match existing construction.
 - O. Where required, provide and coordinate removal and re-installation of existing equipment. Take care to protect materials and equipment indicated for reuse. Contractor shall repair or replace items which are damaged. Contractor shall have Owner's representative present to confirm condition of equipment prior to demolition.

- P. Before demolition begins, and in the presence of the Owners representative, test and note all deficiencies in all existing systems affected by demolition but not completely removed by demolition. Provide a copy of the list of system deficiencies to the Owner and the Engineer. Videotape existing conditions in each space prior to beginning demolition work.
- Q. The Owner shall have the first right of refusal for all fixtures, devices and equipment removed by the Contractor.
- R. All devices and equipment designated by the Owner to remain the property of the Owner shall be moved and stored by the Contractor at a location on site as designated by the Owner. It shall be the Contractor's responsibility to store all devices and equipment in a safe manner to prevent damage while stored.
- S. All existing equipment refused by the Owner shall become the property of the Contractor and shall be removed from the site by the Contractor in a timely manner and disposed of in a legal manner.
- T. Work Abandoned in Place: Cut and remove underground pipe a minimum of 2 inches beyond face of adjacent construction. Cap and patch surface to match existing finish.
- U. Temporary Disconnection: Remove, store, clean, reinstall, reconnect, and make operational equipment indicated for relocation.
- V. Terminate services and utilities in accordance with local laws, ordinances, rules and regulations.
- W. Where hydronic system piping and equipment is removed, Contractor shall be responsible for proper disposal of all contained fluids containing glycol (ethylene or propylene), hazardous waste and water treatment chemicals. Contractor shall include in his bid all associated costs with the removal, testing, and disposal of hydronic system fluid in accordance with EPA, Health Department, and the Local Authority Having Jurisdiction.

1.16. DRIVE GUARDS

- A. Provide safety guards on all exposed belt drives, motor couplings, and other rotating machinery. Provide fully enclosed guards where machinery is exposed from more than one direction.
- B. When available, guards shall be factory fabricated and furnished with the equipment. Otherwise fabricate guards of heavy gauge steel, rigidly braced, removable, and finish to match equipment served. Provide openings for tachometers. Guards shall meet local, State and O.S.H.A. requirements.

1.17. VIBRATION ISOLATION

- A. Furnish and install vibration isolators, flexible connections, supports, anchors and/or foundations required to prevent transmission of vibration from equipment, piping or ductwork to building structure. See Division 23 Section, "Vibration Control for HVAC and Plumbing Equipment".

1.18. ALTERNATES

- A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

1.19. DEFINITIONS

- A. Approve - to permit use of material, equipment or methods conditional upon compliance with contract documents requirements.
- B. Furnish and install or provide means to supply, erect, install, and connect to complete for readiness for regular operation, the particular work referred to.
- C. Contractor means the mechanical contractor and any of his subcontractors, vendors, suppliers, or fabricators.
- D. Piping includes pipe, all fittings, valves, hangers, insulation, identification, and other accessories relative to such piping.
- E. Ductwork includes duct material, fittings, hangers, insulation, sealant, identification and other accessories
- F. Concealed means hidden from sight in chases, formed spaces, shafts, hung ceilings, or embedded in construction.
- G. Exposed means not installed underground or concealed as defined above.
- H. Invert Elevation means the elevation of the inside bottom of pipe.
- I. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceiling, and unexcavated spaces.
- J. Review - limited observation or checking to ascertain general conformance with design concept of the work and with information given in contract documents. Such action does not constitute a waiver or alteration of the contract requirements.

1.20. MINIMUM EFFICIENCY REQUIREMENTS

- A. All heating, ventilating, and air conditioning equipment shall be manufactured to provide the minimum efficiency requirements as specified in ASHRAE Standard 90.1, latest edition.
- B. All piping and equipment insulation shall comply with ASHRAE Standard 90.1, latest edition.
- C. All mechanical devices, controls, accessories, and components shall be manufactured to provide the minimum efficiency requirements as specified in ASHRAE Standard 90.1, latest edition.
- D. Department of Energy (DOE) compliance: Pump manufacturers shall comply with US Department of Energy (DOE) energy conservation standard for "clean water pumps" 1-

200 horse power, less than 459 feet of head and greater than 25 gpm. These pumps shall be evaluated using the Pump Energy Index (PEI) of equal to or lesser than 1.0. the PEI number shall appear on the pump name plate and shall be available for the record at <http://er.pumps.org>.

1.21. SYSTEM INTEGRATION

- A. For all HVAC equipment specified to be provided with packaged controls and interfaced with the automatic temperature control system, provide system integration between the equipment manufacturer and the automatic temperature control subcontractor.
- B. HVAC equipment submittals requiring system integration as defined above must identify all required system integration points.
- C. HVAC equipment manufacturers must coordinate with ATC subcontractor regarding system integration prior to submitting on the equipment.
- D. A system integration meeting must be arranged by the Mechanical Contractor and include, but not be limited to the systems integrator for the HVAC equipment manufacturer and the ATC Subcontractor. This portion of systems integration must occur prior to HVAC equipment being delivered to the project.
- E. Once the HVAC equipment is on site, a second systems integration meeting must be arranged by the Mechanical Contractor to coordinate the packaged controls with the ATC system. The HVAC equipment manufacturer's representative familiar with system integration and the ATC subcontractor familiar with programming must be present.
- F. A final system integrations meeting shall occur once all equipment is in place and ready for operation. The Mechanical Contractor, the HVAC equipment systems' integrator, and the ATC Subcontractor shall meet on site to jointly program, schedule, verify points, interlock devices, and fully set up all systems integration components.
- G. All systems integration coordination, programming, and graphics must be completed prior to requesting commissioning and/or inspections by the Engineer of Record.

1.22. COORDINATION WITH INDIAN RIVER SCHOOL DISTRICT I.T. DEPARTMENT

- A. All equipment that interfaces with the internet shall be coordinated with the Indian River School District I.T. Department to verify that the same is suitable for use on the School District IT infrastructure. Coordinate with the Indian River School District I.T. Department regarding the allowable frequency bands to avoid interference with the School District I.T. infrastructure.

1.23. VFD BYPASSES

- A. When VFD's are specified with integral bypasses and the equipment manufacturer is not able to provide bypasses due to space constraints, then the manufacturer must provide spare VFD's for each fan/pump.

PART 2. ELECTRICAL REQUIREMENTS

2.1. GENERAL MOTOR AND ELECTRICAL REQUIREMENTS

- A. Furnish and install control and interlock wiring for the equipment furnished. In general, power wiring and motor starting equipment will be provided under Division 26. Carefully review the contract documents to coordinate the electrical work under Division 23 with the work under Division 26. Where the electrical requirements of the equipment furnished differ from the provisions made under Division 26, make the necessary allowances under Division 23. Where no electrical provisions are made under Division 26, include all necessary electrical work under Division 23.
- B. All electrical work performed under Division 23 shall conform to the applicable requirements of Division 26 and conforming to the National Electrical Code. All wiring, conduit, etc., installed in ceiling plenums must be plenum rated per NFPA and the International Building Code.
- C. Provide wiring diagrams with electrical characteristics and connection requirements.
- D. Test Reports: Indicate test results verifying nominal efficiency and power factor for three phase motors larger than five (5) horsepower.
- E. Protect motors stored on site from weather and moisture by maintaining factory covers and suitable weatherproof covering. For extended outdoor storage, remove motors from equipment and store separately.
- F. All motors shall be furnished with visible nameplate indicating motor horsepower, voltage, phase, cycles, RPM, full load amps, locked rotor amps, frame size, manufacturer's name and model number, service factor, power factor and efficiency.
- G. Motors located in exterior locations, wet air streams, air cooled condensers and outdoors shall be totally enclosed weatherproof epoxy-treated type.
- H. Nominal efficiency and power factor shall be as scheduled at full load and rated voltage when tested in accordance with IEEE 112.
- I. Brake horsepower load requirement at specified duty shall not exceed 85 percent of nameplate horsepower times NEMA service factor for motors with 1.0 and 1.15 service factors.
- J. All single phase motors shall be provided with thermal protection: Internal protection shall automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature ratings of motor insulation. Thermal protection device shall automatically reset when motor temperature returns to normal range, unless otherwise indicated.
- K. Where a motor disconnect is indicated downstream of a variable frequency drive (VFD) provide interlock wiring from the auxiliary contacts on the disconnect to the VFD to de-energize when the disconnect is turned "off".
- L. Where equipment under this Division is specified with integral disconnecting means, the

same shall be a single disconnecting means for disconnecting all ungrounded main power supply conductors that is capable of being locked in the open ("off") position in accordance with the National Electrical Code and the local electrical inspector.

2.2. MOTORS AND CONTROLS

- A. Motors and controls shall conform to the latest requirements of IEEE, NEMA, NFPA-70 and shall be UL listed. Motor sizes are specified with the driven equipment. Motor starting and control equipment is specified either with the motor which is controlled or in an electrical specification section. The Contractor is advised to consult all specification sections to determine responsibility for motors and controls.
- B. Motors shall be designed, built and tested in accordance with the latest revision of NEMA Standard MG 1.
- C. Motors used with variable-frequency controllers shall have ratings, characteristics, and features coordinated with and approved by the variable frequency controller (drive) manufacturer. As a minimum the following shall apply to variable frequency controlled motors:
 - 1. Motors shall be manufactured to withstand peak voltages of 1600 volts with .1 microsecond rise time per NEMA MG-1.
 - 2. Critical vibration frequencies of motor shall not be within operating range of variable frequency controller output.
 - 3. Temperature rise: Match rating for Class B insulation.
 - 4. Insulation: Class F.
 - 5. Thermal Protection: Conform to MG1 requirements for thermally protected motors.
- D. Motors shall be suitable for use under the conditions and with the equipment to which applied, and designed for operation on the electrical systems specified or indicated.
 - 1. Motor capacities shall be such that the horsepower rating and the rated full-load current will not be exceeded while operating under the specified operating conditions. Under no condition shall the motor current exceed that indicated on the nameplates.
 - 2. Motor sizes noted in the individual equipment specifications are minimum requirements only. It is the responsibility of the equipment manufacturers and of the Contractor to furnish motors, electrical circuits and equipment of ample capacity to operate the equipment without overloading, exceeding the rated full-load current, or overheating at full-load capacity under the most severe operating service of this equipment. Motors shall have sufficient torque to accelerate the total WR2 of the driven equipment to operating speed.
 - 3. Motors shall be continuous duty type and shall operate quietly at all speeds and loads.

4. Motors shall be designed for operation on 60 hertz power service. Unless otherwise specified or shown, motors less than $\frac{1}{2}$ horsepower shall be single phase, and motors $\frac{1}{2}$ horsepower and larger shall be 3 phase unless otherwise noted.
 5. Motors shall be mounted so that the motor can be removed without removing the entire driven unit.
- E. Single phase motors, smaller than 1/20 horsepower shall be ball or sleeve bearing; drip-proof, totally enclosed or explosion proof, as specified; 120 volts; permanent-split capacitor or shaded pole type. These motors shall not be used for general power purposes, and shall only be provided as built-in components of such mechanical equipment as fans, unit heaters, humidifiers and damper controllers. When approved by the Engineer, deviations from the specifications will be permitted as follows:
1. Open motors may be installed as part of an assembly where enclosure within a cabinet provides protection against moisture.
 2. Motors used in conjunction with low voltage control systems may have a voltage rating less than 115 volts.
- F. Single phase motors, greater than 1/20 horsepower and less than $\frac{1}{2}$ horsepower shall be ball bearing; drip-proof, totally enclosed or explosion proof, as specified, with Class A or B insulation, as standard with the motor manufacturer; 115 or 120/208/240 volts as required; capacitor start-induction run, permanent split capacitor, or repulsion start-induction run type with minimum efficiency of 70 percent and a minimum full load power of 77 percent.
- G. Except as otherwise specified in the various specification sections, 3 phase motors 60 horsepower and smaller shall be NEMA design B squirrel cage induction type meeting the requirements of this paragraph. Motors shall be drip-proof, totally enclosed or explosion proof, as specified or indicated. Insulation shall be Class B or F, at 40 degrees C ambient temperature. Drip-proof motors shall have a 1.15 service factor and totally enclosed and explosion proof motors shall have a service factor of 1.00 or higher. Motors specified for operation at 480, 240, and 208 volts shall be nameplated 460, 230, 200 volts, respectively. Efficiencies and percent power factor at full load for three phase motors shall be not less than the values listed below for premium efficiency motors:

MOTOR NAMEPLATE	MINIMUM PERCENT EFFICIENCY AT NOMINAL SPEED AND RATED LOAD	MINIMUM PERCENT POWER FACTOR
1HP and above to	85.5 percent	84 percent
1- $\frac{1}{2}$ HP	86.5 percent	85 percent
2HP	86.5 percent	85 percent

MOTOR NAMEPLATE	MINIMUM PERCENT EFFICIENCY AT NOMINAL SPEED AND RATED LOAD	MINIMUM PERCENT POWER FACTOR
3HP	89.5 percent	86 percent
5HP	89.5 percent	87 percent
7½ HP	91 percent	86 percent
10HP	91.7 percent	85 percent
15HP	93.0 percent	85 percent
20HP	93.0 percent	86 percent
25HP	93.6 percent	85 percent

- H. Three phase motors ½ HP or greater shall be the Duty Master XE by Reliance Electric Company, Super-E Premium Efficiency of Baldor Motor and Drives, E-plus Efficient Standard Duty Motor of the Electric Motor Division of Gould, Inc., the MAC II High Efficiency motor of Westinghouse Electric Corp., the equivalent product of General Electric, or approved equal.
- I. For motors serving equipment being controlled by a variable speed drive, motor shall be premium efficiency inverter duty rated.
- J. Motor frames shall be NEMA Standard T-Frames of steel, aluminum, or cast iron with end brackets of cast-iron or aluminum with steel inserts.
- K. Control of each motor shall be manual or automatic as specified for each in the various mechanical sections. In general, and unless otherwise specified for a particular item in the various mechanical sections of the specifications, motor starters and controls shall be specified and provided under the various electrical sections of these specifications.
- L. Provide manufacturer's warranty for all motors for minimum of 5 years including all labor and materials.

2.3. MOTOR INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install securely on firm foundation. Mount ball bearing motors to support shaft regardless of shaft position.
- C. Check line voltage and phase and ensure agreement with nameplate. Check that proper thermal overloads have been installed prior to operating motors.

- D. Use adjustable motor mounting bases for belt-driven motors.
- E. Align pulleys and install belts.
- F. Tension belts according to manufacturer's written instructions.

2.4. WIRING DIAGRAMS

- A. The Contractor is responsible for obtaining and submitting wiring diagrams for all major items of equipment.
- B. Wiring diagrams shall be provided with shop drawings for all equipment requiring electric power.
- C. Provide wiring diagrams for all major mechanical items of equipment to electrical contractor and ATC subcontractor for coordination.

2.5. VARIABLE FREQUENCY DRIVE MOTOR BEARING PROTECTIVE RINGS:

- A. For all motors driven by a variable frequency drive include a maintenance free, circumferential, conductive micro fiber shaft grounding ring to discharge shaft currents. Grounding rings shall be manufactured by AEGIS SGR or approved equal.
- B. Furnish units with one year warranty.
- C. Size and select Bearing Protective Rings per the manufacturer requirements based on the motor size, shaft diameter, and shaft shoulder length. For motors with slingers furnish and install NEMA /IEC kit as required.
- D. Furnish and apply Colloidal silver shaft coating to all shafts with Bearing Protective Rings to improve shaft voltage discharge capability.

2.6. ENCLOSURES

- A. Electrical enclosures including factory provided enclosures, field provided and installed enclosures, and automatic temperature control system enclosures shall be as follows:
 - 1. Dry Interior Locations: NEMA 1.
 - 2. Damp/Wet Locations, Including Exterior Locations: NEMA 3R.

PART 3. EXECUTION

3.1. EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- A. Install equipment to provide maximum possible headroom, if mounting heights are not indicated.
- B. Install equipment according to approved submittal data. Portions of the work are shown only in diagrammatic form. Refer conflicts to Engineer.
- C. Install equipment level and plumb, parallel and perpendicular to other building systems

and components in exposed interior spaces, unless otherwise indicated.

- D. Install mechanical equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
- E. Install equipment giving right of way to piping installed at required slope.
- F. Install flexible connectors on equipment side of shutoff valves, horizontally and parallel to equipment shafts if possible.
- G. Do not install equipment, or piping over electrical gear, electrical panels, motor controllers, and similar electrical equipment. Install equipment, ductwork, and piping to maintain clear space above and in front of all electrical components per the National Electric Code.

3.2. SUPPORTS, HANGERS AND FOUNDATIONS

- A. Provide supports, hangers, braces, attachments and foundations required for the work. Support and set the work in a thoroughly substantial and workman-like manner without placing strains on materials, equipment, or building structure, submit shop drawings for approval. Coordinate all work with the requirements of the structural division.
- B. Supports, hangers, braces, and attachments shall be standard manufactured items or fabricated structural steel shapes. All interior hangers shall be galvanized or steel with rust inhibiting paint. For un-insulated copper piping provide copper hanger to prevent contact of dissimilar metals. All exterior hangers shall be constructed of galvanized or stainless steel utilizing stainless steel rods, nuts, washers, bolts, etc.
- C. Concrete housekeeping pads and foundations shall be not less than 4 inches high and shall extend a minimum of 6 inches beyond equipment bases. Provide wire-mesh reinforcement; chamfer exposed edges and corners; and finish exposed surfaces smooth.
- D. Where new concrete housekeeping pads are placed on existing concrete, saw cut the existing concrete to the perimeter dimension of the new pad to a depth of ½ inch. Break out the top ½ inch area of the existing concrete. Add stubs of #4 rebar angled into the existing concrete at a depth of approximately 50 percent of the existing slab thickness. The top portion of the rebar stub shall extend into the new pad by approximately 50 percent of its thickness. Furnish one rebar stub per every two square feet of new pad. Chemically bond the new concrete to the existing concrete.

3.3. PROVISIONS FOR ACCESS

- A. The contractor shall provide access panels and doors for all concealed equipment, valves, strainers, dampers, filters, controls, control devices, damper operators, and other devices requiring maintenance, service, adjustment, balancing or manual operation.
- B. Where access doors are necessary, furnish and install manufactured painted steel door assemblies consisting of hinged door, key locks, and frame designed for the particular wall or ceiling construction. Properly locate each door. Door sizes shall be a minimum of 12 inches x 12 inches for hand access, 18 inches x 18 inches for shoulder access and 20 inches x 30 inches for full body access where required. Review locations and sizes with Engineer

prior to fabrication. Provide U.L. approved and labeled access doors where installed in fire rated walls or ceilings. Doors shall be Milcor Metal Access Doors as manufactured by Inland-Ryerson, Mifab, or approved equal.

1. Acoustical or Cement Plaster: Style B
 2. Hard Finish Plaster: Style K or L
 3. Masonry or Dry Wall: Style M
- C. Where access is by means of liftout ceiling tiles or panels, mark each ceiling grid using small color-coded and numbered tabs. Provide a chart or index for identification. Place markers within ceiling grid not on ceiling tiles.
- D. Access panels, doors, etc. described herein shall be furnished under the section of specifications providing the particular service and to be turned over to the pertinent trade for installation. Coordinate installation with installing contractor. All access doors shall be painted in baked enamel finish to match ceiling or wall finish. Label inside of access door as to what it serves.
- E. Submit shop drawings indicating the proposed location of all access panels/doors. Access doors in finished spaces shall be coordinated with air devices, lighting and sprinklers to provide a neat and symmetrical appearance.

3.4. PAINTING AND FINISHES

- A. Provide protective finishes on all materials and equipment. Use coated or corrosion-resistant materials, hardware and fittings throughout the work. Paint bare, untreated ferrous surfaces with rust-inhibiting paint. All exterior components including supports, hangers, nuts, bolts, washers, vibration isolators, etc. shall be stainless steel.
- B. Clean surfaces prior to application of insulation, adhesives, coatings, paint, or other finishes.
- C. Provide factory-applied finishes where specified. Unless otherwise indicated factory-applied paints shall be baked enamel with proper pretreatment.
- D. Protect all finishes and restore any finishes damaged as a result of work under Division 23 to their original condition.
- E. The preceding requirements apply to all work, whether exposed or concealed.
- F. Remove all construction marking and writing from exposed equipment, ductwork, piping and building surfaces. Do not paint manufacturer's labels or tags.
- G. All exposed ductwork, piping, equipment, etc. shall be painted. Colors shall be as stated in this division or as selected by the Owner and conform to ANSI Standards.
- H. All exposed piping, equipment, etc., in Mechanical Rooms, Boiler Rooms, Penthouses, Mezzanines, and Storage where PVC jacketed shall not require painting. Label and identify and color code as specified.

3.5. CLEANING OF SYSTEMS

- A. Thoroughly clean systems after satisfactory completion of pressure tests and before permanently connecting fixtures, equipment, traps, strainers, and other accessory items. Blow out and flush piping until interior surfaces are free of foreign matter.
- B. Flush piping in re-circulating water systems to remove cutting oil, excess pipe joint compound, solder slag and other foreign materials. Do not use system pumps until after cleaning and flushing has been accomplished to the satisfaction of the Engineer. Employ chemical cleaners, including a non-foaming detergent, not harmful to system components. After cleaning operation, final flushing and refilling, the residual alkalinity shall not exceed 300 parts per million. Submit a certificate of completion to Engineer stating name of Service Company used.
- C. Maintain strainers and dirt pockets in clean condition.
- D. Clean fans, enclosures, registers, grilles, and diffusers at completion of work.
- E. Install filters of equal efficiency to those specified in permanent air systems operated for temporary heating during construction. Replace with clean filters as specified prior to acceptance and after cleaning of system.
- F. Pay for labor and materials required to locate and remove obstructions from systems that are clogged with construction refuse after acceptance. Replace and repair work disturbed during removal of obstructions.
- G. Leave systems clean, and in complete running order.
- H. All HVAC piping/equipment strainers must be pulled and cleaned prior to substantial completion. In addition six (6) months after substantial completion all HVAC piping/equipment strainers must be pulled and cleaned a second time. Document and submit verification of strainer cleaning to Engineer, and Owner.

3.6. COLOR SELECTION

- A. Color of finishes shall be as selected by the Owner.
- B. Submit color of factory-finished equipment for acceptance prior to ordering.

3.7. PROTECTION OF WORK

- A. Protect work, material and equipment from weather and construction operations before and after installation. Properly store and handle all materials and equipment.
- B. Cover temporary openings in piping, ductwork, and equipment to prevent the entrance of water, dirt, debris, or other foreign matter. Deliver pipes and tubes with factory applied end caps.
- C. Cover or otherwise protect all finishes.
- D. Replace damaged materials, devices, finishes and equipment.

- E. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, where stored inside.
- F. Provide moisture protection for ductwork in areas which are not under roof or where ductwork would be exposed to rainwater.

3.8. OPERATION OF EQUIPMENT

- A. Clean all systems and equipment prior to initial operation for testing, balancing, or other purposes. Lubricate, adjust, and test all equipment in accordance with manufacturer's instructions. Do not operate equipment unless all proper safety devices or controls are operational. Provide all maintenance and service for equipment that is authorized for operation during construction.
- B. Where specified, or otherwise required, provide the services of the manufacturer's factory-trained servicemen or technicians to start up the equipment. Where factory start-up of equipment is not specified, provide field start-up by qualified technician.
- C. Submit factory start-up sheets or field start-ups sheets for all equipment prior to the commencement of testing and balancing work. Testing and balancing work shall not commence until start-up reports have been completed, reviewed by Engineer and forwarded to Testing and Balancing Agency.
- D. Do not use mechanical systems for temporary services or temporary conditioning during construction, unless approved by Owner in writing. Refer to Division 01 Section "Temporary Facilities and Controls" for temporary heating/cooling during construction.
- E. Upon completion of work, clean and restore all equipment to new conditions; replace expendable items such as filters.

3.9. DEMONSTRATION AND TRAINING VIDEO RECORDINGS

- A. General: Record demonstration and training video recordings. Record each training module separately.
 - 1. At beginning of each training module, record each chart containing learning objective and lesson outline.
- B. Video Recording Format: Provide high-quality color video recordings with menu navigation in format acceptable to Engineer
- C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to show area of demonstration and training. Display continuous running time.
- D. Narration: Describe scenes on video recording by audio narration by microphone while video recording is recorded. Include description of items being viewed.
- E. Transcript: Provide a transcript of the narration. Display images and running time captured from videotape opposite the corresponding narration segment.

3.10. IDENTIFICATIONS, FLOW DIAGRAMS, ELECTRICAL DIAGRAMS AND OPERATING INSTRUCTIONS

- A. Contractor shall submit for approval schematic piping diagrams of each piping system installed in the building. Diagrams shall indicate the location and the identification number of each valve in the particular system. Following approval by all authorities, the diagrams shall be framed, mounted under safety glass and hung in each Mechanical Room where directed. Contractor shall deliver the tracing or sepia from which the diagrams were reproduced to the Owner.
- B. All valves shall be plainly tagged. For any bypass valves, install sign indicating valve position as "Normally Open" or "Normally Closed" as required.
- C. All items of equipment, including motor starters, disconnects and ATC panels shall be furnished with white on black plastic permanent identification cards. Lettering shall be a minimum of ¼ inch high. Identification plates shall be secured, affixed to each piece of equipment, starters, disconnects, panels by screw or adhesive (tuff bond #TB2 or as approved equal).
- D. Provide three (3) copies of operating and maintenance instructions for all principal items of equipment furnished. This material shall be bound as a volume of the Record and Information Booklet as hereinafter specified.
- E. All lines piping installed under this contract shall be stenciled with direction of flow arrows and with stenciled letters naming each pipe and ductwork and service. Refer to Division 23 Section, "HVAC Piping, Fittings, Valves, Etc." and Division 23 Section, "HVAC Air Distribution". Color-code all direction of flow arrows and labels. In finished spaces omit labeling and direction of flow arrows. Paint in color as selected by Owner.
- F. Submit list of wording, symbols, letter size, and color coding for mechanical identification. Submit samples of equipment identification cards, piping labels, and valve tags to Engineer for review prior to installation.
- G. Provide at least 24 hours of straight time instruction to the operating personnel. Time of instruction shall be designated by the Owner. Additional instruction time for the automatic temperature control (ATC) system is specified in Division 23 Section, "Instrumentation & Controls of HVAC & Plumbing Systems".
- H. Contractor shall demonstrate Sequences of Operation of all equipment in presence of Owner's representative, Engineer, and ATC subcontractor.

3.11. WALL AND FLOOR PENETRATION

- A. All penetrations of partitions, ceilings, roofs and floors by ducts, piping or conduit under Division 23 shall be sleeved, sealed, and caulked airtight for sound and air transfer control. Penetrations of mechanical room partitions, ceilings, and floors shall be as specified in Division 23 Section, "Vibration Control for HVAC and Plumbing Equipment".
- B. All penetration of fire rated assemblies shall be sleeved, sealed, caulked and protected to maintain the rating of the wall, roof, or floor. Fire Marshal approved U.L. assemblies shall be utilized. See Division 07 Section, "HVAC & Plumbing Penetration Firestopping".

- C. Where piping extends through exterior walls or below grade, provide waterproof pipe penetration seals, as specified in another division of these specifications.
- D. Provide pipe escutcheons for sleeved pipes in finished areas.
- E. Piping sleeves:
 - 1. Galvanized steel pipe, standard weight where pipes are exposed and roofs and concrete and masonry walls. On exterior walls provide anchor flange welded to perimeter.
 - 2. Twenty-two (22) gauge galvanized steel elsewhere.
- F. Extend all floor sleeves through floor at least 3/4-inches above finished floor, caulk sleeve the entire depth and furnish and install floor plate.

3.12. RECORD DRAWINGS

- A. Upon completion of the mechanical installations, the Contractor shall deliver to the Engineer one complete set of prints of the mechanical contract drawings which shall be legibly marked in red pencil to show all changes and departures of the installation as compared with the original design. They shall be suitable for use in preparation of Record Drawings.
- B. Contractor shall incorporate all sketches, addendums, value engineering, change orders, etc., into record drawings prior to delivering to Engineer.

3.13. WARRANTY

- A. Contractor's attention is directed to warranty obligations contained in the GENERAL CONDITIONS.
- B. The above shall not in any way void or abrogate equipment manufacturer's guarantee or warranty. Certificates of equipment manufacturer's warranties shall be included in the operations and maintenance manuals.
- C. The Contractor guarantees for a two (2) year period from the time of final acceptance by the Owner.
 - 1. That the work contains no faulty or imperfect material or equipment or any imperfect, careless, or unskilled workmanship.
 - 2. That all work, equipment, machines, devices, etc. shall be adequate for the use to which they are intended, and shall operate with ordinary care and attention in a satisfactory and efficient manner.
 - 3. That the contractor will re-execute, correct, repair, or remove and replace with proper work, without cost to the Owner, any work found to be deficient. The contractor shall also make good all damages caused to their work or materials in the process of complying with this section. Contractor shall repair and/or replace any/all damage to finishes and furniture resulting from their corrective work.

4. That the entire work shall be water-tight and leak-proof.

3.14. LUBRICATION

- A. All bearings, motors, and all equipment requiring lubrication shall be provided with accessible fittings for same. Before turning over the equipment to the Owner, the Contractor shall fully lubricate each item of equipment, shall provide one year's supply of lubricant for each, and shall provide Owner with complete written lubricating instructions, together with diagram locating the points requiring lubrication. Include this information in the Record and Information Booklet.
- B. In general, all motors and equipment shall be provided with grease lubricated roller or ball bearings with Alemite or equal accessible or extended grease fittings and drain plugs.

3.15. OPERATIONS AND MAINTENANCE MANUALS

- A. The Contractor shall have prepared three (3) hardcopies and one (1) electronic copy of the Operations and Maintenance Manuals for each of the six schools on the project and deliver these copies of the booklet to the Owner. The booklet shall be as specified herein. The booklet must be approved and will not be accepted as final until so stamped.
- B. The booklet shall be bound in a three ring loose-leaf binder similar to National No. 3881 with the following title lettered on the front: Operations and Maintenance Manuals – Indian River School District – (The appropriate name of the school where the manual will be stored) - Heat of Rejection Equipment Replacement - HVAC. No sheets larger than 8-1/2 inches x 11 inches shall be used, except sheets that are neatly folded to 8-1/2 inches x 11 inches and used as a pull-out. Provide divider tabs and table of contents for organizing and separating information.
- C. Electronic copies of the manual shall be saved on USB flash drives, and shall be in searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of Volume 1 (if applicable) of hard copies of the manual.
- D. Provide the following data in the booklet:
 1. As first entry, an approved letter indicating the starting/ending time of Contractor's warranty period.
 2. Maintenance operation and lubrication instructions on each piece of equipment furnished.
 3. Complete catalog data on each piece of heating and air conditioning equipment furnished including approved shop drawing.
 4. Manufacturer's extended limited warranties on equipment including but not limited to closed circuit evaporative coolers, variable frequency drives and cooling towers.
 5. Chart form indicating frequency and type of routine maintenance for all mechanical equipment. The chart shall also indicate model number of equipment, location and service.

6. Provide sales and authorized service representatives names, address, and phone numbers of all equipment and subcontractors.
 7. Provide supplier and subcontractor's names, address, and phone number.
 8. Catalog data of all equipment, valves, etc. shall include wiring diagrams, parts list and assembly drawing.
 9. Provide and install in locations as directed by the Owner, valve charts including valve tag number, valve type, valve model number, valve manufacturer, style, service and location. Each valve chart shall be enclosed in a durable polymer based frame with a cover safety glass.
 10. Copy of the approved balancing report.
 11. ATC systems including as-built ATC drawings of systems including internal of all panels.
 12. Access panel charts with index illustrating the location and purpose of access panels.
 13. Approved HVAC Inspector and Electrical Certificates.
 14. Start-up reports for equipment.
 15. Water treatment test reports.
 16. Provide and install in locations as directed by Owner, filter charts, including filter type, size, model number, manufacturer, quantity and size for each filter utilized on the project. Filter charts shall be enclosed in a durable polymer based frame with a cover safety glass.
 17. Insert color graphic with embedded parameters for ATC system into record and information booklet.
 18. Filter charts indicating equipment served, size, and type of filter required.
 19. Documentation of strainer pulling and cleaning.
 20. Base mounted pump shaft laser alignment report.
- E. Submit Record and Information Booklets prior to anticipated date of substantial completion for Engineer review and approval. Substantial completion requires that Record and Information booklets be reviewed and approved.

3.16. INSTALLATION AND COORDINATION DRAWINGS

- A. Prepare, submit, and use composite installation and coordination drawings to assure proper coordination and installation of work. Drawings shall include, but not be limited, to the following:
1. Complete Plumbing and HVAC Piping Drawings showing coordination with

lights, electrical equipment, HVAC equipment and structural amenities.

- B. Draw plans to a scale not less than 3/8-inch equals one foot. Include plans, sections, and elevations of proposed work, showing all equipment, piping and ductwork in areas involved. Fully dimension all work including lighting fixtures, conduits, pullboxes, panelboards, and other electrical work, walls, doors, ceilings, columns, beams, joists and other architectural and structural work.
- C. Identify all equipment and devices on wiring diagrams and schematics. Where field connections are shown to factory-wired terminals, include manufacturer's literature showing internal wiring.
- D. Refer to Division 01 Section "Project Management and Coordination" for additional requirements related to coordination drawings.

3.17. PIPING SYSTEMS TESTING

- A. The entire new HVAC piping systems shall be tested hydrostatically before insulation covering is applied and proven tight under the following gauge pressures for a duration of twenty-four (24) hours. Testing to be witnessed by Owner's representative and documented in writing.

SYSTEM	TEST PRESSURE
Heat Pump Water Supply & Return Piping, Cooling Tower Supply & Return Piping, and Chemical Treatment Piping	100 psi
Heating Water Supply and Return Piping	100 psig

- B. Testing and acceptance thereof shall be in accordance with local requirements and shall meet approval of authority having jurisdiction. Submit certificates and approved permits and insert one (1) copy in the Operations and Maintenance Manuals.

3.18. EQUIPMENT BY OTHERS

- A. This Contractor shall make all system connections required to equipment furnished and installed under other divisions or furnished by the Owner. Connections shall be complete in all respects to render this equipment functional to its fullest intent.
- B. It shall be the responsibility of the supplier of this equipment to furnish complete instructions for connections. Failure to do so will not relieve this contractor of any responsibility for improper equipment operation.

3.19. STRAINER CLEANING

- A. All equipment strainers must be pulled and cleaned at substantial completion. Document in writing and via digital photographs that all strainers have been pulled and cleaned.
- B. One year after project substantial completion all strainers shall be pulled again and cleaned. Document in writing and via digital photographs that all strainers were pulled and clean at the one year after project substantial completion data.

- C. Insert documentation that the strainers have been pulled and cleaned in the Record and Information Books.
- D. Re-purge hydronic systems of all air after strainers are pulled and cleaned.

3.20. OUTAGES

- A. Provide a minimum of fourteen (14) days notice to schedule outages. The Contractor shall include in their bid outages and/or work in occupied areas to occur on weekends, holidays, or at night. Coordinate and get approval of all outages with the Owner.
- B. Submit Outage Request form, attached at end of this Section, to Owner for approval.

END OF SECTION

OUTAGE REQUEST

DATE APPLIED: _____ BY: _____

DATE FOR OUTAGE: _____ FIRM: _____

START OUTAGE-TIME: _____ DATE: _____

END OUTAGE -- TIME: _____ DATE: _____

AREAS AND ROOMS: _____

FLOOR(S): _____

AREA(S): _____

ROOM(S): _____

WORK TO BE PERFORMED: _____

SYSTEM(S): _____

REQUEST APPROVED BY: _____

(FOREMAN OR OTHER PERSON IN CHARGE)

(FOR OWNER'S USE ONLY):

APPROVED: _____

YES ____ NO ____ BY: _____ DATE: _____

DATE/TIME-AS REQUESTED: _____ OTHER : _____

OWNER'S PRESENCE REQUIRED: _____

YES: ____ NO: ____ NAME: _____

POINT OF CONTACT: _____ PHONE: _____

DIVISION 23 SECTION 23 05 05
HVAC PIPING, FITTINGS & VALVES
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. SUMMARY	3
1.2. SYSTEM DESCRIPTION CONDITIONS	3
1.3. QUALITY ASSURANCE	3
1.4. DELIVERY, STORAGE AND HANDLING	4
1.5. ENVIRONMENTAL REQUIREMENTS	4
1.6. ALTERNATES	4
PART 2. PRODUCTS	4
2.1. PIPE MATERIALS	4
2.2. PIPE HANGERS, ROLLER SUPPORTS, ANCHORS, GUIDES, AND SADDLES	9
2.3. VALVES	12
2.4. STRAINERS (NON-COOLING TOWER STRAINERS)	13
2.5. UNIONS, FLANGES, AND COUPLINGS	13
2.6. MANUAL AIR VENTS	14
2.7. AUTOMATIC AIR VENTS	14
2.8. THERMOMETERS	14
2.9. PRESSURE GAUGES	15
2.10. FLOW METERS	15
2.11. PIPING SPECIALTIES	15
2.12. ESCUTCHEONS	15
2.13. DIELECTRIC CONNECTIONS:	16
2.14. SLEEVES	16
2.15. PRESSURE REDUCING VALVES	16
2.16. WATER PROOF PIPE PENETRATION SEALS	17
2.17. TEST PLUGS	17
2.18. TRANSITION FITTINGS	17
PART 3. EXECUTION	18
3.1. GENERAL PIPING INSTALLATION REQUIREMENTS	18
3.2. THERMOMETER AND PRESSURE GAGE INSTALLATION REQUIREMENTS	20
3.3. VALVE INSTALLATION REQUIREMENTS	20
3.4. PIPE JOINTS INSTALLATION REQUIREMENTS	21
3.5. HANGERS, SUPPORTS, ANCHORS, GUIDES INSTALLATION REQUIREMENTS	22
3.6. AIR VENTING INSTALLATION REQUIREMENTS	23
3.7. PIPING IDENTIFICATION INSTALLATION REQUIREMENTS	24
3.8. VALVE IDENTIFICATION REQUIREMENTS	24
3.9. CLEANING PIPING AND EQUIPMENT	25
3.10. PRESSURE SEAL FITTING INSTALLATION REQUIREMENTS	25
END OF SECTION	26

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 23 05 05 - HVAC PIPING, FITTINGS AND VALVES

PART 1. GENERAL

1.1. SUMMARY

- A. The conditions of the contract and other general requirements apply to the work specified in this section. All work under this section shall also be subject to the requirements of Division 23 Section, Common Work Results for HVAC and Division 01, General Requirements.
- B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SYSTEM DESCRIPTION CONDITIONS

- A. Provide all labor and materials necessary to furnish and install all piping systems on this project as herein specified and/or shown on the drawings. Final connections to equipment furnished in other sections of the specifications shall be included under this section.
- B. All piping and insulation installed in ceiling plenums must be plenum rated and comply with NFPA and International Building Code (IBC).
- C. Where more than one piping system material is specified, ensure system components are compatible and joined to ensure the integrity of the system is not jeopardized. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.
- D. Use unions, flanges, and couplings downstream of valves and at equipment or apparatus connections. Do not use direct welded or threaded connections to valves, equipment or other apparatus.
- E. Use non-conducting dielectric connections whenever jointing dissimilar metals in open systems.
- F. Provide pipe hangers and supports in accordance with ASTM B31.9 and MSS SP69 unless indicated otherwise.
- G. Use spring loaded "silent" check valves on discharge of all pumps.
- H. Use 3/4 inch (20 mm) ball valves with cap and chain for drains at main shut-off valves, low points of piping, bases of vertical risers, and at equipment. Pipe to nearest floor drain.
- I. At all runout piping serving equipment, use swing joints with elbows to prevent excessive movement of piping due to expansion.

1.3. QUALITY ASSURANCE

- A. Valves: Manufacturer's name and pressure rating marked on valve body.
- B. All grooved joint couplings, fittings, valves, and specialties shall be the products of a single manufacturer. Grooving tools shall be of the same manufacturer as the grooved

components.

1. All castings used for coupling housings, fittings, and valve bodies shall be date stamped for quality assurance and traceability.

C. Maintain one copy of each document on site.

1.4. DELIVERY, STORAGE AND HANDLING

- A. Deliver, store, protect and handle products to site under as hereinbefore specified.
- B. Accept valves on site in shipping containers with labeling in place. Inspect for damage.
- C. Provide temporary protective coating on cast iron and steel valves.
- D. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.
- E. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed systems.

1.5. ENVIRONMENTAL REQUIREMENTS

- A. Do not install underground piping when bedding is wet or frozen.

1.6. ALTERNATES

- A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

PART 2. PRODUCTS

2.1. PIPE MATERIALS

- A. All materials, unless otherwise specified, shall be new and of the best quality of their respective kinds, and shall conform to the requirements and ordinances of local, state and insurance authorities having jurisdiction.
 1. Heating Water Supply & Return Piping, Closed Loop Chemical Treatment Piping, and Heat Pump Water Supply/Return Piping:
 - a. Manufactures: Victaulic, Grinnell, or Sure-Joint.
 - b. Pipe: Schedule 40 Black steel pipe, ASTM A53
1-1/2 inch and smaller - Type F, ASTM A53 steel (CW) with threaded joints
2 inch and larger - Grade B, Type E, ASTM A53 steel (ERW) with welded, flanged or grooved joints.
 - c. Fittings & Joints: 2-1/2 inches & larger, schedule 40 wrought steel ASTM A234 Grade WPB or Std. B16.9 long radius welding; factory-fabricated from ASTM A53 pipe; or ASTM A536 ductile iron; 2 inches & smaller 125 lb. std. cast iron screwed, ASTM Standard B16.4; or Vic-Press precision, cold drawn, stainless steel with elastomer O-ring seals. Joints

- shall be threaded or AWS D1.1 welded. Victaulic, Apollo/Shurjoint, or approved equal grooved joints shall be acceptable.
- d. Flanges: Wrought steel Class 150 welding neck. ASTM Standard B16.5.
 - e. Grooved Joint Couplings: Two ductile iron housings, pressure responsive elastomer gasket, and ASTM A449 zinc electroplated steel bolts and nuts. Couplings shall comply with ASTM F1476 Standard Specification for the Performance of Gasketed Mechanical Couplings for Use in Piping Applications.
 - i. Rigid Type: Coupling housings shall be cast with offsetting, angle-pattern bolt pads to provide joint rigidity and support and hanging in accordance with ASNI B31.1 and B31.9.
 - 1) Victaulic Style 107H, Apollo/Shurjoint Z-07, Installation-Ready or approved equal, for direct stab installation without field disassembly, with grade EHP gasket, suitable for water service to +250 degrees F.
 - ii. Flexible Type: For use in locations where vibration attenuation and stress relief are required, and for the elimination of flexible connectors. Victaulic Installation-Ready Style 177 or Style 77, or approved equal.
 - iii. Flange adapters shall be suitable for direct connection to ANSI Class 125 or 150 flanged components. Victaulic Style 741/W741, Apollo/Shurjoint 7041, or approved equal.
 - iv. Rolled form grooves only. Cut grooves are prohibited.
 - v. Verify gasket compatibility on Chemical Treatment piping.
 - f. Gate Valves: 2-1/2 inches & larger - IBBM, 150 lb. OS&Y grooved end or flanged; 2 inches & smaller - 150 lb. Bronze body bronze trim. Basis of Design: Victaulic Series 771V or approved equal.
For valves 4 inch and larger located in mechanical equipment spaces 10 feet-0 inch or greater above finished floor, valve shall have chain wheel operators with chains extending to within 6 feet-0 inch above finished floor. Chain wheels and guides shall be galvanized.
 - g. Ball Valves: Shut-off valves 2 inches and smaller shall be ball valves. Ball valves shall be 600cwp, 150swp full port, with RPTFE seats, chrome plated ball and stem 2 1/2 and larger, class 125 cast iron OS&Y IBBM gate valve, brass or bronze body, standard port, 2 piece body. Ball valves shall be VicPress end, threaded end or solder end as required to accommodate piping. Ball valves shall be as manufactured by Victaulic, Crane, Apollo, Nibco, Watts or engineer approved equal.
 - h. Globe Valves: 2-1/2 inches & larger – IBBM 125 lb.std. flanged, with No. 1 disc; 2 inches & smaller - bronze 150 lb. std. screw ends, with #1 disc.
 - i. Check Valves: 2-1/2 inches & larger – IBBM or stainless steel trim, 125 lb.std. grooved end or flanged spring-assisted swing check suitable for vertical or horizontal installation, with metal disc; 2 inch & smaller - 125 lb. std. screwed. Provide "silent" spring loaded check valves at all pump discharges. Victaulic Series 716/W715 or approved equal.
 - j. Balancing Valves: Victaulic Series 377/365, DeZurik Series 100, Fig. 118 or approved equal, ductile iron or cast iron construction, stainless steel bearings, nickel seats (3 inches and larger) non-lubricated, eccentric plug with EPDM, chlorobutyl rubber or Bunz-N resilient faced plugs suitable for 230 degrees F, semi-steel screwed with fig. 159, removable lever and

- open. nut for valves 3 inches and smaller. For valves 4-inch and larger, provide gear operators and grooved ends or flanged connections. Provide chain operated valves for sizes 4-inches and larger located 10 feet-0 inches or more above finished floor. Chains shall extend to within 6 inch-0 inches above finished floor. All valves shall have adjustable memory stop. Chain wheel and guide shall be galvanized.
- k. Butterfly Valves: Victaulic Vic300 MasterSeal/ AGS-Vic300, DeZurik, Apollo 215L series, high performance or Keystone K-Loc, type with infinite position lever (for 3-inches and smaller) and pressure-responsive seat or double seat type and memory stop. Provide gear operator on valves 4-inches and larger.
- i. Valve stem shall be stainless steel, and shall be offset from the disc centerline to provide complete 360 degree circumferential seating.
 - ii. Valve shall be rated to +250 deg F in sizes through 12-inches.
 - iii. Seat shall be elastomer, of a grade suitable for the intended service. The seat shall be pressure responsive in sizes through 12 inches.
 - iv. For valves 4 inches and larger located 10 feet-0 inches or more above finished floor shall be provided with chain operators with chains extending to within 6 feet-0 inches above finished floor. Chain wheel and guide shall be galvanized.
- l. Combination Shut-off/Balancing Valves:
Victaulic/ TA Hydronics, Taco Circuit Setter, Bell & Gossett Circuit Setter Plus, Flowset Accuset, Gerand, or as approved equal, 2-inch-3-inch 300 lb. rated Ametal (copper-alloy) body globe type or ball valve with bronze body/brass ball construction with glass and carbon filled TFE seats, in-line flow meter and balancing and shut-off valve with built in ball valve for flow adjustment. Valve shall have memory stop, calibrated nameplate, Schrader valve connections and preformed molded insulation. Valves shall be leaktight at full rated working pressure. Balance valve size shall be selected based on manufacturer's acceptable flow range and design flow rate. Pressure drop through combination shut off balance valves shall not exceed 5 feet of head at design flow rate.
- m. Extended Valve Stems: Provide and install round collar type extended valve stems on all valves installed in insulated piping. Valve stem and collar shall be selected to suit insulation thickness and maintain valve handles outside of insulation.
- n. Alternate:
- i. At contractors option all HVAC water supply and return lines may be copper type L (ASTM Std. B88) with wrought copper fittings (ASTM Std. B 16.22) with brazed or 95-5 silver solder joints lead and antimony based solders are prohibited and all bronze valves may be used on piping 2 inches and less in size.
 - ii. At Contractors option, copper press fittings may be utilized as manufactured by Viega Pro Press/ Mega Press, Apollo Press/Apollo Power Press, or Mueller Streamline Co. Viega, ProPress, and Mueller Streamline Co. Pressure Seal Fittings: Bronze or copper shall conform to ASME B16.51, ICC LC 1002, and IAPMO PS 117. ProPress fittings ½-inch thru 4- inch for use with ASTM B88 copper tube type L and ½-inch up to 1-1/4-inch

annealed copper tube. ProPress fittings shall have an EPDM sealing element and Smart Connect (SC) feature. 2-1/2-inch thru 4-inch shall have a 420 stainless steel grip ring, PBT separator ring, EPDM sealing element and leak detection feature.

2. Cooling Tower Supply/Return Piping (Inside and Outside Building):

- a. Pipe:
 - i. Schedule 80 CPVC, solid wall ASTM D1789 minimum cell classification 23447, Type IV, Grade 1 and shall be manufactured and marked to meet the requirements of ASTM F441.
- b. Fittings:
 - i. Schedule 80 CPVC, ASTM 1784 cell classification 2344713, Type IV, Grade 1 and conform to ASTM F-441. Fittings shall be Butt fusion (machine) welded where feasible, hand welded (fillet welded) by a certified welder, or solvent welded conforming to ASTM. F493 and ASTM D2846.
- c. Globe Valves:
 - i. 2-1/2" and larger – IBBM, 125 lb. std. flanged, outside screw and yoke, cast iron with bronze trim. Crane No. 351 or approved equal of listed manufacturers. Provide chain wheel and chain for valves located 12'-0" or greater above finish floor. Provide chains to terminate 6'-0" above finished floor.
- d. Check Valves:
 - i. 2-1/2" and larger – IBBM, 125 lb. std. flanged swing check, with bronze trim, bolted cap, and complies with MSS-SP-71. Crane No. 373 or approved equal of the listed manufacturers.
 - ii. 2" and smaller – 150 lb. Threaded, bronze disc, complies with MSS SP-80, Crane swing check No. 137 or approved equal of the listed manufacturers.
- e. Ball Valves:
 - i. 2-1/2" and smaller – 150 SWP, 2-piece, threaded ends, bronze construction, regular port with Type 316 stainless steel ball and Type 316 stainless steel blowout-proof stem. Provide lever handle except where lever handle will not fit, provide tee or round handle. For insulated piping, provide extension stem. Where used for balancing, provide memory stop. Milwaukee BA 100S/150S.
 - ii. 3"-6" 125 WSP, 2-piece full port cast iron flanged type with stainless steel ball and stem and lever handles up to 6". All valves shall have adjustable memory stop. Provide lever handle except where lever handle will not fit, provide tee or round handle. For insulated piping, provide extension stem. Where used for balancing, provide memory stop.
- f. Balancing Valves:
 - i. DeZurik Series PEC
 - ii. 2-1/2" and larger – cast iron body.
 - iii. 2" and smaller – bronze body, 2" and smaller – drip-tight shut-off, stainless steel bearings, bolted bonnet, nickel seats (3" and larger)

non-lubricated, eccentric plug with chlorobutyl rubber or Bunz-N resilient faced plugs suitable for 250°F, semi-steel screwed with Fig 159, removable lever and oper. Nut for valves 3" and smaller. For valves 4" and larger, provide gear operators and flanged connections. All valves shall have adjustable memory stop. Provide galvanized chain wheel, Code 103, for all gear-operated valves located 12'-0" or greater above finished floor. Provide chains to terminate 6'-0" above finished floor.

g. Butterfly Valves:

- i. 7-inch and larger shut-off valves: Bray Series 41 or equal of DeZurik, High Performance, Jamesbury High Performance, Keystone High Performance K-Loc type, or milwaukee High Performance, with gear operator, Class 150 lug style with carbon steel body, 316 stainless steel disc and extended shaft, PTFE seat ring and packing, and memory stop. Bubble tight shut-off for dead end service both ways. For valves 7 inches and larger with valve centerline located 12'-0" or more above finished floor shall be provided with chain operators with chains extending to within 6'-0" above finished floor. Chain wheel and guide shall be galvanized.

h. Combination Shut-Off/Balancing Valves:

- i. 2" and Less – Flowset Accusetter Plus, Flowpak, Griswold, Nexus or Bell & Gossett Cirbuit Setter Plus, 250 lb. bronze body/brass ball flow control plug or equal percentage globe style resin construction with glass and carbon filled TFE seats, in-line flow meter and balancing and shut-off valve with built in valve for flow adjustment and threaded connections. Two (2) 1/4" NPT Brass body extended Superseal P/T metering points with EPDM check and gasketed cap, two 1/4" drain tapings. Valve shall have memory stop, calibrated metal nameplate, connections and preformed insulation (or extended P/T's and handles when field lagged). Valve shall be suitable for horizontal or vertical mounting. Provide Schedule in Submittal Data.

i. Extended Valve Stems:

- i. Provide and install round collar type extended valve stems on all valves installed in insulated piping. Valve stem and collar shall be selected to suit insulated piping. Valve stem and collar shall be selected to suit insulation thickness and maintain valve handles outside of insulation.

3. Open Loop Chemical Treatment Piping: Schedule 40 PVC Pressure Pipe, Valves, and Fittings.

- B. Steel pipe shall be similar and equal to National Tube Company, Grinnell, Republic, or Bethlehem black or zinc-coated (galvanized) as hereinafter specified. Pipe shall be free from all defects which may affect the durability for the intended use. Each length of pipe shall be stamped with the manufacturer's name.

- C. Copper pipe shall be Revere, Anaconda or Chase with approved solder fittings.

2.2. PIPE HANGERS, ROLLER SUPPORTS, ANCHORS, GUIDES, AND SADDLES

- A. All hangers for metallic piping shall be adjustable, wrought clevis type, or adjustable malleable split ring swivel type, having rods with machine threads. Hangers shall be Grinnell Company's Figure 260, Victaulic, or Shurjoint for pipe ¾-inch and larger, and Figure 65 for pipe 2-inches and smaller, or approved equal Victaulic, Shurjoint, Carpenter Patterson, or approved equal. Adjustable pipe stanchion with U-bolt shall be Grinnell Company's Figure 191. Pipe roller supports shall be Grinnell's Figure 181 or Figure 271 Victaulic or Shurjoint. Exterior pipe hangers shall be galvanized or stainless steel construction. For copper piping in direct contact with the hanger, hanger construction shall be copper coated to prevent contact of dissimilar metals similar to Grinnell's Figure CT-65. Hanger spacing and rod sizes for steel and copper pipe shall not be less than the following:

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
¾ & 1	6	5	3/8
1 - ½	6	8	3/8
2	8	8	3/8
2 – ½	10	9	½
3	12	10	½
4	14	12	5/8

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
5	14	12	5/8
6	16	14	3/4
8	18	16	7/8
10	20	18	7/8
12	20	18	7/8

- B. Install hangers for PVC piping with the following maximum horizontal spacing and minimum rod diameters.
- C. Install hangers for PVC piping with the following maximum horizontal spacing and minimum rod diameters:
1. NPS 1 ½ and NPS 2 (DN and DN 50): 48 inches (1200 mm) with 3/8 inch (10-mm) rod.
 2. NPS 3 (DN 80): 48 inches (1200 mm) with ½ inch (13 mm) rod.
 3. NPS 4 and NPS 5 (DN 100 and DN 125): 48 inches (1200 mm) with 5/8 inch (16 mm) rod.
 4. NPS 6 (DN 150): 48 inches (1200 mm) with 3/4 inch (19 mm) rod.
 5. NPS 8 to NPS 12 (DN 200 to DN 300): 48 inches (1200 mm) with 7/8 inch (22 mm) rod
- D. Install supports for vertical PVC piping every 48 inches (1200 mm).

- E. Spacing of hangers for polypropylene pipe (where specified) shall be as follows:
 - 1. 2-inches & smaller - every 2 feet
 - 2. Larger than 2-inches - every 3 feet
 - 3. Plastic piping shall not be installed in ceiling plenums per NFPA.]
- F. Anchors, guides, and roller supports shall be installed in accordance with the contract drawings and manufacturer's recommendations to provide pipe support and control pipe movement for all piping systems. Anchors and guides shall be securely attached to the pipe support structure. Submit shop drawing for proposed pipe support structure for guides and anchors for approval of the Structural Engineer. Pipe alignment guides shall be Fig. 255 Grinnell, or as approved equal. Guides shall be sized to accommodate the pipe with insulation. Guides shall be steel factory, fabricated, with bolted two section outer cylinder and base for alignment of piping and two section guiding spider for bolting to pipe.
- G. Hangers for pipe sizes ½ to 1 ½ inch (13 to 38 mm): Carbon steel, adjustable swivel, split ring.
- H. Hangers for cold pipe sizes 2 inches (50 mm) and over: Carbon steel, adjustable, clevis.
- I. Hangers for cold pipe sizes 2 to 4 inches (50 to 100 mm): Carbon steel, adjustable, clevis.
- J. Hangers for cold pipe sizes 6 inches (150 mm) and over: adjustable steel yoke, cast iron roll, double hanger.
- K. Multiple or Trapeze hangers: Steel channels with welded spacers and hanger rods.
- L. Multiple or Trapeze hangers for hot pipe sizes 6 inches (150 mm) and over: Steel channels with welded spacers and hanger rod, cast iron roll.
- M. Wall support for pipe sizes to 3 inches (76 mm): cast iron hook
- N. Wall support for pipe sizes 4 inches (100 mm) and over: Welded steel bracket and wrought steel clamp.
- O. Wall support for hot pipe sizes 6 inches (150 mm) and over: welded steel bracket and wrought steel clamp with adjustable steel yoke and cast iron roll.
- P. Vertical Support: Steel riser clamp.
- Q. Floor support for cold pipe: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
- R. Floor support for hot pipe sizes to 4 inches (100 mm): Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
- S. Floor support for hot pipe sizes 6 inches (150 mm) and over: Adjustable cast iron roll and stand, steel screws, and concrete pier or steel support.
- T. Copper pipe support: Carbon steel ring, adjustable, copper plated.

- U. Hanger rods: Mild steel threaded both ends, threaded one end, or continuous threaded.
- V. Inserts: Malleable iron case of galvanized steel shell and expander plug for threaded connection with lateral adjustment, top slot for reinforcing rods, lugs for attaching to forms; size inserts to suit threaded hanger rods.
- W. For exterior pipe supports provide stainless steel, supports, brackets, hardware and anchors.

2.3. VALVES

- A. Provide parts list and assembly drawings (exploded view) for all valves in shop drawing submittals. Provide valves of the same type by the same manufacturer.
- B. Check valves in base mounted pump discharges shall be of the vertical type and shall be Victaulic Series 716/ W715, Miller "non-slam" check valves, Apollo/Shurjoint SJ-900, Grinnell, Sure-Joint, or approved equal suitable for service intended. Check valves in circulator discharges shall be horizontal type.
- C. Provide at each closed loop base mounted pump a suction diffuser of size and type shown on drawings. Units shall consist of a ductile cast iron angle type body with inlet vanes, magnetic insert, and blowdown connection tapped gauge post, 125 psi ANSI flange and a combination stainless steel diffuser strainer with 5/32 or 3/16-inch diameter opening for pump protection. Unit shall be equipped with a disposable fine 20-mesh stainless steel start up strainer which shall be removable after 30 days. For cooling tower pumps, suction diffusers shall not be provided and in place of the suction diffusers, strainers shall be installed and shall be located at least 5 pipe diameters upstream of the pump suction flanges. Flow direction shall be from inside the strainer to outside for ease of service and cleaning. The body shall fit the pump and connecting pipe size. The unit shall be provided with a base support boss or an adjustable support foot to relieve piping strains from the pump suction. Suction diffuser shall be Victaulic 731 Series, Taco "SD" Series Catalog 300-4.1, Bell and Gossett Model FLG, Armstrong, Patterson, Apollo/Shurjoint 725F, or engineer approved equal.
- D. Cooling tower (open loop) pump suction strainers shall be Watts Series 77F-BI or approved equal. Cooling tower pump suction strainers shall be bronze, flanged wye-pattern strainers with blow down valves. The seal shall be machined allowing the stainless steel screen to be self-aligning and assure a perfect fit. The strainer cover shall be a bolted type cover with PTFE gasket. Furnish with tapped blow down plug and install blow down valve. The strainer screen shall be low pressure drop, 304 stainless steel large mesh screen. The stainless steel strainer perforations shall be 1/4 inch minimum. Fine mesh strainers shall be installed downstream of the cooling tower pumps as indicated on the contract documents.
- E. Multi-purpose valve (non-slam check valve, throttling valve, shut-off valves and calibrated balancing valve) shall be provided at discharge side of constant speed pumps. The valve shall be of heavy-duty cast iron construction with standard ANSI flanged connections and rated for a maximum working pressure of 175 psig at 240°F. The valve shall be fitted with a stainless steel stem or stem sleeve and brass seat with "O" ring seal. Valve shall be Taco "Plus One" Number 300-4.2, Bell and Gossett 3DS Triple Duty Valve, Armstrong, Patterson, or as approved equal, and shall have check and plug valve features plus a memory stop with pointer and scale. Provide additional shut-off valve to allow servicing of check valve if a multipurpose valve is utilized in lieu of separate check, shut-off, and

balance valve. Provide additional shut-off valve downstream of multi-purpose valve to allow servicing of multi-purpose check valve feature. Provide pre-manufactured, removable insulation covers for all multipurpose valves.

- F. Triple Duty Valve Assembly: Assembly shall consist of a Victaulic Master Seal, Apollo/Shurjoint SJ-900, Grinnell, Sure-Joint, or approved equal butterfly valve with memory stop and a Series 779 Venturi-Check, rated for water service to 230 degrees Fahrenheit (110 degrees Celsius) and pressures to 300 psig (2065-kPa).
 - 1. For 14" through 24" sizes, Victaulic AGS-Vic300, Apollo/Shurjoint SJ-300N-L/SJ-300N-W, Grinnell, Sure-Joint, or approved equal butterfly valve with Series W715 AGS check valve, rated for pressures to 230 psig (1575-kPa).
- G. Do not install multipurpose valves or balance valves on the discharge of variable speed pumps.

2.4. STRAINERS (NON-COOLING TOWER STRAINERS)

- A. Refer to 2.3 Valves, for open loop cooling tower strainers.
- B. Strainers shall be of the basket or "Y" type and shall be heavy and durable, constructed of ductile iron to ASTM A536 or the best grade gray iron with the bottoms drilled and plugged. Bodies shall have arrows clearly cast on the sides to show flow direction. Strainers shall be equipped with easily removable covers and brass sediment baskets made of stainless steel or brass not less than #22 gauge in thickness. Total area of basket perforations shall be not less than four times the cross section of the entering pipe. Flow shall be into basket, and then out through the perforations. Strainers shall be suitable for water or the intended fluid. Strainers 2 inches and smaller shall have threaded or solder ends, 2 inches and larger shall have flanged ends.
- C. Strainer screens shall be stainless steel with perforations and shall be 1/16-inch for pipe sizes 5 inches and less, 1/8-inch (40 percent open area) perforations for pipe sizes 6-inch and greater.
- D. Provide valved and capped (with chain) blowdowns in each strainer. Blowdown valves shall be Apollo 78-100/200 series or as approved equal.
- E. Strainers shall be manufactured by Victaulic Style 732/W732, Watts, Mueller, Armstrong, Yarway, Spirax/Sarco, Apollo/Shurjoint 726, or as approved equal.

2.5. UNIONS, FLANGES, AND COUPLINGS

- A. Unions in steel pipe 2-inches and smaller shall be malleable iron with brass inserted seats designed for a working pressure of 150 psig.
- B. Unions in copper pipe 2-inches and smaller shall be sweat fittings with bronze seats designed for a working pressure of 125 psig.
- C. Unions in stainless steel pipe 2-inches and smaller shall be hexagonal threaded type stainless steel unions, with VicPress ends. Basis of Design: Victaulic Style P584.

- D. Flanges for steel pipe over 2 inches shall be 150 psig, forged steel, slip on. Gaskets shall be 1/16 inch thick pre-formed neoprene.
- E. Flanges for copper pipe over 2 inches shall be bronze. Gaskets shall be 1/16 inch thick preformed neoprene.

2.6. MANUAL AIR VENTS

- A. Manual air vents shall be similar to the hereinafter specified gauge valves. Provide 1/4-inch size on 3/4-inch pipe and smaller, 1/2 -inch size on 1-inch pipe and larger. Install at all high points of piping. Valves shall be Crane No. 88, or as approved equal, with threaded ends, bronze body, bronze or brass bonnet and bronze stem.

2.7. AUTOMATIC AIR VENTS

- A. Provide at existing heat exchangers, air separators, expansion tanks and where shown on the drawings, float actuated non-modulating high capacity air vent to purge free air from the system and provide a positive shut-off at pressures up to 150 psig at a maximum temperature of 250 degrees Fahrenheit. The high capacity air vent shall prevent air from entering the system if the system pressure drops below atmospheric pressure. The air vent shall be pilot operated for intermittent purging of free air up to pressures of 2 psig during normal system operation and diaphragm operated for full capacity purging of free air at pressures between 2 and 150 psig. The high capacity air vent shall be constructed of cast iron and fitted with components of type 313 stainless steel, brass, EPDM and silicone rubber. Pipe discharge to closest floor drains with Type K copper tubing. The high capacity vent shall be Model 107 by Bell and Gossett, Model 13w by Spirax Sarco, Taco, Spirotherm Spirotop, or as approved equal.

2.8. THERMOMETERS

- A. Unless otherwise indicated, thermometers shall be ASTM E1, in a glass type, organic filled, 9-inch scale size, corrosion-resistant metal case, with "any-angle" mounting with positive locking device. Trerice Industrial Thermometers, Weksler Instruments, Ernst Gage Co., Miljoco, or approved equal. Insertion stem length shall suite the pipe size and configuration. Thermometer wells shall be brass with brass union hubs in copper and in ferrous piping. Where piping is insulated or otherwise covered, use wells with lagging extension. Where wells are installed in pipe tees at turns, increase pipe size so that well does not restrict flow. Accuracy shall be 2 percent.
- B. Unless otherwise indicated, thermometer ranges shall be as follows:
 - 1. Heat pump water systems: 30 degrees F to 100 degrees Fahrenheit, 1 degrees Fahrenheit Division
 - 2. Cooling tower water systems: 30 degrees Fahrenheit to 100 degrees Fahrenheit, 2 degrees Fahrenheit Division.
 - 3. Heating water systems: 30 degrees Fahrenheit to 240 degrees Fahrenheit, 2 degrees Fahrenheit Division.
- C. Provide heat conducting compound in wells.

2.9. PRESSURE GAUGES

- A. Unless otherwise indicated, pressure gauges shall be the bronze bourdon tube type, 4-1/2-inch dial, stem mounting, cast aluminum adjustable pointer, 1 percent accuracy over middle half of scale range, 1-1/2 percent over balance: Trerice Model 600C; Weksler Instruments, Ernst Gage Co., Miljoco, or as approved equal.
- B. Gauges shall have pressure, vacuum, compound, or retard ranges as required, select ranges so that the normal readings are at the approximate midpoint and maximum system pressures do not exceed full scale.
- C. Furnish and install a gauge valve at each pressure gauge. Gauge valves shall be Crane Model No. 88, Needle Valve, Ernst Gage Co. FLG 200, Wexler Instrument Corp. Type BBV4, or approved equal, rated for pressure intended.
- D. Gauge connections for pressure gauges, thermometers, or control instruments shall be made using tee fittings, except that gauge connections up to 1-inch size in steel may be using threaded extra heavy pipe couplings welded directly to the main, provided that the main is at least 2-inch size for 2-inch connections, 3-inch size for 3/4-inch connections, and 4-inch size for 1-inch connections. Minimum gauge connection shall be 2-inch ips.
- E. Provide snubbers on all gauges. Snubbers shall be No. 872 by Trerice, RS1/RS6 by Wexler Instruments, Miljoco or as approved equal.

2.10. FLOW METERS

- A. Griswold or Bell & Gossett Venturi disturbed flow measurement quickset flow meters shall be utilized in lieu of sentinel type flow meters. Units shall consist of a spun steel venturi welded into the pipe. Disturbed fluid shall be channeled through the throat of the venturi with a multi-point Piezo Ring. Accuracy shall be $\pm 1\%$ PSID with no straight pipe run required. Furnish differential pressure gauge supplied with carrying case and hoses.

2.11. PIPING SPECIALTIES

- A. Furnish and install flexible pipe connections, as specified and/or shown on the drawings, at suction and discharge connections of all base mounted and vertical in-line pumps, all vibrating equipment, and elsewhere as shown. Refer to Division 23 Section, Vibration Controls for HVAC and Plumbing Equipment for specifications.
- B. Pressure relief valves shall be provided in the number and sizes required to relieve 110 percent of the full input to the systems. Valves shall be rated; and installed in accordance with ASME, and CSD-1 including all amendments. Pipe discharge full size to floor drain, (with union) and support discharge pipe to prevent exerting any strain on relief valve body, piping to be Type-L copper. Water safety relief valves shall be Watts Series 740, Conbraco, Series 154A, Bell and Gossett, or approved equal. Provide pressure gauge adjacent to all safety relief valves.

2.12. ESCUTCHEONS

- A. Provide chromium plated escutcheons properly fitted and secured with set screws on all exposed piping which passes through walls, floors or ceilings of finished spaces.

- B. All escutcheon plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface. Plastic escutcheon plates will not be accepted.

2.13. DIELECTRIC CONNECTIONS:

- A. Furnish and install electrically insulated dielectric waterway fittings, unions or flanges, as manufactured by Victaulic Company Style 47, EPCO Sales, Inc., or approved equal at the following locations:
 - 1. Where steel piping systems join copper piping.
 - 2. Where copper tube connects to cooling towers/closed circuit fluid coolers, heat exchangers, and other steel vessels.
 - 3. Avoid the installation of steel nipples, cast iron or steel valves and specialties, or other ferrous components in predominately copper piping systems. Where such installation is necessary, isolate the component with dielectric connections. Do not mix steel pipe and copper tube in the same run of pipe or in the same section of a piping system.
 - 4. Dielectric Waterway: Copper silicon casting conforming to UNS C87850 with grooved and/or threaded ends. UL classified in accordance with NSF-61 for potable water service, and shall meet the low-lead requirements of NSF-372. Basis of Design: Victaulic Series 647.

2.14. SLEEVES

- A. Sleeves shall be provided around all pipes through walls, floors, ceilings, partitions, roof structure members or other building parts. Sleeves shall be standard weight galvanized iron pipe two sizes larger than the pipe or insulation so that pipe or insulation shall pass through masonry or concrete walls or floors. Provide 20 gauge galvanized steel sheet or galvanized pipe sleeves for all piping passing through frame walls.
- B. Sleeves through floors shall be flush with the floor except for sleeves passing through Equipment Rooms which shall extend 3/4-inch above the floor. Refer to Division 23 Section, Vibration Controls for HVAC and Plumbing Equipment for mechanical equipment room penetrations additional requirements. Space between the pipe and sleeve shall be caulked. Escutcheon plates shall be constructed to conceal the ends of sleeves. Each trade shall be responsible for drilling existing floors and walls for necessary sleeve holes. Drilling methods and tools shall be as hereinbefore specified.
- C. Sleeves through walls and floors shall be sealed with a waterproof caulking compound.
- D. Firestop at sleeves that penetrate smoke barriers smoke partitions and/or rated walls/floors.

2.15. PRESSURE REDUCING VALVES

- A. Provide pressure reducing valves as indicated, of size and capacity selected by the installer to maintain operating pressure on the system. Body shall be cast-iron or bronze construction, renewable stainless steel seat, non-corrosive disc, water tight cage assembly, adjustable pressure ranges and inlet strainer Watts Regulator Model 223-S, Armstrong,

Bell and Gossett, Apollo 36LFPR, or as approved equal.

- B. Provide pressure gauge adjacent to all pressure reducing valves to verify proper set point.

2.16. WATER PROOF PIPE PENETRATION SEALS

- A. Provide and install waterproof pipe penetration seals at all pipes that enter the building below grade or through exterior wall.
- B. Link seals are to be Metraflex Metraseals, Model MS, Linkseal, or approved equal, black EPDM seal material, glass reinforced plastic pressure plates, zinc plated nuts and bolts, seals are to be resistant to sunlight and ozone, pressure rated to make a hydrostatic seal of up to 20 psig and up to 40 feet of head, temperature rated from -40 degrees F to 250 degrees Fahrenheit.

2.17. TEST PLUGS

- A. Where indicated, furnish and install P/T plugs or Pete's Plugs as manufactured by IMAC Systems or approved equal.
- B. Description: Nickel-plated, brass-body test plug in NPS 2 (DN15) fitting. Test plugs shall be as manufactured by Trerice, Watts, Natural Meter, Apollo Brass Test Plugs, or approved equal. Test-station fitting made for insertion in piping tee fitting.
- C. Body: Length as required to extend beyond insulation. Brass or stainless steel with core inserts and gasketed and threaded cap. Include extended stem on units to be installed in insulated piping.
- D. Thread Size: NPS ¼ (DN 8) or NPS ½ (DN15) as required, ASME B1.20.1 pipe thread.
- E. Pressure Rating: 500 psig minimum.
- F. Minimum Pressure and Temperature Rating: 500 psig at 200 deg F.
- G. Core Inserts: One or two self-sealing valves, suitable for inserting 1/8 inch OD probe from dial-type thermometer or pressure gage. Chlorosulfonated polyethylene synthetic and EPDM self-sealing rubber.
- H. Core Insert: Self-sealing valve, suitable for inserting 1/8 inch OD probe from dial-type thermometer or pressure gage.
- I. Core Material for Air, Water, Oil, and Gas: 20 to 300 degrees F chlorosulfonated polyethylene synthetic rubber.
- J. Test-Plug Cap: Gasketed and threaded cap, with retention chain or strap.
- K. Pressure Gage and Thermometer Ranges: approximately two times the system's operating conditions.
- L. Self-closing valves with caps and retaining straps.

2.18. TRANSITION FITTINGS

- A. General Requirements:
 - 1. Same size as pipes to be joined.
 - 2. Pressure rating at least equal to pipes to be joined.
 - 3. End connections compatible with pipes to be joined.
- B. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.
- C. Plastic-to-Metal Transition Fittings:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Charlotte Pipe and Foundry Company.
 - b. Harvel Plastics, Inc.
 - c. Spears Manufacturing Company.
 - 2. Description: PVC or CPVC one-piece fitting with manufacturer's Schedule 80 equivalent dimensions; one end with threaded brass insert and one solvent-cement-socket end.
- D. Plastic-to-Metal Transition Unions:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Colonial Engineering, Inc.
 - b. NIBCO INC.
 - c. Spears Manufacturing Company.
 - 2. Description: PVC or CPVC four-part union. Include brass threaded end, solvent-cement-joint plastic end, rubber O-ring, and union nut.

PART 3. EXECUTION

3.1. GENERAL PIPING INSTALLATION REQUIREMENTS

- A. All pipes shall be cut accurately to measurements established at the building, and shall be worked into place without springing or forcing, properly clearing all windows, doors and other openings. Excessive cutting or other weakening of the building structure to facilitate piping installation will not be permitted. All pipes shall be so installed as to permit free expansion and contraction without causing damage. All horizontal mains shall pitch down in the direction of flow with a grade of not less than 1 inch in 40 feet. All open ends of pipe lines, equipment, etc., shall be properly capped or plugged during installation to keep dirt or other foreign material out of the system. All pipes shall be run parallel with the lines of the building and as close to walls, columns and ceilings as may be practical, with proper pitch. All piping shall be arranged so as not to interfere with removal of other equipment on devices not to block access to doors, windows, manholes, or other access

openings. Flanges or unions, as applicable for the type of piping specified, shall be provided in the piping at connections to all items of equipment, coils, etc., and installed so that there will be no interference with the installation of the equipment, ducts, etc. All valves and specialties shall be placed to permit easy operation and access and all valves shall be regulated, packed and glands adjusted at the completion of the work before final acceptance. All piping shall be installed so as to avoid air or liquid pockets throughout the work. Ends of pipe shall be reamed so as to remove all burrs.

- B. All piping shall be graded to convey entrained air to high points where automatic air vents shall be provided. The size of supply and return pipes for each piece of equipment shall in no case be smaller than the outlets in the equipment.
- C. All piping shall be run to provide a minimum clearance of 2-inches between finished covering on such piping and all adjacent work. Group piping wherever practical at common elevations.
- D. All valves, strainers, caps, and other fittings shall be readily accessible.
- E. Drain valves with hose connections shall be provided at low points for drainage of piping systems. Blow down valves shall be provided at the ends of all mains and branches so as to properly clean by blowing down the lines throughout in the direction of normal flow.
- F. Discharge lines from all relief valves shall be piped to within 4-inches of floor and extend to floor drains wherever floors are not pitched to drains. Pitch the relief valve piping away from the relief valve to insure that no fluid can be trapped in valve discharge. Support all relief valve piping to prevent exerting strain on the relief valve body. The end of the relief valve discharge piping shall not be threaded to prevent capping or plugging.
- G. All branches from water mains shall be taken from the top of the supply mains at an angle of forty-five (45) degrees above the horizontal, unless otherwise directed. Branches feeding down shall be taken from the side or bottom of the main on water mains only. All connections shall be carefully made to insure unrestricted circulation, eliminate air pockets or trapped condensate, and permit the complete drainage of the system.
- H. Cutoff valves shall be provided on each branch line from the mains on all heating/air conditioning lines.
- I. Shut-off valves shall be installed at the inlet and outlet of each coil and piece of equipment to permit isolation for maintenance and repair. Units having multiple coils shall have separate valves for each coil.
- J. Balancing valves shall be installed in all heating/air conditioning water branches and at all pumps, and where indicated on the drawings.
- K. Unions shall be installed on all bypasses, ahead of all traps, at all connections to equipment, where shown on drawings or where required to facilitate removal of equipment whether shown or not.
- L. Spring clamp plates (escutcheons) shall be provided where pipes are exposed in the building and run through walls, floors, or ceilings. Plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface.

- M. If the size of any piping is not clearly evident in the drawings, the Contractor shall request instructions for the Engineer as to the proper sizing. Any changes resulting from the Contractor's failure to request clarification shall be at his expense. Where pipe size discrepancies or conflicts exist in the drawings, the larger pipe size shall govern.
- N. Install all valves with stem upright or horizontal, not inverted.
- O. Where pipe support members are welded to structural building framing, scrape, brush clean, weld and apply one coat of zinc rich primer.
- P. Provide clearance for installation of insulation and access to valves and fittings.
- Q. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed system.
- R. All water containing pipes shall be routed clear of combustion air dampers and louvers to prevent freezing condition when dampers are open.
- S. Provide manual air vents at top of piping systems.

3.2. THERMOMETER AND PRESSURE GAGE INSTALLATION REQUIREMENTS.

- A. Install thermometers and adjust vertical and tilted positions.
- B. Install separable sockets in vertical position in piping tees where fixed thermometers are indicated.
 - 1. Install with socket extending to one-third diameter of pipe.
 - 2. Fill sockets with oil or graphite and secure caps.
- C. Install pressure gages in piping tees with pressure-gage valve located on a pipe at most readable location.
- D. Adjust faces of thermometer and gages to proper angle for best visibility.
- E. Clean windows of thermometer and gages and clean factory-finished surfaces. Replace cracked and broken window, and repair scratched and marred surfaces with manufacturer's touch up paint.
- F. Install pressure gauges on both sides of all strainers.

3.3. VALVE INSTALLATION REQUIREMENTS

- A. Examine piping system for compliance with requirements for installation tolerances and other conditions affecting performance of valves. Do not proceed with installation until unsatisfactory conditions have been corrected.
- B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

- C. Operate valves from fully open to fully closed positions. Examine guides and seats made accessible by such operation.
- D. Examine threads on valve and mating pipe for form and cleanliness.
- E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Check gasket material for proper size, material composition suitable for service, and freedom from defects and damage.
- F. Do not attempt to repair defective valves; replace with new valves.
- G. Install valves as indicated, according to manufacturer's written instructions.
- H. Piping installation requirements are specified in other Division 23 Sections. Drawings indicate the general arrangement of piping, fittings, and specialties.
- I. Install valves with unions or flanges at each piece of equipment arranged to allow servicing, maintenance, and equipment removal without system shutdown.
- J. Locate valves for easy access and provide separate support where necessary.
- K. Install valves in horizontal piping with stem at or above the center of the pipe.
- L. Install valves in a position to allow full stem movement.
- M. For chain wheel operators, extend chains to 60 inches above finished floor elevation.
- N. Adjust or replace packing after piping systems have been tested and put into service, but before final adjusting and balancing. Replace valves if leak persists.

3.4. PIPE JOINTS INSTALLATION REQUIREMENTS

- A. Grooved Joints: Grooved joint shall be installed in accordance with the manufacturer's written recommendations. Grooved ends shall be clean and free from indentations, projections, or roll marks. The gasket shall be molded and produced by the coupling manufacturer of an elastomer suitable for the intended service. The coupling manufacturer's factory trained representative shall provide on-site training for the contractor's field personnel in the use of grooving tools and installation of product. The representative shall periodically visit the job site to ensure best practices in grooved product installation are being followed. (A distributor's representative is not considered qualified to conduct the training.)
- B. Screwed Joints: All screwed joints shall be made with tapered threads properly cut. Screwed joints shall be made perfectly tight with a stiff mixture of graphite and oil, applied with a brush to the male threads on the fittings.
- C. Brazed Joints and Copper Piping: Joints in copper piping shall conform to the following minimum standards.
 - 1. The pipes shall be cut to a length making certain that the ends are square, using a fins hacksaw blade or tube cutter. The ends of all pipes shall be reamed and all burrs removed.

2. The outside end of the pipe and the cut end of the fitting shall be cleaned with steel wool, sand cloth, or steel wire brush. All dark spots shall be removed.
 3. The flux shall be applied evenly and sparingly to the outside end of the pipe and the inside of the outer end of the fitting until all surfaces to be jointed are completely covered. The piping and fitting shall be slipped together and reworked several times to insure an even distribution of the flux.
 4. The correct amount of brazing material per joint for each size pipe shall be used in accordance with the manufacturer's recommendations.
 5. Brazed joints shall be made by using a direct flame from a torch.
 6. On pipe sizes larger than 1/4-inch, the fittings and valves in the pipe shall be moved or tapped with a hammer when the brazing material starts to melt to insure an even distribution of the brazing material.
 7. The excess brazing material shall be removed while it is still in the plastic state leaving a fillet around the cup of the fitting.
 8. Brazed joints shall be suitable for working pressure of 550 psig and for working temperature of not less than 250 degrees F. The type of brazing material and flux used will be submitted for approval. Type 95-5 shall be the minimum standard.
 9. Lead and antimony-based solders shall not be used for potable water systems. Brazing and silver solders are acceptable.
- D. Where copper piping joins steel piping, approved bronze adapters shall be used.
- E. Prohibited Connections: No direct weld or brazed connections without unions or flanges, shall be made to valves, strainers, apparatus, or related equipment. Right and left couplings, long threads, or caulking of pipe threads or gasket joints will not be permitted.
- F. Plastic piping solvent cement joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:
1. Comply with ASTM F 402 for safe handling practice of cleaners, primers, and solvent cements. Apply primer.
 2. PVC Piping: Join according to ASTM D2855.

3.5. HANGERS, SUPPORTS, ANCHORS, GUIDES INSTALLATION REQUIREMENTS

- A. General: All hangers shall be of an approved type arranged to maintain the required grading and pitching of lines to prevent vibration and to provide for expansion and contraction. Provide protection saddles between hangers and insulation on heating water insulated pipe. Saddles shall be Grinnells Figure 173/273 or approved equal. Provide approved spacers between saddles and pipe where flexible insulation is specified. Provide insulation protection shields for insulated piping without saddles. Shield shall be Grinnell Figure 167 or as approved equal.

- B. Spacing: Regardless of spacing, hangers shall be provided at or near all changes in direction, both vertical and horizontal, for all piping. For cast iron soil pipe, one hanger shall be placed at each hub or bell.
- C. Vertical Lines: Shall be supported at their bases, using either a suitable hanger placed in a horizontal line near the riser, or a base type fitting set on a pedestal, foundation or support. All vertical lines extending through more than one floor level shall be supported at each floor with a riser clamp. Riser clamp shall be Grinnell Co.'s Figure 261, or approved equal. All vertical drops to pump suction elbows shall be supported by floor posts.
- D. Racks and Brackets: All horizontal piping on vertical walls shall be properly supported by suitable racks securely anchored into the wall construction. Where not practical to obtain ceiling anchorage, all piping near walls shall be supported by approved brackets securely anchored into the wall construction. Washer plates (Fib. 60, 60L) and other miscellaneous attachments, fasteners, etc., shall be Grinnell or as approved equal. All exterior hanger and bracket systems in their entirety shall be galvanized.
- E. Pipe Hangers and supports shall be attached to the panel point at the top chord of bar joist or at a location approved by the structural engineer.
- F. Select hangers and components for loads imposed. Secure rods with double nuts.
- G. Support of horizontal piping shall allow for vertical adjustment after installation of piping.
- H. Support overhead piping with clevis hangers.
- I. Do not support all parallel piping from the same joist. Stagger all supports in accordance with the engineer's recommendations.
- J. Install guides on piping adjoining expansion fittings and loops.
- K. Attach guides to pipe and secure to building structure.
- L. Install anchors at locations to prevent stresses from exceeding those permitted by ASME B31.9 and to prevent transfer of loading and stresses to connected equipment.
- M. Fabricate and install steel anchors by welding steel shapes, plates, and bars to piping and to structure. Comply with ASME B31.9 and AWS D1.1.
- N. Construct concrete anchors of poured in place concrete of dimensions indicated and include embedded fasteners.
- O. Install pipe anchors according to expansion fitting manufacturer's written instructions if expansion fittings are indicated.
- P. Use grout to form flat bearing surfaces for expansion fittings, guides, and anchors installed on or in concrete.

3.6. AIR VENTING INSTALLATION REQUIREMENTS

- A. The top of each hydronic water supply and return piping and other points as indicated or where necessary for the removal of air from the system or equipment, shall be vented using

an approved type of manual air vent.

- B. In addition to manual air vents at high points of system, each item of water heat transfer equipment shall be manually vented using an approved type manual air vent. All air vents shall be accessible.

3.7. PIPING IDENTIFICATION INSTALLATION REQUIREMENTS

- A. All piping shall be identified with painted background marked with the name of the service with arrows to indicate flow direction. Color code and system identification shall comply with ANSI Standards and piping identification system shall comply with ASME A13.1-81., scheme for the identification of piping systems and ASHRAE Fundamentals Handbook, latest edition.
- B. Markings shall be plain block letters, stenciled on pipes, and shall be located near each branch connection, near each valve, and at least every 10 feet on straight runs of pipe. Where pipes are adjacent to each other, markings shall be neatly lined up. All markings shall be located in such manner as to be easily legible from the floor. Pipe identification schedule shall be as follows:

OUTSIDE DIAMETER OF PIPE OR COVERING (INCHES)	LENGTH OF COLOR FIELD (INCHES)	SIZE OF LETTERS (INCHES)
$\frac{1}{2}$ to $1 \frac{1}{4}$	8	$\frac{1}{2}$
$1\text{-}\frac{1}{2}$ to 2	8	$\frac{3}{4}$
$2 \frac{1}{2}$ to 6	12	$1 \frac{1}{4}$
8 to 10	24	$2 \frac{1}{2}$
Over 10	32	$3 \frac{1}{2}$

3.8. VALVE IDENTIFICATION REQUIREMENTS

- A. All valves shall be tagged with a numbered tag.

- B. The tags shall be made of 1-inch diameter brass tags fastened to the valve by means of brass chains. Numbers shall agree with valve numbers on diagrammatic herein before specified.
- C. Provide a minimum of three (3) valve charts with valve numbers indicating valve type, size, manufacturer and service.
- D. Additional valve charts shall be mounted behind glazed wooden frames and be hung in each mechanical equipment room including each air handling unit mechanical equipment room. Additional copies shall be provided in each copy of the O&M manuals.

3.9. CLEANING PIPING AND EQUIPMENT

- A. All heat pump water, heating water, HVAC closed circuit evaporative fluid cooler and cooling tower systems shall be cleaned by filling with a solution of one (1) pound of trisodium phosphate to each 50 gallons of water and circulating this solution for a period of six (6) hours during which time the system shall reach operating temperature. The systems shall then be flushed with fresh water and refilled with fresh water and purged of all air.
- B. All heat pump water, heating water, HVAC, and closed circuit evaporative fluid cooler/cooling tower piping system shall be flushed clean with fresh water. See Division 22 Sections, Plumbing Fixtures and Plumbing Equipment for domestic potable water cleaning and sterilization.
- C. Any equipment, such as coils that have small tubing, shall be bypassed to prevent deposition of debris from the piping. Water balancing shall not be scheduled until the completion of the cleaning and treatment process.
- D. All strainers shall be inspected and cleaned prior to testing and balancing. In addition, prior to substantial completion, contractor must inspect and clean all strainers.
- E. Where new equipment is connected to existing piping systems, install temporary bypasses as required for flushing new equipment piping.

3.10. PRESSURE SEAL FITTING INSTALLATION REQUIREMENTS

- A. Viega, ProPress Pressure Seal bronze or copper fittings: Sealing element shall be verified for the intended use. Tube ends shall be cut on a right angle (square) to the tube. Tube ends shall be reamed and chamfered, all grease, oil or dirt shall be removed from the tube end with a clean rag. Visually examine the fitting sealing element to ensure there is no damage, and it is properly seated into the fitting. Utilizing a Viega Insertion Depth Inspection Gauge mark the tube wall, with a felt tip pen, at the appropriate location, or insert the tube fully into the fitting and mark the tube wall at the face of the fitting. Always examine the tube to ensure it is fully inserted into the fitting prior to pressing the joint. ProPress fittings ½-inch thru 4-inch shall be installed according to the most current edition of the Viega installation guidelines, using appropriate sized rigid ProPress tools. Installers shall attend a Viega ProPress installation training class.
- B. After ProPress Pressure Seal fittings have been installed a “two step test” shall be followed. Pressurize the system with application appropriate test medium, water between 15 and 85

psi, or air/dry nitrogen between .5 and 45 psi. Check the pressure gauge for pressure loss. If the system does not hold pressure, walk the system and check for un-pressed fittings. Should you identify an un-pressed fitting ensure the tube is fully inserted into the fitting, and properly marked, prior to pressing the joint. After appropriate repairs have been made, retest the system per specification requirements, not to exceed 600 psi with water.

END OF SECTION

DIVISION 23 SECTION 23 05 48
VIBRATION CONTROLS FOR HVAC AND PLUMBING EQUIPMENT
TABLE OF CONTENTS

PART 1.	RELATED DOCUMENTS.....	3
1.1.	GENERAL.....	3
1.2.	SUMMARY.....	3
1.3.	SUBMITTALS	3
1.4.	PROJECT RECORD DOCUMENTS.....	4
1.5.	COLOR CODING	4
1.6.	ALTERNATES	4
PART 2.	PRODUCTS.....	4
2.1.	MANUFACTURERS.....	4
2.2.	CORROSION PROTECTION FOR STEEL PARTS	4
2.3.	SPRING MOUNTS AND SOUND PADS	4
2.4.	SPRINGS.....	4
2.5.	NEOPRENE	4
2.6.	FLOOR MOUNTED ISOLATORS:	4
2.7.	SPRING ISOLATORS	5
2.8.	SUSPENSION ISOLATORS	5
2.9.	INERTIA BASES	6
2.10.	FLEXIBLE CONNECTORS FOR PIPING.....	6
2.11.	NEOPRENE PAD ISOLATORS.....	8
2.12.	RUBBER MOUNTS.....	8
PART 3.	EXECUTION.....	8
3.1.	GENERAL PROVISIONS	8
3.2.	PIPE ISOLATION.....	10
3.3.	FLEXIBLE PIPE CONNECTORS.....	11
3.4.	ISOLATION FOR SPECIFIC EQUIPMENT.....	12
3.5.	MANUFACTURER'S FIELD SERVICES.....	12
	END OF SECTION	12

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 23 05 48 - VIBRATION CONTROLS FOR HVAC AND PLUMBING EQUIPMENT

PART 1. RELATED DOCUMENTS

1.1. GENERAL

- A. Drawings and General Provisions of Contract, including General and Supplementary Conditions and Division 01 Specification Sections apply to work of this section.
- B. All work under this section shall also be subject to the requirements of Division 23 Section, Common Work Results for HVAC.

1.2. SUMMARY

- A. Provide all labor and materials necessary to furnish and install vibration control systems on this project as herein specified and/or shown on the drawings.
- B. Mount all mechanical equipment on suitable vibration isolators so as to prevent transmission of vibration into or through the building structure. Isolators shall be as manufactured by Mason Industries, Inc., Korfund, Inc., Amber Booth, Vibration Mounting and Controls, or approved equal, and shall be selected by the isolator manufacturer for each item of equipment in accordance with requirements hereinafter specified.
- C. The equipment manufacturer shall supply all pump and motor bases, fan and motor bases, cradles, isolation pipe/duct hangers, spring and/or neoprene isolators, neoprene pads, flexible connectors, etc. as a coordinated package by a single manufacturer.
- D. Select isolators for uniform static deflections according to distribution of weight; and for not less than the indicated isolation efficiency with the lowest rotational speed of equipment as the disturbing frequency.
- E. Isolators and bases shall be stable during stopping and starting of equipment without transverse or eccentric movement of equipment, and shall be designed to resist horizontal forces of equipment which may operate unbalanced.
- F. In general, select isolators on the basis of criteria as specified in the ASHRAE Applications Handbook, Latest Edition.

1.3. SUBMITTALS

- A. Shop Drawings: Indicate inertia bases and locate vibration isolators, with static and dynamic load on each.
- B. Product Data: Provide schedule of vibration isolator type with location and load on each.
- C. Manufacturer's Installation Instructions: Indicate special procedures and setting dimensions.
- D. Manufacturer's Certificate: Certify that isolators are properly installed and adjusted to meet or exceed specified requirements.

1.4. PROJECT RECORD DOCUMENTS

- A. Record actual locations of hangers including attachment points.

1.5. COLOR CODING

- A. All springs shall be color coded for load carrying capacity.

1.6. ALTERNATES

- A. Refer to Division 01 Section, Alternates - Alternates for description of work under this section affected by alternates.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Isolators shall be the equivalent of the following types by Mason Industries, Inc., Korfund, Inc., Kinetic Noise Control, Inc., Vibro Acoustics or approved equal.

2.2. CORROSION PROTECTION FOR STEEL PARTS

- A. Where steel parts are exposed to weather or humid environments provide hot-dipped galvanized coating of at least 2 ounces of zinc per square foot of surface. Coat springs with neoprene.

2.3. SPRING MOUNTS AND SOUND PADS

- A. Provide all spring mounts with leveling devices, minimum .25 inch thick neoprene sound pads, and zinc chromate plated hardware.
- B. All sound pads shall be size for minimum deflection of .05 inch; meet requirements for neoprene pad isolators.

2.4. SPRINGS

- A. All springs shall have minimum horizontal stiffness equal to 75 percent vertical stiffness, with working deflection between .3 and .6 of maximum deflection.

2.5. NEOPRENE

- A. Grade durometer 40, 50 OR 60 AND OIL RESISTANT.

2.6. FLOOR MOUNTED ISOLATORS:

- A. Neoprene Isolation Pads: Provide pads at least ¼ " thick with cross-ribbed or waffle design. For concentrated loads provide steel bearing plates bonded or cold cemented to the pads. Neoprene isolation pads shall be Type Super W.
- B. Neoprene Isolators: Rubber (neoprene)-in-shear mounting: Provide molded neoprene isolators having steel base plates with mounting holes and, at the top, steel mounting plates with mounting holes or threaded inserts. Provide elements of type and size coded with

molded letters or color-coded for capacity identification. Embed metal parts completely in neoprene. Double deflection neoprene mountings shall have a minimum static deflection of 0.35". Bolt holes shall be provided for these areas where bolting is required. On equipment such as small vent sets and close coupled pumps, steel rails shall be used above the mounting to compensate for the over-hang. Mountings shall be type ND or rails type DNR.

2.7. SPRING ISOLATORS

- A. General: Provide spring isolators or protected spring isolators that are adjustable and laterally stable with free-standing springs of horizontal stiffness at minimum 80 percent of the vertical (axial) stiffness. For machine-attached and floor-attached restraining elements, separate from metal-to-metal contact by neoprene cushions 1/8-inch thick minimum. Provide neoprene acoustic friction pads at least ¼ inch thick.
- B. Spring Isolator: Spring type isolators shall be free standing and laterally stable without any housing and complete with ¼ " neoprene acoustical friction pads between the baseplate and the support. All mountings shall have leveling bolts that must be rigidly bolted to the equipment. Spring diameters shall be no less than 0.8 of the compressed height of the spring at rated load. Springs shall have a minimum additional travel to solid equal to 50% of the rated deflections, compressed spring height and solid spring height. Mountings shall be type SLF as manufactured by Mason Industries, Inc. or as approved equal.
- C. Restrained Spring Isolator: Equipment with operating weight different from the installed weight and equipment exposed to the wind such as cooling towers, closed circuit evaporative fluid coolers, shall be mounted on spring mountings as described above, but a housing shall be used that includes vertical limit stops to prevent spring extension when weight is removed. The housing shall serve as blocking during erection and mounts shall be located between the supporting steel and roof or the grillage and dunnage as shown on the drawings. The installed and operating heights shall be the same. A minimum clearance of ½" shall be maintained around restraining bolts and between the housing and the spring so as not to interfere with the spring action. Limit stops shall be out of contact during normal operations. Mounting shall be type SLR.

2.8. SUSPENSION ISOLATORS

- A. General: Provide hangers with suspension isolators encased in open steel brackets. Isolate hanger rods from isolator steel brackets with neoprene-lined opening.
- B. Suspension Neoprene Isolators: Provide double-deflection elements with minimum 3/8 inch deflection.
- C. Suspension Spring Isolators: Vibration hangers shall contain a steel spring and 0.3" deflection neoprene element in series. The neoprene element shall be molded with a rod isolation bushing that passes through the hanger box. Spring diameters and hanger box lower hole sizes shall be large enough to permit the hanger rod to swing thru a 30° arc before contacting the hole and short circuiting the spring. Springs shall have a minimum additional travel to solid equal to 50% of the rated deflection. Submittals shall include a scale drawing of the hanger showing the 30° capability. Hangers shall be type 30N.
- D. Precompressed Suspension Spring Isolators: Vibration hangers shall be as described in

"C" above, but they shall be precompressed to the rated deflection so as to keep the piping or equipment at a fixed elevation during installation. The hangers shall be designed with a release mechanism to free the spring after the installation is complete and the hanger is subjected to its full load. Deflection shall be clearly indicated by means of a scale. Submittals shall include a scale drawing of the hanger showing the 30° capability. Hangers shall be type PC30N.

2.9. INERTIA BASES

- A. Structural Bases: Vibration isolator manufacturer shall furnish integral structural steel bases. Bases shall be rectangular in shape for all equipment other than centrifugal refrigeration machines and pump bases which may be "T" or "L" shaped. All perimeter members shall be beams with a minimum depth equal to 1/10th of the longest dimension of the base. Beam depth need not exceed 14" provided that the deflection and misalignment is kept within acceptable limits as determined by the manufacturer. Height saving brackets shall be employed in all mounting locations to provide a base clearance of one inch- bases shall be type WF.
- B. Structural Rails: Vibration isolator manufacturer shall provide steel members welded to height saving brackets to cradle machines having legs or bases that do not require a complete supplementary base. Members shall be sufficiently rigid to prevent strains in the equipment. Inverted saddles shall be type ICS.
- C. Concrete Bases: Vibration isolator manufacturer shall furnish rectangular structural beam or channel concrete forms for floating foundations. The base depth need not exceed 12" unless specifically recommended by the base manufacturer for mass or rigidity. In general, bases shall be a minimum of 1/12th of the longest dimension of the base, but not less than 6". Forms shall include minimum concrete reinforcement consisting of half inch bars or angles welded in place on 6" centers running both ways in a layer 1-1/2" above the bottom, or additional steel as is required by the structural conditions. Forms shall be furnished with steel members to hold anchor-bolt sleeves when the anchor bolts fall in concrete locations. Height saving brackets shall be employed in all mounting locations to maintain a 1" clearance below the base. Concrete shall be 3,000 psi concrete. Mass of concrete inertia bases shall be minimum of 2 times weight of isolated equipment. Bases shall be type K.

2.10. FLEXIBLE CONNECTORS FOR PIPING

- A. General: Straight or elbow flexible connectors rated for temperatures, pressures, and fluids to be conveyed. Provide flexible connectors with the strength 4 times operating pressure at highest system operating temperature. Provide elbow flexible connectors with a permanently set angle.
- B. Elastomeric Flexible Connectors: Flexible neoprene connectors shall be manufactured of multiple plies of nylon tire cord fabric and neoprene both molded and cured in hydraulic rubber presses. No steel wire or rings shall be used as pressure reinforcement. Straight connectors shall have two spheres. Connectors up to and including 1 ½ " diameter may have threaded ends. Connectors 2" and larger shall be manufactured with floating galvanized flanges recessed to lock the connector's raised face neoprene flanges. Hoses shall be installed on the equipment side of the shut-off valves. Connectors shall be rated a minimum of 150 psi at 220oF. Flanged equipment shall be directly connected to neoprene elbows in the size range 2 ½ " through 12" if the piping makes a 90o turn at the equipment.

All straight through connections shall be made with twin-spheres properly pre-extended as recommended by the manufacturer to prevent additional elongation under pressure. 12" and larger sizes operating above 100 psi shall employ control cables with end fittings isolated by means of ½ " thick bridge bearing neoprene washer bushings designed for a maximum of 1000 psi.

- C. Submittals shall include two test reports by independent consultants showing minimum reductions of 20 DB in vibration accelerations and 10 DB in sound pressure levels at typical blade passage frequencies.
- D. Elbows shall be Mason-Flex type MFNEC, straight connectors Mason-Flex type MFTFU or MFTNC, and control cable assemblies type ACC.
- E. Metal Flexible Connectors: Fabricated of Grade E phosphor bronze, monel or corrugated stainless steel tube covered with comparable bronze or stainless steel braid restraining and pressure cover. Sizes 3" and larger shall be flanged. Sizes 2 ½ " and smaller shall have male nipples. Lengths shall be as indicated:

Nominal Diameter (Inches)	Length (Inches)
½ "	12"
¾"	12"
1 ½ "	12"
1 ½ "	12"
2"	12"
2 ½ "	12"
3"	18"
4"	18"
5"	24"
6"	24"
8"	24"
10"	24"
12"	36"
14"	36"

16"	36"

- F. Hoses shall be installed on the equipment side of the shut-off valves horizontally and parallel to the equipment shafts wherever possible. Hoses shall be type BSS.

2.11. NEOPRENE PAD ISOLATORS

- A. Rubber or neoprene waffle pads.
1. 30 durometer
 2. Minimum 2 inch (13mm) thick
 3. Maximum loading 40 psi (275 kPa)
 4. Height of ribs shall not exceed 0.7 times width.
- B. Configuration: ½ inch (13mm) thick waffle pads bonded each side of ¼ inch (6 mm) thick steel plate.

2.12. RUBBER MOUNTS

- A. Molded rubber designed for 0.6 inches (13 mm) deflection with threaded insert.

PART 3. EXECUTION

3.1. GENERAL PROVISIONS

- A. Install vibration-and-noise isolation materials and equipment as indicated and in accordance with machinery manufacturer's instructions.
- B. Where neoprene elements of vibration isolator may be subjected to high pipe temperatures above 160°F, provide metal heat shields or thermal isolators.
- C. A minimum of 4" thick reinforced concrete housekeeping pads shall be provided under all floor mounted equipment. Rest subbases on structural floor and reinforce with steel rods interconnected with floor reinforcing bars by tie bars hooked at both ends. Provide at least one (1) inch clearance between subbases and inertia bases, steel bases, and steel saddles with machinery in operation.
- D. All vibration isolators exposed to weather or humid environment shall be hot dipped galvanized with springs coated with neoprene in accordance with paragraph hereinbefore described.
- E. Concrete inertia bases shall be a minimum of two (2) times the weight supported. Clearance between the underside of the inertia base and the housekeeping pad below shall not be less than 1 inch. Concrete shall be 3000 psi. Install inertia bases in accordance with the recommendations of the machinery manufacturer and the inertia base manufacturer.
- F. Anchor Bolts and Grout: Secure machinery to foundations and inertia bases with anchor bolts. Grout equipment with baseplates, the full area under baseplates with premixed non-shrinking grout. After grout has set, remove wedges, shims, and jack bolts and fill spaces

with grout.

- G. Common Machinery Foundations: Mount electrical motors on the same foundations as driven machinery. Support piping connections, strainers, valves, and risers on the same foundation as the pumps.
- H. Vertical Stops: For machinery affected by wind pressure or having an operational weight different from installed weight, provide resilient vertical limit stops which prevent spring extension when weight is removed. Provide vertical stops for machinery containing liquid, such as closed circuit evaporative fluid coolers, and cooling towers. Spring isolated or protected spring isolated machinery must rock and move freely within limits of stops or seismic restraint devices.
- I. Thrust Restraints: Where required, provide pairs of thrust restraints, symmetrically installed on both sides of the steady state line of thrust.
- J. Machinery: Provide vibration isolators, flexible connectors and seismic snubbers in accordance with manufacturer's recommendations. Machinery with spring isolators or protected spring isolators shall rock or move freely within limits of stops or seismic snubber restraints.
- K. Stability: Isolators shall be stable during starting and stopping of machinery without traverse and eccentric movement of machinery that would damage or adversely affect the machinery or attachments.
- L. Lateral Motion: The installed vibration isolation systems for each piece of floor or ceiling mounted machinery shall have a maximum lateral motion under machinery start up and shut down conditions of not more than ¼ -inch. Restrain motions in excess by approved spring mountings.
- M. Unbalanced Machinery: Provide foundation suspension systems specifically designed to resist horizontal forces for machinery with large unbalanced horizontal forces. Vibration isolator systems shall conform to the machinery manufacturer's recommendations.
- N. Nonrotating Machinery: Mount nonrotating machinery in systems which includes rotating or vibrating machinery on isolators having the same deflection as the hangers and supports for the pipe connected to.
- O. Roof and Upper Floor Mounted Machinery: On the roof or upper floors, mount machinery on isolators with vertical stops. Rest isolators on beams or structures designed and installed in accordance with the SMACNA ASMM Plate 61.
- P. Vibration isolation ceiling hangers shall be installed so that the hanger rods do not touch the sides of the isolator housing, thereby seriously degrading the vibration isolation performance. Vibration isolation ceiling hangers shall be located so that the hanger housing may rotate 360 degrees without touching any object.
- Q. Electrical Connections: Provide flexible conduit or multiple conductor cable connections for machinery with sufficient extra length to permit 2 inch minimum displacement in any direction without damage.

- R. Systems Not To Be Vibration Isolated: Do not provide vibration isolation for electrical raceways and conduits or for fire protection, storm, sanitary, and domestic water piping systems which do not include pumps or other vibrating, rotating, or pulsating equipment including control and pressure reducing valves.
- S. Install in accordance with manufacturer's instructions.
- T. Install isolation for motor driven equipment.
- U. Bases:
 - 1. Set steel bases for one inch (25mm) clearance between housekeeping pad and base.
 - 2. Set concrete inertia bases for 2 inch (50mm) clearance between housekeeping pad and base.
 - 3. Adjust equipment level.
- V. Install spring hangers without binding.
- W. On closed spring isolators, adjust so side stabilizers are clear under normal operating conditions.
- X. Prior to making piping connections to equipment with operating weights substantially different from installed weights, block up equipment with temporary shims to final height. When full load is applied, adjust isolators to load to allow shim removal.
- Y. Connect wiring to isolated equipment with flexible hanging loop.

3.2. PIPE ISOLATION

- A. Horizontal Pipe Isolation:
 - 1. Precompressed Suspension Spring Isolators:
 - a. For the first three pipe hangers in the main lines near the mechanical equipment provide precompressed suspension spring isolators. Floor supported piping shall rest on trained spring isolators. All precompressed suspension spring isolators hangers or the first three trained spring isolators mounts as noted above, will have the same static deflection as specified for the mountings under the connected equipment. If piping is connected to equipment located in basements and hangs from ceiling under occupied spaces, the first three hangers shall have 0.75" deflection for pipe sizes up to and including 3", 1.5" deflection for pipe sizes up to and including 6" and 2.5" deflection thereafter. All other hangers and mounts will have a minimum steel spring deflection of 0.75". Hangers shall be located as close to the overhead supports as practical.
 - 2. Combination Spring and Neoprene Suspension Hanger:
 - a. For horizontal runs in other than those hereinbefore specified provide suspension spring hangers (combination spring and neoprene) with .75"

- minimum steel spring deflection.
 - b. Condenser water, heating water and heat pump supply/return:
 - i. For the first 20 feet of the branch connection of the main supply and return piping at each floor.
 - ii. For all piping over 2" diameter.
- B. Floor-Supported Piping:
 - 1. Floor supports for piping in equipment rooms and adjacent to isolated equipment shall use vibration isolators as described hereinbefore and selected to the guidelines of hangers.
 - 2. The first three adjacent floor supports shall be the restrained spring type with a blocking feature that prevents load transfer to equipment flanges as the piping is filled and drained.
 - 3. Where piping is subject to larger thermal movement a slide plate shall be installed on the top of the isolator. Slide plate shall be teflon, graphite or steel.
 - 4. Provide a thermal barrier where neoprene products are installed directly beneath steam or hot water lines.
- C. Pipe Risers: Provide pipe riser supports with bearing plates and two layers of ¼ " thick ribbed or waffled neoprene pad loaded to not more than 50 psi. Separate isolation pads with ¼ " steel plate. Weld pipe riser clamps at anchor points to the pipe and to pairs of vertical acoustical pipe anchor mountings which shall be rigidly fastened to the steel framing.
- D. Supports at Base of Pipe Risers: Piping isolation supports at the base of risers shall be two layers of ½" thick heavy-duty neoprene pad separated by ¼ " thick steel plate. Use bearing plates sized to provide a pad loading of not more than 500 psi. Weld the stanchion between the pipe and isolation support to the pipe and weld or bolt to the isolation support. Bolt isolation support to the floor slab with resilient sleeves and washers. Where supplementary steel is required to support piping, provide a maximum deflection of 0.08 inches at the mid-span of this steel under the load. Rigidly support piping from the supplementary steel with the supplementary steel isolated from the building structure with isolators.
- E. Pipe Anchors: Attach each end of the pipe anchor to an omni-directional pipe isolator which in turn shall be rigidly fastened to the steel framing or structural concrete. Provide a telescoping pipe isolator of two sizes of steel tubing separated by a minimum ½ " thick pad of heavy-duty neoprene or heavy-duty neoprene and canvas. Provide vertical restraints by similar material to prevent vertical travel in either direction. The load on the isolation material shall not exceed 500 psi.

3.3. FLEXIBLE PIPE CONNECTORS

- A. Provide flexible connectors in accordance with manufacturers instructions where piping systems serving vibration isolated equipment and as shown on the drawings. Flexible connectors shall be installed near the connection to the equipment. Where liquid pulsation dampening is required, flexible connectors with spherical configuration may be used. Provide restraints for pipe connectors at pumps to prevent connector failure upon pump

start-up.

3.4. ISOLATION FOR SPECIFIC EQUIPMENT

- A. The vibration isolator manufacture shall provide isolators for all pieces of equipment provided for the job. Isolator shall be selected by the isolator manufacturer on the basis of criteria as specified in the ASHRAE Applications Handbook, latest edition, unless a more stringent requirement is indicated on the drawings.
- B. Pumps:
 - 1. All base mounted pumps shall be mounted on concrete inertia bases supported on stable steel springs in series with ribbed neoprene pads selected for not less than 1.5 inch static deflection under full operating load. Mason Industries type SLF or as approved equal.
 - 2. Floor support of the initial pipe elbows at the pump discharge and suction diffuser at the pump intake shall be made from the isolated inertia base, not from the equipment room floor. Mason Industries Type K or as approved equal.
 - 3. Provide flexible pipe connections at pump suction and discharge. Mason Industries Type BSS or MFTNC/MFTFU with control rods type ACC or as approved equal.
 - 4. Provide discharge and suction vibration isolaters at all in-line pumps.
- C. Cooling Tower/Closed Circuit Evaporative Fluid Coolers:
 - 1. Refer to specification sections 23 65 15, "Closed Circuit Evaporative Fluid Coolers" and 23 65 17, "Open-Circuit, Low Profile, Forced Draft Cooling Towers".

3.5. MANUFACTURER'S FIELD SERVICES

- A. Inspect isolated equipment after installation and submit report. Include static deflections.

END OF SECTION

DIVISION 23 SECTION 23 05 93
TESTING, ADJUSTING & BALANCING FOR HVAC & PLUMBING
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. GENERAL.....	3
1.2. ALTERNATES	5
1.3. GENERAL COMMISSIONING REQUIREMENTS.....	5
1.4. PRELIMINARY EXAMINATION.....	5
1.5. QUALIFICATIONS OF THE BALANCE AGENCY	6
1.6. PERSONNEL	6
1.7. WARRANTY	6
1.8. PRE-BALANCING CONFERENCE	6
1.9. STANDARDS	6
1.10. COORDINATION.....	7
1.11. INSTALLATION TOLERANCE.....	7
1.12. RESPONSIBILITIES OF THE TAB AGENCY	7
1.13. REPORTS.....	11
1.14. TAB FINAL ACCEPTANCE INSPECTION.....	11
1.15. RESPONSIBILITIES OF THE MECHANICAL CONTRACTOR	12
1.16. CONTRACTOR SUPPLIED ITEMS	14
1.17. RESPONSIBILITIES OF THE TEMPERATURE CONTROL CONTRACTOR	15
1.18. NOTIFICATION FOR TESTING AND BALANCING WORK TO BEGIN	15
1.19. DEFICIENCIES	16
1.20. ADJUSTING	16
PART 2. PRODUCTS (NOT APPLICABLE)	17
PART 3. EXECUTION	17
3.1. GENERAL.....	17
3.2. EXAMINATION.....	17
3.3. AIR SYSTEM PROCEDURES	18
3.4. WATER SYSTEM PROCEDURES.....	19
3.5. TESTING AND BALANCING OF EXISTING SYSTEMS	21
3.6. VERIFICATION OF TEMPERATURE CONTROL	21
3.7. TEST AND BALANCE REPORTS	21
3.8. TEST REPORT FORMS	22
END OF SECTION	26

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 23 05 93 - TESTING, ADJUSTING, AND BALANCING FOR HVAC AND PLUMBING

PART 1. GENERAL

1.1. GENERAL

- A. This section covers performance testing, adjusting and balancing of heating, ventilating, air conditioning as specified in Division 23 Section, Heating, Ventilating, and Air Conditioning Equipment.
- B. For Common Work Results of HVAC, See Division 23. See Division 01 for General Requirements.
- C. The mechanical contractor shall select and employ an impartial, independent balancing agency to provide testing and balancing services for the heating, ventilating and air conditioning (HVAC) systems, plumbing systems, and other specified systems of this project.
- D. The work included in this section consists of furnishing labor, instruments, and tools required in testing, adjusting and balancing the HVAC and plumbing systems, as described in these specifications or shown on accompanying drawings. Services shall include checking equipment performance, taking the specified measurements, and recording and reporting the results. Where balance valves and/or flow meter fittings are not indicated utilize ultrasonic flow meter to record fluid flow rates in gallons per minute.
 - 1. Perform all work required to prepare the building HVAC and Plumbing systems for testing, adjusting, and balancing indicated by the Contract Documents as follows:
 - a. Verify the air systems are ready for balancing.
 - b. Verify the hydronic systems are ready for balancing.
 - c. Verify the control systems are ready for balancing.
 - d. Notify appropriate parties the system is ready for balancing.
 - 2. Scope of work.
 - a. Testing, adjusting, and balancing (TAB) of the HVAC systems, Plumbing Systems, and related ancillary equipment will be performed by an independent, third party, AABC Certified Agency, selected and employed directly by the Contractor. The preparation and corrections necessary for the testing and balancing of these systems, as described herein, are the responsibility of the Contractor.
 - b. As part of the project Construction Contract, the Contractor shall make any changes or replacements to the sheaves, belts, dampers, valves, or other components required for correct balance as advised by the TAB Agency, at no additional cost to the Owner.
 - c. The Contractor shall provide and coordinate the services of qualified, responsible subcontractors, suppliers and personnel as required to correct, repair, and/or replace any and all deficient items or conditions found during the course of this project, including the testing, adjusting, and balancing period.

- d. In order that all systems may be properly tested, adjusted and balanced as required herein by these Specifications, the Contractor shall operate the systems at their expense for the length of time necessary to properly verify their completion and readiness for TAB, and the entire duration required for the TAB process.
 - e. Project Contract completion schedules shall allow for sufficient time to permit the completion of TAB services prior to Owner occupancy. The Contractor shall allow adequate time for the testing and balancing activities of the Owner-provided services during the construction period and prior to Substantial Completion, as defined in the AIA General Conditions and Supplementing Condition of this Construction Document.
 - f. The Drawings and Specifications indicate valves, dampers, and miscellaneous adjustment devices to be adjusted to obtain optimum operating conditions. It is the responsibility of the Contractor to install these devices in a manner that will leave them accessible and readily adjustable. Should any such device not be readily accessible, the Contractor shall provide access, as requested by the TAB Agency. Any malfunction encountered by TAB personnel and reported to the Contractor shall be corrected by the Contractor immediately so that the balancing work can proceed with a minimum of delays.
 - g. The scope of work, as defined herein, is to advise the Contractor of the coordination, adjustment, and system modifications that will be required under the project work to complete Owner requirements for final TAB. The Contractor's original bid shall allow for the costs of all work which may be required in the TAB phases, and which may be necessary for the completion of the TAB work as defined by the TAB Agency.
3. Submittals. The TAB Agency shall submit an agenda that will include:
- a. Field observation reports.
 - b. An overview of system TAB procedures.
 - c. System testing which will include where ducts will be traversed, which instrumentation will be used, how correction factors for grille and diffuser will be obtained, how measurements will be verified at maximum and minimum, and how control components will be verified.
 - d. Report forms with each system's components identified and numbered.
- E. The items requiring testing, adjusting, and balancing include, but are not limited to, the following:

Air Systems:

- 1. Closed Circuit Evaporative Fluid Cooler Fans
- 2. Cooling Tower Fans

Hydronic Systems:

- 1. Condenser Water Pumps
- 2. Cooling Tower Pumps

3. Coupon Rack and Chemical Feed Tank Flow Rates
4. Cooling Towers/Evaporative Coolers/Evaporative Spray Pump
5. Closed Circuit Evaporative Fluid Coolers
6. Differential Pressure Bypass Valves
7. Flow Measuring Stations
8. Flow Meter Fittings
9. Flow Switches
10. Existing Heat Exchangers
11. Existing Boilers
12. In-line Pumps
13. Minimum Flow Bypass Valves.
14. Pumps/Spray Pumps
15. System Mains and Branches
16. In addition, existing equipment or air devices specified to be re-used under this project shall be tested and balanced, similar to new fans.

1.2. ALTERNATES

- A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

1.3. GENERAL COMMISSIONING REQUIREMENTS

- A. Refer to Division 01 Section, "General Commissioning Requirements" for description of work under this Division affected by General Commissioning.

1.4. PRELIMINARY EXAMINATION

- A. Verify that systems are complete and operable before commencing work. Ensure the following conditions:
 1. Systems are started and operating in a safe and normal condition.
 2. Temperature control systems are installed complete and operable.
 3. Proper thermal overload protection is in place for electrical equipment.
 4. Fans are rotating correctly.

5. Access doors are closed and duct end caps are in place.
 6. Hydronic systems are flushed, filled, and vented.
 7. Pumps are rotating correctly.
 8. Proper strainer baskets are clean and in place.
 9. Service and balance valves are open.
- B. Submit field reports. Report defects and deficiencies noted during performance of services which prevent system balance.
- C. Beginning of work means acceptance of exiting conditions.

1.5. QUALIFICATIONS OF THE BALANCE AGENCY

- A. The balancing agency shall be a member of the Associated Air Balance Council (AABC).
- B. The certified test and balance engineer shall be responsible for supervision and certification for the total work herein specified.
- C. All final reports shall be signed by the certified test and balance engineer.
- D. All personnel used on the project will be employees of an AABC Certified Agency. All work will be performed under the direct supervision of the AABC Certified Test and Balance Engineer (TBE). All work will be performed with AABC Certified Test and Balance Technicians (TBT) Resumes including education, experience, and certification of each person on the project shall be submitted.
- E. Warranty. The AABC Agency shall submit a National Project Performance Guaranty.

1.6. PERSONNEL

- A. All personnel used on the project will be employees of an AABC Certified Agency. All work will be performed under the direct supervision of the AABC Certified Test and Balance Engineer (TBE). All work will be performed with AABC Certified Test and Balance Technicians (TBT). Resumes including education, experience, and certification of each person on the project shall be submitted as informational submittals.

1.7. WARRANTY

- A. The AABC Agency shall submit a National Project Performance Guaranty.

1.8. PRE-BALANCING CONFERENCE

- A. Convene a conference one week prior to commencing work of this Section with all appropriate individuals.

1.9. STANDARDS

- A. The balancing agency shall perform the services specified herein in accordance with the

Associated Air Balance Council's National Standards, including revisions, to the date of the contract.

- B. All terms in this specification shall have their meaning defined as stated in the National Standards.
- C. ADC: Test Code for grilles, registers, and diffusers.
- D. ASHRAE III: Practice for measurement, testing, adjusting and balancing of building heating, ventilation, air conditioning, and refrigeration systems.
- E. NEBB: Procedure standards for testing, adjusting, and balancing of environmental systems.
- F. SMACNA: HVAC systems testing, adjusting, and balancing.
- G. AABC: Associated Air Balance Council

1.10. COORDINATION

- A. It will be necessary for the balancing agency to perform its services in close coordination with the mechanical contractor.
- B. The plans and specifications have indicated meters, valves, dampers, and other devices for the purpose of adjusting the system to obtain optimum operating conditions. It will be the responsibility of the mechanical contractor to install these devices in a manner that will leave them accessible and readily adjustable. The balancing agency shall provide guidance if there is a questionable arrangement of a control or balancing device.
- C. The mechanical contractor, temperature control contractor and suppliers of the HVAC equipment shall all cooperate with the balancing agency to provide all necessary data on the design and proper application of the system components.

1.11. INSTALLATION TOLERANCE

- A. Unless otherwise indicated, all air devices shall be adjusted to within plus or minus 10 percent of design. All fans shall be adjusted to within plus or minus 5 percent of design. All pumps and Hydronic equipment shall be adjusted to within plus or minus 5 percent of design.

1.12. RESPONSIBILITIES OF THE TAB AGENCY

- A. Liaison and Early Inspection. The following reviews, observations, and tests shall be performed by the TAB Agency:
 - 1. Review the mechanical drawings and specifications for balanceability and provide commentary. Verify proper types and locations of all Test and Balance devices.
 - 2. During construction, review all approved HVAC submittals such as control diagrams, air handling devices, hydronic devices, and other components that pertain to TAB work and balanceability. Assist the commissioning agent with all Functional Performance Testing.

3. Perform construction observations and submit a written report:
 - a. On the piping prior to insulation and/or ceiling cover-up.
 4. Perform a pre-balance site review, and submit a written report.
 5. During the balancing process, abnormalities and malfunctions of equipment or components may be discovered by the TAB personnel. The Construction Inspector, Engineer, and Owner shall be advised in writing so that the condition(s) can be corrected by the Contractor. The written document need not be formal, but shall be understandable and legible. The TAB Agency shall not instruct or direct the Contractor in any of the work, but will make reports to the appropriate parties.
- B. Final Air Balance. When systems are complete and ready for operation, the TAB Agency will perform a final air balance for all air systems and record the results. The volume of air for the heat of rejection equipment will be tested and balanced within the tolerances of the AABC Standard, or as specified, whichever is more stringent. Air handling unit and fan volumes shall be adjusted by changing fan speed. Air distribution device volumes shall be adjusted using the duct dampers and not the grille face. Air distribution devices shall be balanced with air patterns as specified. The general scope of balancing by the TAB Agency will include, but is not limited to, the following:
1. Fan Speed: Measure and record RPM for each fan. Provide Controls Contractor with drive parameters for variable speed drives.
 2. Voltage and Amperage Readings: Measure and record the final operating voltage and amperage for each motor.
 3. Static Pressure Profile: Static pressure profiles shall be measured and recorded across each supply fan and heat of rejection equipment fans.
 4. Equipment Air Flow: Adjust and record CFM and temperatures, as applicable, at each fan and coil.
 5. Heat Exchanger Temperatures: Set controls for full heating loads. Read and record entering and leaving dry bulb and wet bulb (cooling only) temperatures at each heating coil, and HVAC terminal unit. At the time of reading, record water flow and entering and leaving water temperatures and pressure drops. In variable flow systems, adjust the air and water flow to design for all the above readings.
- C. Final Water Balance. When systems are complete and ready for operation, the TAB Agency will perform a final water balance for each hydronic HVAC system. The general scope of balancing by the TAB Agency will include, but not be limited to, the following:
1. Adjusted System Tests: Adjust balancing valves at each coil and heat exchanger for design flow per the AABC Standard. Adjust balancing valves at pumps to obtain design water flow. Record pressure rise across pumps, and obtain GPM flow from the pump curve. Permanently mark the balanced position for each valve. If discharge valves on the pumps are used for balancing, record the head being restricted by the valves. Test and record autoflow valve differential pressures and adjust pump speed to optimize and minimize outflow differential pressure.

2. Temperature Readings: Read and record entering and leaving water temperature at each water coil, cooling tower, closed circuit evaporative fluid cooler, and existing heat exchanger at design flow. Adjust as necessary to secure design operating conditions. Provide final readings at all thermometer well locations.
 3. Pressure Readings: Water pressure shall be recorded at all gauge connections. Pressure readings at coils and pumps shall be related to coil and pump curves in terms of GPM flow and through flow measuring stations, where provided and installed, at each hydronic unit. The flow of water through all water coils shall be adjusted by balancing valves until the rated pressure drop across each coil is obtained and total water flow is verified by flow measuring station. For coils equipped with three-way valves, the rated pressure drop shall first be adjusted through the coils. The bypass valve shall then be adjusted on each coil until the pressure drop between supply and return connections is the same as with the flow through the coil.
 4. Voltage and Amperage Readings: Read and record the final operating voltage and amperage for each pump motor.
 5. Pump Speed: Measure and record RPM for each pump. Provide Controls Contractor with drive parameters for variable speed pumps.
- D. Testing of Temperature Control Systems as applicable to the project.
1. Fan Systems
 - a. Start each fan or fan system; verify and document:
 - Interlocks and lockouts operate in accordance with the sequence.
 - Fan(s) VFD ramps to design speed or proper controlled speed.
 - All alarms and safeties are operational and will alarm or shut down the fan.
 - Dampers modulate properly and in the correct sequence.
 - All interlocked fans and/or devices energize.
 - All end switches and positioners are properly set.
 - All pressure controllers respond to increases or decreases in system pressure.
 - All temperature and pressure sensors are calibrated.
 - Correct operation of fan sequences when multiple fans are installed.
 - b. Shut down each fan or fan system; verify and document:
 - Dampers respond properly (open, close, or modulate) and in the correct sequence.
 - All fan systems ramp down and stop.
 - Correct operation of fan sequences when multiple fans are installed.
 - Interlocked devices turn off.
 - All alarms and safeties remain operational.
 2. Hydronic Systems
 - a. Start hydronic systems; verify and document:

- Valves modulate properly and in the correct sequence.
 - Pump(s) VFD ramps to design speed or proper controlled speed.
 - All isolation valves go to their “system on” position.
 - All coil valves operate in response to the controlled temperature.
 - All interlocked devices energize.
 - All alarms and safeties are operational and will alarm or shut down the system.
 - All operating scenarios are tested; e.g.: minimum/maximum water flows, minimum/maximum pressure, and special sequences.
 - All end switches and positioners are properly set.
 - All pressure controllers respond to increases or decreases in system pressure.
 - All temperature and pressure sensors are calibrated.
 - Flow meters report the correct water flow and that control devices respond correctly to a change in water flow.
 - Reset control sequences operate in response to changes in system temperatures, flows or pressures.
 - Correct operation of pump and/or heat exchangers sequences when multiples are installed.
 - Emergency mode operation; e.g.: power outage, freeze protection.
 - The controls have time delay strategy to avoid excessive cycling of pumps and heat exchangers.
- b. Shut down hydronic systems; verify and document:
- Valves modulate properly and in the correct sequence.
 - Pump(s) VFD ramps down to off position.
 - All heat exchanger valves go to their normal off position.
 - All heat exchanger valves go to their normal off position.
 - All interlocked devices de-energize.
 - All alarms and safeties remain operational.
 - Correct shutdown of pump and/or heat exchangers sequences when multiples are installed.
 - Emergency mode operation; e.g.: freeze operation.

3. Component Calibration

All temperature, airflow, fluid flow, pressure, and flow measuring components shall be measured and compared to the control system readout; verify and document:

- The air temperature sensors for each heat exchanger. If the temperature is not reading within tolerance, the sensor will be reported to the control contractor for calibration.
- The room temperature, humidity, and CO₂ sensors. If the sensors are not reading within tolerance, the sensors shall be reported to the control contractor for calibration.
- The water temperature sensors for each heat exchanger. If the temperature is not reading within tolerance, the sensors shall be reported to the control contractor for calibration.
- All air and water pressure sensor readouts. If the pressure is not

reading within tolerance, the sensor shall be reported to the control contractor for calibration.

- All flow measuring device readouts. If the flow readout is not recording within tolerance, the sensor shall be reported to the control contractor for calibration.

4. Point Verification

- Point verification for the digital control system documents that every point is operational and the setpoint, flow, temperature, or pressure is reporting correctly to the graphic interface. Verify and document all points.

5. Dynamic Testing

- Dynamic testing involves making a change of value at the sensor in order to observe the system's reaction and how it regains the original setpoint. Verify and document the system's response.

1.13. REPORTS

- A. The report shall be a complete record of the HVAC system performance, including conditions of operation, items outstanding, and any deviations found during the process. The final report also provides a reference of actual operating conditions for the owner and/or operations personnel. The report summary is a project narrative describing the outcome of the testing and balancing and shall include a list of items that document all system variations deviating from design tolerances. Information can also be included that suggests possible resolutions.
- B. All measurements and recorded readings that appear in the reports shall be certified by the Agency's Test and Balance Engineer.
- C. Submit reports on forms approved by the Engineer. Hard and/or electronic copies of the final report shall be submitted in accordance with the Contract Requirements. The report shall indicate a summary of actual operating data and any abnormal operating conditions. The report shall contain all required information as described within this specification, including the information formatted and shown in the AABC Standard.
- D. When the Engineer reviews TAB reports and provides comments, address each comment in writing for all re-submitted TAB reports.

1.14. TAB FINAL ACCEPTANCE INSPECTION

- A. At the time of TAB final acceptance inspection, the TAB agency shall recheck, in the presence of the Owner's representative, specific and random selections of data recorded in the certified test and balance report.
- B. Points and areas for recheck shall be selected by the Owner's representative.
- C. Measurements shall be verified at the same test conditions as the submitted and approved test and balance agenda.

- D. Selections for verification shall not exceed 10% of the total number tabulated in the report, except where special air systems require a complete recheck for safety reasons.
- E. If 10% of the random verification tests demonstrate a measured flow deviation of 10%, or more from that recorded in the certified test and balance report, the report shall be automatically rejected. In the event the report is rejected, all systems shall be readjusted and tested, new data recorded, a new certified test and balance submitted, and a new inspection test made. There shall be no additional cost to the Owner for this work.
- F. Final acceptance shall occur after successful completion of the TAB verification process.

1.15. RESPONSIBILITIES OF THE MECHANICAL CONTRACTOR

- A. The mechanical contractor shall sufficiently complete the installation and start all HVAC and plumbing systems to insure they are working properly and shall perform all other items as described hereinafter to assist the balancing agency in performing the testing and balancing of the HVAC system.
- B. Record equipment manufacturer's standard start-up information and submit to Engineer for review. Testing and balancing work shall not commence on any equipment until start-up reports have been completed, reviewed by Engineer, and forwarded to Testing and Balancing Agency.
- C. The Contractor shall:
 - 1. Have the building, air conditioning systems, heating systems, and plumbing systems in complete operational readiness for TAB work to begin.
 - 2. The Contractor shall allow sufficient time for the TAB Agency to perform their contracted work within the construction schedule. The Contractor shall complete work by systems or floors, whichever is the most efficient for testing systems. After award of the contract and the completion of the construction schedule by the Contractor, a TAB coordination meeting shall be held with the TAB Agency, the Contractor and primary subcontractors, including but not limited to mechanical, electrical, and building automation subcontractors to develop a testing schedule for the project. The Contractor shall submit copies of the proposed schedule to the TAB Agency two weeks prior to this meeting.
 - 3. Promptly correct deficiencies of materials and workmanship identified as delaying completion of TAB work.
 - 4. Be responsible for any added costs to the Owner resulting from the Contractor's failure to have the building HVAC systems ready for TAB when scheduled, or from the Contractor's failure to correct deficiencies promptly.
- D. Facility Operational Readiness
 - 1. Complete operational readiness of the building requires that the building envelope be complete. This includes the installation of doors, windows, and ceilings to obtain simulated or projected operating conditions.

E. Air Distribution Systems

1. Verify installation for conformity to design.
2. Ensure that air-handling systems, units, and associated apparatus, such as closed circuit fluid cooler and cooling tower fill, access doors, etc., are blanked and/or sealed to eliminate excessive bypass or leakage of air.
3. Ensure that all fans are operating and free of vibration. All fans and drives shall be checked for proper fan rotation and belt tension. Overload protection shall be of proper size and rating. A record of motor current and voltage shall be made to verify that the motors do not exceed nameplate rating. Record thermal overload ratings for all motors in the Test and Balance Report.
4. Make any necessary changes to the sheaves, belts, and dampers, as required by the balancing agency, at no additional cost to the owner.
5. Coils shall be clean with fins straightened, bearings shall be properly greased, belts shall be aligned and tightened, and the system shall be completely operational. The Contractor shall verify that all systems are operating within the design pressure limits of the piping and ductwork.
6. All fans shall be operating and verified for: freedom from vibration, proper fan rotation and belt tension; heater elements in motor starters to be of proper size and rating, as the as per the starter manufacturer. Record motor amperage and voltage on each phase at start-up, verifying they do not exceed nameplate ratings.

F. Water Circulating Systems

1. Verify installation for conformity to design.
2. Check all pumps to verify pump alignment and rotation.
3. Ensure that systems are clean, with the proper strainer screens installed for normal operation.
4. Check all pump motors for current on each phase and voltage, to ensure that motors do not exceed nameplate rating.
5. Provide thermal overload protection of proper size per the starter manufacturer and rating. Record thermal overload ratings for all motors. Insert data in Test and Balance Report.
6. Ensure that all water circulating systems shall be full and free of air; that expansion tanks are set for proper water level; and that all air vents were installed at high points of systems and are operating.
7. All piping shall be terminated and pressure tested for leakage as required by the specification. All valves shall be set to their full open position, bypass stop valves shall be closed, and mixing valves shall be set to full-flow through the the system's components. After the system is flushed and checked for proper operation, all

strainers shall be removed and cleaned. The Contractor shall repeat the operation until circulating water is clean. The start-up strainers shall then be removed and hung adjacent to the pumps.

8. Chemicals shall be added to closed systems to treat piping and inhibit corrosion. The system static pressure shall be adequate to completely fill the system without operating the pumps.
9. The operating parameters of the existing heat exchangers, existing indirect fluid storage tanks, existing boilers, coils, and control devices shall be capable of obtaining design requirements.
10. Proper balancing devices shall be installed in the designated locations. These devices include but are not limited to flow meters, pressure taps, thermometer wells, and balancing valves.

G. Notification of System Readiness

1. After completion of the work, the Contractor shall notify the Owner and TAB Agency, in writing, certifying that the work has been accomplished and that the building, air conditioning, and plumbing systems are ready for testing, adjusting, and balancing. The Contractor shall include a copy of the tabulated data of the start-up reports.
2. The Contractor shall notify the TAB Agency of the readiness for balancing and forward copies of the Contractor's certification and the tabulated data.
3. Should the TAB Agency be notified as described above and the inspection reveal the TAB services notification to have been premature, all costs of the inspection by the TAB Agency shall be reimbursed by the Contractor.

1.16. CONTRACTOR SUPPLIED ITEMS

- A. As a requirement of the TAB contract, the Contractor's Project Manager shall compile and provide the TAB Agency the following:
1. One set of mechanical specifications.
 2. All pertinent change orders.
 3. All Request(s) for Information (RFI).
 4. One complete set of MEP Drawings.
 5. One copy of approved submittal data on equipment installed and controls submittal with sequences of operation.
 6. All HVAC Control Communications software with the appropriate licenses and hardware interfaces.

1.17. RESPONSIBILITIES OF THE TEMPERATURE CONTROL CONTRACTOR

- A. The temperature control contractor shall complete the installation of the temperature control system, and operate and test all control systems to ensure they are functioning properly as designed. The temperature control contractor shall assist the balancing agency in testing and balancing the HVAC systems, as described hereinafter.
 - 1. Verify that all control components are installed in accordance with project requirements and are functional, including all electrical interlocks, damper sequences, air and water reset, freeze stats, high and low temperature thermostats, safeties, and duct smoke detectors.
 - 2. Verify that all controlling instruments are calibrated and set for design operating conditions.
 - 3. Calibrate temperature sensors after installation, and before the temperature sensors control verification tests are performed. The balancing agency shall prove the accuracy of final settings by taking temperature readings. The readings shall be in a typical conditional space for each separately controlled zone.
 - 4. The temperature control contractor shall allow sufficient time in the project to provide assistance and instruction to the balancing agency in the proper use and setting of control components such as, but not limited to, computers, static pressure controllers, or any other device that may need set points changed so that the testing and balancing work can be performed.
 - 5. The Control Contractor shall schedule a meeting with the Mechanical Contractor, TAB Agency, and Owner's representative for a pre-submittal review to establish that their interpretation of the control sequence is correct.
 - 6. The Control Contractor shall verify that all controlling instruments are calibrated and set for design operating conditions, with the exception of components that require input from the TAB Agency. A default shall be set for such components. The Control Contractor shall cooperate with the TAB Agency and provide all software and interfaces necessary to communicate with the system.
 - 7. The Automatic Temperature Control Contractor shall thoroughly check all controls, sensors, operators, and sequences before notifying the TAB Agency that the Energy Management System is operational. The Energy Management System Contractor shall provide technical support in the form of technicians and necessary computers to the TAB Agency for a complete check of those systems.
- B. All control sequences, software, equipment, and components shall be started-up by a qualified technician. Start-up report shall be submitted to Engineer prior to the commencement of testing and balancing work. Testing and balancing shall not commence until start-up reports are completed, reviewed by Engineer and forwarded to Testing and Balancing Agency.

1.18. NOTIFICATION FOR TESTING AND BALANCING WORK TO BEGIN

- A. The mechanical contractor shall notify the balancing agency in writing when all heating,

ventilating, and air conditioning and plumbing systems are complete and ready for testing and balancing. The mechanical contractor shall attest that he has completed all items as herein described.

- B. The following must be completed prior to start of system balancing:
 - 1. Piping systems completed, flushed and filled.
 - 2. Equipment properly started by qualified personnel or start-up technicians.
 - 3. Ceiling tiles installed.
 - 4. Automation system (temperature controls) installed and completed for both air and water systems.
 - 5. All equipment controlled in automatic ("Auto") mode.
 - 6. Access granted to the balancing contractor to the automation/controls system provided.
- C. Mechanical Contractor shall notify the General Contractor of the start date of this portion of the work.

1.19. DEFICIENCIES

- A. Any deficiencies in the installation or performance of a system or component observed by the TAB agency shall be brought to the attention of the appropriate responsible person.
- B. The work necessary to correct items on the deficiency listing shall be performed and verified by the affected Contractor before the TAB Agency returns to retest. Unresolved deficiencies shall be noted in the final report.
- C. TAB Agency shall notify General Contractor of all deficiencies found during initial survey.

1.20. ADJUSTING

- A. Ensure recorded data represents actual measured observed conditions.
- B. Permanently mark settings of valves, dampers, and other adjustment devices allowing settings to be restored. Set and lock memory stops.
- C. After adjustment, take measurements to verify balance has not been disrupted or that such disruption has been rectified.
- D. Leave systems in proper working order, replacing belt guards, closing access doors, closing doors to electrical switch boxes, and restoring all sensors to specified settings.
- E. At final inspection, recheck random selections of data recorded in report. Recheck points or areas as selected and witnessed by the Owner.
- F. Check and adjust systems approximately six months after final acceptance and submit report.

PART 2. PRODUCTS (NOT APPLICABLE)

PART 3. EXECUTION

3.1. GENERAL

- A. Perform all testing and balancing in complete accordance with AABC National Standards for Field Measurements and Instrumentation.
- B. Furnish all test instruments and equipment. All instruments must have been calibrated within twelve (12) months prior to use and shall be checked for accuracy prior to and during the work. Submit certificate for calibration of all equipment utilized on project with date of calibration clearly identified.
- C. Review all systems designs and equipment, manufacturers' data, and be completely familiar with the work before proceeding.
- D. Report all malfunctions or deficiencies to the contractor so that corrective action can be taken. Test and Balance Report shall not be submitted for review until all malfunctions or deficiencies are corrected. Repeat tests where required until design conditions are achieved.
- E. Where systems or equipment cannot be balanced or adjusted to design conditions, determine the cause and submit a complete report to the Engineer.
- F. Retest or rebalance the system as required during the warranty period.
- G. Test and balance all systems under adequate load condition. If, in the opinion of the Engineer, there is insufficient load to properly test and balance the systems, perform sufficient preliminary balancing and adjustment to permit operation of the systems until such time as final testing and balancing can be done. Provide in writing the future date when systems shall be tested under sufficient load.

3.2. EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems' designs that may preclude proper TAB of systems and equipment.
- B. Examine systems for installed balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are accessible.
- C. Examine the approved submittals for HVAC systems and equipment.
- D. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems' output, and statements of philosophies and assumptions about HVAC/plumbing system and equipment controls.
- E. Examine equipment performance data including fan and pump curves.
 - 1. Relate performance data to Project conditions and requirements, including system

effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.

2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems – Duct Design". Compare results with the design data and installed conditions.
- F. Examine system and equipment installations and verify that field quality-control testing, cleaning and adjusting specified in individual Sections have been performed.
- G. Examine test reports specified in individual system and equipment Sections.
- H. Examine HVAC equipment and filters and verify that bearings are greased, belts are aligned and tight, and equipment with functioning controls is ready for operation.
- I. Examine terminal units, and verify that they are accessible and their controls are connected and functioning.
- J. Examine strainers. Verify that startup screens are replaced by permanent screens and indicated perforations.
- K. Examine three-way valves for proper installation for their intended function of diverting or mixing fluid flows.
- L. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- M. Examine system pumps to ensure absence of entrained air in the suction piping.
- N. Examine operating safety interlocks and controls on HVAC equipment.
- O. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.3. AIR SYSTEM PROCEDURES

- A. The balancing agency shall perform the following testing and balancing functions in accordance with the Associated Air Balance Council's National Standards:
 1. Fan Speeds - Test and adjust fan RPM to achieve design CFM requirements.
 2. Current and Voltage - Measure and record motor current and voltage. Check and record thermal overload ratings for all motors.
 3. Static Pressure - Test and record system static pressures, including suction and discharge static pressure of each fan. Measure static air pressure conditions on air supply units, including coil pressure drops, and total pressure across the fan.
 4. Air Temperature - Take wet-bulb and dry-bulb air temperatures on the entering

and leaving side of each cooling tower and closed circuit evaporative fluid cooler.

5. Tolerances - Test and balance each heat of rejection equipment to within 5 percent of design requirements. Test and balance all fans to within 5 percent of design requirements.
6. Where modulating dampers are provided, take measurements and balance at extreme conditions.

3.4. WATER SYSTEM PROCEDURES

- A. The various water circulating systems shall be filled, purged of air, and put into operation before hydronic balancing by the mechanical contractor.
- B. The flow of water through all coils shall be adjusted by manipulating balancing valves until the rated pressure drop through the coil or metering device is obtained. Perform balancing by measurement of temperature differential in conjunction with air balancing.
- C. The balancing agency shall perform the following testing and balancing functions in accordance with the AABC National Standards.
- D. All Hydronic equipment and HVAC pumps shall be Tested and Balanced as described below:
 1. Water Treatment - Examine the water in the system and determine if the water has been treated and cleaned. If it has not, request the mechanical contractor to clean and treat the water prior to TAB work
 2. Strainers - Request that the mechanical contractor clean all strainers.
 3. Air Vents - Check all air vents at the high points of the water system and determine if they are installed and operating.
 4. Valves - Set all balancing valves to the full-open position for balancing.
 5. Pumps - Adjust all pumps to meet design GPM requirements. Check pumps for proper operation. Pumps shall be free of vibration and cavitation. Measure and record operating current and voltage. Check and record thermal overloads installed on all pumps. Record in Test and Balance Report.
 6. Tolerances - Proceed to balance all coils, pumps, balance valves heat exchangers, cooling towers, and closed circuit evaporative fluid coolers to within 5 percent of design requirements.
 7. Marking - Mark all settings and record all data after completing the flow readings and coil adjustments.
 8. Where available pump capacity (due to diversity) is less than total flow requirements or individual system parts, full flow in one part may be simulated by temporary restriction of flow to other parts.
 9. Test cooling tower and closed circuit evaporative fluid cooler water level

controllers.

10. For all equipment specified with floats, test operation of such device and record results. Verify interlock with ATC system.

E. Cooling Towers/Closed Circuit Evaporative Fluid Coolers:

1. Verify that cooling towers/closed circuit evaporative fluid coolers have been filled and started by others, and are in operation. Test cooling towers/closed circuit evaporative fluid coolers fans for proper RPM and airflow.
2. Test and adjust water flows to balance cells.
3. Test and record temperature profiles for water and air side operation.
4. Current and Voltage: Test and record motor voltage and amperage, and compare with nameplate limits to ensure fan motor is not in or above service factor.
5. Test cooling tower/closed circuit evaporative fluid cooler per AABC basic test requirements for a cooling tower/closed circuit evaporative fluid cooler.

F. Existing Boilers:

1. Verify that boilers have been filled and started by others, and are in operation.
2. Current and Voltage - As applicable, test and record motor voltage and amperage, and compare data with the nameplate limits to ensure motor is not in or above the service factor.
3. Test and adjust water flow through water boilers.
4. Test and record temperature and pressure profiles of boilers.
5. Test flame failure alarms and low water cut-off alarms.
6. Test condensate block alarm.

G. Existing Heat Exchangers:

1. Verify that existing heat exchangers have been filled and started by others, and are in operation.
2. Test and adjust water flow through existing heat exchangers.
3. Test and record temperature and pressure profiles of existing heat exchangers.
4. Verification: Verify the type, location, final pressure drop and GPM of each heat exchanger. This information shall be recorded on heat exchangers test forms.

H. Closed Circuit Fluid Cooler and Indirect Fired Storage Tank:

1. Tolerances - Test, adjust, and balance all hydronic coils within 5 percent of design

requirements.

2. Verification - Verify the type, location, final pressure drop and GPM of each coil. This information shall be recorded on coil data sheets.

3.5. TESTING AND BALANCING OF EXISTING SYSTEMS

- A. The balancing agency shall perform testing and balancing of existing equipment and pump systems to the extent indicated.
- B. Test and Balance Agency shall assist the mechanical contractor in selection of new sheaves and belts, if required. Re-sheaving of cooling tower and closed circuit evaporative fluid cooler fans shall be done at no additional cost to owner. Where required, new sheave and belt size calculations shall be forwarded to the Engineer for review and approval.
- C. The Test and Balance Agency shall perform water system procedures (here-in before specified) on the following hydronic systems.
 1. Refer to schedule on Contract Drawings.
 2. Provide temperature measurements across all existing heat exchangers.
 3. For variable speed pumps, adjust existing differential pressure sensor serving existing variable speed pumps as required and record setpoint in TAB report.

3.6. VERIFICATION OF TEMPERATURE CONTROL

- A. The balancing agency shall be assisted by the temperature control contractor in verifying the operation and calibration of all temperature control systems. The following tests shall be conducted:
 1. Verify that all control components are installed in accordance with project requirements and are functional, including all electrical interlocks, damper sequences, air and water reset.
 2. Verify that all controlling instruments are calibrated and set for design operating conditions.
 3. Verify the accuracy of the final settings by taking temperature readings. The readings shall be in a typical conditioned space for each separately controlled zone.
 4. Test and calibrate all differential pressure sensors. Record set point in Record and Information Books.

3.7. TEST AND BALANCE REPORTS

- A. The test and balance report shall be complete with logs, data, and records as required herein. All logs, data, and records shall be typed on white bond paper and bound. The report shall be certified accurate and complete by the balancing agency's certified test and balance engineer.
- B. Three (3) hardcopies and one (1) electronic copy of the test and balance report are required

and shall be submitted to the Engineer. If, in the opinion of the Engineer, test results or portions thereof are incomplete or inconclusive, repeat necessary portions of the work to the satisfaction of the Engineer.

- C. The report shall contain the following general data in a format selected by the balancing agency:
 - 1. Project Number
 - 2. Contract Number
 - 3. Project Title
 - 4. Project Location
 - 5. Project Mechanical Engineer
 - 6. Test & Balance Agency
 - 7. Test & Balance Engineer
 - 8. Mechanical Contractor
 - 9. Dates tests were performed
 - 10. Certification
 - 11. Phone Numbers of all Individuals Listed Above
- D. The test and balance report shall be recorded on report forms conforming to the recommended forms in the AABC National Standards.

3.8. TEST REPORT FORMS

- A. Air Moving Equipment and Fan Test Forms - Submit fan curve showing design and operating points of operation. Also, record the following on each air-handling equipment test form:
 - 1. Manufacturer, model number, serial number, arrangement.
 - 2. All design and manufacturer-rated data.
 - 3. Suction and discharge static pressure of each fan, as applicable. Include pressure drops across coils, and similar devices.
 - 4. Actual operating current, voltage and brake horsepower of each fan motor. For packaged equipment, this includes supply fans, relief air fans, and condenser fans.
 - 5. Final RPM of each fan.
 - 6. Fan and motor sheave manufacturer, model, size, number of grooves, bore, and center distance.

7. Belt size, quantity and make.
 8. Total and external static pressure.
- B. Pump Test Forms - Submit pump curve showing design, operating, and no-flow points of operation. Also, record the following items on each pump test form:
1. Manufacturer, size, model, service and serial number.
 2. All design and manufacturer's rated data.
 3. Pump operating suction and discharge pressure and final total dynamic head.
 4. No flow (pump discharge valve closed) suction and discharge pressure and corresponding total dynamic head. This procedure is to determine actual impeller size. Record impeller size.
 5. Rated and actual operating current, voltage, and brake horsepower of each pump motor.
 6. Total operating head pressure.
 7. Shutoff, discharge and suction pressures.
 8. Shutoff, total head pressure.
- C. Closed Circuit Evaporative Fluid Cooler Coil Test Forms - Record the following items on each test form:
1. Manufacturer, location, service.
 2. All design and manufacturer's rated data.
 3. Rated and actual water pressure drop through each coil and related GPM.
 4. Rated and actual static pressure drop across each coil.
 5. Rated and actual entering and leaving water temperatures across each coil.
 6. Wet-bulb and dry-bulb temperatures entering and leaving each cooling coil; dry-bulb temperatures entering and leaving each heating coil.
 7. Air flow (Design and Actual).
 8. Electrical characteristics.
 9. Spray pump flow rate, head, and electrical data.
 10. Electric heat trace operation and safeties.
- D. Flow Measuring Station Test Forms:

1. Identification/location.
 2. Manufacturer.
 3. Size and Model Number.
 4. Design and Actual Flow Rate.
 5. Design and Actual Pressure Drop.
 6. ATC flow rate versus field measured flow rate.
- E. Existing Heat Exchanger Test Forms:
1. Identification/number.
 2. Location.
 3. Service.
 4. Manufacturer.
 5. Model number.
 6. Serial number.
 7. Water pressure, design and actual.
 8. Source water entering temperature, design and actual.
 9. Source water leaving temperature, design and actual.
 10. Source water flow, design and actual.
 11. Source water pressure drop, design and actual.
 12. Load water entering temperature, design and actual.
 13. Load water leaving temperature, design and actual.
 14. Load water flow, design and actual.
 15. Load water pressure drop, design and actual.
- F. Electric Motors Test Forms: (Applies to all motors, including pumps, fans and HVAC equipment)
1. Manufacturer.
 2. Model/Frame.
 3. HP/BHP.

4. Phase, voltage, amperage; nameplate, actual, no load.
5. RPM.
6. Service factor.
7. Starter size, rating, heater elements.
8. Sheave Make/Size/Bore.
9. Thermal overload settings

G. V-Belt Drive Test Forms:

1. Identification/location.
2. Required driven RPM.
3. Driven sheave, diameter and RPM.
4. Belt, size and quantity.
5. Motor sheave diameter and RPM.
6. Center to center distance, maximum, minimum, and actual.

H. Cooling Tower Test Forms:

1. Tower identification/number.
2. Manufacturer.
3. Model number.
4. Serial number.
5. Rated Capacity.
6. Entering air WB temperature, specified and actual.
7. Leaving air WB temperature, specified and actual.
8. Ambient Air DB temperature, specified and actual.
9. Condenser water entering temperature, specified and actual.
10. Condenser water leaving temperature, specified and actual.
11. Condenser water flow rate, specified and actual.
12. Fan RPM, specified and actual.

13. Electric heat trace operation and safeties.
14. Spray pump operation and safeties.

END OF SECTION

DIVISION 23 SECTION 23 06 00
HEATING, VENTILATING, AND AIR CONDITIONING EQUIPMENT
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. GENERAL	3
1.2. DESCRIPTION	3
1.3. SUBMITTALS	3
1.4. OPERATION AND MAINTENANCE DATA	3
1.5. DELIVERY, STORAGE, AND HANDLING	3
1.6. ENVIRONMENTAL REQUIREMENTS	4
1.7. ALTERNATES	4
1.8. EXTRA MATERIALS	4
1.9. SHORT CIRCUIT CURRENT RATINGS	4
PART 2. PRODUCTS	4
2.1. CLOSED LOOP BASE MOUNTED PUMPS - END SUCTION	4
2.2. COOLING TOWER BASE MOUNTED PUMPS - END SUCTION	5
2.3. IN-LINE CLOSE COUPLED CIRCULATING PUMP	6
2.4. CLOSED LOOP BASE MOUNTED PUMPS – END SUCTION (CLOSE COUPLED)	7
2.5. VARIABLE SPEED DRIVES	8
2.6. COMBINATION COALESCING AIR AND DIRT SEPARATOR	11
2.7. EXPANSION TANKS	12
2.8. EXTERIOR PIPE ROLLER SUPPORTS	12
2.9. WATER TREATMENT SERVICES	12
2.10. DOMESTIC WATER METER WITH ATC INTERLOCK CAPABILITIES	16
2.11. REFURBISHMENT OF EXISTING SELBYVILLE HEAT EXCHANGER	17
PART 3. EXECUTION	17
3.1. EXAMINATION	17
3.2. GENERAL INSTALLATION REQUIREMENTS	18
3.3. FIELD QUALITY CONTROL	19
3.4. DEMONSTRATION	19
3.5. CLEANING	20
3.6. FAN INSTALLATION REQUIREMENTS.	20
3.7. HVAC PUMP INSTALLATION REQUIREMENTS	21
3.8. HYDRONIC EQUIPMENT AND SPECIALTIES INSTALLATION REQUIREMENTS	22
3.9. WATER TREATMENT INSTALLATION REQUIREMENTS	23
3.10. WATER METER INSTALLATION REQUIREMENTS	23
3.11. HEAT REJECTION EQUIPMENT INSTALLATION REQUIREMENTS	23
3.12. COOLING TOWER/CLOSED CIRCUIT EVAPORATIVE FLUID COOLER WINTERIZATION REQUIREMENTS	24
END OF SECTION	25

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 23 06 00 – HEATING, VENTILATING, AND AIR CONDITIONING EQUIPMENT

PART 1. GENERAL

1.1. GENERAL

- A. The Conditions of the Contract and other General Requirements apply to the work specified in this section. All work under this section shall also be subject to the requirements of Division 23 Section, Common Work Results for HVAC and Division 01 Section General Requirements.

1.2. DESCRIPTION

- A. The work to be performed shall include all labor, materials and equipment necessary to furnish and install complete, all mechanical equipment as shown on drawings, hereinafter specified or reasonably implied, and leaving the same in satisfactory operation condition. It is the intent that systems be installed complete with all items necessary to accomplish this purpose.

1.3. SUBMITTALS

- A. Shop Drawings: Indicate assembly, equipment dimensions, weight loading, required clearances, construction details, field connection details, and electrical characteristics and connection requirements.
- B. Product Data:
 - 1. Provide literature which indicates dimensions, weights, capacities, ratings, performance, gages and finishes of materials, and electrical characteristics and connection requirements.
 - 2. Provide fan and pump curves with specified operating point clearly plotted.
 - 3. Submit sound power level data for both fan outlet and casing radiation at rated capacity. Submit sound power levels by octave band or sound pressure levels by octave band for all equipment.
 - 4. Submit electrical requirements for power supply wiring including wiring diagrams for interlock and control wiring, clearly indicating factory-installed and field-installed wiring.

1.4. OPERATION AND MAINTENANCE DATA

- A. Maintenance Data: Include instructions for lubrication, filter replacement, motor and drive replacement, spare parts lists, and wiring diagrams.

1.5. DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, protect, and handle products to site under provisions of General Requirements.
- B. Accept products on site in factory-fabricated protective containers, with factory-installed

shipping skids and lifting lugs. Inspect for damage.

- C. Store all equipment in clean dry place and protect from weather and construction traffic. Handle carefully to avoid damage to components, enclosures, and finish.
- D. Comply with manufacturer's installation instructions for rigging, unloading and transporting equipment.
- E. Protect all motors, shafts, and bearings from weather and construction dust.

1.6. ENVIRONMENTAL REQUIREMENTS

- A. Do not operate any equipment for any purpose, temporary or permanent, until ductwork/piping is clean, filters/strainers are in place, bearings lubricated, and equipment has been test run under observation.

1.7. ALTERNATES

- A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

1.8. EXTRA MATERIALS

- A. Provide one set of seals for each type and model of pump provided at each school on the project.

1.9. SHORT CIRCUIT CURRENT RATINGS

- A. Unless otherwise noted, all HVAC equipment shall include a nameplate that identifies the short circuit current rating (SCCR). Unless otherwise noted the SCCR rating for all HVAC equipment shall be a minimum of 65 KA.

PART 2. PRODUCTS

2.1. CLOSED LOOP BASE MOUNTED PUMPS - END SUCTION

- A. Furnish and install base mounted centrifugal end suction pumps to circulate hydronic water to the various items of equipment throughout the building, associated with the HVAC system. Pumps shall have sizes and capacities as indicated on the drawings.
- B. All pumps shall be suitable for the service and temperatures designated and shall conform to the following requirements. Each pump shall have a factory installed seal flushing line running from the seal area to the pump suction to insure removal of trapped air from the seal area, removal of sediment, and cooling of the seal to extend seal life. Provide and install Cuno five (5) micron filters in seal flushing lines. Provide two (2) sets of cartridges for each side - stream filter.
- C. Pumps shall be cast iron bronze fitted and shall be suitable for up to 175 psi working pressure and up to 250 degrees F water temperature. Pumps shall have center-line discharge for positive venting and flanged bodies. Pumps shall incorporate a grease lubrication system and be so designed that the bearing assembly can be removed in one piece. A water slinger shall be provided between the mechanical seal and bearing areas.

Pump shafts shall be stainless steel with a cupro-nickel sleeve, and be coupled to the motor shaft by a noiseless, non-metallic coupler with guard. Impellers shall be one piece cast bronze, dynamically balanced. Motors shall be 1750 rpm. For variable speed pumps, motors shall be inverter duty rated.

- D. Pumps shall be designed so that they shall not overload at low heads and shall not develop excessive pressure under throttled flow conditions or overload motor anywhere on the operating curve. Operating performance curves shall be submitted for approval. Provide gauge tapings on each pump flange. Furnish dust caps at all oil fill tubes. Pump motors shall be non-overloading throughout the range of the curves.
- E. Units shall be provided with motors of not less than the horsepower indicated, suitable for the service and available electrical characteristics. Units shall be controlled as hereinafter specified. After installation and prior to operation, each pump shall be aligned. Motors shall be as specified hereinbefore.
- F. Casing: Cast iron, with suction and discharge gage ports, renewable bronze casing wearing rings, seal flush connection, drain plug, flanged suction and discharge.
- G. Impeller: Bronze, fully enclosed, keyed to shaft. For open loop cooling tower/closed circuit evaporative fluid cooler applications, the impellers shall be Type 304 stainless steel.
- H. Baseplate: Cast iron or fabricated steel with integral drain rim.
- I. Pumps shall be primed and painted in baked enamel, rust resistant paint.
- J. Electrical characteristics shall be as scheduled on the contract drawings. Provide terminal lugs to match branch circuit conductor quantities, sizes, and materials indicated. Enclose terminal lugs in terminal box sized to NFPA-70.
- K. Pumps shall be FE series as manufactured by Taco, 2000 Series by Allis Chalmers, Aurora, Bell & Gossett, PACO, Armstrong, Patterson, or as approved equal.

2.2. COOLING TOWER BASE MOUNTED PUMPS - END SUCTION

- A. Furnish and install base mounted centrifugal end suction pumps to circulate cooling tower water to the various items of equipment throughout the building, associated with the HVAC system. Pumps shall have sizes and capacities as indicated on the drawings.
- B. All pumps shall be suitable for open loop service and temperatures designated and shall conform to the following requirements. Each pump shall have a factory installed external seal flushing line with separator/filter running from the seal area to the pump suction to insure removal of trapped air from the seal area, removal of sediment, and cooling of the seal to extend seal life. Provide and install Cuno five (5) micron filters in seal flushing lines. Provide two (2) sets of cartridges for each side - stream filter.
- C. Pumps shall be bronze fitted and shall be suitable for up to 175 psi working pressure and up to 250 degrees F water temperature. Pumps shall have center-line discharge for positive venting and flanged bodies. Pumps shall incorporate a grease lubrication system and be so designed that the bearing assembly can be removed in one piece. A water slinger shall be provided between the mechanical seal and bearing areas. Pump shafts shall be stainless

steel with a cupro-nickel sleeve, and be coupled to the motor shaft by a noiseless, non-metallic coupler with guard. Impellers shall be one piece cast bronze, dynamically balanced. Motors shall be 1750 rpm. For variable speed pumps, motors shall be inverter duty rated.

- D. Pumps shall be designed so that they shall not overload at low heads and shall not develop excessive pressure under throttled flow conditions or overload motor anywhere on the operating curve. Operating performance curves shall be submitted for approval. Provide gauge tapings on each pump flange. Furnish dust caps at all oil fill tubes. Pump motors shall be non-overloading throughout the range of the curves.
- E. The pump seal shall be specifically selected for open cooling tower water with a fluid PH of between 7.0 and 8.5. Tungsten carbide pump seals shall be provided due to abrasion resistance.
- F. Units shall be provided with motors of not less than the horsepower indicated, suitable for the service and available electrical characteristics. Units shall be controlled as hereinafter specified. After installation and prior to operation, each pump shall be aligned. Motors shall be as specified hereinbefore.
- G. Casing: Cast iron, with suction and discharge gage ports, renewable bronze casing wearing rings, seal flush connection, drain plug, flanged suction and discharge.
- H. Impeller: Type 304 stainless steel fully enclosed, keyed to shaft.
- I. Baseplate: Cast iron or fabricated steel with integral drain rim.
- J. Pumps shall be primed and painted in baked enamel, rust resistant paint.
- K. Electrical characteristics shall be as scheduled on the contract drawings. Provide terminal lugs to match branch circuit conductor quantities, sizes, and materials indicated. Enclose terminal lugs in terminal box sized to NFPA-70.
- L. Pumps shall be FE series as manufactured by Taco, 2000 Series by Allis Chalmers, Aurora, Bell & Gossett, PACO, Armstrong, Patterson, or as approved equal.

2.3. IN-LINE CLOSE COUPLED CIRCULATING PUMP

- A. Furnish and install in-line closed coupled circulating pumps as shown on the contract drawings. Pump and motor shall be equipped with permanently lubricated bearings for quiet operation. Pumps shall be suitable for up to 150 psi working pressure and up to 225 degrees F water temperature as per ASA B16.1. Pump rating curves shall be the result of testing and rating in accordance with the procedures of the Hydraulic Institute.
- B. The pumps shall be of the horizontal, permanently lubricated type, specifically designed and guaranteed for quiet operation.
- C. Provide gauge tapings on each pump flange.
- D. The pumps shall have a steel shaft supported by permanently lubricated, sealed precision ball bearings. The pumps are to be equipped with a water-tight seal to prevent leakage.

Mechanical seal faces to be carbon on silicon carbide. The motor shall be non-overloading at any point on the pump performance curve.

- E. The motor shall be of the drip-proof, sealed precision ball-bearing, quiet-operating construction. The permanent split-capacitor motor shall be equipped with thermal overload protection.
- F. Pumps to be suitable for 0 degrees to 225 degrees F (107 degrees C) operating temperature at 150 psig (10 bar) working pressure.
- G. Pumps shall be provided with all bronze construction when used in open systems and shall be bronze fitted for closed systems.
- H. Electrical characteristics shall be as scheduled on the contract drawings. Provide terminal lugs to match branch circuit conductor quantities, sizes, and materials indicated. Enclose terminal lugs in terminal box sized to NFPA-70.
- I. In line pumps shall be close coupled in-line circulators Model PL as manufactured by Bell & Gossett, Thrush, Armstrong, Taco, Patterson, or as approved equal.

2.4. CLOSED LOOP BASE MOUNTED PUMPS – END SUCTION (CLOSE COUPLED)

- A. Furnish and install base mounted close coupled centrifugal end suction pumps to circulate hydronic water to the various items of equipment throughout the building, associated with the HVAC system. Pumps shall have sizes and capacities as indicated on the drawings.
- B. All pumps shall be suitable for the service and temperatures designated and shall conform to the following requirements. Each pump shall have a factory installed seal flushing line running from the seal area to the pump suction to ensure removal of trapped air from the seal area, removal of sediment, and cooling of the seal to extend seal life. Provide and install Cuno five (5) micron filters in seal flushing lines. Provide two (2) sets of cartridges for each side - stream filter.
- C. Pumps shall be cast iron bronze fitted and shall be suitable for up to 175 psi working pressure and up to 250°F water temperature. Pumps shall have center-line discharge for positive venting and flanged bodies. Pumps shall incorporate a grease lubrication system and be so designed that the bearing assembly can be removed in one piece. A water slinger shall be provided between the mechanical seal and bearing areas. Pump shafts shall be stainless steel with a cupro-nickel sleeve, and be close coupled to the motor shaft. Impellers shall be one piece cast bronze, dynamically balanced. Motors shall be 1750 rpm.
- D. Pumps shall be designed so that they shall not overload at low heads and shall not develop excessive pressure under throttled flow conditions or overload motor anywhere on the operating curve. Operating performance curves shall be submitted for approval. Provide gauge tappings on each pump flange. Furnish dust caps at all oil fill tubes. Pump motors shall be non-overloading throughout the range of the curves.
- E. Units shall be provided with motors of not less than the horsepower indicated, suitable for the service and available electrical characteristics. Units shall be controlled as hereinafter specified. After installation and prior to operation, each pump shall be aligned. Motors shall be as specified hereinbefore.

- F. Casing: Cast iron, with suction and discharge gage ports, renewable bronze casing wearing rings, seal flush connection, drain plug, flanged suction and discharge.
- G. Impeller: Bronze, fully enclosed, keyed to shaft.
- H. Baseplate: Cast iron or fabricated steel with integral drain rim.
- I. Pumps shall be primed and painted in baked enamel, rust resistant paint.
- J. Electrical characteristics shall be as scheduled on the contract drawings. Provide terminal lugs to match branch circuit conductor quantities, sizes, and materials indicated. Enclose terminal lugs in terminal box sized to NFPA-70.
- K. Pumps shall be CI series as manufactured by Taco, Allis Chalmers, Aurora, Bell & Gossett, PACO, Armstrong, Patterson, or approved equal.

2.5. VARIABLE SPEED DRIVES

- A. Provide variable speed drive controllers for cooling tower fans, closed circuit evaporative fluid cooler fans, and pumps as indicated on contract drawings. Drive shall be subject to the requirements of this section.
- B. The adjustable frequency controller (AFC) shall convert three phase 60 Hertz utility power to adjustable voltage and frequency, three phase, AC power for stepless motor control from 5 percent to 110 percent of base speed.
- C. The AFC shall be a voltage source type with a PWM output utilizing power transistor semi-conductors.
- D. The AFC together with all options and modifications shall mount within a standard NEMA 1 enclosure or NEMA-4X for exterior installation suitable for continuous operation at ambient temperature of 0 to 40 degrees C. with relative humidity to 95 percent non-condensing. All high voltage components within enclosure shall be isolated with steel covers. The complete unit shall be UL approved and UL labeled.
- E. Circuits shall provide DV/DT and DI/DT protection for semi-conductors. AFC shall be capable of starting into a rotating load without delay. Protective circuits shall cause instantaneous trip (IET) should any of the following faults occur:
 - 1. Motor overload.
 - 2. Shortcircuit.
 - 3. Motor overtemperature fault.
 - 4. Reverse phase.
 - 5. 110 percent of controller maximum sine wave current rating is exceeded.
 - 6. Output phase to phase and phase to ground short circuit condition.
 - 7. High input line voltage.

8. Low input line voltage.
 9. Loss of input phase.
 10. External fault. This protective circuit shall permit, by means of the terminal strip, wiring of remote NC safety contacts such as high static, firestat, etc., to shut down the drive.
- F. The following adjustments shall be available in the controller and retained in non-volatile memory:
1. Maximum frequency (15 to 400 Hz) factory set at 60 Hz.
 2. Minimum frequency (3 to 60 Hz) factory set at 6 Hz.
 3. Acceleration (.1 to 360 seconds) factory set at 20 seconds.
 4. Deceleration (.1 to 360 seconds) factory set at 20 seconds.
 5. Volts/Hertz ratio factory set for 460V at 60 Hz.
 6. Voltage offset or boost factory set at 100 percent torque.
 7. Current limit (50 percent to 110 percent sine wave current rating) factory set at 100 percent current.
- G. The AFC shall have the following basic features:
1. Door-mounted operators controls consisting of a membrane command center which allows manual stop/start and speed control, local/remote indication and manual/or automatic speed control selection. In addition, the command center shall serve as a means to configure controller parameters such as min speed, max speed, acceleration and deceleration times, Volts/Hz ratio, torque boost etc. Potentiometers shall not be allowed for these settings.
 2. Main input disconnect to provide a positive disconnect between the controller and all phases of the incoming A-C line. This disconnect shall be mounted inside the controller enclosure and have through-the-door interlocking toggle with provisions for padlocking.
 3. Electronic motor overload relay.
 4. Automatic restart after power outage, drive fault or external fault, with drive in automatic mode. The circuit shall allow the user to select up to (10) restart attempts as well as the dwell time between attempts. The reset time between fault occurrences shall also be selectable. All settings shall be via the membrane command center.
 5. Door-mounted LED display for digital indication of:
 - a. Frequency output
 - b. Voltage output

- c. Current output
 - d. First fault indication
 - e. Fan or Pump Speed (RPM)
- 6. Relay contacts for remote indication of drive fault and motor finning.
 - 7. Three critical frequency avoidance bands, field programmable via the membrane command center. Each critical frequency avoidance band shall have a bandwidth adjustable via keypad entry of up to 10 Hz.
 - 8. Three programmable preset speeds which shall force the AFC to a preset speed upon a user contract closure.
 - 9. Isolated process follower to enable VFC to follow a 4-20 mA signal.
 - 10. The AFC shall have the capability to ride through power dips up to 500 msec without a controller trip depending on load and operating condition.
 - 11. Line reactor to minimize line surges, line notching, and voltage distortions. Line reactor shall be installed upstream of the drive.
- H. Manual bypass-to-line with magnetic contactors to transfer motor from the variable frequency controller to full speed operation on utility supplied input power while the motor is at any speed. Two motor contactors, electrically interlocked shall be utilized, one contactor between the controller output and the motor and the other between the bypass power line and the motor, providing across-the-line starting.
 - I. Motor protection per National Electrical Code shall be provided in both the "controller" mode and the "bypass" mode by a motor overload relay. The 115 volt A-C relay control logic, allowing common start/stop commands in the "controller" mode and the "bypass" mode shall also be included within the enclosure.
 - J. The bypass shall include a door interlocked, main power input circuit breaker providing positive shutdown of all power to both the bypass circuitry and the VFC. The bypass circuit shall also include a second input disconnect to the VFC. This disconnect shall provide the ability to safely troubleshoot and test the controller, both energized and de-energized, while operating the bypass mode.
 - K. The VFC and all components shall be supplied within a single NEMA 1 enclosure, and shall be U.L. Listed as a single unit. Furnish all components necessary to provide a minimum lead length between motor and drive of 400 ft. The VFC shall not generate damaging transistor pulses greater than the limits set by NEMA MG-1 at 400 Ft lead length.
 - L. The VFC manufacturer shall maintain and staff nationwide service centers. These service engineers shall be employed by the manufacturer and provide start-up service including physical inspection of drive and connecting wiring and final adjustments to meet specified performance requirements.
 - M. The VFC shall carry a full parts and labor warranty for two years from date of substantial completion.

- N. The variable speed drive shall be ABB, or approved equal of Accutrol, Cutler Hammer, Graham, York, Baldor, AC Tech, Trane, Emerson, Danfos, Yaskawa, Toshiba, or as approved equal.
- O. The variable speed drive manufacturer shall coordinate with the ATC contractor and provide all necessary devices whether optional or not to perform complete and automatic operation as described in the sequence of operation. All safeties, including freezestats, duct smoke detectors, and high static pressure sensors shall be enabled when variable speed drives are in manual or bypass.
- P. BAS Interface: Factory-installed hardware and software to enable the BAS to monitor, control, and display VFC status and alarms. Allows VFC to be used with an external system within a multidrop LAN configuration; settings retained within VFC's nonvolatile memory.
 - 1. Network Communications Ports: Ethernet and RS-422/485.
 - 2. Embedded BAS Protocols for Network Communications: ASHRAE 135 BACnet; protocols accessible via the communications ports.
- Q. Variable speed drives shall be carefully selected for the duty required. Variable speed drives shall be specifically designed for the specified equipment to be controlled. Pump drives shall be selected for pumps and fan drives shall be selected for fans.

2.6. COMBINATION COALESCING AIR AND DIRT SEPARATOR

- A. Furnish and install as shown on the drawings a Spirotherm steel, Taco Series 4900, Caleffi, Armstrong, Wessels, or approved equal air elimination and dirt separator. All fittings shall be fabricated steel, rated for 150 psig design pressure and selected for less than 1 foot of water pressure drop and velocity not to exceed 4 feet per second through the unit at specified GPM. All units shall include an integral copper bundle of Spirotubes or approved equal, to act as the turbulence suppressive coalescing medium which must completely fill the fitting's internal area. Units are to remove free and entrained air during system start up and continue to eliminate dissolved air and dirt through continual circulation and the coalescing action of the Spirotubes. Each fitting is to have a separate air and venting chamber to prevent system contaminants from harming the float and venting valve operation. At the top of the venting chamber shall be an integral float actuated brass air vent. There shall be no restriction in the connection from the venting chamber to the vent. The fittings are to include a valve side tap to flush floating dirt or liquids and for quick bleeding of large amounts of air during system fill or refill. Units shall include a bottom connection for use as a blow down connection for periodic cleaning. Unit shall have the bottom of the vessel extended for dirt separation with the system connection nozzles equal distant from the top and bottom of the vessel. Air separator shall be primed and finished in rust resistant paint. Units shall be Spirovent dirt models of the size required to meet pressure drop and velocity criteria.
- B. A blowdown connection and valve shall be provided to facilitate routine cleaning of the strainer and the separator. Unit shall include a removable lower head to facilitate removal of the tube assembly for cleaning.
- C. A manufacturer's data report for pressure vessels, for U-1 as required by the provisions of

ASME Boiler and Pressure Vessel code, shall be furnished for each air separator upon request. Manufacturer to furnish data sheet specifying air collection efficiency and pressure drop at rated flow.

- D. Conventional tangential or centrifugal non-coalescing air separators shall not be acceptable.

2.7. EXPANSION TANKS

- A. Furnish and install as shown on the drawings, pre-pressurized captive air bladder type expansion tank pre-charged with air. Tank shall be suitable for a maximum working pressure of 125 psi and constructed and certified to ASME Section VII. It shall have a replaceable elastomeric bladder suitable for a maximum operating temperature of 240 degrees F (115 degrees C). Expansion tanks shall be primed and finished in rust resistant paint. It shall have an integral steel base ring for vertical mounting and saddle for horizontal mounting. Expansion tank shall be as manufactured by Taco, Bell & Gossett, Wessels, Amtrol, Armstrong or as approved equal.

2.8. EXTERIOR PIPE ROLLER SUPPORTS

- A. Furnish and install pipe roller supports for all exterior piping as indicated on contract drawings. Pipe roller supports shall be constructed of heavy gauge galvanized steel, continuous welded corner seams, 2 x 4 treated wood nailer, heavy gauge galvanized steel counterflashing with galvanized steel channel track attached.
- B. Roller assembly shall consist of galvanized steel channel track, galvanized steel fittings, washers, nuts, and painted cast iron roller. Installation shall permit both vertical and horizontal adjustment. Units shall be Pate Model RAC, RTS, or approved equal.

2.9. WATER TREATMENT SERVICES

- A. Complete chemical water treatment service shall be provided by an organization regularly engaged in water treatment, Condor, ARC, Inc., RCCO Corp., Aquatel Ind., Inc., Mogul Corp., Oilin, Inc., HVAC Services, Inc., Feedwater Treatment Systems, Inc., Eco-Lab, Kurita, or approved equal. The service shall provide all equipment, chemicals and labor necessary to prevent corrosion, inhibit scale build-up and minimize organic growth for a period of 2 years starting from building acceptance. Service visits for the purpose of adding chemicals to feeding equipment, regulating bleed-off, inspecting and adjusting water treatment equipment, and obtaining samples of laboratory analysis shall be performed at monthly intervals for closed systems and every two weeks for open systems during the entire guarantee period. Chemicals shall not be injurious to water side equipment and construction materials. Records of all injurious to water side equipment and construction materials. Records of all service visits, chemical additions, laboratory tests, etc., shall be maintained and shall be provided to owner after each visit during guarantee period. Instruct mechanical contractor in field on piping and wiring of chemical feeding equipment.
- B. Systems to be protected shall include open loop cooling tower, closed circuit evaporative fluid cooler systems, and heat pump water systems. Services shall include flushing and cleaning of piping systems specified under Division 23 Section, "HVAC Piping, Fittings, and Valves" section, furnishing and installing all chemical treatment equipment and accessories to perform the water treatment specified below. Maintain complete records of the treatment program for each system. The potable makeup water properties for each

school are as follows: Water Treatment Systems and Chemicals shall be custom designed for the potable water properties at each school.

G.W. Carver Educational Center		
Attribute	MU	Units
Conductivity	296	umho/cm
pH	7.4	
Total Hardness	40	ppm as CaCO ₃
Ca Hardness	22	ppm as CaCO ₃
Alkalinity	52	ppm as CaCO ₃
Silica	18	ppm
Chlorides	14	ppm
Phosphate	0.1	ppm
Iron	0.09	ppm

Selbyville Middle School		
Attribute	MU	Units
Conductivity	293	umho/cm
pH	7.9	
Total Hardness	28.0	ppm as CaCO ₃
Ca Hardness	15.9	ppm as CaCO ₃
Mg Hardness	12.2	ppm as CaCO ₃
Alkalinity	81.1	ppm as CaCO ₃
Silica	14	ppm
Chlorides	23.2	ppm

Selbyville Middle School		
Attribute	MU	Units
Sulfate	30.0	ppm
Phosphate	0.6	ppm
Sodium	46.8	ppm
Iron	<0.1	ppm
Manganese	<0.1	ppm

- C. Contractor shall perform an analysis of the building water supply as a basis of the chemical treatment. Contractor shall provide the Owner with written instructions for chemical feeding bleed-off, blowdown control and testing procedures, provide all required chemicals, filters, and testing during the guarantee period, and provide all required test kits.
- D. Contractor shall maintain the following conditions in each system:

SYSTEMS	Heat pump systems (Closed Loop)	Closed Circuit Evaporative Fluid Cooler System/Cooling Tower System (Open Loop)
ph	8.0 to 10.5	7.0 to 8.5
Inhibitor for Scale & Corrosion Cycles	---	4 to 8 PPM (as Molybdate)
Cycles*	---	6 maximum
Organic growths	---	less than 10,000 bacteria/ml
Buffered Nitrate	550 ppm	
Chromate (Low)		
Molybdate	30 to 50 ppm	---
Sulfite	---	---
Sodium Nitrite	500 to 1000 PPM	
Corrosion Inhibitor	100 to 150 PPM (as Molybdate) or 1000 to 1500 PPM sodium Nitrite	50 to 100 PPM (as Molybdate) or 500 to 1000 PPM Sodium Nitrite

*Actual cycles of concentration to be determined from analysis of make-up water.

- E. Chemical Feeding Equipment: Provide chemical feeding equipment, as specified below, to introduce chemicals into each system only when the system is operating.
1. Closed Recirculating Systems
 - a. Five (5) gallon steel by-pass feeder installed across circulating pump suction and discharge lines, with tank and piping insulated using the same thickness and type of insulation as provided for the piping system. Provide filter. Unit shall contain quick opening cap and shall be suitable for working pressure of 175 psig. Tank shall be primed and finished in baked enamel paint.
 2. Replace bypass feeder filter monthly during the entire 2-year warranty period.
 3. The filters shall be provided and replaced for both the new bypass feeders and the existing to be reused bypass feeders for the entire warranty period.
 4. Closed Circuit Evaporative Fluid Cooler and Cooling Towers:
 - a. Controlled volume chemical feed pumps Stenner Model - LMI Model P021-352TI, Peristaltic pumps or approved equal. (115/1/60 Elec. Characteristics).
 - b. Thirty-five (35) gallon polyethylene chemical solution tanks with pump mounted on tank lid. Provide separate tanks and pumps for inhibitors and biocides.
 - c. Motorized ball valves for bleed-off.
 - d. WALCHEM Model W600 control panel for automatic control of chemical feed, bleed-off and dual biocide feed. The panel shall contain a solid state temperature compensated conductivity controller with instant visual readout of conductivity, indicator lights for power, flow, feed and bleed, plus a solid state timer for chemical feed pump operation. Panel shall have 0-20-000 micromho range, temperature display, high and low alarm, water meter totalizer, 4-20 milliamp recorder output, inhibitor chemical pump output. Panel shall be supplied with a pre-piped PVC flow switch assembly with conductivity sensor. Panel function will be deactivated when cooling tower or closed circuit evaporative fluid cooler spray pumps are not operating. Provide Bacnet interface card for mapping over all control points and alarms. Perform system integration with BMS vendor/system.
 - e. All make-up water, chemical treatment and bleed-off power and control wiring, shall be furnished and installed under Division 23.
 - f. Motorized ball valves for makeup water.
 - g. Provide corrosion coupon racks as detailed and scheduled. Coupon racks shall be four (4) test coupon type with clear PVC piping, flow regulator, variable inline flow meter, and Y strainer as manufactured by Eddington Industries or approved equal.
 - h. Provide contacting head domestic water meter as specified below.
 - i. All open loop water treatment piping and valves shall be PVC.

- F. Legionella Test: Perform monthly tests of the cooling tower and closed circuit evaporative fluid cooler water, when operating, for Legionella pneumophila. Submit reports stating legionella bacteria count per milliliter to customer. Tests shall be conducted in a certified laboratory and not by a technician in the field.
- G. Closed Recirculating Systems shall be filled and sufficient detergent and dispersant added to remove all dirt, oil, and grease. System shall be circulated for at least 48 hours after which a drain valve at the lowest point shall be opened and allowed to bleed while the system continues to circulate. The automatic make-up valve shall be checked to be sure it is operating. Bleeding shall continue until water runs clear and all detergent is removed. A sample of water shall be tested and if PH exceeds the PH of the make-up water, flushing shall be resumed. After chemical cleaning is satisfactorily complete, open the inlet and outlet valves to each coil and close the bypass valves. Also, clear all strainers.
- H. Before adding cleaned chemicals to the closed system, all coils should be isolated by closing the inlet and outlet valves by opening the bypass valves. Also clean all strainers.

2.10. DOMESTIC WATER METER WITH ATC INTERLOCK CAPABILITIES

- A. Furnish and install a bronze contacting head water meter on make-up water service to cooling tower and closed circuit evaporative fluid coolers and where indicated. The water meter shall be Model AWM as manufactured by Advantage Controls, Niagara, Rockwell, Hersey, or approved equal. Unit shall be sized and selected so as not to exceed the scheduled maximum pressure drop at design flow.
- B. Main cases for all sizes shall be cast Water Works bronze. Size, model and direction of flow shall be cast, in raised characters, on both sides of the Main cases.

Operating Characteristics		
Meter Size	Low Flow (95 percent minimum)	Normal Range (100.0 +/- 1.5 percent)
1-inch	1	1 to 50
1-1/4 inch	1.5	1.5-100

- C. Meters shall have performance capabilities of continuous operation up to the rated maximum flows as outlined above without affecting long term meter accuracy or causing undue wear. Meters shall also have a 25 percent flow capacity in excess of the maximum flows listed for intermittent flow demands.
- D. The measuring chamber shall be of unitized construction (i.e., complete with measuring element, calibration device and register in one assembly). The measuring chamber shall be capable of operating within above listed accuracy limits without recalibration when transferred from one main case to another. The measuring element shall be mounted on a horizontal stationary shaft with sleeve bearings and be essentially weightless in water.
- E. The register shall be permanently hermetically sealed; all registers of similar size and registration to have a standard ratio gear reduction so as to permit interchange ability. The register shall be assembled to measuring chamber in a tamper proof manner so removal can be made only after measuring chamber is removed from the maincase. Sweep hand reading and odometer wheel details will conform to American Water Works Standard C-701, as most recently revised.

- F. All reduction gearing shall be enclosed in the permanently hermetically sealed register. The drive magnet shall be located in the measuring element, and the follower magnet shall be located inside the permanently hermetically sealed register. An intermediate magnetically active material shall be required to distribute the magnetic flux uniformly to the follower magnet, thereby improving the service life of the register's rotating components.
- G. All meters shall operate without leakage, damage or malfunction up to a maximum operating pressure of 150 pounds per square inch.
- H. The water meter shall be fully field insulated and jacketed to prevent condensation.
- I. The water meter shall be provided with a high frequency pulse output device for interface with Automatic Temperature Control System and water treatment system.
- J. A Pulse to DC converter shall be supplied with the Infrared Pulser. The device shall convert pulses from a variety of liquid flow sensing devices to a 4-20mA output signal which is proportional to the flow rate. This output shall transmit flow rate data over long distances with no loss of accuracy. The converter shall be Model 1005 as manufactured by Hersey or approved equal.
- K. Water meter shall be provided by the water treatment contractor and coordinated with the water treatment system control panel and the automatic temperature control system.

2.11. REFURBISHMENT OF EXISTING SELBYVILLE HEAT EXCHANGER

- A. The existing heat exchanger shall be refurbished per the following scope of work:
 - 1. Clean, flush, and purge heat exchanger per the existing heat exchanger manufacturer's requirements.
 - 2. Provide and coordinate jobsite dumpster for proper disposal of materials.
 - 3. Replace plates and gaskets per manufacturer's requirements. Pressure test per manufacturer's requirements.
 - 4. Clean heat exchanger heat transfer surfaces of accumulated dirt and debris.
 - 5. Record entering and leaving temperatures/pressures on both sides of heat exchanger.
 - 6. Test and Balance existing heat exchangers and submit all test results.
 - 7. Furnish and install new pipe trim and controls as detailed.
 - 8. Replace entire plate pack for a Tranter Model UXP-200 with 137 plates.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Verify all dimensions by field measurements. Verify that all equipment may be installed

in accordance with pertinent codes and regulations, the original design, and the referenced standards.

- B. Verify structure, mounting supports and membrane installations are completed to the proper point to allow installation of roof mounted equipment, where applicable.
- C. Examine rough-in requirements for all piping systems to verify actual locations of piping connections prior to installation.
- D. Verify that electrical work installation is in accordance with manufacture's submittal and installation requirements of Division 26 sections. Do not proceed with equipment start-up until electrical work is acceptable to equipment installer. Coordinate sizes of all thermal overloads with Division 26.
- E. Do not proceed until unsatisfactory conditions have been corrected.
- F. Provide wiring diagrams of all equipment as specified in Division 23 Section, Common Work Results for HVAC.

3.2. GENERAL INSTALLATION REQUIREMENTS

- A. Install all equipment in accordance with manufacturer's installation instructions, in accordance with state and local code requirements, and in accordance with the contract drawings. Install all equipment plumb and level, to tolerances as required by the manufacturer of each item of equipment. Maintain manufacturer recommended clearances around and over all equipment.
- B. Coordinate vibration isolation requirements with all equipment in accordance with Division 23 Section, Vibration Controls for HVAC and Plumbing Equipment.
- C. Coordinate all electrical requirements with Division 26.
- D. Coordinate all indoor and outdoor equipment pad locations and sizes with approved shop drawing submittals. Provide operating weights of equipment to Engineer for review. Coordinate equipment pad locations and sizes with the Concrete Contractor or General Contractor. Furnish anchor bolts which are to be inserted in concrete pads to concrete installer.
- E. Verify piping arrangements of all equipment with the contract drawings. Piping details shall be strictly adhered to concerning valves, fittings, components, etc. At coils, where a rebuildable and repairable autoflow valve is installed in the line without the need for draining or shutting of the water, the same may be utilized as the isolation valve and additional shut-off valve is not required.
- F. Connect all equipment, devices and components to wiring systems and to ground as indicated and instructed by manufacturer. Tighten connectors and terminals, including screws and bolts, according to equipment manufacturer's published torque tightening values for equipment connectors. Where manufacturer's torquing requirements are not indicated, tighten connectors and terminals according to tightening requirements specified in UL 486A.

- G. Testing: After installing HVAC equipment, devices and components and after electrical circuitry has been energized, demonstrate product capability and compliance with requirements.
- H. Remove and replace malfunctioning units with new units and retest.
- I. All mechanical penetrations or terminations in exterior walls shall be flashed and caulked watertight.
- J. Arrange for equipment such as cooling towers and closed circuit evaporative fluid coolers to be shipped to project in modules where space constraints require the same. Field erect components as required.

3.3. FIELD QUALITY CONTROL

- A. Where indicated provide the services of a factory authorized service representative to examine the field assembly of components, installation, piping, electrical connections, controls, and clearances. Submit factory start-up check list to Engineer for information purposes. Testing and balancing work shall not commence until start-up reports have been completed, reviewed by Engineer, and forwarded to Testing and Balancing Agency.
- B. Where factory start-up of equipment is not specified, provide field start-up by qualified technician to examine the field assembly of components, installation, piping, electrical connections, controls and clearances. Record equipment manufacturers standard start-up information and submit to Engineer for review. Testing and balancing work shall not commence until start-up reports have been completed, reviewed by Engineer, and forwarded to Testing and Balancing Agency.
- C. Charge all refrigerant systems with refrigerant and oil and test for leaks. Repair leaks and replace lost refrigerant and oil.
- D. Fill all hydronic systems with water and/or antifreeze (when required after flushing and test for leaks. Repair leaks and replace lost water and/or antifreeze. Coordinate with water treatment contractor.
- E. Submit to Engineer a written table of all relief valve and make-up water valve settings for each system. Provide an additional copy in the Operations and Maintenance Manuals.
- F. Verify proper motor sizes, voltages, thermal overloads, nameplate data, etc. All equipment voltages and current shall be recorded to insure that motors are operating below their service factors. Test and Balance Engineer shall record electrical data before continuous or permanent operation.

3.4. DEMONSTRATION

- A. Provide the services of a factory authorized service representative to provide start-up and to demonstrate and train the Owner's maintenance personnel.
- B. Place equipment into operation and adjust controls and safeties. Replace damaged or malfunctioning components and controls.

C. Training:

1. Train the Owner's maintenance personnel on start-up and shut-down procedures, trouble shooting procedures, lubrication, servicing procedures and preventative maintenance schedules/procedures. Review with the Owner's personnel, the contents of the operation and maintenance data specified in Division 23 Section, Common Work Results for HVAC.
2. Submit operation and maintenance data as soon as possible prior to project close-out. Operations and maintenance data shall be submitted to the Owner for review and comment prior to submission to the Engineer.
3. Schedule training with the Owner through the Engineer with at least seven (7) days prior notice.

3.5. CLEANING

- A. After completing installation, inspect exposed finish. Remove burrs, dirt, and construction debris, and repair damaged finishes including chips, scratches, and abrasions.
- B. Clean fan and equipment interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheels, cabinets, and coils' entering air face.

3.6. FAN INSTALLATION REQUIREMENTS.

- A. Install fans with resilient mounting and flexible electrical leads.
- B. Install flexible connections and vibration isolators as specified in Division 23 Section, Common Work Results for HVAC and Division 23 Section Vibration Controls for HVAC, Plumbing Equipment. Ensure metal band of connectors are parallel with minimum one inch flex between ductwork and fan while running.
- C. Provide safety screens/guards on all fans and permanently mount after final testing and balancing.
- D. Do not operate fans for any purpose until ductwork is clean, filters in place, bearings lubricated, and fans have been test run under operation.
- E. Provide sheave required for final air balance.
- F. Install fans according to manufacturer's written instructions.
- G. Adjust damper linkages for proper damper operation.
- H. Adjust belt tension.
- I. Lubricate bearings.
- J. Replace fan and motor pulleys and belts as required to achieve design conditions.

3.7. HVAC PUMP INSTALLATION REQUIREMENTS

- A. Provide access space around pumps for service. Provide no less than minimum as recommended by manufacturer.
- B. Decrease from line size with long radius reducing elbows or reducers. Support piping adjacent to pump such that no weight is carried on pump casings. For close coupled or base mounted pumps, provide supports under elbows on pump suction and discharge line sizes 4 inches (102 mm) and over.
- C. Provide drains for bases and seals, piped to and discharging into floor drains.
- D. Check, align, and certify alignment of base mounted pumps prior to start-up. Prior to starting pumps, the alignment of the pumps and their motors or other drivers shall be carefully checked. Alignment should be checked for both offset and angularity. Alignment by means of a laser shall be accomplished for all base mounted pumps. Alignment by straight edge across the pump couplings shall not be acceptable. Submit laser pump shaft alignment results to Engineer for review.
- E. Install close coupled and base mounted pumps on concrete housekeeping pads, with anchor bolts, set and level, and grout in place. See Division 23 Section, Vibration Controls for HVAC and Plumbing Equipment for inertia pad requirements. After alignment is correct, tighten foundation bolts evenly but not too firmly, completely fill baseplate with non-shrink, non-metallic grout while metal blocks and shims or wedges are in place. After grout has cured, fully tighten foundation bolts. Submit and insert a copy of the laser alignment test report in the Operations and Maintenance Manuals.
- F. Lubricate pumps before start-up.
- G. Provide side-stream filtration system for base mounted pumps. Install across pump with flow from pump discharge to pump suction from pump tappings. Install flow indicator, filter housing with cartridge filter, shut-off valves, and flow control valves. Install 30 micron filter for start-up and 5 micron filter for system operation.
- H. Install pumps according to manufacturer's written instructions.
 - 1. Install pumps according to HI 1.1 1.5, Centrifugal Pumps for Nomenclature, Definitions, Application and Operation.
- I. Install pumps to provide access for periodic maintenance, including removing motors, impellers, couplings, and accessories.
- J. Suspend in line pumps using continuous thread hanger rod and vibration isolation hangers. Install kindorf pump supports for vertical in-line pumps and maintain clean space above for future motor replacement.
- K. Set base mounted pumps on concrete foundation. Disconnect coupling halves before setting. Do not reconnect couplings until alignment operations have been completed.
 - 1. Support pump baseplate on rectangular metal blocks and shims, or on metal wedges with small taper, at points near foundation bolts to provide a gap of 3/4 to

1 1/2 inches between pump base and foundation for grouting.

2. Adjust metal supports or wedges until pump and driver shafts are level. Check coupling faces and suction and discharge flanges of pump to verify that they are level and plumb.
- L. Cooling tower pumps shall not be installed with suction diffusers. Large mesh flanged wye-pattern strainers shall be installed on the suction side of the cooling tower pumps a minimum of 5 pipe diameters from the cooling tower pump suction flanges. Install blow down valves on the large mesh strainers. Refer to Division 23 specification section HVAC Piping, Fittings and Valves for the cooling tower pump suction strainer requirements. Install pressure gauges on both sides of the suction strainers.
- M. Install fine mesh strainers on the discharge of the cooling tower pumps as indicated on the contract drawings to protect the existing heat exchangers and new cooling tower nozzles. Install pressure gauges on both sides of the strainers and blow down valves.

3.8. HYDRONIC EQUIPMENT AND SPECIALTIES INSTALLATION REQUIREMENTS

- A. Where large air quantities can accumulate, provide enlarged air collection standpipes.
- B. Provide manual air vents at system high points and as indicated.
- C. For automatic air vents provide vent tubing to nearest drain.
- D. Provide air separator on suction side of system circulation pump and connect to expansion tank.
- E. Provide valved drain and hose connection on strainer blow down connection.
- F. Provide pump suction fitting on suction side of base mounted centrifugal pumps. Remove temporary strainers after cleaning systems.
- G. Support pump fittings with floor mounted pipe and flange supports.
- H. Select system relief valve capacity so that it is greater than make-up pressure reducing valve capacity. Select equipment relief valve capacity to exceed rating of connected equipment and in accordance with ASME requirements.
- I. Pipe all relief valve outlets to nearest floor drain.
- J. Where one line vents several relief valves, make cross sectional area equal to sum of individual vent areas.
- K. Install equipment exposed to finished area after walls and ceiling are finished and painted. Avoid damage.
- L. Testing: After installing and connecting units, demonstrate product capability and compliance with requirements.
- M. Remove and replace malfunctioning units with new units and retest.

3.9. WATER TREATMENT INSTALLATION REQUIREMENTS

- A. Systems shall be operational, filled, started, and vented prior to cleaning. Use water meter to record capacity in each system.
- B. Place terminal control valves in open position during cleaning. Open bypass valves on coils and close isolation valves on coils during initial flushing.
- C. Verify that electric power is available and of the correct characteristics.
- D. Use neutralizer agents on recommendation of system cleaner supplier and approval of Engineer.
- E. Flush open systems and closed systems with clean water for four (4) hours minimum. Drain completely and refill.
- F. Remove, clean, and replace strainer screens.
- G. Inspect, remove sludge, and flush low points with clean water after cleaning process is completed. Include disassembly of components as required.

3.10. WATER METER INSTALLATION REQUIREMENTS

- A. Install water meters, piping, and specialties according to details on the contract drawings and the Manufacturer's requirements.
 - 1. Install water meters with shutoff valve on water meter inlet. Install valve on water meter outlet and valved bypass around meter, unless prohibited by authorities having jurisdiction.
- B. Install power and control wiring from water meter to chemical treatment system and the ATC system.
- C. Field insulate and jacket water meter to prevent condensation.

3.11. HEAT REJECTION EQUIPMENT INSTALLATION REQUIREMENTS

- A. Cooling towers and closed circuit evaporative fluid coolers shall be field assembled by factory authorized installers. Unit shall be shipped in modules where required. Coordinate max part/module size crane capacity.
- B. Examine proposed route of moving closed circuit evaporative fluid coolers/cooling towers into place and verify that it is free of interference.
- C. Examine elements and surface to support closed circuit evaporative fluids coolers/cooling towers.
- D. Install closed circuit evaporative fluid coolers/cooling towers according to manufacturer's written instructions.
- E. Install and anchor closed circuit evaporative fluid coolers/cooling towers level and plumb, and fasten to existing supporting structure and existing vibration isolations.

- F. Maintain recommended clearances for service and maintenance.
- G. Manufacturers Field Service: Engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including piping and electrical connections. Report results in writing.
- H. Adjust water-level control for proper operating level.
- I. After completing system installation, including outlet fittings and devices, inspect exposed finish. Remove burrs, dirt and construction debris, and repair damaged finishes including chips, scratches and abrasions.
- J. Obtain wet-bulb, condenser-size, and performance selection tables from manufacturer.
- K. Lubricate bearings on fans and shaft as recommended by manufacturer.
- L. Ensure fan wheels rotate in correct direction without vibration or binding.
- M. Adjust belts to proper alignment and tension.
- N. Start closed circuit evaporative fluid coolers and cooling towers. Follow manufacturers written starting procedures.
- O. Check water level in closed circuit evaporative fluid cooler/cooling tower basin.
- P. Check operation of closed circuit evaporative fluid cooler/cooling tower basins, make-up line, motorized ball valves, dampers, end switches, and low water cut-off controlling device.
- Q. Wire all make-up water motorized ball valves, chemical treatment panel, bleed-off motorized ball valves, water level controls, pump interlocks, fan interlocks, basin heaters, heat tracing, low water cut-offs, spray pumps, basin heater thermostats, damper end switches and control panel under Division 23.
- R. Pipe all chemical treatment piping from chemical treatment panel to closed circuit evaporative fluid coolers and cooling towers.
- S. Pipe all drain pipes and bleed-off motorized ball valves to splash blocks or floor drains with suitable air gaps.

**3.12. COOLING TOWER/CLOSED CIRCUIT EVAPORATIVE FLUID COOLER
WINTERIZATION REQUIREMENTS**

- A. The cooling towers/closed circuit evaporative fluid coolers shall be winterized every winter. Contractor to install all drain valves, plugs, and Schrader valves to allow proper winterization.
- B. Contractor to include in scope and bid all costs, material, and labor for winterizing the cooling towers/closed circuit evaporative fluid coolers in preparation for the first winter.
- C. A detailed plan with instructions for winterizing the cooling towers/closed circuit evaporative fluid coolers shall be provided by the Contractor and inserted in the operation

and maintenance manuals.

- D. Contractor shall train Owner on exact method and sequence for winterizing the cooling towers/closed circuit evaporative fluid coolers.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 23 SECTION 23 07 01
HVAC INSULATION
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. REFERENCE	3
1.2. DESCRIPTION	3
1.3. SCOPE.....	3
1.4. STANDARDS	3
1.5. SYSTEM PERFORMANCE	4
1.6. QUALITY ASSURANCE.....	4
1.7. DELIVERY AND STORAGE OF MATERIALS	4
1.8. ALTERNATES	5
PART 2. PRODUCTS.....	5
2.1. GENERAL.....	5
2.2. PIPE INSULATION MATERIALS	5
2.3. PIPING INSULATION THICKNESSES SCHEDULE	8
2.4. EQUIPMENT INSULATION MATERIALS AND THICKNESSES.....	8
2.5. ACCESSORY MATERIALS	10
2.6. FIELD-APPLIED JACKET	10
2.7. HANGER BLOCKS	11
PART 3. EXECUTION.....	11
3.1. WORKMANSHIP	11
3.2. SITE INSPECTION.....	11
3.3. PREPARATION.....	11
3.4. INSTALLATION	12
3.5. FIELD QUALITY ASSURANCE.....	14
3.6. PROTECTION	14
3.7. SAFETY PRECAUTIONS.....	14
3.8. INSULATION COVERING.....	14
END OF SECTION	15

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 23 07 01 – HVAC INSULATION

PART 1. GENERAL

1.1. REFERENCE

- A. The Conditions of the Contract and other General Requirements apply to the work specified in this Section. All work under this Section shall be subject to the requirements of Division 23 Section, Common Work Results for HVAC.
- B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section

1.2. DESCRIPTION

- A. All piping and equipment installed under this Contract shall be covered as specified.

1.3. SCOPE

- A. The work covered by this specification consists of furnishing all labor, equipment, materials and accessories, and performing all operations required, for the correct fabrication and installation of thermal insulation applied to all piping, equipment, and duct systems, in accordance with applicable project specifications and drawings, subject to the terms and conditions of the contract.

1.4. STANDARDS

- A. Thermal insulation materials shall meet the property requirements of one or more of the following specifications as applicable to the specific product or use:
 - 1. American Society for Testing of Materials Specifications:
 - a. ASTM C 547, "Standard Specification for Mineral Fiber Preformed Pipe Insulation".
 - b. ASTM C 533, "Standard Specification for Calcium Silicate Pipe & Block Insulation".
 - c. ASTM C 55, "Standard Specification for Mineral Fiber Blanket and Felt Insulation".
 - d. ASTM E 96, "Standard Test Methods for Water Vapor Transmission of Material".
 - e. ASTM C 585, "Recommended Practice for Inner and Outer Diameters of Rigid Pipe Insulation for Nominal Sizes of Pipe and Tubing (NPS System)".
 - f. ASTM C 612, "Standard Specification for Mineral Fiber Block and Board Thermal Insulation".
 - g. ASTM C 1136, "Standard Specification for Barrier Material, Vapor, "Type 1 or 2 (Jacket only)".
 - 2. ASHRAE 90.1 "Energy efficient design of new buildings except low-rise residential buildings", latest edition.

3. International Energy Conservation Code, latest edition.
- B. Insulation materials, including all weather and vapor barrier materials, closures, hangers, supports, fitting covers, and other accessories, shall be furnished and installed in strict accordance with project drawings, plans, and specifications.

1.5. SYSTEM PERFORMANCE

- A. Insulation materials furnished and installed hereunder should meet the minimum economic insulation thickness requirements of the North American Insulation Manufacturers' Association (NAIMA) (formerly known as TIMA), to ensure cost-effective energy conservation performance. Alternatively, materials should meet the minimum thickness requirements of National Voluntary Consensus Standard 90.1, (latest edition) and "Energy Efficient Design of New Buildings," of the American Society of Heating, Refrigeration, and Air-Conditioning Engineers (ASHRAE), latest edition. However, if other factors such as condensation control or personnel protection are to be considered, the selection of the thickness of insulation should satisfy the controlling factor. As minimum, all insulation thicknesses shall be as hereinafter specified.
- B. Insulation materials furnished and installed hereunder shall meet the fire hazard requirements of any one of the following specifications:
 1. American Society for Testing of Materials ASTM E 84
 2. Underwriters' Laboratories, Inc. UL 723
 3. National Fire Protection Association NFPA 255
 4. ASTM E 96, "Standard Test Methods for Water Vapor Transmission of Materials".
- C. Calcium silicate products shall include a visual identification system to permit positive field determination of their asbestos-free characteristics.

1.6. QUALITY ASSURANCE

- A. Insulation materials and accessories furnished and installed hereunder shall, where required, be accompanied by manufacturers' current submittal or data sheets showing compliance with applicable specifications listed in Section 1.4 above.
- B. Insulation materials and accessories shall be installed in a workmanlike manner by skilled and experienced workers who are regularly engaged in commercial insulation work.

1.7. DELIVERY AND STORAGE OF MATERIALS

- A. All of the insulation materials and accessories covered by this specification shall be delivered to the job site and stored in a safe, dry place with appropriate labels and/or other product identification.
- B. The Contractor shall use whatever means are necessary to protect the insulation materials and accessories before, during, and after installation. No insulation material shall be installed that has become damaged in any way. The Contractor shall also use all means

necessary to protect work and materials installed by other trades.

- C. If any insulation material has become wet because of transit or job site exposure to moisture or water, the Contractor shall not install such material, and shall remove it from the job site. An exception may be allowed in cases where the Contractor is able to demonstrate that wet insulation when fully dried out (either before installation, or afterward following exposure to system operating temperatures) will provide installed performance that is equivalent in all respects to new, completely dry insulation. In such cases, consult the insulation manufacturer in writing for technical assistance.
- D. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cements. Protect all insulation from water, construction traffic, dirt, chemical and mechanical damage.

1.8. ALTERNATES

- A. Refer to Division 01 Section, "Alternates" for description of work under this section affected by alternates.

PART 2. PRODUCTS

2.1. GENERAL

- A. All materials to be insulated shall be thoroughly cleaned, after completion of successful tests, and shall be covered as specified below. Fiberglass insulation shall be Owens-Corning, Manville, Armstrong, or P.P.G, or as approved equal.

2.2. PIPE INSULATION MATERIALS

- A. Unless otherwise noted, insulation shall be one piece or half sectional molded fibrous glass with "K" rating of .23 at 75 degrees Fahrenheit mean temperature, for service temperatures between -60 degrees Fahrenheit and +450 degrees Fahrenheit with all service poly-encapsulated jacket. Pipe insulation shall be fiberglass ASJMax SSL II with double closure system as manufactured by Owens Corning, Johns Manville, Knauf or approved equal.
- B. Unless otherwise noted, pipe insulation jacket shall be factory-applied vinyl coated, embossed and reinforced vapor barrier laminate, with a perm rating of not more than 0.02 perms. All hot and cold, concealed and exposed butt strips shall be of the same material as the jacket. Jacket and butt strips shall be sealed with field-applied Foster 85-20/85-60 or Childers CP-82 (5 gal cans only) adhesive. Jacket and butt strips shall be off-white color and shall be equivalent to Owens-Corning Fiberglass 25-ASJ.
- C. Indoor pipe insulation shall be ASJ Max with SSL-II closure system pipe insulation as manufactured by Owens Corning or approved equal. Pipe insulation shall be composed of heavy density fiberglass insulation with an organic binder. The insulation shall include a white, factory jacketed, resilient, tough, soil resistant polymer facing that matches standard PVD fitting covers. Furnish all accessories and matching butt joints sealing tape for system closure. Insulation shall be suitable for operating temperatures between 32 degrees Fahrenheit and 220 degrees Fahrenheit. Flame spread rating of 25 or less, and smoke development rating of 50 or less to comply with building codes for installation in return air plenums. The maximum thermal conductivity (K-value) at a mean temperature of 50 shall

be .22 BTU-in/hr-Ft²-degess Fahrenheit.

- D. For fittings on all piping, valves and flanges, apply fiberglass molded or segmented insulation equal in thickness to the adjoining insulation and securely fasten in place using wire. Cold piping: Apply a tack coat of vapor barrier coating and reinforcing mesh. After ½ hour, apply second coat of same vapor barrier coating, UL labeled, Type C, for cold water piping, Hot piping Type H for hot water piping: Apply tack of breather mastic. Wrap fitting with fiberglass reinforcing cloth overlapping adjoining sections of pipe insulation by 2-inches. Apply a second coat of breather mastic over the reinforcing cloth, working it to a smooth finish.
1. Vapor Barrier Coating: Foster 30-65; Childers CP-34 or Vimasco 749. Permeanie shall be 0.03 perms or less at 45 mils dry as test by ASTM E96.
 2. Breather mastic: Foster 46-50; Childers CP-10/11 or Vimasco WC-5
 3. Reinforcing Mesh: Foster Mast a Fab; Childers Chil Glas #10 or Vimasco Elastafab
- E. All pipe insulation, jackets, or facings, and adhesives used to adhere jacket or facing to the insulation, including fittings and butt strips, shall have non-combustible fire and smoke hazard system rating and label as tested by ASTM E-84, NFPA 225, and UL 73, not exceeding Flame Spread 25, Fuel Contributed 50, Smoke Developed 50. Accessories such as adhesives, mastic cements, tapes and cloth for fittings shall have the same ratings as listed above. All products or their shipping cartons shall bear the Underwriter's label indicating that flame and smoke ratings do not exceed the above criteria.
- F. For piping having a vapor barrier insulation and for all insulated piping requiring supports, hangers and supports shall be installed outside the insulation. Wherever hangers and supports are installed outside the insulation, pipe insulation protecting shields shall be provided. Where insulation is a load bearing material, of sufficient strength to support the weight of the piping, pipe shields one-third the circumference of the insulation and of a length not less than three times the diameter of the insulation (maximum length 24-inches) shall be provided. Insulation of 7-1/4 pound or greater density will be considered as load bearing for pipe sizes up to and including 2-inches. Where insulation is not of sufficient strength to support the weight of the piping, a half section of high density fiberglass or foam inserts, shall be provided. Vapor barrier and finish shall be applied as required to match adjoining insulation. In addition, shields shall be furnished as specified above.
- G. For piping located outside of the building, a corrugated aluminum weatherproof jacketing system shall be provided. This system shall be Micro-Lot ML as manufactured by Manville, Polyweld by Pabco Metals Corp., Childers, or as approved equal, and installed per the manufacturer's recommendations. Where outdoor piping is receiving electric heat tape, the insulation shall be oversized so that the heat tape is not compressed tightly to the pipe. Pipe jacketing shall be corrugated (3/16-inch) deep aluminum, .016-inch thickness of H-14 temper with aluminum strapping of .75-inch width and .020 inch thickness with moisture barrier. Aluminum jacketing elbows shall be smooth, .016-inch thickness and 1100 alloy. All jacketing shall have an integrally bonded moisture barrier over the entire surface in contact with the insulation. Longitudinal joints shall be applied so they will shed water and shall be sealed completely with metal jacketing sealant. Sealant shall be Foster 95-44 or Childers CP-76. Circumferential joints shall be closed using preformed butt strips

following manufacturer's recommendations for securement. Jacket seams shall be located on the bottom side of the horizontal piping.

- H. All disturbed piping insulation in existing areas shall be re-insulated with insulation type, density, and thickness as specified for new piping. Insulation damaged due to new work and demolition only shall be replaced unless otherwise noted.
- I. On cold systems vapor barrier performance is extremely important. All penetrations and seams of the ASJ and exposed ends of insulation must be sealed with vapor barrier coating. The ASJ must be protected with either a coating or a suitable vapor retarding outer jacket. Vapor seals at butt joints shall be applied at every fourth pipe section joint and at each fitting to provide isolation of water incursion. Vapor Barrier Coating: Foster 30-65; Childers CP-34 or Vimasco 749. Permeance shall be 0.03 perms or less at 45 mils dry as test by ASTM E96.
- J. Fittings and valves shall be insulated with pre-formed fiberglass fittings, fabricated sections of fiberglass pipe insulation, Fiberglass pipe and tank insulation, Fiberglass blanket insulation, or insulating cement. Thickness shall be equal to adjacent pipe insulation. Finish shall be with pre-formed PVC fitting covers or as otherwise specified on contract drawings. Where applicable, Victaulic PVC fitting valve and coupling covers shall be utilized. Victaulic PVC covers shall be installed with matching pipe insulation jacketing material, vinyl tape solvent weld adhesive and appropriate fasteners.
 - 1. Flanges, couplings and valve bonnets shall be covered with an oversized pipe insulation section sized to provide the same insulation thickness as on the main pipe section. An oversized insulation section shall be used to form a collar between the two insulation sections with low density blanket insulation being used to fill gaps. Jacketing shall match that used on straight pipe sections. Rough cut ends shall be coated with a suitable weather or vapor-resistant mastic as dictated by the system location and service. Finish valve installation with a Tyvac jacket with ends that secure to adjacent piping.
 - 2. On hot systems where fittings are to be left exposed, insulation ends should be beveled away from bolts for easy access.
 - 3. On cold systems, particular care must be given to vapor sealing the fitting cover or finish to the pipe insulation vapor barrier. All valve stems must be sealed with caulking which allows free movement of the stem but provides a seal against moisture incursion. All gauge and thermometer penetrations and extensions shall be correctly sealed and insulated to prevent surface condensation. Install oversized hangers to prevent penetrations of pipe insulation vapor barrier.
- K. All piping shall be supported in such a manner that neither the insulation or the vapor/weather barrier is compromised by the hanger or the effects of the hanger. In all cases, hanger spacing must be such that the circumferential joint may be made outside the hanger. On cold systems, vapor barrier must be continuous, including material covered by the hanger saddle.
 - 1. Piping systems 3-inches (7.5cm) in diameter or less, insulated with Fiberglass insulation, may be supported by placing saddles of the proper length and spacing, as designated in Owens-Corning Pub. 1-IN-12534, under the insulation. Hangers

saddles shall be minimum 16 gauge with a saddle arc of 120 degrees minimum.

2. For hot or cold piping systems larger than 3-inches (7.5 cm) in diameter, operating at temperatures less than +200 degrees F (93 degrees C) and insulated with fiber glass, high density inserts such as foam or wood blocks with sufficient compressive strength shall be used to support the weight of the piping system. At temperatures exceeding +_200 degrees F (93 degrees C), Owens-Corning Pink Calcium Silicate, IIG, or approved equal pipe insulation shall be used for high density inserts.
3. Owens-Corning Pink Calcium Silicate pipe insulation may be used to support the entire weight of the piping system provided the hanger saddle is designed so the maximum compressive load does not exceed 100 psi (7kg/cm).
4. Where pipe shoes and roller supports are required, insulation shall be inserted in the pipe shoe to minimize pipe heat loss. Where possible, the pipe shoe shall be sized to be flush with the outer pipe insulation diameter.
5. Thermal expansion and contraction of the piping and insulation system shall generally be taken care of by utilizing double layers of insulation and staggering both longitudinal and circumferential joints. Where long runs are encountered, expansion joints may be required where single layers of insulation are being used and should be so noted on the contract drawings.
6. On vertical runs, insulation support rings shall be used.

2.3. PIPING INSULATION THICKNESSES SCHEDULE

- A. All piping shall be insulated with pipe insulation of the thicknesses indicted below:

PIPING INSULATION THICKNESS SCHEDULE SERVICES	THICKNESS
Cooling tower loop supply, return, drain, and overflow piping	1-½ inch thickness
Heating Hot Water Piping 2-inches & Larger	2 inch thickness
Heating Hot Water Piping 1-½ -inches & Smaller	1-½ inch thickness
Chemical Treatment System Piping	1 inch thickness
Interior & Exterior Water Source Heat Pump Piping Including Chemical Treatment Piping	1-½ inch thickness

2.4. EQUIPMENT INSULATION MATERIALS AND THICKNESSES

- A. The following equipment shall be insulated with Fiberglass Rigid Board Insulation or Foam Plastic Insulation:
1. Air Separators.
 2. Expansion Tanks.
 3. Chemical Feed Tanks.
 4. Existing Heat Exchangers.

5. Pumps.

- B. Insulation for cold surfaces shall be 1-1/2-inch thickness, 6 lb. density, 705 FRK with a "K" rating of .23 at 75 degrees F mean temperature. Insulation for hot surfaces except as otherwise noted shall be 1-1/2-inch thickness, 6 lb. density, 705 with a "K" rating of .23 at 75 degrees F mean temperature. Insulation shall be applied with staggered joints firmly butted and joined. The insulation shall be held in place by steel bands. Bands shall be 1-inch by 25 gauge galvanized steel spaced on not over 12-inch centers. All joints and voids shall be filled with Owens-Corning #110 cement, well troweled into openings. For 705 FRK insulation, all joints and voids shall be FRK taped and vapor sealed. There shall be applied over the insulation surface 1-inch galvanized wire netting laced together at all edges and wired to the steel bands with 16 gauge soft annealed wire. Over this shall be applied 2-inch thick layer of Owens-Corning #110 cement applied in two layers. Install metal corner beads at all corners and edges in order to provide a permanent installation. Onto the dry cement surface apply a brush coat of Foster Sealfas 30-36 or Childers CP-50AMV1 lagging adhesive at the rate of 60-70 square feet per gallon. Cleanouts, nameplates, and manholes shall not be insulated, and the insulation on surrounding surfaces shall be neatly beveled off at such openings.
- C. Insulation Installation on Pumps:
1. Fabricate metal boxes lined with insulation. Fit boxes around pumps and coincide box joints with splits in pump casings. Fabricate joints with outward bolted flanges. Bolt flanges on 6-inch (150-mm) centers, starting at corners. Install 3/8-inch- (10-mm-) diameter fasteners with wing nuts. Alternatively, secure the box sections together using a latching mechanism.
 2. Fabricate boxes from aluminum at least 0.040 inch (1.0 mm) thick.
 3. For below ambient services, install a vapor barrier at seams, joints, and penetrations. Seal between flanges with replaceable gasket material to form a vapor barrier.
- D. The following equipment shall be insulated with calcium silicate insulation:
1. Existing Heat Exchangers. Insulation shall be removable with latches.
- E. Calcium silicate insulation shall be 2-inch thickness, 6 pcf minimum density, flat, curved, and grooved-block sections of non-combustible, inorganic, hydrous calcium silicate with a non-asbestos fibrous reinforcement. Comply with ASTM 533, Type I. All equipment insulation shall be covered with lagging adhesive and an 8oz glass cloth or canvas cover neatly cut and pasted over equipment. Calcium silicate insulation shall be suitable for operating temperatures between 100 to 450 degrees Fahrenheit.
- F. Boards shall be scored to allow them to conform to curved or irregular surfaces.
- G. Mechanical fasteners shall be utilized to hold insulation to surface with bands as required to hold the curvature of the material.
- H. Support rings shall be provided to support the top head insulation where required.

- I. Outdoor installations require a weather barrier for protection of the insulation jacketing.
- J. Insulation types materials shall be suitable for temperatures encountered by each item of equipment.

2.5. ACCESSORY MATERIALS

- A. Accessory materials installed as part of insulation work under this section shall include, but not be limited to:
 - 1. Closure Materials - Butt strips, bands, wires, staples, mastics, adhesives; pressure-sensitive tapes.
 - 2. Field-applied jacketing materials - sheet metal, plastic, canvas, fiber glass cloth, insulating cement; PVC fitting covers, PVC jacketing.
 - 3. Support Materials - Hanger straps, hanger rods, saddles.
 - 4. Fasteners, weld pins/studs, speed clips, insulation washers.
 - 5. Metal mesh or expanded metal lagging.
- B. All accessory materials shall be installed in accordance with project drawings and specifications, manufacturer's instructions, and/or in conformance with the current edition of the Midwest Insulation Contractors Association (MICA) "Commercial & Industrial Insulation Standards."

2.6. FIELD-APPLIED JACKET

- A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.
- B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
 - 1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Johns Manville; Zeston.
 - b. P.I.C. Plastics, Inc.; FG Series.
 - c. Proto PVC Corporation; LoSmoke.
 - d. Speedline Corporation; SmokeSafe.
 - 2. Adhesive: As recommended by jacket material manufacturer.
 - 3. Color: High gloss white.
 - 4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
 - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical

joints, and P-trap and supply covers for lavatories.

5. Factory-fabricated tank heads and tank side panels.

2.7. HANGER BLOCKS

- A. For all pipes larger than 3 inches in diameter the hanger blocks shall be high compressive strength foam or wood blocks. Wood blocks shall be precision cut thickness to match specified insulation and shall include flared edge hanger saddle as manufactured by Buckaroo.
- B. The wood blocks shall be suitable for temperatures from -120 degrees Fahrenheit to 200 degrees Fahrenheit. Do not utilize the wood blocks for piping systems operating outside of the indicated temperature range.
- C. Wood blocks are not acceptable for use at refrigerant pipe hangers.

PART 3. EXECUTION

3.1. WORKMANSHIP

- A. The Contractor shall take special care to prevent soiling equipment below or adjacent to areas being insulated. He shall be completely responsible for removing insulation cement splashes and smears and all surfaces that he mars or otherwise soils or defaces, and he will be totally responsible for restoring these damaged surfaces to their like-new condition when delivered to the site.

3.2. SITE INSPECTION

- A. Before starting work under this section, carefully inspect the site and installed work of other trades and verify that such work is complete to the point where installation of materials and accessories under this section can begin.
- B. Verify that all materials and accessories can be installed in accordance with project drawings and specifications and material manufacturers' recommendations.
- C. Verify, by inspecting product labeling, submittal data, and/or certifications which may accompany the shipments, that all materials and accessories to be installed on the project comply with applicable specifications and standards and meet specified thermal and physical properties.

3.3. PREPARATION

- A. Ensure that all pipe and equipment surfaces over which insulation is to be installed are clean and dry.
- B. Ensure that insulation is clean, dry, and in good mechanical condition with all factory-applied vapor or weather barriers intact and undamaged. Wet, dirty, or damaged insulation shall not be acceptable for installation.
- C. Ensure that pressure testing of piping systems has been completed prior to installing insulation.

3.4. INSTALLATION

A. Piping Systems

1. General:

- a. Install all insulation materials and accessories in accordance with manufacturer's published instructions and recognized industry practices to ensure that it will serve its intended purpose.
- b. Install insulation on piping subsequent to installation of heat tracing, painting, testing, and acceptance tests.
- c. Install insulation materials with smooth and even surfaces. Insulate each continuous run of piping with full-length units of insulation, with single cut piece to complete run. Do not use cut pieces or scraps abutting each other. Butt insulation joints firmly to ensure complete, tight fit over all piping surfaces.
- d. Maintain the integrity of factory-applied vapor barrier jacketing on all pipe insulation, protecting it against puncture, tear or other damage. Seal all tears, punctures and other penetrations of the pipe insulation vapor barrier coating.
- e. On exposed piping, locate insulation and cover seams in least visible location.

2. Fittings: Cover valves, fittings, unions, flanges, strainers, flexible connections, expansion joints, pump bodies, drain valves, strainers, blowdowns, backflow preventers, autoflow valves and similar items in each piping system using one of the following:

- a. Mitered sections of insulation equivalent in thickness and composition to that installed on straight pipe runs.
- b. Cold pipe fittings: Apply a tack coat of vapor barrier coating and reinforcing mesh to produce a smooth surface. After ½ hour, apply a second coat of same vapor barrier coating, UL labeled, Type C, for cold water piping.
- c. Hot pipe fittings and Type H for hot water piping: Apply tack of breather mastic. Wrap fitting with fiberglass reinforcing cloth overlapping adjoining sections of pipe insulation by 2-inches. Apply a second coat of Type C or Type H breather mastic over the reinforcing cloth, working it to a smooth finish.
- d. Insulation cement equal in thickness to the adjoining insulation.
- e. PVC fitting covers insulated with material equal in thickness and composition to adjoining insulation.

3. Penetrations: Extend piping insulation without interruption through walls, floors, and similar piping penetrations, except where otherwise specified.

4. Joints:

- a. Butt pipe insulation against hanger inserts. For hot pipes, apply 3-inch (7.5cm) wide vapor barrier tape or bank over butt joints. For cold piping, apply wet coat of vapor barrier lap cement on butt joints, and seal joints

- with 3-inch (7.5cm) wide vapor barrier tape or band.
 - b. All pipe insulation ends shall be tapered and sealed, regardless of service.
 - 5. For heat traced piping, insulate fittings, joints, and valves with insulation of like material, thickness and finish as adjoining pipe. Size insulation large enough to enclose pipe and heat trace. Cover with aluminum jacket with seams located on bottom side of horizontal piping.
 - 6. Indoor piping shall be ASJ max with SSL-II closure system as manufactured by Owens Corning, Johns Manville, Knauf or approved equal.
 - 7. Exterior above ground piping shall be insulated with ASJ max SSL-II closure system insulation. Fiberglass insulation with aluminum jacketing shall be utilized for exterior above ground applications. Seal all aluminum jacketing laps with 1/8" bead of metal jacketing sealant to prevent water entry.
- B. Equipment Insulation:
- 1. General:
 - a. Install insulation in accordance with manufacturer's published instructions and recognized industry practices to ensure that it will serve its intended purpose.
 - b. Install insulation on equipment after installation of heat tracing, painting, testing, and acceptance tests.
 - c. Install insulation materials with smooth, even surfaces. Rework poorly fitted joints. Do not use joint sealer or mastic as filler for joint gaps and excessive voids resulting from poor workmanship. Apply insulation using staggered joint method for both single and double layer installation, applying each layer of insulation separately.
 - d. Coat insulated surfaces where specified on contract drawings with layer of insulating cement, troweled in a workmanlike manner, leaving a smooth and continuous surface. Fill in seams, broken edges, and depressions. Cover over wire mesh and joints with cement sufficiently thick to remove surface irregularities.
 - e. Maintain the integrity of factory-applied vapor barrier jacketing on all insulation, protecting it against puncture, tears or other damage. Seal all tears, punctures and other penetrations of equipment insulation facing.
 - f. Where specification calls for field-applied all-service vapor barrier jacketing, it shall be neatly fitted and tightly secured. Lap seams 2-inches (5cm) (min.). Seal all joints with adhesive. Tape with 3-inches (7.5cm) matching pressure-sensitive tape or 3-inch (7.5cm) glass fabric and vapor barrier coating.
 - g. On exposed equipment, locate insulation and cover seams in least visible location.
 - 2. Removable Insulation: Provide removable insulation sections to cover parts of equipment which must be opened periodically for maintenance, such as vessel covers, fasteners, flanges, frames accessories, manholes, handholes, cleanouts ASME stamp, and manufacturer nameplates.

3. Areas Left Uninsulated: Items such as manholes, handholes, clean-outs, ASME stamp, and manufacturers' nameplates should be left uninsulated unless omitting insulation would cause a condensation problem. When such is the case, provide removable insulation and appropriate tagging to identify the presence of these items. Provide neatly beveled edges at interruptions of insulation.
4. Equipment Exposed to Weather: Protect outdoor insulation from weather by installation of weather barrier mastic protective finish or jacketing as recommended by the jacketing manufacturer.

3.5. FIELD QUALITY ASSURANCE

- A. Upon completion of all insulation work covered by this specification, visually inspect the work and verify that it has been correctly installed. This may be done while work is in progress, to assure compliance with requirements herein to cover and protect insulation materials during installation.

3.6. PROTECTION

- A. Replace damaged insulation which cannot be satisfactorily repaired, including insulation with vapor barrier damage and moisture-saturated insulation.
- B. The insulation contractor shall advise the general and/or the mechanical contractor as to requirements for protection of the insulation work during the remainder of the construction period, to avoid damage and deterioration of the finished insulation work.

3.7. SAFETY PRECAUTIONS

- A. Insulation contractor's employees shall be properly protected during installation of all insulation. Protection shall include proper attire when handling and applying insulation materials, and shall include (but not be limited to) disposable dust respirators, gloves, hard hats, and eye protection.
- B. The insulation contractor shall conduct all job site operations in compliance with applicable provisions of the Occupational Safety and Health Act, as well as with all state and/or local safety and health codes and regulations that may apply to the work.

3.8. INSULATION COVERING

- A. Unless otherwise noted, all exposed equipment insulation shall have a field applied PVC jacket cover neatly cut and pasted over ductwork and equipment insulation. PVC shall be high gloss white and shall be 20 mils thick.
- B. Unless otherwise noted, all exposed pipe insulation required to be insulated shall be jacketed with a PVC Jacketing with fitting covers. PVC jacket shall be color fade resistant, white high gloss, U.S.D.A. authorized as manufactured by Proto Corporation or approved equal. PVC jacketing shall be high impact, ultraviolet resistant PVC. Minimum thickness shall be 20 mils, roll stock ready for shop or field cutting and forming.
- C. Exposed areas include, but are not limited to, all mechanical equipment rooms/fan rooms, boiler rooms, electric rooms, storage rooms, janitor closets, exposed in an occupied space.

- D. Where PVC jackets are indicated, install with 1 inch overlap at longitudinal seams and end joints, for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturers recommended adhesive.
 - 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.
- E. Exterior exposed pipe insulation required to be insulated shall be jacketed with a corrugated aluminum jacketing system as previously described. Seal all laps with 1/8" bead metal jacketing sealant.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 23 SECTION 23 09 00
INSTRUMENTATION AND CONTROLS OF HVAC AND PLUMBING SYSTEMS
TABLE OF CONTENTS

PART 1.	GENERAL	3
1.1.	SUMMARY	3
1.2.	DEFINITIONS	5
1.3.	SYSTEM PERFORMANCE	5
1.4.	DELIVERY, STORAGE, AND HANDLING	6
1.5.	COORDINATION	6
1.6.	WORK BY OTHERS	6
1.7.	QUALITY ASSURANCE	6
1.8.	GUARANTEE AND INSTRUCTION	7
1.9.	SUBMITTALS	8
1.10.	SOFTWARE LICENSE AGREEMENT	10
1.11.	ELECTRICAL SURGE PROTECTION	10
1.12.	TRAINING	10
1.13.	ALTERNATES	11
1.14.	INDIAN RIVER SCHOOL DISTRICT SPECIFIC REQUIREMENTS	11
1.15.	GLOBAL SENSORS	12
PART 2.	PRODUCTS	13
2.1.	BUILDING MANAGEMENT SYSTEM	13
2.2.	WIRING	24
2.3.	CONTROLLERS	24
2.4.	PRESSURE INDEPENDENT HYDRONIC CONTROL VALVES	25
2.5.	CONTROL PANELS	28
2.6.	MISCELLANEOUS ELECTRICAL DEVICES	28
2.7.	UNINTERRUPTIBLE POWER SUPPLY	29
2.8.	DESKTOP WORKSTATIONS	29
2.9.	CENTRAL CONTROL AND MONITORING SYSTEM (CCMS) (HARDWARE DESCRIPTION)	31
2.10.	SYSTEM SOFTWARE DESCRIPTION	42
2.11.	EXCEPTION REPORTING SEQUENCES	42
2.12.	MONITORING SYSTEM, SENSORS AND WIRING	43
2.13.	MAKE-UP WATER FLOW METER/ALARM	45
2.14.	FLOW MEASURING STATIONS	46
2.15.	WATER METER	47
PART 3.	EXECUTION	47
3.1.	GENERAL	47
3.2.	BMS SPECIFIC REQUIREMENTS	47
3.3.	WORKSTATION INSTALLATION	47
3.4.	INSTALLATION & SUPERVISION	48
3.5.	ACCEPTANCE TESTING	49
3.6.	COORDINATE WITH TAB AGENCY	50
3.7.	EXAMINATION	50
3.8.	INTERLOCK REQUIREMENTS	51
3.9.	SUBMITTALS AT PROJECT CLOSEOUT	51
3.10.	CONNECTIONS	51

3.11.	FIELD QUALITY CONTROL.....	51
3.12.	ADJUSTING	53
3.13.	ON-SITE ASSISTANCE.....	54
3.14.	SCHEDULING.....	54
3.15.	STAGING.....	54
END OF SECTION		54

SECTION 23 09 00 - INSTRUMENTATION AND CONTROLS OF HVAC AND PLUMBING SYSTEMS

PART 1. GENERAL

1.1. SUMMARY

- A. For General Mechanical Requirements, see Division 23 Section, Common Work Results for HVAC, and Division 01 Sections.
- B. Comply with all code requirements and fire safety requirements as specified in Division 23 Section, Common Work Results for HVAC.
- C. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- D. This Section includes control equipment for HVAC systems and components, including control components for terminal heating and cooling units not supplied with factory wired controls.
- E. The automatic temperature control system ATC and central control and monitoring system (CCMS) shall be electric/electronic direct digital control (DDC), Johnson Controls FX as installed by Modern Controls or Trane. All work associated with the automatic temperature control system shall be performed by personnel regularly and directly employed by the Automatic Temperature Controls Contractor. Control System shall be web based, allowing the client access via a standard web browser.
- F. Coordinate controls with controlled equipment. Upon completion of the work, calibrate and adjust all controls for proper function. Electric wiring, including interlock wiring for all equipment shall be furnished and installed under this section. All electrical work shall conform to the applicable requirements of Division 26.
- G. All automatic temperature control dampers, valves and separable wells for immersion elements furnished by the Control Manufacturer shall be installed by the Mechanical Contractor or his sheet metal subcontractor under the Control Manufacturer's supervision.
- H. Reference is hereby made for this contractor to become familiar with Division 26 of these specifications. Familiarization is for coordination purposes only. The control contractor shall provide all necessary relays, contacts, interlock wiring etc. not provided under Division 26 for the automation of the ATC and CCMS systems as required by the sequence of operation and input/output schedule. The control contractor shall provide all additional devices and interlock wiring required for the automation of the ATC system and monitoring of the CCMS system.
- I. Furnish all labor, materials, software, equipment and services necessary for and incidental to furnishing and installing a complete direct digital control, automatic temperature control system to meet the requirements of the sequence of operation described on the Drawings.
- J. Unless the necessary items are specified to be provided with mechanical equipment by Division 23, the ATC contractor shall coordinate with Division 23, Mechanical, and shall furnish and install all items necessary to meet the requirements of the Sequence of

Operation and the Central Control and Monitoring System (CCMS) indicated on the drawings and as required in this specification.

- K. The control system shall include all necessary and specified control equipment properly installed in accordance with the specifications and drawings and shall include, but not be limited to the automatic temperature control and energy management system of the following:
1. Closed Circuit Evaporative Fluid Cooler/Cooling Tower Control Valves
 2. Closed Circuit Evaporative Fluid Cooler System Interlocks and Alarms
 3. Cooling Tower System Interlocks and Alarms
 4. Differential Bypass Valves and Transmitters
 5. Chemical treatment system interlocks and alarms
 6. Electric Heat Tracing Monitoring
 7. Existing Heat Exchangers
 8. Existing Boilers
 9. Flow Measuring Stations
 10. Flow Switches
 11. Heating System
 12. High Temperature Alarms
 13. Make-up Water Systems Interlocks and Alarms
 14. All Pumps
 15. Variable Speed Drives
- L. All labor, material, equipment and software to meet the functional intent of the system, as specified herein and as shown on the drawings, shall be included. Drawings are diagrammatic only. Equipment and labor not specifically referred to herein or on the plans, that are required to meet the functional intent, shall be provided without additional cost to the owner.
- M. Where equipment is specified to be provided by equipment manufacturer or where packaged controls are specified map out all points provided by the manufacturer so the same can be viewed by ATC system. As a minimum all points indicated in the point list and control diagram must be viewable and adjustable from the ATC system. Coordinate with equipment manufacturer.

1.2. DEFINITIONS

- A. DDC: Direct digital control.
- B. I/O: Input/output.
- C. LonWorks: A control network technology platform for designing and implementing interoperable control devices and networks.
- D. MS/TP: Main tracking/token passing.
- E. PC: Personal computer.
- F. PID: Proportional plus integral plus derivative.
- G. RTD: Resistance temperature detector.
- H. UPS: Uninterruptible Power Supply.
- I. NAE: Network Automated Engine.

1.3. SYSTEM PERFORMANCE

- A. Comply with the following performance requirements:
 - 1. Graphic Refresh: Update graphic with minimum 20 dynamic points with current data within 8 seconds.
 - 2. Object Command: Reaction time of less than two seconds between operator command of a binary object and device reaction.
 - 3. Object Scan: Transmit change of state and change of analog values to control units or workstation within six seconds.
 - 4. Alarm Response Time: Annunciate alarm at workstation within 45 seconds. Multiple workstations must receive alarms within five seconds of each other.
 - 5. Program Execution Frequency: Run capability of applications as often as five seconds, but selected consistent with mechanical process under control.
 - 6. Performance: Programmable controllers shall execute DDC PID control loops, and scan and update process values and outputs at least once per second.
 - 7. Reporting Accuracy and Stability of Control: Report values and maintain measured variables within tolerances as follows:
 - a. Water Temperature: Plus or minus 1 deg F (0.5 deg C).
 - b. Water Flow: Plus or minus 5 percent of full scale.
 - c. Water Pressure: Plus or minus 2 percent of full scale.
 - d. Space Temperature: Plus or minus 1 deg F (0.5 deg C).
 - e. Ducted Air Temperature: Plus or minus 1 deg F (0.5 deg C).
 - f. Outside Air Temperature: Plus or minus 2 deg F (1.0 deg C).

- g. Temperature Differential: Plus or minus 0.25 deg F (0.15 deg C).
- h. Relative Humidity: Plus or minus 5 percent.
- i. Airflow (Pressurized Spaces): Plus or minus 3 percent of full scale.
- j. Electrical: Plus or minus 5 percent of reading.

1.4. DELIVERY, STORAGE, AND HANDLING

- A. Factory-Mounted Components: Where control devices specified in this Section are indicated to be factory mounted on equipment, arrange for shipping of control devices to equipment manufacturer.
- B. System Software: Update to latest version of software at Project completion.

1.5. COORDINATION

- A. Coordinate location of temperature sensors and other exposed control sensors with plans and room details before installation.
- B. Coordinate supply of conditioned electrical branch circuits for control units and operator workstation.
- C. Coordinate equipment with Division 26 Section, Panelboards to achieve compatibility with starter coils and annunciation devices.
 - 1. Coordinate equipment with Division 26 Section, Motor-Controllers to achieve compatibility with motor starters and annunciation devices.

1.6. WORK BY OTHERS

- A. Automatic temperature control valves, air flow stations, pipe taps, flow meters, and separable wells for immersion elements furnished by the control manufacturer shall be installed by the mechanical contractor under the control manufacturer's supervision. The control contractor shall deliver to the mechanical contractor valves and wells for installation within the various systems.
- B. All automatic dampers furnished by the control manufacturer shall be installed by the mechanical contractor under the control manufacturer's supervision.

1.7. QUALITY ASSURANCE

- A. Supplier shall have an in-place support facility with technical staff, spare parts inventory and all necessary test and diagnostic equipment. The fully staffed and equipped office shall be within a 60 mile radius of the job site.
- B. The systems shall be complete in all respects, and shall be installed by skilled personnel. The Control Contractor shall have a successful history in the installation and maintenance of automatic temperature control systems similar in size and performance to that specified herein.
- C. All electrical wiring in connection with the Automatic Temperature Control System shall be furnished and installed by the ATC Contractor. This shall include all interlock wiring

between the fans, pumps, heating systems, heat exchangers, boilers, dampers, cooling towers, closed circuit fluid coolers, flow measuring stations, etc.

- D. Bids by wholesalers, contractors or franchised dealers or any other firm whose principal business is not that of manufacturing or installing automatic temperature control systems, shall not be acceptable. Bid documents that are not complete in their response to these documents or take exception to any of the capabilities defined within these documents shall not be acceptable.
- E. Installer Qualifications: Automatic control system manufacturer's authorized representative who is trained and approved for installation of system components required for this Project.
- F. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- G. Comply with ASHRAE 135 for DDC system components.

1.8. GUARANTEE AND INSTRUCTION

- A. The control system including all components, system software, parts and assemblies herein specified shall be free from defects in workmanship and materials under normal use and service. After completion of the installation, the Control Manufacturer shall regulate and adjust all thermostats, control valves, control motors, and other equipment provided under this contract. If within two (2) years from the date of acceptance by Owner any of the equipment herein described is proved to be defective in workmanship or materials, it will be replaced or repaired at no additional cost to the Owner. The Control Manufacturer shall, after completion, provide any service incidental to the proper performance of the Control System under guarantees outlined above for a period of two (2) years. Normal maintenance of the system is not to be considered part of the guarantee. All corrective modifications made during warranty service periods shall be updated on all user documentation including "as-built" shop drawings and on user and manufacturer archived software disks.
- B. The control contractor shall completely check out, calibrate and test all connected hardware to insure that the system performs in accordance with the approved specifications and sequences of operation submitted.
- C. Upon completion of the work, the control drawings encased in heavy plastic shall be provided where directed. Layout shall show all control equipment and the function of each item indicated.
- D. The temperature control contractor's office shall be within a 100 mile radius of the job site.
- E. The contractor shall respond to the job site with qualified technicians within a 4 hour period for any emergency relating to the control system or energy management systems.
- F. This agreement shall include emergency service during normal working hours.

1.9. SUBMITTALS

- A. Product Data: Include manufacturer's technical literature for each control device. Indicate dimensions, capacities, performance characteristics, electrical characteristics, finishes for materials, and installation and startup instructions for each type of product indicated.
 - 1. DDC System Hardware: Bill of materials of equipment indicating quantity, manufacturer, and model number. Include technical data for operator workstation equipment, interface equipment, control units, transducers/transmitters, sensors, actuators, valves, relays/switches, control panels, and operator interface equipment.
 - 2. Control System Software: Include technical data for operating system software, operator interface, color graphics, and other third-party applications.
 - 3. Controlled Systems: Instrumentation list with element name, type of device, manufacturer, model number, and product data. Include written description of sequence of operation including schematic diagram.
- B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 1. Bill of materials of equipment indicating quantity, manufacturer, and model number.
 - 2. Schematic flow diagrams showing equipment, fans, pumps, coils, dampers, valves, and control devices.
 - 3. Wiring Diagrams: Power, signal, and control wiring.
 - 4. Details of control panel faces, including controls, instruments, and labeling.
 - 5. Written description of sequence of operation.
 - 6. Schedule of dampers including size, leakage, and flow characteristics.
 - 7. Schedule of valves including flow characteristics.
 - 8. DDC System Hardware:
 - a. Wiring diagrams for control units with termination numbers.
 - b. Schematic diagrams and floor plans for field sensors and control hardware.
 - c. Schematic diagrams for control, communication, and power wiring, showing trunk data conductors and wiring between operator workstation and control unit locations.
 - 9. Control System Software: List of color graphics indicating monitored systems, data (connected and calculated) point addresses, output schedule, and operator notations.
 - 10. Controlled Systems:

- a. Schematic diagrams of each controlled system with control points labeled and control elements graphically shown, with wiring.
 - b. Scaled drawings showing mounting, routing, and wiring of elements including bases and special construction.
 - c. Written description of sequence of operation including schematic diagram.
 - d. Points list.
- C. Data Communications Protocol Certificates: Certify that each proposed DDC system component complies with LonWorks or Bacnet.
- D. Software and Firmware Operational Documentation: Include the following:
 1. Software operating and upgrade manuals.
 2. Program Software Backup: On a magnetic media or compact disc, complete with data files.
 3. Device address list.
 4. Printout of software application and graphic screens.
 5. Software license required by and installed for DDC workstations and control systems.
- E. Software Upgrade Kit: For Owner to use in modifying software to suit future systems revisions or monitoring and control revisions.
- F. Qualification Data: For Installer and manufacturer.
- G. Field quality-control test reports.
- H. Submit screen shots of ATC system graphics at substantial completion.
- I. Operation and Maintenance Data: For HVAC instrumentation and control system to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section, Operation and Maintenance Data, and Division 23 Section, Common Work Results for HVAC include the following:
 1. Maintenance instructions and lists of spare parts for each type of control device.
 2. Interconnection wiring diagrams with identified and numbered system components and devices.
 3. Keyboard illustrations and step-by-step procedures indexed for each operator function.
 4. Inspection period, cleaning methods, cleaning materials recommended, and calibration tolerances.
 5. Calibration records and list of set points.
- J. Upon completion of the work, provide a complete set of "as-built" drawings and

application software on CD, USB, or other type of electronic storage device. Drawings shall be provided in format as acceptable to the Owner's files. Submit as-built drawings and specification to Owner's representative for review and approval prior to final project closeout.

1.10. SOFTWARE LICENSE AGREEMENT

- A. The owner shall sign a copy of the manufacturer's standard software and firmware licensing agreement as a condition of this contract. Such license shall grant use of all programs and application software to owner as defined by the manufacturer's license agreement, but shall protect manufacturer's rights to disclosure of trade secrets contained within such software. All software and hardware upgrades shall be included in two (2) year warranty period.
- B. Software license agreement shall not apply on projects where existing ATC system is being extended.
- C. Minimum of four (4) software license seats shall be provided. Storage of all software shall be coordinated with the Indian River School District's IT Manager.

1.11. ELECTRICAL SURGE PROTECTION

- A. It is the responsibility of the ATC/FMS contractor to provide adequate surge protection for all wall mounted control panels required for this project.
 - 1. Devices under surge protection shall be of design that loss of memory will not occur in the event of the surge protection device being activated due to surge/spike conditions.
 - 2. Surge protection devices will be required to be hard wired, with the exception of peripheral devices that use standard 110VAC plugs for connections (i.e. Modems).
 - 3. Surge protection devices are to be rated for 120 VAC single phase, 20 (or greater) amps capacity.
 - 4. Surge Protection devices to include internal fuse protection, audible surge alarm & LED indicators.
 - 5. Surge protectors to have clamping voltage of 480V peak, maximum surge current rating of 50,000 amps. Unit to have NEMA 12 enclosure with wall mounting bracket and conduit connection.

1.12. TRAINING

- A. The training time period shall be coordinated with the school system's facility Engineer. The schedule training period shall be arranged at the owner's convenience.
- B. Cost shall include all training material, instruction books, and two copies of video tape with sound DVD of training session.
- C. Upon completion of the work, the Control Contractor shall have completely adjusted the entire control system. He shall arrange to instruct the Owner's representative on the

operation of the control system for a period of not less than 16 hours. All training shall be by the control contractor and shall utilize specified manuals and as-built documentation.

- D. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain control systems and components.
1. Train Owner's maintenance personnel on procedures and schedules for starting and stopping, troubleshooting, servicing, and maintaining equipment and schedules.
 2. Provide operator training on data display, alarm and status descriptors, requesting data, executing commands, calibrating and adjusting devices, resetting default values, and requesting logs. Include a minimum of 40 hours' dedicated instructor time on-site.
 3. Review data in maintenance manuals. Refer to Division 01 Section, Contract Closeout.
 4. Review data in maintenance manuals. Refer to Division 01 Section, Operation and Maintenance Data.
 5. Schedule training with Owner, with at least seven days' advance notice.
 6. Control Contractor shall also attend and participate in separate HVAC equipment systems training in addition to ATC training.

1.13. ALTERNATES

- A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

1.14. INDIAN RIVER SCHOOL DISTRICT SPECIFIC REQUIREMENTS

- A. The ATC Subcontractor shall include in his bid all costs associated with incorporating the following specific requirements:
1. All holiday schedules shall incorporate a 12 month block. Coordinate exact holidays, schedules, calendars, occupied, unoccupied periods with Owner prior to writing software. All schedules shall be reviewed and approved by the Owner.
 2. Relays for ATC equipment shall not be located in ceilings. All relays shall be located in equipment control panels and/or mechanical rooms.
 3. Graphics on ATC computer shall in addition to basic requirements indicate the percentage open or closed on all valves and dampers.
 4. The ATC Computer Graphics shall indicate for each item of equipment the "on" or "off" status and command shall be "run" or "stop".
 5. All Temperature Sensors, equipment, relative humidity sensors, current sensors, differential pressure sensors, etc. indicated on ATC Control Diagrams and point list shall be displayed on the ATC Computer Graphic. Measured value or status shall be displayed.

6. The exact heat of rejection temperature set points, changeover set points. etc., shall be coordinated with Owner prior to final data entry. All items indicated in sequences of Operation as “adjustable” shall be reviewed and approved by Owner prior to implementation of the same.
7. The outside air relative humidity and outside air temperature shall be monitored on ATC system and reported on ATC Computer Graphics. See Floor plans for exact locations.
8. Provide a graphic of all floor plans indicating location of all equipment interlocked with ATC System including all control panels.
9. Graphic shall also indicate area of building served by each item of equipment. Graphics shall indicate all global sensor readings.
10. All equipment shall be labeled with name of equipment, area served, and area location (room name/number).
11. Provide additional software package and license so that Owner can install software on Owner provided laptop. Assist owner with installation of software.

1.15. GLOBAL SENSORS

A. General

1. Furnish and install global sensors and report the same on the automatic temperature control system.
2. Global sensors shall monitor and trend the following conditions:
 - a. Monitor all electric heat tracing/cables.
 - b. Outside air temperature.
 - c. Outside air relative humidity.
 - d. Closed circuit evaporative fluid cooler supply temperature.
 - e. Closed circuit evaporative fluid cooler return temperature.
 - f. Cooling tower supply temperature.
 - g. Cooling tower return temperature.
 - h. Heat pump water supply temperature and return temperature.
 - i. Heating water supply temperature
 - j. Heating water return temperature.
 - k. All fan speeds where variable frequency drives are specified.
 - l. All pump speeds where variable frequency drives are specified.
 - m. All pump amperage's where variable frequency drives are specified.
 - n. All fan amperages where variable speed fans are indicated. Graphic shall also indicate area of building served by each item of equipment.
 - o. Global holiday schedules:
 - i. Provide all interlock wiring and programming to allow a global holiday schedule for all equipment except the administration equipment. Global holiday schedule shall allow the Owner to shut down the entire building's HVAC systems if an unscheduled event occurs when school is cancelled.

- ii. System shall also be capable of individual scheduling of equipment as specified or all can be globally modified at once.
- p. All equipment interlocked with ATC system shall be able to be turned on/off via ATC system as specified. Changing temperature set point alone is not acceptable method for turning equipment on/off.
- q. Where valve or damper position is indicated ATC graphic shall indicate percentage open or percentage closed.

PART 2. PRODUCTS

2.1. BUILDING MANAGEMENT SYSTEM

- A. The Building Management System (BMS) shall use an open architecture and fully support a multi-vendor environment. To accomplish this effectively, the BMS shall support open communication protocol standards and integrate a wide variety of third-party devices and applications. The system shall be designed for use on the Internet, or intranets using off the shelf, industry standard technology compatible with other owner provided networks.
- B. The Building Management System shall consist of the following:
 - 1. Standalone Network Automation Engine(s)
 - 2. Field Equipment Controller(s)
 - 3. Input/Output Module(s)
 - 4. Local Display Device(s)
 - 5. Distributed User Interface(s)
 - 6. Network processing, data storage and communications equipment
 - 7. Other components required for a complete and working BMS
- C. The system shall be modular in nature, and shall permit expansion of both capacity and functionality through the addition of sensors, actuators, controllers and operator devices, while re-using existing controls equipment.
- D. System architectural design shall eliminate dependence upon any single device for alarm reporting and control execution. The failure of any single component or network connection shall not interrupt the execution of control strategies at other operational devices.
- E. Automation Network
 - 1. The automation network shall be based on a PC industry standard of Ethernet TCP/IP. Where used, LAN controller cards shall be standard "off the shelf" products available through normal PC vendor channels.
 - 2. The automation network shall be capable of operating at a communication speed of 100 Mbps, with full peer-to-peer network communication.

3. Network Automation Engines (NAE) and/or system controllers shall reside on the automation network.
4. The automation network will be compatible with other enterprise-wide networks. Where indicated, the automation network shall be connected to the enterprise network and share resources with it by way of standard networking devices and practices.

F. Control Network

1. Network Automation Engines and/or system controllers shall provide supervisory control over the control network and shall support all three (3) of the following communication protocols:
 - a. BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135, Clause 9.
 - b. LonWorks enabled devices using the Free Topology Transceiver (FTT-10a).
 - c. The Johnson Controls N2 Field Bus or equivalent.
 - d. Tridium FX-40
 - e. Honeywell Webs
 - f. TAC Controls by Schneider Electric
 - g. Siemens P1/P2 Serial
2. Control networks shall provide either "Peer-to-Peer," Main-Tracking, or Supervised Token Passing communications, and shall operate at a minimum communication speed of 9600 baud.
3. DDC Controllers shall reside on the control network.
4. Control network communication protocol shall be BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135.
5. A BACnet Protocol Implementation Conformance Statement shall be provided for each controller device (main or tracking) that will communicate on the BACnet MS/TP Bus.
6. The Conformance Statements shall be submitted with the BAS Submittals.

G. Integration

1. Hardwired
 - a. Analog and digital signal values shall be passed from one system to another via hardwired connections.
 - b. There will be one separate physical point on each system for each point to be integrated between the systems.
2. BACnet Protocol Integration – BACnet
 - a. The neutral protocol used between systems will be BACnet over Ethernet and comply with the ASHRAE BACnet standard 135-2003.

- b. A complete Protocol Implementation Conformance Statement (PICS) shall be provided for all BACnet system devices.
- c. The ability to command, share point object data, change of state (COS) data and schedules between the host and BACnet systems shall be provided.

H. Dedicated Web Based User Interface

- 1. Where required by the Owner, the BMS Contractor shall provide and install a personal computer for command entry, information management, network alarm management, and database management functions. All real-time control functions, including scheduling, history collection and alarming, shall be resident in the BMS Network Automation Engines to facilitate greater fault tolerance and reliability. Coordinate with Owner to determine computer type (i.e. PC (Windows based) or Macintosh (Apple)).
- 2. Dedicated User Interface Architecture – The architecture of the computer shall be implemented to conform to industry standards, so that it can accommodate applications provided by the BMS Contractor and by other third party applications suppliers, including but not limited to Microsoft Office Applications. Specifically it must be implemented to conform to the following interface standards.
 - a. Microsoft Internet Explorer for user interface functions
 - b. Microsoft Office Professional for creation, modification and maintenance of reports, sequences other necessary building management functions
 - c. Microsoft Outlook or other e-mail program for supplemental alarm functionality and communication of system events, and reports
 - d. Required network operating system for exchange of data and network functions such as printing of reports, trends and specific system summaries.
- 3. Computer Hardware – The personal computer(s) shall be configured as follows:
 - a. Description: A tower or all-in-one computer designed for normal use at a single, semipermanent location.
 - b. Performance Requirements:
 - i. Performance requirements may dictate equipment exceeding minimum requirements indicated.
 - ii. Energy Star compliant.
 - c. Personal Computer:
 - i. Minimum Processor Speed: 3 gigahertz (GHz).
 - d. RAM:
 - i. Capacity: 16GB.
 - ii. Speed and Type: 1333 MHz, SDRAM.
 - e. Hard Drive:
 - i. Media: Solid state.
 - ii. Number of Hard Drives: One.
 - iii. Capacity: 250GB.
 - f. Optical Read and Write Drive:
 - i. Include with at least 2 MB of data buffer.
 - ii. Type: SCSI CD-ROM Drive with Read/Write Capability.

- iii. Average access time of 150 ms or less.
- g. At least four expansion slots.
- h. Video Card:
 - i. Resolution: 1920 by 1200 pixels.
 - ii. RAM: 4 GB.
 - iii. Controller Speed: 4GHz.
- i. Sound Card:
 - i. At least 128 voice wavetable synthesis.
 - ii. Capable of delivering three-dimensional sound effects.
 - iii. High-resolution 16-bit stereo digital audio recording and playback with user-selectable sample rates up to 48,000 Hz.
- j. Two (2) Network Interface Cards: Include cards with connection, as applicable.
 - i. 10-100-1000 base TX Ethernet with RJ45 connector port.
 - ii. 100 base FX Ethernet with SC or ST port.
- k. Wireless Ethernet, 802.11 a/b/g/n.
- l. Optical Modem: Full duplex link for connection to optical fiber cable provided.
- m. I/O Ports:
 - i. Two USB 3.0 ports on front panel, six on back panel, and three internal on motherboard.
 - ii. One serial port.
 - iii. One parallel port.
 - iv. Two PS/2 ports.
 - v. One RJ-45.
 - vi. One stereo line-in and headphone/line-out on back panel.
 - vii. One microphone and headphone connector on front panel.
 - viii. One IEEE 1394 on front and back panel with PCI-e card.
 - ix. One ESATA port on back panel.
- n. Battery: Life of at least three years to maintain system clock/calendar and ROM, as a minimum.
- o. Keyboard:
 - i. 101 enhanced keyboard.
 - ii. Full upper- and lowercase ASCII keyset, numeric keypad, dedicated cursor control keypad, and 12 programmable function keys.
 - iii. Wireless operation within up to 72 inches (1800 mm) in front of workstation.
- p. Pointing Device:
 - i. Either a two- or three-button mouse.
 - ii. Wireless operation within up to 72 inches (1800 mm) in front of workstation.
- q. Flat Panel Display Monitor:
 - i. Display:
 - 1. Color display with 21 inches diagonal viewable area.
 - 2. Digital input signal.
 - 3. Aspect Ratio: 16 to 9.
 - 4. Antiglare display.
 - 5. Tilt adjustable base.
 - 6. Energy Star compliant.
 - 7. Resolution: 1920 by 1200 pixels at 60 Hz.

- 8. Number of Displays: One.
- r. Speakers:
 - i. Two, with individual controls for volume, bass and treble.
 - ii. Signal to Noise Ratio: At least 65 dB.
 - iii. Power: At least 4 W per speaker/channel.
 - iv. Magnetic shielding to prevent distortion on the video monitor.
- s. I/O Cabling: Include applicable cabling to connect I/O devices.

I. User Interface Application Components

1. Operator Interface

- a. An integrated browser based client application shall be used as the user operator interface program.
- b. All Inputs, Outputs, Setpoints, and all other parameters as defined within Part 3 or on the drawings, shown on the design drawings, or required as part of the system software, shall be displayed for operator viewing and modification from the operator interface software.
- c. The user interface software shall provide help menus and instructions for each operation and/or application.
- d. All controller software operating parameters shall be displayed for the operator to view/modify from the user interface. These include: setpoints, alarm limits, time delays, PID tuning constants, run-times, point statistics, schedules, and so forth.
- e. The Operator Interface shall incorporate comprehensive support for functions including, but not necessarily limited to, the following:
 - i. User access for selective information retrieval and control command execution
 - ii. Monitoring and reporting
 - iii. Alarm, non-normal, and return to normal condition annunciation
 - iv. Selective operator override and other control actions
 - v. Information archiving, manipulation, formatting, display and reporting
 - vi. FMS internal performance supervision and diagnostics
 - vii. On-line access to user HELP menus
 - viii. On-line access to current FMS as-built records and documentation
 - ix. Means for the controlled re-programming, re-configuration of FMS operation and for the manipulation of FMS database information in compliance with the prevailing codes, approvals and regulations for individual FMS applications.
 - x. The operation of the control system shall be independent of the user interface, which shall be used for operator communications only. Systems that rely on an operator workstation to provide supervisory control over controller execution of the sequences of operations or system communications shall not be acceptable.

2. Navigation Trees

- a. The system will have the capability to display multiple navigation trees that will aid the operator in navigating throughout all systems and points connected. At minimum provide a tree that identifies all systems on the

networks.

- b. Provide the ability for the operator to add custom trees. The operator will be able to define any logical grouping of systems or points and arrange them on the tree in any order. It shall be possible to nest groups within other groups. Provide at minimum 5 levels of nesting.
- c. The navigation trees shall be “dockable” to other displays in the user interface such as graphics. This means that the trees will appear as part of the display, but can be detached and then minimized to the Windows task bar or closed altogether. A simple keystroke will reattach the navigation to the primary display of the user interface.

3. Alarms

- a. Alarms shall be routed directly from Network Automation Engines to PCs and servers. It shall be possible for specific alarms from specific points to be routed to specific PCs and servers. The alarm management portion of the user interface shall, at the minimum, provide the following functions:
 - i. Log date and time of alarm occurrence.
 - ii. Generate a “Pop-Up” window, with audible alarm, informing a user that an alarm has been received.
 - iii. Allow a user, with the appropriate security level, to acknowledge, temporarily silence, or discard an alarm.
 - iv. Provide an audit trail on hard drive for alarms by recording user acknowledgment, deletion, or disabling of an alarm. The audit trail shall include the name of the user, the alarm, the action taken on the alarm, and a time/date stamp.
 - v. Provide the ability to direct alarms to an e-mail address or alphanumeric pager. This must be provided in addition to the pop up window described above. Systems that use e-mail and pagers as the exclusive means of annunciating alarms are not acceptable.
 - vi. Any attribute of any object in the system may be designated to report an alarm.
- b. The FMS shall annunciate diagnostic alarms indicating system failures and non-normal operating conditions
- c. The FMS shall annunciate application alarms as required.

4. Reports and Summaries

- a. Reports and Summaries shall be generated and directed to the user interface displays, with subsequent assignment to printers, or disk. As a minimum, the system shall provide the following reports:
 - i. All points in the BMS
 - ii. All points in each BMS application
 - iii. All points in a specific controller
 - iv. All points in a user-defined group of points
 - v. All points currently in alarm
 - vi. All points locked out
 - vii. All BMS schedules
 - viii. All user defined and adjustable variables, schedules, interlocks and the like.
- b. Summaries and Reports shall be accessible via standard UI functions and

- c. not dependent upon custom programming or user defined HTML pages. Selection of a single menu item, tool bar item, or tool bar button shall print any displayed report or summary on the system printer for use as a building management and diagnostics tool.
- d. The system shall allow for the creation of custom reports and queries via a standard web services XML interface and commercial off-the-shelf software such as Microsoft Access, Microsoft Excel, or Crystal Reports.

5. Schedules

- a. A graphical display for time-of-day scheduling and override scheduling of building operations shall be provided. At a minimum, the following functions shall be provided:
 - i. Weekly schedules
 - ii. Exception Schedules
 - iii. Monthly calendars
- b. Weekly schedules shall be provided for each group of equipment with a specific time use schedule.
- c. It shall be possible to define one or more exception schedules for each schedule including references to calendars
- d. Monthly calendars shall be provided that allow for simplified scheduling of holidays and special days for a minimum of five years in advance. Holidays and special days shall be user-selected with the pointing device or keyboard, and shall automatically reschedule equipment operation as previously defined on the exception schedules.
- e. Changes to schedules made from the User Interface shall directly modify the Network Automation Engine schedule database.
- f. Schedules and Calendars shall comply with ASHRAE SP135/2003 BACnet Standard.
- g. Selection of a single menu item or tool bar button shall print any displayed schedule on the system printer for use as a building management and diagnostics tool.

6. Password

- a. Multiple-level password access protection shall be provided to allow the user/manager to user interface control, display, and database manipulation capabilities deemed appropriate for each user, based on an assigned password.
- b. Each user shall have the following: a user name (24 characters minimum), a password (12 characters minimum), and access levels.
- c. The system shall allow each user to change his or her password at will.
- d. When entering or editing passwords, the system shall not echo the actual characters for display on the monitor.
- e. A minimum of five levels of access shall be supported individually or in any combination as follows:
 - i. Level 1 = View Data
 - ii. Level 2 = Command
 - iii. Level 3 = Operator Overrides
 - iv. Level 4 = Database Modification
 - v. Level 5 = Database Configuration

- vi. Level 6 = All privileges, including Password Add/Modify
 - f. A minimum of 100 unique passwords shall be supported.
 - g. Operators shall be able to perform only those commands available for their respective passwords. Display of menu selections shall be limited to only those items defined for the access level of the password used to log-on.
 - h. The system shall automatically generate a report of log-on/log-off and system activity for each user. Any action that results in a change in the operation or configuration of the control system shall be recorded, including: modification of point values, schedules or history collection parameters, and all changes to the alarm management system, including the acknowledgment and deletion of alarms.
7. Screen Manager - The User Interface shall be provided with screen management capabilities that allow the user to activate, close, and simultaneously manipulate a minimum of 4 active display windows plus a network or user defined navigation tree.
8. Dynamic Color Graphics
- a. The graphics application program shall be supplied as an integral part of the User Interface. Browser or Workstation applications that rely only upon HTML pages shall not be acceptable.
 - b. The graphics applications shall include a create/edit function and a runtime function. The system architecture shall support an unlimited number of graphics documents (graphic definition files) to be generated and executed.
 - c. The graphics shall be able to display and provide animation based on real-time data that is acquired, derived, or entered.
 - d. Graphics runtime functions – A maximum of 16 graphic applications shall be able to execute at any one time on a user interface or workstation with 4 visible to the user. Each graphic application shall be capable of the following functions:
 - i. All graphics shall be fully scalable
 - ii. The graphics shall support a maintained aspect ratio.
 - iii. Multiple fonts shall be supported.
 - iv. Unique background shall be assignable on a per graphic basis.
 - v. The color of all animations and values on displays shall indicate the status of the object attribute.
 - e. Operation from graphics – It shall be possible to change values (setpoints) and states in system controlled equipment by using drop-down windows accessible via the pointing device
 - f. Graphic editing tool – A graphic editing tool shall be provided that allows for the creation and editing of graphic files. The graphic editor shall be capable of performing/defining all animations, and defining all runtime binding.
 - i. The graphic editing tool shall in general provide for the creation and positioning of point objects by dragging from tool bars or drop-downs and positioning where required.
 - ii. In addition, the graphic editing tool shall be able to add additional content to any graphic by importing backgrounds in the SVG, BMP or JPG file formats.

- g. Aliasing – Many graphic displays representing part of a building and various building components are exact duplicates, with the exception that the various variables are bound to different field values. Consequently, it shall be possible to bind the value of a graphic display to aliases, as opposed to the physical field tags.

9. Historical trending and data collection

- a. Each Automation Engine shall store trend and point history data for all analog and digital inputs and outputs, as follows:
 - i. Any point, physical or calculated, may be designated for trending. Two (2) methods of collection shall be allowed:
 - 1. Defined time interval
 - 2. Upon a change of value.
 - ii. Each Automation Engine shall have the capability to store multiple samples for each physical point and software variable based upon available memory, including an individual sample time/date stamp. Points may be assigned to multiple history trends with different collection parameters.
- b. Trend and change of value data shall be stored within the engine and uploaded to a dedicated trend database or exported in a selectable data format via a provided data export utility. Uploads to a dedicated database shall occur based upon one of the following: user-defined interval, manual command, or when the trend buffers are full. Exports shall be as requested by the user or on a time scheduled basis. Trend data shall be available for a minimum of twelve (12) months.

10. Trend data viewing and analysis

- a. Provide a trend viewing utility that shall have access to all database points.
- b. It shall be possible to retrieve any historical database point for use in displays and reports by specifying the point name and associated trend name.
- c. The trend viewing utility shall have the capability to define trend study displays to include multiple trends
- d. Displays shall be able to be single or stacked graphs with on-line selectable display characteristics, such as ranging, color, and plot style.
- e. Display magnitude and units shall both be selectable by the operator at any time without reconfiguring the processing or collection of data. This is a zoom capability.
- f. Display magnitude shall automatically be scaled to show full graphic resolution of the data being displayed.
- g. Trend studies shall be capable of calculating and displaying calculated variables including highest value, lowest value and time based accumulation.

J. Network Automation Engine (NAE)/ System Controllers

- 1. The Network Automation Engine (NAE)/ System Controllers or approved equal shall be a fully user-programmable, supervisory controller. The NAE shall monitor the network of distributed application-specific controllers, provide global

- strategy and direction, and communicate on a peer-to-peer basis with other Network Automation Engines.
2. Automation network – The NAE shall reside on the automation network and shall support a subnet of system controllers.
 3. User Interface – Each NAE shall have the ability to deliver a web based User Interface (UI) as previously described. All computers connected physically or virtually to the automation network shall have access to the web based UI.
 - a. The web based UI software shall be imbedded in the NAE. Systems that require a local copy of the system database on the user's personal computer are not acceptable.
 - b. The NAE shall support up four (4) concurrent users.
 - c. The web based user shall have the capability to access all system data through one NAE.
 - d. Remote users connected to the network through an Internet Service Provider (ISP) or telephone dial up shall also have total system access through one NAE.
 - e. Systems that require the user to address more than one NAE to access all system information are not acceptable.
 - f. The NAE shall have the capability of generating web based UI graphics. The graphics capability shall be imbedded in the NAE.
 - g. Systems that support UI Graphics from a central database or require the graphics to reside on the user's personal computer are not acceptable.
 - h. The web based UI shall support the following functions using a standard version of Microsoft Internet Explorer:
 - i. Configuration
 - ii. Commissioning
 - iii. Data Archiving
 - iv. Monitoring
 - v. Commanding
 - vi. System Diagnostics
 - i. Systems that require workstation software or modified web browsers are not acceptable.
 - j. The NAE shall allow temporary use of portable devices without interrupting the normal operation of permanently connected modems.
 4. Processor – The NAE shall be microprocessor-based with a minimum word size of 32 bits. The NAE shall be a multi-tasking, multi-user, and real-time digital control processor. Standard operating systems shall be employed. NAE size and capability shall be sufficient to fully meet the requirements of this Specification.
 5. Memory – Each NAE shall have sufficient memory to support its own operating system, databases, and control programs, and to provide supervisory control for all control level devices.
 6. Hardware Real Time Clock – The NAE shall include an integrated, hardware-based, real-time clock.
 7. The NAE shall include troubleshooting LED indicators to identify the following

conditions:

- a. Power - On/Off
 - b. Ethernet Traffic – Ethernet Traffic/No Ethernet Traffic
 - c. Ethernet Connection Speed – 10 Mbps/100 Mbps
 - d. FC Bus – Normal Communications/No Field Communications
 - e. Peer Communication – Data Traffic Between NAE Devices
 - f. Run – NAE Running/NAE In Startup/NAE Shutting Down/Software Not Running
 - g. Bat Fault – Battery Defective, Data Protection Battery Not Installed
 - h. Fault – General Fault
 - i. Modem RX – NAE Modem Receiving Data
 - j. Modem TX – NAE Modem Transmitting Data
8. Communications Ports – The NAE shall provide the following ports for operation of operator Input/Output (I/O) devices, such as industry-standard computers, modems, and portable operator’s terminals.
- a. Up to two (2) USB port
 - b. Up to two (2) URS-232 serial data communication port
 - c. Up to two (2) RS-485 port
 - d. One (1) Ethernet port
9. Diagnostics – The NAE shall continuously perform self-diagnostics, communication diagnosis, and diagnosis of all panel components. The Network Automation Engine shall provide both local and remote annunciation of any detected component failures, low battery conditions, or repeated failures to establish communication.
10. Power Failure – In the event of the loss of normal power, The NAE shall continue to operate for a user adjustable period of up to 10 minutes after which there shall be an orderly shutdown of all programs to prevent the loss of database or operating system software.
- a. During a loss of normal power, the control sequences shall go to the normal system shutdown conditions. All critical configuration data shall be saved into Flash memory.
 - b. Upon restoration of normal power and after a minimum off-time delay, the controller shall automatically resume full operation without manual intervention through a normal soft-start sequence.
11. Certification – The NAE shall be listed by Underwriters Laboratories (UL).
12. Controller network – The NAE shall support the following communication protocols on the controller network:
- a. The NAE shall support BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135, Clause 9 on the controller network.
 - i. A BACnet Protocol Implementation Conformance Statement shall be provided for each controller device (main or tracking) that will communicate on the BACnet MS/TP Bus.

- ii. The Conformance Statements shall be submitted 10 day prior to bidding.
 - iii. The NAE shall support a minimum of 100 control devices.
- b. The NAE shall support the Johnson Controls N2, Tridium FX-40, or Honeywell Webs or approved equal Field Bus.
 - i. The NAE shall support a minimum of 100 N2 control devices.
 - ii. The Bus shall conform to Electronic Industry Alliance (EIA) Standard RS-485.
 - iii. The Bus shall employ a main/tracking protocol where the NAE is the main.
 - iv. The Bus shall employ a four (4) level priority system for polling frequency.
 - v. The Bus shall be optically isolated from the NAE.
 - vi. The Bus shall support the Metasys Integrator System.

2.2. WIRING

- A. The multi-conductor cable for field wiring of electronic analog sensors shall be minimum No. 22 AWG, 300 volt, thermoplastic with stranded copper wire and 100 percent shield coverage. The number of conductors in each sensor cable shall be as determined by the Contractor. 2/c #22 shielded cables shall be Belden Cat. #8451 3/c #20 shielded cables shall be Belden Cat. #9770 or approved equal.
- B. Conductors for digital sensors or contact control shall be the same as for the analog sensors, except the grounded shield is not required.
- C. Individual conductors shall be color coded and in addition shall be numbered in the field to identify the particular terminal to which attached. Field numbering shall be performed with Brady or approved equal markers wrapped around the wire near the terminal connection. All wires shall be terminated with pressure type connectors suitable for wire size, material and terminal connection.
- D. All exposed wiring or wiring concealed in partitions shall be installed in a designated conduit raceway. The conduit shall conform to Division 26 of the specification. Where wiring is installed in an air plenum the same shall be plenum rated cable.
- E. All junction boxes shall have covers painted safety green, and be rigid steel.
- F. All wiring between differential pressure transmitters and variable frequency drive pump controllers shall be shielded and grounded at the pump controller end. Directly route the variable frequency drive pump controller to the differential pressure transmitter(s).
- G. Where a motor disconnect is indicated downstream of a variable frequency drive (VFD) provide interlock wiring from the auxiliary contacts on the disconnect to the VFD to de-energize when the disconnect is turned "off".

2.3. CONTROLLERS

- A. All global sensors shall be monitored in accessible locations. Exterior sensors shall be provided with sun shield and be installed to prevent bird nesting.

2.4. PRESSURE INDEPENDENT HYDRONIC CONTROL VALVES

- A. All automatic control valves 2 inches and smaller shall be screwed type, and valves 2 ½ inches and larger shall be flanged. Valves shall be factory-rated to withstand the pressures encountered. Valves shall have stainless-steel stems and spring loaded Teflon packing with replaceable seats and discs. All control valves must be capable of withstanding the shut-off head of the pumps, they are connected to without the valve seat lifting. Valves shall have stainless steel stems and spring loaded Teflon packing with replaceable seats and discs.
1. All modulating straight-through water valves shall be provided with equal-percentage contoured throttling plugs and shall be pressure independent type. All three-way valves shall be provided with linear throttling plugs such that the total flow through the valve shall remain constant regardless of the valve's position modulating. Valves shall be sized for a pressure drop equal to the coil they serve but not to exceed 5 psi. Valves shall have replaceable seats and discs. Pressure independent control valves shall be as manufactured by Griswold, Delta P, Warren Controls, Danfos, Bray, or approved equal.
 2. Pressure Independent Actuated Ball Valves (PIC-V) for Flows up to 85 GPM
 - a. The modulating control valves shall be pressure independent.
 - b. Valves shall accurately control flow within +/-5% (including manufacturing tolerance) independent of system pressure fluctuation by maintaining a constant pressure differential across the control valve so that the valve only repositions on a change in load demand.
 - c. The pressure independent modulating control valve shall include a Pressure Compensating Cartridge, Actuated Ball Valve, 2 PT's, Manual Air Vent, Union, and Manual Isolation Ball in a single valve housing.
 - d. The valve shall have an accuracy of +/- 5% including manufacturing tolerances and pressure variations.
 - e. Valve housing shall consist of forged brass, rated at no less than 360 psi at 250°F.
 - f. A venturi flow meter fitting shall be field installed so that the flow rate can be read by means of differential pressure. Venturi metering station shall not require any straight runs of piping before or after meter.
 - g. Both the ATC and shutoff valve shall have stems that are field repairable with the valve in the line. The body design shall allow inspection or repair of the stem without disturbing piping connections or draining water. The repairable stem shall include two Teflon seals and one EPDM O-ring for protection against chemicals and modulating temperature.
 - h. Valve shall have a union end connection with factory installed air vent to allow for venting of the coil or heat pump.
 - i. The control valve shall accurately control the flow from 0 to 100% full rated flow.
 - j. The ATC portion of the valve shall use the full 90 degrees of the stroke for control. Stroke limiting of the valve shall not be acceptable.
 - k. A flow tag shall be furnished with each valve.
 - l. A universal mounting plate shall allow installation of actuators meeting the system electrical requirements and valve torque requirements as provided by Honeywell, Invensys, Johnson Controls, KMC, Schneider,

- Neptronic, or Siemens.
- m. The actuator and plate can be rotated after mounting.
- n. The actuator mounting assembly shall accommodate no less than 1 ½" of insulation.
- o. Pressure Compensating Cartridge (PCC)
 - i. PCC shall automatically compensate for pressure changes in valve and shall maintain a constant pressure drop across the flow limiting actuated ball.
 - ii. The operating pressure range shall be available with the minimum range requiring 3 PSID to actuate the cartridge and the maximum 8 psid to actuate the cartridge
 - iii. Valve internal control mechanism includes a diaphragm and full travel linear coil spring.
 - iv. Valves shall include an accessible/ replaceable cartridge.
 - v. Dual pressure/temperature test valves for verifying the pressure differential across the cartridge and flow limiting ball shall be standard.
- p. Actuated Ball Valve
 - i. Valve ball shall consist of chemically plated nickel brass or stainless steel.
 - ii. Actuator stem shall be removable/ replaceable without removing valve from line.
 - iii. Manufacturer shall be able to provide ball insert to limit flow to maximum flow rate with $\pm 5\%$ accuracy. Insert shall be constructed of a Glass-Filled Polymer. The insert shall be press fit to the inside of the ball. Clipping the insert onto the exiting side of the ball shall not be acceptable.
 - iv. Each maximum flow rate selected shall use a different characterizing disc so that stroke limiting is not required.
 - v. Valve shall have a minimum rangeability as follows: ½"-40:1, ¾"-160:1, 1" to 3"-400:1
 - vi. Valve shall have EPDM O-rings behind Reinforced Teflon (PTFE) ball seals.
 - vii. The valve shall have a minimum close-off pressure differential rating of 100 psi with 35 in-lbs of torque for 1/2" to 2" sizes.
 - viii. Actuator shall provide minimum torque required for full valve shutoff position.
- q. Isolation Ball Valve
 - i. Valve shall include a 600 WOG manual isolation ball valve.
 - ii. Stem shall be removable/replaceable with the valve in the line.
- r. The control valve actuator will be furnished by the controls contractor under Section 230900.
- s. Pressure independent valves shall come as one complete assembly from Griswold Controls or approved equal and shall include a supply side combination shutoff/ strainer valve.

3. MVP Pressure Independent Control Valves for Flows above 85 GPM.

- a. Pressure Independent Flow Control Valve 2.5" and Larger
 - i. The modulating control valves shall be pressure independent.
 - ii. Valve shall accurately control flow within $\pm 5\%$ (including

- manufacturing tolerance) independent of system pressure fluctuation by maintaining a constant pressure differential across the control valve so that the valve only repositions on a change in load demand.
- iii. Contactor shall install pressure independent flow control valves where indicated in drawings.
- iv. Valve shall be electronic, pressure independent, modulating 2-way control device.
- v. Balancing valves shall not be required where pressure-independent valves are installed.
- vi. Install flow meter fitting to measure flow rate in gallons per minute.
- b. Valve Actuator
 - i. Valve actuator housing shall be rated to IP44 insulation.
 - ii. Actuator shall be driven by a 24Vdc motor, and shall accept 2-10 Vdc, 4-20mA, 3-point floating or pulse width modulation electric signal and shall include resistor to facilitate any of these signals.
 - iii. Actuator shall be capable of providing 4-20mA or 2-10 Vdc feedback signal to the control system so that the gpm can be determined.
 - iv. External LED readout of current valve position and maximum valve position setting shall be standard.
 - v. Maximum flow setting shall be adjustable to 51 different settings within the range of the valve size by changing the settings electronically on the actuator.
 - vi. Optional fail safe system to power valve to either open or closed position from any position in case of power failure shall be provided per the sequence of operations and the automatic temperature control diagrams.
- c. Valve Housing
 - i. 2.5"–6": Housing shall be constructed of Ductile Iron ASTM A536-65T, Class 60-45-18 rated at no less than 580 psi static pressure and 248°C.
- d. Pressure Regulation Unit
 - i. Pressure regulation unit shall consist of 304 Stainless Steel and hydrogenated acrylonitrile butadiene rubber (1/2"–1-1/2") or 316 Stainless Steel and EPDM (2"–6").
 - ii. Flow regulation unit shall be accessible for maintenance without disturbing the piping.
 - iii. Valve shall have a maximum of 8.6 psid to actuate the pressure regulating cartridge.
 - iv. Dual pressure/temperature test valves for verifying accuracy of flow performance shall be available for all valve sizes.
- 4. Optional accessories shall include a stem packing lubricator for factory or field assembly. Valve stem packing shall be low friction, tight sealing Teflon.
- 5. Unitary valves shall be straight-through or three way type as specified in the sequence of operation with high-pressure connections suitable for copper pipe and rated for 250 psig. Stems shall be polished stainless-steel and packing shall be ethylene-propylene suitable for both chilled water and 250 degree hot water

service. Straight-through valves shall have back-seating feature, to allow packing to be replaced without draining system.

6. All valves shall use guided valve plugs for good seating and reliable operation. Valves ½ inch to 1 inch shall be ANSI Class 125 brass body with screwed ends. Valves 1-1/4 inches to 2 inches shall be ANSI Class 150 brass body with screwed ends. Valves 2-1/2 inches to 4 inches shall be Class 125 cast iron body with bronze trim and flanged ends. Valves 6 inches and larger shall be Class 125 steel body with bronze trim and flanged ends. Butterfly valves shall be DeZurick HIGH performance or Keystone Keylock, Lug style as specified in Division 23 Section, HVAC Piping, Fittings, and Valves.

B. Control Valve Operators

1. Electric valve actuators shall be properly sized to provide sufficient torque to position valves throughout its operating range.
2. Use devices which are quiet in operation and which in the event of power failure, will "fail safe" by spring action in either the normally open or normally closed position as required for freeze, moisture, smoke, or fire protection. Spring return valves are required for all control valves where coils are exposed to outside air conditions.
3. Electric actuators requiring a 24VAC power supply will be utilized. Motors shall be specifically designed and sized with proper torque according to requirements of the device it is to be used on (i.e.: valve, damper). Each actuator will accept the proper control input as the system is designed, (i.e.: floating, 0-10VDC, 4-10Ma etc.) without the need for any additional interface devices.

2.5. CONTROL PANELS

- A.** Furnish and install local panels for ATC devices. Control panels shall be fully enclosed cabinets, all steel construction and shall meet the requirements of NEMA 1 enclosures. Cabinet shall have piano hinged door with a locking latch. All cabinet locks shall use common key. Provide means of storing control system instructions and drawings inside cabinet for future reference. Panel shall be wall mounted or free standing and located where directed by the Contract Drawings or Engineer.

1. Each panel shall have all internal devices factory wired to a numbered terminal strip. Controllers and associated devices shall be mounted within the panel, accessible through a hinged door.
2. All ATC panels shall be provided with integral disconnect, wiring, and control transformers.
3. Any ATC control panel that is serving equipment on the emergency generator must be powered by an emergency generator fed circuit/electrical panel. Refer to electrical contract documents for all emergency powered equipment.

2.6. MISCELLANEOUS ELECTRICAL DEVICES

- A. Electric Actuators. All automatically controlled devices, unless specified otherwise elsewhere, shall be provided with electric actuators which shall be sized to operate their appropriate loads with sufficient reserve power to provide smooth modulating action or two-position action and tight close off as specified.
- B. Aquastats shall be line voltage strap on type with single pole, single throw switching. Switches shall have an adequate rating for the applied load. All wiring from aquastats to domestic recirculating pumps shall be by ATC contractor.

2.7. UNINTERRUPTIBLE POWER SUPPLY

- A. Furnish, size and install uninterruptible power supplies (UPS's) at all ATC panels.
- B. Provide all interlock and power wiring from U.P.S. to control panels as required such that all components are powered via the UPS. For hard-wired equipment furnished with pigtails/wire leads, e.g. control power transformers, splice pigtails/wire leads in junction box to a flexible cord with NEMA 5-15P Plug, which shall be plugged into the UPS.
- C. UPS's shall be sized for the ATC panel load and shall provide at least 10 minutes of full load power in the event of a power outage.
- D. UPS shall be furnished with plug and cord and shall be powered from power receptacle(s) in ATC panels.

2.8. DESKTOP WORKSTATIONS

- A. Description: A tower or all-in-one computer designed for normal use at a single, semipermanent location.
- B. Performance Requirements:
 - 1. Performance requirements may dictate equipment exceeding minimum requirements indicated.
 - 2. Energy Star compliant.
- C. Personal Computer:
 - 1. Minimum Processor Speed: 3 gigahertz (GHz).
 - 2. RAM:
 - a. Capacity: 16GB.
 - b. Speed and Type: 1333 MHz, SDRAM.
 - 3. Hard Drive:
 - a. Media: Solid state.
 - b. Number of Hard Drives: One.
 - c. Capacity: 250GB.
 - 4. Optical Read and Write Drive:

- a. Include with at least 2 MB of data buffer.
 - b. Type: SCSI CD-ROM Drive with Read/Write Capability.
 - c. Average access time of 150 ms or less.
- 5. At least four expansion slots.
- 6. Video Card:
 - a. Resolution: 1920 by 1200 pixels.
 - b. RAM: 4 GB.
 - c. Controller Speed: 4GHz.
- 7. Sound Card:
 - a. At least 128 voice wavetable synthesis.
 - b. Capable of delivering three-dimensional sound effects.
 - c. High-resolution 16-bit stereo digital audio recording and playback with user-selectable sample rates up to 48,000 Hz.
- 8. Two (2) Network Interface Cards: Include cards with connection, as applicable.
 - a. 10-100-1000 base TX Ethernet with RJ45 connector port.
 - b. 100 base FX Ethernet with SC or ST port.
- D. Wireless Ethernet, 802.11 a/b/g/n.
 - 1. Optical Modem: Full duplex link for connection to optical fiber cable provided.
 - 2. I/O Ports:
 - a. Two USB 3.0 ports on front panel, six on back panel, and three internal on motherboard.
 - b. One serial port.
 - c. One parallel port.
 - d. Two PS/2 ports.
 - e. One RJ-45.
 - f. One stereo line-in and headphone/line-out on back panel.
 - g. One microphone and headphone connector on front panel.
 - h. One IEEE 1394 on front and back panel with PCI-e card.
 - i. One ESATA port on back panel.
 - 3. Battery: Life of at least three years to maintain system clock/calendar and ROM, as a minimum.
- E. Keyboard:
 - 1. 101 enhanced keyboard.
 - 2. Full upper- and lowercase ASCII keyset, numeric keypad, dedicated cursor control keypad, and 12 programmable function keys.
 - 3. Wireless operation within up to 72 inches (1800 mm) in front of workstation.

F. Pointing Device:

1. Either a two- or three-button mouse.
2. Wireless operation within up to 72 inches (1800 mm) in front of workstation.

G. Flat Panel Display Monitor:

1. Display:
 - a. Color display with 21 inches diagonal viewable area.
 - b. Digital input signal.
 - c. Aspect Ratio: 16 to 9.
 - d. Antiglare display.
 - e. Tilt adjustable base.
 - f. Energy Star compliant.
 - g. Resolution: 1920 by 1200 pixels at 60 Hz.
 - h. Number of Displays: One.

H. Speakers:

1. Two, with individual controls for volume, bass and treble.
2. Signal to Noise Ratio: At least 65 dB.
3. Power: At least 4 W per speaker/channel.
4. Magnetic shielding to prevent distortion on the video monitor.

I. I/O Cabling: Include applicable cabling to connect I/O devices.

2.9. CENTRAL CONTROL AND MONITORING SYSTEM (CCMS) (HARDWARE DESCRIPTION)

A. General

1. The Facilities Management Control System (FMCS) shall be comprised of a network of various independent, Stand-alone Digital Controllers (SDC'S), Mechanical System Digital Controllers (MSDC's), Unitary Digital Controllers (UDC's); together with Centralized Control Stations (CCS), and Centralized Host Stations (CHS) as specified, to provide centralized access and facility wide control functions. The SDC's, MSDC's, AHDC's, and UDC's shall be interconnected in a communicating network to provide facility wide access and sharing of information. A Gateway Digital Controller (GDC's) shall be provided to allow interface with third party microprocessor based control systems that are specified for integration within specification. A Local Area Network (LAN) shall be provided to interconnect SDC's for high-speed data transmission.

2. Specification Nomenclature

a.	FMCS	Facility Management Control System
b.	SDC	Stand-alone Digital Controller

c.	MSDC	Mechanical System Digital Controller
d.	UDC	Unitary Digital Controller
e.	GDC	Gateway Digital Controller
f.	GP	Graphical Programmer
g.	CHS	Central Host Station
h.	CCS	Central Control Station
i.	RPTR	Communications Repeater

B. Centralized Host Stations (CHS)

1. The FMCS shall include Centralized Host Stations. CHS's shall, in conjunction with the full compliment of Digital Controllers, provide the performance requirements within this specification. Each CHS shall include all hardware and software components to serve as a centralized facility operator station, providing color graphics, facility wide access, operator initiation of global control strategies, and centralized documentation.

The CHS shall be capable of simultaneously interfacing with the following:

- a. -mouse pointing device
- b. -two parallel printers
- c. -high resolution VGA color graphics monitor
- d. -seven auto answer/auto dial modems
- e. -color inkjet printer
- f. -two serial printers
- g. -three FMCS LAN interface
- h. -Alarm Graphic and Report FAX dial out service interface
- i. -Mass storage tape system

As a minimum, the temperature control contractor shall provide the types and quantities of CHS, CCS, SDC, MSDC, GDC and UDC as required.

2. Computer

- a. The existing FMS computer located in the Indian River School District's Central Maintenance Office shall be utilized with the new CCMS System. Provide modem terminal, and wiring as required to interface this school's CCMS system with FMS computer. I/P data drop shall be provided adjacent to the network panels.
- b. Coordinate IP address with Owners' I.T. Department for network connection. The CCMS must be fully networkable.
- c. Provide fiber optic cable as required.

3. Operator Workstation: One PC-based microcomputer with minimum configuration as follows:

- a. Uninterruptible Power Supply: 2 kVa.
- b. Operating System: Microsoft Windows – Latest Version.
 - i. ASHRAE 135 Compliance: Workstation shall use ASHRAE 135 protocol and communicate using ISO 8802-3 (Ethernet) datalink/physical layer protocol.

- ii. LonWorks Compliance: Control units shall use LonTalk protocol and communicate using EIA/CEA 709.1 datalink/physical layer protocol.
- c. Printer: Color, ink-jet type as follows:
 - i. Print Head: 4800 x 1200 dpi optimized color resolution.
 - ii. Paper Handling: Minimum of 100 sheets.
 - iii. Print Speed: Minimum of 17 ppm in black and 12 ppm in color.

C. Centralized Control Stations (CCS)

- 1. The FMCS shall include Centralized Control Stations, as required. CCS's shall, in conjunction with the network of SDC's and additional CCS components as required, provide the performance requirements within this section of the specification. Each CCS shall include all hardware and software components to serve as a centralized facility operator station, providing facility wide access, for review and modification of global control strategies, real time system monitoring, controller database editing or creation, and centralized documentation.

D. Local Area Networks

- 1. The LAN shall utilize packetized transmissions, CRC 16 error checking, and distributed error recovery. Single or multiple SDC failures shall not cause loss of communication between other LAN-connected SDC's.
 - 2. LAN connected SDC's shall be provided with a communications watchdog to assure that an individual SDC cannot permanently occupy the LAN. If an SDC is determined to be monopolizing communications, it shall be automatically shut down and an exception reported to annunciate this fact.
 - 3. The LAN shall employ a token passing, peer-to-peer convention, same as or similar to the industry standard format IEEE 802.4. The content of messages shall be the manufacturer's standard. The Local Area Network components shall be manufacturer's standard or available from third party vendors which utilize the same chip implementation as used by the manufacturer.
 - 4. Industry standard ANSI, RS-485 Network Communication System, Lon, or Bacnet, or Equivalent shall be utilized.
 - 5. Trunk Wiring Practices - General
 - a. The distributed communication network system shall consist of a multi-drop RS-485 bus architecture connecting SDC's, MSDC's, GDC's, and UDC's. The trunk shall consist of:
 - i. A twisted pair of wires (24 awg) completely encased in continuous metallic conduit.
 - ii. A twisted shielded pair of wires (24awg) with the shield grounded in accordance with the manufacturer's wiring practices.
 - iii. Or a dual channel, 62.5 micron fiber cabling system with ST type connectors.
- There shall be no power wiring, in excess of 30 VAC rms voltage, run in conduit with communications trunk wiring. In cases where power or signal

wiring is run in conduit with trunk wiring, all communications trunk wiring and power wiring shall be run using separate twisted shielded pairs (24awg) with the shields grounded in accordance with the manufacturer's wiring practices.

b. Communication Transient Protection

i. The manufacturer's catalog data sheet shall provide evidence that all FMCS products offered by the manufacturer are tested and comply with the standard for Transient Surge withstand capabilities for electrical devices ANSI C62.41, IEEE-587-1980, Categories A and B. Such testing shall have included power and communication trunk wiring. Compliance with IEEE-587 shall imply conformance with IEEE-472 transient standards based on the stated position of ANSI and IEEE regarding applicability of the rated standards.

ii. In addition, at each building entry and exit point, the wire communications trunk wiring shall be protected with a transient surge protection device providing the minimal protection specifications of the General semiconductor, Model #422E device. Transient surge protection is not necessary if the communication trunk, external to the building, is fiber optic in nature.

iii. The communications circuitry and input/output circuitry, of the SDC's, and MSDC's shall provide protection against a 1000 volt, 3 amp transient signal, directly applied to the communication or input/output terminations. The manufacturer's catalog data sheet shall provide evidence of conformance with this requirement. Systems not complying with this requirement shall provide equivalent protection external to the FMCS controller. Protection shall be provided for the individual communications and input/output terminations for each FMCS controller. Submittal documentation shall clearly define how this requirement will be met and how the external protection will not affect the performance of the controllers.

c. RS-485 Trunk Distance and Topology

The manufacturer's RS-485 trunk shall provide operation over end to end linear distances of 4000 feet for wire connections and 6,500 feet for fiber optic connections, without repeaters, at communication data rates of up to 64 kbps. The trunk may be extended up to 20,000 feet through the use of wire repeaters or 80,000 feet through the use of fiber optic repeaters.

At data rates of up to 19.2 kbps, the trunk distance shall be extendible to distances of up to 20,000 feet using RS-485 communication wire or fiber optic repeaters. A repeater shall be used each 4,000 feet of linear distance for wire or every 6,500 feet for fiber optics. Repeating devices shall contain separate LED indication for each communication interface trunk to indicate proper operation of the repeater as well as the communications trunks.

Contractors shall provide devices which are of FMCS control system manufacturer's design.

d. It shall be possible for the trunk to be "T" eed or "starred", at any location using a repeater, to facilitate the installation. Systems which do not provide this capability shall provide a trunk riser diagram showing end to end

distances and locations of system topology necessary to meet the trunk diagram shown on the plans.

e. Fiber Optic Communication Trunk

The temperature control contractor shall provide a dual channel fiber optic data link, as required, to minimize the effects of transient surges caused by lightning or external EMI generating equipment. The data link shall be comprised of a single duplex cable containing two fibers (transmit and receive), of 62.5 micron construction, to accommodate data rates of up to 64 kbps.

The fiber optic trunk shall be connected to SDC devices using manufacturer's standard RS-485 to fiber optic data link modem. Repeating devices shall contain separate LED indication for each communication interface and the fiber modem, to indicate proper operation of all aspects of the device. Fiber modem devices shall be tested and conform with transient surge withstand tests for electrical devices, ANSI C62.41 IEEE-587 Categories A and B. Manufacturer's data sheet shall provide evidence of compliance with this requirement. Manufacturer's products which do not meet this minimum performance requirement shall not be acceptable. Systems which require a special gateway controller to accommodate the fiber optic trunks, shall provide such a controller per point where the fiber optic cable enters and leaves the building. Gateway controllers shall not inhibit transfer of point data values between SDC controllers throughout the LAN. Such inhibitive systems shall not be acceptable.

In lieu of the above two options, the contractor may provide a fiber optic link to each SDC controller within the LAN. All controllers shall have access to the fiber optic link for LAN.

Fiber optic cable shall be fully tested and terminated by the temperature control contractor.

E. Standalone Digital Controllers (SDC)

1. General

Standalone Digital Controllers (SDC) shall be 16 bit microcomputer based, utilizing a multi-tasking, multi-user operating system.

The SDC controllers shall permit the simultaneous operation of all control, communication facilities management and operator interface software, as programmed by the Contractor or User. Modification of the on-board SDC controller database shall be performed on-line using the built-in or HHOT interface. Systems which require the SDC to be removed from service while DDC control sequences are modified shall not be acceptable.

SDC controllers shall utilize true floating point arithmetic capabilities. To accommodate totalization of large totalized values, SDC's with reporting capability shall support the calculation, accumulation and display of values within the range of +/-10 to the 10th power.

2. Database and Memory Back-up

All programming defining the functions to be performed by the SDC, including

but not limited to application programs and point database within each SDC, shall be protected from loss due to power failure for a minimum of six months. Systems providing non-volatile memory for these functions are preferred. Systems not providing non-volatile memory shall provide a system rechargeable battery backup system sufficient to provide protection for the specified 6 month period. Systems not in compliance shall provide for uninterrupted power to each SDC.

3. Service Ports

SDC controllers shall be equipped with a minimum of one operator service port for the connection of a HHOT. The service port shall be either a built-in RS-232 data terminal port or an RJ-11 type jack which connects to the manufacturer's standard HHOT.

Connection of a service device, to a service port, shall not cause the SDC controller to lose communications with its peers or other networked device controllers.

The service port shall allow utilization of the same HHOT from any location. The same HHOT shall be utilized for any SDC, MSDC, or UDC Systems which utilize more than one variety of HHOT shall not be acceptable.

4. Display and Readout Capability

The SDC controller shall provide manufacturer's standard display and readout capability.

5. Manual/Auto Control and Notification

The SDC controller shall provide commanded override capability from the HHOT or the built-in operator interface. Such overrides shall be annunciated to the CHS's. Such overrides shall be valid as long as power is applied to the controller.

Manual service overrides, such as Hand/Off/Auto switches, shall be provided as indicated on the drawings. Such overrides shall be located at the controlled device location and conform with OSHA Manual lockout regulations, as appropriate, for safety reasons. SDC indication of such manual override actions shall be provided as feedback status indication points shown on the drawings, in conjunction with the application programs within the SDC. Systems which provide built-in H/O/A switching devices with integral feedback shall provide external manual service overrides, as indicated, to comply with OSHA manual lockout regulations. H/O/A switches remotely located at the SDC controller are not acceptable.

6. Adjustments

Every control panel shall provide adjustments for the functions specified. In general, adjustments shall be provided for all set points used by controllers within each control panel. In addition, adjustments shall be provided for throttling ranges, mixed air damper minimum positions, or other items as specified. Adjustments shall be integral to each individual SDC. The built-in operator interfaces shall allow the easy execution of the adjustment through named identifiers within the SDC. From a single SDC user interface, any other SDC shall be accessible and

full adjustment capabilities shall be provided.

7. Sensing and Control Outputs Requirements

a. Sensing

i. All sensing inputs shall be provided via industry standard signals. Temperatures, humidities, differential pressure signals, and other signal inputs shall be one of the following types:

- 1) 0-20 mA
- 1) 4-20 mA
- 1) 0-5 VDC
- 1) 0-12 VDC

ii. 1000 ohm platinum (at 0°C, 2.62 ohms/°C)

iii. 1000 ohm Balco (2.2 ohms/°F)

iv. 10 k ohm Thermistor (at 25°C/77°F)

Custom, definable input signals (accept sensor inputs from RTD devices, other than those of the manufacturer).

All signal inputs shall be compatible with the controllers used, and with the requirements for readout of variables in true scaled engineering units as specified.

b. Control Outputs

i. On/Off Outputs

Control panel shall internally provide test points for the circuit driving the equipment contactor, for the purpose of troubleshooting the 120 VAC or 240 VAC circuit to the contactor. All such relays or digital output modules shall provide a pilot light or LED display of the same status. On/Off output modules shall be of the modular construction that can be easily and quickly replaced, on an individual basis, if the module were to be damaged.

ii. Modulating Outputs

Modulating outputs shall be industry standard 0-5 VDC, or 0-12 VDC with definable output spans, to adapt to industry available control products. Milliamp outputs of 0-20 mA or 4-20 mA are also acceptable. Drive open/Drive closed type modulating outputs are acceptable provided that they also comply with the following requirements.

All modulating outputs shall provide within the control panel, a meter gauge, or display indication via on board display or HHOT, the commanded position signal for the actuating device. This meter, gauge, or display must provide either a 0-100 percent position indication, or read out directly in the engineering unit of the signal being used. Drive open/Drive closed type controllers shall include sufficient components and control algorithms to comply with this requirement. In the case of Drive open/closed technology, position feedback shall be provided to insure positive indication that the control device is at the commanded position.

F. Mechanical System Digital Controllers (Msdc's)

1. General

a. Controls shall be microprocessor based, Mechanical System Direct Digital Controllers (MSDC's). MSDC's shall be provided for air handling units, central pump systems and other applications as required. MSDC's shall

be based on a minimum 16 bit microprocessor working from software program memory which is physically located in the MSDC. The application control program shall be resident within the same enclosure as the input/output circuitry which translates sensor signals. All input/output signal conversion shall be performed through a minimum of a 12 Bit A to D converter. All input/output points shall be universal in nature allowing their individual function definition to be assigned through the application software. All unused input/output points must be available as universally definable at the owner discretion. If input/output points are not fully universal in nature, unused points must be equal in quantity between Analog Input, Digital Input, Analog Output, Digital Output.

Contractor shall provide a minimum of one MSDC controller per mechanical system, as shown on the drawings.

The BAS contractor shall provide and field install all MSDC's specified under this section. Mechanical Equipment manufacturers desiring to provide MSDC type controls as factory mounted equipment, shall provide a separate bid for their product less all controls, BAS/Temperature Control Contractor.

- b. All input/output signals shall be directly hardwired to the MSDC. Trouble shooting of input/output signals shall be easily executed with a volt-ohm-milli-amp meter (VOMA). As a result of this intent, it is specified that power line carrier systems, or other systems which command multiple outputs over a single pair of wires, shall not be used.
- c. MSDC shall be in continuous direct communication with the network which forms the facility-wide Building Automation System (BAS). The MSDC's shall communicate with the SDC at a baud rate of not less than 19,200 baud.

2. Non-Volatile Memory

- a. All control sequences programmed into the MSDC shall be stored in non-volatile memory, which is not dependent upon the presence of a battery to be retained. Power failures shall not cause the MSDC memory to be lost, nor shall there be any need for batteries to be recharged or replaced to maintain the integrity of the controller database. The MSDC shall allow for the creation of unique application control strategies. Systems that allow selection of sequences from the library or table are not acceptable.
- b. All control sequences shall be fully field programmable at the MSDC controller, allowing for the creation or editing of an application sequence of operations.
- c. Each MSDC shall be provided with manufacturer's standard built-in Operator Interface.
- d. The MSDC shall allow for internal processing and reporting of user defined Time of Day Schedules, Alarms, Trend Reports, Run Time Totalization, Energy Utilization Reports, Application Program Documentation and interface with a peripheral device such as an autodial/autoanswer modem, a VT-100 Display Terminal, or a serial printer.
 - i. Systems not providing the above functionality at the MSDC are not acceptable and shall utilize an SDC in place of the MSDC.
- e. The MSDC shall provide LED indication of transmit/receive

communications performance as well as for the proper/improper operation of the controller itself.

- f. The MSDC shall be provided with a battery backed time clock that is capable of maintaining the time of day and calendar for up to thirty days without loss of setting. The battery for the time clock shall be field replaceable by the customer. Integral daily, weekly, holiday and special event scheduling shall be provided, such that all schedules can be custom tailored to the facility. Predefined schedules, with set quantities of on/off cycles are not acceptable.

3. Controller Location

- a. To simplify controls, mechanical service and troubleshooting, the MSDC shall be mounted directly in or on the control compartment of the mechanical system. The MSDC shall be provided in a NEMA 1 enclosure to accommodate direct mounting on the equipment to be controlled. The MSDC shall be constructed in a modular orientation such that service of the failed components can be performed quickly and easily. The modular construction should limit the quantities of printed circuit boards to a maximum of three. When required to replace a printed circuit board, it shall not be necessary to disconnect any field wiring. The MSDC shall allow for the creation of, unique, application control strategies. Systems that allow selection of sequences from a library or table are not acceptable. This shall allow all controls maintenance and troubleshooting to be made while at the unit location. MSDC shall be directly wired to sensory devices, staging relays or modulating valves for heating and cooling.
- b. For compatibility to the environment of the mechanical systems, MSDC shall have wide ambient ratings. MSDC shall be rated for service from - 40 Deg F (Degrees Fahrenheit) to 140 Deg F.
- c. Contractor shall submit description of location for the MSDC's on all mechanical equipment.

G. Unitary Digital Controller (UDC)

1. General

- a. Controls shall be microprocessor based Unitary Digital Controllers (UDC's). UDC's shall be provided for equipment as necessary. UDC's shall be based on a minimum 16 bit microprocessor working from software program memory which is physically located in the UDC. The application control program shall be resident within the same enclosure as the input/output circuitry which translates the sensor signals. All input/output signal conversion shall be performed through a minimum of a 10 bit A to D converter.

Contractor shall provide a minimum of one UDC controller per unitary system as required.

The BAS contractor shall provide and install all UDC's specified under this section. Mechanical equipment manufacturers desiring to provide UDC type controls as factory mounted equipment, shall provide a separate bid for their products less all controls, actuators, valve assemblies and sensors, which are specified to be provided by the BAS/Temperature

control contractor.

- b. All input/output signals shall be directly hardwired to the UDC. Troubleshooting of input/output signals shall be easily executed with a volt-ohm-milli-amp meter (VOMA). As a result of this intent, it is specified that power line carrier systems, or other systems which command multiple outputs over a single pair of wires, shall not be utilized.
- c. UDC's shall be in continuous, direct communication with the network which forms the facility wide building automation system. The UDC's shall communicate with the SDC at a baud rate of not less than 9,600 baud.

2. Non-Volatile Memory

- a. All control sequences programmed into the UDC shall be stored in non-volatile memory, which is not dependent upon the presence of a battery, to be retained. Power failures shall not cause the UDC memory to be lost, nor shall there be any need for batteries to be recharge or replaced to maintain the integrity of the controller database. The UDC shall allow for the creation of unique application control sequences. Systems that allow only selection of sequences from a library or table are not acceptable.
- b. All control sequences shall be fully configurable at the AHDC, allowing for the creation and change of a sequence while at the unit.
- c. The UDC shall be provided with the ability to interface with the HHOT. The interface port shall be provided at the wall sensor or within the unitary equipment, as specified on the plans. The interface port shall allow the HHOT to have full functionality as described hereinbefore of this specification. From the interface port, the HHOT shall be able to directly access any UDC in the network.
- d. The UDC shall provide an input/output point trending utility that is capable of accumulating 48 analog point samples and 10 digital point samples per Input/Output point. Each sample shall be taken on a user defined interval, ranging from 1 second to 255 hours per sample. The digital readings shall be on a change of state occurrence for the digital points. All samples shall be recorded with the engineering units for the value, along with a time and date identifier for each sample taken. Systems unable to provide the above capability shall provide for the individual input/output point trending at the SDC. Specifics as to how each UDC point will be trended, at the SDC, shall be provided in the submittal documents. Included in the explanation shall be the sample intervals, the memory allocation in the SDC and the number of UDC's per SDC that can be expected.
- e. The UDC shall provide LED indication of transmit/receive communication performance, as well as for the proper/improper operation of the controller itself.

3. Controller Location

- a. To simplify controls and mechanical service troubleshooting, the UDC shall be mounted directly in the controls compartment of the unitary system. The UDC shall be provided with a sheet metal or polymeric enclosure that is constructed of material allowing for the direct mounting within the primary air stream, as defined by UL-465. The direct mounting

shall allow all controls maintenance and troubleshooting to be made while at the unitary equipment. The UDC shall be directly wired to sensory devices, staging relays or modulating valves for heating and cooling.

- b. For compatibility to the environment of the unitary equipment, UDC's shall have wide ambient ratings. UDC's shall be rated for service from 32 Deg F (Degrees Fahrenheit) to 140 Deg F.
- c. Contractor shall submit description of location of UDC's on all mechanical and unitary equipment.

H. Gateway Digital Controller (GDC)

1. General

- a. Controls shall be microprocessor based, Gateway Digital Controllers (GDC's). GDC's shall be provided for the purpose of integrating microprocessor based, communicating, direct digital control systems from vendors other than the primary, selected controls manufacturer. GDC's shall be based on a minimum 16 bit microprocessor working from software program memory which is physically located in the GDC. All communications interface control programs shall be resident within the GDC.

The BAS contractor shall provide and field install all GDC's specified under this section. Any interface requirement beyond a two wire communications wire link, shall be provided by the equipment manufacturer supplying the non-primary or third party microprocessor based, communicating, direct digital controllers.

- b. All GDC's shall exist at the LAN level with the SDC's. The GDC's shall possess all capabilities described under the SDC section while additionally providing the interface to the third party systems described above. The GDC's shall communicate with the third party controllers at the highest possible baud rate offered by the third party system. As a minimum, 9,600 baud communications shall be utilized.
- c. All control sequences programmed into the GDC shall be stored in non-volatile memory, which is not dependent upon the presence of a battery, to be retained. Power failures shall not cause the GDC memory to be lost, nor shall there be any need for batteries to be recharged or replaced to maintain the integrity of the controller database. The GDC shall allow the standard database information from the third party system to be integrated in standard FMCS data formats, allowing for the creation of unique application control sequences. Systems that only allow selection of data and sequences from a library or table, are not acceptable.
- d. Each GDC shall be provided with manufacturer's standard built-in operator interface.

The GDC shall provide Alarming, point trending and Energy report generation capabilities. Alarming points shall be uniquely definable, with multiple alarms assignable to a single point. Such alarm shall be provided with a unique 80 character message. Systems utilizing an alarm message library, shall describe the size of the library and verify how all alarming within the GDC will be guaranteed unique 80 character messages.

The quantities of trended point values shall be limited only by total controller memory space. If necessary, a GDC may be dedicated fully to

a trending task, allowing all controller memory to be available for the trend storage. Each unique trend report shall contain a minimum of 4 different points and a minimum of 128 samples per point. Trending frequency for each report shall be operator definable from a sample once a second to a sample once every 24 hours. Trend reports shall be internally formatted by the GDC and shall be reportable directly to a serial printer, a VT-100 display terminal, a CCS, CHS or any other device capable of receiving a formatted ASCII data file.

- e. The energy reports shall not be limited in quantities only by available memory within the GDC. Each Energy Report shall be fully formatted and reportable to a serial printer, a VT-100 display terminal, a CCS, a CHS or any other device capable of receiving a formatted ASCII data file. As a minimum, each Energy Report shall provide a daily report and a monthly report with summary information such as outside air temperature, outside air humidity, total energy consumed and degree day calculations.
- f. The GDC shall be provided with a battery backed clock that is capable of maintaining the time of day and calendar for up to thirty days, upon loss of power to the GDC, without loss of setting. The battery for the time clock shall be field replaceable by the customer.

2.10. SYSTEM SOFTWARE DESCRIPTION

A. General

- 1. Contractor shall provide all software for a complete and operational system as described herein. Software shall include manufacturer's standard multi-tasking, multi-user operating system for operator consoles and controllers, network communication software for dial-up and hard trunk applications, operator man-machine interface software, control application software and all other software necessary to provide the functions specified herein.
- 2. System software shall be as manufactured by Johnson Controls FX or Trane.

2.11. EXCEPTION REPORTING SEQUENCES

A. Alarm/COS Reports

- 1. For those digital points indicated on the drawings, the Contractor shall provide a unique change-of-state alarm message of up to 70 characters. The message shall report to all devices assigned to the alarm class.
- 2. For those points indicated on the drawings which are designated as interrupt priority, the Contractor shall provide an interrupting process display at the CHS location which displays the current conditions for the operator.

In addition, the CHS computer shall automatically send a picture of the process graphic display to the remote locations via e-mail.

- 3. For those points designated in paragraph 3 above, the FMCS shall also send a history log to the system report printer of the immediate prior history of the points causing the interrupt priority. This log shall contain 1 minute samples of the

previous 15 minutes of operation.

4. For those points on the drawings designed as Hard Facts points, the Contractor shall provide an alarm message to a remote facsimile location designated by the Owner. The FMCS system shall provide at the remote location, a facsimile print-out showing location, time/date of alarm and alarm message of the point. For interrupt priority fax alarms, the remote facsimile machine shall receive a hard copy of the interrupt process screen showing on-line dynamic data values of the current conditions.

B. Off Hours Exception Reporting

1. The Owner shall specify up to five sites to which off hours exceptions shall be auto-dialed and reported. This shall allow the owner to assign off hours exception responses to various facility personnel as necessary. Selection of the site to be dialed can be programmed by the Owner, and set to change automatically per time of day and day of week.

2.12. MONITORING SYSTEM, SENSORS AND WIRING

A. Sensors and other Devices for Input/Output Summary Schedule:

1. Provide all necessary sensors, relays, panels, conduits and wire for the points indicated in the input/output summary as shown on the contract drawings.
2. Analog sensing elements for remote indication shall be independent of local sensors used for local control loops.
3. Temperature sensors shall be Resistance Temperature Detector (RTD) type of 1000 ohm balco. Space (60-90 degrees F); Duct/Well (-30-250 degrees F); Averaging Duct (-30-225 degrees F) or as required under Division 26.
 - a. Space temperature sensors shall be provided with blank commercial type locking satin chrome covers.
4. Relative humidity sensors shall be capacitance type with 10 percent to 90 percent range. Duct mounted relative humidity sensors shall be provided with a sampling chamber. Wall mounted sensors shall be provided with covers identical to temperature sensors. Space 10 percent -90 percent RH; Duct 10 percent - 90 percent RH.
5. All wall mounted temperature sensors and relative humidity sensors shall be installed with stainless steel wire guard. Set point adjustment shall be achievable without removing the wire guard.
6. Differential and Static Pressure Sensors and Switches
 - a. Fan proof-of-flow switches shall be U.L. listed adjustable set point and differential pressure type. Switches shall be piped to fan discharge except where fans operate at less than one inch WG, they shall be piped across the fan. For fractional horsepower and non-ducted fans, relays or auxiliary

- contacts may be used. Maximum pressure rating shall be at least 10 inches WG. with .05-12 inch W.C. range.
- b. Pump proof-of-flow switches shall be U.L. listed adjustable differential pressure or flow type as specified in the sequence of operation or data point summary. Devices shall be 150 psi rated except chilled water flow switches shall be provided with totally sealed vapor tight switch enclosure on 300 psi body. Differential pressure switches shall have valved manifold for servicing, and a range of 3 psi-150 psi.
 - c. Air flow and static pressure analog sensors shall be high accuracy suitable for the low velocity pressures to be encountered, be selected for approximately 50 percent overrange, and have a 4 to 20 ma output. These differential pressure sensors shall be connected to the air flow measuring station with valved lines for testing and calibration, and shall have adjustments for zero and span. 5 inch W.C. range.
 - d. Water flow analog sensors shall be provided complete with flow element and shall be an all solid state precision industrial type with stainless steel meter body, maximum error of no more than .5 percent or span, and 4 to 20 ma output. Sensor shall be rated for 250 psi minimum and installed in strict accordance to the manufacturer's instructions complete with three-valve manifold for calibration and maintenance.
7. Overall system accuracy, including electronic analog sensing elements, shall be as follows:
- a. Air: Plus or minus 1.0 degrees F temperature, plus or minus 2.5 percent r.h., plus or minus 2.0 percent static pressure.
 - b. Water: Plus or minus 0.7 degrees F over full scale range for water points, plus or minus 1.0 degree F for others.
 - c. Proof of fan or pumps operating status, or alarm conditions shall be through positive feedback from differential pressure switches across fan or pump. Auxiliary dry contacts may be used for proof of fans or pumps if the motors are fractional H.P., and other non-ducted fans.
8. Digital inputs from devices with isolated, dry type contacts (no grounds, no voltage) of either normally open (N.O.) or normally closed (N.C.) configuration shall be provided. Live contact inputs, those that have voltage present, shall be provided with isolating devices to meet dry contact requirements.
9. Liquid flow data shall be received and transmitted by commercial grade instrument similar in quality to Honeywell 411, Rosemount, Foxboro, MAMAC Systems or approved equal, type differential pressure transmitter. Pulse type data sensors shall not be acceptable. Speed response of differential pressure transmitters shall be at least 500 milliseconds. Maximum error signal shall be +/- 1 foot.
10. Start-stop relay module shall contain relays for start-stop function at the remote point, with relays mounted and factory wired to numbered terminal strips.
11. Outage Devices:
- a. Control Relays: Control relay contacts shall be rated for the application, with a minimum of two sets of Form C contacts, enclosed in a dustproof

enclosure. Relays shall have silver-cadmium contacts with a minimum life-span rating of one million operations. Operating time shall be 20 milliseconds or less, with release time of 10 milliseconds or less. Relays shall be equipped with coil transient suppression limiting transients to nondamaging levels.

- b. Time Delay Relays: Time delay relay contacts shall be rated for the application with a minimum of two sets of Form C contacts enclosed in a dustproof enclosure. Relays shall have silver-cadmium contacts with a minimum life span rating of one million operations. Relays shall be equipped with coil transient suppression devices to limit transients to nondamaging levels. Delays contact opening or closing shall be adjustable from one to 60 seconds with a minimum accuracy of plus or minus 2 percent of setting.
- c. Latching Relays: Latching relay contacts shall be rated for the application with a minimum of two sets of Form C contacts enclosed in a dustproof enclosure. Relays shall have silver-cadmium contacts with a minimum life-span rating of one million operations. Operating time shall be 20 milliseconds or less, with release time of 10 milliseconds or less. Relays shall be equipped with coil transient suppression devices to limit transients to nondamaging levels.
- d. Reed Relays: Reed relays shall be encapsulated in a glass-type container housed in a plastic or epoxy case. Contacts shall be rated for the application. Operating and release times shall be one millisecond or less. Reed relays shall have a minimum life span rating of 10 million operations.
- e. Contactors: Contactors shall be of the single-coil, electrically operated, mechanically held type. Positive locking shall be obtained without the use of hooks, latches, or semi-permanent magnets. Contacts shall be double-break silver-to-silver type protected by arcing contacts. Number of contacts and ratings shall be selected for the application. Operating and release times shall be 100 milliseconds or less. Contactors shall be equipped with coil transient suppression devices to limit transients to nondamaging levels.
- f. Solid-State Relays: Input-output isolation shall be greater than 1000 megohms with a breakdown voltage of 1500 V rms or greater at 60 Hz. The contact life shall be 10 million operations or greater. The ambient temperature range shall be minus 20 degrees to plus 140 degrees F. Input impedance shall not be less than 500 ohms. Relays shall be rated for the application. Operating and release times shall be one millisecond or less. Transient suppression shall be provided as an integral part of the relay to limit transients to nondamaging levels.

12. Audible Alarm:

- a. All alarms shall annunciate on the ATC system front end computer and via pagers.

2.13. MAKE-UP WATER FLOW METER/ALARM

- A. In-line T-mounted Flowmeter: Made for installation between pipe flanges; measures flow directly in gallons per minute. As manufactured by Aaliant, Badger, Hersey, Kele, Data Industrial or approved equal.

1. Construction: Stainless steel body, with integral transmitter and direct - reading scale.
 2. Pressure rating: 400 psig maximum.
 3. Temperature Rating: 221 F maximum
 4. Display: Two lines; alphanumeric characteristic each. Visual instantaneous rate of flow, with register to indicate total volume in gallons.
 5. Output: Two simultaneous outputs; 4 to 20 mA, two-wire, pulse.
 6. Transmitter: Universal flow transmitter with pulse output (totalization) to convert digital pulses to totalized gallons.
 7. Electronic Housing: NEMA4, 3/4 NPT conduit connection, epoxy coated aluminum.
 8. Accuracy: Plus or minus 1 percent of reading.
 9. Key Pad: Setting of recalibration, engineering units, data logging sample time, alarms, response time.
- B. Power and control wiring to be furnished and installed under this Section of Division 23.

2.14. FLOW MEASURING STATIONS

- A. Furnish and install an Onicon Model F-1210, Hersey, Kobold or approved equal dual turbine insertion flow sensor complete with hot tap full port ball valve and installation hardware. The dual turbine element shall have counter rotating axial turbine elements, each with its own rotational sensing system, and an averaging circuit to reduce measurement errors due to swirl and flow profile distortion. Paddle type rotors will not be acceptable. Rotational sensing of each turbine shall be accomplished electronically by sensing impedance change and not with magnetic or photo-electric means. Each sensor shall be individually calibrated and tagged accordingly against the manufacturers primary standards which must be accurate to within 0.1 percent and traceable to the U.S. National Institute of Standards and Technology (NIST).
- B. The sensor shall have a maximum operating pressure of 400 PSI, maximum operating temperature of 220 degrees F (optional 300 degrees F) and a pressure drop of less than 1 PSI at 17 feet per second flow rate. Flow sensor shall have 100:1 turndown ratio. Accuracy shall be + 2 percent of actual reading from 0.4 feet per second to 20.0 feet per second.
- C. The sensor shall have integral analog outputs of 0-10 VDC and 4-20 mA current output for connection to the Central Control System. The sensor shall also include three integral frequency outputs, (top turbine, bottom turbine, average frequency) for diagnostic purposes and for connection to peripheral equipment (local display, BTU meter, etc.). All outputs shall be linear with flow rate.
- D. The turbine elements shall be made of polypropylene with sapphire jewel bearings and tungsten carbide shafts. The flow sensor shall be constructed of 316 stainless steel with an

aluminum electronics enclosure and gasketed cover.

- E. Install flow measuring stations with minimum straight lengths of pipe upstream and downstream from sensor as prescribed by manufacturer's written instructions.
- F. Make electrical connections to power supply and interlock with ATC system.
- G. Calibrate meters per manufacturer's requirements.

2.15. WATER METER

- A. A water meter shall be provided and installed under Division 23 Section, "HVAC Equipment". Water meters shall be installed on the makeup water lines at all cooling towers and closed circuit evaporative fluid coolers. Refer to drawing for type and location. The ATC contractor shall provide all necessary wiring, relays, terminations, etc., as required to interlock water meters with ATC system and water chemical treatment system control panels. Coordinate with water treatment Contractor. Flow rate and volume shall be reported on ATC central computer.
- B. Trend hourly, daily, monthly, and yearly water use (in gallons) and forward to Engineer for one year. Create graphic on ATC system.

PART 3. EXECUTION

3.1. GENERAL

- A. The Automatic Temperature Control System and Central Control and Management System, shall be designed, installed, and commissioned in a turnkey fully implemented and operational manner.

3.2. BMS SPECIFIC REQUIREMENTS

- A. Graphic Displays
 - 1. Provide a color graphic system flow diagram display for each new and where indicated existing system with all points as indicated on the point list. All terminal unit graphic displays shall be from a standard design library.
 - 2. User shall access the various system schematics via a graphical penetration scheme and/or menu selection.
- B. Custom Reports:
 - 1. Provide custom reports as required for this project:

3.3. WORKSTATION INSTALLATION

- A. Desktop Workstations Installation:
 - 1. Install workstation(s) at location(s) directed by Owner.
 - 2. Install multiple-receptacle power strip with cord for use in connecting multiple

workstation components to a single duplex electrical power receptacle.

3. Install software on workstation(s) and verify software functions properly.
4. Develop Project-specific graphics, trends, reports, logs and historical database.
5. Power each workstation through a dedicated UPS unit. Locate UPS adjacent to workstation.

B. Portable Workstations Installation:

1. Turn over portable workstations to Owner at Substantial Completion.
2. Install software on workstation(s) and verify software functions properly.

C. Color Graphics Application:

1. Use system schematics indicated as starting point to create graphics.
2. Develop Project-specific library of symbols for representing system equipment and products.
3. Incorporate digital images of Project-completed installation into graphics where beneficial to enhance effect.
4. Submit sketch of graphic layout with description of all text for each graphic for Owner's review before creating graphic using graphics software.
5. Seek Owner input in graphics development once using graphics software.
6. Final editing shall be done on-site with Owner's review and feedback.
7. Refine graphics as necessary for Owner acceptance.
8. On receiving Owner acceptance, print a hard copy for inclusion in operation and maintenance manual. Prepare a scanned copy PDF file of each graphic and include with softcopy of DDC system operation and maintenance manual.

3.4. INSTALLATION & SUPERVISION

- A. All wiring shall be properly supported and run in a neat and workmanlike manner. All wiring exposed and in equipment rooms shall run parallel to or at right angles to the building structure. All piping and wiring within enclosures shall be neatly bundled and anchored to prevent restriction to devices and terminals.
- B. The control contractor shall be responsible for all electrical installation required for a fully functional control and automation system and not shown on the electrical plans or required by the electrical specifications. All wiring shall be in accordance to all local and national codes.
 1. All line voltage wiring, all wiring exposed, and all wiring in equipment rooms shall be installed in conduit in accordance to the electrical specifications.

2. All electric and electronic wiring shall be minimum #20 AWG minimum THHN and shielded if required.
3. All wiring in the central control room shall be concealed in an approved manner.
- C. Verify locations of temperature sensors, relative humidity sensors, and other exposed control sensors with plans and Owner prior to installation.
- D. The installation and supervision of this project shall be carried out by factory trained personnel who are employed by the Contractor and licensed for this type of work.
- E. Install control units and other hardware in position on permanent walls where not subject to excessive vibration.
- F. Install software in control units and in operator work station. Implement all features of programs to specified requirements and appropriate to sequence of operation.
- G. Install in accordance with manufacturer's instructions.
- H. Check and verify location of temperature sensors, relative humidity sensors, and other exposed control sensors with plans and room details before installation. Align with lighting switches and humidistats.
- I. Mount freeze protection thermostats using flanges and element holders.
- J. Mount outdoor reset thermostats and outdoor sensors indoors, with sensing elements outdoors with sun shield.
- K. Provide separable sockets for liquids and flanges for air bulb elements.
- L. Mount control panels adjacent to associated equipment on vibration free walls or free standing angle iron supports. One cabinet may accommodate more than one system in same equipment room. Provide engraved plastic nameplates for instruments and controls inside cabinet and engraved plastic nameplates on cabinet face.
- M. Install equipment plumb and level.
- N. Install all equipment to be accessible for service and maintenance.

3.5. ACCEPTANCE TESTING

A. Point Verification

To verify end-to-end operation of the system the Contractor shall provide a hard copy of an All Points Summary Listing to the Owner of each part or system to be placed in warranty by the Owner. For CHS systems, the Contractor shall additionally provide a print screen of the process display showing real time dynamic point information for all points on the subsystem(s) to be accepted.

B. Sequence Verification

1. The Contractor shall notify the Owner's representative of systems which perform

all specified sequences.

2. The warranty acceptance test shall be of 5 days duration and the system shall perform as follows:
 - a. During the five days, the FMCS system shall not report any system diagnostics from the subsystem under test.
 - b. The subsystem shall be performance verified as operational using temporary trends of each control loop located in the SDC or MSDC.
 - c. During the occupied periods, BAS control loops, under test, shall maintain control of the process variable within the following scales:
 - i. Pump Head Pressure ± 10 percent of control range
 - ii. Pipe Temperature Loops ± 2 degrees F
 - d. The contractor shall provide a hard copy printout of the process variable, process variable set point and control loop output percent for the period of 2 hours prior to occupancy to 2 hours after occupancy with samples taken every 15 minutes.

3.6. COORDINATE WITH TAB AGENCY

- A. Verify that all control components are installed in accordance with project requirements and are functional, including all electrical interlocks, damper sequences, air and water reset, freeze stats and duct smoke detectors.
- B. Verify that all controlling instruments are calibrated and set for design operating conditions prior to commencement of TAB work.
- C. Calibrate sensors after installation, and before the sensor control verification tests are performed. Prove the accuracy of final settings by taking temperature readings. The readings shall be in a typical conditional space for each separately controlled zone.
- D. Allow sufficient time in the project to provide assistance and instruction to the balancing agency in the proper use and setting of control components such as but not limited to computers or any other device that may need set points changed so that the testing and balancing work can be performed.
- E. All control sequences, software, equipment, and components shall be started-up by a qualified technician. Start-up report shall be submitted to Engineer prior to the commencement of testing and balancing work. Testing and balancing shall not commence until start-up reports are completed, reviewed by Engineer and forwarded to Testing and Balancing Agency.

3.7. EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that systems are ready to receive work.
- C. Beginning of installation means installer accepts existing conditions.
- D. Sequence work to ensure installation of components is complementary to installation of

similar components in other systems.

- E. Coordinate installation of system components with installation of mechanical systems equipment such as air handling units and air terminal units.
- F. Verify that conditioned power supply is available to the control units and to the operator work station. Verify that field end devices, wiring, and tubing is installed prior to installation proceeding.

3.8. INTERLOCK REQUIREMENTS

- A. The fan and equipment interlock requirements are as scheduled on the contract drawings.
- B. Furnish and install all necessary relays, transformer, contactors, wiring, conduit, and accessories to perform fan, equipment, and damper interlocks.
- C. Unless otherwise noted, fan interlocks shall be arranged such that dampers associated with fan shall be open when fan starts and close when fan stops.

3.9. SUBMITTALS AT PROJECT CLOSEOUT

- A. Project Record Documents: Record actual locations of components and set points of controls, including changes to sequences made after submission of shop drawings.

3.10. CONNECTIONS

- A. Piping installation requirements are specified in other Division 23 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
 - 1. Install piping adjacent to machine to allow service and maintenance.
- B. Ground equipment.
 - 1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- C. Connect hand-off-auto selection switches to override automatic interlock controls when switch is in hand position.

3.11. FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connections, and to assist in field testing. Report results in writing.
- B. Perform the following field tests and inspections and prepare test reports:
 - 1. Operational Test: After electrical circuitry has been energized, start units to confirm proper unit operation. Remove and replace malfunctioning units and retest.

2. Test and adjust controls and safeties.
 3. Test calibration of electronic controllers by disconnecting input sensors and stimulating operation with compatible signal generator.
 4. Test each point through its full operating range to verify that safety and operating control set points are as required.
 5. Test each control loop to verify stable mode of operation and compliance with sequence of operation. Adjust PID actions.
 6. Test each system for compliance with sequence of operation.
 7. Test software and hardware interlocks.
 8. Test all end switches and verify status is reported on the ATC system.
- C. DDC Verification:
1. Verify that instruments are installed before calibration, testing, and loop or leak checks.
 2. Check instruments for proper location and accessibility.
 3. Check instrument installation for direction of flow, elevation, orientation, insertion depth, and other applicable considerations.
 4. Check flow instruments. Inspect tag number and line and bore size, and verify that inlet side is identified and that meters are installed correctly.
 5. Check pressure instruments, piping slope, installation of valve manifold, and self-contained pressure regulators.
 6. Check temperature instruments and material and length of sensing elements.
 7. Check control valves. Verify that they are in correct direction.
 8. Check DDC system as follows:
 - a. Verify that DDC controller power supply is from emergency power supply, if applicable.
 - b. Verify that wires at control panels are tagged with their service designation and approved tagging system.
 - c. Verify that spare I/O capacity has been provided.
 - d. Verify that DDC controllers are protected from power supply surges.
- D. Replace damaged or malfunctioning controls and equipment and repeat testing procedures.
- E. All temperature control and interlock wiring shall be installed in conduit unless otherwise noted on the plans. Power or interlock wiring shall be run in separate conduit from sensor and communications wiring.

3.12. ADJUSTING

A. Calibrating and Adjusting:

1. Calibrate instruments.
2. Make three-point calibration test for both linearity and accuracy for each analog instrument.
3. Calibrate equipment and procedures using manufacturer's written recommendations and instruction manuals. Use test equipment with accuracy at least double that of instrument being calibrated.
4. Control System Inputs and Outputs:
 - a. Check analog inputs at 0, 50, and 100 percent of span.
 - b. Check analog outputs using volt-ohm-milli-amp meter (VOMA) at 0, 50, and 100 percent output.
 - c. Check digital inputs using jumper wire.
 - d. Check digital outputs using ohmmeter to test for contact making or breaking.
 - e. Check resistance temperature inputs at 0, 50, and 100 percent of span using a precision-resistant source.
5. Flow:
 - a. Set differential pressure flow transmitters for 0 and 100 percent values with 3-point calibration accomplished at 0, 50, 90, and 100 percent of span.
 - b. Manually operate flow switches to verify that they make or break contact.
6. Pressure:
 - a. Calibrate pressure transmitters at 0, 50, and 100 percent of span.
 - b. Calibrate pressure switches to make or break contacts, with adjustable differential set at minimum.
7. Temperature:
 - a. Calibrate resistance temperature transmitters at 0, 50, and 100 percent of span using a precision-resistance source.
 - b. Calibrate temperature switches to make or break contacts.
8. Stroke and adjust control valves and dampers.
9. Provide diagnostic and test instruments for calibration and adjustment of system.
10. Provide written description of procedures and equipment for calibrating each type of instrument. Submit procedures review and approval before initiating startup procedures.

B. Adjust initial temperature set points.

- C. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to three visits to Project during other than normal occupancy hours for this purpose.

3.13. ON-SITE ASSISTANCE

- A. Occupancy Adjustments: Within one year of date of Substantial Completion, provide up to three Project site visits, when requested by Owner, to adjust and calibrate components and to assist Owner's personnel in making program changes and in adjusting sensors and controls to suit actual conditions.

3.14. SCHEDULING

- A. Submit spreadsheet to Owner indicating occupied/unoccupied times for each item controlled by ATC system. Incorporate all scheduling requirements into sequence of operation.

3.15. STAGING

- A. Coordinate staging requirements with equipment being controlled. Where multistage units are scheduled or specified, provide all devices, controllers, wiring to control and sequence all stages.

END OF SECTION

DIVISION 23 SECTION 23 65 15
CLOSED CIRCUIT EVAPORATIVE FLUID COOLERS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS	3
1.2. SUMMARY	3
1.3. DEFINITIONS	3
1.4. PERFORMANCE REQUIREMENTS	3
1.5. ACTION SUBMITTALS	3
1.6. INFORMATIONAL SUBMITTALS	5
1.7. CLOSEOUT SUBMITTALS	5
1.8. QUALITY ASSURANCE	5
1.9. COORDINATION	6
1.10. WARRANTY	6
1.11. EXTRA MATERIALS	6
PART 2. PRODUCTS	6
2.1. CLOSED-CIRCUIT, INDUCED-DRAFT, COMBINED-FLOW EVAPORATIVE COOLERS ..	6
2.2. SOURCE QUALITY CONTROL	15
PART 3. EXECUTION	15
3.1. EXAMINATION	15
3.2. INSTALLATION	15
3.3. EQUIPMENT INSTALLATION REQUIREMENTS	16
3.4. PIPING CONNECTIONS	17
3.5. FIELD QUALITY CONTROL	18
3.6. STARTUP SERVICE	18
3.7. ADJUSTING	19
3.8. DEMONSTRATION	19
END OF SECTION	19

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 23 65 15 - CLOSED CIRCUIT EVAPORATIVE FLUID COOLERS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Refer to Division 23 Section 230600 – “Heating, Ventilating and Air Conditioning Equipment” for water treatment system to serve closed circuit evaporative fluid coolers.

1.2. SUMMARY

- A. Section Includes:
 - 1. Closed-circuit, induced-draft, combined-flow evaporative coolers.

1.3. DEFINITIONS

- A. BMS: Building management system.
- B. SEER: Short circuit current rating.

1.4. PERFORMANCE REQUIREMENTS

- A. Delegated Design: Design closed circuit evaporative fluid cooler support structure and seismic restraints and wind restraints, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- B. Structural Performance: Closed circuit evaporative fluid cooler support structure shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated according to SEI/ASCE 7.
 - 1. Wind Loads: 30PSF.
 - 2. Deflection Limits: Design system to withstand design loads without deflections greater than the following:
 - a. 1-inch.
- C. Overall dimensions and weight shall not exceed scheduled dimensions and weight.

1.5. ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include rated capacities, pressure drop, fan performance data, rating curves with selected points indicated, furnished specialties, and accessories.
 - 1. Maximum flow rate.

2. Minimum flow rate.
 3. Drift loss as percent of design flow rate.
 4. Sound power levels in eight octave bands for operation with fans off, fans at minimum, and design speed.
 5. Performance curves for the following:
 - a. Varying entering-water temperatures from design to minimum.
 - b. Varying ambient wet-bulb temperatures from design to minimum.
 - c. Varying water flow rates from design to minimum.
 - d. Varying fan operation (off, minimum, and design speed).
 6. Fan airflow, brake horsepower, and drive losses.
 7. Pump flow rate, head, brake horsepower, and efficiency.
 8. Motor amperage, efficiency, and power factor at 100, 75, 50, and 25 percent of nameplate horsepower.
 9. Electrical power requirements for each evaporative cooler component requiring power.
 10. Peak make-up water flow rate in gallons per minute.
- B. Shop Drawings: Complete set of manufacturer's prints of evaporative cooler assemblies, control panels, sections and elevations, and unit isolation. Include the following:
1. Assembled unit dimensions.
 2. Weight and load distribution.
 3. Required clearances for maintenance and operation.
 4. Sizes and locations of piping and wiring connections.
 5. Wiring Diagrams: For power, signal, and control wiring.
 6. All water treatment piping, power wiring, signal, and control wiring.
- C. Delegated-Design Submittal: For evaporative cooler support structure indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
1. Detail fabrication and assembly of support structure.
 2. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.
 3. Design Calculations: Calculate requirements for selecting vibration isolators and

seismic restraints and wind restraints and for designing vibration isolation bases.

1.6. INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Floor plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from Installers of the items involved:
 - 1. Structural supports and vibration isolation.
 - 2. Piping roughing-in requirements.
 - 3. Wiring roughing-in requirements, including spaces reserved for electrical equipment.
 - 4. Access requirements, including working clearances for mechanical controls and electrical equipment, and tube pull and service clearances.
- B. Certificates: For certification required in "Quality Assurance" Article.
- C. Seismic Qualification Certificates: For closed circuit evaporative fluid coolers, accessories, and components, from manufacturers.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- D. Source quality-control reports.
- E. Field quality-control reports.
- F. Startup service reports.
- G. Warranty: Sample of special warranty.

1.7. CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For the closed circuit evaporative fluid cooler to include in emergency, operation, and maintenance manuals.
- B. Instructional Videos: Including those that are pre-recorded and those that are recorded during training.

1.8. QUALITY ASSURANCE

- A. Testing Agency Qualifications: Certified by CTI.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in

NFPA 70, by a qualified testing agency, and marked for intended location and application.

- C. ASHRAE/IESNA 90.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."
- D. ASME Compliance: Fabricate and label heat-exchanger coils to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.
- E. CTI Certification: Evaporative cooler thermal performance according to CTI STD 201, "Certification Standard for Commercial Water-Evaporative coolers Thermal Performance."

1.9. COORDINATION

- A. Coordinate sizes and locations of concrete bases with actual equipment provided.
- B. Coordinate sizes, locations, and anchoring attachments of structural-steel support structures.
- C. Coordinate sizes and locations of structural rails, equipment supports, and building penetrations with actual equipment provided.

1.10. WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace the following components of closed circuit evaporative fluid coolers that fail in materials or workmanship within specified warranty period:
 - 1. Fan assembly including fan, drive, fans shafts, bearings, sleeves, and associated supports and motors.
 - 2. All components of closed circuit evaporative fluid coolers.
 - 3. Warranty Period: Five years from date of Substantial Completion.

1.11. EXTRA MATERIALS

- A. Furnish complete set of spare belts for each fan.
- B. Furnish spare spray pump seals.

PART 2. PRODUCTS

2.1. CLOSED-CIRCUIT, INDUCED-DRAFT, COMBINED-FLOW EVAPORATIVE COOLERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Baltimore Aircoil Company.

2. Evapco
3. Manufacturers: The Basis of Design on the drawing is based upon products of the manufacturer scheduled (B.A.C.). Alternate equipment manufacturers will be acceptable if equipment meets the scheduled performance and complies with these specifications. If equipment manufactured by manufacturer other, than Basis of Design is utilized, then the Mechanical Contractor shall be responsible for coordinating with all other Contractors and all affected Subcontractors to insure proper provisions for installation of the furnished unit. This coordination shall include, but not limited to, the following:
 - a. Structural supports for units.
 - b. Piping size and connection/header locations.
 - c. Electrical power requirements and wire/conduit and over current protection sizes.
 - d. Controls and Integration.
 - e. Vibration Isolation.
 - f. Water Treatment Systems.
 - g. The Mechanical Contractor shall be responsible for all costs incurred by the other contractor, Subcontractors, and Consultants to modify the building provisions to accept the furnished units.
- B. Fabricate closed circuit evaporative fluid cooler mounting bases with reinforcement strong enough to resist closed circuit evaporative fluid cooler movement during a seismic event when evaporative cooler is anchored to field support structure.
- C. Evaporative coolers shall be designed to resist wind load of 30 lbf/sq. ft. (1.44 kPa).
- D. Casing and Frame:
 1. Casing and Frame Material: Heavy gauge Type 304 stainless steel.
 2. Frame Material: Type 304 stainless steel.
 3. Fasteners: Stainless steel.
 4. Joints and Seams: Sealed watertight.
 5. Welded Connections: Continuous and watertight.
 6. Straight hood lined with sound absorbing acoustical baffles; positive closure dampers, insulation, and stainless steel linkages.
 7. Galvanized structural steel I-beams with vibration isolation rail below the entire unit.
- E. Collection Basin:
 1. Material: Heavy gauge Type 304 stainless steel all welded construction.
 2. Strainer: Removable 304 stainless-steel strainer with openings smaller than nozzle

zle orifices.

3. Overflow and drain connections.
4. Makeup water connection and valve with electronic float.
5. Anti-Vortex Device: 304 stainless steel.

F. Electric/Electronic, Collection Basin Water-Level Controller with Motorized Ball Valves:

1. Enclosure: NEMA 250, Type 4.
2. Standpipe Assembly: Schedule 40 PVC with vent holes and stainless steel hard-wire.
3. Sensor: Solid-state controls with multiple electrode probes and relays factory wired to a terminal strip to provide heater safety cut-out, high water level, low water level, control of water makeup valve, low- and high-level alarms, and output for shutoff of pump on low level.
4. Electrode Probes: Stainless steel.
5. Water Stilling Chamber: PVC pipe.
6. Motorized Ball Valve: Slow closing with stainless-steel body, controlled and powered through level controller in response to water-level set point. Furnish and install make-up water and bleed water motorized ball valves.
7. Electrical Connection Requirements: 120 V, single phase, 60 Hz.

G. Electric Basin Heater:

1. Stainless-Steel Electric Immersion Heaters: Installed in a threaded coupling on the side of the collection basin.
2. Heater Control Panel: Mounted in the closed circuit evaporative fluid cooler control panel.
3. Enclosure: NEMA 250, Type 4.
4. Magnetic contactors controlled by a temperature sensor/controller to maintain collection basin water-temperature set point. Water-level probe shall monitor evaporative cooler water level and de-energize the heater when the water reaches low-level set point.
5. Control-circuit transformer with primary and secondary side fuses.
6. Terminal blocks with numbered and color-coded wiring to match wiring diagram.
7. Single-point, field-power connection to a fused disconnect switch and heater

- branch circuiting complying with NFPA 70.
- 8. Factory Wiring Method: Metal raceway for factory-installed wiring outside of enclosures, except make connections to each electric basin heater with liquidtight conduit.
- 9. Maintain 40°F pan water temperature at 0°F ambient.
- H. Pressurized Water Distribution Piping: Main header and lateral branch piping designed for even distribution over heat-exchanger coil or fill throughout the flow range without the need for balancing valves and for connecting individual, removable, nonclogging spray nozzles.
 - 1. Pipe Material: PVC.
 - 2. Spray Nozzle Material: Plastic.
 - 3. Piping Supports: Corrosion-resistant hangers and supports to resist movement during operation and shipment.
- I. Recirculating Piping: PVC, with connections for separately provided, remote spray pump.
- J. Spray Pump: Close-coupled, end-suction, single-stage, bronze-fitted centrifugal pump; with suction strainer and flow balancing valve, and mechanical seal suitable for outdoor service. The system shall include a metering valve and bleed line to control the bleed rate from the spray pump discharge to the overflow connection.
 - 1. General Requirements for Spray Pump Motor: Comply with NEMA designation and temperature-rating requirements specified in Division 23 Section "Common Work Results for HVAC" and not indicated below.
 - 2. Motor Enclosure: Totally enclosed fan cooled (TEFC) with epoxy or polyurethane finish.
 - 3. Energy Efficiency: Comply with ASHRAE/IESNA 90.1.
 - 4. Service Factor: 1.15.
 - 5. Furnish and install pressure gauges on each side of spray pump.
- K. Fill:
 - 1. Materials: PVC, self extinguishing, with maximum flame-spread index of 5 according to ASTM E 84.
 - 2. Minimum Thickness: 15 mils (0.4 mm), before forming.
 - 3. Fabrication: Fill-type sheets fabricated, formed, and bonded together after forming into removable assemblies that are factory installed by manufacturer.
 - 4. Fill Material Operating Temperature: Suitable for entering-water temperatures up

through 120 deg F (49 deg C).

L. Heat-Exchanger Coils:

1. Tube and Tube Sheet Materials: Heavy gauge Type 304 Stainless Steel.
2. Heat-Exchanger Arrangement: Serpentine tubes Serpentine tubes with removable cover plate on inlet and outlet headers; and sloped for complete drainage of fluid by gravity.
3. ASME Compliance: Designed, manufactured, and tested according to ASME Boiler and Pressure Vessel Code: Section VIII, Division 1 and bearing ASME "U" stamp; and sloped for complete drainage of fluid by gravity.
4. Field Piping Connections: Vent, supply, and return suitable for mating to ASME B16.5, Class 150 flange.

M. Drift Eliminator:

1. Material: PVC; with maximum flame-spread index of 5 according to ASTM E 84.
2. UV Treatment: Inhibitors to protect against damage caused by UV radiation.
3. Configuration: Multipass, designed and tested to reduce water carryover to achieve performance indicated.
4. Fill Drift Eliminators: Separate and removable from fill.
5. Heat-Exchanger Coil Drift Eliminators: Located on discharge side and removable.

N. Air-Intake Louvers/Shields:

1. Material: PVC.
2. UV Treatment: Inhibitors to protect against damage caused by UV radiation.
3. Louver Blades: Arranged to uniformly direct air into evaporative cooler, to minimize air resistance, and to prevent water from splashing out of tower during all modes of operation including operation with fans off.
4. Location: Separate from fill and top mounted combined inlet shields.
5. Intake sound attenuation: Fiberglass acoustical baffles encased in steel.

O. Removable Air-Intake Screens: Stainless-steel wire mesh.

P. Axial Fans: Balanced at the factory after assembly.

1. Blade Material: Aluminum alloy.

2. Hub Material: Aluminum Alloy.
3. Blade Pitch: Field adjustable.
4. Protective Enclosure: Removable, galvanized-steel, wire-mesh screens complying with OSHA regulations.
5. Fan Shaft Bearings: Self-aligning ball or roller bearings with moisture-proof seals and premium, moisture-resistant grease suitable for temperatures between minus 20 and plus 300 deg F. Bearings designed for an L-10 life of 80,000 hours.
6. Bearings Grease Fittings: Extended lubrication lines to an easily accessible location.
7. For units with multiple fans the VFD shall be arranged to control the fan speed of both motors simultaneously. Should a fan motor fail the VFD shall be arranged to operate the fan that is still operational.

Q. Belt Drive:

1. Service Factor: 1.5 based on motor nameplate horsepower.
2. Sheaves: Fan and motor shafts shall have taper-lock sheaves fabricated from corrosion-resistant materials.
3. Belt: Multiple V-belt design with a matched set of cogged belts.
4. Belt: One-piece, multigrooved, solid-back belt.
5. Belt Material: Oil resistant, nonstatic conducting, and constructed of neoprene polyester cord.
6. Belt-Drive Guard: Comply with OSHA regulations.

R. Fan Motor:

1. General Requirements for Fan Motors: Comply with NEMA designation and temperature-rating requirements specified in Division 23 Section "Common Work Results for HVAC" and not indicated below.
2. Motor Enclosure: Totally enclosed air over (TEAO) with epoxy or polyurethane finish.
3. Energy Efficiency: Comply with ASHRAE/IESNA 90.1.
4. Service Factor: 1.15.
5. Insulation: Class F.
6. Variable-Speed Motors: Inverter-duty rated per NEMA MG-1, Section IV, "Performance Standard Applying to All Machines," Part 31, "Definite-Purpose, Inverter-Fed, Polyphase Motors."

7. Motor Location: Mounted outside of closed circuit evaporative fluid cooler casing and evaporative cooler discharge airstream.
8. Severe-duty rating with the following features:
 - a. Rotor and stator protected with corrosion-inhibiting epoxy resin.
 - b. Double-shielded, vacuum-degassed bearings lubricated with premium, moisture-resistant grease suitable for temperatures between minus 20 and plus 300 deg F (minus 29 and plus 149 deg C.)
 - c. Internal heater automatically energized when motor is de-energized.
 - d. Moisture protection on windings, shafts, and bearings.
9. Motor Base: Adjustable, or other suitable provision for adjusting belt tension.
10. Motor Removal System: Mechanical equipment removal davit to allow motors to be lowered to grade without tools.
11. Aegis shaft grounding ring for motor shafts.
- S. Fan Discharge Stack: Material shall match casing, design.
 1. Stack Termination: Wire-mesh, stainless-steel screens; complying with OSHA regulations. Provide positive closure motor operated damper and actuator.
- T. Vibration Switch: For each fan drive.
 1. Enclosure: NEMA 250, Type 4.
 2. Vibration Detection: Sensor with a field-adjustable, acceleration-sensitivity set point in a range of 0 to 1 g and frequency range of 0 to 3000 cycles per minute. Closed circuit evaporative fluid cooler manufacturer shall recommend switch set point for proper operation and protection.
 3. Provide switch with manual-reset button for field connection to a BMS and hardwired connection to fan motor electrical circuit.
 4. Switch shall, on sensing excessive vibration, signal an alarm through the BMS and shut down the fan.
- U. Control Package: A combination of factory installed and field installed and wired controls. Factory controls shall be functionally tested at factory before shipment. Field installed controls shall be installed, tested and commissioned to accomplish sequence of operation and points list.
 1. NEMA 250, Type 3R enclosure with removable internally mount backplate.
 2. Control-circuit transformer with primary and secondary side fuses.
 3. Terminal blocks with numbered and color-coded wiring to match wiring diagram. Spare wiring terminal block for connection to external controls or equipment.

4. Microprocessor-based controller for automatic control of fan and spray pump based on closed circuit evaporative fluid cooler leaving-water temperature with control features to improve operating efficiency based on outdoor ambient wet-bulb temperature by using adaptive logic.
5. Fan motor sequencer for multiple-cell with automatic lead stage rotation.
6. Variable frequency drive with full across the line bypass for fan motors.
7. Collection basin level controller complying with requirements in "Electric/Electronic, Collection Basin Water-Level Controller with Solenoid Valve" Paragraph.
8. Electric basin heaters with temperature control and low-water-level safety switch for each cell, complying with requirements in "Electric Basin Heater" Paragraph.
9. Vibration switch for each fan, complying with requirements in "Vibration Switch" Paragraph.
10. Single-point, field-power connection to a fused disconnect switch.
 - a. Branch power circuit to each motor and electric basin heater and to controls with a disconnect switch or circuit breaker.
 - b. NEMA-rated motor controller, hand-off-auto switch, and overcurrent protection for each motor. Provide variable frequency controller with manual bypass and line reactors for each variable-speed motor indicated.
11. Factory-installed wiring outside of enclosures shall be in metal raceway, except make connections to each motor and electric basin heater with liquidtight conduit.
12. Visual indication of status and alarm with momentary test push button for each motor.
13. Audible alarm and silence switch.
14. Visual indication of elapsed run time, graduated in hours for each motor.
15. Closed circuit evaporative fluid coolers shall have hardware to enable BMS to remotely monitor and display the following:
 - a. Operational status of each motor.
 - b. Position of dampers.
 - c. Closed circuit evaporative fluid cooler leaving-fluid temperature.
 - d. Fan vibration alarm.
 - e. Collection basin high- and low-water-level alarms.
16. Closed circuit evaporative fluid coolers shall be provided with automatic restart after power outage, drive fault or external fault, with drive in automatic mode. The circuit shall allow the user to select up to (10) restart attempts as well as the dwell time between attempts. The reset time between fault occurrences shall also

be selectable. All settings shall be via the membrane command center.

V. Personnel Access Components:

1. Doors: Large enough for personnel to access closed circuit evaporative fluid coolers internal components from both closed circuit evaporative fluid cooler end walls. Doors shall be operable from both sides of the door and shall be hinged.
2. Handrail: Stainless steel complete with kneerail and toeboard, around top of closed circuit evaporative fluid cooler. Comply with 29 CFR 1910.23.
3. Internal Walkway and Platforms: Aluminum, FRP, or galvanized-steel bar grating.
 - a. Spanning the collection basin from one end of closed circuit evaporative fluid cooler to the other and positioned to form a path between the access doors. Platform shall be elevated so that all parts are above the high water level of the collection basin.
 - b. Elevated internal platforms with handrails accessible from fixed vertical ladders to access the fan drive assembly when out of reach from collection basin platform.
 - c. Internal walkway shall be provided in the plenum for inspection and maintenance.
 - d. Integral ladders and OSHA cages as required shall be provided.
4. Davit for removing fan motors.

W. Capacities and Characteristics (Also refer to schedules on the Contract Drawings):

1. Air-Inlet Arrangement: Sides and top.
2. Maximum Drift Loss: 0.005 percent of design water flow.
3. Fan Drives: Belt.
4. Fan Motors:
 - a. Type: Inverter duty rated variable speed.
5. Sound Pressure Levels shall not exceed the following:
 - a. Back Lp = 75dB at 5 ft, 65dB at 50 ft
 - b. Connection End Lp = 73dB at 5 ft, 65dB at 50 ft
 - c. Top Lp = 90dB at 5 ft, 76dB at 50 ft
 - d. End Lp = 73dB at 5 ft, 65dB at 50 ft
 - e. Air Inlet Lp = 83dB at 5 ft, 66dB at 50 ft
 - f. Integrated ladders as required.

X. Vibration isolation base. Provide Vibro-Acoustics Model CTB or approved equal isolation base per closed circuit evaporative fluid cooler manufacturer's requirements. Finish shall be hot dipped galvanized. Isolators shall be restrained spring isolators Model SCSR

with 3 inch of deflection. Base and isolation shall be approved by closed circuit evaporative fluid cooler manufacturer and coordinated with dimensions and final operating weight.

Y. Electrical:

1. The closed circuit evaporative fluid coolers shall ship from the factory with fan motors and vibration cut-out switch wired to terminal blocks encased in type 304 stainless steel NEMA 3R enclosure, mounted in the control panel of the closed circuit evaporative fluid cooler.

2.2. SOURCE QUALITY CONTROL

- A. Verification of Performance: Test and certify closed circuit evaporative fluid cooler performance according to CTI STD 201, "Certification Standard for Commercial Water-Evaporative Coolers Thermal Performance."
- B. Factory pressure test heat exchangers after fabrication and prove that it is free of leaks.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Before closed circuit evaporative fluid coolers installation, examine roughing-in for support, anchor-bolt sizes and locations, piping, and electrical connections to verify actual locations, sizes, and other conditions affecting tower performance, maintenance, and operation.
 1. Closed circuit evaporative fluid cooler locations indicated on Drawings are approximate. Determine exact locations before roughing-in for piping and electrical connections.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2. INSTALLATION

- A. Install closed circuit evaporative fluid coolers on support structure including structural beams.
- B. Equipment Mounting:
 1. Install closed circuit evaporative fluid coolers on cast-in-place concrete equipment bases.
 2. Comply with requirements for vibration isolation and seismic control devices specified in Section 230548 "Vibration Controls for HVAC, Plumbing & Fire Protection Equipment."
- C. Install anchor bolts to elevations required for proper attachment to supported equipment.
- D. Maintain manufacturer's recommended clearances for service and maintenance.

- E. Loose Components: Install electrical components, devices, and accessories that are not factory mounted.
- F. Install and interlock all water treatment equipment and including all control and automatic temperature control wiring.
- G. All exterior pipes containing water shall be heat traced, insulated, jacketed, and labeled.

3.3. EQUIPMENT INSTALLATION REQUIREMENTS

- A. Examine proposed route of moving closed circuit evaporative fluid cooler into place and verify that it is free of interference.
- B. Examine elements and surface to support closed circuit evaporative fluid coolers.
- C. Install closed circuit evaporative fluid coolers according to manufacturer's written instructions.
- D. Install and anchor closed circuit evaporative fluid coolers level and plumb, and fasten/anchor to supporting structure vibration isolators and base.
- E. Maintain recommended clearances for service and maintenance.
- F. Manufacturers Field Service: Engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including piping and electrical connections. Report results in writing.
- G. Adjust water-level controls for proper operating level.
- H. After completing system installation, including outlet fittings and devices, inspect exposed finish. Remove burrs, dirt and construction debris, and repair damaged finishes including chips, scratches and abrasions.
- I. Obtain wet-bulb, condenser-size, and performance selection tables from manufacturer.
- J. Lubricate bearings on fans and shaft as recommended by manufacturer.
- K. Ensure fan wheels rotate in correct direction without vibration or binding.
- L. Adjust belts to proper alignment and tension.
- M. Start closed circuit evaporative fluid coolers. Follow manufacturers written starting procedures.
- N. Check water level in closed circuit evaporative fluid cooler basins.
- O. Check operation of closed circuit evaporative fluid cooler basins, make-up lines, motorized ball valves, motorized bleed ball valves, water meters, dampers, end switches, and low water cut-off controlling device.
- P. Wire all motorized ball valves, chemical treatment panel, bleed-off motorized ball valves, water level controls, pump interlocks, fan interlocks, basin heaters, low water cut-offs,

spray pumps, basin heater thermostats, damper end switches and control panel under Division 23.

- Q. Pipe all water treatment piping and wiring from water treatment panels to closed circuit evaporative fluid coolers. Install all wiring, controls, piping etc. under this division.
- R. Pipe all drain pipes and bleed-off valves to open hubs or floor drains on to splash blocks with suitable air gaps.
- S. Install and design custom galvanized steel vibration isolation rails below closed circuit evaporative fluid cooler. Coordinate with closed circuit evaporative fluid cooler steel drawings. All documents shall be signed and sealed by a structural engineer with a Delaware P.E. stamp.
- T. Assist automatic temperature controls contractor with all interlock wiring and mapping over BACnet points to the automatic temperature control system.
- U. Passivation of Galvanized Components or Piping (Not Required for Stainless Steel Components):
 - 1. Provide passivation of all galvanized components (piping, equipment, etc.) of closed circuit evaporative fluid coolers.
 - 2. Water treatment contractor shall notify the water treatment service provider of date and time of the system start-up so that the water treatment service provider can perform the conditioning process at the proper time.
 - 3. Conditioning of the galvanized components/piping shall be performed after full start-up either through specific conductivity settings on the blowdown controller for the first six (6) weeks for operation of through temporarily applied chemicals.
 - 4. Provide corrosion inhibitors.
 - 5. Provide conditioning of galvanized surfaces by conductivity control or chemical conditioning by the closed circuit evaporative fluid cooler water treatment certified service provider.

3.4. PIPING CONNECTIONS

- A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to closed circuit evaporative fluid coolers to allow service and maintenance.
- C. Install flexible pipe connectors at pipe connections of closed circuit evaporative fluid coolers mounted on vibration isolators.
- D. Provide drain piping with valve at closed circuit evaporative fluid cooler drain connections and at low points in piping.
- E. Connect closed circuit evaporative fluid cooler overflows and drains, and piping drains to

location shown on Contract Drawings.

- F. Domestic Water Piping: Comply with applicable requirements in Division 22 "Plumbing Piping, Fittings, and Valves." Connect to water-level control with shutoff valve and union, flange, or mechanical coupling at each connection.
- G. Supply and Return Piping: Comply with applicable requirements in Division 23 Section "HVAC Piping, Fittings, and Valves". Connect to entering closed circuit evaporative fluid cooler connections with shutoff valve, balancing valve, thermometer, plugged tee with pressure gage, flow meter, and drain connection with valve. Connect to leaving closed circuit evaporative fluid cooler connections with shutoff valve. Make connections to closed circuit evaporative fluid coolers with a union, flange, or mechanical coupling.

3.5. FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to perform field tests and inspections.
- C. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- D. Tests and Inspections: Comply with CTI ATC 105, "Acceptance Test Code for Water Evaporative Coolers."
- E. Closed circuit evaporative fluid coolers will be considered defective if they do not pass tests and inspections.
- F. Prepare test and inspection reports.

3.6. STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
- B. Inspect field-assembled components, equipment installation, and piping and electrical connections for proper assemblies, installations, and connections.
- C. Obtain performance data from manufacturer.
 - 1. Complete installation and startup checks according to manufacturer's written instructions and perform the following:
 - a. Clean entire unit including basins.
 - b. Verify that accessories are properly installed.
 - c. Verify clearances for airflow and for closed circuit evaporative fluid cooler servicing.
 - d. Check for vibration isolation and structural support.
 - e. Lubricate bearings.

- f. Verify fan rotation for correct direction and for vibration or binding and correct problems.
 - g. Adjust belts to proper alignment and tension.
 - h. Verify proper oil level in gear-drive housing. Fill with oil to proper level.
 - i. Operate variable-speed fans through entire operating range and check for harmonic vibration imbalance. Set motor controller to skip speeds resulting in abnormal vibration.
 - j. Check vibration switch setting. Verify operation.
 - k. Verify water level in closed circuit evaporative fluid cooler basin. Fill to proper startup level. Check makeup water-level motorized ball valve and check bleed water motorized ball control valves.
 - l. Verify operation of basin heater and control.
 - m. Verify that closed circuit evaporative fluid cooler air discharge is not recirculating air into closed circuit evaporative fluid cooler or HVAC air intakes. Recommend corrective action.
 - n. Test all heat tracing.
 - o. Replace defective and malfunctioning units.
 - p. Test all interlocks to water treatment system.
- D. Start closed circuit evaporative fluid cooler and associated water pumps. Follow manufacturer's written starting procedures.
- E. Prepare a written startup report that records the results of tests and inspections.

3.7. ADJUSTING

- A. Set and balance water flow to each inlet.
- B. Adjust water-level control for proper operating level and bleed water flow.

3.8. DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain evaporative coolers.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 23 SECTION 23 65 17
OPEN-CIRCUIT, LOW PROFILE, FORCED DRAFT COOLING TOWERS
TABLE OF CONTENTS

PART 1.	GENERAL	3
1.1	RELATED DOCUMENTS	3
1.2	REFERENCE STANDARDS	3
1.3	SUMMARY	3
1.4	DEFINITIONS	4
1.5	ACTION SUBMITTALS	4
1.6	INFORMATIONAL SUBMITTALS	5
1.7	CLOSEOUT SUBMITTALS	6
1.8	MAINTENANCE MATERIAL SUBMITTALS	6
1.9	QUALITY ASSURANCE	6
1.10	DELIVERY, STORAGE, AND HANDLING	6
1.11	WARRANTY	7
1.12	EXTRA MATERIALS	7
PART 2.	PRODUCTS	7
2.1	MANUFACTURERS	7
2.2	PERFORMANCE REQUIREMENTS	8
2.3	DESIGN ARRANGEMENT	8
2.4	CASING AND FRAME	9
2.5	COLLECTION BASIN	9
2.6	COLLECTION BASIN MAKEUP-WATER ASSEMBLY	9
2.7	COLLECTION BASIN HEATER	10
2.8	PRESSURIZED DISTRIBUTION NETWORK	10
2.9	FILL	10
2.10	DRIFT ELIMINATORS	11
2.11	AIR INLET	11
2.12	FAN AND DRIVE ASSEMBLY	11
2.13	ELECTRICAL POWER	12
2.14	CONTROLS	15
2.15	WATER TREATMENT	16
2.16	SERVICE ACCESS	16
2.17	CAPACITIES AND CHARACTERISTICS (ALSO REFER TO CONTRACT DRAWINGS) ..	17
2.18	SOURCE QUALITY CONTROL	17
2.19	VIBRATION ISOLATION	18
PART 3.	EXECUTION	18
3.1	EXAMINATION	18
3.2	INSTALLATION	18
3.3	PIPING CONNECTIONS	19
3.4	ELECTRICAL POWER CONNECTIONS	20
3.5	CONTROLS CONNECTIONS	20
3.6	FIELD QUALITY CONTROL	20
3.7	STARTUP SERVICE	20
3.8	ADJUSTING	21
3.9	DEMONSTRATION	21

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 23 65 17- OPEN-CIRCUIT, LOW PROFILE, FORCED-DRAFT COOLING TOWERS

PART 1. GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Refer to Division 23 Section 230600 "Heating, Ventilating, and Air Conditioning Equipment" for water treatment system to serve cooling towers.

1.2 REFERENCE STANDARDS

- A. ASHRAE 90.1-2019 – Energy Standard for Buildings Except Low-Rise Residential Buildings.
- B. ASTM A123/A123M – Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products 2017.
- C. ASTM A653/A653M – Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process 2018.
- D. ASTM B117 – Standard Practice for Operating Salt Spray (Fog) Apparatus 2018.
- E. ASTM E84 – Standard Test Method for Surface Burning Characteristics of Building Materials 2018b.
- F. ASTM D2794 – Standard Test Method for Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact).
- G. CTI STD-201 OM – Operations Manual for Thermal Performance Certification of Evaporative Heat Rejection Equipment 2017.
- H. CTI-STD-201 RS – Performance Rating of Evaporative Heat Rejection Equipment 2017.
- I. ISO 9001 – Quality Management Systems – Requirements 2015.
- J. NEMA MG 1 – Motors and Generators 2017.
- K. ASCE/SEI 7 – Minimum Design Loads and Associated Criteria for Buildings and Other Structures.

1.3 SUMMARY

- A. Section includes factory-assembled, open-circuit, forced-draft cooling towers.

1.4 DEFINITIONS

- A. SCCR: Short-circuit current rating.
- B. BMS: Building management system.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include rated capacities, pressure drop, fan performance data, rating at selected points indicated, and furnished specialties and accessories.
 - 2. Maximum flow rate.
 - 3. Minimum flow rate.
 - 4. Pressure required at cooling tower supply piping connections.
 - 5. Pressure required at basin heater supply piping connections.
 - 6. Drift loss as percent of design flow rate.
 - 7. Volume of water in suspension for purposes of sizing remote storage.
 - 8. Sound:
 - a. Sound pressure levels for operation with fan off, fan at minimum speed, and design speed. If sound requirements are indicated at a specific distance, submit performance using same distance for comparative analysis.
 - b. Sound power levels in eight octave bands for operation with fans off, fans at minimum speed, and design speed.
 - 9. Performance curves for the following:
 - a. Varying entering-water temperatures from design to minimum in one-degree temperature increments.
 - b. Varying ambient wet-bulb temperatures from design to minimum in one-degree temperature increments.
 - c. Varying water flow rates from design to minimum in increments of 1 percent of flow rate difference between design and minimum flow rates.
 - d. Varying fan operation from design to minimum speed in 5 percent speed increments, and with fan off.
 - 10. Fan airflow at design conditions, brake horsepower, and drive losses (indicated in horsepower and percentage of brake horsepower).
 - 11. Fan motor electrical characteristics, including but not limited to, speed, voltage, phase hertz, amperage, efficiency, and power factor at 100, 75, 50, and 25 percent of nameplate horsepower.
 - 12. Electrical power requirements for each cooling tower component requiring power.
 - 13. Peak make-up water flow rate in gallons per minute.
 - 14. Manufacturer's certificate: certifying that cooling tower performance based on CTI STD-201 meets or exceeds specified requirements and submit performance curve plotting leaving water temperature against wet bulb temperature.
- B. Shop Drawings:

1. Manufacturer's drawings of assembled cooling towers, control panels, sections, and elevations.
 2. Assembled unit dimensions.
 3. Diagram showing each separate piece requiring field assembly.
 4. Shipped sub-assembly dimensions and weights for field assembly.
 5. Assembled unit weight without water.
 6. Operating weight and load distribution.
 7. Unit vibration isolation.
 8. Required clearances for maintenance and operation.
 9. Sizes and dimensioned locations of piping and wiring connections.
 10. Diagrams for power, signal, and control wiring.
 11. All water treatment piping, power wiring, signal, and control wiring.
- C. Delegated-Design Submittal: For cooling tower support structure indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
1. Detail fabrication and assembly of support structure.
 2. Vibration Isolation Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment.
 3. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and wind restraints and for designing vibration isolation bases.

1.6 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings:
1. Drawings on which the following items are shown and coordinated with each other, using input from Installers of the items involved:
 - a. Structural supports and vibration isolation.
 - b. Piping roughing-in requirements.
 - c. Conduit and wiring roughing-in requirements for controls and electrical power, including spaces reserved for controls and electrical equipment.
 - d. Access requirements, including working clearances for controls and electrical equipment, and service clearances. Mark and label clearances.
 2. Drawings showing plans, sections, and elevation views, drawn to scale.
 3. Each view to show screened background with the following:
 - a. Structural grids.
 - b. Adjacent walls, floors, and roofs.
 - c. Equipment and products of other trades that are located in vicinity of cooling towers and are part of final installation, such as controls, power, lighting, fire-suppression systems, and plumbing systems.
- B. Product Certificates: For certification required in "Quality Assurance" Article.
- C. Seismic Qualification Data: Certificates, for cooling towers, accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- D. Source quality-control reports.
- E. Field quality-control reports.
- F. Field Test Reports: Include startup service reports.
- G. Sample Warranty: For special warranty.

1.7 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For each cooling tower to include in emergency, operation, and maintenance manuals.
- B. Instructional Videos: Including those that are pre-recorded and those that are recorded during training.

1.8 MAINTENANCE MATERIAL SUBMITTALS

- A. Belts:
1. Furnish one set of matching belts for each unique belt configuration and size furnished.
- B. Touch-up Coating: 32-oz. (1-L) container of paint coating used. Label outside of container with detailed description of coating to allow for procurement of a matching coating in the future.

1.9 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Certified by CTI.
- B. CTI Certification: Cooling tower thermal performance according to CTI STD 201RS.
- C. FM Global: Approval and listing in the latest edition of FM Global's "Approval Guide."
- D. ASHRAE 90.1 – Energy Standard for Buildings Except Low-Rise Residential Buildings.

1.10 DELIVERY, STORAGE, AND HANDLING

- A. Coordinate requirements for multi-piece assembly for shipment. Limit the number of separate pieces for field installation to as few as possible.
- B. If factory assembly of multiple pieces is required for testing or other reasons, disassemble cool-

ing tower into major assemblies as required by installation before packaging for shipment.

1. Clearly label each package with a unique designation and include assembly instructions for each complete cooling tower.

1.11 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace the following components of cooling towers that fail in materials or workmanship within specified warranty period:
 1. All components of cooling tower.
 2. Fan assembly, including fan, drive, and motor.
 3. Warranty Period: Five years from date of Substantial Completion.

1.12 EXTRA MATERIALS

- A. Furnish a spare set of fan belts for each fan.

PART 2. PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 1. Baltimore Aircoil Company.
 2. Evapco
 3. Manufacturers: The Basis of Design on the drawing is based upon products of the manufacturer scheduled (B.A.C.). Alternate equipment manufacturers will be acceptable if equipment meets the scheduled performance and complies with these specifications. If equipment manufactured by manufacturer other, than Basis of Design is utilized, then the Mechanical Contractor shall be responsible for coordinating with all other Contractors and all affected Subcontractors to insure proper provisions for installation of the furnished unit. This coordination shall include, but not limited to, the following:
 - a. Structural supports for units.
 - b. Piping size and connection/header locations.
 - c. Electrical power requirements and wire/conduit and over current protection sizes.
 - d. Controls and Integration.
 - e. Vibration Isolation.
 - f. Water Treatment Systems.
 - g. The Mechanical Contractor shall be responsible for all costs incurred by the other contractor, Subcontractors, and Consultants to modify the

building provisions to accept the furnished units.

- B. Fabricate cooling tower mounting bases with reinforcement strong enough to resist cooling tower movement during a seismic event when closed cooling tower is anchored to field support structure.
- C. Cooling towers shall be designed to resist wind load of 30 lbf/sq. ft. (1.44 kPa).

2.2 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer to design cooling tower support structure seismic restraints and wind restraints, including comprehensive engineering analysis.
- B. Structural Performance: Cooling tower and support structure shall withstand the effects of loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
- C. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
- E. Operation Following Loss of Normal Power:
 - 1. Equipment, associated factory- and field-installed controls, and associated electrical equipment and power supply connected to backup power system shall automatically return equipment and associated controls to the operating state occurring immediately before loss of normal power without need for manual intervention by an operator when power is restored either through a backup power source, or through normal power if restored before backup power is brought online.
 - 2. Include means and methods required to satisfy requirement even if not explicitly indicated.
- F. Vibration:
 - 1. Rotating assemblies shall be dynamically balanced to achieve a balance level of "good" while complying with industry-standard requirements for cooling towers.
 - 2. Critical speed shall be at least 115 percent of design speed.

2.3 DESIGN ARRANGEMENT

- A. Counterflow pattern with inlet airflow from one side and forced-draft, bottom-mounted centrifugal fans; and with pressurized pipe distribution near top.
- B. Low-profile design with counterflow pattern, with inlet airflow from one side and forced-draft, side-mounted centrifugal fans to reduce overall height; and with pressurized pipe distribution near top.

2.4 CASING AND FRAME

- A. Casing Material: Stainless steel, Type 304.
- B. Frame Material: Stainless steel, Type 304.
- C. Hardware: Stainless steel.
- D. Joints and Seams: Sealed watertight.
- E. Welded Connections: Sealed watertight by continuous welds.

2.5 COLLECTION BASIN

- A. Factory-Assembled Collection Basin:
 - 1. Material: Stainless steel, Type 304.
 - 2. Hardware: Stainless steel.
 - 3. Joints and Seams: Sealed watertight.
 - 4. Welded Connections: Sealed watertight by continuous welds.
 - 5. Removable stainless-steel strainer with openings smaller than nozzle orifices.
 - 6. Overflow and drain connections.
 - 7. Makeup-water connection.
 - 8. Outlet Connection: Configured to mate to ASME B16.5, Class 150 flange.
 - 9. Anti-Vortex Device: Stainless steel, Type 304.
 - 10. Equalizer connection for field-installed equalizer piping configured to mate to ASME B16.5, Class 150 flange.

2.6 COLLECTION BASIN MAKEUP-WATER ASSEMBLY

- A. Electric/Electronic, Collection Basin Water-Level Controller with Makeup-Water Motorized Ball Valve:
 - 1. Enclosures: NEMA 250, Type 4.
 - 2. Sensor: Solid-state controls with multiple electrode probes and relays factory wired to a terminal strip to control makeup-water valve and low- and high-level alarms control makeup-water valve, low- and high-level alarms, and output for shutoff of pump on low level.
 - 3. Electrode Probes: Stainless steel.
 - 4. Water-Stilling Chamber: PVC pipe.
 - 5. Makeup-Water Valve:
 - a. Slow closing with stainless-steel body.
 - b. Valve actuator controlled and powered through level controller in response to water-level set point.
 - c. Actuator Enclosure: NEMA 250, Type 4.
 - d. Fail Position: Closed.
 - e. Action: Two position, motorized ball valve.

6. Electrical Connection Requirements: 120-V ac, single phase, 60 Hz.

2.7 COLLECTION BASIN HEATER

A. Electric Heater:

1. Stainless-Steel Electric Immersion Heaters: Installed in a threaded coupling on the side of the collection basin.
2. Heater Control Panel: Mounted on the side of each cooling tower cell.
3. Enclosure: NEMA 250, Type 4.
4. Magnetic contactors controlled by a temperature sensor/controller to maintain collection basin water-temperature set point. Water-level probe shall monitor cooling tower water level and de-energize the heater when the water reaches low-level set point.
5. Control-circuit transformer with primary and secondary side fuses.
6. Terminal blocks with numbered and color-coded wiring to match wiring diagram.
7. Single-point, field-power connection to a fused disconnect switch and heater branch circuiting complying with NFPA 70.
8. Factory Wiring Method: Metal raceway for factory-installed wiring outside of enclosures; except, connections to each electric basin heater shall be liquidtight conduit.
 - a. Raceway shall be corrosion-resistant stainless steel.

2.8 PRESSURIZED DISTRIBUTION NETWORK

- A. Main header and lateral branch piping designed for even distribution over fill and heat-exchanger coils throughout the entire flow range without the need for balancing valves and for connecting individual, easily removable, nonclogging spray nozzles.
- B. Pipe Material: Schedule 40 PVC.
- C. Spray Nozzle Material: Plastic Polypropylene or PVC.
- D. Piping Supports: Corrosion-resistant hangers and supports to resist movement during operation and shipment.

2.9 FILL

A. PVC:

1. Flame-Spread Index: 5 according to ASTM E84.
2. Minimum Thickness: 15 mils (0.4 mm), before forming.
3. Fabrication: Fill-type sheets, fabricated, formed, and bonded together after forming into removable assemblies that are factory installed by manufacturer.
4. Fill Material Operating Temperature: Suitable for entering-water temperatures up through 120 deg F (49 deg C).

B. Hardware: stainless steel.

2.10 DRIFT ELIMINATORS

- A. Material: PVC, with maximum flame-spread index of 5 according to ASTM E84.
- B. UV Treatment: Inhibitors to protect against damage caused by UV radiation.
- C. Arrangement: Multiple, easily removable sections.
- D. Configuration: Multipass, designed and tested to reduce water carryover to 0.001 percent of design flow rate indicated.
- E. Hardware: stainless steel.

2.11 AIR INLET

- A. Air-Intake Screens:
 - 1. Stainless-steel wire mesh, with openings of size sufficient to not restrict airflow or impact performance.
 - 2. Segmented into manageable individual sections arranged to facilitate independent removal of each section without disturbing adjoining sections.
- B. Hardware: stainless steel.

2.12 FAN AND DRIVE ASSEMBLY

- A. Centrifugal Fans: Double-width, double-inlet, forward-curved blades; statically and dynamically balanced at the factory after assembly.
 - 1. Cooling Tower Cell Fan Assembly: Each cooling tower cell shall have a single fan or multiple fans connected to a common shaft.
 - 2. Fan Wheel and Housing Materials: Hot-dip galvanized steel.
 - 3. Fan Shaft: Steel, coated to resist corrosion.
 - 4. Fan Shaft Bearings: Self-aligning ball or roller bearings with moisture-proof seals and premium, moisture-resistant grease suitable for temperatures between minus 20 and plus 300 deg F (minus 29 and plus 149 deg C). Bearings designed for an L-10 life of 50,000 hours.
 - 5. Bearing Grease Fittings: Extended lubrication lines to an easily accessible location.
 - 6. Protective Enclosure: Removable, galvanized-steel, wire-mesh screens complying with OSHA regulations.
- B. Belt Drives:
 - 1. Service Factor: 1.5 based on motor nameplate horsepower.
 - 2. Sheaves: Fan and motor shafts shall have taper-lock sheaves fabricated from corrosion-resistant materials.
 - 3. Belt: Multiple V-belt design with a matched set of cogged belts.
 - 4. Belt: One-piece, multigrooved, solid-back belt.
 - 5. Belt Material: Oil resistant, nonstatic conducting, and constructed of neoprene polyester cord.

6. Belt-Drive Guard: Comply with OSHA regulations.

C. Fan Motors:

1. Comply with NEMA MG 1 unless otherwise indicated.
2. Description: NEMA MG 1, Design B, as required to comply with capacity and torque characteristics; medium induction motor.
3. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.
4. Motor Enclosure: Totally enclosed.
5. Rotor: Random wound, squirrel cage.
6. Energy Efficiency: Comply with ASHRAE/IES 90.1.
7. Service Factor: 1.15.
8. Temperature Rise: Match One class lower than insulation rating.
9. Insulation: Class F.
10. Variable-Speed Motors: Inverter-duty rated according to NEMA MG 1, Section IV, "Performance Standard Applying to All Machines," Part 31, "Definite-Purpose, Inverter-Fed, Polyphase Motors."
11. Motor Location: Mounted outside of cooling tower airstream.
12. Severe-Duty Rating:
 - a. Rotor and stator protected with corrosion-inhibiting epoxy resin.
 - b. Double-shielded, vacuum-degassed bearings lubricated with premium, moisture-resistant grease suitable for temperatures between minus 20 and plus 300 deg F (minus 29 and plus 149 deg C.).
 - c. Internal Heater: Automatically energized when motor is de-energized.
 - d. Complying with IEEE 841.
13. Motor Base: Adjustable, or other suitable belt-tensioning provisions.
14. Motor Shaft Grounding: Motors shall be controlled through variable-frequency controllers with shaft grounding system to protect motor bearings from induced voltage. Drag on motor shaft due to shaft ground system shall be less than 0.5 percent of motor nameplate horsepower.

D. Hardware: stainless steel.

2.13 ELECTRICAL POWER

A. Factory Install: A disconnect switch and variable-frequency controller for each fan motor.

1. Locate in a convenient and field-accessible location within sight of motor.
2. Installation shall comply with NFPA 70.
3. Wire, Conduit, and Enclosures:
 - a. Minimum Conduit Size: 0.75 inch (20 mm).
 - b. Materials: Corrosion resistant and constructed of stainless steel.
 - c. Motor Termination: Liquidtight conduit, not to exceed 36 inches (900 mm) long.
 - d. Supports: Support, conduits boxes, and enclosures using corrosion-resistant fastening hardware constructed of stainless steel.

e. Wire:

- 1) Copper, rated for 600-V solid wire for size No. 10 AWG and smaller and stranded wire for larger sizes.
- 2) Minimum Wire Size: No. 12 AWG.
- 3) Each circuit shall have a ground wire.
- 4) Install wire in conduit.

f. Boxes, Condulets, and Enclosures: NEMA 250, Type 4.

B. Disconnect Switches:

1. Specification Grade; "Heavy-Duty Type," "quick-make," "quick-break" construction.
2. Three pole fused.
3. 600-V rated.
4. Minimum SCCR: As required by electrical power distribution system, but not less than 65,000 A.
5. Enclosure: NEMA 250, Type 4.
6. Operating handle shall be of box-mounted type that directly drives switch mechanism.
7. Disconnect switch shall use a flange-operated visible blade that is close coupled to a vertical-lift-type handle that achieves a positive visible indication of disconnect with cover open or closed.
8. Disconnect switch shall have a defeatable, front-accessible, mechanical interlock to prevent opening of cover when switch is in "ON" position, and to prevent turning switch "ON" when the door is open.
9. Include a solid neutral as required by authorities having jurisdiction.
10. Include a ground lug for ground wire termination.
11. Operating handle shall be lockable in open position.
12. Horsepower rated.
13. Feed through or double lugged.

C. Variable-Frequency Controllers:

1. Description: NEMA ICS 2; arranged to achieve motor variable speed by adjusting output voltage and frequency.
2. Enclosure: Unit mounted, NEMA 250, Type 4, with hinged full-front access door with lock and key.
3. Externally Operated, Door-Interlocked Disconnect: Fused disconnect switch with lockable handle.
4. Minimum SCCR: As required by electrical power distribution system, but not less than 65,000 A.
5. Technology: Pulse-width-modulated (PWM) output with insulated gate bipolar transistors (IGBTs); suitable for variable-torque loads.
6. Controller shall consist of a rectifier converter section, a digital/analog driver regulator section, and an inverter output section.
7. Output Rating: Three phase; with voltage proportional to frequency throughout voltage range.
8. Output signal shall be programmed to not cause mechanical vibration issues with fan drive assembly.
9. Operating Requirements:

- a. Input AC Voltage Tolerance: 10 percent.
 - b. Input frequency tolerance of 60 Hz, plus or minus 2 Hz.
 - c. Capable of driving full motor load, without derating.
 - d. Minimum Efficiency: 96 percent at 60 Hz, full load.
 - e. Minimum Displacement Primary-Side Power Factor: 95 percent.
 - f. Overload Capability: 1.05 times the full-load current for seven seconds.
 - g. Starting Torque: As required by fan and motor drive assembly.
 - h. Speed Regulation: 1 percent.
 - i. Speed Range: 10:1 speed range.
 - j. To avoid equipment resonant vibrations, include critical speed lockout circuitry to allow bands of operating frequency at which controller shall not operate continuously.
 - k. Capable of being restarted into a motor, coasting in either the forward or reverse direction without tripping.
10. Controller Adjustability Capabilities: Minimum and maximum output frequency, acceleration and deceleration, and current limit.
11. Self-Protection and Reliability Features: Subjecting the controller to any of the following conditions shall not result in component failure or the need for replacement:
- a. Overtemperature.
 - b. Short circuit at controller output.
 - c. Ground fault at controller output. Variable-frequency controller shall be able to start a grounded motor.
 - d. Open circuit at controller output.
 - e. Input undervoltage.
 - f. Input overvoltage.
 - g. Loss of input phase.
 - h. Reverse phase.
 - i. AC line-switching transients.
 - j. Instantaneous overload, line to line or line to ground.
 - k. Sustained overload exceeding 100 percent of controller-rated current.
 - l. Starting a rotating motor.
12. Motor Protection: Controller shall protect motor against overvoltage and undervoltage, phase loss, reverse phase, overcurrent, overtemperature, and ground fault.
13. Automatic Reset and Restart:
- a. Capable of multiple restarts after controller fault or on return of power after an interruption and before shutting down for manual reset or fault correction.
 - b. Capable of automatic restart on phase-loss and overvoltage and undervoltage trips.
14. Visual Indication: On face of controller; indicating the following conditions:
- a. Power on.
 - b. Run.
 - c. Overcurrent and overvoltage.
 - d. Motor speed (percent).
 - e. Various faults with alarm status.
 - f. Input kilovolt amperes.
 - g. Power factor.

- h. Input kilowatts and kilowatt-hours.
 - i. Three-phase input and output voltage.
 - j. Three-phase input and output current.
 - k. Output frequency.
 - l. Elapsed operating time (hours).
 - m. Diagnostic and service parameters.
- 15. Operator Interface: Start-stop and auto-manual selector with manual-speed-control potentiometer.
 - 16. Control Signal Interface: A minimum of four (4) analog inputs (0 to 10 V or 0/4 to 20 mA) and six (6) programmable digital inputs.
 - 17. Bypass Controller:
 - a. Integrated NEMA ICS 2, Class A, full-voltage, non-reversing, motor-rated controller to operate fan motor if variable-frequency controller is not operational.
 - b. Configure power supply to bypass controller and variable-frequency controller to completely isolate power to variable-frequency controller while operating fan motor through bypass controller, for safe servicing of variable-frequency controller.
 - c. Include "Bypass/VFC" manual selector switch on face of enclosure to provide for local operator control of preferred controller.
 - d. Include fail-safe control logic to automatically transfer fan motor operation from failed variable-frequency controller to bypass controller.
 - e. Install bypass controller in same enclosure as variable-frequency controller.

2.14 CONTROLS

A. Vibration Switch: For each fan drive.

- 1. Enclosure: NEMA 250, Type 4.
- 2. Vibration Detection: Sensor with a field-adjustable, acceleration-sensitivity set point in a range of 0 to 1 g and frequency range of 0 to 3000 cycles per minute. Cooling tower manufacturer shall recommend switch set point for proper operation and protection.
- 3. Switch shall have manual-reset button with hardwired connection to fan motor electrical circuit.
- 4. Switch shall have field connection for hardwired connection to control system.
- 5. Switch shall, on sensing excessive vibration, signal an alarm through the BMS and shut down the fan.

B. Control Package:

- 1. Factory installed and wired, and functionally tested at factory before shipment.
- 2. NEMA 250, Type 4 enclosure with removable, internally mounted backplate.
- 3. Control-circuit transformer with primary and secondary side fuses.
- 4. Terminal blocks with numbered and color-coded wiring to match wiring diagram. Spare wiring terminal block for connection to external controls or equipment.
- 5. Microprocessor-based controller for automatic control of fan based on cooling tower leaving-water temperature, with control features to improve operating efficiency based on outdoor ambient wet-bulb temperature by using adaptive logic.
- 6. Fan motor sequencer for multiple-cell and two-speed applications with automatic lead stage rotation.

7. Collection basin water-level controller complying with requirements in "Electric/Electronic, Collection Basin Water-Level Controller with Makeup-Water Valve" Paragraph.
8. Electric basin heaters with temperature control and low-water-level safety switch for each cell, complying with requirements in "Collection Basin Heater" Article.
9. Vibration switch for each fan, complying with requirements in "Vibration Switch" Paragraph in "Controls" Article.
10. Single-point, field-power connection to a fused disconnect switch.
 - a. Branch power circuit to each motor and electric basin heater and to controls with a disconnect switch.
 - b. NEMA-rated motor controller, hand-off-auto switch, and overcurrent protection for each motor. Provide variable-frequency controller with manual bypass and line reactors for each variable-speed motor indicated.
11. Factory-installed wiring outside of enclosures shall be in metal raceway; except, make connections to each motor and electric basin heater with liquidtight conduit.
12. Visual indication of status and alarm with momentary test push button for each motor.
13. Audible alarm and silence switch.
14. Visual indication of elapsed run time, graduated in hours for each motor.
15. Cooling tower shall have hardware to enable control system to remotely monitor and display the following:
 - a. Operational status of each motor.
 - b. Cooling tower leaving-fluid temperature.
 - c. Fan vibration alarm.
 - d. Collection basin high- and low-water-level alarms.

2.15 WATER TREATMENT

- A. Water Treatment System: Complete factory-installed system consisting of the following:
 1. Conductivity control of electrically operated valve designed to control totally dissolved solids levels and bleed rates.
 2. Piping associated with system.
 3. Interconnecting power and control wiring installed in corrosion-resistant metal raceway.

2.16 SERVICE ACCESS

- A. Doors:
 1. Large enough for personnel to access cooling tower internal components.
 2. Doors shall be hinged with handles operable from both sides of the door.
 3. Door materials shall match casing.
 4. Hinges and handles shall be stainless steel.
- B. External Ladders with Safety Cages: Aluminum fixed ladders, with ladder extensions to access external platforms and top of cooling tower from adjacent grade without the need for portable ladders. Comply with 29 CFR 1910.27.

- C. External Platforms with Handrails: Aluminum bar grating at cooling tower access doors when cooling towers are elevated and not accessible from grade.
- D. Handrail: Aluminum complete with kneerail and toeboard, around external platforms and top of cooling tower. Comply with 29 CFR 1910.23.
- E. Hardware: Galvanized steel when connecting galvanized-steel components and stainless steel when connecting other materials.

2.17 CAPACITIES AND CHARACTERISTICS (ALSO REFER TO CONTRACT DRAWINGS)

- A. Fan Drive Assembly:
 - 1. Type: Belt.
 - 2. Fan Motor:
 - a. Type: Inverter Duty variable speed.
- B. Sound Pressure Levels shall not exceed the following:
 - 1. Back Lp = 75dB at 5 ft, 65dB at 50 ft
 - 2. Connection End Lp = 73dB at 5 ft, 65dB at 50 ft
 - 3. Top Lp = 90dB at 5 ft, 76dB at 50 ft
 - 4. End Lp = 73dB at 5 ft, 65dB at 50 ft
 - 5. Air Inlet Lp = 83dB at 5 ft, 66dB at 50 ft
 - 6. Integrated ladders as required.
- C. Collection Basin Heater:
 - 1. Basin Water Temperature: 40 deg F (5 deg C).
 - 2. Outdoor Ambient Temperature: 0 deg F (minus 18 deg C) Minus 20 deg F (Minus 29 deg C).

2.18 SOURCE QUALITY CONTROL

- A. Performance Test: Factory test and certify cooling tower performance according to CTI STD 201RS.
- B. Factory Functional Tests:
 - 1. Test collection and distribution basins after assembly, and prove free of leaks.
 - 2. Test factory-installed electric/electronic water-level controls for proper operation.
 - 3. Test factory-installed electric basin heaters for proper operation.
 - 4. Test factory-installed fan and drive assemblies for proper operation.
 - 5. Test factory-installed control package for proper operation.
 - 6. Test access doors to ensure smooth operation and proper fit.

2.19 VIBRATION ISOLATION

- A. Vibration isolation base. Provide Vibro-Acoustics Model CTB or approved equal isolation base per cooling tower manufacturer's requirements. Finish shall be hot dipped galvanized. Isolators shall be restrained spring isolators Model SCSR with 3 inch of deflection. Base and isolation shall be approved by closed circuit evaporative fluid cooler manufacturer and coordinated with dimensions and final operating weight.

PART 3. EXECUTION

3.1 EXAMINATION

- A. Examine cooling towers before installation. Reject cooling towers that are damaged.
- B. Before cooling tower installation, examine roughing-in for tower support, anchor-bolt sizes and locations, piping, controls, and electrical connections to verify actual locations, sizes, and other conditions affecting cooling tower performance, maintenance, and operation.
 - 1. Cooling tower locations indicated on Drawings are approximate. Determine exact locations before roughing-in for piping, controls, and electrical connections.
 - 2. Verify sizes and locations of concrete bases and support structure with actual equipment.
 - 3. Verify sizes, locations, and anchoring attachments of structural-steel support structures.
 - 4. Verify sizes and locations of roof curbs, equipment supports, and roof penetrations with actual equipment.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install cooling towers on support structure.
- B. Equipment Mounting:
 - 1. Install cooling towers on cast-in-place concrete equipment bases.
 - 2. Comply with requirements for vibration isolation specified in Section 230548 "Vibration Controls for HVAC and Plumbing, and Fire Protection Equipment."
 - 3. Comply with requirements for vibration isolation devices specified in Section 230548.13 "Vibration Controls for HVAC."
- C. Install anchor bolts to elevations required for proper attachment to supported equipment.
- D. Maintain manufacturer's recommended clearances for service and maintenance.
- E. Maintain clearances required by governing code.
- F. Loose Components: Install components, devices, and accessories furnished by manufacturer with cooling tower, that are not factory mounted.
 - 1. Loose components shall be installed by Contractor under supervision of manufacturer's

factory-trained service personnel.

- G. All exterior pipes containing water shall be heat traced, insulated, jacketed, and labeled.
- H. Install cooling tower on structural beams and isolation bases.

3.3 PIPING CONNECTIONS

- A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Where installing piping adjacent to cooling towers, allow space for service and maintenance.
- C. Install flexible pipe connectors at pipe connections of cooling towers mounted on vibration isolators.
- D. Install motorized ball type bleed valves and pipe to a suitable location.
- E. Install drain piping with valve at cooling tower drain connections and at low points in piping.
- F. Discharge cooling tower overflows and drains, and piping drains as indicated.
- G. Makeup-Water Piping:
 - 1. Connect to makeup-water connections with motorized ball valves, shutoff valve, shock absorbers, backflow preventers, plugged tee with pressure gage, flow meter, and drain connection with valve and union.
 - 2. Pitch piping to cooling tower.
- H. Supply and Return Piping:
 - 1. Connect to entering-cooling-tower connections with shutoff valve, strainer, balancing valve, thermometer, plugged tee with pressure gage, flow meter, and drain connection with valve.
 - 2. Connect to leaving-cooling-tower connection with shutoff valve thermometer, plugged tee with full port ball valve for portable field instruments, and drain connection with valve.
 - 3. Make connections to cooling tower with a flanges.
 - 4. Pitch condenser water supply to cooling tower and condenser water suction away from cooling tower.
- I. Equalizer Piping:
 - 1. Piping requirements to match supply and return piping.
 - 2. Connect an equalizer pipe, full size of cooling tower connection, between tower cells.
 - 3. Connect to cooling tower with shutoff valve and drain connection with valve.
 - 4. Make connections to cooling tower with a flange.

3.4 ELECTRICAL POWER CONNECTIONS

- A. Connect field electrical power source to each separate electrical device requiring field electrical power. Coordinate termination point and connection type with Installer.
- B. Comply with requirements in Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for wiring connections.
- C. Comply with requirements in Section 260526 "Grounding and Bonding for Electrical Systems" for grounding connections.
- D. Install nameplate for each electrical connection indicating electrical equipment designation and circuit number feeding connection. Nameplate shall be laminated phenolic layers of black with engraved white letters at least 1/2 inch (13 mm) high. Locate nameplate where easily visible.

3.5 CONTROLS CONNECTIONS

- A. Install control and electrical power wiring to field-mounted control devices.
- B. Connect control wiring between cooling towers and other equipment to interlock operation as required to achieve a complete and functioning system.
- C. Connect control wiring between cooling tower control interface and control system for HVAC for remote monitoring and control of cooling towers. Comply with requirements in Section 230900 "Instrumentation and Controls of HVAC & Plumbing Systems".
- D. Install label at each termination indicating control equipment designation serving cooling tower and the I/O point designation for each control connection.

3.6 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform tests and inspections with the assistance of a factory-authorized service representative.
- D. Tests and Inspections: Comply with ASME PTC 23 or CTI ATC 105.
- E. Cooling towers will be considered defective if they do not pass tests and inspections.
- F. Prepare test and inspection reports.

3.7 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
- B. Inspect field-assembled components, equipment installation, and piping; controls; and electrical

connections for proper assemblies, installations, and connections.

- C. Obtain performance data from manufacturer.
 - 1. Complete installation and startup checks according to manufacturer's written instructions and perform the following:
 - a. Clean entire unit, including basins.
 - b. Verify that accessories are properly installed.
 - c. Verify clearances for airflow and for cooling tower servicing.
 - d. Check for vibration isolation and structural support.
 - e. Lubricate bearings.
 - f. Verify fan rotation for correct direction and for vibration or binding, and correct problems.
 - g. Adjust belts to proper alignment and tension.
 - h. Operate variable-speed fans through entire operating range and check for harmonic vibration imbalance. Set motor controller to skip speeds resulting in abnormal vibration.
 - i. Check vibration switch setting. Verify operation.
 - j. Verify water level in tower basin. Fill to proper startup level. Check makeup-water-level control and valve.
 - k. Verify operation of basin heater and control.
 - l. Verify that cooling tower air discharge is not recirculating air into tower or HVAC air intakes. Recommend corrective action.
 - m. Replace defective and malfunctioning units.
- D. Start cooling tower and associated water pumps. Follow manufacturer's written starting procedures.
- E. Prepare a written startup report that records the results of tests and inspections.

3.8 ADJUSTING

- A. Set and balance water flow to cooling tower.
- B. Adjust water-level control and bleed valve control for proper operating level.
- C. Adjust basin heater control for proper operating set point.
- D. Adjust all heat tracing operating setpoints.

3.9 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain cooling towers.
 - 1. Video record the training sessions.
 - 2. Instructor shall be factory trained and certified.
 - 3. Perform not less than eight hours of training.

4. Train personnel in operation and maintenance and to obtain maximum efficiency in plant operation.
5. Include instructional videos showing general operation and maintenance that are coordinated with operation and maintenance manuals.
6. Obtain Owner sign-off that training is complete.
7. Owner training shall be held at each school's project site.

END OF SECTION 236517

DIVISION 26 SECTION 26 05 00
COMMON WORK RESULTS FOR ELECTRICAL
TABLE OF CONTENTS

PART 1.	GENERAL	3
1.1.	RELATED DOCUMENTS	3
1.2.	ALTERNATES	3
1.3.	SUMMARY	3
1.4.	CONTRACTOR QUALIFICATION	4
1.5.	PERMITS, FEES, AND INSPECTIONS	4
1.6.	EXAMINATION OF SITE.....	5
1.7.	INTERPRETATION OF DOCUMENTS.....	5
1.8.	MATERIALS AND EQUIPMENT	6
1.9.	ELECTRICAL WORK UNDER OTHER DIVISIONS	6
1.10.	FIRE SAFE MATERIALS	7
1.11.	REFERENCED STANDARDS, CODES AND SPECIFICATIONS	7
1.12.	SUBMITTALS	8
1.13.	SUBMITTAL PROCEDURES.....	8
1.14.	SHOP DRAWINGS.....	11
1.15.	DEFINITIONS	12
1.16.	RECORD DRAWINGS.....	13
1.17.	WARRANTY	13
1.18.	OPERATION AND MAINTENANCE MANUALS.....	14
1.19.	INSTRUCTION.....	15
1.20.	INSTALLATION AND COORDINATION DRAWINGS	16
PART 2.	PRODUCTS.....	17
2.1.	SLEEVES FOR RACEWAYS AND CABLES	17
2.2.	GROUT	17
PART 3.	EXECUTION.....	17
3.1.	TEMPORARY FACILITIES	17
3.2.	COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION.....	18
3.3.	SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS	19
3.4.	FIRESTOPPING	19
3.5.	SUPPORTS, HANGERS AND FOUNDATIONS	20
3.6.	PROVISIONS FOR ACCESS	20
3.7.	PAINTING AND FINISHES.....	21
3.8.	COLOR SELECTION	21
3.9.	PROTECTION OF WORK	21
3.10.	OPERATION OF EQUIPMENT.....	22
3.11.	TESTING AND ADJUSTMENT	22
3.12.	WALL AND FLOOR PENETRATIONS.....	22
3.13.	EQUIPMENT BY OTHERS	23
3.14.	OUTAGES.....	23
3.15.	CUTTING AND PATCHING	23
3.16.	PENETRATION OF WATERPROOF CONSTRUCTION	23
3.17.	CONCRETE AND MASONRY WORK.....	23
3.18.	CONNECTIONS AND ALTERATIONS TO EXISTING WORK	24
3.19.	COORDINATION.....	24

3.20. DEMOLITION	24
3.21. EXCAVATION AND BACKFILLING	26
END OF SECTION	27

SECTION 26 05 00 - COMMON WORK RESULTS FOR ELECTRICAL

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. ALTERNATES

- A. Refer to Division 01 Section 012300, "Alternates", for description of work under this Division affected by Alternates.

1.3. SUMMARY

- A. Section Includes:
 - 1. Electrical equipment coordination and installation.
 - 2. Sleeves for raceways and cables.
 - 3. Grout.
 - 4. Common electrical installation requirements.
- B. Provide all labor, materials, equipment, and services necessary for and incidental to the complete installation and operation of all electrical work.
- C. Unless otherwise specified, all submissions shall be made to, and acceptances and approvals made by the Architect and the Engineer.
- D. Contract Drawings are generally diagrammatic and all offsets, fittings, transitions and accessories are not necessarily shown. Furnish and install all such items as may be required to fit the work to the conditions encountered.
- E. Arrange conduits, equipment, and other work generally as shown on the Contract Drawings, providing proper clearance and access. Where departures are proposed because of field conditions or other causes, prepare and submit detailed shop drawings for approval in accordance with Article "Submittals" specified below. The right is reserved to make reasonable changes in location of equipment, boxes, conduit/wiring, and devices, up to the time of rough-in or fabrication.
- F. Conform to the requirements of all rules, regulations and codes of local, state and federal authorities having jurisdiction.
- G. Coordinate the work under Division 26 with the work of all other construction trades.
- H. Be responsible for all construction means, methods, techniques, procedures, and phasing sequences used in the work. Furnish all tools, equipment and materials necessary to properly perform the work in first class, substantial, and workmanlike manner, in accordance with the full intent and meaning of the Contract Documents.

1.4. CONTRACTOR QUALIFICATION

- A. Any Contractor or Subcontractor performing work under Division 26 shall be fully qualified and acceptable to the Architect/Engineer and Owner. Submit the following evidence when requested:
 - 1. A list of not less than five comparable projects which the Contractor completed.
 - 2. Letter of reference from not less than three registered professional engineers, general contractors or building owners.
 - 3. Local and/or State License, where required.
 - 4. Membership in trade or professional organizations where required.
 - 5. Copy of Master Electrician's License.
- B. A Contractor is any individual, partnership, or corporation, performing work by contract or subcontract on this project.
- C. Acceptance of a Contractor or Subcontractor will not relieve the Contractor or subcontractor of any contractual requirements or his responsibility to supervise and coordinate the work, of various trades.
- D. Supervisory Qualifications: The electrical work on the project shall be under the direct supervision of a licensed Master Electrician.
- E. Qualifications of Installers:
 - 1. For the actual fabrication, installation, and testing of the work, shall use only thoroughly trained and experienced personnel who are completely familiar with the requirements of this work and with the installation recommendations of the manufacturers of the specified items.
 - 2. Utilize a full-time project foreman in charge of all electrical work. This person shall be fully qualified and experience in such work and shall be available, on site, at all times during Construction. All problems, questions, coordination, etc. related to electrical work shall take place through this person to the Architect.

1.5. PERMITS, FEES, AND INSPECTIONS

- A. Obtain all permits and pay taxes, fees and other costs in connection with the work. File necessary plans, prepare documents, give proper notices and obtain necessary approvals. Deliver inspection and approval certificates to Owner prior to final acceptance of the work.
- B. Permits and fees shall comply with Division 01 Section, General Requirements.
- C. Notify Inspection Authorities to schedule inspections of work.
- D. Notify Engineer in advance of scheduled inspections.
- E. An electrical foreman, superintendent or other supervisor shall be in attendance for all

scheduled inspections.

1.6. EXAMINATION OF SITE

- A. Examine the site, determine all conditions and circumstances under which the work must be done, and make all necessary allowances for same. No additional cost to the Owner will be permitted for Contractor's failure to do so.
- B. Examine and verify specific conditions described in individual Specifications sections.
- C. Verify that utility services are available, of the correct characteristics, and in the correct locations.

1.7. INTERPRETATION OF DOCUMENTS

- A. Any discrepancies between Drawings, Specifications, Drawings and Specifications, or within Drawings and Specifications shall be promptly brought to the attention of the Owner during the bidding period. No allowance shall subsequently be made by reason of failure to have brought said discrepancies to the attention of the Owner during the bidding period or of any error on the Bidder's part.
- B. The locations of products shown on Drawings are approximate. Place the devices to eliminate all interference with overhead ducts, piping, etc. Where any doubt exists, the exact location shall be determined by the Owner.
- C. No electrical equipment, e.g. panelboards, disconnect switches, motor controllers, etc. shall be installed beneath ductwork, piping, etc.
- D. All general trades and existing conditions shall be checked before installing any outlets, power wiring, etc.
- E. Equipment sizes shown on the Drawings are estimated. Before installing any wire or conduit, obtain the exact equipment requirements and install wire, conduit, or other item of the correct size for the equipment actually installed. However, wire and conduit sizes shown on the Drawings shall be taken as a minimum and shall not be reduced without written approval from the Owner.
- F. Where variances occur between the Drawings and Specifications or within either document itself, the item or arrangement of better quality, greater quality, or higher cost shall be included in the Contract Price. The Engineer will decide on the item and manner in which the work shall be installed.
- G. Contract Drawings are generally diagrammatic and all offsets, fittings, transitions, and accessories are not necessarily shown. Furnish and install all such items as may be required to fit the work to the conditions encountered. Arrange conduits, equipment, and other work generally as shown on the Contract Drawings, providing proper clearance and access. Where departures are proposed because of field conditions or other causes, prepare and submit detailed Shop Drawings for approval in accordance with Article "Submittals" as herein after specified. The right is reserved to make reasonable changes in location of equipment, conduit/wiring, and devices, up to the time of rough-in or fabrication.

- H. Work not specifically outlined, but reasonably incidental to the completion of the work, shall be included without additional compensation from the Engineer, and Owner.
- I. Perform the work in a first-class, substantial and workmanlike manner. Any materials installed which do not present an orderly and neat workmanlike appearance shall be removed and replaced when so directed by the Engineer, at the Contractor's expense.
- J. The complete set of Mechanical and Electrical Drawings and Specifications apply to this work. The successful Bidder shall familiarize himself with all other related documents.

1.8. MATERIALS AND EQUIPMENT

- A. Materials and equipment installed as a permanent part of the project shall be new, unless otherwise indicated or specified, and of the specified type and quality.
- B. Where material or equipment is identified by proprietary name, model number and/or manufacturer, furnish named item, or its equal, subject to approval by Engineer. Substituted items shall be equal or better in quality and performance and must be suitable for available space, required arrangement, and application. Submit all data necessary to determine suitability of substituted items, for approval.
- C. The suitability of named item only has been verified. Where more than one item is named, only the first named item has been verified as suitable. Substituted items, including items other than first named shall be equal or better in quality and performance to that of specified items, and must be suitable for available space, required arrangement and application. Contractor, by providing other than the first named manufacturer, assumes responsibility for all necessary adjustments and modifications necessary for a satisfactory installation. Adjustments and modifications shall include but not be limited to electrical, structural, support, and architectural work.
- D. Substitution will not be permitted for specified items of material or equipment where noted.
- E. All items of equipment furnished shall have a service record of at least five (5) years.

1.9. ELECTRICAL WORK UNDER OTHER DIVISIONS

- A. HVAC Equipment and Systems
 - 1. In general, any electrically operated or controlled equipment furnished under HVAC divisions shall be supplied with control wiring, transformers, contacts, etc.
 - 2. Division 26 shall provide power circuits to such equipment and a disconnecting means for each piece of equipment, as well as all electrical control equipment and wiring related thereto.
 - 3. Certain mechanical units are furnished from the factory with motor starters, contactors, transformers, fuses, wiring, etc., required for fans, pumps, etc. When this equipment is supplied from the factory, Division 26 shall coordinate with Division 23 such that only one set of starters, fuses, switches, etc. is provided.
 - 4. Some HVAC equipment must be protected by fuses, which shall be marked on the

equipment nameplate. In these instances, if the equipment has an integral non-fused disconnecting means, the fusible safety switch indicated on the electrical drawings must remain per NEC Article 440.

5. In general, control and interlock equipment (including, but not limited to wiring, conduit, transformers, relays, contacts, etc.) for HVAC equipment and systems is furnished under Division 23. Division 26 shall install and connect all equipment as necessary.
6. HVAC equipment refers to, but is not limited to the following:
 - a. ATC Panels
 - b. Closed Circuit Evaporative Fluid Cooler
 - c. Cooling Tower
 - d. Ductwork/Piping
 - i. Do not install any electrical equipment, including but not limited to panelboards, safety switches, motor controllers, etc. beneath ductwork/piping. Where this cannot be accomplished due to field conditions, notify the Engineer in writing.
 - e. Heating/Cooling Pump
7. To ensure proper electrical coordination between the electrical components supplied under Division 26 and the equipment supplied under Division 23, a schedule shall be submitted, prior to start of work, for review by the Engineer with the following column headings:
 - a. Equipment or Item
 - b. HP or KVA
 - c. Voltage and Phase
 - d. Power Factor
 - e. Capacitor
 - f. Motor Starter
 - g. Disconnect
 - h. Controls
 - i. Remarks

1.10. FIRE SAFE MATERIALS

- A. Unless otherwise indicated, materials and equipment shall conform to UL, NFPA and ASTM standards for fire safety with smoke and fire hazard rating not exceeding flame spread of 25 and smoke developed of 50.

1.11. REFERENCED STANDARDS, CODES AND SPECIFICATIONS

- A. Specifications, Codes and Standards listed below are included as part of this Specification, latest edition:
 1. ADA - Americans with Disabilities Act
 2. ANSI - American National Standards Institute

3.	ASTM	-	American Society for Testing and Materials
4.	CSA	-	Canadian Standards Association
5.	EPA	-	Environmental Protection Agency
6.	FM	-	Factory Mutual
7.	IBC	-	International Building Code
8.	IEEE	-	Institute of Electrical and Electronics Engineers
9.	NEC	-	National Electrical Code
10.	NECA	-	National Electrical Contractors Association
11.	NEMA	-	National Electrical Manufacturers Association
12.	NFPA	-	National Fire Protection Association
13.	OSHA	-	Occupational Safety and Health Act
14.	UL	-	Underwriters' Laboratories

- B. Electrical construction materials shall, where a listing is normal for the particular class of material, be listed in Electrical Construction Materials List of the Underwriters' Laboratories, Inc. (U.L.) and shall bear the listing label. Electrical equipment shall, where a listing is normal for the particular class of equipment, be listed in the Electrical Appliance and Utilization Equipment List of the Underwriters' Laboratories, Inc. (U.L.) and shall bear the listing label. Materials and equipment listed and labeled as "approved for the purpose" by other nationally recognized testing laboratory, inspection agency or approved organization (such as E.T.L. or Factory Mutual) shall be acceptable.

1.12. SUBMITTALS

- A. Product Data: Include complete descriptive product data for items specified in Part 2 of this Section.

1.13. SUBMITTAL PROCEDURES

- A. Refer to Division 01 Section, "Submittal Procedures", for requirements in addition to those indicated herein.
- B. Equipment, materials, installation, workmanship and arrangement of work are subject to review and acceptance. No substitution will be permitted after acceptance of equipment or materials except where such substitution is considered by the Engineer, to be in the best interest of the Owner.
- C. After acceptance of Material and Equipment List, submit three (3) copies, or more as required under the General Conditions, of complete descriptive data for all items as outlined below.

- D. Electronic submittals shall be prepared as a Portable Document Format (PDF) file and shall include as page 1 the Contractor's stamp, followed by the submittal contents. Submittal form shall identify the Project, Contractor, Subcontractor or Supplier, and pertinent Contract Document references.
- E. Submittals shall consist of specifications, product data sheets, manufacturer's catalog cuts, dimensional shop drawings, wiring diagrams, installation instructions, samples, and any other information necessary to indicate complete compliance with Contract Documents.
- F. Submittals shall include, but not be limited to, the following information: size, type, functional characteristics, compliance with standards in Division 26, required service access which shall be suitable for intended location and use, electrical service connections and requirements, and deviations from Contract Document requirements.
- G. Identify submittals, indicating intended application, location and service of submitted items. Refer to Specification sections or paragraphs and Drawings where applicable.
- H. Clearly indicate exact type, model number, style, size, operating characteristics, ratings, options and special features of proposed item specifically for application to this project. Submittals of a general nature will not be acceptable.
- I. Submit actual operating conditions or characteristics for all equipment where required capacities are indicated. Factory order forms showing only required capacities will not be acceptable. Call attention, in writing, to deviation from contract requirements.
- J. Thoroughly review and stamp all submittals to indicate compliance with contract requirements prior to submission. Coordinate installation requirements and all electrical requirements for equipment submitted. The Contractor shall be responsible for correctness of all submittals.
- K. Submittals will be reviewed for general compliance with design concept in accordance with Contract Documents, but dimensions, quantities, or other details will not be verified.
- L. For any submittal requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold Contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.
- M. For substituted items, clearly list on the first page of the submittal all differences between the specified item and the proposed item. The Contractor shall be responsible for corrective action and maintaining the Specification requirements if differences have not been clearly indicated in the submittal.
- N. Where proposals to use an item of equipment or application other than that specified or detailed on the Contract Drawings, which requires any redesign of the structure, partitions, foundation, HVAC, piping, wiring, or any other part of the mechanical, electrical, or architectural layout, all such redesign and all new drawings and detailing required thereafter shall be prepared by the Contractor at his own expense for review by the Owner's representative before any such work is implemented.
- O. All Contractor-proposed changes and revisions shall be at the Contractor's risk and

expense. The Contractor shall fully coordinate all revisions, substitutions and changes with other trades for a complete, code compliant, and fully functional installation.

- P. Acceptance will not constitute waiver of contract requirements unless deviations are specifically indicated and clearly noted. Use only final or corrected submittals and data prior to fabrication and/or installation.
- Q. Every submittal including, but not limited to the list below, shall be forwarded with its own transmittal as a separate, distinct submittal. Identify all submittals by the name of the item/system and the applicable Specification Section and/or Drawing number. Grouping of items/systems that are not related shall be unacceptable.
- R. Items and Systems
 - 1. Access Doors
 - 2. Analysis & Coordination Study
 - 3. Arc Flash Hazard Analysis
 - 4. Arc Flash Hazard Labels
 - 5. Circuit Breakers
 - 6. Conductors and Cables - 600V or Less
 - 7. Conduit and Raceway
 - 8. Connectors and Splices
 - 9. Electric Heating Cables and Controllers
 - 10. Electrical Connection Coordination Schedule
 - 11. Equipment Nameplates/Labels
 - 12. Firestopping Materials
 - 13. Fuses, 600V or Less
 - 14. Ground Conductors
 - 15. Grout
 - 16. Hangers and Supports
 - 17. Identification Products
 - 18. Installation/Coordination Drawings
 - 19. Installer Certificates

20. Junction and Pull Boxes
 21. Motor Controllers
 22. Operation and Maintenance Manual
 23. Outlet and Device Boxes
 24. Panelboard Circuit Directories
 25. Panelboards
 26. Qualification Data
 27. Receptacles
 28. Record Drawings
 29. Sleeves
 30. Surface Metal Raceway
 31. Surge Protective Devices
 32. Testing Agency Qualifications
 33. Test Reports
 34. Toggle/Snap Switches
 35. Weatherproof Boxes and Covers
 36. Wiring Diagrams
- S. Submit for approval any other submittals as required by the Engineer or Owner. No item listed above shall be delivered to the site, or installed, until approved. After the proposed materials have been approved, no substitution will be permitted except where approved by the Engineer.
- T. For resubmissions, the Contractor must address in writing all of the Engineer's comments on the original submission to verify compliance.

1.14. SHOP DRAWINGS

- A. Prepare and submit Shop Drawings for all electrical equipment, specially fabricated items, modifications to standard items, specially designed systems where detailed design is not shown on the Contract Drawings, or where the proposed installation differs from that shown on Contract Drawings.
- B. Shop drawings shall include identification of products being installed, compliance with specified standards, notation of coordination requirements, notation of dimensions verified by field measurement, etc. Do not base shop drawings on reproductions of the Contract

Documents or standard printed data.

- C. Submit shop drawings concurrent with product data. Shop drawings received without associated product data will be returned without review.
- D. Submit for approval schematic diagrams of each electrical system installed in the building, including but not limited to Riser Diagrams and Schematic Wiring Diagrams:
- E. Shop Drawing diagrams shall indicate device location, service, type, make, model number and the identification number of each device in the particular system. Following approval by all authorities, the diagrams shall be inserted into the O&M Manual specified herein.
- F. Submit for approval any other shop drawings as required by the Engineer or Owner. No item listed above shall be delivered to the site, or installed, until approved. After the proposed materials have been approved, no substitution will be permitted except where approved by the Engineer.
- G. For any shop drawing requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold Contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return for any reason.
- H. Refer to individual Specification Sections and Contract Drawings for additional shop drawing requirements.
- I. For resubmissions, the Contractor must address in writing all of the Engineer's comments on the original submission to verify compliance.

1.15. DEFINITIONS

- A. Approve: To permit use of material, equipment or methods conditional upon compliance with contract documents requirements.
- B. Building Line: Exterior wall of building.
- C. Concealed: Hidden from sight in chases, formed spaces, shafts, hung ceilings, or embedded in construction.
- D. Conduits: Include conduit, all fittings, identification, and other accessories relative to such conduit.
- E. Contractor: The Electrical Contractor and any of his subcontractors, vendors, suppliers, or fabricators.
- F. EPDM: Ethylene-propylene-diene terpolymer rubber
- G. Exposed: Not installed underground or concealed as defined above.
- H. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceiling, unexcavated spaces, crawl spaces, and tunnels.

- I. Furnish and install or Provide: To supply, erect, install, and connect to complete for readiness for regular operation, the particular work referred to.
- J. Location, Damp: Locations protected from water and not subject to saturation with water or other liquids, but subject to moderate degrees of moisture. Examples of such locations include interior locations such as basements, crawlspaces, attics, cold-storage rooms, etc...
- K. Location, Dry: A location not normally subject to dampness or wetness. A dry location may temporarily be subject to dampness or wetness during building construction.
- L. Location, Wet: Locations subject to saturation with water or other liquids, locations exposed to weather, and installations underground or in concrete slabs or masonry in direct contact with the Earth. Examples of such locations include all exterior locations (including those under canopies, roofed open porches, etc...) commercial kitchens, and vehicle washing areas.
- M. NBR: Acrylonitrile-butadiene rubber.
- N. Review: Limited observation or checking to ascertain general conformance with design concept of the work and with information given in contract documents. Such action does not constitute a waiver or alteration of the contract requirements.

1.16. RECORD DRAWINGS

- A. Upon completion of the electrical installations, the Contractor shall deliver to the Engineer one complete set of prints of the electrical Contract Drawings which shall be legibly marked in red pencil to show all changes and departures of the installation as compared with the original design. They shall be suitable for use in preparation of Record Drawings.
- B. Contractor shall incorporate all sketches, addendums, value engineering, change orders, etc., into record drawings prior to delivering the same to the Architect.

1.17. WARRANTY

- A. Contractor's attention is directed to warranty obligations contained in the General Conditions.
- B. The above shall not in any way void or abrogate equipment manufacturer's guarantee or warranty. Certificates of equipment manufacturer's warranties shall be included in the operations and maintenance manuals.
- C. The Contractor guarantees for a two (2) year period from the time of final acceptance by the Owner:
 - 1. That the work contains no faulty or imperfect material or equipment or any imperfect, careless, or unskilled workmanship.
 - 2. That all work, equipment, machines, devices, etc. shall be adequate for the use to which they are intended, and shall operate with ordinary care and attention in a satisfactory and efficient manner.

3. That the Contractor will re-execute, correct, repair, or remove and replace with proper work, without cost to the Owner, any work found to be deficient. The Contractor shall also make good all damages caused to their work or materials in the process of complying with this section.
4. That the entire work shall be water-tight and leak-proof.

1.18. OPERATION AND MAINTENANCE MANUALS

- A. The Contractor shall prepare three (3) hard copies and one (1) electronic copy of the Operation and Maintenance Manual for each of the six schools on the project and shall deliver these copies of the manual to the Owner. Provide one (1) electronic copy for each hard copy set of the O&M manual.
- B. The manual shall be as specified herein. The manual must be approved and will not be accepted as final until so stamped.
- C. Hard copies of the manual shall be bound in three-ring loose-leaf binders similar to National No. 3881 with the following title lettered on the front and spine of the binder: *Operation and Maintenance Manual - Indian River School District – (The appropriate name of the school where the manual will be stored) – Heat of Rejection Equipment Replacement – Electrical.*
 1. Provide divider tabs and table of contents for organizing and separating information. Tab titling shall be clearly printed under reinforced plastic tabs.
 2. If more than one (1) binder is required, volume numbers shall be included on front and spine of each volume.
 3. No sheets larger than 8-1/2 inches x 11 inches shall be used, except sheets that are neatly folded to 8-1/2 inches x 11 inches and used as a pull-out.
- D. Electronic copies of the manual shall be saved on USB flash drives, and shall be in searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of volume 1 (if applicable) of hard copies of the manual.
- E. Provide the following data in the manual:
 1. As first entry, an approved letter indicating the starting/ending time of Contractor's warranty period.
 2. Directory listing names, addresses, e-mail addresses, and telephone numbers for, Engineer, Contractor, Sub-contractor(s), equipment suppliers, sales and authorized service representatives.
 3. Maintenance operation and lubrication instructions on each piece of equipment furnished.
 4. Complete catalog data on each piece of electrical equipment furnished including approved Shop Drawing/Submittal with Engineer's Comments (if any).

5. Manufacturer's extended limited warranties on equipment.
 6. Catalog data of all equipment, starters, etc. shall include wiring diagrams, parts list and assembly drawing(s).
 7. Access panel charts with index illustrating the location and purpose of access panels.
 8. Approved Electrical Certificates, including certificate of approval from electrical inspector.
 9. List of extra materials turned over to Owner, with transmittal/receipt signed by Owner.
 10. Sign-in sheets from demonstration and training sessions.
 11. Start-up and test reports for equipment.
- F. Additional items identified within other Sections of these Specifications.
- G. Submit Operation and Maintenance Manual prior to the anticipated date of Substantial Completion for Engineer review and approval. Substantial Completion requires that Operation and Maintenance Manuals be reviewed and approved.

1.19. INSTRUCTION

- A. Upon completion of all work, thoroughly instruct the Owner's representatives in the proper operation and maintenance of all electrical equipment and systems.
- B. Instructions shall be done only after completed systems have been put into operation and tested for proper operation and performance.
- C. Instructions shall be given only by experts in the equipment or system and shall include descriptions and demonstrations of procedures of operation, data record keeping, etc.
- D. Furnish the necessary technicians, skilled workers, and helpers to operate the electrical systems and equipment of the entire project for one (1) 8-hour day.
- E. Where specified in technical sections, provide longer periods required for specialized equipment.
- F. The Operation and Maintenance Manual shall be available at the time of the instructions, for use by Instructors and Owner personnel.
- G. Deliver all instruction materials to the Owner prior to the formal instruction period.
- H. Schedule the general and specialized instruction periods for a time agreed upon by the Owner and Engineer.
- I. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

1.20. INSTALLATION AND COORDINATION DRAWINGS

- A. Prepare, submit and use composite installation and coordination drawings to assure proper coordination and installation of the work. Drawings shall include, but not be limited to the following:
 - 1. Mechanical Rooms indicating transformers, panelboards, enclosures, boxes, conduits, mechanical equipment, ductwork, and piping, etc...
 - 2. Electrical Rooms indicating switchboards, panelboards, enclosures, boxes, transformers, conduits, wireways, etc...
- B. Draw plans to a scale not less than ¼ inch equals one foot. Include plans, sections and elevations of the proposed work, showing all equipment (mechanical, plumbing and electrical), conduit and wiring in the areas involved. Fully dimension all work, horizontally and vertically. Show coordination with other work including piping, ductwork and other mechanical work, walls, doors, ceilings, columns, beams, joists and other architectural and structural work.
- C. Identify all equipment and devices on wiring diagrams. Where field connections are shown to factory-wired terminals, furnish manufacturer's literature showing internal wiring of equipment.
- D. Prepare, submit, and use scaled layout drawings indicating dimensions, clearances, and actual equipment dimensions. Layout Drawings shall include, but not be limited to the following:
 - 1. Pad-mounted equipment and equipment connections.
 - 2. Building penetrations.
- E. Prepare scaled coordination drawings in accordance with the Specifications. Indicate locations where space is limited for installation and access and where sequencing and coordination of installations are of importance to the efficient flow of the Work, including (but not necessarily limited to) the following:
 - 1. Indicate the proposed locations of power, lighting, and all special system raceways, equipment, and materials. Include the following:
 - a. Working space and dedicated space clearances per the NEC.
 - b. Clearances for equipment disassembly required for periodic maintenance.
 - c. Exterior wall and foundation penetrations.
 - d. Fire-rated wall and floor penetrations.
 - e. Equipment connections and support details.
 - 2. Indicate scheduling, sequencing, movement, and positioning of large equipment into the building during construction, including, but not limited to, the following: Major conduits and feeders.
 - 3. Prepare floor plans, elevations, and details to indicate penetrations in floors, walls, and ceilings and their relationship to other penetrations and installations.

4. The successful Bidder shall be responsible for indicating all raceways described in notes or indicated by home run symbols.
5. The complete set of Mechanical and Electrical Drawings and Specifications apply to this work. The successful bidder shall familiarize himself with all other related documents to avoid possible demolition and installation conflicts.

PART 2. PRODUCTS

2.1. SLEEVES FOR RACEWAYS AND CABLES

- A. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.

2.2. GROUT

- A. Nonmetallic, Non-Shrink Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, non-staining, mixed with water to consistency suitable for application and a 30-minute working time.

PART 3. EXECUTION

3.1. TEMPORARY FACILITIES

- A. General: Refer to the Division 01 Sections for general requirements of temporary facilities.
- B. Description: Furnish and install the necessary metering and distribution equipment for an adequate, 3-phase, 4-wire temporary electrical service and all temporary wiring, including step-down or step-up dry-type transformers as required. Exact requirements for temporary service shall be determined by the successful bidder.
- C. Attention is directed to the Occupational Safety and Health Act (OSHA), Americans with Disabilities Act (ADA) and National Electrical Code (NEC) requirements for electrical work on construction sites.
- D. Materials:
 1. Lights at each floor in each stair. At least one light outlet per 900 square feet on each floor.
 2. One 20-ampere circuit with ground fault protection for each 7500 square feet of gross floor area per floor to which various trades may attach their cords.
 3. One temporary power line in each corridor and lobby, including connections to saws, if required, with ground fault protection.
- E. Installation: Temporary lighting shall provide minimum foot candle levels for construction as follows:

AREA	FOOT CANDLE LEVEL
General construction area lighting, corridors, hallways and exit ways.	5
Electrical equipment rooms, active storerooms, shops, locker and dressing areas	10

- F. The Owner shall pay for all energy charges for temporary service.
- G. Obtain and pay for temporary electrical service for construction power.
- H. Provide all equipment, transformers, overcurrent devices, wires, connections, etc., for obtaining power from the existing electrical distribution system.
- I. Remove all temporary power installations and connections after permanent power is established and/or prior to completion of the project.

3.2. COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION

- A. Comply with NECA 1.
- B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- D. Install equipment with working space and dedicated space in strict accordance with NEC Article 110.
- E. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electrical equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- F. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.
- G. Verify exact electrical requirements for each piece of equipment receiving one or more electrical connections, including but not limited to voltage, phase, and maximum fuse/overcurrent protection device rating. Provide electrical circuit of proper characteristics to serve provided equipment.
- H. Include any and all items required by the National Electrical Code and/or field conditions for the proper connection and installation of each piece of equipment.
- I. Make all connections to equipment in accordance with manufacturer's instructions.

- J. Right of Way: Give to piping systems installed at a required slope.
- K. Coordinate electrical work under other Divisions in accordance with Part 1 of this Section, Article "Electrical Work Under Other Divisions".

3.3. SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Electrical penetrations occur when raceways, cables, wireways, cable trays, or busways penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used.
- C. Cut sleeves to length for mounting flush with both surfaces of walls.
- D. Sleeves installed in floors shall extend 2 inches (50 mm) above finished floor level unless otherwise indicated on the Contract Drawings.
- E. Size pipe sleeves to provide 1/4-inch (6.4-mm) annular clear space between sleeve and raceway or cable, unless indicated otherwise.
- F. Seal space outside of sleeves with grout for penetrations of concrete and masonry
- G. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
- H. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint.
- I. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials. Comply with requirements of Division 26 Section 260258, "Firestopping for Electrical Systems".
- J. Aboveground, Exterior-Wall Penetrations: Seal penetrations using steel pipe sleeves and joint sealant/grout.
- K. Underground, Exterior-Wall Penetrations: Install cast-iron pipe sleeves. Size sleeves to allow for 1-inch (25-mm) annular clear space between raceway or cable and sleeve for installing mechanical sleeve seals. Seal interior of each raceway with Foam Duct Sealant as specified herein.

3.4. FIRESTOPPING

- A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for electrical installations to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 26 Section 260528, "Firestopping for Electrical Systems".

3.5. SUPPORTS, HANGERS AND FOUNDATIONS

- A. Provide supports, hangers, braces, attachments and foundations required for the work. Support and set the work in a thoroughly substantial and workmanlike manner without placing strains on materials, equipment, or building structure, submit shop drawings for approval. Coordinate all work with the requirements of the structural division.
- B. Supports, hangers, braces, and attachments shall be standard manufactured items or fabricated structural steel shapes. All interior hangers shall be galvanized or steel with rust inhibiting paint. All exterior hangers shall be constructed of stainless steel utilizing stainless steel rods, nuts, washers, bolts, etc.
- C. Refer to Division 26 Section 260529, "Hangers and Supports for Electrical Systems", for additional requirements.

3.6. PROVISIONS FOR ACCESS

- A. The Contractor shall provide access panels and doors for all concealed equipment, and other devices requiring maintenance, service, adjustment or manual operation.
- B. Where access doors are necessary, furnish and install manufactured painted steel door assemblies consisting of hinged door, key locks, and frame designed for the particular wall or ceiling construction. Properly locate each door. Door sizes shall be a 12 inches x 12 inches for hand access, 18 inches x 18 inches for shoulder access and 24 inches x 24 inches for full body access where required. Review locations and sizes with Architect prior to fabrication. Provide U.L. approved and labeled access doors where installed in fire rated walls or ceilings. Doors shall be Milcor Metal Access Doors as manufactured by Inland-Ryerson, Mifab, or approved equal.
 - 1. Acoustical or Cement Plaster: Style B
 - 2. Hard Finish Plaster: Style K or L
 - 3. Masonry or Dry Wall: Style M
- C. Where access is by means of lift-out ceiling tiles or panels, mark each ceiling grid using small color-coded and numbered tabs. Provide a chart or index for identification. Place markers within ceiling grid not on ceiling tiles.
- D. Access panels, doors, etc. described herein shall be furnished under the section of Specifications providing the particular service and to be turned over to the pertinent trade for installation. Coordinate installation with installing Contractor. All access doors shall be painted in baked enamel finish to match ceiling or wall finish.
- E. Submit shop drawings indicating the proposed location of all access panels/doors. Access doors in finished spaces shall be coordinated with air devices, lighting and sprinklers to provide a neat and symmetrical appearance.
- F. Provide sufficient access and working space for repair and maintenance about all lighting and electrical equipment to permit ready and safe operation and maintenance of such equipment in accordance with OSHA 29 CFR 1910 Subpart D and 1910.303(g).

3.7. PAINTING AND FINISHES

- A. Provide protective finishes on all materials and equipment. Use coated or corrosion-resistant materials, hardware and fittings throughout the work. Paint bare, untreated ferrous surfaces with rust-inhibiting paint. All exterior components including supports, hangers, nuts, bolts, washers, vibration isolators, etc. shall be stainless steel.
- B. Clean surfaces prior to application of insulation, adhesives, coatings, paint, or other finishes.
- C. Provide factory-applied finishes where specified. Unless otherwise indicated factory-applied paints shall be baked enamel with proper pretreatment.
- D. Protect all finishes and restore any finishes damaged as a result of work under Division 26 to their original condition.
- E. The preceding requirements apply to all work, whether exposed or concealed, as defined herein.
- F. Remove all construction marking and writing from exposed equipment, conduit, boxes, and building surfaces. Do not paint manufacturer's labels or tags.
- G. All exterior equipment and conduits shall be painted to match adjacent surface in color as selected by Owner, unless otherwise indicated by the Owner.
- H. All exposed conduit, boxes, equipment, etc. in finished spaces shall be painted. Colors shall be as selected by the Owner and conform to ANSI Standards.
- I. Do not paint panelboard fronts, motor controllers, safety switches, grounding busbars, equipment nameplates, warning labels, etc.

3.8. COLOR SELECTION

- A. Color of finishes shall be as selected by the Owner.

3.9. PROTECTION OF WORK

- A. Protect work, material and equipment from weather and construction operations before and after installation. Properly store and handle all materials and equipment.
- B. Cover temporary openings in conduits and equipment to prevent the entrance of water, dirt, debris, or other foreign matter. Deliver conduits with factory applied end caps.
- C. Cover or otherwise protect all finishes.
- D. Replace damaged materials, devices, finishes and equipment.
- E. Protect stored conduits from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, where stored inside.

3.10. OPERATION OF EQUIPMENT

- A. Clean all systems and equipment prior to initial operation for testing, or other purposes. Lubricate, adjust, and test all equipment in accordance with manufacturer's instructions. Do not operate equipment unless all proper safety devices or controls are operational. Provide all maintenance and service for equipment that is authorized for operation during construction.
- B. Where specified, or otherwise required, provide the services of the manufacturer's factory-trained servicemen or technicians to start up the equipment. Where factory start-up of equipment is not specified, provide field start-up by qualified technician.
- C. Submit factory start-up sheets or field start-ups sheets for all equipment prior to the commencement of testing.
- D. Upon completion of work, clean and restore all equipment to new conditions; replace expendable items.

3.11. TESTING AND ADJUSTMENT

- A. Perform all tests which are specified or required to demonstrate that the work is installed and operating properly. Where formal tests are required, give proper notices and perform all necessary preliminary tests to assure that the work is complete and ready for final test.
- B. Adjust all systems, equipment and controls to operate in a safe, efficient and stable manner.
- C. On all circuits, 600 volts or less, provide circuits that are free from ground faults, short circuits and open circuits.
- D. Other tests of a specific nature for special equipment shall be as specified under the respective equipment.
- E. Submit all test results to the Engineer for approval.

3.12. WALL AND FLOOR PENETRATIONS

- A. All penetrations of partitions, ceilings, roofs and floors under Division 26 shall be sleeved, sealed, and caulked as specified herein.
- B. All penetrations of fire rated assemblies shall be sleeved, sealed, caulked and protected to maintain the rating of the wall, roof, or floor. Fire Marshal approved U.L. assemblies shall be utilized. See Division 26 Section 260528, "Firestopping for Electrical Systems".
- C. Provide conduit escutcheons for all exposed conduit penetrations in finished interior spaces and all exposed exterior penetrations.
- D. Conduit sleeves:
 - 1. Galvanized steel pipe, standard weight where pipes are exposed and roofs and concrete and masonry walls. On exterior walls provide anchor flange welded to perimeter.

2. Twenty-two (22) gauge galvanized steel elsewhere.

3.13. EQUIPMENT BY OTHERS

- A. This Contractor shall make all system connections required to equipment furnished and installed under other divisions or furnished by the Owner. Connections shall be complete in all respects to render this equipment functional to its fullest intent.
- B. It shall be the responsibility of the supplier of the equipment to furnish complete instructions for connections. Failure to do so will not relieve the Contractor of any responsibility for improper equipment operation.

3.14. OUTAGES

- A. Provide a minimum of five (5) days' notice to schedule outages. The Contractor shall include in their bid outages and/or work in occupied areas to occur on weekends, holidays, or at night. Coordinate and get approval of all outages with the Owner.
- B. Submit Outage Request Form, attached at the end of this Section, to Owner for approval.

3.15. CUTTING AND PATCHING

- A. Accomplish all cutting and patching necessary for the installation of work under Division 26. Damage resulting from this work to other work already in place, shall be repaired at Contractor's expense. Where cutting is required, perform work in neat and workmanlike manner. Restore disturbed work to match and blend with existing construction and finish, using materials compatible with the original. Use mechanics skilled in the particular trades required.

3.16. PENETRATION OF WATERPROOF CONSTRUCTION

- A. Coordinate the work to minimize penetration of waterproof construction, including roofs, exterior walls, and interior waterproof construction. Where such penetrations are necessary, furnish and install all necessary curbs, sleeves, flashings, fittings and caulking to make penetrations absolutely watertight.

3.17. CONCRETE AND MASONRY WORK

- A. Furnish and install concrete and masonry work for equipment foundations, supports, pads, and other items required under Division 26. Perform work in accordance with requirements of Division 03 and other applicable Divisions of these Specifications.
- B. Concrete shall achieve compressive strength not less than 3,000 psi after 28 days.
- C. Grout shall be non-shrink, high strength mortar, free of iron of chlorides and suitable for use in contact with all metals, without caps or other protective finishes. Apply in accordance with manufacturer's instructions and standard grouting practices.
- D. Properly align, level, and grout all equipment where necessary.

3.18. CONNECTIONS AND ALTERATIONS TO EXISTING WORK

- A. Unless otherwise noted on the Drawings, where existing electrical work is removed, including hangers, to a point below finished floors or behind finished walls and capped, such point shall be far enough behind finished surfaces to allow for installation of normal thickness of required finish material.
- B. Where work specified in Division 26 connects to existing equipment, conduits, etc., Contractor shall perform all necessary alterations, cuttings, fittings, etc., of existing work as may be necessary to make satisfactory connections between new and existing work, and to leave completed work in a finished and workmanlike condition.
- C. Where the work specified under Division 26, or under other Divisions, requires relocation of existing equipment, conduit etc., Contractor shall perform all work and make necessary changes to existing work as may be required to leave completed work in a finished and workmanlike condition.
- D. Where the relocation of existing equipment is required for access or the installation of new equipment, the Contractor shall temporarily remove and/or relocate and re-install as required to leave the existing and new work in a finished and workman like condition.

3.19. COORDINATION

- A. Coordinate arrangement, mounting, and support of electrical equipment:
 - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
 - 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
 - 3. To allow right of way for piping and conduit installed at required slope.
 - 4. So connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
 - 5. To provide working space and dedicated space clearances per NEC Article 110.26.
- B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- C. Coordinate location of access panels and doors for electrical items that are behind finished surfaces or otherwise concealed. Access doors and panels are specified in this Section.

3.20. DEMOLITION

- A. Unless otherwise noted all existing equipment, conduit, wire, etc., shall remain.
- B. Where existing equipment is indicated to be removed, all associated conduit, power, controls, insulation, hangers, supports and housekeeping pads, etc..., shall also be removed. Patch, paint and repair walls/roof/floor to match existing and/or new finishes.

- C. The Contractor shall be responsible for visiting the site and determining the existing conditions in which the work is to be performed.
- D. Where any abandoned conduits in existing floors, walls, ceilings, etc., conflict with new work, remove abandoned conduits as necessary to accommodate new work.
- E. The location of all existing equipment, conduits etc., indicated is approximate only and shall be checked and verified. Provide all new electrical work required to connect to or clear existing work as applicable.
- F. Maintain egress at all times. Coordinate egress requirements with the State Fire Marshal, the Owner and the Authority(ies) Having Jurisdiction (AHJ).
- G. Make provisions and include in bid all costs associated with confined entry/space requirements in crawl spaces and all other applicable OSHA regulations.
- H. Where required to maintain the existing systems in operation, temporarily back-feed existing systems from new equipment. Contractor shall temporarily extend existing conduit systems to new conduit systems.
- I. At completion of project all temporary conduit, wires, etc., shall be removed in their entirety.
- J. Existing conduit, equipment, wiring, etc., not required for re-use or re-installation in this project, shall be removed from the project site.
- K. Deliver to the Owner, on the premises where directed, existing equipment and materials which are removed and which are desired by the Owner or are indicated to remain the property of the Owner.
- L. All other materials and equipment which are removed shall become property of the Contractor and shall be promptly removed, from the premises, and disposed of by the Contractor, in an approved manner.
- M. Where conduit and wiring are removed, remove all conduit hangers which were supporting the removed conduit. Patch the remaining penetration voids with like materials and paint to match existing construction.
- N. Where required, provide and coordinate removal and re-installation of existing equipment. Take care to protect materials and equipment indicated for reuse. Contractor shall repair or replace items which are damaged. Contractor shall have Owner's representative present to confirm condition of equipment prior to demolition.
- O. Before demolition begins, and in the presence of the Owners representative, test and note all deficiencies in all existing systems affected by demolition but not completely removed by demolition. Provide a copy of the list of system deficiencies to the Owner and the Engineer.
- P. The Owner shall have the first right of refusal for all fixtures, devices and equipment removed by the Contractor.

- Q. All devices and equipment designated by the Owner to remain the property of the Owner shall be moved and stored by the Contractor at a location on site as designated by the Owner. It shall be the Contractor's responsibility to store all devices and equipment in a safe manner to prevent damage while stored.
- R. All existing equipment refused by the Owner shall become the property of the Contractor and shall be removed from the site by the Contractor in a timely manner and disposed of in a legal manner.
- S. Work Abandoned in Place: Cut and remove conduit a minimum of 2 inches beyond face of adjacent construction. Cap and patch surface to match existing finish.
- T. Temporary Disconnection: Remove, store, clean, reinstall, reconnect, and make operational equipment indicated for relocation.
- U. Terminate services and utilities in accordance with local laws, ordinances, rules and regulations.

3.21. EXCAVATION AND BACKFILLING

- A. General:
 - 1. Perform all necessary excavation, or installation of work under Division 26, in whatever materials or conditions encountered, using suitable methods and equipment.
 - 2. Accurately establish required lines and grades and properly locate the work.
 - 3. Determine the locations of all existing utilities before commencing the work.
- B. Excavation:
 - 1. Excavate only the required elevations. If excavation is carried below the foundation lines or other required limits, backfill the excess with concrete.
 - 2. Keep banks of trenches as nearly vertical as possible, and provide sheeting and/or shoring as required for protection of work and safety of personnel. Follow local, State, OSHA and other applicable Guidelines.
 - 3. Keep excavations dry. Protect excavations from freezing.
- C. Backfilling:
 - 1. Backfill excavations to the required elevations and restore surfaces to their original or required conditions.
 - 2. Backfill shall be similar material, free from objectionable matter such as rubbish, roots, stumps, brush, rocks and other sharp objects. Unless otherwise indicated, suitable material from the excavation may be used for backfill.
 - 3. Carefully place and mechanically tamp backfill in layers not exceeding 12 inches loose thickness. Compact to 95 percent minimum.

4. Do not backfill against frozen material. Do not use frozen material for backfill.

END OF SECTION

OUTAGE REQUEST FORM

DATE APPLIED: _____ BY: _____

DATE FOR OUTAGE: _____ FIRM: _____

START OUTAGE-TIME: _____ DATE: _____

END OUTAGE - TIME: _____ DATE: _____

AREAS AND ROOMS: _____

FLOOR(S): _____

AREA(S): _____

ROOM(S): _____

WORK TO BE PERFORMED: _____

SYSTEM(S): _____

REQUEST APPROVED BY: _____

(FOREMAN OR OTHER PERSON IN CHARGE)

PART 1 (FOR OWNER'S USE ONLY):

APPROVED: _____

YES ____ NO ____ BY: _____ DATE: _____

DATE/TIME-AS REQUESTED: _____ OTHER : _____

OWNER'S PRESENCE REQUIRED: _____

YES: ____ NO: ____ NAME: _____

POINT OF CONTACT: _____ PHONE: _____

DIVISION 26 SECTION 26 05 19
LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SUMMARY	3
1.3. SUBMITTALS	3
1.4. QUALITY ASSURANCE	3
1.5. DELIVERY, STORAGE, AND HANDLING	4
1.6. COORDINATION.....	4
1.7. PROJECT CONDITIONS	4
PART 2. PRODUCTS.....	5
2.1. MANUFACTURERS	5
2.2. BUILDING WIRES AND CABLES	6
2.3. CONNECTORS AND SPLICES	6
2.4. METAL CLAD (MC) CABLE.....	8
2.5. METAL CLAD (MC) CABLE CONNECTORS	8
2.6. INSULATING TAPE, PUTTY, RESIN AND SUPPORTS.....	9
PART 3. EXECUTION.....	9
3.1. EXAMINATION	9
3.2. PREPARATION	9
3.3. WIRE AND INSULATION APPLICATIONS.....	10
3.4. MC CABLE APPLICATIONS	11
3.5. INSTALLATION	11
3.6. CONNECTIONS	13
3.7. IDENTIFICATION.....	14
3.8. FIELD QUALITY CONTROL	14
END OF SECTION	15

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 19 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SUMMARY

- A. This Section includes building wires and cables and associated connectors, splices, and terminations for wiring systems rated 600 V and less.

1.3. SUBMITTALS

- A. Product Data: Provide for each cable assembly type, wire, cables, conductors, and connectors.
- B. Project Record Documents: Record actual locations of components and circuits.

1.4. QUALITY ASSURANCE

- A. Listing and Labeling: Provide wires and cables specified in this Section that are listed and labeled.
 - 1. The Terms Listed and Labeled: As defined in NFPA 70, Article 100.
 - 2. Listing and Labeling Agency Qualifications: A Nationally Recognized Testing Laboratory as defined in OSHA Regulation 1910.7.
- B. Comply with NEMA/Insulated Cable Engineers Association (ICEA) Standards.
- C. Comply with NECA Standard of Installation.
- D. Comply with NETA ATS - Acceptance Testing Specifications for Electrical Power Distribution Equipment and Systems.
- E. American Society for Testing and Materials (ASTM): Comply with requirements of the following:
 - 1. B3: Standard Specification for Soft or Annealed Copper Wire
 - 2. B8: Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
 - 3. D753: Standard Specification for General Purpose Polychloroprene Jacket for Wire and Cable
- F. Electrical Testing Laboratories (ETL): Provide wiring, cabling and connector products which are ETL listed and labeled.

- G. Institute of Electrical and Electronics Engineers (IEEE): Comply with the following standards which apply to wiring systems:
 - 1. 82: Test procedure for Impulse Voltage Tests on Insulated Conductors
 - 2. 241: Recommended Practice for Electric Power Systems in Commercial Buildings
- H. NFPA: Comply with NFPA 70 requirements for construction, installation and color coding of electrical wire, cable and connections.
- I. National Electrical Manufacturer's Association (NEMA): Comply with requirements of the following:
 - 1. WC70: Power Cables Rated 2000 Volts or Less for the Distribution of Electrical Energy.
- J. UL: Provide material conforming to the following standards:
 - 1. UL 83 - Thermoplastic-Insulated Wires and Cables.
 - 2. UL 486A - Wire Connectors and Soldering Lugs for Use with Copper Conductors
- K. UL Labels: Provide wiring, cabling and connector products which are UL listed and labeled.

1.5. DELIVERY, STORAGE, AND HANDLING

- A. Deliver wires and cables according to NEMA WC 26, Binational Wire and Cable Packaging Standard.
- B. Storage: Store wire and cable in a clean dry space in original containers. Protect products from weather, damaging fumes, construction debris and traffic.
- C. Handling: Handle wire and cable carefully to avoid abrading, puncturing and tearing wire and cable insulation and sheathing. Ensure that dielectric resistance integrity of wires/cables is maintained.

1.6. COORDINATION

- A. Coordinate layout and installation of cables with other installations.
- B. Revise locations and elevations from those indicated, as required to suit field conditions and as approved by Engineer.
- C. Determine required separation between cables and other work.
- D. Determine cable routing to avoid interference with other work.

1.7. PROJECT CONDITIONS

- A. Verify that field measurements are as shown on the Drawings.

- B. Feeder conductor sizes are based on copper as indicated on the Contract Drawings.
- C. Branch circuit conductor sizes are based on copper.
- D. Wire and cable routing shown on Drawings is approximate unless dimensioned. Route wire and cable as required to meet Project Conditions.
- E. Where wire and cable routing is not shown, and destination only is indicated, determine exact routing and lengths required.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Wires and Cables:
 - a. American Insulated Wire Corp.
 - b. BICC Brand Rex Company.
 - c. CME Wire and Cable.
 - d. Colonial Wire Company.
 - e. Encore Wire Corporation.
 - f. General Cable.
 - g. Senator Wire & Cable Company.
 - h. Southwire Company.
 - 2. Connectors and Accessories for Wires and Cables:
 - a. 3M Company; Electrical Products Division.
 - b. AMP Incorporated.
 - c. Buchanan.
 - d. General Signal; O Z/Gedney Unit.
 - e. Greaves Corporation.
 - f. Ideal Industries.
 - g. Monogram Company; AFC.
 - h. NSI Industries, Inc.
 - i. Square D Company; Anderson.
 - 3. Metal Clad (MC) Cable
 - a. Alcan Cable.
 - b. Atkore AFC Cable Systems.
 - c. Encore Wire Corporation.
 - d. General Cable.
 - e. Nexans.
 - f. Prysmian Cables and Systems.
 - g. Service Wire Company.
 - h. Southwire Company.

- i. United Copper Industries.
- 4. Metal Clad (MC) Connectors
 - a. Arlington Industries, Inc.
 - b. Bridgeport.
 - c. Crouse-Hinds.
 - d. Thomas & Betts.

2.2. BUILDING WIRES AND CABLES

- A. UL-listed building wires and cables with conductor material, insulation type, cable construction and rating as specified herein.
- B. Building wires and cables shall be annealed (soft) copper, 600 volt, Type THHN/THWN (dual-rated) single conductors rated 90°C dry / 75°C wet, with a minimum conductivity of 98 percent at 20°C (68°F), or a maximum resistivity of 1.7 micro-ohms per centimeter.
- C. Conductors shall meet or exceed requirements of all applicable ASTM specifications, UL Standard 83, UL Standard 1581, NEMA WC 70, Federal Specification A-A-59544 and shall be RoHS/REACH Compliant.
- D. Conductors shall be solid for 10 AWG and smaller, and stranded for 8 AWG and larger.
- E. Building wire and cables shall be color-coded using colors factory impregnated throughout the insulation and jacket. The following color code convention(s) shall be used except where existing systems have established another color code convention:
 - 1. 120/208-Volt, 3-Phase, 4-Wire System:
 - a. Phase A: Black
 - b. Phase B: Red
 - c. Phase C: Blue
 - d. Neutral: White
 - e. Ground: Green
 - 2. 277/480-Volt, 3-Phase, 4-Wire System:
 - a. Phase A: Brown
 - b. Phase B: Orange
 - c. Phase C: Yellow
 - d. Neutral: Gray
 - e. Ground: Green

2.3. CONNECTORS AND SPLICES

- A. UL listed, factory fabricated wiring connectors of size, ampacity rating, material, type, and class for application and service indicated. Comply with Project's installation requirements and as specified in Part 3 Article, "Wire and Insulation Applications".
- B. Split Bolt Connectors: Not acceptable.

- C. Solderless Pressure Connectors: High copper alloy terminal. May be used only for cable termination to equipment pads or terminals. Not approved for splicing.
- D. Spring Wire Connectors: Not acceptable.
- E. Mechanical Connectors: Bolted type tin-plated; high conductivity copper alloy; spacer between conductors; beveled cable entrances.
- F. Compression (crimp) Connectors: Long barrel; seamless, tin-plated electrolytic high conductivity copper tubing, internally beveled barrel ends. Connector shall be clearly marked with the wire size and type and proper number and location of crimps.
- G. Heat shrinkable tubing shall meet the requirements of ANSI C119.1-1986 for buried connections to 90 degrees C and shall be material flame-retarded per IEEE 383 Vertical Tray Flame Test.
- H. Motor connection kits shall consist of heat-shrinkable, polymeric insulating material over the connection area and a high dielectric strength mastic to seal the ends against ingress of moisture and contamination. Motor connection kits shall accommodate a range of cable sizes for both in-line and stub-type configurations. Connection kits shall be independent of cable manufacturer's tolerances.
- I. Wire Nut Connectors:
 - 1. Description: Twist-on wire connectors for branch circuit conductors 10 AWG and smaller with a color-coded housing.
 - 2. Construction: Flame-retardant polypropylene housing, rated for 105 degrees Celsius. Zinc-plated steel insert. Square-wire spring to maintain secure positive grip that will not relax over time, no pre-twisting required.
 - 3. Dimensions: Connectors shall be appropriately sized according to manufacturer's recommendation for the suitable wire sizes and voltage rating (600 volts minimum).
 - 4. Quality Assurance:
 - a. UL Listed to 486C and 94V-2 Flame Rating.
 - b. CSA Certified to C22.2 No. 188
 - c. RoHS Compliant
 - 5. Special Features:
 - a. Wire connectors for making grounding connections shall have green-colored housing and shall have opening at end of connector for grounding conductor to pass through for connection to metallic outlet boxes.
 - b. Wire connectors for all exterior and underground work and work in damp/wet interior locations shall be pre-filled with silicone-based sealant to protect against moisture and corrosion, and shall be UL Listed to 486D for use in damp/wet locations, including direct burial applications.

6. Basis of Design: Provide products by Ideal Industries, Inc. or approved equal.
- J. Insulated Connectors (for Conductors 8 AWG and Larger in Dry Locations)
1. Description: Multi-conductor connectors for low voltage (600V or less) circuits, insulated with high-dielectric strength plastisol, molded for precise fit and supplied with removable access plugs over the hex screws.
 2. Construction: Range-taking mechanical connector made of aluminum accepts both aluminum and copper conductors. Molded cover of UV stable, impact resistant polypropylene provides rugged protection. Mounting holes at each end of the connector for direct isolated mounting to wiring trough, panelboard, or wireway.
 3. Dimensions: Splices and connectors shall be appropriately sized according to manufacturer's recommendation for the suitable wire sizes, quantities, and voltage rating.
 4. Quality Assurance: UL listed. UV resistant.
 5. Special Features: Connectors shall be rated for temperatures from -45 degrees Celsius to 90 degrees Celsius.
 6. Basis of Design: IPLM/IPLMD Series as manufactured by Polaris, or approved equal.

2.4. METAL CLAD (MC) CABLE

- A. Cable shall meet or exceed the requirements of UL Standard 83, UL Standard 1063, and UL Standard 1569 for Type MC cable, Federal Specification A-A59544 Vertical Cable Tray Flame Test and the National Electrical Code. Cable shall be listed for use in UL 1, 2, and 3 Hour Through-Penetration Firestop Systems.
- B. Cable shall be constructed with soft drawn copper, 600 volt, type THHN/THWN conductors rated 90°C dry/75°C wet, with a green insulated copper grounding conductor. Conductors shall be cabled together with a binder tape bearing a print legend that is wrapped around the assembly. An interlocked armor shall be applied over the assembly. Conductors shall be protected by an anti-short bushing at each termination.
- C. Only cables with conductor sizes 12 AWG and 10 AWG shall be permitted.
- D. Multi-circuit MC cable is not permitted.

2.5. METAL CLAD (MC) CABLE CONNECTORS

- A. Snap-In Connectors
 1. Snap-in connectors for metal clad cable shall be constructed of die-cast zinc, shall be compatible with steel and aluminum cables, and shall have the following features:
 - a. Insulated throat
 - b. Removable ring to secure connector to box

- c. Angled, two-prong clip to secure cable
 - d. Removable screw to secure cable clip
- 2. Snap-in connectors shall be available in a variety of sizes and configurations to accommodate different cable sizes/diameters, wire counts, cable counts, etc.
- 3. Single connectors shall be compatible with 1/2-inch knockouts. Duplex connectors shall be compatible with 3/4-inch knockouts.
- 4. Provide SNAP²IT connectors as manufactured by Arlington Industries, Inc., or approved equal by listed manufacturer.
- B. Lock-Nut Connectors
 - 1. Straight connectors shall be one-piece spring-steel, set screw design with nylon insulator and locknut. Provide ACB series, as manufactured by Crouse-Hinds, or approved equal.
 - 2. 45 and 90 degree connectors shall be die cast zinc, clamp type with insulated throat and locknut. Provide ACBXX45 or ACBXX90 series as manufactured by Crouse-Hinds, or approved equal.

2.6. INSULATING TAPE, PUTTY, RESIN AND SUPPORTS

- A. Tape: Provide plastic electrical insulating tape which is flame-retardant, cold and weather-resistant. Tape for use in areas subject to temperatures 30 degrees C to 105 degrees C, or where the tape will be subjected to an oil splash, tape shall have a minimum thickness of 8.5 mils, and shall consist of an oil-resistant acrylic adhesive.
- B. Materials: Provide all insulating materials for splices and connections such as glass and synthetic tapes, putties, resins, splice cases, or compositions of the type approved for the particular use, location, voltage and temperature and apply and install in an approved manner, all in accordance with the manufacturer's recommendations.
- C. Supports: Provide cable supports of the wedge type which firmly clamp each individual cable and tighten due to the cable weight.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Examine raceways and building finishes to receive wires and cables for compliance with requirements for installation tolerances and other conditions affecting performance of wires and cables. Do not proceed with installation until unsatisfactory conditions have been corrected.
- B. By beginning work, the Contractor has accepted conditions and assumes responsibility for correcting unsuitable conditions encountered at no additional cost to the Owner.

3.2. PREPARATION

- A. Completely and thoroughly swab raceway before installing wire.

3.3. WIRE AND INSULATION APPLICATIONS

- A. No branch circuit wires smaller than 12 AWG shall be used unless otherwise indicated. Conductors shall be continuous from outlet to outlet and from terminal board to point of final connection, and no splice shall be made except within outlet or junction boxes. All conductors shall be of the size indicated. All wires 8 AWG and larger shall be stranded.
- B. Control wiring shall not be less than 14 AWG and shall be color coded using colors impregnated into the insulation. All control wiring shall be color coded with wires of colors different from those used to designate phase wires.
- C. All wiring, contacts, and terminal blocks shall be suitably tagged for ease in identification and tracing of circuits. Identification tags shall be engraved fiber or plastic type, subject to acceptance. Wires shall be numbered and coded, using Brady Quicklabels, or equal.
- D. Wiring shall be tagged at terminations, in pull boxes, junction boxes, outlet boxes, panelboards, etc.
- E. Switch leg wire shall be labeled with "S" tag.
- F. Wiring for general 15 and 20 amp branch circuit work shall be as follows unless otherwise indicated:

HOME RUN LENGTH AND WIRE SIZE				CIRCUIT LENGTH AND WIRE SIZE			
120 Volt		277 Volt		120 Volt		277 Volt	
0 – 60 '	12AWG	0 – 175 '	12AWG	0-100 '	12AWG	0 – 200 '	12AWG
60 – 100 '	10AWG	175 - 350'	10AWG	100' & Up	10AWG	200 ' & Up	10AWG
100' & Up	8AWG	350> & Up	8AWG				

- G. Circuit length as given above shall be the wire length between the first and last outlet on the circuit. Home run length as given above shall be the wire length between the first outlet and the panelboard. In accordance with the above, where the size of branch circuit conductors is increased by the minimum required by the NEC for the branch circuit rating, ensure that the termination provisions of all equipment connected to such circuits are listed as suitable for the conductor sizes involved.
- H. Joints of 10 AWG and smaller shall be made with properly insulated solderless type pressure connectors. Where stranded conductors or multiple solid conductors are connected to terminals, solderless lugs manufactured by Thomas and Betts Company or equivalent shall be used.
- I. Joints of 8 AWG and larger shall be of the type indented into the conductor by means of a hand or hydraulic pressure tool. Connectors shall be Burndy Hy dent, T&B Sta Kon, or equivalent. Connectors for control wiring shall be Burndy Hy Lug, or equivalent.
- J. All circuits for underground exterior electric work shall be 10 AWG (minimum) and

contain a 10 AWG (minimum) copper grounding conductor. All exterior wiring shall be installed in conduit as specified above, unless otherwise noted on the Drawings.

3.4. MC CABLE APPLICATIONS

- A. MC cable shall be permitted only where concealed above accessible ceilings and/or within drywall partitions and in accordance with the requirements of Division 26 Section 260533, "Raceways and Boxes for Electrical Systems".
- B. MC Cable shall be allowed for connections within a room from a junction box to lighting fixtures.
- C. MC cable shall be allowed from a junction box within a room to receptacles in the same room.
- D. MC cable shall not be allowed to cross one room to another room whether the wall between two rooms goes up to slab or not. If the rooms are identified as two separate rooms, MC cable shall not be used between the two rooms.
- E. Provide anti-short bushings for all MC cable terminations.
- F. Cables shall be supported with appropriate hangers; tie wire is not acceptable.
- G. MC cable shall not be used to support other cables/wires.

3.5. INSTALLATION

- A. Install wires and cables as indicated, according to manufacturer's written instructions and NECA's Standard of Installation.
- B. Remove existing wires from raceway before pulling in new wires and cables.
- C. Pull Conductors: Use a UL-listed and manufacturer approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- D. Use pulling means including fish tape, cable, rope, and basket weave wire/cable grips that will not damage cables or raceway. Completely and thoroughly swab conduit system before installing conductors.
- E. Install exposed cables, parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- F. Support cables according to Division 26 Section 260500, "Common Work Results for Electrical" and Division 26 Section 265029, "Hangers and Supports for Electrical Systems".
- G. Seal around cables penetrating fire rated elements according to Division 26 Section 260528, "Firestopping for Electrical Systems".
- H. Identify wires and cables according to Division 26 Section 260553, "Identification for

Electrical Systems”.

- I. Conductors installed in parallel shall be of equal lengths.
- J. Wiring at Outlets: Install with at least 6 inches (150 mm) of slack conductor at each outlet in accordance with Article 300.14 of the National Electrical Code.
- K. Connect outlets and components to wiring and to ground as indicated and instructed by manufacturer. Tighten connectors and terminals, including screws and bolts, according to equipment manufacturer's published torque-tightening values for equipment connectors. Where manufacturer's requirements are not indicated, tighten connectors and terminals according to tightening torques specified in UL Standard 486A.
- L. The Contractor shall provide suitable installation equipment to prevent cutting and abrasion of conductor insulation. The Contractor shall use suitable cable guides, pulleys, and protective sleeving to prevent damage to cable during installation. Ropes used for pulling of wire and cable shall be made of polyethylene or other suitable non-metallic material. Pulling lines shall be attached to cable by means of either woven basket grips or pulling types attached directly to the conductors. Wire pulling lubricants, if used, shall conform to UL requirements applicable to the various insulations and raceway materials. The lubricants shall be certified by the manufacturer to be non-injurious to such insulation and materials.
- M. Each cable shall be labeled at terminals and at all accessible points in equipment and in pull boxes. Each wire shall be labeled at both ends. Labels shall be self-sticking wire markers.
- N. For rubber and plastic-covered wire and cable, pulling compound Ideal Yellow 77 may be used.
- O. Terminal lugs for wires 8 AWG and larger shall be T&B 54,000 Series or Burndy HY-Dent, compression type, unless noted otherwise. One-hole lugs for wires 4/0 AWG and smaller. Two-hole lugs for all wires 250 kcmil AWG and larger.
- P. Install wires and cables using braided rope larger than the cable being pulled to keep twists to a minimum.
- Q. Provide an insulated green equipment grounding conductor (EGC), sized per NEC, for all feeder and branch circuits, shown or not shown.
- R. Multi-wire branch circuits shall not be permitted. Provide a separate insulated neutral (grounded) conductor for all feeder and branch circuits requiring a neutral connection.
- S. Install electrical cables, wires, and connectors as indicated in compliance with manufacturer's written instructions, applicable requirements of NEC and NECA's "Standard of Installation", and in accordance with recognized industry practices.
- T. Coordinate cable and wire installation work with electrical raceway and equipment installation work, as necessary for proper interface.
- U. Conductors installed in runs within 6 inches of heating pipes or equipment shall be of types

required by the NEC and shall be listed for the application.

- V. No conductors shall be drawn into conduit until all work, which may cause cable damage, is completed.
- W. All wiring in lighting fixture channels, over boilers and breechings, and in other high ambient temperature areas, shall be of types required by NEC and shall be listed for the application.
- X. During installation, do not deform cable by improper bending, stretching, twisting, kinking, or pinching, nor do any other abusive handling. Any failure to observe these instructions will be detected and corrected during the demonstrations following completion of the installation.
- Y. Cable bends will have a radius not less than the value recommended by the cable manufacturer.
- Z. All labels shall be of durable material and securely fastened to the cable.
- AA. Wiring of different system voltages shall not be mixed at pull boxes enclosures, surface metal raceway, wire troughs, etc., unless a barrier (separator) is provided between the differing systems.

3.6. CONNECTIONS

- A. Conductor Splices: Keep to minimum.
- B. Install splices and taps that possess equivalent or better mechanical strength and insulation ratings than conductors being spliced.
- C. Use splice and tap connectors compatible with conductor material.
- D. Connect outlets and components to wiring and to ground as indicated and instructed by manufacturer.
- E. Tighten electrical connectors and terminals according to manufacturer's published torque tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- F. Wire splices and taps shall be adequate to carry full current rating of wire.
- G. Conductors shall be continuous from outlet to outlet, and no splices shall be made except within outlet or junction boxes. Junction boxes may be utilized where required. Wire connectors of insulating material or solderless pressure connections, properly taped, shall be utilized for all splices in wiring.
- H. Splices in branch circuits and feeders shall be made where indicated or as required for the installation. All splices shall be accessible and made in enclosure approved for that purpose.
- I. For splices in branch circuits provide connectors as follows;

1. Wire Sizes 10 AWG and smaller: Provide wire nut connectors as specified in Part 2 of this Section.
 2. Wire Sizes 8 AWG and Larger: Provide insulated connectors as specified in Part 2 of this Section.
- J. Thoroughly clean wiring prior to installing lugs or connectors.

3.7. IDENTIFICATION

- A. All building wire and cable shall be color-coded to identify the electrical system(s) as specified. Where color-coding is field-applied, the same shall be accomplished with colored electrical tape wrapped concentrically around each conductor in half-lapped turns, for at least the last six (6) inches of the conductor. One turn around the conductor is not acceptable.
- B. Identify wire and cable using Thomas and Betts Type WM vinyl markers.
- C. Identify each phase and neutral conductor with its circuit number or other designation indicated on the Drawings in all junction, pull, terminal boxes, and cabinets.
- D. Provide identification tags on each conductor entering each panelboard, switch, junction box, and pull box to identify conductor.
- E. Comply with the requirements of Division 26 Section 260553, "Identification for Electrical Systems".

3.8. FIELD QUALITY CONTROL

- A. Visual and Mechanical Inspection:
 1. Inspect for defects and physical damage, labeling, and compliance with requirements of drawings and schedules.
 2. Clean conductors using Manufacturer's approved methods and materials.
 3. Verify that conductors are correct size and are terminated with appropriately sized lugs.
 4. Verify that conductors are correct color for phase identification.
 5. Verify that conductors are labeled to identify circuit designation.
 6. Verify that neutral conductors are only terminated at neutral lugs/bus, and that grounding conductors are only terminated at grounding lugs/bus.
- B. Electrical Tests: Upon installation of conductors and before electrical circuitry has been energized, provide the following minimum inspections and tests according to manufacturer's written instructions to ensure conductors are operational within industry and manufacturer's tolerances, are installed according to the Contract Documents, and are suitable for energizing.

1. Inspect accessible components for cleanliness, mechanical and electrical integrity, and damage or deterioration.
2. Inspect bolted electrical connections for tightness according to manufacturer's published torque values or, if not available, those specified in UL 486A and UL 486B.
3. Verify continuity of each conductor.
4. Insulation Resistance Testing: Perform megohm meter tests of all new feeder circuits and branch circuits rated 100A and larger, including each phase, neutral, and grounding conductor, as follows:
 - a. Minimum Test Voltage: 1000 Vdc.
 - b. Minimum Insulation Resistance: 1 megohms.
 - c. Duration of Each Test: 1 minute.
 - d. Temperature Correction: Correct results for test temperature deviation from 20 degrees C standard.
 - e. Compare test results with specified performance or manufacturer's data. Correct deficiencies identified by tests and retest.
 - f. Prepare reports identifying equipment checked and describing results of tests. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
5. Test Labeling: On satisfactory completion of tests and related effort, apply a label to tested components indicating test results, date, and responsible organization and person.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 26 SECTION 26 05 20
ELECTRIC HEATING CABLES
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SUMMARY	3
1.3. DEFINITIONS.....	3
1.4. SUBMITTALS	3
1.5. QUALITY ASSURANCE	3
1.6. COORDINATION.....	3
1.7. WARRANTY	3
PART 2. PRODUCTS.....	4
2.1. MANUFACTURERS	4
2.2. HEATING CABLES.....	4
2.3. HEATING CABLE CONTROLLER – ELECTRONIC WITH GROUND FAULT PROTECTION AND BMS GATEWAY	5
2.4. ACCESSORIES	6
PART 3. EXECUTION.....	6
3.1. EXAMINATION	6
3.2. INSTALLATION	6
3.3. CONNECTIONS	7
3.4. FIELD QUALITY CONTROL	7
3.5. ADJUSTING.....	7
3.6. PROTECTION.....	7
END OF SECTION	8

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 20 ELECTRIC HEATING CABLES

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SUMMARY

- A. This Section includes heating cables for the following applications:
 - 1. Heat tracing for freeze protection.

1.3. DEFINITIONS

- A. AWG: American Wire Gauge.
- B. C: Celsius.
- C. F: Fahrenheit.

1.4. SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Field Test Reports: Indicate and interpret test results for compliance with performance requirements.
- C. Maintenance Data: For electric heating cables to include in maintenance manuals specified in Division 01.
- D. Warranties: Special warranties specified in this Section.

1.5. QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

1.6. COORDINATION

- A. Coordinate layout and installation of electric heating cables and system components with other construction.
 - 1. Coordinate with piping installer, for condensate and sanitary piping provided under Division 22 and 23.

1.7. WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of

other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.

- B. Special Warranty: Written warranty, executed by manufacturer agreeing to repair or replace components of electric heating cables that fail in materials or workmanship within specified warranty period.
- C. Warranty Period: Two years from date of Substantial Completion.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Accutron Heat Tracing Systems.
 - 2. Ari Industries.
 - 3. BICC Pyrotenax USA Inc.
 - 4. Caloric, Inc.
 - 5. Chromalox; Wiegard Industrial Division; Emerson Electric Company.
 - 6. Copperheat Inc.
 - 7. Delta Therm Corp.
 - 8. Easy Heat, Inc.
 - 9. INDEECO.
 - 10. Maxxon Corp.; Infloor Heating Systems Div.
 - 11. Nelson Heat Tracing Systems.
 - 12. Omega Engineering Inc.
 - 13. Raychem Corporation. (Basis of Design)
 - 14. Thermon Manufacturing Co.

2.2. HEATING CABLES

- A. The self-regulating heater shall consist of two (2) 16 AWG nickel coated-copper bus wires embedded in parallel in a self-regulating polymer core that varies its power output to respond to temperature all along its length, allowing the heater to be crossed over itself without overheating, to be used directly on plastic pipe, and to be cut to length in the field.

The heater shall be covered by a radiation cross-linked modified polyolefin dielectric jacket.

- B. In order to provide energy conservation and to prevent overheating, the heater shall have a self-regulating factor of at least 90 percent. The self-regulation factor is defined as the percentage reduction, without thermostatic control, of the heater output going from 40 degrees F pipe temperature operation to 150 degrees F pipe temperature operation.
- C. The heater shall operate on line voltages of 120 volts without the use of transformers.
- D. The heater shall be sized according to this table. The required heater output rating is in watts per foot at 50 degrees F.

Pipe Size	Watts per foot
3 inch or less	5 watt
4 inch	5 watt
6 inch	8 watt
8 inch	2 strips - 5 watt

- E. Power connection, end seal, splice and tee kit components shall be applied in the field.
- F. The system shall be controlled by a thermostat set at 40 degrees F either directly or through an appropriate contactor.

2.3. HEATING CABLE CONTROLLER – ELECTRONIC WITH GROUND FAULT PROTECTION AND BMS GATEWAY

- A. Description: Heat trace cables providing freeze protection for water piping shall be controlled by an electronic outdoor controller with integrated 30-mA ground fault protection and a multi-protocol gateway for communication with Modbus and/or BACnet building management systems to allow the building management system to remotely configure, control, and monitor the heating cable circuit(s).
- B. Electronic heat trace controllers shall have the following features:
 - 1. Modbus RTU/RS-485 communication module.
 - 2. BACnet MSTP multi-protocol gateway.
 - 3. Six character alphanumeric display.
 - 4. -40 degrees Fahrenheit to 140 degrees Fahrenheit (-40 degrees Celsius to 60 degrees Celsius) operation.
 - 5. Single or dual temperature sensor inputs to allow selection of one or eight control modes and programming of all temperature parameters.

6. High and low temperature alarms.
 7. High temperature cut-out.
 8. Low current alarms.
 9. 30A rated electromechanical relay (EMR) output switch with device failure alarm.
 10. Ground fault alarm and trip.
 11. Proportional ambient sensing control to maximize energy efficiency.
 12. Minimum/Maximum temperature tracking
 13. Auto-cycling to momentarily energize the circuit during periods of non-use to detect issues with the heat tracing circuit.
- C. Provide Raychem Digitrace C910-485 heat trace controller with Raychem ProtoNode Gateway, or approved equal by listed manufacturer.

2.4. ACCESSORIES

- A. Cable Installation Accessories: Tapes, cable ties, warning labels, end seals and splices, and installation clips.
- B. Provide manufacturer's pipe support bracket for thermostats installed at piping.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Examine surfaces and substrates to receive heating cables for compliance with requirements for installation, tolerances, and other conditions affecting performance.
1. Ensure surfaces and pipes in contact with electric heating cables are free of burrs and sharp protrusions.
 2. Ensure pipe testing is complete.
 3. Ensure surfaces and substrates are level and plumb.
- B. Test cables for electrical continuity before installing.
- C. Test cables for insulation resistance before installing.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2. INSTALLATION

- A. Cut cable(s) to lengths required.
- B. Install heater to cold lead connections in accessible locations. Do not embed in concrete

or plaster.

- C. Avoid crossing expansion, construction, or control joints with heating cables. Provide sufficient slack conductor in expansion loop.
- D. Provide labels for piping insulation/jacketing to identify the same as “electrically heat-traced”.

3.3. CONNECTIONS

- A. Electrical installation requirements are specified in other Division 26 Sections. Drawings indicate general arrangement of wiring, conduit, and specialties.
- B. Connect heating cables and other components to wiring systems.
- C. Ground equipment:
 - 1. Tighten electrical connectors and terminals according to manufacturer's published torque tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- D. Connecting heating cable controller(s) for domestic water freeze protection to building management system via Modbus or BACnet gateway to remotely configure, control, and monitor the heating cable circuit(s), including transmitting alarm conditions (e.g. temperature sensor failure, high or low temperature, and ground-fault) if detected. Coordinate work with Division 23 Contractor.

3.4. FIELD QUALITY CONTROL

- A. Testing: Perform tests after installation but before application of coverings, such as insulation, plaster, or concrete.
 - 1. Test cables for electrical continuity before energizing.
 - 2. Test cables for insulation resistance before energizing. Remove cables if measured resistance is less than 10 megohms to ground.
 - 3. Test cables to verify rating and power input. Energize and measure voltage and current simultaneously.
- B. Repeat tests for continuity, insulation resistance, and input power after applying thermal insulation.
- C. Repair or replace malfunctioning units. Retest as specified above after repairs or replacements are made.

3.5. ADJUSTING

- A. Set field adjustable thermostat ranges as indicated.

3.6. PROTECTION

- A. Protect installed heating cables, including leads, from damage prior to Substantial Completion.

END OF SECTION

DIVISION 26 SECTION 26 05 26
GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS	3
1.2. SUMMARY	3
1.3. DEFINITIONS	3
1.4. SUBMITTALS	3
1.5. QUALITY ASSURANCE	3
PART 2. PRODUCTS	4
2.1. MANUFACTURERS	4
2.2. GROUNDING AND BONDING PRODUCTS	4
2.3. WIRE AND CABLE GROUNDING CONDUCTORS	4
2.4. MISCELLANEOUS CONDUCTORS	5
2.5. CONNECTOR PRODUCTS	5
PART 3. EXECUTION	6
3.1. APPLICATION	6
3.2. INSTALLATION	6
3.3. CONNECTIONS	7
END OF SECTION	8

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 26- GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections include the following:
 - 1. Division 26 Section 260519, "Low-Voltage Electrical Power Conductors and Cables", for conductor and cable requirements.

1.2. SUMMARY

- A. This Section includes grounding of electrical systems and equipment and basic requirements for grounding for protection of life, equipment, circuits, and systems. Grounding requirements specified in this Section may be supplemented in other Sections of these Specifications.
- B. Bond together system neutrals; service equipment enclosures; exposed non-current carrying metal parts of electrical equipment; metal raceway systems; grounding conductor in raceways; receptacle ground connectors; and plumbing systems.

1.3. DEFINITIONS

- A. EGC: Equipment grounding conductor.
- B. GEC: Grounding electrode conductor.
- C. SSBJ: Supply-side bonding jumper.

1.4. SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 01 Specification Sections.
- B. Product Data for grounding rods, conductors, connectors and connection materials, and grounding fittings. Submit ground system manufacturer's recommended installation procedure for review.
- C. Field tests and observation reports indicating and interpreting the test reports for compliance with performance requirements.

1.5. QUALITY ASSURANCE

- A. Comply with NFPA 70 - National Electrical Code.
- B. Comply with UL 467 - UL Standard for Safety Grounding and Bonding Equipment.
- C. Comply with ANSI/IEEE C2 - National Electrical Safety Code.

- D. Comply with ANSI/IEEE 32 - Requirements, terms and test procedures for neutral grounding devices.
- E. Comply with IEEE Standard 142 - Recommended Practice for Grounding of Industrial and Commercial Power Systems.
- F. Comply with ANSI C33.8.
- G. Listing and Labeling: Provide products specified in this Section that are listed and labeled.
 - 1. The Terms Listed and Labeled: As defined in the National Electrical Code, Article 100.
 - 2. Listing and Labeling Agency Qualifications: A Nationally Recognized Testing Laboratory (NRTL) as defined in OSHA Regulation 1910.7.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Erico Inc.; Electrical Products Group.
 - 2. Harger Lightning and Grounding; Harger, Inc.
 - 3. Heary Brothers Lightning Protection Co.
 - 4. Ideal Industries, Inc.
 - 5. ILSCO.
 - 6. O-Z/Gedney Co.
 - 7. Raco, Inc.
 - 8. Thomas & Betts, Electrical.

2.2. GROUNDING AND BONDING PRODUCTS

- A. Governing Requirements: Where types, sizes, ratings, and quantities indicated are in excess of National Electrical Code (NEC) requirements, the more stringent requirements and the greater size, rating, and quantity indications govern.

2.3. WIRE AND CABLE GROUNDING CONDUCTORS

- A. Comply with Division 26 Section 260519, "Low-Voltage Electrical Power Conductors and Cables". Conform to NEC Table 8, except as otherwise indicated, for conductor properties, including stranding.

- B. Equipment Grounding Conductors: Size as indicated on the Drawings, or as required by National Electrical Code (NEC) Table 250-122, whichever is larger. Insulated with green color insulation.
- C. Grounding Electrode Conductors: Size as indicated on the Drawings, in the Specifications, or as required by National Electrical Code (NEC) Table 250-66, whichever is larger. Insulated with green color insulation, unless installed in direct contact with earth, in which case conductors shall be bare.
- D. Bare Copper Conductors: Conform to the following:
 - 1. Solid Conductors: ASTM B 3.
 - 2. Assembly of Stranded Conductors: ASTM B 8.
 - 3. Tinned Conductors: ASTM B 33.

2.4. MISCELLANEOUS CONDUCTORS

- A. Braided Bonding Jumpers: Copper tape, braided bare copper wire, terminated with copper ferrules.
- B. Bonding Straps: Soft copper, 0.05 inch (1 mm) thick and 2 inches (50 mm) wide, unless otherwise indicated.

2.5. CONNECTOR PRODUCTS

- A. Mechanical Connectors
 - 1. The mechanical connector bodies shall be manufactured from high strength, high conductivity cast copper alloy material. Bolts, nuts, washers and lock-washers shall be made of silicon bronze and supplied as a part of the connector body and shall be of the two-bolt type.
 - 2. Split bolt connector types are NOT allowed unless indicated on the Drawings.
 - 3. The connectors shall meet or exceed UL 467 and be clearly marked with the catalog number, conductor size and manufacturer.
- B. Compression Connectors
 - 1. The compression connectors shall be manufactured from pure wrought copper. The conductivity of this material shall be no less than 99 percent by IACS Standards.
 - 2. The connectors shall meet or exceed the performance requirements of IEEE 837, latest revision.
 - 3. The installation of the connectors shall be made with a compression, tool and die system, as recommended by the manufacturer of the connectors.
 - 4. The connectors shall be clearly marked with the manufacturer, catalog number,

conductor size and the required compression tool settings.

5. Each connector shall be factory filled with an oxide-inhibiting compound.

PART 3. EXECUTION

3.1. APPLICATION

- A. Equipment Grounding Conductors: Comply with NEC Article 250 for types, sizes, and quantities of equipment grounding conductors, except where specific types, larger sizes, or more conductors than required by NEC are indicated.
 1. Install Equipment Grounding Conductor (EGC) with circuit conductors for the items below in addition to those required by Code:
 - a. Feeder circuits.
 - b. Lighting branch circuits.
 - c. Receptacle branch circuits.
 - d. Single-phase motor or appliance branch circuits.
 - e. Three-phase motor or appliance branch circuits.
 - f. Flexible raceway runs.
 - g. Metal-clad (MC) cable runs.
 2. Nonmetallic Raceways: Install an equipment grounding conductor in nonmetallic raceways unless they are designated for telephone or data cables.
 3. Electric Heat Tracing Circuits: Install a separate equipment grounding conductor to each electric heat-tracing assembly and heating cable. Bond conductor to heater units, piping, connected equipment, and components.
- B. Mechanical System Grounding:
 1. All mechanical equipment, including but not limited to pumps, motors, packaged equipment, fans, heaters, etc. and their enclosures shall be properly grounded in accordance with Article 250 of the National Electrical Code.
 2. Terminal Cabinets: Terminate grounding conductor on cabinet grounding terminal.

3.2. INSTALLATION

- A. General: Ground electrical systems and equipment according to NEC requirements, except where Drawings or Specifications exceed NEC requirements.
- B. Grounding Conductors: Route along the shortest and straightest paths possible, except as otherwise indicated. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.
- C. Grounding shall satisfy requirements of the applicable publications. All exposed noncurrent-carrying metallic parts of electrical equipment, metallic raceway systems, grounding conductor in nonmetallic raceways, and grounded conductors of the wiring

system shall be grounded.

- D. The grounded conductor (neutral) of the wiring system shall be connected to the system grounding conductor at a single place in the system by removable bonding jumpers, sized according to the applicable provisions of the National Electrical Code. The grounded conductor (neutral) connection to the grounding conductor (ground) shall be located in the enclosure for the system's overcurrent protection or where otherwise indicated on the Drawings or Specifications.
- E. Ground buses and neutral buses in all branch panelboards, and those provided in any equipment shall be isolated except where required to be connected as specified above for the service entrance and in transformer terminal compartments.
- F. Equipment grounding conductors shall be extended from the ground bus in the distribution equipment to the receptacle, fixture or device lugs where they are provided. When not provided, they shall be connected to equipment enclosures. The connections shall be arranged such that removal of receptacle, the equipment grounding conductors, or ground jumpers from ground busing, shall not affect the system ground.
- G. Raceways shall not be considered as a grounding conductor. Each power, lighting, or control raceway shall have a separate equipment grounding conductor installed. Receptacles shall have a separate grounding pole.

3.3. CONNECTIONS

- A. General: Make connections so possibility of galvanic action or electrolysis is minimized. Select connectors, connection hardware, conductors, and connection methods so metals in direct contact will be galvanically compatible.
 - 1. Use electroplated or hot-tin-coated materials to assure high conductivity and to make contact points closer in order of galvanic series.
 - 2. Make connections with clean, bare metal at points of contact.
 - 3. Make aluminum-to-steel connections with stainless-steel separators and mechanical clamps.
 - 4. Make aluminum-to-galvanized steel connections with tin-plated copper jumpers and mechanical clamps.
 - 5. Coat and seal connections having dissimilar metals with inert material to prevent future penetration of moisture to contact surfaces.
- B. Equipment Grounding Conductor (EGC) Terminations: For 8 AWG and larger, use compression-type grounding lugs. 10 AWG and smaller grounding conductors may be terminated with wire nut connectors as specified in Division 26 Section, "Conductors and Cables".
- C. Non-Contact Metal Raceway Terminations: Where metallic raceways terminate at metal housings without mechanical and electrical connection to housing, terminate each conduit with a grounding bushing. Connect grounding bushings with a bare grounding conductor

to grounding bus or terminal in housing. Bond electrically non-continuous conduits at both entrances and exits with grounding bushings and bare grounding conductors, except as otherwise indicated.

- D. Tighten screws and bolts for grounding and bonding connectors and terminals according to manufacturer's published torque-tightening values. Where these requirements are not available, use those specified in UL 486A and UL 486B.
- E. Compression-Type Connections: Use hydraulic compression tools to provide correct circumferential pressure for compression connectors. Use tools and dies recommended by manufacturer of connectors. Provide embossing die code or other standard method to make a visible indication that a connector has been adequately compressed on grounding conductor.

END OF SECTION

DIVISION 26 SECTION 26 05 28
FIRESTOPPING FOR ELECTRICAL SYSTEMS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SUMMARY	3
1.3. REFERENCES	3
1.4. DEFINITIONS.....	3
1.5. SYSTEM DESCRIPTION	4
1.6. SUBMITTALS	4
1.7. QUALITY ASSURANCE	4
1.8. DELIVERY, STORAGE, AND HANDLING	4
1.9. PROJECT CONDITIONS	5
1.10. GUARANTEE.....	5
PART 2. PRODUCTS.....	5
2.1. MANUFACTURERS	5
2.2. THROUGH-PENETRATION FIRESTOPPING OF FIRE-RATED CONSTRUCTION	5
2.3. ACCESSORIES	6
PART 3. EXECUTION.....	6
3.1. EXAMINATION	6
3.2. PREPARATION	6
3.3. INSTALLATION	6
3.4. FIELD QUALITY CONTROL	7
3.5. ADJUSTING AND CLEANING.....	7
3.6. SYSTEMS AND APPLICATION SCHEDULES*	7
END OF SECTION	9

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 28 FIRESTOPPING FOR ELECTRICAL SYSTEMS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections include the following:
 - 1. Division 26 Section 260533, "Raceways and Boxes for Electrical Systems", for raceway seals and manufactured electrical devices.

1.2. SUMMARY

- A. Section includes:
 - 1. Through-penetration firestopping in fire rated construction.

1.3. REFERENCES

- A. Underwriters Laboratories
 - 1. UL Fire Resistance Directory
 - a. Through-penetration firestop devices (XHCR)
 - b. Fire resistance rating (BXUV)
 - c. Through-penetration firestop systems (XHEZ)
 - d. Fill, void, or cavity material (XHHW)
- B. American Society for Testing and Materials Standards: ASTM E 814-88: Standard Test Method for Fire Tests of Through-Penetration Firestops.

1.4. DEFINITIONS

- A. Assembly: Particular arrangement of materials specific to given type of construction described or detailed in referenced documents.
- B. Barriers: Time-rated fire walls, time rated ceiling/floor assemblies and structural floors.
- C. Firestopping: Methods and materials applied in penetrations and unprotected openings to limit spread of heat, fire, gasses and smoke.
- D. Penetration: Opening or foreign material passing through or into barrier or structural floor such that full thickness of rated materials is not obtained.
- E. System: Specific products and applications classified and numbered by Underwriters Laboratories, Inc. to close specific barrier penetrations.
- F. Sleeve: Metal fabrication or pipe section extended through thickness of barrier and used to permanently guard penetration. Refer to Division 26 Section 260500, "Common Work

Results for Electrical”, for sleeve requirements.

1.5. SYSTEM DESCRIPTION

A. Design Requirements

1. Fire-rated construction: Maintain barrier and structural floor fire resistance ratings including resistance to cold smoke at all penetrations, connections with other surfaces or types of construction, at separations required to permit building movement and sound or vibration absorption.

1.6. SUBMITTALS

A. Submit in accordance with Division 01, unless otherwise indicated.

B. Product Data: Manufacturer's specifications and technical data including the following:

1. Detailed specification of construction and fabrication.
2. Manufacturer's installation instructions.

1.7. QUALITY ASSURANCE

A. Installer's qualifications: Firm experienced in installation or application of systems similar in complexity to those required for this project, plus the following:

1. Acceptable to or licensed by manufacturer, State or local authority where applicable.
2. At least 2 years' experience with systems.
3. Successfully completed at least 5 comparable scale projects using this system.

B. Local and State regulatory requirements: Submit forms or acceptance for proposed assemblies not conforming to specific UL Firestop System numbers, or UL classified devices.

C. Materials shall have been tested to provide fire rating at least equal to that of the construction.

D. Manufacturer shall be a member of the International Firestop Council (IFC).

1.8. DELIVERY, STORAGE, AND HANDLING

A. Packing and shipping:

1. Deliver products in original unopened packaging with legible manufacturer's identification.
2. Coordinate delivery with scheduled installation date, allow minimum storage at site.

- B. Storage and protection: Store materials in a clean, dry, ventilated location. Protect from soiling, abuse, moisture and freezing when required. Follow manufacturer's instructions.

1.9. PROJECT CONDITIONS

- A. Existing conditions:
 - 1. Verify existing conditions and substrates before starting work. Correct unsatisfactory conditions before proceeding.
 - 2. Proceed with installation only after penetrations of the substrate and supporting brackets have been installed.
- B. Environmental requirements:
 - 1. Furnish adequate ventilation if using solvent.
 - 2. Furnish forced air ventilation during installation if required by manufacturer.
 - 3. Keep flammable materials away from sparks or flame.
 - 4. Provide masking and drop cloths to prevent contamination of adjacent surfaces by firestopping materials.

1.10. GUARANTEE

- A. Submit copies of written guarantee agreeing to repair or replace joint sealers which fall in joint adhesion, extrusion resistance, migration resistance, or general durability or appear to deteriorate in any other manner not clearly specified by submitted manufacturer's data as an inherent quality of the material for the exposure indicated. The guarantee period shall be two years from date of substantial completion unless otherwise noted.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Subject to compliance with requirements, manufacturers offering products that may be incorporated into the work include, but are not limited to, the following:
 - 1. Hilti
 - 2. 3M
 - 3. Nelson

2.2. THROUGH-PENETRATION FIRESTOPPING OF FIRE-RATED CONSTRUCTION

- A. Systems of devices listed in the UL Fire Resistance Directory under categories XHCR and XHEZ may be used, providing that it conforms to the construction type, penetrate type, annular space requirements and fire rating involved in each separate instance, and that the system be symmetrical for wall applications. Systems or devices must be asbestos-free.

1. Additional requirements: Withstand the passage of cold smoke either as an inherent property of the system, or by the use of a separate product included as a part of the UL system or device, and designed to perform this function.
2. Acceptable manufacturers and products.
 - a. Those listed in the UL Fire Resistance directory for the UL System involved and as further defined in the "System and Applications Schedule" in Part 3 of this Section.
 - b. All firestopping products must be from a single manufacturer.

2.3. ACCESSORIES

- A. Fill, void or cavity materials: As classified under category XHHW in the UL Fire Resistance Directory.
- B. Forming materials: As classified under category XHKU in the UL Fire Resistance Directory.
- C. Sleeves: Minimum 24 MSG galvanized steel, 12-inch diameter or smaller steel pipe. Sleeve shall project ½-inch from each surface of the floor/wall. Size as recommended by firestop manufacturer.
- D. Box Inserts: Intumescent inserts designed for installation inside of outlet and switch boxes to help protect fire-rated assemblies.
- E. Putty Pads: Moldable firestop putty designed for installation on outside of outlet and switch boxes.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
 1. Verify barrier penetrations are properly sized and in suitable condition for application of materials.
 2. Do not proceed until unsatisfactory conditions have been corrected.

3.2. PREPARATION

- A. Clean surfaces to be in contact with penetration seal materials of dirt, grease, oil, loose materials, rust, or other substances that may affect proper fitting, adhesion, or the required fire resistance.

3.3. INSTALLATION

- A. Install penetration seal materials in accordance with printed instructions of the UL Fire Resistance Directory and in accordance with manufacturer's instruction.

- B. Seal holes or voids made by penetrations to ensure an effective barrier.
- C. Protect materials from damage on surfaces subject to traffic.
- D. When large openings are created in walls or floors to permit installation of conduits, cable tray, or other items, close unused portions of opening with firestopping materials tested for the application.
- E. Provide sleeves the full thickness of the assembly being penetrated and cut sleeves to a length of 1-inch more than the overall thickness of the penetration, or as recommended by the firestop manufacturer.
- F. Provide firestop box inserts and/or putty pads for outlet boxes in fire-rated partitions.

3.4. FIELD QUALITY CONTROL

- A. Examine penetration sealed areas to ensure proper installation before concealing or enclosing areas.
- B. Keep areas of work accessible until inspection by applicable code authorities.
- C. Perform under this section patching and repairing of firestopping caused by cutting or penetration by other trades.

3.5. ADJUSTING AND CLEANING

- A. Clean up spills of liquid components.
- B. Neatly cut and trim materials as required.
- C. Remove equipment, materials and debris, leaving area in undamaged, clean condition.

3.6. SYSTEMS AND APPLICATION SCHEDULES*

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/CEILING
Metal Pipe	CAJ1001 CP25S/L, CP25N/S CAJ1006 CS-195+, FS-195+ CAJ1007 FS-195+, 1-inch & 2-inch Wide CAJ1009 2000, 2000+, 2003 CAJ1010 2000, 2000+, 2003 CAJ1012 2000, 2000+, 2003 CAJ1013 2000, 2000+, 2003 CAJ1014 2000, 2000+, 2003 CAJ1015 2000, 2000+, 2003 CAJ1017 FD 150 CAJ1021 FD 150 CAJ1027 MPS-2+ CAJ1044 CP 25WB+ CAJ1052 CP 25S/L, CP 25N/S CAJ1058 2000, 2000+, 2003 CAJ1060 2000, 2000+, 2003 CAJ1063 2000, 2000+, 2003	WL1001 CP 25 WL1002 FS-195+ WL1003 CP 25WB+, CP 25N/S WL1008 2000+ WL1009 2000+ WL1010 2000+ WL1016 CP 25WB+ WL1017 CP 25WB+, CP 25N/S WL1032 CP 25WB+, CP 25N/S WL1036 FD 150 WL1037 CS-195+, FS-195+ WL1067 CP 25N/S WL1073 CP 25WB+ WL1080 MPS-2+ WL1082 2000+	FC1002 CP 25 FC1003 2000, 2000+, 20003 FC1006 CP 25WB+

PENETRATING ITEM	CONCRETE	GYP SUM	WOOD FLOOR/CEILING
	CAJ1066 CP 25N/S,CP 25S/L, CP 25WB+ CAJ1091 CP 25N/S,CP 25S/L, CP 25WB+ CAJ1092 CP 25WB+ CAJ1112 FS-195+ CAJ1160 CP 25S/L, CP 25N/S CAJ1175 CP 25WB+ CAJ1176 CP 25WB+ CAJ1188 2000+ CBJ1020 CS-195+, FS-195+ CBJ1021 CS-195+, MPS-2+ CBJ1031 2001 CBJ1032 2001 FA1002 CP 25WB+ WJ1010 CP 25WB+ WJ1023 2001		
Non-Metallic	CAJ2001 FS-195+, 1-inch& 2-inch WIDE, PPD'S CAJ2002 FS-195+ CAJ2003 CS-195+, FS-195+ CAJ2005 FS-195+ CAJ2006 FS-195+ CAJ2013 FS-195+ CAJ2019 2000, 2000+, 2003 CAJ2027 FS-195+, CP 25N/S, CP 25S/L, CP 25WB+ CAJ2028 FS-195, MPS-2+ CAJ2029 FS-195+, PPD'S CAJ2030 CS-195+, FS-195+ CAJ2040 FS-195+, CP 25WB+ CAJ2044 FS-195+, CP 25N/S, CP 25S/L CP 25 WB+ CAJ2090 FS-195+ CAJ2177 FS-195+, PPD'S FA2001 FS-195+, PPD'S FS2002 CS-195+, FS-195+, MPS-2+, PPD'S FA2011 FS-195+ WJ2012 FS-195+ 1-inch WIDE	WL2002 FS-195+, PPD'S WL2003 FS-195+ WL2004 FS-195+ WL2005 FS-195+ 4' WIDE WL2006 FS-195+ WL2013 FS-195+ WL2031 CS-195+, FS-195+ WL2032 CS-195+, FS-195+ WL2033 FS-195+ WL2073 FS-195+ 1-inch WIDE	FC2002 FS-195+, PPD'S FC2007 FS-195+, PPD'S FC2008 FS-195+ FC2009 FS-195+, PPD'S FC2024 FS-195+ FC2026 FS-195+ FC2028 FS-195+, 1' & 2-inch WIDE, PPD'S
Insulated Cable	CAJ3001 CP 25N/S, CP 25S/L CAJ3005 CS 195+, FS-195+ CAJ3007 2001 CAJ3009 2000, 2000+, 2003 CAJ3010 2000, 2000+, 2003 CAJ3011 2001 CAJ3014 FD 150 CAJ3015 FD 150 CAJ3021 MPS-2+ CAJ3029 2000, 2000+, 2003 CAJ3030 CP 25WB+ CAJ3031 CP 25N/S, CP 25S/L CAJ3041 2000, 2000+, 2003 CAJ3044 CS-195+, FS-195+ CAJ3058 FS-195+, MPS-2+ CAJ3071 CP 25N/S, CP 25S/L CAJ3074 CP 25N/S, CP 25S/L CAJ3075 2001 CAJ3080 CP 25WB+	WL3001 CP 25, MPS-2+ WL3008 2000+ WL3009 2000+ WL3015 CP 25WB+, CP 25N/S WL3022 2000+ WL3030 FS-195+ WL3031 MPS-2+ WL3032 CP 25WB+ WL3041 2000+ WL3051 CP 25N/S WL3056 CP25N/S WL3062 CP 25WB+	FC3001 CP 25S/L, CP 25N/S FC3002 2000+ FC3003 2000, 2000+, 2003 FC3007 CP 25WB+, MPS-2+ FC3008 FS-195+

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/CEILING
	CBJ3016 CS-195+, FS-195+ CBJ3017 CS-195+, MPS-2+ FA3001 CP 25WB+ FB3004 CS-195+, MP WJ3015 2001 WJ3016 2001		
Mixed Penetrating Items Combos	CAJ8001 CS-195+ FS-195+ CAJ8003 2000, 2000+, 20003 CAJ8004 2000, 2000+, 20003 CAJ8006 2001 CAJ8013 FS-195+, CP 25 CBJ8004 CS-195, FS-195+ CBJ8005 CS-195+, MPS-2+ CBJ8008 2001 FA8001 FS-195+, CP 25WB+	WL8002 CS-195+, FS-195+	

*Underwriter's Laboratories, Inc., Fire Resistance Directory.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 26 SECTION 26 05 29
HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SUMMARY	3
1.3. SUBMITTALS	3
1.4. QUALITY ASSURANCE	3
1.5. PRODUCT DELIVERY, STORAGE, AND HANDLING.....	4
1.6. GUARANTEE	4
PART 2. PRODUCTS.....	4
2.1. MANUFACTURERS	4
2.2. COATINGS	4
2.3. MANUFACTURED SUPPORTING DEVICES	5
2.4. ANCHOR METHODS.....	5
PART 3. EXECUTION.....	6
3.1. EXAMINATION	6
3.2. INSTALLATION	6
3.3. CLEANUP	11
3.4. PROTECTION.....	11
END OF SECTION	11

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 29 HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections include the following:
 - 1. Division 26 Section 260500, "Common Work Results for Electrical", for general installation requirements.

1.2. SUMMARY

- A. This Section includes secure support from the building structure for electrical items by means of hangers, supports, anchors, sleeves, inserts, seals, and associated fastenings.
- B. Provide equipment supports consisting of platforms, curbs, concrete pads, cradles, structural members, hangers, rods, racks, and incidental materials.
- C. Provide all labor, supervision, and fabrication. Design and construct supporting structures of strength to safely withstand stresses to which they may be subjected and to properly distribute the load and impact over building areas. Provide all engineering and fabrication as required for installation of support system.
- D. Provide hangers, clamps, anchors, inserts, supports, supplementary steel framing, and hardware of the proper size and load capacity to support electrical equipment and raceways, whether indicated on the drawings or not.

1.3. SUBMITTALS

- A. General: Submit the following in accordance with conditions of Contract and Division 01 Specification Sections.
- B. Product data for each type of product specified.

1.4. QUALITY ASSURANCE

- A. Electrical Component Standard: Components and installation shall comply with NFPA 70 National Electrical Code.
- B. Electrical components shall be listed and labeled by UL, ETL, CSA, or other approved, nationally recognized testing and listing agency that provides third-party Certification follow-up services.
- C. Installation Standard: Installation shall meet or exceed the National Electrical Contractors Association (NECA) Standard of Installation.
- D. Manufacturer's Qualifications:

1. The Manufacturer shall not have had less than ten years' experience in manufacturing Strut Support Systems.
 2. The Manufacturer must certify in writing all components supplied have been produced in accordance with an established quality assurance program.
- E. All Strut Support System components must be supplied by a single manufacturer.
- F. Standards:
1. Work shall meet the requirements of the following standards:
 - a. Federal, State and Local Codes.
 - b. American Iron and Steel Institute (AISI) Specification for the Design of Cold-Formed Steel Structural Members.
 - c. American Society for Testing and Materials (ASTM).
 - d. Underwriters Laboratories (UL).
 - e. National Electrical Code (NEC).

1.5. PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. All material is to be delivered to the work site in original factory packaging to avoid damage to the finish.
- B. Upon delivery to the work site, all components shall be protected from the elements by a shelter or other covering.

1.6. GUARANTEE

- A. Separate guarantees shall be issued from the erector and manufacturer, valid for a period of one year against any defects that may arise from the installation or manufacture of the Strut Support System components.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated in the Work include, but are not limited to, the following:
1. Slotted Metal Angle and U-Channel Systems:
 - a. American Electric, Kindorf
 - b. Alstrut
 - c. Unistrut Diversified Products
 - d. Power-Strut
 - e. Thomas & Betts

2.2. COATINGS

- A. Dry, Interior Locations: Supports, support hardware, and fasteners shall be protected with

zinc coating or with treatment of equivalent corrosion-resistance using approved alternative treatment, finish, or inherent material characteristic. All products installed in dry interior locations shall be hot-dip galvanized, unless otherwise noted.

- B. Damp or Wet Locations: Supports, support hardware, and fasteners installed in damp or wet locations, including exterior locations, shall be Type 304 stainless steel.

2.3. MANUFACTURED SUPPORTING DEVICES

- A. Raceway Supports: Clevis hangers, riser clamps, conduit straps, threaded C-clamps with retainers, ceiling trapeze hangers, wall brackets, and spring steel clamps.
- B. Fasteners: Types, materials, and construction features, as follows:
 - 1. Expansion Anchors - Carbon steel wedge or sleeve type.
 - 2. Toggle Bolts - All steel springhead type.
 - 3. Power-Driven Threaded Studs - Heat-treated steel, designed specifically for the intended application.
- C. U-Channel Systems:
 - 1. Sixteen-gauge channels with 9/16-inch-diameter slotted holes at a minimum of two inches on center in top surface.
 - 2. Provide fittings and accessories that mate and match with U-channel and are of the same manufacturer.
 - 3. Provide plastic end caps for ends of u-channel at free-standing equipment supports and exterior locations.
- D. Floor-Mounted Stands: Construct with structural steel members or steel pipe and fasten with flanges bolted to the floor.
- E. Wall-Mounted Platforms: Construct with steel brackets.

2.4. ANCHOR METHODS

- A. Hollow Masonry: Toggle bolts or plastic conical type expansion anchors.
- B. Solid Masonry: Lead expansion anchors or preset inserts.
- C. Metal Surfaces: Machine screws, bolts, or welded studs.
- D. Wood Surfaces: Wood screws.
- E. Concrete Surfaces: Self-drilling anchors or power-driven studs (non-seismic zones).

PART 3. EXECUTION

3.1. EXAMINATION

- A. The installer shall inspect the work area prior to installation. If work area conditions are unsatisfactory, installation shall not proceed until satisfactory corrections are completed.

3.2. INSTALLATION

- A. Set Strut System components into final position true to line, level and plumb, in accordance with approved Shop Drawings.
- B. Anchor material firmly in place. Tighten all connections to their recommended torques.
- C. Install supporting devices to fasten electrical components securely and permanently in accordance with NEC requirements.
- D. Coordinate with the building structural system and with other electrical installation.
- E. Raceway Supports: Comply with the NEC and the following requirements:
 - 1. Conform to manufacturer's recommendations for selection and installation of supports.
 - 2. Strength of each support shall be adequate to carry present and future load multiplied by a safety factor of at least four. Where this determination results in a safety allowance of less than 200 pounds, provide additional strength until there is a minimum of 200 pounds safety allowance in the strength of each support.
 - 3. Install individual and multiple (trapeze) raceway hangers and riser clamps as necessary to support raceways. Provide U-bolts, clamps, attachments, and other hardware necessary for hanger assembly and for securing hanger rods and conduits.
 - 4. Support parallel runs of horizontal raceways together on trapeze-type hangers.
 - 5. Support individual horizontal raceways by separate pipe hangers. Spring steel fasteners may be used in lieu of hangers only for 1-1/2-inch and smaller raceways serving lighting and receptacle branch circuits above suspended ceilings only. For hanger rods with spring steel fasteners, use 1/4-inch-diameter or larger threaded steel. Use spring steel fasteners that are specifically designed for supporting single conduits or tubing.
 - 6. Space supports for raceways in accordance with Table I of this Section. Space supports for raceway types not covered by the above in accordance with NEC.
 - 7. Support exposed and concealed raceway within one foot of an unsupported box and access fittings. In horizontal runs, support at the box and access fittings may be omitted where box or access fittings are independently supported and raceway terminations are not made with chase nipples or threadless box connectors.
 - 8. In vertical runs, arrange support so the load produced by the weight of the raceway

and the enclosed conductors is carried entirely by the conduit supports with no weight load on raceway terminations.

- F. Miscellaneous Supports: Support miscellaneous electrical components as required to produce the same structural safety factors as specified for raceway supports. Install metal channel racks for mounting disconnects, light fixtures, and other devices.
- G. In open overhead spaces, cast boxes threaded to raceways need not be supported separately except where used for fixture support; support sheet metal boxes directly from the building structure or by bar hangers. Where bar hangers are used, attach the bar to the raceways on opposite sides of the box and support the raceway with an approved type of fastener not more than 24 inches from the box.
- H. Fastening: Unless otherwise indicated, fasten electrical items and their supporting hardware securely to the building structure, including, but not limited to conduits, raceways, boxes, disconnect switches, and control components in accordance with the following:
 - 1. Fasten by means of toggle bolts on hollow masonry units, concrete inserts or expansion bolts on concrete or solid masonry, and machine screws, welded threaded studs, or spring-tension clamps on steel. Threaded studs driven by a powder charge and provided with lock washers and nuts may be used instead of expansion bolts and machine screws. Do not weld conduit, pipe straps, or items other than threaded studs to steel structures.
 - 2. Holes cut to depth of more than 1-1/2 inches in reinforced concrete beams or to depth of more than 3/4-inch in concrete shall not cut the main reinforcing bars. Fill holes that are not used.
 - 3. Ensure that the load applied to any fastener does not exceed 25 percent of the proof test load. Use vibration-and shock-resistant fasteners for attachments to concrete slabs.
- I. General Supporting Installations:
 - 1. Provide appropriate concrete anchors for hanger rods. Rods shall be screwed into or extended through frame construction (with washer and nut). Supports shall secure conduit in place, and shall prevent vibration, provide for expansion and contraction and shall make neat appearance. Strap hangers or chains are not permitted.
 - 2. Electrical raceways 1-1/2-inches and smaller shall be secured with 1-hole malleable iron straps or brackets to walls. Trapeze supports shall be used for groups or parallel raceways with raceways secured to trapeze with approved clamps. Individual runs of raceways 2-inches and larger shall be supported by Clevis type hangers.
 - 3. Provide all steel supports including roof curbs for all equipment provided under this Section.
 - 4. Electrical raceway supports to be spaced on the following maximum centers,

unless otherwise required by the NEC:

- a. 3/4-inch to 1-inch conduit - 8 feet
 - b. 1-1/4-inch and larger conduit - 10 feet
- J. Provide additional hangers or steel members to distribute the load among two or more structural members when required or directed.
- K. Locations:
1. Anchor bolts, sleeves, inserts, hangers, and supports required for the electrical work shall be furnished and installed under Division 26.
 2. Coordinate with other trades the location of anchors, sleeves, inserts, and supports and ensure that they are properly installed.
 3. Openings and sleeves shall be set true to line, level, plumb, and position and shall be so maintained during construction. Where sleeves and openings are provided in poured concrete, inspect same during and after concrete is poured to ensure proper position and correct any deviation.
- L. Hangers and Supports:
1. Provide hangers, angles, channels, and other supports required by field conditions to install items of electrical equipment. Design of supports and methods of fastening to building structure shall be acceptable to the Owner.
 2. Use of power-actuated fasteners and devices is permitted in the vertical surfaces of the building only with the following requirements.
 - a. For fastening conduits 1-1/2-inch and smaller and lighting fixtures 50 lbs or less.
 - b. Load capacity per manufacturers' recommendations.
 - c. Fasteners shall be located in the thickest part of the slab.
 - d. Devices shall comply with OSHA requirements.
 3. Use of lead shield expansion anchors is not permitted.
 4. No electrical items shall rest on, or depend for support on suspended ceiling media (tiles, lath, plaster, splines, etc.).
 5. In spaces with suspended ceilings, support conduits directly from structural slabs, decks (or framing members). Do not support conduits on ceiling suspension members.
 6. Provide weight-distribution facilities, where required so as not to exceed the load bearing capabilities of floor or walls that bear the weight of, or support, electrical items.
 7. For point-of-attachment weight of 100 lbs. or less, fasten items as follows:

- a. On wood, use wood screws.
 - b. On concrete and solid masonry that is already in place, use self-drilling concrete anchors or expansion bolt and couplings.
 - c. On hollow construction, use toggle bolts.
 - d. On structural steel, use beam clamps.
8. For point-of-attachment weights from 100 lbs. to 300 lbs., provide supports as follows:
- a. At cast-in-place concrete slabs, use concrete inserts in bottom of slab, with 8" slip-through steel rods set transverse to the reinforcing steel.
 - b. At concrete slab already in place, uses 16-inches x 8-inches x ½-inch steel plates at the top of the slab, with through-bolts welded in place. The plates shall be chased in and grouted flush, where no fill is to be applied.
9. Equipment shall not be held in place by its own dead weight. Provide base anchor fasteners in each case.
10. Trapeze type hangers may be used where several conduits are to be installed at the same elevation. The spacing of such trapeze hangers shall be in accordance with the NEC for the smallest conduit in the run.
11. Vertical conduits shall be supported by heavy wrought iron clamps or collars anchored to construction at each floor.

M. Inserts:

1. Inserts for suspended items in poured concrete construction shall be malleable-iron concrete inserts, adjustable type with insert nut. Items manufactured by Barrett, Crawford, Elcen, or Grinnell shall be used where applicable.
2. Inserts for surface-mounted items shall be suitable for the composition of the slab, wall, or structure on which installation is to be made.

N. TABLE I: SPACING FOR RACEWAY SUPPORTS

TABLE I: SPACING FOR RACEWAY SUPPORTS				
Raceway Size (Inches)	No. of Conductors in Run	Location	PVC & RMC (Ft.)	EMT (Ft.)
		HORIZONTAL RUNS		
3/4	1 or 2	Flat ceiling or wall.	5	5
3/4	1 or 2	Where it is difficult to provide supports except at intervals fixed by the building construction.	7	7
3/4	3 or more	Any location.	7	7
3/4 - 1	3 or more	Any location.		
1 & larger	1 or 2	Flat ceiling or wall.	6	6
1 & larger	1 or more	Where it is difficult to provide supports except at intervals fixed by the building construction.	10	10
1 & larger	3 or more	Any location.	10	10
Any	---	Concealed.	10	10
		VERTICAL RUNS		
1/2, 3/4	---	Exposed.	7	7
1, 1-1/4	---	Exposed.	8	8
1-1/2 & larger	---	Exposed.	10	10
Any	---	Concealed.	10	10

Abbreviations:	EMT	Electrical Metallic Tubing
	RMC	Rigid Metal Conduit

3.3. CLEANUP

- A. Upon completion of this Section of work, remove all protective wraps and debris. Repair any damage due to installation of this section of work.

3.4. PROTECTION

- A. During installation, protect this work from damage.
- B. Upon completion of this scope of work, it shall become the responsibility of the General Contractor to protect this work from damage during the remainder of construction on the project and until substantial completion.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 26 SECTION 26 05 33
RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS	3
1.2. SUMMARY	3
1.3. DEFINITIONS	4
1.4. SUBMITTALS	4
1.5. QUALITY ASSURANCE	4
1.6. COORDINATION	4
1.7. PROJECT RECORD DOCUMENTS:	4
PART 2. PRODUCTS	5
2.1. MANUFACTURERS	5
2.2. METAL CONDUIT AND TUBING	6
2.3. NONMETALLIC CONDUIT AND TUBING	6
2.4. METAL WIREWAYS	6
2.5. OUTLET AND DEVICE BOXES	7
2.6. PULL AND JUNCTION BOXES	7
2.7. BOX EXTENSIONS	7
2.8. BUSHINGS	7
PART 3. EXECUTION	7
3.1. EXAMINATION	7
3.2. RACEWAY AND BOX REQUIREMENTS	7
3.3. INSTALLATION OF RACEWAYS	11
3.4. INSTALLATION OF BOXES	14
3.5. INSTALLATION OF TERMINATIONS	16
3.6. FLEXIBLE CONNECTIONS	16
3.7. PAINTING AND FINISHES	16
3.8. PROTECTION	17
3.9. CLEANING	17
END OF SECTION	17

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 33 RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections include the following:
 - 1. Division 26 Section 260519, "Low-Voltage Electrical Power Conductors and Cables", for conductors installed in raceways and boxes and conductor terminations.
 - 2. Division 26 Section 260528, "Firestopping for Electrical Systems", for requirements for firestopping at penetrations through walls and floors that are fire barriers.
 - 3. Division 26 Section 260529, "Hangers and Supports for Electrical Systems", for raceways and box supports.
 - 4. Division 26 Section 260533.23, "Surface Raceways for Electrical Systems", for surface raceways, fittings, and accessories.
 - 5. Division 26 Section 262726, "Wiring Devices", for devices installed in boxes.

1.2. SUMMARY

- A. This Section includes raceways, fittings, boxes, enclosures, and cabinets for electrical wiring.
 - 1. Raceways include the following:
 - a. EMT
 - b. FMC
 - c. LFMC
 - d. PVC
 - e. RMC
 - f. Wireways
 - 2. Boxes, enclosures, and cabinets include the following:
 - a. Device boxes
 - b. Outlet boxes
 - c. Pull and junction boxes
 - 3. Miscellaneous Products include the following:
 - a. Bushings

1.3. DEFINITIONS

- A. EMT: Electrical Metallic Tubing.
- B. FMC: Flexible Metal Conduit.
- C. LFMC: Liquidtight Flexible Metal Conduit.
- D. PVC: Rigid Polyvinyl Chloride Conduit.
- E. RMC: Rigid Metal Conduit.

1.4. SUBMITTALS

- A. Product Data: For raceways, wireways and fittings, hinged cover enclosures, and cabinets.
- B. Shop Drawings: Include layout drawings showing components and wiring for nonstandard boxes, enclosures, and cabinets.

1.5. QUALITY ASSURANCE

- A. Listing and Labeling: Provide raceways and boxes specified in this Section that are listed and labeled.
 - 1. The Terms "Listed" and "Labeled": As defined in NFPA 70, Article 100.
 - 2. Listing and Labeling Agency Qualifications: A "Nationally Recognized Testing Laboratory" as defined in OSHA Regulation 1910.7.
- B. Comply with NECA's "Standard of Installation" and NECA 101 "Recommended Practice for Installing Steel Conduits".
- C. Comply with NFPA 70.

1.6. COORDINATION

- A. Coordinate layout and installation of raceways and boxes with other construction elements to ensure adequate headroom, working clearance, and access.
- B. Verify routing and termination locations of conduits and boxes prior to rough-in.
- C. Conduit routing shown on Drawings is only approximate and diagrammatic. Route conduits as required for a complete conduit and wiring system.
- D. Coordinate final locations, mounting heights, and orientation of all outlet, junction, and pull boxes.

1.7. PROJECT RECORD DOCUMENTS:

- A. Accurately record routing of all concealed conduits. Record actual routing of all exposed conduits/larger than 1 inch. Indicate actual locations and mounting heights of outlet boxes, pull and junction boxes, branch circuits, arrangements, etc.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Metal Conduit and Tubing:
 - a. Allied Tube & Conduit Corporation.
 - b. Anamet, Inc.; Anaconda Metal Hose.
 - c. AFC/Monogram Company.
 - d. Carol Cable Co., Inc.
 - e. Cole Flex Corp.
 - f. Electri Flex Co.
 - g. Flexcon, Inc.; Coleman Cable Systems, Inc.
 - h. Grinnell Co.; Allied Tube and Conduit Div.
 - i. Monogram Co.; AFC.
 - j. Spiraduct, Inc.
 - k. Triangle PWC, Inc.
 - l. Wheatland Tube Corporation
 2. Conduit Bodies and Fittings:
 - a. American Electric; Construction Materials Group.
 - b. Crouse Hinds; Div. of Cooper Industries.
 - c. Emerson Electric Co.; Appleton Electric Co.
 - d. Hubbell, Inc.; Killark Electric Manufacturing Co.
 - e. Lamson & Sessions; Carlon Electrical Products.
 - f. Z/Gedney; Unit of General Signal.
 - g. Scott Fetzer Co.; Adalet PLM.
 - h. Spring City Electrical Manufacturing Co.
 - i. Thomas & Betts Corporation.
 3. Metal Wireways:
 - a. Hoffman Engineering Co.
 - b. Keystone/Rees, Inc.
 - c. Square D Co.
 4. Boxes, Enclosures, and Cabinets:
 - a. American Electric; FL Industries.
 - b. Butler Manufacturing Co.; Walker Division.
 - c. Crouse Hinds; Div. of Cooper Industries.
 - d. Electric Panelboard Co., Inc.
 - e. Erickson Electrical Equipment Co.
 - f. Hoffman Engineering Co.; Federal Hoffman, Inc.
 - g. Hubbell Inc.; Killark Electric Manufacturing Co.
 - h. Hubbell Inc.; Raco, Inc.

- i. Lamson & Sessions; Carlon Electrical Products.
- j. Z/Gedney; Unit of General Signal.
- k. Parker Electrical Manufacturing Co.
- l. Robroy Industries, Inc.; Electrical Division.
- m. Scott Fetzer Co.; Adalet PLM.
- n. Spring City Electrical Manufacturing Co.
- o. Thomas & Betts Corp.
- p. Woodhead Industries, Inc.; Daniel Woodhead Co.

2.2. METAL CONDUIT AND TUBING

- A. EMT and Fittings: Hot galvanized steel O.D. with an organic corrosion-resistant I.D. coating. Listed to UL Safety Standard 797 and manufactured in accordance with ANSI C80.3.
 - 1. Fittings: Compression type, NEMA FB1.
- B. FMC: Zinc coated steel.
- C. LFMC: Flexible steel conduit with PVC jacket.
- D. RMC: ANSI C80.1 and UL 6.
- E. Fittings: NEMA FB 1; compatible with conduit/tubing materials.

2.3. NONMETALLIC CONDUIT AND TUBING

- A. PVC: NEMA TC 2, UL 651, Schedule 40 or 80.
- B. PVC Fittings: NEMA TC 3; match to conduit or conduit/tubing type and material.

2.4. METAL WIREWAYS

- A. Material: Sheet metal sized and shaped as indicated.
- B. Fittings and Accessories: Include couplings, offsets, elbows, expansion joints, adapters, hold down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- C. Select features, unless otherwise indicated, as required to complete wiring system and to comply with NFPA 70.
- D. Wireway Covers: Screw cover type.
- E. Finish:
 - 1. Dry Interior Locations: Manufacturer's standard enamel or galvanized finish, NEMA 1.
 - 2. Damp/Wet Locations: ANSI 49 gray polyester over phosphatized steel, NEMA 3R.

2.5. OUTLET AND DEVICE BOXES

- A. Sheet Metal Boxes: NEMA OS 1, galvanized flat-rolled sheet steel.
- B. Cast Metal Boxes: NEMA FB 1, Type FD, cast box, deep type, with gasketed cover, and threaded hubs.
- C. Outlet Box Accessories: Provide outlet box accessories as required for each installation, including corrosion-resistant screws, mounting brackets, wallboard hangers, extension rings, fixture studs, cable clamps, and metal straps for supporting outlet boxes which are compatible with outlet boxes being used and fulfilling requirements of individual wiring situations.

2.6. PULL AND JUNCTION BOXES

- A. Small Sheet Metal Boxes: NEMA OS 1, galvanized flat-rolled sheet steel.
- B. Sheet metal boxes over 12" in any dimension shall comply with the requirements of Article "Enclosures and Cabinets" of this Section.
- C. Boxes for Outdoor and Wet Locations: Flat flanged, surface-mounted, UL listed as raintight, galvanized cast iron box and cover with neoprene gasket and stainless-steel cover screws.

2.7. BOX EXTENSIONS

- A. Prohibited on new construction.
- B. Where more than one box is needed to flush out installation, provide a large (i.e., 6" x 6") box to flush out the existing box and nipple over to a new box.

2.8. BUSHINGS

- A. Bushings shall be self-extinguishing thermoplastic type with 105 degrees C (minimum) temperature rating.
- B. Bushings with grounding lugs shall be malleable iron body with 105 degrees C (minimum) insulating ring. Insulating material shall be locked in place and non-removable.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Examine surfaces to receive raceways, boxes, enclosures, and cabinets for compliance with installation tolerances and other conditions affecting performance of raceway installation. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.2. RACEWAY AND BOX REQUIREMENTS

- A. Conduit Application Schedule:

APPLICATION	CONDUIT TYPE	REMARKS
Exposed exterior locations.	RMC	Use threaded or rain-tight fittings and stainless steel hardware.
Damp/Wet interior locations.	RMC	Use threaded or rain-tight fittings and stainless steel hardware.
Exposed dry interior locations.	EMT, RMC	Schedule 40 PVC is acceptable for concealing grounding electrode conductors, except for plenum spaces. Provide RMC conduit where subject to physical damage.
Exterior underground.	RNC (Sched. 40 PVC)	RMC Elbows/Sweeps unless otherwise noted on the Drawings. Coat RMC with two heavy coats of asphaltum, or provide PVC-coated RMC.
Equipment connections in dry interior locations.	FMC (e.g. Greenfield)	Short lengths only (maximum 6 feet).
Equipment connections in wet interior locations.	LFMC (e.g. Sealtite)	Short lengths only (maximum 6 feet). Use threaded or rain-tight fittings and stainless steel hardware.
Equipment connections in exterior locations.	LFMC (e.g. Sealtite)	Short lengths only (maximum 6 feet). Use threaded or rain-tight fittings and stainless steel hardware.
Concealed in dry wall construction.	EMT	
Concealed above suspended ceilings.	EMT	
Concealed in masonry walls.	EMT	

B. General Requirements

1. Provide hot-dip Rigid Metal Conduit (RMC) for exposed work in locations subject to physical damage and for work in damp/wet locations.
2. Conduits for exterior underground electric work shall be rigid steel, galvanized and sherardized, leaving the building and to points 5 feet beyond footings. Beyond 5 feet of building, underground conduits shall be non-metallic Schedule 40 PVC, Type II.
3. Elbows for conduits turning up through slabs and/or equipment pads shall be rigid metal conduit (RMC) unless otherwise noted on the Drawings or required by the electric utility.
4. Conduits shall slope from entrance equipment toward outside of building.
5. Aluminum conduit is prohibited.

C. Fittings:

1. All fittings to match conduit material and to be suitable for the purpose intended. Join conduit with fittings designed and approved for the purpose and make joints

tight.

2. Provide UL listed compound filled sealing fittings for NEC-required locations, for conduits passing from interior to exterior, and at the interface of widely different space temperatures such as refrigeration or cold storage rooms where conduits pass from warm locations to cool locations, such as the boundaries of air-conditioned spaces and non-conditioned air spaces. For concealed conduits, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces.
3. Provide expansion fittings with bonding jumpers where conduits cross expansion joints or where otherwise required to compensate for thermal expansion and contraction. Provide expansion fittings in each straight uninterrupted run of surface-mounted conduit, both horizontal and vertical, in excess of 200 feet. Distance between fittings shall not exceed 200 linear feet. The Contractor shall refer to the Architectural Drawings for expansion joint locations.
4. Fasten rigid steel conduit with threaded galvanized steel fittings, double locknuts, and insulated bushings. Insulated bushings shall be OZ/Gedney type "B", or equal.
5. Fasten EMT conduit with concrete-tight or rain-tight compression fittings made from zinc-plated steel. Fittings using set screw or indentations as a means of attachment or made from cast "white metal" are prohibited. All connectors shall have insulated throats.
6. Fasten liquid-tight conduit with fittings incorporating a threaded ferrule, nylon sealing ring, and steel or malleable iron compression nut and body. Furnish Crouse Hinds metallic liquid-tight fittings, or equal.
7. Fasten Flexible Metallic Conduit (FMC) with Thomas & Betts (T&B) "Tite-Bite" insulated connectors, or equal.
8. Watertight fittings shall use a copper base anti-corrosive conductive compound. Provide watertight fittings for conduits in damp or wet locations and underground locations.

D. Box Locations:

1. Electrical boxes shall accommodate wire pulling, splices, taps, equipment connections and Code compliance.
2. Coordinate access doors as required to provide access to boxes in hard ceilings and similar inaccessible areas.

E. Outlet Boxes:

1. Outlet boxes for dry interior locations and for concealed work shall be zinc-coated or cadmium-plated sheet steel boxes suitable for the service and type outlet.
2. Extra-large boxes shall be provided in accordance with the National Electrical Code where necessary to prevent crowding of wire in the box.

3. Plastic boxes and cast "white metal" boxes classified as NEMA 4 will not be acceptable.
4. Outlet boxes in un-plastered brick or block walls shall be provided with deep square-cut device covers. They shall be set so that the brick or block can be cut and fitted closely to the cover opening and so that the standard wall plate will cover the joint between the brick or block and the box.
5. All outlet boxes used for supporting fixtures shall be furnished with malleable iron fixture studs of "no-bolt" type secured by locknut.
6. Provide support for boxes occurring in suspended ceilings. Outlets in ceilings directly on bottom of joists shall be supported independent of ceiling construction. Outlets in suspended ceilings shall not be supported from ceiling construction.
7. All boxes, whether outlet, junction, pull, or equipment, shall be furnished with appropriate covers.
8. No sectionalized boxes shall be used.
9. Back-to-back outlet boxes are not permitted. Separate boxes a minimum of 6" in standard walls and a minimum of 2 feet in acoustical walls.
10. Provide factory-made knockout closures for unused openings in outlet boxes.
11. Provide blank coverplates for all unused boxes.
12. For multiple device installations, provide multi-gang boxes. Sectional boxes are not permitted. Provide barrier separation of different voltage conductors in the same box.
13. Provide recessed outlet boxes in finished areas, supported from interior partition studs. Supports are to be stamped steel stud bridges for hollow stud walls and adjustable steel channel fasteners for flush ceiling outlet boxes.
14. Provide back supports for boxes in metal stud walls.

F. Junction and Pull Boxes:

1. Junction and pull boxes shall be furnished and installed as shown or where required to facilitate pulling of wires or cables. Such boxes shall be installed in accessible locations. All boxes for concealed work shall be constructed of 12-gauge USS galvanized sheet steel minimum, unless otherwise specified or indicated and provided with mounting brackets and flat screw covers secured in position by round head brass or stainless steel 300 grade machine screws. Boxes for exterior work shall be cast aluminum or galvanized cast iron type with threaded hubs unless otherwise directed. Gasketed cover plates shall be furnished for outdoor installation.
2. Wherever possible, locate pull and junction boxes above accessible ceilings in finished areas.

3. Pull or junction boxes shall be supported independently of conduit.

3.3. INSTALLATION OF RACEWAYS

- A. Install raceways, boxes, enclosures, and cabinets as indicated, according to manufacturer's written instructions.
- B. Furnish and install a separate and independent raceway system as shown on the Drawings for each of the various wiring systems including, but not limited to, the following:
 1. Communications System
 2. Control Wiring
 3. Power 120/208 volt
 4. Power 277/480 volt
- C. All raceway systems shall be completely wired as specified herein, shown on drawings and/or required for satisfactory operation of the various systems.
- D. Raceways, generally, shall be concealed conduit as specified herein. Where wiring troughs are required or used to facilitate the wiring installation, they shall be equal to Square D Company's Square-Duct and fittings, with hinged cover arranged for total removal, all finished in baked enamel and all components U/L listed. The gutters shall be of ample size to accommodate conductors therein and as required by the NEC.
- E. Support all conduit not embedded in concrete or masonry such that strain is not transmitted to outlet boxes and pull/junction boxes, etc. Supports to be sufficiently rigid to prevent distortion of conduits during wire pulling.
- F. Minimum Raceway Size:
 1. 3/4-inch trade size for interior work
 2. 1-inch trade size for exterior underground work.
- G. Conceal raceways within finished walls, ceilings, and floors wherever possible, unless otherwise indicated.
- H. Electrical Metallic Tubing (EMT) shall be used for the following unless otherwise indicated:
 1. Branch circuits and feeders for lighting, receptacles, and power concealed in:
 - a. Dry wall construction.
 - b. Hard ceilings, e.g. gypsum, plaster, etc.
 - c. Masonry walls.
 2. Exposed in equipment room areas as needed to serve fixed equipment.
 3. Circuits for communication and signaling concealed in:

- a. Dry wall construction.
 - b. Hard ceilings, e.g. gypsum, plaster, etc...
- I. Rigid Metal Conduit (RMC) shall be used for the following, unless otherwise indicated:
 - 1. Branch circuits and feeders for lighting, receptacle and power, installed exposed in areas subject to physical damage.
 - 2. Circuits for communication and signaling exposed in areas subject to physical damage.
- J. Communications, Control and Automatic Temperature Control (ATC) system wiring shall be installed in raceways within partitions, terminated 8" above accessible ceiling with 90 degree bend with insulating bushing on the end. Free-run cabling above accessible ceilings shall be supported by J-hooks and/or bridle rings at required spacing intervals. Cabling above inaccessible ceilings and in exposed locations shall be installed completely in raceway.
- K. Wiring installed concealed above hard ceilings and exposed in areas with no ceilings shall be installed in conduit.
- L. Conduit shall be run concealed wherever possible, within walls, ceilings, or floors, unless otherwise indicated or specified. Where exposed conduits runs are shown or required, they shall be run parallel to building construction and shall be suitably supported at required intervals.
- M. Conduit may be run exposed in Mechanical Equipment rooms, Electrical rooms, and where necessary in Storage rooms and unfinished areas. Where conduit is run exposed, it shall be run as close as possible to walls and ceilings and shall not interfere with equipment, ductwork and piping.
- N. Keep raceways at least 12 inches (300 mm) away from parallel runs of flues, steam or hot water pipes and other hot surfaces above 77 degrees F. Install horizontal raceway runs above water and steam piping.
- O. Install raceways level and square and at proper elevations. Provide adequate headroom.
- P. Complete raceway installation before starting conductor installation.
- Q. Support raceways as specified in Division 26 Section 260529, "Hangers and Supports for Electrical Systems". Arrange supports to prevent misalignment during wiring installation.
- R. Use capped bushings or "push-penny" plugs to prevent foreign matter from entering the conduit system during construction. Clean and plug or cap all conduits left empty for future use.
- S. Make bends and offsets so the inside diameter is not reduced. Keep legs of bends in the same plane and straight legs of offsets parallel, unless otherwise indicated.
- T. Use raceway fittings compatible with raceways and suitable for use and location. For intermediate steel conduit, use threaded rigid steel conduit fittings, unless otherwise

indicated.

- U. Run concealed raceways, with a minimum of bends, in the shortest practical distance considering the type of building construction and obstructions, unless otherwise indicated.
- V. Install exposed raceways parallel to or at right angles to nearby surfaces or structural members, and follow the surface contours as much as practical.
- W. Run parallel or banked raceways together, on common supports where practical.
- X. Make bends in parallel or banked runs from same centerline to make bends parallel. Use factory elbows only where elbows can be installed parallel; otherwise, provide field bends for parallel raceways.
- Y. Join raceways with fittings designed and approved for the purpose and make joints tight.
 - 1. Make raceway terminations tight. Use bonding bushings or wedges at connections subject to vibration. Use bonding jumpers where joints cannot be made tight.
 - 2. Use insulating bushings to protect conductors.
- Z. Tighten set screws of threadless fittings with suitable tools.
- AA. Install pull wires in empty raceways. Use 14 AWG zinc coated steel or monofilament plastic line with not less than 200 lb (90 kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of the pull wire.
- BB. Lubricants for pulling wires shall be approved for use with the types of wire and conduit installed.
- CC. All metal raceways for circuits over 250-volts to ground shall be bonded per NEC Article 250.97.
- DD. Install no more than equivalent of three 90° bends between boxes. Use conduit bodies to make sharp changes in direction, as around beams. Use factory elbows for bends in metal conduit larger than 2 inches (50 mm) in size.
- EE. Avoid moisture traps; provide junction box with drain fittings at low points in conduit system.
- FF. Die-cast fittings of pot metal will not be accepted.
- GG. Conduits shall be free of any burrs, foreign objects, and water prior to conduit installation.
- HH. Conduit placed against concrete or masonry above ground shall be fastened to the concrete or masonry with pipe straps or one screw clamp attached to the concrete by means of expansion screw anchors and screws. "Caddy Clip" type hangers or straps will be permitted only in non-exposed areas and restricted to 3/4" conduit.
- II. Rigid conduit or Electrical Metallic Tubing (EMT) shall not be strapped or fastened to equipment subject to vibration or mounted on shock-absorbing bases.

- JJ. Conduit shall be installed in such manner as to ensure against the collection of trapped condensation, and runs of conduit shall be without traps wherever possible. Drill 1/8" diameter weep holes where necessary.
- KK. Conduits run to and from cabinets shall be run neatly, in accurate manner and shall emerge from the floors and ceilings at right angles thereto.
- LL. Exposed conduit installed on or adjacent to ventilating ducts shall be installed after the ducts are in place, and shall be run from ceiling or wall junction boxes in such manner as to retain accessibility to junction box covers and to permit future removal or replacement of ducts.
- MM. Conduits and other electrical items shall not be fastened to, or supported from ventilating ducts but shall be separately supported. The method of supporting and details of the supporting members shall be reviewed by the Owner's Representative. In no case shall screws penetrate the sheet metal of the ducts.
- NN. Exposed conduit run on surface shall be supported according to Code and within three feet of each outlet, junction box, or cabinet, by galvanized malleable conduit clamps and clamp backs. Suspended conduits shall be supported every five feet by conduit hangers and round rods, or where two or more conduits are run parallel, by trapeze hangers suitably braced to prevent swaying.
- OO. Screws and other hardware for all work in damp/wet locations shall be stainless steel, unless otherwise noted.
- PP. Zinc coated galvanized steel screws may be used for interior dry locations only.
- QQ. No running threads shall be cut or used.
- RR. Conduits which are installed at this time and left empty for future use and which are five feet or more in length shall have a non-ferrous, 600 lb. tensile strength drag line left in place for future use.

3.4. INSTALLATION OF BOXES

- A. Provide grounding connections for raceway, boxes, and components as indicated and instructed by manufacturer. Tighten connectors and terminals, including screws and bolts, according to equipment manufacturer's published torque-tightening values for equipment connectors.
- B. Provide junction boxes, pull boxes, cable support boxes, and wireways as required for proper installation of the electrical work. Covers shall be accessible. Small junction boxes shall be similar to outlet boxes.
- C. Pull boxes, cable support boxes, and large junction boxes for indoor use shall be made of Code gauge steel or no less than 12 gauge. Covers shall be held in place with zinc-coated galvanized steel screws. Paint interior and exterior surfaces with rust-inhibitive paint. (Pull boxes and covers shall be hot-dipped galvanized.)
- D. Pull boxes shall be installed at all necessary points to facilitate pulling of wires and to

prevent injury to the insulation or other damage that might result from pulling resistance or for other reasons necessary for proper installation. Pull box locations shall be approved by the Owner's representative prior to installation.

- E. Where boxes are used in connection with exposed conduit, plain covers attached to the box with a suitable number of countersunk flat head machine screws shall be used.
- F. Pull boxes with barriers shall have a single cover plate and the barriers shall be of the same gauge as the pull box.
- G. Exposed pull boxes will not be permitted in finished spaces.
- H. Location of pull boxes shall be coordinated with piping, ductwork, and other equipment so as to permit sufficient clearance for maintenance and access.
- I. Pull boxes recessed in walls or partitions shall be provided with flanged type covers.
- J. Outlet boxes and covers shall be of proper Code size for the number of wires and/or conduits passing through or terminating therein, as well as the quantity, type, and dimensions of wiring device(s) installed therein. In no case shall any box be less than 4" square. Special attention shall be paid to boxes with deep wiring devices, E.G., GFCI receptacles.
- K. Outlet boxes for switches shall be of the gang type.
- L. Each circuit in each pullbox shall be marked with a tag guide denoting panels to which they connect.
- M. Boxes shall be separated to prevent sound transmission. Back-to-back boxes shall not be used.
- N. Outlet boxes shall be provided with suitable plaster rings and covers or plates.
- O. Unused knockout holes shall remain closed and those opened by error shall be closed with approved factory-made knock-out seals.
- P. Outlet boxes installed in plenum ceilings shall be in accordance with applicable codes.
- Q. Outlet boxes shall be installed true and plumb so that the covers or plates will be level and at uniform elevations for the types of outlets contained.
- R. Outlet boxes for toggle switches at doorways shall be located at the strike side of the door as finally hung.
- S. Outlet box locations as indicated shall be considered to be approximate only. Determine exact locations from architectural details or from field instructions and coordinate outlet box locations with the work of other trades.
- T. Install junction and pull boxes to be accessible.
- U. Locations of junction and pull boxes requiring access panels shall be reviewed by the Owner's Representative.

- V. Install hinged-cover enclosures and cabinets plumb. Support at each corner at minimum.

3.5. INSTALLATION OF TERMINATIONS

- A. Where raceways are terminated with lock nuts and bushings, align the raceway to enter squarely, and install the lock nuts with dished part against the box. Where terminations cannot be made secure with one lock nut, use two lock nuts, one inside and one outside of the box.
- B. Where terminating in threaded hubs, screw the raceway or fitting tight into the hub so the end bears against the wire protection shoulder. Where chase nipples are used, align the raceway so the coupling is square to the box, and tighten the chase nipple so no threads are exposed.
- C. Open ends shall be capped with approved manufactured conduit seals as soon as installed and kept capped until ready to pull in conductors.
- D. Where conductors enter a raceway, cabinet, pull box, and junction box, the conductors shall be protected by an insulated bushing providing a smoothly rounded surface.
- E. Water tight hubs or double lock nuts shall be used at termination of rigid conduit in knock-out openings.
- F. Ends of conduits shall be equipped with insulating bushings for 1" and smaller, and insulated metallic bushings for 1-1/4" and larger. Ends of conduit shall be temporarily capped prior to installation and during construction to exclude foreign material.

3.6. FLEXIBLE CONNECTIONS

- A. Provide Flexible Metal Conduit (FMC), e.g. Greenfield, in short lengths (maximum 6 feet) for the final connection of equipment in dry interior locations.
- B. Provide Liquidtight Flexible Metal Conduit (LFMC), e.g. Sealtite, in short lengths (maximum 6 feet) for the final connection of exterior equipment, motors and equipment in damp or wet locations as defined in Division 26 Section "Common Work Results for Electrical".
- C. Grounding conductors with green colored insulation shall be extended through all flexible connections including fixture "whips", and fastened to terminals within the first junction boxes on either side of the flexible length.
- D. Flexible connections shall be sized per the Contract Drawings, or as required in accordance with Code; the more stringent requirement shall apply.

3.7. PAINTING AND FINISHES

- A. All exterior equipment and conduits shall be painted to match adjacent surface in color as selected by Owner, unless otherwise indicated by the Owner.
- B. All exposed conduit, boxes, equipment, etc. in finished spaces shall be painted. Colors shall be as selected by the Owner and conform to ANSI Standards.

3.8. PROTECTION

- A. Provide final protection and maintain conditions, in a manner acceptable to Manufacturer and Installer that ensure coatings, finishes, and cabinets are without damage or deterioration at the time of Substantial Completion.
- B. Repair damage to galvanized finishes with zinc rich paint recommended by manufacturer.
- C. Repair damage to paint finishes with matching touchup coating recommended by manufacturer.
- D. Steel conduit: Conduit that shows corrosion within the guarantee period shall be replaced.

3.9. CLEANING

- A. On completion of installation, including outlet fittings and devices, inspect exposed finish. Remove burrs, dirt, and construction debris and repair damaged finish, including chips, scratches, and abrasions.
- B. After conduits and accessories have been installed, and concreting operations completed, conduit runs shall be satisfactorily cleared of obstructions and foreign matter. Defects which might damage cable upon installation shall be corrected. Where new conduits installed are connected to existing conduits or new conduits installed by others, the entire run to the nearest box or other termination point shall be cleaned.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 26 SECTION 26 05 33.23
SURFACE RACEWAYS FOR ELECTRICAL SYSTEMS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SCOPE	3
1.3. CLASSIFICATION AND USE	3
1.4. SUBMITTALS	3
PART 2. PRODUCTS.....	3
2.1. MANUFACTURERS	3
2.2. MATERIALS.....	3
2.3. SINGLE-CHANNEL SURFACE METAL RACEWAY.....	4
PART 3. EXECUTION.....	4
3.1. INSTALLATION	4
3.2. REMODELING WORK	5
3.3. PAINTING AND FINISHES	6
END OF SECTION	6

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 33.23 SURFACE RACEWAYS FOR ELECTRICAL SYSTEMS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and General Provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SCOPE

- A. This specification covers a surface metal raceway systems used for branch circuit wiring or data network, voice, video and other low-voltage wiring. The metal raceway systems shall consist of raceway, appropriate fittings and device boxes to complete installation per the Electrical Drawings.
- B. In finished spaces, where conduit cannot be concealed and/or routed through existing walls, surface metal raceway shall be used. This applies to devices and equipment under Division 23 (e.g. thermostats, humidistats, control wiring, etc...), Division 26 (e.g. receptacles, switches, branch circuit wiring, etc...) and Division 27 (data/voice outlets, communications cabling, etc...).
- C. The contractor shall thoroughly review the complete set of architectural drawings to determine existing wall types and locations.

1.3. CLASSIFICATION AND USE

- A. Surface metal raceway is to be utilized in dry interior locations only as covered in Article 386 of the National Electrical Code, as adopted by the National Fire Protection Association and as approved by the American National Standards Institute. Surface metal raceway systems shall be listed by Underwriters Laboratories under File Nos. E4376 Guide RJBT and E41751 Guide RJPR.

1.4. SUBMITTALS

- A. Submittals shall include catalog cuts of mounting devices, material sections, accessories, internal area descriptions, and wiring capacity charts. Submit sample of finish colors for final selection and approval.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. The surface metal raceway system specified herein for branch circuit wiring or low-voltage wiring shall be manufactured by The Wiremold Company, Hubbell, or Steel City. Systems of other manufacturers may be considered equal if, in the opinion, and the written approval of the Engineer, they meet all the performance standards specified herein.

2.2. MATERIALS

- A. The raceway and all system components must be UL Listed. They shall be manufactured of steel; zinc plated, galvanized and/or finished in ScuffCoat™ (a polyester topcoat over

base) and shall be suitable for field repainting to match surroundings.

2.3. SINGLE-CHANNEL SURFACE METAL RACEWAY

- A. Description: The raceway shall be a one-piece design with a base and cover factory assembled. Nominal raceway dimensions shall be 3/4" wide by 21/32" deep, with an approximate cross-sectional area of 0.30 square inches. The raceway base and cover shall have an approximate thickness of 0.040". The raceway shall be available in five and ten foot lengths.
- B. Fittings: A full complement of fittings must be available including but not limited to mounting clips and straps, couplings, flat, internal and external elbows, cover clips, tees, entrance fittings, conduit connectors and bushings. The covers shall be painted with an enamel finish, color to match the raceway. They shall overlap the raceway to hide uneven cuts. All fittings shall be supplied with a base where applicable. A transition fitting shall be available to adapt to other raceways.
- C. Device Boxes:
 - 1. Device boxes shall be available for mounting standard devices and faceplates. A device box shall be available in single- and multiple-gang configurations, up to six-gang. Single-gang boxes shall allow for snap-on and fastener application. Minimum depth shall be 2-1/4".
 - 2. Provide extra deep boxes (nominal 4" depth) where required to accommodate large devices.
 - 3. Extension boxes shall be available to adapt to existing standard flush switch and receptacle boxes.
 - 4. Round fixture and extension boxes shall be available to mount fixtures and other devices with mounting centers of 1-15/32", 1-5/8", 1-23/32", 1-27/32", 2-3/4", 3-1/2" and 4-1/16" diameters. Round fixture and extension boxes shall be available in depths ranging from 0.47" to 1.00" and in diameters of 3.00", 4.75", 5.50" and 6.38".
- D. Finish: Raceway components (e.g. base, cover, boxes, fittings, etc.) shall be painted with an enamel finish, ivory.
- E. Basis of Design: Wiremold V700 Series raceway with 5700 Series device boxes.

PART 3. EXECUTION

3.1. INSTALLATION

- A. Prior to and during installation, refer to system layout or approval drawings containing all elements of the system. Installer shall comply with detailed manufacturer's instruction sheets which accompany system components as well as complete system instruction sheets, whichever is applicable.
- B. Mechanical Security: All raceway systems shall be mechanically continuous and

connected to all electrical outlets, boxes, device mounting brackets, and cabinets, also in accordance with manufacturer's installation sheets.

- C. Electrical Security: All metal raceway shall be electrically continuous and bonded in accordance with the National Electrical Code for proper grounding.
- D. Raceway Support: Raceway shall be securely supported at intervals not exceeding 10 feet or in accordance with manufacturer's installation sheets.
- E. Completeness: All raceway systems shall be installed complete, including insulating bushings and inserts, appropriate fittings, and mounting hardware. All unused raceway openings shall be closed. All fittings shall be furnished by the raceway manufacturer.
- F. Provide grounding per the National Electrical Code and Local Codes. Maintain grounding continuity between raceway components to provide a continuous grounding path.
- G. All surface metal raceways shall be installed parallel with and perpendicular to the structure. All exposed edges where field cut, shall be coated by the Contractor to prevent corrosion, and field-painted to match surface raceway finish.
- H. Field cut straight cover sections between specific device covers.
- I. Use flat-head screws to fasten channel to surfaces. Mount plumb and level. Channels shall be secured at least every four feet (1220mm) with two-hole straps.
- J. Use suitable insulating bushings and inserts at connections to outlets and corner fittings.
- K. Fastener Option: Use clips and straps suitable for the purpose.
- L. Raceway surfaces damaged during installation shall be touched up with raceway manufacturer's matching paint.
- M. Provide UL-approved expansion fittings, complete with grounding jumpers, where raceways cross building expansion joints.
- N. Allow a minimum of 6-inches (152 mm) clearance from heat sources.
- O. Surface raceways shall be visually seamless, without gaps between sections. Gaps exceeding the width of 1/16-inch shall be corrected to reduce width of gap.
- P. Cut ceiling tiles tight to surface raceway, within a 1/4-inch tolerance. Ceiling tile not cut tight to raceway shall be replaced at Contractor's expense.
- Q. Provide manufacturer's touch-up paint. Paint all screws and scratches to match surface raceway.

3.2. REMODELING WORK

- A. Surface metal raceway shall only be utilized where devices and/or wiring cannot be concealed in existing walls, unless otherwise indicated on the Contract Documents.
 - 1. New devices installed in existing metal stud/GWB walls shall be cut in with

conduit/wiring concealed within the wall.

2. New devices installed on existing CMU walls, where devices cannot be concealed, shall be installed in surface-mounted device boxes as specified in this section served by surface metal raceway as specified in this Section.
- B. Exposed wiring on existing walls in finished areas, (e.g. classrooms, offices, corridors, toilets, etc.), shall be installed in surface metal raceways. The exposed raceways shall be run in corners, adjacent to door trims, and in other ways to be as inconspicuous as possible, even when requiring additional lengths.
- C. All exposed raceways shall be painted to match adjacent surface(s) unless otherwise directed by the Owner.
- D. All exposed raceways shall be installed in a manner approved by the Architect/Engineer.
- E. The exposed runs shall not be across an open wall surface.
- F. Horizontal runs of raceways shall be kept to an absolute minimum. Exposed raceway shall be run vertically into ceiling spaces above and below.

3.3. PAINTING AND FINISHES

- A. All exposed surface raceway, boxes, etc. in finished spaces shall be painted to match adjacent surfaces. Colors shall be as selected by the Owner and shall conform to ANSI Standards.

END OF SECTION

DIVISION 26 SECTION 26 05 53
IDENTIFICATION FOR ELECTRICAL SYSTEMS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SUMMARY	3
1.3. SUBMITTALS	3
1.4. QUALITY ASSURANCE	3
PART 2. PRODUCTS.....	3
2.1. RACEWAY AND CABLE LABELS	3
2.2. WIRING DEVICE FACEPLATE LABELS.....	4
2.3. EQUIPMENT NAMEPLATES	4
2.4. MISCELLANEOUS IDENTIFICATION PRODUCTS.....	5
PART 3. EXECUTION.....	5
3.1. INSTALLATION	5
END OF SECTION	9

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 53 IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections include the following:
 - 1. Division 26 Section 260520, "Electric Heating Cables", for labeling materials specific to electrically heat-traced piping.
 - 2. Division 26 Section 260573, "Power System Studies", for arc-flash hazard labels for electrical equipment.
 - 3. Division 26 Section 262416, "Panelboards", for circuit directories to be installed in panelboards.

1.2. SUMMARY

- A. This Section includes electrical identification materials and devices required to comply with ANSI C2, NFPA 70, OSHA standards, and authorities having jurisdiction.
- B. This section includes labeling of all terminations and related subsystems; including, but not limited to, nameplates, wire and cable markers, labeling and identification of cables, equipment and other products.

1.3. SUBMITTALS

- A. Product Data: For each electrical identification product indicated.

1.4. QUALITY ASSURANCE

- A. Comply with ANSI C2.
- B. Comply with NFPA 70.
- C. Comply with ANSI A13.1 and NFPA 70 for color-coding.
- D. Comply with applicable EIA/TIA Standards.
- E. Comply with OSHA Standards.

PART 2. PRODUCTS

2.1. RACEWAY AND CABLE LABELS

- A. Comply with ANSI A13.1, Table 3, for minimum size of letters for legend and for minimum length of color field for each raceway and cable size.

1. Color: Black letters on orange field.
2. Legend: Indicates voltage and service.
- B. Adhesive Labels: Preprinted, flexible, self-adhesive vinyl with legend, overlaminated with a clear, weather- and chemical-resistant coating.
- C. Pretensioned, Wraparound Plastic Sleeves: Flexible, preprinted, color-coded, acrylic band sized to suit the diameter of the line it identifies and arranged to stay in place by pretensioned gripping action when placed in position.
- D. Colored Adhesive Tape: Self-adhesive vinyl tape not less than 3 mils thick by 3/4 inch wide, in appropriate colors for system voltage and phase.
- E. Tape Markers: Vinyl or vinyl-cloth, self-adhesive, wraparound type with preprinted numbers and letters.

2.2. WIRING DEVICE FACEPLATE LABELS

- A. Adhesive Labels:
 1. Thermal transfer printable, clear polyester material with glossy finish, 1/2" high, width as required. Printed lettering shall be 1/4" high black text.
 2. Labels shall be backed with permanent acrylic adhesive and shall exhibit good adhesion to many metal and other types of surfaces, including textured surfaces and low surface energy plastics.
 3. Labels shall be resistant to humidity, temperature and UV light.
 4. Labels shall meet requirements of UL 969 Labeling and Marking Standard and shall be RoHS compliant.
 5. Provide Brady B-432 Series, or approved equal by acceptable manufacturer.

2.3. EQUIPMENT NAMEPLATES

- A. General Nameplate Requirements:
 1. Use colors prescribed by ANSI A13.1, NFPA 70 and as follows:
 - a. Normal Power System: White lettering on black background.
 2. Backed with adhesive material formulated for the type of surface, intended use and installed location.
- B. Nameplates for Dry, Interior Locations:
 1. Engraving stock, melamine 3-layer plastic laminate.
 2. Minimum 1/16-inch (1.6-mm) thick for signs up to 20 sq. inches (129 sq. cm)

3. Minimum 1/8-inch (3.2-mm) thick for signs larger than 20 sq. inches.
- C. Nameplates for Damp/Wet Interior and Exterior Locations:
 1. Weather-resistant, UV Resistant, minimum 1/8-inch (3.2-mm) thick.
- D. Refer to Contract Drawings for typical nameplate details.
- E. Refer to Paragraph "Equipment Identification Nameplates" under Part 3 of this Section for installation requirements.

2.4. MISCELLANEOUS IDENTIFICATION PRODUCTS

- A. Cable Ties: Fungus-inert, self-extinguishing, one-piece, self-locking, Type 6/6 nylon cable ties.
 1. Minimum Width: 3/16 inch (5 mm).
 2. Tensile Strength: 50 lb (22.3 kg) minimum.
 3. Temperature Range: Minus 40 to plus 185 deg F (Minus 40 to plus 85 deg C).
 4. Color: According to color-coding.
- B. Paint: Formulated for the type of surface and intended use.
 1. Primer for Galvanized Metal: Single-component acrylic formulated for galvanized surfaces.
 2. Primer for Concrete Masonry Units: Heavy-duty-resin block filler.
 3. Primer for Concrete: Clear, alkali-resistant, binder-type sealer.
 4. Enamel: Silicone-alkyd or alkyd urethane as recommended by primer manufacturer.

PART 3. EXECUTION

3.1. INSTALLATION

- A. General:
 1. Where mixed voltages are used in one building (e.g., 480 volts, 208 volts), each new piece of equipment, including but not limited to, panelboard(s), safety switches, outlet/pull/junction boxes, etc., on each system must be labeled for voltage in addition to other requirements listed herein.
 2. All branch circuit panelboards must be identified with the same designation used in the circuit directory in the Main Distribution Panelboard/Main Switchboard and in Distribution Panelboards.
 3. Before attaching labels, clean all surfaces with the label manufacturer's

recommended cleaning agent.

4. Install all labels firmly, as recommended by the label manufacturer.
5. Labels attached to wiring device faceplates and electrical equipment shall be installed plumb and neatly on all equipment.
6. Install nameplates/labels parallel to equipment lines.
7. Install nameplates/labels on equipment fronts/covers unless otherwise noted.
8. Install nameplates/labels on inside face of equipment door/cover, including junction boxes, where exposed in finished spaces.
9. Secure nameplates to inside of recessed panelboards in finished locations.
10. Embossed tape will not be permitted for any application.
11. Stenciling is prohibited.
12. Labels: All labels shall be permanent and be machine-generated. NO HANDWRITTEN OR NON-PERMANENT LABELS SHALL BE ALLOWED.
13. Label size shall be appropriate for the conductor/cable size(s), and wiring device faceplate layout. All labels to be used shall be self-laminating, white/transparent vinyl and be wrapped around the conductor/cable sheath. Flag type labels are not allowed. The labels shall be of adequate size to accommodate the circumference of the cable being labeled and properly self-laminated over the full extent of the printed area of the label.

B. Panelboard Circuit Directories:

1. Panelboards shall be equipped with equipment nameplates as specified in paragraph "Equipment Identifications Labels" in this Section.
2. Panelboards shall have accurate typed circuit directories indicating exactly what each branch circuit serves.
3. The Contractor shall provide up to date circuit directories in new and existing panelboards, indicating all deletions and additions, and to note the date of all changes on the directory.
4. The circuit directories shall reflect the actual room numbers. Directories indicating the reference room numbers on the contract drawings or in the panelboard schedule shall not be acceptable.
5. The circuit directories shall include the name, address, and contact information for the Electrical/Division 26 Contractor.
6. If at any time after occupancy the circuit directories are found to be incorrect due to negligence by the installer, then the Contractor shall trace out circuits, and correct the directories at no additional cost to the Owner.

- C. Miscellaneous Identification:
 - 1. Individual circuit breakers, in distribution panelboards and switchboards: 1/4-inch text (6 mm); identify circuit and load served, including location.
 - 2. Individual circuit breakers, enclosed switches, and motor starters: 1/4-inch text (6 mm); identify load served, circuit and voltage.
 - 3. Junction boxes: 1/4-inch text (13 mm); identify load served, circuit and voltage.
- D. Identification Materials and Devices: Install at locations for most convenient viewing without interference with operation and maintenance of equipment.
- E. Lettering, Colors, and Graphics: Coordinate names, abbreviations, colors, and other designations with corresponding designations in the Contract Documents or with those required by codes and standards. Use consistent designations throughout Project.
- F. Sequence of Work: If identification is applied to surfaces that require finish, install identification after completing finish work.
- G. Self-Adhesive Identification Products: Clean surfaces before applying.
- H. Install painted identification according to manufacturer's written instructions and as follows:
 - 1. Clean surfaces of dust, loose material, and oily films before painting.
 - 2. Prime surfaces using type of primer specified for surface.
 - 3. Apply one intermediate and one finish coat of enamel.
- I. Caution Labels for Boxes and Enclosures: Provide pressure-sensitive, self-adhesive labels identifying system voltage with black letters on orange background.
- J. Circuit Identification Labels on Boxes:
 - 1. Exposed Boxes: Pressure-sensitive, self-adhesive plastic label on cover.
 - 2. Concealed Boxes: Plasticized card-stock tags.
 - 3. Labeling Legend: Permanent, waterproof listing of panel and circuit number or equivalent.
- K. Feeder and Branch-Circuit Conductors: Color-code new conductors throughout the secondary electrical system. Refer to Division 26 Section 260519, "Low-Voltage Electrical Power Conductors and Cables", for additional requirements.
- L. Power-Circuit and Control Wire Identification: Metal tags or aluminum, wraparound marker bands for each conductor, cables, feeders, and power circuits in vaults, panelboard gutters, outlet boxes, junction boxes, pull boxes, switchboards, and at load connections. Identify with branch circuit or feeder number for power and lighting circuits and with control wire number as indicated on equipment manufacturer's shop drawings for control

wiring.

1. Legend: 1/4-inch- (6.4-mm-) steel letter and number stamping or embossing with legend corresponding to indicated circuit designations.
2. Tag Fasteners: Nylon cable ties.
3. Band Fasteners: Integral ears.

M. Apply identification to conductors as follows:

1. Conductors to be Extended in the Future: Indicate source and circuit numbers.
2. Multiple Power or Lighting Circuits in the Same Enclosure: Identify each conductor with source, voltage, circuit number, and phase. Use color-coding to identify circuits' voltage and phase.
3. Multiple Control and Communication Circuits in the Same Enclosure: Identify each conductor by its system and circuit designation. Use a consistent system of tags, color-coding, or cable marking tape.

N. Apply warning, caution, and instruction signs as follows:

1. Warnings, Cautions, and Instructions: Install to ensure safe operation and maintenance of electrical systems and of items to which they connect. Install engraved plastic-laminated instruction signs with approved legend where instructions are needed for system or equipment operation. Install metal-backed butyrate signs for outdoor items.

O. Equipment Nameplates

1. Install on each new unit of equipment, including central or master unit of each system. This includes power, lighting, communication, signal, and alarm systems, unless units are specified with their own self-explanatory identification.
2. Install on each new piece of equipment provided with factory installed disconnecting means, e.g. Cooling Tower units, where a separate external disconnecting means is not provided under Division 26.
3. Install on each new variable frequency drive serving pumps, fans, etc. provided by others where a separate motor controller is not provided under Division 26.
4. Unless otherwise noted, nameplates shall identify equipment designation(s), voltage rating, and source (including source locations).
5. Nameplates for disconnect switches, motor starters, etc..., shall indicate the designation of the load served as the "equipment designation".
6. In general, nameplates requiring one or two lines of text shall be 1-1/2 inches high. Labels requiring three lines of text shall be 2 inches high. The first line of text, which shall indicate equipment designation/load served, shall utilize 1/2 inch high lettering. Remaining lines of text, which shall indicate voltage ratings and source

information shall utilize ¼ inch high lettering. Refer to the Drawings for nameplate examples.

7. Apply nameplates to each unit of the following categories of equipment:
 - a. Panelboards.
 - b. Disconnect Switches.
 - c. Motor Controllers.
 - d. Electrical Cabinets and Enclosures.
 - e. Access Doors and Panels for Concealed Electrical Items.
- P. Surfaces shall be cleaned and painted, if specified, before applying markings.
- Q. Place markings so that they are visible from the floor.
- R. Protect finished identification to ensure that markings are clear and legible when project is turned over to the Owner.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 26 SECTION 26 05 73
POWER SYSTEM STUDIES
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SCOPE	3
1.3. REFERENCES	3
1.4. SUBMITTALS	4
1.5. QUALITY ASSURANCE	5
PART 2. PRODUCTS.....	6
2.1. STUDIES	6
2.2. DATA	7
2.3. SHORT-CIRCUIT ANALYSIS.....	7
2.4. ARC FLASH HAZARD ANALYSIS	8
PART 3. EXECUTION.....	9
3.1. FIELD ADJUSTMENT	9
3.2. ARC FLASH HAZARD LABELS.....	9
3.3. AVAILABLE FAULT CURRENT LABELS.....	11
END OF SECTION	11

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 73 – POWER SYSTEM STUDIES

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SCOPE

- A. Power system studies shall be performed on and include all portions of the electrical distribution system. The power system studies shall include the following:
 - 1. Short-circuit analysis with protective device evaluation
 - 2. Arc flash hazard analysis
- B. The power system studies shall begin at the existing overcurrent protective device ahead of the existing pad-mounted transformer, to the existing service entrance equipment/disconnecting means, and continue through the 480Y/277V and 208Y/120V distribution systems to the existing branch panelboards, including dry-type transformers.
- C. The short-circuit analysis shall, at a minimum, include determining the available fault current at the following equipment:
 - 1. Service equipment in accordance with NEC Article 110.16(B).
 - 2. Existing panelboards affected by the work in accordance with NEC article 408.6.
 - 3. New air-conditioning and refrigeration equipment in accordance with NEC Article 440.10, including closed circuit evaporative coolers.
 - 4. New variable frequency controllers/ drives.
- D. The arc flash hazard analysis shall be per the requirements set forth in the current version of NFPA 70E – Standard for Electrical Safety in the Workplace, and shall be performed according to the latest edition of IEEE Standard 1584, the IEEE Guide for Performing Arc-Flash Calculations.

1.3. REFERENCES

- A. Institute of Electrical and Electronics Engineers, Inc. (IEEE):
 - 1. IEEE 141 – Recommended Practice for Electric Power Distribution and Coordination of Industrial and Commercial Power Systems.
 - 2. IEEE 242 – Recommended Practice for Protection and Coordination of Industrial and Commercial Power Systems.
 - 3. IEEE 399 – Recommended Practice for Industrial and Commercial Power System Analysis.

4. IEEE 241 – Recommended Practice for Electric Power Systems in Commercial Buildings.
 5. IEEE 1015 – Recommended Practice for Applying Low-Voltage Circuit Breakers Used in Industrial and Commercial Power Systems.
 6. IEEE 1584 – Guide for Performing Arc-Flash Hazard Calculations.
- B. American National Standards Institute (ANSI):
1. ANSI C57.12.00 – Standard General Requirements for Liquid-Immersed Distribution, Power, and Regulating Transformers.
 2. ANSI C37.13 – Standard for Low Voltage AC Power Circuit Breakers Used in Enclosures.
 3. ANSI C37.010 – Standard Application Guide for AC High Voltage Power Circuit Breakers Rated on a Symmetrical Current Basis.
 4. ANSI C37.41 – Standard Design Tests for High Voltage Fuses, Distribution Enclosed Single-Pole Air Switches, Fuse Disconnecting Switches and Accessories.
- C. The National Fire Protection Association (NFPA)
1. NFPA 70 – National Electrical Code, latest edition.
 2. NFPA 70E – Standard for Electrical Safety in the Workplace.

1.4. SUBMITTALS

- A. The studies shall be submitted to the Engineer prior to receiving final approval of the distribution equipment shop drawings and/or prior to release of equipment drawings for manufacturing. If formal completion of the study may cause delays in equipment shipments, approval from the Engineer may be obtained for a preliminary submittal of data to ensure that the selection of device ratings and characteristics will be satisfactory to properly select the distribution equipment. The formal study will be provided to verify preliminary findings.
- B. The results of the short circuit, protective device coordination and arc flash hazard analysis studies shall be summarized in a final report. A minimum of three (3) bound copies of the complete final report shall be submitted. Electronic PDF copies of the report shall be provided upon request.
- C. The report shall include the following sections:
1. Executive Summary including Introduction, Scope of Work and Results/Recommendations.
 2. Short-Circuit Methodology Analysis Results and Recommendations.
 3. Short-Circuit Device Evaluation Table

4. Arc Flash Hazard Methodology Analysis Results and Recommendations including the details of the incident energy and flash protection boundary calculations, along with Arc Flash boundary distances, working distances, Incident Energy levels and Personal Protection Equipment levels.
 5. Arc Flash Labeling section showing types of labels to be provided. Section will contain descriptive information as well as typical label images.
 6. One-line system diagram that shall be computer generated and will clearly identify individual equipment buses, bus numbers used in the short circuit analysis, cable and bus connections between the equipment, calculated maximum short-circuit current at each bus location, device numbers used in the time-current coordination analysis, and other information pertinent to the computer analysis.
- D. Qualification data for firms and persons specified in “Quality Assurance” Article to demonstrate their capabilities and experience. Include list of completed projects with project names, addresses, names of Engineer and Owner, and other information specified.

1.5. QUALITY ASSURANCE

- A. The short-circuit, protective device coordination and arc flash hazard analysis studies shall be conducted under the responsible charge and approval of a Registered State of Delaware Professional Electrical Engineer skilled in performing and interpreting the power system studies. Report shall be signed and sealed by the Engineer.
- B. The Registered Professional Electrical Engineer shall have a minimum of five (5) years of experience in performing power system studies.
- C. The approved engineering firm shall demonstrate experience with Arc Flash Hazard Analysis by submitting names of at least ten actual arc flash hazard analyses it has performed in the past year.
- D. Engineering Analysis and Coordination Study shall be performed by one of the following, or an approved and qualified equal.
 1. AB Engineering, LLC
303 Dressage Court
West Chester, PA 19382
Telephone: 610-765-1290
Fax: 610-785-1319
Contact: Alton Baum, P.E.
 2. Coordinated Power Engineering, Inc.
1340-G Charwood Road
Hanover, MD 21076
Telephone: 410-694-9494
Fax: 410-694-0085
Contact: Carl E. Rager, P.E.
 3. DNR Engineering, Inc.
5 Mount Vernon Court

Livingston, NJ 07039
Telephone: 973-796-8409
Contact: David Schnaper, P.E.

4. IETC
5410 Mt. Pigsah Road
York, PA 17406
Telephone: 717-252-4730
Fax: 717-252-4793
Contact: William N. Luddy, P.E.
5. Keystone Engineering Group, Inc.
590 East Lancaster Avenue, Suite 200
Frazer, PA 19355
Telephone: 610-407-4100
Fax: 610-407-4101
Contact: Philip M. Gonski, P.E.
6. Potomac Testing, Inc.
1610 Professional Blvd, Suite A
Crofton, MD 21114
Telephone: 301-352-1930
Toll-Free: 1-800-331-2022
Contact: Paul Gill, P.E.
7. Premium Power, LLC.
505 School House Road
Kennett Square, PA 19348
Telephone: 302-369-5420
Fax: 302-369-5515
Contact: Chris Fultz
8. Reuter Hanney
11620 Crossroads Circle, Suite D-E
Middle River, MD 21220
Telephone: 410-344-0300
Fax: 410-335-4389
9. Schneider Electric
9 East Court, Suite G
Owings Mills, MD 21117
Telephone: 410-559-2917
Contact: Larry Long

PART 2. PRODUCTS

2.1. STUDIES

- A. The contractor shall furnish an Arc Flash Hazard Analysis Study per NFPA 70E – Standard for Electrical Safety in the Workplace, reference Article 130.3 and Annex D. This study shall also include short-circuit and protective device coordination studies.

2.2. DATA

- A. Contractor shall furnish all data as required for the power system studies. The Engineer performing the short-circuit, protective device coordination and arc flash hazard analysis studies shall furnish the Contractor with a list of required data immediately after award of the contract. The Contractor shall expedite collection of the data to assure completion of the studies as required for final approval of the distribution equipment shop drawings and/or prior to the release of the equipment for manufacturing.
- B. Source contribution may include present and future motors.
- C. Load data utilized may include existing and proposed loads obtained from Contract Documents provided by Owner, or Contractor.
- D. If applicable, include fault contribution of existing motors in the study. The contractor shall obtain required existing equipment data, if necessary, to satisfy the study requirements.

2.3. SHORT-CIRCUIT ANALYSIS

- A. Transformer design impedances shall be used when test impedances are not available.
- B. Provide the following:
 - 1. Calculation methods and assumptions
 - 2. Selected base per unit quantities.
 - 3. One-line diagram of the system being evaluated that clearly identifies individual equipment buses, bus numbers used in the short-circuit analysis, cable and bus connections between the equipment, calculated maximum short-circuit current at each bus location and other information pertinent to the computer analysis.
 - 4. The study shall include input circuit data including electric utility system characteristics, source impedance data, conductor lengths, number of conductors per phase, conductor impedance values, insulation types, transformer impedances and X/R ratios, motor contributions, and other circuit information as related to the short-circuit calculations.
 - 5. Tabulations of calculated quantities including short-circuit currents, X/R ratios, equipment short circuit interrupting or withstand current ratings and notes regarding adequacy or inadequacy of the equipment rating.
 - 6. Results, conclusions, and recommendations. A comprehensive discussion section evaluating the adequacy or inadequacy of the equipment must be provided and include recommendations as appropriate for improvements to the system.
- C. For solidly-grounded systems, provide a bolted line-to-ground fault current study for applicable buses as determined by the engineer performing the study.
- D. Protective Device Evaluation:

1. Evaluate equipment and protective devices and compare to short circuit ratings.
2. Adequacy of panelboard bus bars to withstand short-circuit stresses.
3. Contractor shall notify Engineer in writing, of any circuit protective devices improperly rated for the calculated available fault current.

2.4. ARC FLASH HAZARD ANALYSIS

- A. The arc flash hazard analysis shall be performed according to the IEEE 1584 equations that are presented in NFPA 70E, Annex D. The arc flash hazard analysis shall be performed in conjunction with the short-circuit analysis (Section 2.03) and the protective device time-current coordination analysis (Section 2.04).
- B. The flash protection boundary and the incident energy shall be calculated at all locations in the electrical distribution system (distribution panelboard, branch panelboards) where work could be performed on energized parts.
- C. Working distances shall be based on IEEE 1584. The calculated arc flash protection boundary shall be determined using those working distances.
- D. When appropriate, the short circuit calculations and the clearing times of the phase overcurrent devices will be retrieved from the short-circuit and coordination study model. Ground overcurrent relays should not be taken into consideration when determining the clearing time when performing incident energy calculations.
- E. The short-circuit calculations and the corresponding incident energy calculations for multiple system scenarios must be compared and the greatest incident energy must be uniquely reported for each equipment location in a single table. Calculations must be performed to represent the maximum and minimum contributions of fault current magnitude for normal and emergency operating conditions. The minimum calculation will assume that the utility contribution is at a minimum. Conversely, the maximum calculation will assume a maximum contribution from the utility. Calculations shall take into consideration the parallel operation of synchronous generators with the electric utility, where applicable as well as any stand-by generator applications.
- F. The Arc-Flash Hazard Analysis shall be performed utilizing mutually agreed upon facility operational conditions, and the final report shall describe, when applicable, how these conditions differ from worst-case bolted fault conditions.
- G. The incident energy calculations must consider the accumulation of energy over time when performing arc flash calculations on buses with multiple sources. Iterative calculations must take into account the changing current contributions, as the sources are interrupted or decremented with time. Fault contribution from motors should be decremented as follows:
 1. Fault contribution from induction motors should not be considered beyond 5 cycles.
- H. For each piece of ANSI rated equipment with an enclosed main device, two calculations shall be made. A calculation shall be made for the main cubicle, sides or rear; and shall be based on a device located upstream of the equipment to clear the arcing fault. A second

calculation shall be made for the front cubicles and shall be based on the equipment's main device to clear the arcing fault. For all other non-ANSI rated equipment, only one calculation shall be required and it shall be based on a device located upstream of the equipment to clear the arcing fault.

- I. When performing incident energy calculations on the line side of a main breaker (as required per above), the line side and load side contributions must be included in the fault calculation.
- J. Mis-coordination should be check amongst all devices within the branch containing the immediate protective device upstream of the calculation location and the calculation should utilize the fastest device to compute the incident energy for the corresponding location.
- K. Arc Flash calculations shall be based on actual overcurrent protective device clearing time. A maximum clearing time of 2 seconds will be used based on IEEE 1584, Section B.1.2. Where it is not physically possible to move outside of the flash protection boundary in less than 2 seconds during an arc flash event, a maximum clearing time based on the specific location shall be utilized.
- L. Provide the following:
 - 1. Results of the Arc-Flash Hazard Analysis shall be submitted to tabular form, and shall include device or bus name, bolted fault and arcing fault current levels, flash protection boundary distances, working distances, personal protective equipment classes and AFIE (Arc Flash Incident Energy) levels.
 - 2. The Arc Flash Hazard Analysis shall report incident energy values based on recommended device setting for equipment within the scope of the study.
 - 3. The Arc-Flash Hazard Analysis may include recommendations to reduce AFIE levels and enhance worker safety.
 - 4. The Arc-Flash Hazard Analysis shall also include copies of arc-flash hazard warning labels specified in Part 3 of this Section, for all pieces of equipment receiving a label, which shall also be included in the O&M Manual specified in Division 01.

PART 3. EXECUTION

3.1. FIELD ADJUSTMENT

- A. Contractor shall adjust relay and protective device settings according to the recommended setting table provided by the coordination study.
- B. Contractor shall make minor modifications to equipment as required to accomplish conformance with short circuit and protective device coordination studies.
- C. Contractor shall notify Engineer in writing of any required major equipment modifications.

3.2. ARC FLASH HAZARD LABELS

- A. Contractor shall provide a 4.0 in. x 4.0 in. (nominal) Brady thermal transfer type label of high adhesion polyester for each work location analyzed.
- B. The labels shall be designed according to the following standards:
 - 1. UL969 – Standard for Marking and Labeling Systems
 - 2. ANSI Z535.4 – Product Safety Signs and Labels
 - 3. NFPA 70 (National Electrical Code) – Article 110.16
- C. The labels shall include the following information:
 - 1. Equipment Designation
 - 2. Source Designation
 - 3. Fault Current (kA)
 - 4. System Voltage
 - 5. Flash Protection boundary
 - 6. Personal Protective Equipment category
 - 7. Arc Flash Incident energy value (cal/cm²)
 - 8. Limited and restricted Approach Boundaries
 - 9. Study report number and issue date
 - 10. Name of Company who completed study
- D. Labels shall be printed by a thermal transfer type printer, with no field markings.
- E. Arc flash labels shall be provided for equipment as identified in the study and the respective equipment access areas per the following:
 - 1. Floor Standing Equipment – Labels shall be provided on the front of each individual section. Equipment requiring rear and/or side access shall have labels provided on each individual section access area. Equipment line-ups containing sections with multiple incident energy and flash protection boundaries shall be labeled as identified in the Arc Flash Analysis table.
 - 2. Wall Mounted Equipment – Labels shall be provided on the front cover or a nearby adjacent surface, depending upon equipment configuration.
 - 3. General Use Safety labels shall be installed on equipment in coordination with the Arc Flash labels. The General Use Safety labels shall warn of general electrical hazards associated with shock, arc flash, and explosions, and instruct workers to turn off power prior to work.

- F. Labels shall be field installed by Contractor.

3.3. AVAILABLE FAULT CURRENT LABELS

- A. Contractor shall provide a 4.0 in. x 4.0 in. Brady thermal transfer type label of high adhesion polyester to identify the maximum available fault current at the following equipment:
1. Service equipment in accordance with NEC Article 110.16(B).
 2. Existing panelboards affected by the work in accordance with NEC Article 408.6.
 3. New air-conditioning and refrigeration equipment in accordance with NEC Article 440.10, including closed circuit evaporative coolers.
 4. New variable frequency controllers/drives.
- B. The labels shall be designed according to the following standards:
1. UL969 – Standard for Marking and Labeling Systems
 2. ANSI Z535.4 – Product Safety Signs and Labels
 3. NFPA 70 (National Electrical Code) – Article 110.24.
- C. The labels shall include the following information:
1. Line 1 – “Maximum Available Fault Current”
 2. Line 2 – “_____ Amperes”; Contractor shall field mark maximum available fault current available at the line terminals of the equipment.
 3. Line 3 – Date of Installation
- D. Labels shall be printed by a thermal transfer type printer.
- E. Labels shall be field-installed by the Contractor.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 26 SECTION 26 24 16
PANELBOARDS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS	3
1.2. SUMMARY	3
1.3. REFERENCES	3
1.4. SUBMITTALS	4
1.5. QUALITY ASSURANCE	5
1.6. DELIVERY, STORAGE, AND HANDLING	5
1.7. PROJECT CONDITIONS	6
1.8. WARRANTY	6
PART 2. PRODUCTS	6
2.1. MANUFACTURERS	6
2.2. OVERCURRENT PROTECTIVE DEVICES	6
2.3. IDENTIFICATION	7
PART 3. EXECUTION	7
3.1. EXAMINATION	7
3.2. INSTALLATION	7
3.3. GROUNDING	8
3.4. CONNECTIONS	8
3.5. IDENTIFICATION	8
3.6. FIELD QUALITY CONTROL	9
3.7. CLEANING	10
3.8. PROTECTION	10
END OF SECTION	10

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 24 16 - PANELBOARDS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provision of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections include the following:
 - 1. Division 26 Section 260500, "Common Work Results for Electrical", for general materials and installation methods.
 - 2. Division 26 Section 260553, "Identification for Electrical Systems", for identification materials for labeling panelboards, including, but not limited to equipment nameplates.
 - 3. Division 26 Section 260573, "Power System Studies", for engineering analysis involving panelboards specified herein, including but not limited to short-circuit analysis.

1.2. SUMMARY

- A. This Section includes modifications to existing lighting and power panelboards and associated auxiliary equipment rated 600 V and less.
- B. Provide design and engineering, labor, material, equipment, related services and supervision required, including, but not limited to, modifications to existing panelboards as required for the complete performance of the work, and as shown on the Drawings and as specified herein.
- C. New circuit breakers for existing panelboards shall be rated for the AIC identified on the panelboard schedules on the Contract Drawings or the AIC rating of the existing panelboard, whichever is higher. New circuit breakers shall be tested, listed, and labeled for the available short circuit current.
- D. Minimum short-circuit current ratings for panelboards shall be verified by short circuit analysis specified under Division 26 Section 260573, "Power System Studies", prior to ordering equipment.

1.3. REFERENCES

- A. The publications listed below form a part of this Specification to the extent referenced. The publications are referred to in the text by the basic designation only. The edition/revision of the referenced publications shall be the latest date as of the date of the Contract Documents, unless otherwise specified.
- B. American Society of Testing Materials (ASTM):
 - 1. ASTM E 329, "Standard Specification for Agencies Engaged in the Testing and/or inspection of Materials Used in Construction."

- C. Federal Specifications (FS):
 - 1. FS W-C-375, "Circuit Breakers, Molded Case, Branch Circuit and Service."
- D. International Electrical Testing Association (NETA):
 - 1. NETA ATS, "Acceptance Testing Specifications for Electrical Power Distribution Equipment and Systems."
- E. International Organization for Standardization (ISO):
 - 1. ISO 9001, "Quality Management Systems – Requirements."
- F. National Electrical Contractors Association (NECA):
 - 1. NECA 407, "Standard for Installing and Maintaining Panelboards."
- G. National Electrical Manufacturers Association (NEMA):
 - 1. NEMA PB 1, "Panelboards."
 - 2. NEMA PB 1.1, "General Instructions for Proper Installation, Operation and Maintenance of Panelboards Rated 600 Volts or Less."
 - 3. NEMA PB 1.2, "Application Guide for Ground Fault Protective Devices."
- H. National Fire Protection Association (NFPA):
 - 1. NFPA 70, "National Electrical Code."
 - 2. NFPA 70B, "Electrical Equipment Maintenance."
 - 3. NFPA 70E, "Standard for Electrical Safety in the Workplace."
- I. Underwriters Laboratories, Inc. (UL):
 - 1. UL 50, "Standard for Enclosures for Electrical Equipment."
 - 2. UL 67, "Standard for Panelboards."
 - 3. UL 489, "Standard for Molded-Case Circuit Breakers and Circuit Breaker Enclosures."

1.4. SUBMITTALS

- A. Product Data: Submit product data showing material proposed. Submit sufficient information to determine compliance with the Drawings and Specifications.
 - 1. Submit product data for each new, overcurrent protective device, accessory, and component indicated.
 - 2. Include dimensions and manufacturer's technical data on features, performance,

electrical characteristics, ratings, and finishes of individual protective devices and auxiliary components.

- B. Quality Control Submittals: Submit field quality control test reports.
- C. Contract Closeout Submittals:
 - 1. Operation and Maintenance Data: Submit operation and maintenance data for panelboards to include in operation and maintenance manuals specified in Division 01.
 - 2. Warranty Data: Submit manufacturer's standard warranty documents.
 - 3. Panelboard Circuit Directories: For installation in panelboards. Submit final versions in operation and maintenance manuals.
 - 4. Project Record Data: Record actual locations of panelboards, indicating actual branch circuit arrangement.

1.5. QUALITY ASSURANCE

- A. Manufacturer Qualifications: Manufacturer shall be a firm engaged in the manufacture of panelboards of types and sizes required, and whose products have been in satisfactory use in similar service for a minimum of 20 years. The manufacturer shall be ISO 9001 certified and shall be designed to internationally accepted standards.
- B. Installer Qualifications: Installer shall be a firm that shall have a minimum of five years of successful installation experience with projects utilizing panelboards similar in type and scope to that required for this Project.
- C. Testing Agency Qualifications: In addition to the requirements specified in Division 01 Section Quality Control an independent testing agency shall meet OSHA criteria for accreditation of testing laboratories, Title 29, Part 1907, or shall be a full member company of the International Electrical Testing Association.
 - 1. Testing Agency's Field Supervisor: Person currently certified by the International Electrical Testing Association or National Institute for Certification in Engineering Technologies, to supervise on-site testing specified in Part 3 of this Section.
- D. Listing and Labeling: Provide products specified in this Section that are listed and labeled.
 - 1. The Terms Listed and Labeled: As defined in the National Electrical Code, Article 100.
 - 2. Listing and Labeling Agency Qualifications: A Nationally Recognized Testing Laboratory as defined in OSHA Regulation 1910.7.

1.6. DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to the Project site in supplier's or manufacturer's original wrappings and containers, labeled with supplier's or manufacturer's name, material or product brand name, and lot number, if any.

- B. Store materials in their original, undamaged packages and containers, inside a well-ventilated area protected from weather, moisture, soiling, extreme temperatures, and humidity.

1.7. PROJECT CONDITIONS

- A. Verify Dimensions: Verify NEC and all Code clearance requirements by field measurements. Locate panelboards to meet installation tolerances.
- B. Revise locations of circuit breakers in existing panelboards from those indicated as required to suite project conditions.

1.8. WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Manufacturer shall warrant equipment to be free from defects in materials and workmanship for the lesser of one (1) year from date of installation or eighteen (18) months from date of purchase.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, supply equipment from one of the following manufacturers; no other manufacturers are acceptable:
 - 1. General Electric (Selbyville Middle School to match existing)
 - 2. Siemens (Carver EC to match existing.)
- B. Replacement circuit breakers for existing panelboards shall be obtained from the original manufacturer through an authorized factory distributor, complete with full factory warranty. Original manufacturer product data shall be submitted for review.

2.2. OVERCURRENT PROTECTIVE DEVICES

- A. Overcurrent protective devices include, but are not limited to, the following:
 - 1. Thermal magnetic circuit breakers.
- B. Molded-Case Circuit Breaker Features and Accessories:
 - 1. Characteristics: Frame size, trip rating, number of poles, and auxiliary devices as indicated and interrupting capacity rating to meet available fault current.
 - 2. Lugs: Mechanical style, suitable for quantity, size/gauge, and material of conductors indicated.

3. Application Listing: Appropriate for application, including switching lighting loads (Type SWD) or heating, air-conditioning, and refrigerating equipment (Type HACR).
4. Handle Padlock Attachment: Circuit breakers in panelboards shall be equipped with fixed handle padlock attachment to allow padlocking the circuit breaker in the OFF only position at the following locations:
 - a. Branch or sub-feed circuit breakers serving variable frequency drives.
 - b. Other locations as indicated on the Contract Drawings.
5. Handle Clamp Attachment: Circuit breakers in panelboards shall be equipped with removable handle clamp attachments to prevent accidental operation of the circuit breaker at the following locations:
 - a. Locations as indicated on the Contract Drawings.

2.3. IDENTIFICATION

- A. Refer to Division 26 Section 260553, "Identification for Electrical Systems", for additional information.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Examine elements and surfaces to receive panelboards for compliance with installation tolerances and other conditions affecting performance of panelboards.
 1. Do not proceed with installation until unsatisfactory conditions have been corrected.
 2. Verify dimensions of panelboard and working space clearances.

3.2. INSTALLATION

- A. Install new circuit breakers in existing panelboards according to NEMA PB 1.1 and manufacturers instructions.
- B. Panelboard dead fronts shall remain intact except where tabs are removed for circuit breakers. Install filler plates in unused pole spaces not filled by a circuit breaker that are accidentally opened. Do not remove all tabs in dead front and fill the same with filler plates.
- C. Wiring in Panelboard Gutters: Arrange conductors into groups, and bundle and wrap with wire ties after completing load balancing.
- D. Two or three pole circuit breakers shall be common trip type. Single pole breakers with handle ties will not be permitted.
- E. Tandem circuit breakers will not be permitted.

- F. Provide handle clamps for circuit breakers serving electric heating cables and other locations noted on the Contract Drawings to prevent accidental operation.
- G. Replacement circuit breakers for existing panelboards shall be obtained from the original manufacturer through an authorized factory distributor, complete with full factory warranty. Original manufacturer product data shall be submitted for review.

3.3. GROUNDING

- A. Make equipment grounding connections for panelboards as indicated.
- B. Provide ground continuity to main electrical ground bus as indicated.

3.4. CONNECTIONS

- A. Tighten electrical connectors and terminals, including grounding connections, according to manufacturer's published torque-tightening values. Where manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- B. Neutral and ground conductors shall be isolated and terminated only at their respective bus bars. There shall only be one neutral-ground connection in service-entrance equipment by means of a removable main bonding jumper. Neutral and ground terminations at one bus bar shall not be acceptable.

3.5. IDENTIFICATION

- A. Identify field-installed wiring and components and provide warning signs as specified in Division 26 Section 260553, "Identification for Electrical Systems".
- B. Circuit Directories:
 - 1. Panelboards shall have accurate typed circuit directories indicating exactly what each branch circuit serves.
 - 2. The Contractor shall provide up to date circuit directories in new and existing panelboards, indicating all deletions and additions, and to note the date of all changes on the directory.
 - 3. The circuit directories shall reflect the actual room numbers. Directories indicating the reference room numbers on the contract drawings or in the panelboard schedule shall not be acceptable.
 - 4. The circuit directories shall include the name, address, and contact information for the Electrical/Division 26 Contractor.
 - 5. If at any time after occupancy the circuit directories are found to be incorrect due to negligence by the installer, then the Contractor shall trace out circuits, and correct the directories at no additional cost to the Owner.
- C. Provide arc flash hazard and fault current labels per Division 26 Section 260573, "Power System Studies".

3.6. FIELD QUALITY CONTROL

- A. Visual and Mechanical Inspection: Include the following inspections and related work:
1. Inspect for defects and physical damage, labeling, and nameplate compliance with requirements of up-to-date drawings and panelboard schedules.
 2. Clean new devices using Manufacturer's approved methods and materials.
 3. Verify that panelboard arc flash hazard labels are installed.
 4. Exercise and perform operational tests of all new mechanical components and other operable devices in accordance with manufacturer's instruction manual.
 5. Check alignment and fit of new components.
 6. Check tightness of new bolted electrical connections with calibrated torque wrench. Refer to manufacturer's instructions for proper torque values.
 7. Perform visual and mechanical inspection and related work for new overcurrent protective devices.
 8. Verify that neutral-ground bonds do not exist at locations that are not service entrances or separately derived power sources.
- B. Panelboard Electrical Testing: After installing panelboards and after electrical circuitry has been energized, demonstrate product capability and compliance with requirements.
1. Inspect accessible components for cleanliness, mechanical and electrical integrity, and damage or deterioration. Verify that temporary shipping bracing has been removed. Include internal inspection through access panels and covers.
 2. Inspect bolted electrical connections for tightness according to manufacturer's published torque values or, if not available, those specified in UL 486A and UL 486B.
 3. Protective Device Ratings and Settings: Verify indicated ratings and settings to be appropriate for final system configuration and parameters. Where discrepancies are found, recommend final protective device ratings and settings. Use accepted ratings or settings to make the final system adjustments.
 4. Make continuity tests of each new circuit. Refer to Division 26 Section 260519, "Low-Voltage Electrical Power Conductors and Cables" for testing specific to feeder conductors.
 5. Infrared Scanning: Perform an infrared scan of all electrical connections in each panelboard affected by the work, as follows:
 - a. Remove equipment covers so terminations are accessible to scanner.
 - b. Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values.
 - c. Provide calibration record for device.

- d. Compare test results with specified performance or manufacturer's data. Correct deficiencies identified by tests and retest.
 - e. Prepare reports identifying equipment checked and describing results of tests. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
- 6. Test Labeling: On satisfactory completion of tests and related effort, apply a label to tested components indicating test results, date, and responsible organization and person.
 - 7. Submit all test reports to the Engineer for review and approval.
 - 8. Provide copy of all test reports in the O&M manual.

3.7. CLEANING

- A. Upon completion of installation, inspect interior and exterior of panelboards. Remove paint splatters and other spots, dirt, and debris. Touch up scratches and mars of finish to match original finish.

3.8. PROTECTION

- A. Provide final protection and maintain conditions in a manner that shall ensure that the panelboard(s) shall be without damage at time of Substantial Completion.

END OF SECTION

DIVISION 26 SECTION 26 27 26
WIRING DEVICES
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS	3
1.2. SUMMARY	3
1.3. DEFINITIONS	3
1.4. SUBMITTALS	3
1.5. QUALITY ASSURANCE	3
1.6. EXTRA MATERIALS	4
PART 2. PRODUCTS	4
2.1. MANUFACTURERS	4
2.2. STRAIGHT BLADE RECEPTACLES	5
2.3. GFCI RECEPTACLES	5
2.4. SWITCHES	6
2.5. FINISHES	7
2.6. DEVICE PLATES	7
PART 3. EXECUTION	8
3.1. EXAMINATION	8
3.2. INSTALLATION – GENERAL	8
3.3. INSTALLATION – RECEPTACLES	9
3.4. IDENTIFICATION	9
3.5. CONNECTIONS	10
3.6. FIELD QUALITY CONTROL	10
3.7. CLEANING	10
END OF SECTION	10

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 27 26 WIRING DEVICES

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SUMMARY

- A. This Section includes the following:
 - 1. Straight-blade receptacles.
 - 2. GFCI receptacles.
 - 3. Weather-Resistant receptacles.
 - 4. Toggle switches.
 - 5. Device plates.

1.3. DEFINITIONS

- A. GFCI: Ground-Fault Circuit Interrupter.
- B. Pigtail: Short lead used to connect a device to a branch-circuit conductor.
- C. WR: Weather-Resistant.

1.4. SUBMITTALS

- A. Product Data: For each product specified, indicating configurations, finishes, dimensions, and manufacturer's instructions.
- B. Maintenance Data: For materials and products to include in maintenance manuals specified in Division 01.

1.5. QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction.
- B. Comply with NFPA 70.
- C. Comply with NECA Standard of Installation.
- D. Codes: Provide wiring devices conforming to the following:
 - 1. American National Standards Institute (ANSI): Provide lugs and receptacle devices constructed in accordance with ANSI C73, Attachment Plugs and

Receptacles, Dimensions of.

2. Institute of Electrical and Electronics Engineers (IEEE): Construct and install wiring devices in accordance with requirements of IEEE 241, Recommended Practice for Electric Power Systems in Commercial Building.
3. National Electrical Manufacturers Association (NEMA): Provide wiring devices constructed and configured in accordance with the requirements of
 - a. WD1: General Requirements for Wiring Devices
 - b. WD5: Special Purpose Wiring Devices
 - c. WD6: Wiring Devices - Dimensional Requirements.
4. National Fire Protection Association (NFPA): Comply with NFPA 70, National Electrical Code, as applicable to construction and installation of electrical wiring devices.
5. Underwriters Laboratories, Inc. (UL): Provide wiring devices which are UL listed and comply with the requirements of:
 - a. 20: General-Use Snap Switches.
 - b. 498: Attachments, Plugs and Receptacles
 - c. 514A: Metallic Outlet Boxes.
 - d. 514B: Fittings for Conduit and Outlet Boxes.
 - e. 514C: Non-Metallic Outlet Boxes, Flush-Device Boxes, and Covers
 - f. 943: Ground-Fault Circuit Interrupters

1.6. EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents. Deliver extra materials to Owner.

1. GFCI Receptacles: One for each ten installed, but not less than two.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 1. Wiring Devices:
 - a. Hubbell, Inc.; Wiring Devices Division
 - b. Pass & Seymour/Legrand; Wiring Devices Division
 - c. Leviton Manufacturing Co., Inc.
 - d. Eaton/Cooper; Wiring Devices Division
 - e. Lutron Electronics, Inc.

2.2. STRAIGHT BLADE RECEPTACLES

A. General Requirements

1. Straight blade receptacles shall have the following basic features:
 - a. One-piece brass mounting strap with integral ground for low resistance of fault currents.
 - b. Auto-ground clip to assure positive ground.
 - c. Impact-resistant nylon face and thermoplastic base housing.
 - d. #10 large head brass terminal and ground screws; back- and side-wired.

B. Tamper-Resistant Duplex Convenience Receptacles

1. Tamper-resistant duplex convenience receptacles shall be extra heavy-duty, specification grade, 20A, 125V, with the following features:
 - a. "TR" marking on face as required by UL standard.
 - b. Thermoplastic dual mechanism shutter system to help prevent insertion of foreign objects.
2. Comply with NEMA WD-1, NEMA WD-6 configuration 5-20R, UL 498 and Federal Specification W-C-596.
3. Hubbell HBL5362TR, Pass & Seymour TR63, or approved equal by acceptable manufacturer.

2.3. GFCI RECEPTACLES

A. General Requirements

1. GFCI receptacles shall have the following basic features:
 - a. Solid-state ground-fault sensing and signaling.
 - b. Trip time of 0.025 seconds (nominal).
 - c. Trip threshold of +/- 5mA.
 - d. Indicator light that is lighted when device is tripped.
 - e. Auto-ground clip to assure positive ground.
 - f. Impact-resistant nylon face and thermoplastic base housing.
 - g. #10 large head brass terminal and ground screws; back- and side-wired.
2. GFCI receptacles shall also have the following functions to comply with UL standard 943:
 - a. An auto-monitoring function that will allow for periodic automatic testing (self-test) of the GFCI device and its ability to respond to a ground fault. If a problem is detected one or more of the following will happen:
 - i. Power will be denied (trip with the inability to reset).
 - ii. Trip with the ability to reset, subject to the next auto-monitoring test cycle or repeatedly trip.
 - iii. Visual and/or audible indication

- b. Provisions to ensure that receptacle type GFCIs that contain separate line and load terminals, and that is powered through its load terminals, shall not reset and supply power to its receptacle face or line terminals if mis-wired. This applies both during its initial installation and after reinstallation following a correctly wired installation. If the device is provided with special instructions for removal and reinstallation, the instructions shall be followed during testing.

B. Tamper-Resistant Duplex GFCI Receptacles

1. Duplex GFCI receptacles shall be specification grade, 20A, 125V, with the following features:
 - a. "TR" marking on face as required by UL standard.
 - b. Thermoplastic dual mechanism shutter system to help prevent insertion of foreign objects.
2. Comply with NEMA WD 1, NEMA WD 6 configuration 5-20R, UL 498 and Federal Specification W-C-596.
3. Hubbell GFTRST20, Pass & Seymour 2097TR, or approved equal by acceptable manufacturer.

C. Tamper-Resistant and Weather-Resistant Duplex GFCI Receptacles

1. Weather-resistant duplex GFCI receptacles shall be specification grade, 20A, 125V with the following features:
 - a. "WR" marking on face as required by UL Standard.
 - b. UV-resistant nylon face for longer life under adverse environmental conditions.
 - c. "TR" marking on face as required by UL standard.
 - d. Thermoplastic dual mechanism shutter system to help prevent insertion of foreign objects.
2. Comply with NEMA WD 1, NEMA WD 6 configuration 5-20R, UL 498 and Federal Specification W-C-596.
3. Hubbell GFTWRST20, Pass & Seymour 2097TRWR, or approved equal by acceptable manufacturer.

2.4. SWITCHES

A. General Requirements

1. Switches shall have the following basic features:
 - a. Heavy-gauge one-piece copper alloy contact arm.
 - b. Fast "make" and positive "break" to minimize arcing.
 - c. Heavy-duty bumper pads for quiet operation.
 - d. High strength thermoplastic polycarbonate toggle.

- e. Oversized silvery alloy contacts for long life and heat dissipation.
- f. Nickel-plated steel strap with integral ground.
- g. Auto-ground clip to assure positive ground.

B. Toggle Switches

- 1. Toggle switches shall be quiet-type, extra heavy-duty, horsepower-rated, industrial grade, 120/277V, 20A: Comply with NEMA WD 1, UL 20 and Federal Specification W-S-896.
- 2. Hubbell HBL1221 (single-pole), HBL1222 (two-pole), HBL1223 (three-way), HBL1224 (four-way), Pass & Seymour PS20AC1 (single-pole), PS20AC2 (two-pole), PS20AC3 (three-way), PS20AC4 (four-way), or approved equal by acceptable manufacturer.

C. Lockable Switch Handle Guards

- 1. Provide handle guards with provisions for padlocking at all toggle switches serving as disconnecting means and where indicated on the Drawings.
- 2. Handle guards shall be steel construction, and shall mount directly over standard switch faceplates.
- 3. Provide Square D Class 2510 FL1, or approved equal by listed manufacturer.

2.5. FINISHES

- A. Wiring device catalog numbers in Section text do not designate device color. Device colors shall be as follows, unless otherwise indicated elsewhere in the Specifications and Drawings or as required by NFPA or device listing:

- 1. Wiring Devices connected to Normal Power System: White.

2.6. DEVICE PLATES

- A. Device plates shall be provided for all switches and receptacles. Device plates shall be as manufactured to fit each type of single device, to fit devices which are ganged together, and they shall be same manufacturer as wiring devices with finish as follows:

- 1. Material for Unfinished Spaces: Galvanized steel, unless otherwise noted.
- 2. Material for Finished Spaces: 0.04-inch-thick, Type 302, satin-finished stainless steel, except as otherwise indicated.
- 3. Color: Matches wiring device, except as otherwise indicated.
- 4. Plate-Securing Screws: Metal with heads colored to match plate finish.

- B. Covers for Receptacles in Damp and Wet Locations: Heavy-duty die-cast zinc/aluminum construction with hinged lockable lid, designed to be weatherproof while the device is in use, and listed and labeled "extra duty" for use in "wet locations". All components shall have baked-on electrostatic, polyester, powder paint finish for superior corrosion

resistance. Covers shall comply with NEC Article 406.9(B).

1. Duplex/GFCI Receptacles – Pass & Seymour Model No. WIUCAST1 or approved equal by Hubbell, Intermatic, or other listed manufacturer.
- C. Covers for Switches in Damp and Wet Locations: Heavy-duty die-cast zinc/aluminum construction with actuating levers and shall mount directly over the switch. Covers shall comply with NEC Article 404.4 and shall be UL listed for use in wet locations.
 1. Toggle Switches – Crouse –Hinds Model No. DS185, or approved equal.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Verification of existing conditions before starting work.
- B. Verification of Conditions: Verify that field measurements, surfaces, substrates and conditions are as required, and ready to receive Work.
 1. Verify that outlet boxes are installed at proper height.
 2. Verify that wall openings are neatly cut and will be completely covered by wall plates.
 3. Verify that branch circuit wiring installation is completed, tested, and ready for connection to wiring devices.
- C. By beginning Work, accepts conditions and assume responsibility for correcting unsuitable conditions encountered at no additional cost to the Owner.

3.2. INSTALLATION – GENERAL

- A. Install devices and assemblies plumb, level, and secure.
- B. Arrangement of Devices:
 1. Unless otherwise indicated, mount flush, with long dimension vertical, and grounding terminal of receptacles on top or as required by the local Authority Having Jurisdiction.
 2. Exception: Mount exterior GFCI weatherproof duplex receptacles horizontally with grounding terminals on the left, or as required by the local Authority Having Jurisdiction. Group adjacent switches under single, multi-gang wall plates.
- C. Protect devices and assemblies during painting.
- D. Installation of Device Plates/Covers:
 1. Install device plates when painting is complete.
 2. Install device plates to suit device type and location.

3. Provide damp location covers for wiring devices in damp interior locations.
4. Provide wet location covers for wiring devices in exterior locations.

3.3. INSTALLATION – RECEPTACLES

- A. All non-locking type, 125 volt, 15 ampere and 20 ampere receptacles shall be listed tamper-resistant receptacles in accordance with NEC Article 406.
- B. All 15 ampere and 20 ampere, 125 volt, single-phase, non-locking type receptacles installed in the following locations shall have GFCI protection for personnel, in accordance with NEC Article 210.8(B).
 1. Outdoors
 2. Within six (6) feet (1.8m) of sinks, plumbing fixtures and water piping.
 3. Mechanical rooms, electrical rooms, and similar areas where electrical hand tools or portable lighting equipment are to be used.
- C. Where multiple receptacles are indicated on the Contract Drawings as GFCI type receptacles, each device must be a GFCI type receptacle. Protecting standard receptacles downstream from one GFCI receptacle is not acceptable.
- D. All 15 ampere and 20 ampere, 125 volt and 250 volt, non-locking type receptacles installed in damp or wet locations shall be listed weather-resistant type in accordance with NEC Article 406.9(A) and 406.9(B) and shall be installed within an enclosure that is weather proof when an attachment plug is inserted.

3.4. IDENTIFICATION

- A. Comply with Division 26 Section 260553, “Identification for Electrical Systems”.
 1. Switches: Switches shall be labeled as to lights/load controlled and with circuit number and panel identification.
 2. Receptacles: All device plates shall be labeled to identify panelboard and circuit number from which served. Use machine printed, pressure sensitive, abrasion resistant label tape on face of plate and durable wire markers or tags within outlet boxes. Labels shall be clear with black lettering. Protect label from damage during construction. Replace all damaged and unclear labels.
 3. Mark all conductors with the panel and circuit number serving the device at the device.
 4. Mark the panel and circuit number serving the device on the back side of the device plate with a permanent marking system, machine-generated, that does not show through the front of the plate.
 5. Faceplate labels shall be installed such that they are readable and do not cover any portion of the faceplate securing screw(s) or the wiring device itself.

3.5. CONNECTIONS

- A. Connect wiring device grounding terminal to outlet box with bonding jumper.
- B. Connect wiring device grounding terminal to branch circuit equipment grounding conductor.
- C. Tighten electrical connectors and terminals according to manufacturers published torque tightening values. If manufacturers torque values are not indicated, use those specified in UL 486A and UL 486B.

3.6. FIELD QUALITY CONTROL

- A. Test wiring devices for proper polarity, continuity, short circuits, and ground continuity. Operate each device at least six times.
- B. Test GFCI operation with both local and remote fault simulations according to manufacturer's written instructions.
- C. Replace damaged or defective components.

3.7. CLEANING

- A. Internally clean devices, device outlet boxes, and enclosures. Replace stained or improperly painted wall plates or devices.

END OF SECTION

DIVISION 26 SECTION 26 28 13
FUSES
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS.....	3
1.2. SUMMARY	3
1.3. PERFORMANCE REQUIREMENTS	3
1.4. ACTION SUBMITTALS.....	3
1.5. CLOSEOUT SUBMITTALS	4
1.6. MAINTENANCE MATERIAL SUBMITTALS	4
1.7. QUALITY ASSURANCE	4
PART 2. PRODUCTS.....	5
2.1. MANUFACTURERS	5
2.2. CARTRIDGE FUSES	5
PART 3. EXECUTION.....	6
3.1. EXAMINATION	6
3.2. FUSE APPLICATIONS.....	6
3.3. INSTALLATION	7
END OF SECTION	7

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 28 13 FUSES

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 26 Section 260553, "Identification for Electrical Systems", for labeling materials.
 - 2. Division 26 Section 262913, "Motor Controllers", for enclosed motor controllers with fusible disconnect/safety switches.

1.2. SUMMARY

- A. This Section includes the following:
 - 1. Cartridge fuses rated 600Vac and less for use in the following:
 - a. Control circuits.
 - b. Motor controllers.
- B. The Electrical Contractor shall provide a complete set of fuses for all fusible equipment on the project as indicated on the Contract Documents. Final test and inspections shall be made prior to energizing the equipment.

1.3. PERFORMANCE REQUIREMENTS

- A. Select fuses to provide appropriate levels of short circuit and overcurrent protection for components such as wire, cable, bus structures, and other equipment. Provide system to ensure that component damage is within acceptable levels during a fault.
- B. Select fuses to coordinate with time-current characteristics of other overcurrent protective elements, such as other fuses, circuit breakers, and protective relays. Provide system to ensure that device closest to fault operates.

1.4. ACTION SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 01 Specification Sections.
- B. Product data: For each type of product. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for spare-fuse cabinets. Include the following for each fuse type indicated:
 - 1. Ambient Temperature Adjustment Information: If ratings of fuses have been adjusted to accommodate ambient temperatures, provide list of fuses with adjusted ratings.

- a. For each fuse having adjusted ratings, include location of fuse, original fuse rating, local ambient temperature, and adjusted fuse rating.
 - b. Provide manufacturer's technical data on which ambient temperature adjustment calculations are based.
2. Dimensions and manufacturer's technical data on features, performance, electrical characteristics, and ratings.
3. Current-limitation curves for fuses with current-limiting characteristics.
4. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse. Submit in PDF format.
5. Coordination charts and tables and related data.

1.5. CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For fuses to include in Operation and Maintenance manuals. In addition to items specified under Division 01, include the following:
 1. Ambient temperature adjustment information.
 2. Current-limitation curves for fuses with current-limitation characteristics.
 3. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse. Submit in PDF format.
 4. Coordination charts and tables and related data.
- B. Record Drawings: Record the equipment nameplate rating and actual fuse rating and location of fuses on the record drawings.

1.6. MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 1. Fuses: Furnish quantity equal to 20 percent of each 600 ampere and smaller fuse type and size installed, but not less than one (1) set of three (3) of each type and size.
 2. Fuse Pullers: Furnish two (2) fuse pullers.

1.7. QUALITY ASSURANCE

- A. Comply with NFPA 70 for components and installation.
- B. Listing and Labeling: Provide fuses specified in this Section that are listed and labeled.
 1. The terms Listed and Labeled as defined in the National Electrical Code, Article

100.

2. Listing and Labeling Agency Qualifications: A Nationally Recognized Testing Laboratory (NRTL) as defined in OSHA Regulation 1910.7.
3. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
4. Comply with NFPA 70.
5. Comply with National Electrical Manufacturer's Association NEMA FU-1 Low Voltage Cartridge Fuses.
6. Comply with IEC269.
7. Comply with CANENA Standard 248.
8. Comply with UL 198.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering fuses that may be incorporated into the Work include, but are not limited to, the following:
 1. Bussmann; Eaton Corporation
 2. Littelfuse, Inc.
 3. Mersen (formerly Ferraz Shawmut)
- B. Source Limitations: Obtain fuses, for use within a specific product or circuit, from single source from single manufacturer.

2.2. CARTRIDGE FUSES

- A. Characteristics: NEMA FU 1, current-limiting, nonrenewable cartridge fuses with voltage ratings consistent with circuit voltages.
- B. Fuses shall feature a solid state visual open fuse indicator, metal-embossed date and catalog number for identification.
- C. Coordinate fuse ratings with utilization equipment nameplate limitations of maximum fuse size and with system short-circuit current levels.

PART 3. EXECUTION

3.1. EXAMINATION

- A. Examine fuses before installation. Reject fuses that are moisture damaged or physically damaged.
- B. Examine holders to receive fuses for compliance with installation tolerances and other conditions affecting performance, such as rejection features.
- C. Examine utilization equipment nameplates and installation instructions. Install fuses of sizes and with characteristics appropriate for each piece of equipment.
- D. Evaluate ambient temperatures to determine if fuse rating adjustment factors must be applied to fuse ratings.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2. FUSE APPLICATIONS

- A. Motor Branch Circuits: Class RK1, time delay, 250 Volt or 600 Volt, 0-600 Amp, and 300 kA interrupting rating. Time delay fuses shall hold 500% of rated current for a minimum of 10 seconds.
 - 1. The following guidelines apply for motors protected by properly sized overload relays:
 - a. Fuses for motors with a marked service factor not less than 1.15 shall be installed in ratings of 125% of motor full-load current (or next size larger if 125 percent does not correspond to a fuse size), except where high ambient temperatures prevail, or where the motor drives a heavy revolving part which cannot be brought up to full speed quickly, such as large fans. Under such conditions, the fuses may be 150 percent to 175 percent of the motor full-load current.
 - b. For all other motors, (such as 1.0 service factor motors) fuses shall be sized in ratings of 115 percent of the motor full load current (or next size larger if 115 percent does not correspond to a fuse size) except as noted above.
 - 2. The following guidelines apply where fuses are used as the only overload protection for the motor:
 - a. For motors with a 1.15 service factor or more, fuses should be sized at 125 percent of motor full-load current (or next size smaller if 125 percent does not correspond to a fuse size).
 - b. For all other motors, fuses should be sized at 115 percent of motor full-load current (or next size smaller, if 115 percent does not correspond to a fuse size).
 - 3. Fuse sizes for motor protection shall be chosen from fuse manufacturers published data and recommendations.

- B. Motor Controllers: NEMA and IEC Style motor controllers shall be protected from short-circuits by Dual-Element Time-Delay fuses in order to provide testing agency-witnessed Type 2 coordination for the controller. This provides “no damage” protection for the controller, under low-level and high-level fault conditions, as required by IEC Publication 947-4. For IEC style controller, the fuses shall be installed in ratings to coordinate with the overload relays, such that the relay/fuse curves cross over at 7-10 times the IEC contactor current rating.
- C. Other Branch Circuits: Class RK1, non-time delay, 250 Volt or 600 Volt, 0-600 Amp, and 300 kA interrupting rating.
- D. Control Circuits: Class CC, current limiting rejection type, rated 0-30 amperes, 600 volts, and 200- kA interrupting rating.
- E. Provide fuses of type and rating recommended by equipment manufacturer for packaged and/or specialized equipment.

3.3. INSTALLATION

- A. Fuses shall not be installed until equipment is ready to be energized. This measure prevents fuse damage during shipment of the equipment from the manufacturer to the job site, or from water that may contact the fuse before the equipment is installed. Final tests and inspections shall be made prior to energizing the equipment. This shall include a thorough cleaning, tightening, and review of all electrical connections and inspection of all grounding conductors.
- B. All fuses shall be furnished and installed by the electrical contractor. All fuses shall be of the same manufacturer.
- C. Install fuses in fusible devices as indicated. Arrange fuses so fuse ratings and open fuse indicators are visible without removing fuses.
- D. Provide fuse clips as required.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

DIVISION 26 SECTION 26 29 13
MOTOR CONTROLLERS
TABLE OF CONTENTS

PART 1. GENERAL	3
1.1. RELATED DOCUMENTS	3
1.2. SUMMARY	3
1.3. DEFINITIONS	3
1.4. SUBMITTALS	3
1.5. QUALITY ASSURANCE	4
1.6. DELIVERY, STORAGE, AND HANDLING	4
1.7. PROJECT CONDITIONS	4
1.8. COORDINATION	5
1.9. WARRANTY	5
1.10. EXTRA MATERIALS	6
PART 2. PRODUCTS	6
2.1. MANUFACTURERS	6
2.2. COMBINATION MAGNETIC MOTOR CONTROLLERS	6
2.3. ENCLOSURES	8
PART 3. EXECUTION	8
3.1. APPLICATIONS	8
3.2. INSTALLATION	9
3.3. IDENTIFICATION	9
3.4. CONTROL WIRING INSTALLATION	9
3.5. CONNECTIONS	9
3.6. FIELD QUALITY CONTROL	10
3.7. CLEANING	10
END OF SECTION	10

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 26 29 13 - MOTOR CONTROLLERS

PART 1. GENERAL

1.1. RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections include the following:
 - 1. Division 26 Section 260500, "Common Work Results for Electrical", for Mechanical - Electrical coordination requirements.
 - 2. Division 26 Section 260500, "Common Work Results for Electrical", for general materials and installation methods.
 - 3. Division 26 Section 260553, "Identification for Electrical Systems" for labeling materials.
 - 4. Division 26 Section 262813, "Fuses", for fuses installed in combination magnetic motor controllers with fusible disconnect switches.

1.2. SUMMARY

- A. This Section includes AC motor-control devices rated 600 V and less that are supplied as enclosed units.

1.3. DEFINITIONS

- A. CPT: Control power transformer.
- B. N.C.: Normally closed.
- C. N.O.: Normally open.
- D. OCPD: Overcurrent protective device.

1.4. SUBMITTALS

- A. Product Data: For products specified in this Section. Include dimensions, ratings, and data on features and components.
- B. Maintenance Data: For products to include in the operation and maintenance manuals specified in Division 01.
- C. Load-Current and Overload-Relay Heater List: Compile after motors have been installed and arrange to demonstrate that selection of heaters suits actual motor nameplate full-load currents.
- D. Submit a schedule of equipment to indicate motor controller ratings, sizes, and other electrical characteristics for each item of equipment.

1.5. QUALITY ASSURANCE

- A. Manufacturer Qualifications: Maintain, within 50 miles (80 km) of Project site, a service center capable of providing training, parts, and emergency maintenance and repairs.
- B. Source Limitations: Obtain similar motor-control devices through one source from a single manufacturer.
- C. Comply with NFPA 70.
- D. Listing and Labeling: Provide motor controllers specified in this Section that are listed and labeled.
 - 1. The Terms Listed and Labeled: As defined in the National Electrical Code, Article 100.
 - 2. Listing and Labeling Agency Qualifications: A Nationally Recognized Testing Laboratory as defined in OSHA Regulation 1910.7.
- E. UL Compliance: NEMA ICS 2, Industrial Control Devices, Controllers and Assemblies.

1.6. DELIVERY, STORAGE, AND HANDLING

- A. Store enclosed controllers indoors in clean, dry space with uniform temperature to prevent condensation. Protect enclosed controllers from exposure to dirt, fumes, water, corrosive substances, and physical damage.

1.7. PROJECT CONDITIONS

- A. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:
 - 1. Ambient Temperature: Not less than minus 22 deg F (minus 30 deg C) and not exceeding 104 deg F (40 deg C).
 - 2. Altitude: Not exceeding 6600 feet (2010 m).
- B. Interruption of Existing Electrical Systems: Do not interrupt electrical systems in facilities occupied by Owner or other unless permitted under the following conditions and then only after arranging to provide temporary electrical service according to requirements indicated:
 - 1. Notify Owner no fewer than two days in advance of proposed interruption of electrical systems.
 - 2. Indicate method of providing temporary utilities.
 - 3. Do not proceed with interruption of electrical systems without Owner's written permission.
 - 4. Comply with NFPA 70E.

1.8. COORDINATION

- A. Coordinate features of controllers and accessory devices with pilot devices and control circuits to which they connect.
- B. Coordinate features, accessories, and functions of each motor controller with the ratings and characteristics of the supply circuit, the motor, the required control sequence, and the duty cycle of the motor and load.
- C. The horsepower rating of all starters shall be checked against actual motor to be controlled, before installation and correct size overload elements shall be provided in all starters based on nameplate and manufacturer's recommendation.
- D. Provide all control devices and wiring, where not provided under Division 23, required for all equipment.
- E. Motor controllers shall be provided for voltage and current characteristics as indicated. In the event that equipment provided is of different electrical characteristics than the ones specified, any increase in electrical feeders, conduits, circuit breakers, etc., including increase of labor cost shall be the responsibility of the Contractor.
- F. Provide branch circuits for all motors to the starting equipment and then to the motors, complete with all control wiring for automatic and remote control where required or noted. Conduits to motors shall terminate in the conduit fittings on the motors, the final connection being made with flexible metal conduit (FMC) in dry locations and with Liquid-Tight Flexible Metal Conduit (LFMC) in damp/wet locations.
- G. All conduits and wiring required for control work from the holding coil circuit of the starter, including the furnishing and installation of control devices such as auxiliary contacts, control relays, time delay relays, pilot lights, selector switches, alternators, etc., shall be provided and installed by other trades unless otherwise indicated.
- H. Power Branch Circuits: Wire sizes for branch circuits not specifically called for on drawings or in Specifications shall be based on 125 percent of the full load current of the motor unless the voltage drop of motor branch circuits exceeds 1-1/2 percent from the distribution panel to the motor; in which case, voltage drop shall govern wire sizes. A power factor of 80 percent shall be used for motors in such calculations.

1.9. WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Manufacturer shall warrant equipment to be free from defects in materials and workmanship for the lesser of one (1) year from date of installation or eighteen (18) months

from date of purchase.

1.10. EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Overload Relays: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.
 - 2. Pilot Lights: Equal to 10 percent of quantity installed for each type, but no fewer than two of each type. Where lamps are field replaceable, furnish spare lamps only.
 - 3. Fuses for Fusible Switches: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.
 - 4. Control Power Fuses: Equal to 10 percent of quantity installed for each size and type, but no fewer than two of each size and type.
 - 5. Auxiliary Contacts: Furnish one spare(s) for each size and type of magnetic controller installed.
 - 6. Power Contacts: Furnish three spares for each size and type of magnetic contactor installed.

PART 2. PRODUCTS

2.1. MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, supply equipment from one of the following manufacturers. No other manufacturers are acceptable.
 - 1. Square D Company; Groupe Schneider. (Basis of Design).
 - 2. Eaton Corporation; Westinghouse & Cutler-Hammer Products.
 - 3. Siemens Energy and Automation, Inc.
 - 4. Allen-Bradley Company; Industrial Control Group.
 - 5. Crouse-Hinds ECM; Cooper Industries, Inc. Division.
 - 6. General Electric (GE).
- B. All motor controllers shall be NEMA type controllers. IEC type controllers shall NOT be acceptable.

2.2. COMBINATION MAGNETIC MOTOR CONTROLLERS

- A. Description: Combine magnetic motor controllers with fusible switch disconnect in common enclosure.

1. Magnetic Motor Controllers: NEMA ICS 2, AC general-purpose Class A full-voltage, non-reversing, across-the-line magnetic controller for induction motors rated in horsepower.
 2. Fusible Switch Assemblies: NEMA KS 1, enclosed knife switch with externally operable handle and visible blades. Switch shall have a color-coded externally operated handle. Operating handle shall give positive visual indication of "on/off" with red and black color-coding. Switch shall have fuse clips to accept rejection-type, dual-element, current-limiting, time-delay fuses, as specified in Division 26 Section "Fuses".
- B. Control Circuit: Coordinate with Automatic Temperature Control Contractor; obtained from integral control power transformer.
- C. Coil: Encapsulated type.
- D. Poles: As indicated.
- E. Size: NEMA size 1, unless otherwise indicated.
- F. Contacts: Totally enclosed, double-break, silver-cadmium-oxide power contacts. Contact inspection and replacement shall be possible without disturbing line or load wiring.
- G. Wiring: Straight-through wiring with all terminals clearly marked.
- H. Overload Relay: NEMA ICS. Provide with sensors in each phase matched to nameplate full-load current of specific motor to which they connect, and with appropriate adjustment for motor duty cycle.
1. Solid State: Trip current rating will be established by selection of overload relay and shall be adjustable (3 to 1 current range). The overload shall be self-powered, provide phase loss and phase unbalance protection, have a permanent tamper guard, and be ambient insensitive. It shall be available in Trip Class 10 or Class 20 and have a mechanical test function.
 2. Outputs: Provide normally closed (N.C.) auxiliary contact.
 3. Reset: Unit shall offer both manual reset and remote reset using an external module.
- I. Options and Features:
1. Control Power Transformers: Include a control power transformer with adequate capacity to operate connected pilot light, indicating and control devices. Provide fused secondary protection and bond un-fused leg of secondary to enclosure.
 2. Auxiliary Contacts: Provide two normally open (N.O.) and two normally closed (N.C.) auxiliary contacts in each starter in addition to the standard normally open (N.O.) sealing contact.
 3. Selector Switches: Rotary type, Hand-Off-Automatic (H-O-A) selector switch.

All switch positions shall be maintained contact.

4. Cover Mounted Indicating Lights: Green "Power Available" and red "Running" LED type indicating lights. "Power Available" indicating light shall be connected at the load side of the fused secondary terminals of the control power transformer. "Running" indicating light shall be connected through one normally open (N.O.) auxiliary control contact. Indicating lights connected to the start button or across the load side of starters will not be acceptable. Indicating lights shall be equipped with individual legend plates supplied by the manufacturer.

5. Pilot Device Contacts: NEMA ICS 2, Form "Z".

- J. Furnish Square D, Class 8538 Type S, or approved equal.

2.3. ENCLOSURES

- A. Description: All motor controllers shall be mounted in enclosures, flush or surface mounted as required. Provide flush-mounted enclosures for motor controls in finished locations.
- B. Enclosures shall comply with requirements of NEMA 250 – “Enclosures for Electrical Equipment”, and NEMA ICS 6 – “Enclosures Standard”.
- C. Enclosures shall be provided in accordance with the following requirements in order to meet environmental conditions at the installed location of each motor controller.

1. Dry, Interior Locations: NEMA Type 1.

PART 3. EXECUTION

3.1. APPLICATIONS

- A. Select features of each motor controller to coordinate with ratings and characteristics of supply circuit and motor; required control sequence; duty cycle of motor, drive, and load; and configuration of pilot device and control circuit affecting controller functions.
- B. Select horsepower rating of controllers to suit motor controlled.
- C. Provide fractional-horsepower manual motor controllers for single-phase motors, unless otherwise indicated.
- D. Provide combination magnetic motor controllers for three-phase motors, unless otherwise indicated.
- E. Hand-Off-Automatic Selector Switches: In covers of motor controllers started and stopped by automatic controls or interlocked with other equipment.
- F. Provide heaters and/or fuses correlated with full load nameplate current of motors provided. Set adjustable overload devices to suit motor provided.
- G. Motor controllers shall be protected from short-circuits by dual-element time-delay fuses in order to provide testing agency-witnessed Type 2 coordination for the motor controller. This provides “no damage” protection for the motor controller, under low and high level

fault conditions, as required by IEC Publication 947-4.

3.2. INSTALLATION

- A. Install motor controllers in locations as indicated, according to manufacturer's written instructions.
- B. Install motor controllers level and plumb. Provide mounting brackets, wall bracing, and accessories as required.
- C. Install motor controllers to have adequate working space in accordance with Article 110.26 of the National Electrical Code. Motor controllers shall not be installed beneath ductwork, piping, etc.
- D. Install independently mounted motor-control devices according to manufacturer's written instructions.
- E. Location: Locate controllers within sight of motors controlled, unless otherwise indicated.
- F. For control equipment at walls, bolt units to wall or mount on lightweight structural-steel channels bolted to wall. For controllers not at walls, provide freestanding racks conforming to Division 26 Section 260529, "Hangers and Supports for Electrical Systems".

3.3. IDENTIFICATION

- A. Identify motor-control components and control wiring according to requirements specified in Division 26 Section 260553, "Identification for Electrical Systems".
- B. All motor controllers shall be provided with engraved nameplates which clearly identify the equipment served, circuit designation, and circuit voltage/phase.

3.4. CONTROL WIRING INSTALLATION

- A. Install wiring between motor-control devices according to Division 26 Section 260519, "Low-Voltage Electrical Power Conductors and Cables".
- B. Bundle, train, and support wiring in enclosures.
- C. Connect hand-off-automatic switch and other automatic control devices where available.

3.5. CONNECTIONS

- A. Connect motor controllers and components to wiring system and to ground as indicated and instructed by manufacturer.
- B. Tighten connectors, terminals, bus joints, and mountings. Tighten field-connected connectors and terminals, including screws and bolts, according to manufacturer's published torque-tightening values. Where manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.6. FIELD QUALITY CONTROL

- A. Visual and Mechanical Inspection: Include the following inspections and related work.
1. Inspect for defects and physical damage, NRTL labeling, and nameplate compliance with drawings and schedules.
 2. Exercise and perform operational tests of mechanical components and other operable devices in accordance with manufacturer's instructions.
 3. Check tightness of electrical connections of devices with calibrated torque wrench. Use Manufacturer's recommended torque values.
 4. Clean devices using Manufacturer's approved methods and materials.
 5. Verify proper fuse types and ratings in fusible devices.
 6. Verify that fuses are facing out and that fuse ratings are readable without removing fuses.
 7. Verify proper overload types and ratings in devices with overload protection.
 8. Verify proper operation of pilot lights.
 9. Verify proper operation of hand-off-automatic selector switches.
 10. Motor-Control Device Ratings and Settings: Verify that ratings and settings as installed are appropriate for final loads and final system arrangement and parameters. Recommend final protective-device ratings and settings where differences are found. Use accepted revised ratings or settings to make the final system adjustments. Prepare and submit the load current and overload relay heater list.

3.7. CLEANING

- A. Remove paint splatters and other spots, dirt, and debris. Touch up scratches and mars of finish to match original finish. Clean devices internally, using methods and materials recommended by manufacturer.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK