

*Ring W. Lardner, P.E.
W. Zachary Crouch, P.E.
Michael E. Wheedleton, AIA, LEED GA
Jason P. Loar, P.E.
Jamie L. Sechler, P.E.*

**DIETARY ROOF REPLACEMENT
DELAWARE HOSPITAL FOR THE CHRONICALLY ILL
DOVER, DELAWARE 19901
DBF #0586B064.M01 ❖ OMB/DFM #MC3514000085
JULY 23, 2026**

ADDENDUM NO. 2

The following items shall become a part of the contract documents. Contractor must acknowledge receipt of this addendum on the Bid Form. Failure to do so may subject the Bidder to disqualification.

Item 1: The stone caps on parapet walls shall be removed in its entirety and replaced with metal coping. Refer to Details A6 on Sheet A-501 and H14 on Sheet A-502.

Item 2: At upper roof contractor shall bend up the flashing, extend the EPDM up under it and bend the flashing back down. Refer to Detail L1 on Sheet A-501.

Item 3: Dimensions were added to A-101 & A-102.

Item 4: Detail G18/A-503 was added to the drawings.

END OF ADDENDUM