



Pennsylvania
Duane Morris Plaza
30 S. 17th Street
Suite 830
Philadelphia, PA 19103
Phone
267.804.7286

Delaware
315 S. Chapel Street
Newark, DE 19711
Phone
302.738.7172
Fax
302.738.7175
www.dedc-eng.com

DELAWARE STATE POLICE
HEADQUARTERS BUILDING
OMB/DFM# MC1002001111
ADDENDUM #2

QUESTIONS:

- A. Drawing E-200, panel schedule "HA", note "A" calls out a spec. for a POWER SYSTEM STUDY, and calls out spec. section 260573. There is NO spec. section 260573. Please advise if a power study even needs to be done. We are only adding 30 amps connected load to the system. The study would 3 to 5K to the project.
- a. A power system study is not required for this project.*
- B. With the BAS Contractor providing controls for the Hydronic Unit Heater as seen on the Mechanical Drawings in mind, is there any scope required for the Domestic Hot Water Heater as shown on P-000 for dry contact alarm monitoring, control, integration, etc? The existing Radius Systems Automated Logic BAS currently monitors the existing Domestic Hot Water Heater HWH-1 pump relay.
- a. The existing domestic hot water recirculation pump is to remain and be connected into the new water heater. As the existing relay isn't to be modified, there isn't any BAS scope associated with the new water heater.*
- C. Detail 3 of E200 mentions remote emergency mushroom push-button for the boilers, is the BAS contractor responsible for furnishing and installing the emergency shutdown push-button, and connecting it to the BAS?
- a. This is a single prime contract. The prime contractor shall determine their subcontractor's scope unless otherwise noted in the drawings.*

SUMMARY:

- A. Addendum #2
1. Addendum #2 (this document) (1 page)

Summarized By: DEDC, LLC
Matt Lano
Date: June 29, 2026