

**Addendum  
No. 2**

Addendum Date: June 26, 2026  
Project: East Side Chiller Replacement at SC Courthouse  
DFM Project No: MC1002001123

---

The work herein shall be considered part of the bid documents for the referenced project and carried out in accordance with the following supplemental instructions issued in accordance with the Contract Documents without change in Contract Sum or Contract Time. Acknowledge receipt of addendum on the bid form as indicated.

---

**Clarifications:**

1. There is no contractor parking available in the courthouse parking area. In general, contractors are to park off site. Loading and unloading of equipment and materials is to be performed during off-hours – either weekends or evenings at owner’s option.
2. All wiring exposed to mechanical spaces, electrical spaces, utility spaces, or building exterior shall be provided in rigid galvanized steel conduit.

**Bidder Questions / Responses:**

1. Question – On Drawing E-000, note 27 it states that no MC cable can be used, but on note 21 it specs out a MC cable to be used for VFDs. Please advise.  
Response – In general, MC cable is not permitted with the exception of flexible whips to equipment, light fixtures or wiring devices that may not exceed 4 ft in length. For the case of VFD conductors, the flexible, metal-clad sheathing is to be removed and installed in conduit – with flexible whip connection to electrified components.

**Changes to Specifications:**

None at this time.

**Changes to Drawings:**

None at this time.

**Attachments:**

None.

END