DEDC LLC
ENGINEERING | DESIGN | CONSULTING

Pennsylvania
Duane Morris Plaza
30 S. 17th Street
Suite 830
Philadelphia, PA 19103
Phone
267.804.7286

Delaware
315 S. Chapel Street
Newark, DE 19711
Phone
302.738.7172
Fax
302.738.7175

www.dedc-eng.com

PRE-BID MEETING SUMMARY
PRICKETT BUILDING
GENERATOR REPLACEMENT
OMB/DFM# MC3514000087
ADDENDUM #2

QUESTIONS:

A. There is a lightning protection section in the specifications, but I don't see lightning protection on the drawings. Please confirm if lighting protection is required.

   a. *Lighting protection is required. The new generator is to be connected to the existing building lighting protection system.*

B. There is a power study section in the specifications. Is there a previous power study for these buildings that can be modified for this project?

   a. *There is not an existing power study. The scope of the power study shall only be for the new equipment that is being installed and the existing equipment being tied into. The contractor is not responsible for completing a full building power study.*

C. How long can the buildings that are fed by the "Outdoor SWBD" be without power? Based on what I read on the drawings, it could take weeks to intercept and reroute the conduits in Phase 1 of the project. The power would need to be off for that time.

   a. *Shutdowns shall be limited to a maximum of two (2) hours in a forty-eight (48) hour period. It is the contractor's responsibility to complete the installation in a manner that this downtime can be achieved.*

D. Regarding the new proposed 750kW Natural Gas Generator – Would Hi-Power be an acceptable/approved manufacture?

   a. *No. Insufficient information on this was provided to be considered as a substitution.*

E. What is the weight for the existing generator?

   a. *Unknown. We do not have information on the existing generator and enclosure weights.*

F. What are the normal work hours? Will off-hours be required during outages?

   a. *See addendum #1 for work hours. Yes, all shutdowns are to occur during off-hours.*

DEDC LLC
ENGINEERING | DESIGN | CONSULTING

Pennsylvania
Duane Morris Plaza
30 S. 17th Street
Suite 830
Philadelphia, PA 19103
Phone
267.804.7286

Delaware
315 S. Chapel Street
Newark, DE 19711
Phone
302.738.7172
Fax
302.738.7175
www.dedc-eng.com

DRAWINGS REVISIONS

A. E101
   a. Updated to show a temporary ATS.
B. E102
   a. Added junction box covering the knockout made in Phase 1.
C. E103
   a. Added junction box covering the knockout made in Phase 1.
D. E104
   a. Added junction box covering the knockout made in Phase 1.
E. E200
   a. Updated single line to show a temporary ATS.
F. E201
   a. Added junction box covering the knockout made in Phase 1.

ADDENDUM #2

1. Addendum #2 (this document) (2 pages)
2. Revised Drawings (6 pages)

Summarized By: DEDC, LLC
Matt Lano
Date: November 18, 2026